This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`



THE MICROSCOPE

THE NEW YORK
PUBLIC LIBRARY
ASTOR, LENOX
TILDEN FOUNDATIONS

THE NEW YORK
PUBLIC LIBRARY
ASTOR, LENOX
TILDEN FOUNDATIONS

FRONTISPIECE.

1

X6

2



X510

3

X510

5



X1860

4



X77

6

X490

7

X140

8

X138

THE

MICROSCOPE

AND

ITS REVELATIONS

BY THE LATE

WILLIAM B. CARPENTER, C.B., M.D., LL.D., F.R.S.

SEVENTH EDITION

IN WHICH THE FIRST SEVEN CHAPTERS HAVE BEEN ENTIRELY REWRITTEN AND THE TEXT THROUGHOUT RECONSTRUCTED, ENLARGED, AND REVISED

BY THE REV.

W. H. DALLINGER, LL.D., F.R.S., &c.

WITH TWENTY-ONE PLATES AND EIGHT HUNDRED WOOD ENGRAVINGS

PHILADELPHIA
P. BLAKISTON, SON, & CO.
1012 WALNUT STREET
1891

TO NEW YORK
PUBLIC LIBRARY
133816A
ASTOR, LENOX AND
TILDEN FOUNDATIONS
R 1924 L

PREFACE

THE use of the Microscope, both as an instrument of scientific research and as a means of affording pleasure and recreative instruction, has become so widespread, and the instrument is now so frequently found in an expensive form capable of yielding in skilled hands good optical results, that it is eminently desirable that a treatise should be within the reach of the student and the tiro alike, which would provide both with the elements of the theory and principles involved in the construction of the instrument itself, the nature of its latest appliances, and the proper conditions on which they can be employed with the best results. Beyond this it should provide an outline of the latest and best modes of preparing, examining, and mounting objects, and glance, with this purpose in view, at what is easily accessible for the requirements of the amateur in the entire organic and inorganic kingdoms.

This need has been for many years met by this book, and its six preceding editions have been an extremely gratifying evidence of the industry and erudition of its Author. From the beginning it opened the right path, and afforded excellent aid to the earnest amateur and the careful student.

But the Microscope in its very highest form has become—so far at least as objectives of the most perfect construction and greatest useful magnifying power are concerned—so common that a much more accurate account of the theoretical basis of the instrument itself and of the optical apparatus employed with it to obtain the best results with 'high powers' is a want very widely felt.

The advances in the mathematical optics involved in the construction of the most perfect form of the present Microscope have been very rapid during the last twenty years; and the progress in the principles of practical construction and the application of theory have, even since the last edition of this book was published, been so marked as to produce a revolution in the instrument itself and in its

application. The new dispensation was dimly indicated in the last edition; but it has effected so radical a change in all that appertains to Microscopy that a thorough revision of the treatment of this treatise was required. The great principles involved in the use of the new objectives and the interpretation of the images presented by their means, are distinct and unique; and unless these be clearly understood the intelligent use of the finest optical appliances now produced by mathematical and practical optics cannot be brought about. They have not rendered the use of the instrument more difficult—they have rather simplified its employment, provided the operator understands the general nature and conditions on which his Microscope should be used. If the modern Microscope be, as a mechanical instrument with its accompanying optical apparatus, as good as it can be, a critical image—a picture of the object having the most delicately beautiful character—is attainable with 'low powers' and 'high powers' alike. Microscopists are no longer divisible into those who work with 'high powers' and those who work with 'low powers.' No one can work properly with either if he does not understand the theory of their construction and the principles upon which to interpret the results of their employment. If he is familiar with these the employment of any range of magnifying power is simply a question of care, experiment, and practice; the principles applicable to the one are involved in the other. Thus, for example, a proper understanding of the nature and mode of optical action of a 'sub-stage condenser' is as essential for the very finest results in the use of a 1-inch object-glass as in the use of a 2 mm. with N.A. 1·40 or the 2·5 mm. with N.A. 1·60, while it gives advantages not otherwise realisable if the right class of condenser used in the right way be employed with the older $\frac{1}{50}$th inch or $\frac{1}{25}$th inch achromatic objectives, and especially the $\frac{1}{12}$th inch and $\frac{1}{20}$th inch objectives of Powell and Lealand, of N.A. 1·50. Without comparing the value of the respective lenses, the best possible results in every case will depend upon a knowledge of the nature of the instrument, the quality of the condenser required by it, and its employment upon right principles.

This is but one instance out of the whole range of manipulation in Microscopy to which the same principles apply.

In its present form, therefore, a treatise of this sort, preserving the original idea of its Author and ranging from the theory and construction of the Microscope and its essential apparatus, embracing a discussion of all their principal forms, and the right use of each, and passing to a consideration of the best methods of preparation and mounting of objects, and a review of the whole Animal, Vegetable and Inorganic Kingdoms specially suited for microscopic purpose

must be essentially a cyclopædic work. This was far n possible to one man when Dr. Carpenter began his work than it was even when he issued his last edition. But it is practically impossible now. It is with Microscopy as with every department of scientific work—we must depend upon the specialist for accurate knowledge.

In the following pages I have been most generously aided. In no department, not even that in which for twenty years I have been specially at work, have I acted without the cordial interest, suggestion, and enlightenment afforded by kindred or similar workers. In every section experts have given me their unstinted help. To preserve the character of the book, however, and give it homogeneity, it was essential that all should pass through one mind and be so presented. My work for many years has familiarised me, more or less, with every department of Microscopy, and with the great majority of branches to which it is applied. I have therefore given a common form, for which I take the sole responsibility, to the entire treatise. The subject might have been carried over ten such volumes as this; but we were of necessity limited as to space, and the specific aim has been to give such a condensed view of the whole range of subjects as would make this treatise at once a practical and a suggestive one.

The first five chapters of the last edition are represented in this edition by seven chapters; the whole matter of these seven chapters has been re-written, and two of them are on subjects not treated in any former edition. These seven chapters represent the experience of a lifetime, confirmed and aided by the advice and practical help of some of the most experienced men in the world, and they may be read by anyone familiar with the use of algebraic symbols and the practice of the rule of three. They are not in any sense abstruse, and they are everywhere practical.

In the second chapter, on The Principles and Theory of Vision with the Compound Microscope, so much has been done during the past twenty years by Dr. ABBE, of Jena, that my first desire was to induce him to summarise, for this treatise, the results of his twenty years of unremitting and marvellously productive labour. But the state of his health and his many obligations forbade this; and at length it became apparent that if this most desirable end were to be secured, I must re-study with this object all the monographs of this author. I summarised them, not without anxiety; but that was speedily removed, for Dr. ABBE, with great generosity, consented to examine my results, and has been good enough to write that he has 'read [my] clear expositions with the greatest interest;' and, after words which show his cordial friendliness, he says: 'I find the whole . . . much more adequate to the purposes of the book than I should

have been able to write it. . . . I feel the greatest satisfaction in seeing my views represented in the book so extensively and intensively.'

These words are more than generous ; but I quote them here in order that the reader may be assured of the accuracy and efficiency of the account given in the following pages of the invaluable demonstrations, theories, and explanations presented by Dr. ABBE on the optical principles and practice upon which the recent improvement in the construction of microscopical lens systems has so much depended.

It will not be supposed that I implicitly coincide with every detail. Dr. ABBE is too sincere a lover of independent judgment to even desire this. But it was important that his views as such should be found in an accessible English form ; in that form I have endeavoured to present them ; and in the main there can be no doubt whatever that these teachings are absolutely incident with fact and experience. In details, as may appear here and there in these pages, especially where it becomes a question of practice, I may differ as to method, and even interpretation, from this distinguished master in Mathematical Optics. But our differences in no way affect the great principles he has enunciated or the comprehensive theory of microscopical vision he has with such keen insight laid down.

In preparing the remainder of the seven new chapters of this book I have sought and, without hesitancy, obtained advice and the advantage of the support of my own judgment and experience from many competent men of science, who have shown a sincere interest in my work and have aided me in my endeavours. But, first on the list, I must place my friend Mr. E. M. NELSON. Our lines of experience with the Microscope have run parallel for many years, although the subjects of our study have been wholly different ; but the advantages of his suggestion, confirmation, and help have been of constant and inestimable value to me. He placed his knowledge, instruments, and experience at my disposal, fully and without limit or condition ; and his exceptional skill in Photo-micrography has enabled me to add much to the value of this book.

To Count CASTRACANE I am indebted for valuable suggestions regarding the Diatomaceæ, to be used at my discretion ; to Dr. VAN HEURCK I am also under much obligation for his courtesy in preparing Plate XI. of this book, giving some of his photo-micrographic work with the new object-glass of 2·5 mm. N.A. 1·60. The full description of this plate is given, with some critical remarks, in the General Description of Plates. To the late and deeply lamented Dr. H. B. BRADY, F.R.S., I am under obligation for valuable suggestions regarding the Foraminifera.

From Dr. HUDSON I have received cordial aid in dealing with his special subject, the Rotifera; and to Mr. ALBERT MICHAEL I am under equal obligation for his assistance in regard to the Acarina.

Mr. W. T. SUFFOLK gave me his most welcome judgment and advice regarding my chapter on Mounting, and I received also the suggestions of Mr. A. COLE with much pleasure and advantage. I have received help from Dr. A. HILL, of Downing College, Cambridge, and from Professor J. N. LANGLEY, of Trinity College, Cambridge—from both of whom special processes of preparation for histological work were sent.

Mr. FRANK CRISP, with characteristic generosity, aided me much by suggestions of special and practical value; and Mr. JOHN MAYALL, Jun., the present Secretary of the Royal Microscopical Society, has been untiring in his willingness to furnish the aid which his influence was able to secure.

To Professor W. HICKS, F.R.S., Principal of Firth College, Sheffield, I am indebted for the revision of special sheets; so also I owe acknowledgments to Dr. HENRY CLIFTON SORBY, F.R.S., and to Dr. GROVES, as well as to others, whose suggestions, advice, or confirmation of my judgments have been much esteemed; and prominent amongst these are Professor ALFRED W. BENNETT, B.Sc., and Professor F. JEFFREY BELL, M.A., whose constant advice in their departments of Biology I have received throughout; while in Micro-geological subjects I have been aided by the suggestions and experience of Professor J. SHEARSON HYLAND, D.Sc.

It will be observed that every endeavour has been made to bring each of the many subjects discussed in this book into conformity with the most recent knowledge of experts. Many of the sections, in fact, have been wholly rewritten and illustrated from new and original sources; this may be seen in the sections on the History as well as the Construction and Use of the Microscope and its appliances, as also in those on Diatomaceæ, Desmids, Saprophytes, Bacteria, Rotifera, Acarina, and in the chapters on Microscopic Geology and Mineralogy. To the same end nineteen new plates have been prepared and 300 additional woodcuts, many of which are also new; and for the use of the majority of those which are not so, I am indebted to the Editors and Secretary of the Royal Microscopical Society.

There certainly never was a time when the Microscope was so generally used as it now is. With many, as already stated, it is simply an instrument employed for elegant and instructive relaxation and amusement. For this there can be nothing but commendation, but it is desirable that even this end should be sought intelligently. The social influence of the Microscope as an instrument employed for recreation

and pleasure will be greater in proportion as a knowledge of the general principles on which the instrument is constructed are known, and as the principles of visual interpretation are understood. The interests of these have been specially considered in the following pages ; but such an employment of the Microscope, if intelligently pursued, often leads to more or less of steady endeavour on the part of amateurs to understand the instrument and use it to a purpose in some special work, however modest. This is the reason of the great increase of 'Clubs' and Societies of various kinds, not only in London, and in the provinces, but throughout America ; and these are doing most valuable work. Their value consists not merely in the constant accumulation of new details concerning minute vegetable and animal life, and the minute details of larger forms, but in the constant improvement of the quality of the entire Microscope on its optical and mechanical sides. It is largely to Amateur Microscopy that the desire and *motive* for the great improvements in object-glasses and eye-pieces for the last twenty years are due. The men who have compared the qualities of respective lenses, and have had specific ideas as to how these could become possessed of still higher qualities, have been comparatively rarely those who have employed the Microscope for professional and educational purposes. They have the rather simply *used*—employed in the execution of their professional work —the best with which the practical optician could supply them. It has been by amateur microscopists that the opticians have been incited to the production of new and improved objectives. But it is the men who work in our biological and medical schools that ultimately reap the immense advantage—not only of greatly improved, but in the end of greatly cheapened, object-glasses. It is on this account to the advantage of all that the amateur microscopist should have within his reach a handbook dealing with the principles of his instrument and his subject.

To the medical student, and even to the histologist and pathologist, a treatise which deals specifically with the Microscope, its principles, and their application in practice, cannot fail, one may venture to hope, to be of service.

This book is a practical attempt—the result of large experience and study—to meet this want in its latest form ; and I sincerely desire that it may prove useful to many.

W. H. DALLINGER.

LONDON : 1891.

EXPLANATION OF PLATES

FRONTISPIECE

Fig. 1. × 6 diameters. Horizontal and transverse section of an orbitolite.

Fig. 2. An imperfect or uncritical image of the minute hairs on the lining membrane of the extremity of the proboscis of the blow-fly × 510 diams., taken with a Zeiss apochromatic ½-inch objective of ·95 N.A. × 3 projection eye-piece; but it was illuminated by a cone of small angle, viz. of 0·1 N.A., and illustrates the unadvisability of small cones for illumination.

The first obvious feature in the picture is the doubling of the hairs which are out of focus; but the important difference lies in the bright line with a dark edge round the hairs which are precisely in focus. This is a diffraction effect which is always present round the outlines of every object illuminated by a cone of insufficient angle. Experiment shows that this diffraction line always ceases to be visible when the aperture of the illuminating cone is equal to about two-thirds the aperture of the objective used; but it will become again distinctly apparent when the aperture of the cone is reduced less than half that of the objective.

Fig. 3. × 510 diams. A correct or critical image of the minute hairs on the lining membrane of the extremity of the blow-fly's proboscis. In this picture the focus has been adjusted for the long central hair. It will be observed that this hair is very fine and spinous; it has not the ring socket which is common to many hairs on insects, but grows from a very delicate membrane, which in the balsam mount is transparent. This photograph was taken with a Zeiss apochromatic ⅛ of ·95 N.A. × 3 projection eye-piece. The illumination was that of a large solid axial cone of ·65 N.A. from an achromatic condenser, the source of light being focussed on the object.

Fig. 4. Section of cerebellum of a lamb, × 77 diams., by apochromatic 1-inch .3 N.A. This preparation was courteously supplied to the present Editor by Dr. Hill, whose imbedding and staining processes for these tissues it beautifully illustrates.

Fig. 5. Amphipleura pellucida × 1860 diams., by apochromatic 1/12 1·4 N.A. illuminated by a very oblique pencil in one azimuth along the valve.

Fig. 6. A hair of Polyxenus lagurus, a well-known and excellent test object for medium powers × 490 diams. by apochromatic ⅛ ·95 N.A.

Fig. 7. A small vessel in the bladder of a frog, prepared with nitrate of silver stain, showing endothelium-cells, × 40 diams., by Zeiss A. ·2 N.A. This object has been photographed for the purpose of exposing the fallacy which underlies the generally accepted statement that 'low-angled' glasses are the most suitable for histological purposes. The supposition that it is so has been founded on the fact that the penetration of a lens varies inversely as its aperture; therefore, it is said, a 'low-angled' glass is to be preferred to a wide-angled one, because 'depth of focus,' which is supposed to enable one to see into tissues, is the end in view.

On carefully examining this figure it will be noticed that it is almost

impossible to trace the outline of any particular endothelium-cell because its image is confused with that of the lower side of the pipe. In a monocular microscopical image a perspective view does not exist; it is better, therefore, to use a wide-angled lens, and so obtain a clear view of a thin plane at one time, and educate the mind to appreciate solidity by means of focal adjustment. It will be admitted that unless one approaches fig. 7 with a preconceived idea of what an endothelium-cell is like, the knowledge gained of it will be small indeed.

Fig. 8 represents the same structure, × 138 diams., by an apochromatic $\frac{1}{2}$ ·65 N.A. Here only the upper surface of the pipe is seen, so that the outline of the endothelium-cells can be clearly traced. The circular elastic tissue is also displayed. There is, moreover, an increased sharpness over the whole picture, due to the greater aperture of the objective.

PLATE I

Fig. 1. The inside of a valve of Pleurosigma angulatum, showing a 'postage stamp' fracture, × 1750 diams., with an apochromatic $\frac{1}{12}$ 1·4 N.A. by Mr. T. F. Smith, and illustrating his view of the nature of the Pleurosigma valve.

Fig. 2. The outside of a valve of Pleurosigma angulatum, showing a different form of structure. × 1750 diams., with an apochromatic $\frac{1}{12}$ 1·4 N.A., by Mr. T. F. Smith. These two photo-micrographs demonstrate the existence of at least two layers in the angulatum.

Fig. 3. Coscinodiscus asteromphalus, × 110 diams., with an apochromatic 1-inch ·3 N.A.

Fig. 4. A portion of the preceding, × 2000 diams. to show the lacework inside the areolations. This lacework is believed to be a perforated structure, as a fracture passes through the markings. In the central areolation there are forty-six smaller perforations surrounded by a crown of fifteen larger ones.[1] Photographed with an apochromatic $\frac{1}{8}$ 1·4 N.A.

Fig. 5. Aulacodiscus Kittonii, × 270, by an apochromatic 1-inch ·3 N.A.

Fig. 6. A small portion in the centre of an Aulacodiscus Sturtii, × 2000, by an apochromatic $\frac{1}{8}$ 1·4 N.A. Broadly speaking, the difference between the Coscinodisci and the Aulacodisci lies in the fact that in the former the secondary structure is inside the primary, while in the latter it is exterior to it. This definition, however, is not strictly accurate, as it is believed that the fine perforated structure covers the entire valve, it being only optically hidden by the primary structure.

The whole of these demonstrations were photographed for the present Editor by his friend E. M. Nelson, Esq., and have been reproduced from the negatives by a process of photo-printing.

PLATE II

ARRANGEMENT OF THE MICROSCOPE WITH A STAND FOR THE MICROMETER EYE-PIECE, TO SECURE STEADINESS AND ACCURACY IN MEASUREMENT

PLATE III

ARRANGEMENT OF THE MICROSCOPE AND ACCESSORIES FOR THE EMPLOYMENT OF THE CAMERA LUCIDA

PLATE IV

THE METHOD OF USING THE SILVER SIDE REFLECTOR OR PARABOLOID

[1] A section of this diatom will be found in the *Transactions of the County of Middlesex Natural History Society* for 1889, Plate I. fig. 2.

PLATE V

METHOD OF USING DIRECT TRANSMITTED LIGHT WITHOUT THE EMPLOYMENT OF THE MIRROR

PLATES II. to V. are engraved from photographs, taken at the request of the Editor by Mr. E. M. Nelson, from the arranged instruments.

PLATE VI

SEXUAL GENERATION OF VOLVOX GLOBATOR. (After [illegible])

Fig. 1. Sphere of *Volvox globator* at the epoch of sexual [illegible] sperm-cell containing cluster of antherozoids; a^2, sperm-cell [illegible] view of discoidal cluster of antherozoids; a^3, sperm-cell who[illegible] broken up into its component antherozoids; a^4, sperm-cell par[illegible] the escape of its antherozoids; $b\,b$, flask-shaped germ-cells su[illegible] increase in size without subdivision; b^2, b^3, germ-cells with large vacuoles in their interior; b^4, germ-cell whose shape has changed to the globular.

Fig. 2. Sexual cell, a, distinguishable from sterile cells, b, by its larger size.

Fig. 3. Germ-cell, with antheroids swarming over its endochrome.

Fig. 4. Fertilised germ-cell, or oösphere, with dense envelope.

Fig. 5. Sperm-cell, with its contained cluster of antherozoids, more enlarged.

Figs. 6, 7. Liberated antherozoids, with their flagella.

PLATE VII

OSCILLARIACEÆ AND SCYTONEMACEÆ

Fig. 1. *Lyngbya æstuarii*, Lieb. × 160.
Fig. 2. *Spirulina Jenneri*, Ktz. × 400.
Fig. 3. *Tolypothrix cirrhosa*, Carm. × 400.
Fig. 4. *Oscillaria insignis*, Thw. × 400.
Fig. 5. *O. Frolichii*, Ktz. × 400.
Fig. 6. *O. tenerrima*, Ktz. × 400.
These figures are after Cooke.

PLATE VIII

DESMIDIACEÆ, RIVULARIACEÆ, AND SCYTONEMACEÆ

Fig. 1. Zygosperm of *Micrasterias denticulata*, Bréb. (After Ralfs.)
Fig. 2. *Cosmarium Brebissonii*, Men. (After Cooke.)
Fig. 3. *Euastrum pectinatum*, Bréb. (After Ralfs.)
Fig. 4. Zygosperm of *Staurastrum hirsutum*, Bréb. (After Ralfs.)
Fig. 5. *S. gracile*, Ralfs. (After Cooke.)
Fig. 6. *Xanthidium aculeatum*, Ehrb. (After Ralfs.)
Fig. 7. *Rivularia dura*, Ktz. (After Cooke.)
Fig. 8. *R. dura*, Ktz. × 400. (After Cooke.)
Fig. 9. *Scytonema natans*, Bréb. × 400. (After Cooke.)
Fig. 10. *Staurastrum hirsutum*, Bréb. (After Cooke.)

PLATE IX

DESMIDIACEÆ

Fig. 1. *Micrasterias crux-melitensis*, Ehrb. (After Cooke.)
Fig. 2. *Closterium setaceum*, Ehrb. (After Cooke.)
Fig. 3. *Desmidium Swartzii*, Ag. (After Cooke.)
Fig. 4. *Penium digitus*, Ehrb. (After Cooke.)
Fig. 5. *P. digitus*, Ehrb. (transverse view).
Fig. 6. *Spirotænia condensata*, Bréb. (After Cooke.)
Fig. 7. *Docidium baculum*, Bréb. (After Cooke.)
Fig. 8. *Gonatozygon Brebissonii*, De Bary, conjugating. (After Cooke.)

PLATE X

PLEUROSIGMA ANGULATUM

This is a direct photo-micrograph, taken by Dr. R. Zeiss, as magnified 4900 diameters. We direct attention specially to it as giving evidence of the presence (however originated) of the intercostal markings, which may be seen with considerable clearness on the right-hand side of the midrib and in the middle of the valve.

PLATE XI

This plate has a twofold purpose. It is designed, first, to justify the opinions held by Dr. Henry van Heurck upon the structure of the valves of diatoms, and also to show how the usual microscopical tests present themselves when examined with the new objective with N.A. 1·60, lately constructed by the Firm of Zeiss. This objective is believed by Dr. van Heurck to realise what he considers the highest results of photographic optics, which in his judgment could only be surpassed by finding a new immersion liquid of still higher refractive index presenting all the necessary qualities, and which at the same time would not affect the very delicate flint of which it is necessary to make the front lens of this objective. This medium he hopes may be some day realised. Unfortunately, up to this time, no indication permits us to foresee the discovery of the liquid desired.

The following is the way in which Dr. Henry van Heurck summarises his ideas upon the structure of the valve :-

1. The valve of diatoms [1] is formed by two membranes or thin plates and by an intermediate septum. By this he understands a plate pierced with openings. The superior membrane, often very delicate, may be destroyed in the treatment by acids in the washings, by rubbing, &c. It is possible also that it sometimes only exists in a very rudimentary state. The majority of the students of diatoms agree in believing that these membranes may be sufficiently permeable to permit of exchange by endosmose between the contents of the valve and the surrounding outer water, but that these membranes have no real openings so long as the diatom is living and intact.

2. When the openings of the septum are disposed in alternate rows then they take an hexagonal form. When in perpendicular rows then the openings are square or elongated. The hexagonal form, which is besides so frequent in nature, seems to be the typical form of the openings of the septum, and it is found most frequently when the valve is large, destitute of consolidated sides, and must offer resistance to outside agents. Even in the forms of the square openings we see very frequently deviations and returns to the hexagonal type upon certain parts of the valve. It is possible that the septa may be sometimes composed of many layers, placed one above another, formed successively and closely united; but up to this time we have no proof of it, neither have we met with any form presenting layers placed one above another.

[1] 'The structure of the Valve of Diatoms' in *Records of the Belgian Society*, v. xiii. 1890.

Such, in brief, is the view held by Dr. van Heurck as an interpretation of our present knowledge of the structure of the valve of the diatoms. We give now a description of the objects represented on the plate.

Figs. 1, 2, 3. *Amphipleura pellucida*, Kütz, 1 and 2, valve resolved into pearls. Fig. 2 × 2000 diams. Fig. 1 × 3000 diams. Fig. 3. Valve resolved in striæ at about 2300 diams.

Fig. 4. *Amphipleura Lindheimeri*, Gr., × 2500 diams.

Fig. 5. *Pleurosigma angulatum*, in hexagons, × (about) 10,000 diams.

Fig. 6. *Idem* × 2000 diams., illusory pearls which are formed by the angles of the hexagonal cells when the focussing is not perfect.

Fig. 7. The nineteenth band of Nobert's test plate. This photo-micrograph has been made exceptionally with the apochromatic $\frac{1}{12}$ of 1·4 N.A. The lines being traced upon a cover in crown-glass, the objective of N.A. 1·6 cannot be used here.

Fig. 8. *Surirella gemma*, Ehrb. × (about) 1000 diams.

Fig. 9. *Van Heurckia crassinervis*, Bréb. (Frustulia saxonica, Rabh) × 2000 diams.

All the photo-micrographs (except fig. 7) have been done with the new $\frac{1}{10}$-inch N.A. 1·60 of MM. Zeiss.

These micro-photographs have been produced by sunlight in a monochromatic form, the special compensating eye-piece 12, and the Abbe condenser of N.A. 1·6.

Covers and slides in flint of 1·72; diatoms in a medium 2·4.

We are bound, however, to note that the condenser used is not corrected in any way; its aberrations are enormous. Although the highest admiration must be expressed for the skill exercised by Dr. van Heurck in these remarkable photo-micrographs, and the highest esteem for his courtesy to the present Editor in supplying them, it must not be forgotten that Dr. van Heurck was obliged to employ an imperfect condenser—a condenser absolutely uncorrected—and although we can testify to the high quality and fine corrections of at least one of the lenses of N.A. 1·6, we are convinced that much of its real perfection in image-forming is destroyed by uncorrected sub-stage illumination. Upon the corrections and large aplanatic area presented by the condenser and its careful and efficient employment depends entirely the nature of the image presented by the finest objective ever constructed; and as the perfection of the objective, with a high amplification and a great aperture, is more nearly approached, the more dependent are we upon perfect corrections in the condenser to bring out the perfect image-forming power of the objective. No image formed by such an objective as that possessing N.A. 1·60 can be considered reliable until a condenser corrected for all abberrations like the objective itself is produced; and so convinced are we of the possible value of this objective that we trust its distinguished devisor and maker may be soon induced to produce the condenser referred to.

If, then, by the aid of the chemist we can discover media which will be of sufficiently high refractive index, and still tolerant of or non-injurious to organic tissues immersed in it, a new line of investigation may be open to histology and pathology.—W. H. D.

PLATE XII

ARACHNOIDISCUS JAPONICUS. (After R. Beck)

The specimens attached to the surface of a sea-weed are represented as seen under a $\frac{1}{2}$th objective, with Lieberkühn illumination: A, internal surface; B, external surface; C, front view, showing incipient subdivision.

PLATE XIII

COMPLETE LIFE-HISTORIES OF TWO SAPROPHYTES
(Drawn from nature by Dr. Dallinger)

PLATE XIV

The various stages of the development of the nucleus in two saprophytic organisms, as studied with recent homogeneous and apochromatic objectives, both in the several stages of fission and genetic fusion, indicating *karyokinesis*, and proving, as established in detail by the text, that all the steps in the cyclic changes of these unicellular forms are initiated in the nucleus before being participated in by the whole body of the organism. (Drawn from nature by Dr. Dallinger.)

PLATE XV

ROTIFERÆ

Fig. 1. *Floscularia campanulata.*
Fig. 2. *Stephanoceros Eichhornii.*
Fig. 3. *Melicerta ringens.*
Fig. 4. *Pedalion mirum* (side view).
Fig. 5. *P. mirum* (dorsal view, showing muscles).
Fig. 6. *Copeus cerberus* (side view).
Fig. 7. *Philodina aculeata* (side view, corona expanded).
Fig. 8. Male of *Pedalion mirum.*

All these figures, save fig. 2, are reduced to scale from the beautiful plates in Hudson and Goss's *Rotifera.*

PLATE XVI

FORAMINIFERA

Fig. 1. *Miliolina seminulum* (*a* and *b*, lateral aspects).
Fig. 2. *Alveolina Boscii* (*a*, lateral aspect; *b*, longitudinal section).
Fig. 3. *Astrorhiza limicola* (*a*, lateral aspect; *b*, portion of the test more highly magnified, showing structure).
Fig. 4. *Haliphysema Tumanowiczii*, showing the pseudo-polythalamous foot.
Fig. 5. *Ibid.* (group of specimens *in situ*).
Fig. 6. *Haplophragmium agglutinans* (*a*, lateral aspect; *b*, longitudinal section).
Fig. 7. *H. nanum* (*a*, superior aspect; *b*, peripheral aspect).
Fig. 8. *Textularia gramen* (*a*, lateral aspect; *b*, oral aspect).
Fig. 9. *T. gramen* (peripheral aspect).
Fig. 9*a*. *Paronina flabelliformis* (*a*, lateral aspect; *b*, oral aspect).
Fig. 10. *Bulminia spinulosa.*
Fig. 11. *Chilostomella ovoidea* (*a* and *b*, lateral aspects; *c*, specimen mounted in Canada balsam and seen with transmitted light).

PLATE XVII

FORAMINIFERA

Fig. 12. *Lagena sulcata.*
Fig. 13. *L. sulcata.*
Fig. 14. *L. sulcata.*
Fig. 15. *L. sulcata* (*a*, lateral aspect; *b*, oral aspect).
Fig. 16. *Nodosaria raphanus.*
Fig. 17. *Cristellaria calcar* (*a*, *b*, *c*, lateral aspects).
Fig. 18. *Ramulina globulifera.*
Fig. 19. *R. globulifera.*
Fig. 20. *Globigerina bulloides* (var. *triloba*, pelagic specimen).
Fig. 21. *G. bulloides* (*a*, *b*, *c*, adult typical shell).

Fig. 22. *Rotalia Beccarii.*
Fig. 23. *Polystomella crateulata.*
Fig. 24. *Amphistegina Lessonii* (*a*, superior lateral aspect; *b*, inferior lateral aspect; *c*, peripheral aspect).
Fig. 25. *Nummulites lævigata* (*b*, lateral aspect; *a*, vertical section).
Fig. 26. Portion of *Orbitoides nummulitica.*

PLATES XVIII, XIX, XX

ACARINA

All the figures, except fig. 4, Plate XX., are copied from plates drawn by Mr. A. D. Michael, F.L.S., &c. by the kind permission of the respective societies that published them. Figs. 1 to 6, Plate XVIII., and 1 to 3, Plate XIX., are from 'British Oribatidæ,' published by the Ray Society; fig. 7, Plate XVIII., from the 'Journal of the Linnean Society'; fig. 4, Plate XIX., and fig. 3, Plate XX., from the 'Journal of the Royal Microscopical Society'; fig. 5, Plate XIX., and figs. 1 and 2, Plate XX., from the 'Journal of the Quekett Microscopical Club.' Fig. 4, Plate XX., is drawn after Fürstenberg by the Editor.

PLATE XVIII

ORIBATIDÆ

Fig. 1. Anatomy of *Nothrus tholeproctus* (male, dorsal aspect, × about 60). The dorsal portion of the chitinous exo-skeleton, and the fat and muscles which underlie it, have been removed from the abdomen. The internal organs are shown protruding, as they usually do when the creature is opened, as though they were too large to be contained in the ventral exo-skelcton. Part of the œsophagus is seen at the top (the brain having been removed). The preventricular glands (brown) lie on each side of the œsophagus. The ventriculus is coloured pink; part of it and the whole of the cæca are covered with botryoidal tissue (yellow). The testes (white shaded with blue) show at the sides protruding from beneath the alimentary canal.

Fig. 2. *Hoplophora magna* (female, lateral aspect, × about 50). The chitin at the side and the fatty tissue and muscles have been removed. Alimentary canal pink; cæca of the ventriculus spotted; preventricular glands brown; supercoxal gland white; its vesicles yellow; expulsory vesicle, between supercoxal and ovaries, grey; ovary and oviducts white shaded with blue and yellow. The genital and anal plates are open, and the genital suckers protruding. One maxilla, white, is seen between the legs.

Fig. 3. *Tegeocranus latus* (female, dorsal aspect, × about 55). Dorsal exo-skeleton, fatty tissue, and muscles removed. Same colours as before. Brain (between preventricular glands) blue grey. Mandibles seen from above and behind, their retractor muscles cut short. The tracheæ, which are present in this species, are seen proceeding to their stigmata in the acetabula of the legs.

Fig. 4. Female genital organs of *Cepheus tegeocranus* (× about 25), Vigt. Central ovary, oviducts with eggs, vagina and ovipositor.

Fig. 5. The same of *Damæus geniculatus* (× about 20). The genital plates and the muscles and tendons which move them, and the genital suckers, are shown.

These two figures are reduced from the originals.

Fig. 6. Nymph (active pupal stage) of *Tegeocranus hericius* (× about 100) carrying its cast dorsal skins).

TYROGLYPHIDÆ

Fig. 7. Hypopial (travelling) nymph of *Rhizoglyphus Robini* (ventral aspect, × 100).

PLATE XIX

ORIBATIDÆ

Fig. 1. *Leiosoma palmicinctum* (× about 40).
Fig. 2. Nymph of same species, fully grown (× about 55). The central ellipse with the innermost set of scales attached is the cast larval dorsal abdominal skin. The other rows of scales belong to the successive nymphal skins.
Fig. 3. One of the scales more highly magnified.

CHEYLETIDÆ

Fig. 4. Rostrum and great raptorial palpi, with their appendages of *Cheyletus venustissimus* (× about 150).

MYOBIIDÆ

Fig. 5. *Myobia chiropteralis* (female, × about 125).

PLATE XX

Claw of first leg of same species, being an organ for holding the hair of the bat.

GAMASIDÆ

Fig. 2. *Gamasus terribilis* (male, × 30). A species found in moles' nests.

ANALGINÆ

Fig. 3. *Freyana heteropus* (male, × about 95, a parasite of the cormorant).
Fig. 4. *Sarcoptes scabiei* (the itch mite, × about 150, adult female).

Errata

Page 375, line 25, for *oscillaricæ* read *Oscillariaceæ*.
„ 677, „ 7, for *Cocodia* read *Coccidia*.
„ 702, „ 3 from bottom, for *Ophridium* read *Ophrydium*.
„ 706, „ 3, for *Ophryda* read *Ophrydia*.
„ 770, „ 14, *for* single *read* simple.

PLATE 1.

1

X1750

2



X1750

3



X110

4



X2000

5



X270

6



X2000



THE MICROSCOPE

CHAPTER I

ELEMENTARY PRINCIPLES OF MICROSCOPICAL OPTICS

To be the owner of a well-chosen and admirably equipped *microscope*, and even to have learnt the general purpose and relations of its parts and appliances, is by no means to be a master of the instrument, nor to be able to employ it to the full point of its efficiency even with moderate magnifying powers. It is an instrument of precision, and both on its mechanical and optical sides requires an intelligent understanding of *principles* before the best optical results can be invariably obtained.

We may be in a position, with equal facility, to buy a high-class microscope and a high-class harp; but the mere possession makes us no more a master of the instrument in the one case than the other. An intelligent understanding and experimental training are needful to enable the owner to use either instrument. In the case of the microscope, for the great majority of purposes to which it is applied in science, the amount of study and experimental training needed is by comparison incomparably less than in the case of the musical instrument. But the amount required is absolutely essential, the neglect of it being the constant cause of loss of early enthusiasm and not infrequent total failure.

In the following pages we propose to treat the elementary principles of the optics of the microscope in a practical manner, not merely laying down dogmatic statements, but endeavouring to show the student how to demonstrate and comprehend the application of each general principle. But in doing this we are bound to remember a large section of the readers who will employ this treatise, and to so treat the subject that all the examples given, or that may be subsequently required by the ordinary microscopist, may be worked out with no heavier demand upon mathematics than the employment of vulgar fractions and decimals.

In like manner, although we shall again and again employ the trigonometrical expression 'sine,' its use will not involve a mathematical knowledge of its meaning. The sines of angles may be found

by published tables. A table to quarter degrees is given in Appendi A of this book, which will, in the majority of cases, suffice; it is nc difficult to find such tables as may be required.[1]

Of course it is more than desirable that the microscopist shoul have good mathematical knowledge; but there are many men wh desire to obtain a useful knowledge of the principles of elementar optics who are without time or inclination, or both, to obtain th large mathematical knowledge required.

Now just as a man who is without any accurate knowledge o astronomy or mathematics may find *time* from a sun-dial by applyin the equation of time taken from a table in an almanac, so by th use of a table of sines the microscopist may reach useful and reliabl results, although he may have no clear knowledge of trigonometry physical optics, nor the mathematical proof of formulæ.

All microscopes, whether *simple* or *compound*, in ordinary us depend for their magnifying power upon the ability possessed b lenses to *refract* or bend the light which passes through them. Re fraction acts in accordance with the two following laws, viz. :—

1. A ray which in passing from a rare medium into a dense medium makes a certain angle with the *normal*, i.e. *the perpendicu lar* to the surface or plane at which the two media join, will, or entering the denser medium, make a *smaller angle with the normal* Conversely, a ray passing out from a dense medium into a rarer one making a certain angle with the normal will, on emergence from the dense medium, make a greater angle with the normal.

The ray in one medium is called the *incident* ray, and in the other medium the *refracted* ray.

The incident and refracted rays are always in the same plane.

2. The sine of the angle of incidence divided by the sine of the angle of refraction is a constant quantity for any two particular media.

When one of the media is air (accurately a vacuum) the ratio o these sines is called the absolute refractive index of the medium As every known medium is denser than a vacuum it follows tha the angle of the refracted ray in that medium will be less than th angle of the incident ray in a vacuum; consequently, the absolut refractive index of any medium is greater than unity.

Further, the absolute refractive index for any particular substanc will differ according to the colour of the ray of light employed. Th refraction is least for the red, and greatest for the violet. Th difference between these refractive values determines what is call the *dispersive power* of the substance.

This will be understood by fig. 1. Let I C, a ray of light trave ling in air, meet the surface A B of water at the point C. Throu C draw N N′ at right angles to the surface of the water A B. T line N N′ is called the *normal* to the surface A B. The ray I C w not continue its path through the water in a straight line to Q; b because water is denser than air, it will be bent to R, that towards N′. The whole course of the ray will be I C R, of wh the part I C is called the *incident ray*, and C R the *refracted r*

[1] *Vide* Chambers's *Mathematical Tables.*

The angle I C makes with the normal N N′, viz. I C N, is called the *angle of incidence*; and the angle R C makes with the normal N′ N, viz. R C N′, is called the *angle of refraction*.

Conversely, if a ray R C, travelling in water, meet the surface of air A B in the point C, it will not continue in a straight line, but will be bent to the point I farther away from N. Thus, when a ray passes from a rarer to a denser medium it is bent or refracted *towards* the normal, and when it passes out of a dense medium into a rarer one it is bent or refracted *away* from the normal.

Further, if the shaded portion of the figure were glass instead of water, the refracted ray R C would be bent still nearer N′, and, conversely, if the ray passed out of glass into air, it would be more bent away from the normal than if it had passed out of water into air.



FIG. 1.—The refraction of light. The law of sines.

The angle of incidence I C N is connected with the angle of refraction R C N′ (as stated above) by what is known as Snell's Law of Sines. The constant relation between the two sines for two specific media is called the *refractive index* of the medium, and is usually indicated in problems by the symbol μ.

This law, stated with reference to the figure, would be:

$$\frac{\text{sine I C N}}{\text{sine R C N}'} = \mu = \text{the refractive index of water.}$$

In I C take any point, P, and from P draw P T perpendicular to N N′. Similarly in R C take any point, F, and draw F H perpendicular to N N′.

Now, as sine $ICN = \frac{PT}{PC}$, and sine $RCN' = \frac{FH}{FC}$, then, by Snell's law, $\frac{\frac{PT}{PC}}{\frac{FH}{FC}} = \mu$.

As any points may be taken in I C and R C if the points had been more judiciously selected, we might have greatly simplified the above expression. Thus, if we take two other points, K and E, such that K C = E C, and draw the perpendiculars as before, we shall have sine $ICN = \frac{KS}{KC}$ and sine $RCN' = \frac{ED}{EC}$, and therefore $\frac{\frac{KS}{KC}}{\frac{ED}{EC}} = \mu$.

But as K C = E C by construction, we can write K C for E C thus: $\frac{\frac{KS}{KC}}{\frac{ED}{KC}} = \mu$. K C is cancelled, which leaves $\frac{KS}{ED} = \mu$.

As μ can be experimentally determined for any two particular media, it follows that if one of the other terms is known, then the remaining term can be found. Thus, if μ and the angle of incidence are known, the angle of refraction can be found; and if μ and the angle of refraction are known, the angle of incidence can be found. The unknown quantity can be found either geometrically or by calculation when the other two terms are given.

It will, of course, be understood that, for the same medium in every case, a red ray would be bent or refracted less than a violet ray. The value therefore of μ for a red ray will be less than that of μ' for a violet ray. As a practical illustration: The refractive index for a red ray in crown glass is $1{\cdot}5124 = \mu$, and for a violet ray is $1{\cdot}5288 = \mu'$, the difference being $\mu' - \mu = {\cdot}0164$.

The refractive index for a red ray in dense flint glass is $1{\cdot}7030 = \mu$, and for a violet ray is $1{\cdot}7501 = \mu'$, the difference being $\mu' - \mu = {\cdot}0471$.

Consequently there will be a greater difference between the bending of the refracted red and violet rays in the case of dense flint than in the case of crown glass, the angle of the incident ray with the normal being the same in either case.

Where air (more correctly a vacuum) is not one of the media then the refractive index is called the *relative* refractive index.

The *normal to a plane surface* is always the perpendicular to it the *normal to a spherical surface* is the radius of curvature. The angle of the incident ray and the angle of the refracted ray are always measured *with the normal*, and not with the surface.

Fig. 2, *a*, *b*, shows the *normals* A, B to both a plane and spherical surface, C D.

In the case of the spherical surface, B is the centre of curvature, E

is the incident ray in air, F G the refracted ray in crow[illegible] ie angle A F E is the angle of incidence, B F G the angle [illegible]

Sine A F E divided by sine B F G is equal to the ref active i[illegible] of air into crown glass, or, in other words, the absolu[illegible] refi index of crown glass, μ; thus in this particular case:

(Problem) I.:

$$\frac{\sin A F E}{\sin B F G} = \frac{\sin 45°}{\sin 28°} = \frac{\cdot 707}{\cdot 472} = \frac{3}{2} = \mu.$$

This problem, however, is not actually needed by the reader of this book, for a table of absolute refractive indices is given in Appendix B.

It will be clear from the above that when the refractive index, absolute or relative, of a ray from any first medium is given, the refractive index from the second to the first may be found.

Thus, the absolute refractive index μ from air into glass being given as $\frac{3}{2}$, find μ', the refractive index from glass into air.

(Problem) II.:

$$\mu' = \frac{1}{\mu} = \frac{1}{\frac{3}{2}} = \frac{2}{3}.$$

When the absolute refractive indices of any two media are given, the relative refractive indices between the media can be found.

Thus, the absolute refractive index μ of crown glass is 1·5, and the absolute refractive index μ' of flint glass is 1·6; find the relative refractive index μ'' from crown to flint.





FIG. 2.—The normals to a plane and a curved surface.

(Problem) III.: $\mu'' = \frac{\mu'}{\mu} = \frac{1·6}{1·5} = 1·066.$

The relative refractive index μ''' from flint to crown is determined by (problem) ii.:

$$\mu''' = \frac{1}{\mu''} = \frac{1}{1·066} = ·938$$

Let us now suppose that in fig. 2 the ray is travelling in the opposite direction. G F in the denser medium will now be the incident ray, and F E in the rarer medium will be the refracted ray. Now if the angle B F G be increased, the angle A F E will also be in

FIG. 8.—The phenomenon of total reflexion. (From the 'Forces of Nature,' published by Macmillan.)

creased in a greater proportion, and the ray F E will approach the surface F D.

When F E coincides with F D, G F is said to be incident at the *critical angle* of the medium. When this critical angle is reached none of the incident light will pass out of the denser medium, but

will be totally reflected from the surface C D back into the denser medium.

A simple illustration of this is shown in fig. 3. It represents a glass of water so held that the surface of the water is above the eye. If we look obliquely from below at this surface, it appears brighter than polished silver, and an object placed in the water has the upper portion of it brightly reflected.

The action on all light incident on C D in the denser medium (fig. 2) at an angle greater than the critical angle is precisely the same in fact as if C D were a silvered mirror.

A critical angle can only exist in a denser medium, for obviously there can be no critical angle in the rarer medium, since a ray of any angle of incidence can enter.

When the relative or absolute refractive index of the denser medium is given, the critical angle for that medium can be found, thus: The absolute refractive index of water is $1{\cdot}33 = \mu$; find its critical angle θ.

(Problem) IV.: $$\text{Sin } \theta = \frac{1}{\mu} = \frac{1}{1{\cdot}33} = {\cdot}75;$$
$$\theta = 48\tfrac{1}{2}^\circ \text{ (found by table).}$$

So the sine of the critical angle is the reciprocal of the refractive index.

The connection between the path of an incident ray in a first medium and its refracted ray in a second medium is established by the formula

$$\mu \sin \phi = \mu' \sin \phi',$$

where μ is the absolute refractive index of the first medium, ϕ the angle of the incident ray in it, μ' the absolute refractive index of the second medium, and ϕ' the angle of the refracted ray in it.

The angle $\phi = 45^\circ$ of the incident ray in the first medium A F E (fig. 2) and $\mu = 1$ $\mu' = \frac{3}{2}$, the absolute refractive indices of both the media, air and glass respectively, being given, find ϕ', the angle of the refracted ray in glass.

(Problem) V. 1:
$$\text{Sin } \phi' = \frac{\mu \sin \phi}{\mu'} = \frac{1 \times \sin 45^\circ}{1{\cdot}5} = \frac{1 \times {\cdot}707}{1{\cdot}5} = {\cdot}471;$$
$$\phi' = 28^\circ \text{ (found by table).}$$

To put another case. Suppose the angle $\phi' = 28^\circ$ (fig. 2, B F G) is given; find ϕ, the refractive indices remaining the same as before.

(Problem) V. 2:
$$\text{Sin } \phi = \frac{\mu' \sin \phi'}{\mu} = \frac{1{\cdot}5 \times \sin 28^\circ}{1} = \frac{1{\cdot}5 \times {\cdot}741}{1} = {\cdot}7065.$$
$$\phi = 45^\circ \text{ (found by table).}$$

Now, suppose the A side of C D (fig. 2) is crown glass, $\mu = 1{\cdot}5$, and the B side of C D is flint glass, $\mu' = 1{\cdot}6$. The angle of the incident ray A F E $\phi = 45^\circ$, find the angle of the refracted ray ϕ' or B F G.

Problem V. 3 :

$$\text{Sin } \phi' = \frac{\mu \sin \phi}{\mu'} = \frac{1{\cdot}5 \times \sin 45}{1{\cdot}6} = \frac{1{\cdot}5 \times {\cdot}707}{1{\cdot}6} = \frac{1{\cdot}0605}{1{\cdot}6} = {\cdot}663.$$

$\phi' = 41\frac{1}{2}°$ (found by table).

As a final instance. Suppose the ray to be travelling in the opposite direction, so that G F is the incident ray and B F G, or $\phi' = 41\frac{1}{2}°$, be given, the media being the same as in the last case, $\mu' = 1{\cdot}6$ and $\mu = 1{\cdot}5$, find ϕ, or the angle of the refracted ray.

(Problem) V. 4 :

$$\text{Sin } \phi = \frac{\mu' \sin \phi'}{\mu} = \frac{1{\cdot}6 \sin 41\frac{1}{2}°}{1{\cdot}5} = \frac{1{\cdot}6 \times {\cdot}663}{1{\cdot}5} = \frac{1{\cdot}0608}{1{\cdot}5} = {\cdot}707\ ;$$

$\phi = 45°$ (found by table).

The importance of the prism in practical optics is well known. Its geometrical form in perspective and in section is shown in fig. 4.

FIG. 4.—The geometrical form of the prism. (From the 'Forces of Nature.')

By means of the above problems and their solutions we are now able *to trace the divergence of a ray through a prism.*

In fig. 5 let A B C represent a prism of very dense flint glass whose absolute refractive indices μ' for *red light* is 1·7, and μ'' for blue light is 1·75. Let the refracting angle B A C of the prism = 50°, and let the angle of incidence of a ray of white light D E = 45° = ϕ in air, $\mu = 1$. The dotted lines show the *normals.* Then by (problem) v. 1 for red light we have for the angle of refraction ϕ'.

$$\sin \phi' = \frac{\mu \sin \phi}{\mu'} = \frac{1 \sin 45°}{1{\cdot}7} = \frac{{\cdot}707}{1{\cdot}7} = {\cdot}416\ ;$$

$\phi' = 24\frac{1}{2}°$ (found by table).

And for *blue light* :

$$\text{Sin } \phi'' = \frac{\mu \sin \phi}{\mu''} = \frac{1 \sin 45°}{1{\cdot}75} = \frac{{\cdot}707}{1{\cdot}75} = {\cdot}404\ ;$$

$\phi'' = 23\frac{3}{4}°$ (found by table).

Now, for the red ray draw E F (fig. 5), $24\frac{1}{2}°$ to the normal, and let it meet the other side of the prism A C in F. At F draw another normal.

On the scale of our diagram it is not possible to draw two lines E F, one for the red ray and the other for the blue, for they are too close together, their angular divergence being only $\frac{3}{4}°$. But by

measurement it will be found that E F makes, with [illegible] at F, an angle ϕ' of $25\frac{1}{2}°$, and for the blue ray an angle ϕ [illegible] of 2[illegible].

It should be remembered, however, that if the re[illegible]cting angle of the prism is known, there is no necessity for this measurement, because it is always the difference between this and the angle of refraction before determined, thus $50° - 24\frac{1}{2}° = 25\frac{1}{2}°$.



FIG. 5.—Diagram of de[illegible]

This ray E F now becomes th[illegible]
and as the angle it makes with the no[illegible]
the refractive indices remain the same, we can, by (proble[illegible]
find the angles of refraction for each colour.

If we take red light :

$$\text{Sin } \phi = \frac{\mu' \sin \phi'}{\mu} = \frac{1{\cdot}7 \sin 25\frac{1}{2}°}{1} = \frac{1{\cdot}7 \times {\cdot}43}{1} = {\cdot}732 ;$$

ϕ, the angle of refraction = 47° (found by table).

If we take blue light :

$$\text{Sin } \phi = \frac{\mu'' \sin \phi''}{\mu} = \frac{1{\cdot}75 \sin 26\frac{1}{4}°}{1} = \frac{1{\cdot}75 \times {\cdot}442}{1} = {\cdot}774 ;$$

ϕ, the angle of refraction = $50\frac{3}{4}°$ (found by table).

This *dispersion* can now be represented in the diagram, seeing that it amounts to $3\frac{3}{4}°$.

In optics it is convenient to use an expression to measure the dispersive power of diaphanous substances, which does not depend on the refracting angle of the prism employed. Further, in order that various substances may be compared, their dispersive powers are all measured with reference to a certain selected ray. (For this purpose the bisection of the D or sodium lines is the point in the spectrum often chosen.)

In the crown and flint glasses mentioned on page 4 the dispersion between the lines C and F, in the spectrum, referred to the bisection of the sodium lines D, is as follows. Crown glass :—refractive index bisection of lines D, $1{\cdot}5179 = \mu$; line F, $1{\cdot}52395 = \mu'$; line C, $1{\cdot}51535 = \mu''$. Then the dispersive power ω

$$= \frac{\mu' - \mu''}{\mu - 1} = \frac{1{\cdot}52395 - 1{\cdot}51535}{1{\cdot}5179 - 1} = \frac{{\cdot}0086}{{\cdot}5179} = {\cdot}01661.$$

The values of the same lines for the flint glass are as follows: D, $1{\cdot}7174 = \mu$; F, $1{\cdot}73489 = \mu'$; C, $1{\cdot}71055 = \mu''$.

$$\omega = \frac{\mu' - \mu''}{\mu - 1} = \frac{1{\cdot}73489 - 1{\cdot}71055}{1{\cdot}7174 \quad - 1} = \frac{{\cdot}02434}{{\cdot}7174} = {\cdot}0339.$$

So the dispersive power of the flint between the lines C and F is slightly more than twice that of the crown for the same region of the spectrum. In the above formula the expression $\mu' - \mu''$ is usually written $\delta\mu$; in full it is therefore $\omega = \frac{\delta\mu}{\mu - 1}$.

Having thus traced a ray experimentally through a prism, our next step is to show that a *convex lens is only a curved form of two such prisms* with their bases in contact, as is shown in A, fig. 6, where the curved line shows the lenticular character and the shaded elements the two prisms. A concave lens is in effect two prisms reversed, that is, with their apices in contact, as in B, fig. 6, where, again, the curved line shows the form of the lens and the shaded parts its relation to a pair of prisms. The fact that a lens is, in effect, as such, but an assemblage of superposed prisms is seen in fig. 7, the refracting angle of the prism being more acute as the principal axis is approached, and the deviation being greater as the angle is more obtuse.



FIG. 6.—Convex and concave lenses are related to the prism.



FIG. 7.—Proof that a lens may be considered as an assemblage of prisms. (From the 'Forces of Nature.')

In fig. 8 let O P be the axis in each case; then, from what we have seen, it is manifest that rays parallel to the axis falling on the prisms with their bases in contact and acting like a convex lens will be refracted towards the axis O P. But in the other case, where the prisms have their apices together, as in fig. 9, acting as a concave lens, the light is refracted away from the axis O P.



FIG. 8.—Action of a pair of prisms with their bases in contact on parallel light.



It must, however, be understood that there is a very important difference between the action of spherical lenses, *which is due to the different position of the normals.*

In the prisms (figs. 8, 9) the incident surface A B is a plane; and as the normals are perpendicular to it, they must be parallel to one another, whether near the base or near the apex. Thus the normal at E is parallel to the normal at K; therefore, whatever angle D E makes with the normal at E, H K will make a similar angle with the normal at K, *because the normals are parallel and the incident rays are parallel.*

But in the case of a spherical lens *the normals are radii*; parallelism is therefore impossible, and parallel incident rays will not make equal angles with them, and so the refracted rays will not be parallel.

This explains how it is that when rays parallel to the axis fall on the prism (see fig. 8) those which pass through the prisms *near their bases* cut the axis *nearer* the prisms than those which pass through near the apex.

But in a convex lens the reverse takes place; the rays passing through near the middle of the lens cut the axis *farther from* the lens than those which pass through the edge of the lens. The typical form of a biconvex or magnifying lens is shown in fig. 10,



FIG. 10.—Front and edge views of a biconvex lens.
(From the 'Forces of Nature.')

both in perspective, as seen from the edge, and with a full view of the disc; while the various forms which for various optical purposes are given to lenses is shown in figs. 11 and 12.

Now, if we study the four following figures, we shall see the principal action of lenses on light incident on their surfaces. Fig. 13 shows that if a radiant is placed at the principal focus of a converging lens, the rays are rendered parallel; conversely, if parallel rays fall on a converging lens, they are brought to a principal focus or point upon the axis.

Fig. 14 shows that if a radiant be placed *beyond* the principal

focus of a converging lens, the rays are brought to a focus *beyond* the principal focus on the other side of the lens. The nearer the radiant is to the principal focus, the farther away will be its *conjugate focus* from the other principal focus. In other words, there are two points in the axis such that if the object is one point its focus will be the other; these are reciprocal one to the other. These points,



FIG. 11.—Biconvex, plano-convex, and converging meniscus lenses. (From the 'Forces of Nature.')



FIG. 12.—Biconcave, plano-concave, and diverging meniscus lenses. (From the 'Forces of Nature.')

the focal distances of which can always be calculated, are known as *conjugate foci*.

Should the radiant be at a distance from the principal focus equal to the focal length of the lens (i.e. twice the focal length from the lens) then its conjugate will be at the same distance from the focus



FIG. 13.—A radiant at the principal focus of a biconvex lens makes the refracted rays parallel.



FIG. 14.—A radiant placed beyond the principal focus causes rays to converge beyond the principal focus on the other side of the lens.

on the other side of the lens (i.e. twice the focal length from the lens). In other words, when the object and its image are equidistant on either side of the lens, they are equal to each other *in size*, and are four times the focal length of the lens apart.

This law forms a ready means of determining the focal length of a lens. An object is placed in front of a lens and the distances between this object and the lens and a screen to receive the image of the object are so adjusted that *the image of the object becomes equal in size to the object itself*. The distance of the object from the screen divided by 4 gives the focal length of the lens.

If a radiant be placed *between* a lens and its principal focus, the rays on the other side of the lens are still *divergent*, and will never meet in a focus on that side. This is seen in fig. 15; but if they are traced backwards, as in the dotted lines of fig. 15, they will then



FIG. 15.—Rays diverge when a radiant is placed between a lens and its principal focus. Focus of divergent rays is virtual.

meet in a point. This is called the *virtual conjugate* focus of the radiant. The principal focus of a concave (or diverging) lens is shown in fig. 16. It will be seen that the principal focus is not *real* but *virtual*.[1] Parallel rays falling on a concave lens are rendered



FIG. 16.—'Virtual' focus of concave lens.

divergent on the other side of the lens, and consequently can never come to a focus. But if we trace these divergent rays backwards, as in the dotted lines of fig. 16, we find that they meet in a point, and this point is called the *virtual principal* focus of the lens.

It will be manifest that since the rays in passing through lenses of various kinds are *unequally refracted* they cannot all meet *exactly* in a single focal point. This gives rise to what is a most important feature in the behaviour of lenses, which is known as **spherical aberration**.

[1] A *real* image can be received on a screen, but a *virtual* image cannot.

Figs. 17 and 18 show the refraction of rays of monochromatic light parallel to the axis falling on a plano-convex lens of crown glass. These figures illustrate : (1) Longitudinal spherical aberration and (2) the focal length of a plano-convex lens and the point from which it is measured.

(1) In regard to the former it will be seen that the longitudinal spherical aberration is greatest in fig. 17, where the parallel rays of light fall upon the plane surface, and least where, as in fig. 18, they fall upon the spherical surface. For *spherical aberration is the*



FIG. 17.—Spherical aberration.

distance of the focus for any ray passing through a lens from the principal focus of that lens.

Thus in figs. 17, 18, the spherical aberration is F F′ for the rays $R^2 R^2$, and F F″ for the rays $R^1 R^1$, and the difference between the



FIG. 18.—Spherical aberration.

spherical aberration of the rays $R^1 R^1$ and that of the rays $R^2 R^2$ is F F″—F F′, which is F′ F″.

Thus F F′ and F F″ in (fig. 17), $\delta f = -\frac{9}{2} \cdot \frac{y^2}{f}$; F F′ and F F″ in (fig. 18) $\delta f = -\frac{7}{6} \cdot \frac{y^2}{f}$.

(2) In regard to the focal length of a plano-convex lens, it may be incidentally noted that the focal length in fig. 17 is twice the radius, measured from the vertex A, that is, A F. But in fig. 18 it is twice the radius measured from the point A ; that is, the point F is distant from the lens twice the radius less two-thirds the thickness of the lens.

It will be seen, then, that the *amount* of spherical aberration is due to the *shape* of the lens, and is least in a *biconvex lens*, when the radii of curvature are in the proportion of 6 : 1, *when the more curved surface faces the incident light.* But when the lens is turned round, so that the other side faces the incident light, the spherical aberration reaches a maximum.

It would be well for the student who desires to become familiar with these facts, without attempting any profound mathematical

grasp of them, to draw such a lens, and trace the paths of two rays through it, one near the axis, the other near the edge ; then do the same with the lens reversed.

Formula for spherical aberration : [1]

$$-\delta f = \frac{y^2}{f} \cdot \frac{\mu-1}{2\mu^2}\left\{\frac{1}{r^3} + \left(\frac{\mu+1}{f} - \frac{1}{r'}\right)\left(\frac{1}{f} - \frac{1}{r'}\right)^2\right\} f^3,$$

where f = principal focal length ; y = semi-aperture ; μ = refr. index ; and r, $-r'$, radii.

In an equi-convex of crown, where $\mu = \frac{3}{2}$, $r = -r'$, $\delta f = -\frac{5}{3} \cdot \frac{y^2}{f}$.

In a plano-convex of crown, where $\mu = \frac{3}{2}$, $-r' = \infty$, $r = \frac{f}{2}$, $\delta f = -\frac{7}{6} \cdot \frac{y^2}{f}$. Here parallel rays are incident on the convex surface. But when parallel rays are incident on the plane surface, $\mu = \frac{3}{2}$, $r = \infty$, $-r' = \frac{f}{2}$, $\delta f = -\frac{9}{2} \cdot \frac{y^2}{f}$; consequently the spherical aberration is four times as great (see figs. 17 and 18).

When $-r' = \infty$, and $\mu = 1{\cdot}69$, the plano-convex becomes the form of minimum aberration.

In a crossed [2] biconvex lens, where $-r' = 6r$, and $\mu = \frac{3}{2}$, $\delta f = -\frac{15}{14} \cdot \frac{y^2}{f}$, the parallel rays being incident on the more curved surface.

Formula for finding the principal focus F of a lens equivalent to two other lenses whose foci are f, f' and their distance apart d :

$$\frac{1}{F} = \frac{1}{f} + \frac{1}{f'} - \frac{d}{ff'}.$$

In figs. 5, 8, and 9 we see that when the incident ray D E consists of *white light*, the colours of which it is composed are unequally refracted ; the two extremes, R (red light) and V (violet light), being bent in different directions, the other colours lying between them in their proper order.

This unequal refraction of the different colours takes place in like manner in spherical lenses, and it is then known as *chromatic aberration.*

The effect of this upon the action of a lens is that, if parallel white light fall upon a convex surface, the most refrangible of its component rays (which, as we have seen, is the violet) will be brought to a focus at a point somewhat nearer the lens than the principal focus ; and the red ray, having the least refrangibility, will be brought to a focus at a point farther from the lens than its principal focus, which is, in effect, the mean of the chromatic foci.

[1] *Encyclopædia Brit.* vol. xvii.

[2] A biconvex lens is said to be 'crossed' when the radii of its surfaces are not equal to each other.

This will be fully understood by the aid of fig. 19.

The white light, A A", falling on the peripheral portion of the lens, is so far dispersed or decomposed that the violet rays are brought to a focus at C, and, crossing there, diverge again and pass on towards F F; whilst the red rays are not brought to a focus until they reach the point D, crossing the divergent violet rays at E E. The rest of the intermediate rays of the spectrum (indigo, blue, green, yellow, and orange) are intermediate between these two extremes. The distance C D, limiting the violet and the red, is termed the *longitudinal chromatic aberration of the lens.*

If the image be received upon a screen placed at C, violet will predominate, and will be surrounded by a prismatic fringe in which blue, green, yellow, orange, and red may be distinguished. If, on the other hand, the screen be placed at D, the image will have a



FIG. 19.—Chromatic aberration.

predominantly red tint, and will be surrounded by a series of coloured fringes, in inverted order, formed by the other rays of the spectrum which have met and crossed.

The line E E joins the points of intersection between the red and the violet rays which marks the *mean focus*, or the point where the dispersion of the coloured rays will be least.

The axial ray undergoes neither refraction nor dispersion, and the nearer the rays are to the axial the less dispersion do they undergo. Similarly, when the refraction of the rays is greatest at the periphery of a lens, there the dispersion will be most. Hence the peripheral portions of uncorrected lenses are stopped out, and the centre only often used that the chromatic aberration may be reduced to a minimum.

Manifestly, therefore, the correction or neutralisation of this chromatic aberration, which is known in optics as *achromatism*, is a matter of the first moment. Multiplied colour foci between C and D (fig. 19) make a perfect optical image impossible.

It is a question of interest and importance to the microscopist to know *how achromatism is obtained.*

In a prism the amount of dispersion or unequal bending of R and V (fig. 5) depends on two things: (1) the nature of the glass of which the prism is composed, and (2) the refracting angle B A C.

If, for example, another prism were taken, made of a different kind of glass, possessing only half the dispersive power of that in the figure, but with the angle B A C 50°, as in this case, the separa-

tion of R and V would only be *half as great* as that effected by the prism in the figure.

Then if another prism were made of the *same material* as that assumed in fig. 5, but with only *half the refracting angle*, viz. 25°, the dispersion between R and V would also be but half that represented. Also a prism having 50° of refracting angle gives the same amount of dispersion as that from a prism of 25° of refracting angle, but of twice its dispersive power.

Under these conditions, when one prism, exactly like another in angle and dispersive power, is placed close to it in an inverted position, the dispersion of the first prism is entirely neutralised by that of the second because it is precisely equal in amount and opposite in power. This will be understood by a glance at fig. 20. But it will be seen that not only is dispersion reversed, but refraction also is neutralised, the emergent ray being parallel to the incident ray. Therefore the equal and inverted system of prisms can be of no possible use to the practical optician in the correction of lenses because the *convergence* and *divergence* of rays are both essential to the construction of optical instruments. The dispersion, in fact, must be destroyed without neutralising the refraction.

FIG. 20.—Recomposition of light by prisms. (From the 'Forces of Nature.')

Suppose we take a prism with an angle of 50°, composed of glass having a certain dispersive power, and invert next it a prism of 25° angle, composed of glass having twice the dispersive power of the former. Dispersion will be manifestly destroyed, because it is equal in amount and opposite in nature to that possessed by the prism of 50°; but the prism with an angle of 25° will not neutralise all the refraction effected by the prism of 50°.

These conditions plainly suggest the solution of the problem, for part of the convergence is maintained while the whole of the dispersion is destroyed.

The spherical lenses which answer to these prisms are a crown biconvex, fitting into a flint plano-concave of double the dispersive power.

It has been pointed out above that all the other colours lie in their proper order between the rays R and V (fig. 5). Let us select one, green, and represent it by G. Now if G lies midway between R and V in the prism of 50° of angle, and also between R and V in the prism of 25° of angle, its dispersion will also be neutralised. This means that when the dispersion between the three colours in

e kind of glass is proportional to their dispersion in the other, en when any two are destroyed the third is destroyed with them. is unfortunately is not the case in practice, because two kinds of ass having proportional dispersion powers cannot be obtained. is, however, is what really happens. G may lie midway between and V in one kind of glass, but in the other it may lie, for stance, much nearer R, say a third instead of half the distance E from V. If now the dispersion of R V be destroyed, G will left outstanding. If a different angle of prism be chosen, so that and G are neutralised, then V must be left outstanding.

This want of proportion in the dispersion of the various colours the spectrum in two kinds of glass is termed the *irrationality of e spectrum*, and the colour or colours left outstanding in a corrected mbination of lenses is known as the *secondary spectrum*.

In some subsequent pages we shall have to call attention to the anufacture in Germany of some new vitreous compounds by the mbination of which with fluor spar the secondary spectrum has been moved from microscope objectives, and an *apochromatic* system of nstruction has been introduced.

Meanwhile, we may remember that it has only been in compatively recent times that the construction of achromatic object-asses for microscopes has been brought about, but the gradual largement of aperture and the greater completeness of the corctions soon after the discovery of achromatism rendered sensible **a imperfection in the performance of these lenses under certain rcumstances, which had previously passed unnoticed, and Andrew ss made the important discovery that the use of cover-glass in ounting minute objects introduced aberration, and that a very bvious difference exists in the precision of the image, according as is viewed *with* or *without* a covering of thin glass, an object-lass which may be perfectly adapted to either of these conditions ing sensibly defective under the other.**

He also devised the means of correcting this error, and published is device in vol. li. of 'Transactions of the Society of Arts' for 1837.

Fig. 21 will illustrate the effect produced on the corrections of a object-glass by the interposition of a cover-glass between the bject and the objective.

The rays radiating from the object O in every direction fall upon e cover-glass C C ($\mu = 1{\cdot}6$). On tracing two definite rays, such s O A and O B, it will be found that they will be refracted to R nd P (shown by the dotted lines of the figure). On their emergence nto air they will be again refracted in a direction parallel to their rst path, and will enter the front lens of the objective at the oints M and N.

Now as M R and N P, produced, meet in Y, it follows that, so ar as the objective is concerned, the rays M R, N P might have iverged from the point Y.

Similarly, by tracing two of the less divergent rays from O they rill be made by the refraction of the cover-glass to appear as if hey diverged from X. Therefore, in consequence of the cover-glass, he objective has to deal with rays radiating *apparently from two dis-*

tinct points, X and Y. If there were no cover-glass all the rays would diverge from O, and then the objective would require to be perfectly *aplanatic*. This word (derived from ἀ = privative, and πλανάω, to wander, i.e. free from wandering or error) means, as used by opticians,



FIG. 21.—The effect produced by a cover-glass on the corrections of an object-glass.

that all the rays passing through a lens system are brought to an identical conjugate focus, as shown in fig. 22. But as affected by the cover-glass the marginal rays diverge, apparently, from a focus *nearer the objective* than the central rays ; therefore the objective, to meet this condition, must be what is called *under-corrected* ; a condition presented in fig. 23, so as to focus both these points at once. Here the



FIG. 22.—Aplanatic system.



FIG. 23.—Under-corrected system.

curvature of the surface of the crown lens being increased, the flint plano-concave is not sufficiently powerful to neutralise all the spherical aberration of the crown. As a consequence the peripheral rays are brought to a focus at F', while the central rays pass on to F. This is what is meant by 'under-correction' in an object-glass.



FIG. 24.—Over-corrected system.

In fig. 24 the reverse condition is presented, for the incident curve of the crown lens has been flattened, while that of the flint has been deepened, which increases the corrective power of the flint, and thus destroys the balance of the combination in other directions. The rays passing through the periphery of the combination will be brought to a focus F', while the central rays will be focussed at F. This is what is known as *over-correction*.

An *aplanatic objective* (fig. 22) can be made into an *under-corrected* objective (fig. 23) by either (1) *causing the back lenses of which it is composed to approach the front lens.* This is the device of Andrew Ross, and is now effected [1] by means of a special 'collar' arrangement, which, by the action of a screw, approximates or separates the suitable lenses. But for this a special device is needed for each objective. (2) The result can moreover be secured *by causing the eye-piece to approach the objective.* This of course is accomplished by the use of the draw-tube, and must be employed with objectives having rigid mounts.

Closing lenses, that is, bringing them together, whether in the objective itself or in the microscope as a whole, by shortening the distance between the eye-piece and the objective *under-corrects the objective*, that is, gives positive aberration; while the *separation of lenses over-corrects* or gives negative aberration.

In using the *collar correction* [1] for a longer body or a thicker cover-glass the collar adjustment must be moved so as to cause the back lenses of the objective to *approach the front lens*, while for a shorter body or a thinner cover-glass, the adjustment must be moved so as to cause their separation.

In *correcting by tube length* for a thicker cover shorten the tube, and for a thinner one lengthen it.

For the benefit of those who aim at work with lenses, that is, such as may be compassed with the aid of the most elementary mathematics, it may be well to indicate a simple method for the deduction of the *foci of plano-convex and biconvex lenses.*

In fig. 17 the focus is twice the radius measured from the vertex A, that is, A F. But in fig. 18 it is twice the radius measured from the point A, that is, the point F is distant from the lens twice the radius less two-thirds the thickness of the lens.

Similarly, in fig. 25, *the radius of a biconvex lens* is measured from the point A; in other words, F is distant from the lens the length of the radius less one-fourth the thickness of that lens (nearly).



FIG. 25.—The radius of a convex lens.

Formulæ relating to a biconvex lens.—Where P is one focus, P′ its conjugate, F principal focus (solar focus, or that for a very distant object), R radius of curvature for one surface, R′ for the other surface, μ the refractive index of the medium, then

$$\frac{1}{P}+\frac{1}{P'}=(\mu-1)\left(\frac{1}{R}+\frac{1}{R'}\right);$$

$$\frac{1}{F}=(\mu-1)\left(\frac{1}{R}+\frac{1}{R'}\right);$$

$$\frac{1}{P}+\frac{1}{P'}=\frac{1}{F}.$$

Also, if A is the distance of a focus from F, the principal focus,

[1] See Chapter V.

and B, the distance of its conjugate from F', the other principal focus on the other side, then

$$A B = F F' ;$$

or, in an equiconvex lens,

$$A B = F^2.$$

In an equiconvex lens of crown glass $\mu = 1{\cdot}5$ if F = radius of curvature. But in a plano-convex lens of crown glass $\mu = 1{\cdot}5$ if F = twice the radius of curvature.

In the above formula the thickness of the lens has been neglected. In thick lenses, however, its effect must not be disregarded, even if only approximate results are required. A very approximate determination of the principal focal length of an equiconvex lens may be made by subtracting from the result obtained by the foregoing formulæ one quarter of the thickness of the lens.

Example.—Equiconvex lens of crown glass $\mu = 1{\cdot}5$, $r = \frac{1}{2}$, thickness $= \frac{1}{4}$. By above formula $F = \frac{1}{2}$. Subtracting from this one-quarter of the thickness of the lens we get $F = \frac{7}{16}$ as the distance between the focus and the surface of the lens. This is only $\frac{1}{80}$ inch from the truth. If the lens were a sphere it would be accurate.

In the case of a plano-convex lens the principal focus on the convex side is equal to twice the radius as above, but on the plane side two-thirds of the thickness of the lens must be subtracted from it.

Example.—In a hemispherical lens of crown glass $\mu = 1{\cdot}5$, radius $= \frac{1}{2}$, thickness $= \frac{1}{2}$, the principal focus on the convex side will be one inch from the curved surface and on the plane side $\frac{2}{3}$ inch from the plane surface.

Similarly, in an equiconcave lens subtract from the principal focal length, obtained by the above formula, half the thickness of the lens. In other words, measure the focal length from the centre of the lens. The focus is of course virtual.

But a plano-concave lens follows the plano-convex. The principal focus on the curved side requires no alteration, but from that on the plane side two-thirds of the thickness of the lens must be subtracted. The focus is also virtual.

Example.—Equiconcave of dense flint $\mu = 1{\cdot}75$, radius $= -\frac{1}{2}$, thickness $\frac{1}{4}$, F by formula $= -\frac{1}{3}$. This is about $\frac{1}{10}$ inch too much, but by subtracting half the thickness of the lens, or $\frac{1}{8}$, we obtain $-\frac{5}{24}$, which is only $\frac{1}{35}$ inch too little.

Plano-concave of dense flint $\mu = 1{\cdot}75$, radius $= -\frac{1}{2}$, thickness $\frac{1}{4}$, F by formula $= -\frac{2}{3}$. Subtract from this two-thirds of thickness of lens. Then $F = -\frac{1}{2}$. This is only $\frac{1}{42}$ inch too small.

The *principal focus of a combination of two or more lenses*, whose principal foci and distances are known, can be found from the formula $\frac{1}{p} + \frac{1}{p'} = \frac{1}{f}$ by assigning for the value of p the distance of the principal focus of the first lens from the second, and so on.

Example.—Parallel rays fall on a equiconvex lens of four inches focus. Two inches from this lens is another equiconvex lens of three inches focus. Find the distance of the focal point from this

last lens, to which the rays will be brought. It is evident that the rays would be brought by the first lens to a focus two inches behind the second if it were not there. This point, which is negative with regard to the second lens, must be taken as the value of p in the formula. We have, therefore:

$$-\frac{1}{2}+\frac{1}{p'}=\frac{1}{3};$$
$$p'=\frac{6}{5}.$$

Hitherto our attention has been confined, in studying the action of lenses, to the manner in which they act upon a bundle of parallel rays, or upon a pencil of rays issuing from a radiant point. Moreover, we have considered this point as situated in the line of axis But the surface of every luminous body may be regarded as comprehending an infinite number of such points, from every one of which a pencil of rays proceeds, to be refracted in its passage through the lens according to the laws enunciated. In this way a complete *image*, i.e. picture of the object, will be formed upon a suitable surface placed in the position of the focus.

There are two kinds of image formed by lenses, a *real* image and a *virtual* image.

1. *The formation of a real image* means the production of a picture by a lens, or a combination of lenses, which can be thrown upon a screen; such are the images of a projection lantern and the image produced by the camera upon the focussing glass. The manner in which this takes place will be understood by reference to fig. 26, where A B is an object placed *beyond* P, the principal focus of the aplanatic combination. From every point of A B are rays radiating at every possible angle. Let A F and A H be two such rays



FIG. 26.—The formation of a real image.

radiating from the point A. Now if the refraction of these rays be traced, in the manner already indicated, through the aplanatic combination, it will be found that the rays which before immergence were diverging are by the refraction of the combination on emergence rendered converging. Thus the ray F C meets H C at the point C. The point C is called the conjugate focal point of A, and wherever there is a focal point there will be an image. Therefore, at C, there will be an image of A. In the same manner the rays

issuing from every point along A B may be traced, and will be found to have each one its respective conjugate lying on C D, so the conjugate of B is at D. Hence it is at once manifest that an *inverted* conjugate image of the object A B is formed at C D. Further, it will be noticed that, although the object is straight, the image of it is curved towards the lens.

If the object A B had been curved, so that it presented a convex aspect to the lens, then its conjugate image C D would have been more curved ; but if A B had been slightly concave towards the lens, then its conjugate would have been straight.

As before stated, the point C has been determined by tracing the refraction of two rays,[1] A F and A H, through the lens. Another method is, however, often employed.

In every lens there is a point which is called its optical centre. This point is such that any ray, which in its refraction through the lens passes through this point, will emerge in a direction parallel to its path before immergence. Now as lenses for graphic and theoretical purposes are often assumed to be of insensible thickness, it has become the practice to draw any ray passing through the optical centre of the lens a straight line. Obviously, if the lens has sensible thickness the ray cannot be considered a straight line, and in the microscope, where the lenses are very thick in proportion to the length of their foci, this method will lead to much error. Of course, in those cases where it can be taken as a straight line, it saves the trouble of computing a second ray to intersect the first, as any ray intersecting the straight line will determine a conjugate focal point.

In the upper part of fig. 26 the two rays, A F and A H, are traced through the lens to determine the point C, but in the lower part of the figure only the ray B K is traced, and the intersection of this ray by the straight line B D passing through the optical centre gives the point D.

2. An image is said to be *virtual* when it cannot be received on a screen. Fig. 27 shows how a virtual image is formed. The letters are the same as in the preceding figure, so as to show the analogy between the two. The fundamental difference between this figure and the last is that the object A B is placed *between* P, the principal focus, and the lens.

We have already seen from fig. 15 that when a radiant is placed before a converging lens, and nearer to it than its principal focus, the rays emerging from the lens are still divergent even after their refraction through the lens ; consequently they will never intersect, and as there is no focal point, there can be no screen image. Thus two rays radiating from the point A of the object A B fall on the lens and are refracted in the directions A F, A H : these are divergent and will never meet ; but if the human eye is placed near the lens, so that it can receive the rays F and H, the rays will be converged by the lens of the eye, and will be brought to a focal point in the retina.

[1] In the majority of the preceding diagrams the drawing has represented the facts accurately ; in this instance they are diagrammatic, the size of admissible illustrations making an accurately traced ray impossible.

Similarly, from every point in A B there will be a corresponding retinal point. Now if we produce F and H backwards (see the dotted lines in the figure) we shall find that they intersect at the point C. As the rays F and H are precisely identical with rays which would have diverged from the point C had it been an entity, the retinal image therefore will be an image of a non-existent picture C D.

The method of drawing this is exactly similar to that of the preceding figure. The rays A F and A H are traced through the lens, and their prolongation backwards (see the dotted lines in the figure) gives the point C. Also, as in the preceding figure, any point of the picture can be found by tracing one ray, such as K; then the intersection of its backward prolongation with a straight line joining B with the optical centre, produced, will give D.

The points C and D are called the *virtual conjugate foci* of A



FIG. 27.—The formation of a 'virtual image.'

and B respectively. In mathematical optics it appears as a negative quantity which satisfies an equation, and is a sort of metaphysico-mathematical truth. In this case the virtual image is convex towards the lens.

Fig. 27 illustrates the action of a simple microscope. The object itself is not seen, but the picture presented to the eye is an enlarged ghost of it. As some eyes can take in rays of less divergence than others, it might happen that the rays C F, C H, were too divergent for the observer's eyesight, in which case the lens would have to be withdrawn from the object. Similarly, if the observer were short-sighted, the lens must be placed nearer the object to render the rays more divergent. Dr. Abbe points out[1] that the generally adopted notion of a 'linear amplification at a certain distance' is, in fact, a very awkward and irrational way of defining the 'amplifying power' of a lens or a lens-system.

[1] *Journ. R.M.S.* vol. iv. ser. ii. p. 348.

In the formula $N = \frac{l}{f}$ the amplification of one and the same system varies with the length of l, or the 'distance of vision,' and an arbitrary conventional value of l (i.e. 10 inches, or 250 mm.) must be introduced in order to obtain comparable figures. The actual 'linear amplification' of a system is, of course, different in the case of a short-shorted eye, which projects the image at a distance of 100 mm., and a long-sighted one, which projects it at 1000 mm. Nevertheless, the '*amplifying power*' *of every system is always the same for both, because the short-sighted and the long-sighted observers obtain the image of the same object under the same visual angle*, and consequently *the same real diameter of the retinal image*. That this is so will be seen from fig. 28, where the thick lines show



FIG. 28.—The amplifying power of a lens.

the course of the rays for a short-sighted eye, and the thin lines for a long-sighted one, the eye in each case being supposed at the posterior principal focus of the system.

The other generally adopted expression of the power by $N = \frac{l}{f}$ may be put on a somewhat more rational basis than is generally done by defining the length l (10 inches) not as 'distance of distinct vision,' but rather as 'distance of projection of the image.' As far as 'distinct vision' is assumed for determining the amplification, the value of N has no real signification at all in regard to an observer who obtains distinct vision at 50 inches instead of 10 inches, and, in fact, many microscopists declare the ordinary figures of amplification to be useless for them because they cannot observe the image at the supposed distance. It appears as if—and many have this opinion—the performance of the microscope in regard to magnification depended essentially on the accommodation of the observer's eye. This misleading idea, resulting from the common expression, is

eliminated by defining the 10 inches merely as the distance from the eye at which the image is measured—whether it be a distinct or an indistinct image. For if an observer, owing to the accommodation of his eye, obtains a distinct image at a distance of 10 feet, I may nevertheless assume a plane at a distance of 10 inches from the eye on which the distant image is virtually projected, and measure the diameter of that projection. Now this diameter is strictly the same as the diameter of that image, which another observer would really obtain with distinct vision at that same distance of 10 inches.

The only difference is that in the former case we must take the centres of the circles of indistinctness instead of the sharp image-points in the latter case. If the conventional length of $l = 10$ inches is interpreted in this way (as distance of projection, independently of distinct vision) the absurdity at least of a real influence of the accommodation on the power of a microscope is avoided. It becomes obvious that for long-sighted and for short-sighted eyes the same N must indicate the same visual angle of the enlarged objects, or the same magnitude of the retinal image, because it indicates the same diameter of the projection at 10 inches distance.

It was long since pointed out by Amici, that the introduction of a drop of water between the front surface of the objective, and either the object itself or its covering glass, would diminish the loss of light resulting from the passage of the rays from the object or its covering glass into air, and then from air into the object-glass. But it is obvious that when the rays enter the object-glass from water instead of from air, both its refractive and its dispersive action will be greatly changed, so as to need an important constructive modification to suit the new condition. This modification seems never to have been successfully effected by Amici himself; and his idea remained unfruitful until it was taken up by Hartnack and Nachet, who showed that the application of what is now known as the *immersion system* to objectives of high power and large aperture is attended with many advantages not otherwise attainable. For, as already pointed out, the loss of light increases with the obliquity of the incident rays; so that when objectives of very wide aperture are used 'dry,' the advantages of its increase are in great degree nullified by the reflection of a large proportion of the rays falling very obliquely upon the peripheral portion of the front lens. When, on the other hand, rays of the same obliquity enter the peripheral portion of the lens from water, the loss by reflection is greatly reduced, and the benefit derivable from the large aperture is proportionally augmented. Again, the 'immersion system' allows of a greater working distance between the objective and the object than is otherwise attainable with the same extent of aperture; and this is a great advantage in manipulation. Further, the observer is rendered less dependent upon the exactness in the correction for the thickness of the covering glass, which is needed where objectives of large aperture are used 'dry'; for as the amount of 'negative aberration' is far smaller when the rays which emerge from the covering glass pass into water than when they pass into air, variations in its thickness produce a much less disturbing effect. And it

is found practically that 'immersion' objectives can be constructed with magnifying powers sufficiently high, and apertures sufficiently large, for the majority of the ordinary purposes of scientific investigation, without any necessity for cover-adjustment; being originally adapted to give the best results with a covering glass of suitable thinness, and small departures from this in either direction occasioning comparatively little deterioration in their performance. But beyond all these reasons for the superiority of the 'immersion system' is, as will be presently seen, the fact that it admits into the lens a larger number of '*diffraction spectra*' than can be possibly admitted by a lens working in air; and upon this depends the perfect presentation of the image.

The immersion system has still more recently been advanced upon by the application of a principle which lies at the root of the optical interpretation of the images which modern lenses present, and which has greatly increased the value of the microscope as a scientific instrument. It is an improvement that primarily depends upon a correct theoretical understanding of the principles of the construction of microscopical lenses, and the interpretation of the manner in which the image is realised by the observer. The late Mr. Tolles was the first to adopt this system, as we point out subsequently; but it was to Professor Abbe we are indebted for its practical application, through whom it is now known as the *homogeneous system*. 'The idea of realising the various advantages of such' a system by constructing a certain class of homogeneous objectives had, Professor Abbe says,[1] 'for some time presented itself to his mind.' 'The matter assumed, however, subsequently, a different shape in consequence of a suggestion made by Mr. John Ware Stephenson, . . . of London, who independently discovered the principle of homogeneous immersion.'[2]

This method consists of the replacement of water between the covering glass of the mounted object and the front surface of the object-glass by a liquid having the same refractive and dispersive power as crown glass. With such a fluid taking the place of air, it follows that the correction collar, though still a refinement and aid in the attainment of the finest critical images, would be a necessity no more.

The desirability of the construction of a combination of lenses which would satisfy these conditions was urged by Mr. Stephenson upon Professor Abbe, and he secured the profound knowledge, which, as a mathematical optician he possessed, for the complete and practical solution of the problems involved, and the production of a remarkable series of lenses, marking a distinct epoch in the progress of theoretical and practical optics.

He had, in fact, as we have hinted, already approached the consideration of the subject from another point of view, believing that petrographic work—the study of thin sections of mineral substances—could be far more efficiently accomplished by the use of homo-

[1] On 'Stephenson's System of Homogeneous Immersion for Microscopic Objectives' (Abbe), *Journ. R.M.S.* vol. ii. 1879, p. 257.

[2] *Ibid.*

geneous lenses. But in the new aspect in which the problem was presented by Mr. Stephenson it carried with it new interest to Abbe, not only as promising to largely dispense with the 'correction collar,' but also to greatly enlarge the 'numerical aperture,' and therefore secure a greater resolving power in the objective.

One of the difficulties was to find a suitable fluid to meet the necessities as to refraction and dispersion. But after a long series of experiments Professor Abbe found that oil of cedar wood so nearly corresponds with crown glass in these respects that it served the purpose well.

The result of Abbe's calculations based on Mr. Stephenson's suggestion was the construction by Carl Zeiss of a $\frac{1}{12}$th with a N.A.[1] of 1·25 of fine quality, and still higher promise, and subsequently of a $\frac{1}{8}$th and a $\frac{1}{16}$th in. objective of a like character.

It may be well to note that Amici suggested the use of oil instead of water prior to 1850, and Mr. Wenham again revived the suggestion in 1870.[2] But neither of these is in even a remote sense an anticipation of the 'homogeneous system' of lenses as we now understand it. The 'oil immersion' in both instances was an expedient. The principle on which the construction carried out by Professor Abbe depended was the 'optical' principle that a medium of high refractive power gives an aperture greatly in excess of the maximum (180°) of a dry lens; while Abbe's explanation, propounded in 1874, of the important bearing which the *diffraction pencils* have on the formation of the microscopic image makes the resolving power of the object-glass dependent upon the diffraction pencils that are taken up by it.

All this was unknown or unadmitted by those who had previously suggested oil as an *immersion* medium, which leaves the homogeneous system as now employed wholly dependent upon the principles enunciated by Abbe, arising from the practical suggestion of Stephenson and resulting in the beautiful object-glasses of Abbe and Zeiss.

One of the essential advantages of this system, beyond those stated, is that by the suppression of spherical aberration in front of the objective, facilities are afforded for correcting objectives of great numerical aperture, both in theory and practice, that reduce it to the level of the problem of correcting objectives of moderate 'angle.' As a result, stimulated by the manifest advantage to be obtained and the wants of those engaged in actual research, Messrs. Powell & Lealand, of London, very soon made a $\frac{1}{25}$th inch and a $\frac{1}{30}$th inch objective on the homogeneous principle, with numerical apertures respectively of 1·38, and during the year 1885 produced lenses of an excellence impossible to any previous system of $\frac{1}{4}$th inch, $\frac{1}{12}$th inch, and $\frac{1}{50}$th inch power, having respectively numerical apertures of 1·50, while 1·52 is the theoretical maximum.

The use of a 'correction collar' is continued in the best English and German homogeneous object-glasses, especially as aiding in the delicate corrections required to get the exact length-relation between

[1] The meaning of this expression will be found on p. 49 but the whole of Chapter II. must be carefully read.

[2] *Monthly Micro. Journ.* vol. iii. p. 303.

the object-glass and eye-piece. But this must also be aided in endeavouring to secure the most perfect 'critical images' by a body-tube provided with rack and pinion motion. When the two are combined, if the object-glass is of perfect construction and of latest form (apochromatic, *q.v.*), results never before attainable can be got with comparative ease. And this, be it observed, does not in the least compromise our admission of the perfect accuracy of the theoretical principle of the homogeneous system.

With such evidence of advance in the optical construction of microscopes, dependent apparently on such accessible conditions, the question of what is possible in the future of the instrument no doubt obtrudes itself; that, however, can only be considered as having application to the area of our present knowledge and resources. It is impossible to forecast the future agencies which may be at the disposal of the practical optician. To photograph stars in the immeasurable amplitudes of space, absolutely invisible to the human eye, however aided, was hardly within the purview of the astronomers of a quarter of a century ago; that there may be energies and methods discoverable by man that will open up possibilities to the eager student of the minute in nature which will just as widely overstep our present methods of optical demonstration, there can be little reason to question. But it is no doubt true that with the instruments and media now at the disposal of the practical optician no indefinite and startling advance in microscopic optics is to be looked for. The 'atom' is infinitely inaccessible with any conceivable application of all the resources within our reach. But optical improvement of great value, bringing nature more and more nearly and accurately within our ken and reducing more and more certainly the interpretation of the most difficult textures and constructions in the minutest accessible tissue to an *exact method*, is certainly within our sight and reach. It is not a small matter that the homogeneous lenses were, in a comparatively short period of time, carried from a N.A. of 1·25 to 1·50; and this carried with it the capacity theoretically indicated.

High refractive media can greatly reduce the *value* of even the wave-length of light, and what is possible in the production of vitreous combinations, refractive fluid media, and mounting substances we may not forecast; but, judging from the past, we have by no means reached their limit. At the same time, it may be remembered that photo-micrography, by constantly covering a wider area of application with its ever increasingly delicate and subtle methods, is more penetrating in the revelation of structure than the human eye.

It may be taken for granted that in the present state of optical mathematics the opticians, English, Continental, and American, have given up the quest of many things fruitlessly sought. Empty amplification is a folly of lenses of the past. Magnification without concurrent disclosure of detail is of no more scientific value for the disclosure of structure than the projection of the photo-micrograph by an electric arc upon a screen would be. What is needed is an ever-increasing exactitude in the formation of the dioptrical image. The imperfection of this at the focal point springs from two causes:

one, as we have just demonstrated, arises from the *residual spherical and chromatic aberrations*, the other takes origin in the *want of homogeneity, absolute precision of curve*, and *perfect centering of the system of lenses* in a combination. This causes the cone of rays proceeding from the object to unite, not in perfect image points, but in 'light surfaces of greater or less extent—circles of dissipation'—which limits the distinctness of minute details. It is the faults of the objective that in practice are alone important, and with the crown and flint glass commonly at the disposal of the optician there are two great drawbacks to perfection, or rather to an approximation to it.

1. The first arises from the unequal course of the *dispersion* in crown and flint glass, already described, which makes it impossible to unite perfectly, with the properties they possess, *all the coloured rays in an image*. Absolute achromatism cannot by their means be attained, the dispersion at different parts of the spectrum being so greatly disproportional. It has never been possible to unite more than two different colours of the spectrum. The rest, in spite of all effort, deviate and form the *secondary spectrum*, leaving, in the very finest lenses, circles of dispersion not to be excluded.

2. The second defect arises in the impossibility of correcting by means of ordinary crown and flint glass the *spherical aberration* for more than *one* colour. If the spherical aberration be removed as far as may be for the centre of the spectrum, there remains under-correction for the red, and over-correction for the blue and violet rays, presenting a want of balance between the *chromatic* corrections for the central and marginal zones of the objective. Although perfect chromatic corrections for the central rays may be effected, giving images of great beauty, the chromatic over-correction for the peripheral rays with oblique illumination will show the borders of the image with distinct chromatic fringes.

To compensate these aberrations in the construction of an object-glass, what is needed is a vitreous material applicable to optical purposes possessed of such properties that a relatively smaller refractive index could be united with a higher dispersive power, or a higher refractive index with a relatively lower dispersive power. By proper combination of such materials if they be provided with ordinary crown and flint glass, to partly remove the chromatic and spherical aberrations independently of each other, and so to obey the conditions on which the removal of the chromatic difference depends, these aberrations could be compensated.

All this was seen and fully demonstrated and set forth by Abbe as far back as 1876,[1] and he pointed out that the further perfecting of the microscope in its dioptrical working was dependent on the art of glass making; the production, that is to say, of vitreous compounds possessing different relations of refractive and dispersive power by means of which the secondary spectrum could be removed.

For practical purposes the matter was in abeyance until 1881, but since that time Dr. Schott and Professor Abbe, with the active

[1] Hoffman, A. W., *Bericht über die wissenschaftlichen Apparate auf der Londoner Internationalen Ausstellung im Jahre* 1876.

co-operation of the optical workshops of Zeiss, have undertaken laborious and prolonged investigation into the improvement optical glass, to which we have alluded ; the result has been the p duction of 'crown' and 'flint' glass possessing exactly the quali foreshown as indispensable by Abbe.

By chemical, physical, and optical research of a most labori nature, and by spectrometric observations of numerous experimer fusions systematically carried out with a large variety of chemi elements, the relation between the vitreous products and th chemical composition has been more closely investigated.

In the crown and flint glass produced up to the time of th investigations, the uniformity of property arose from the relativ small number of materials employed. Aluminium and thallii with silica, alkali, lime, and lead, formed the limit. By the use more chemical elements, especially phosphoric and boric acid as essential constituents of glass fluxes in the place of silica alone, fl and crown glass have been produced in which the *dispersion in different parts of the spectrum is nearly proportional* ; so that achromatic combinations it is now a question of detail and practi optics to eliminate almost entirely the secondary spectrum. On other hand, the kinds of glass which can be used for optical purpo have been so increased in variety that, while the mean index of fraction is constant, considerable variations can be given to dispersion or to the refractive index while the dispersion rema constant. A high index of refraction is no longer of necessity companied by a high dispersion in flint glass, but may be retai in crown glass with a low degree of dispersion.

The practical consequence of this is that both the imperfecti inalienable from an objective constructed of ordinary crown a flint glass *can be, and have been, eliminated,* and the second spectrum annulled ; it is removed and reduced to a residue chromatism of a tertiary character, while the chromatic differe of spherical aberration can be eliminated or completely correc for *two different colours* of the spectrum at once, and theref practically for all.

In the lenses formed of the crown and flint glass as used pr to the new German glass, we were provided with what (in co parison with non-achromatised lenses) were called 'achromati but in the new system of lenses, which may be 'dry' or 'homogeneo we have so great a freedom from colour defect as to admit of th being designated *apochromatic lenses* (*ἀ* = privative ; *χρῶμα* = colo *ἀπὸ* = from, away from ; *χρῶμα* = colour).

The practical advantages obtained by this system of object-gl construction are so great as in delicate researches to be invaluabl provided always that the work in all its details is of the most perf kind. The accidental juxtaposition of lenses of the required curv and, relatively, even the careful selection of lenses not homogeneou related to each other by a unity of purpose and work on the part the practical optician, cannot yield perfect results. 'Division labour' is not compatible with perfect results in the making a building up of an apochromatic lens ; and therefore, in their b

form, these objectives must apparently command a high price. But, given such an object-glass—which is the production of a thoroughly competent practical optician—and its advantages, theoretical and practical, are great.

1. *The aperture of the objective can be utilised to its full extent.* In the best of the older object-glasses at least one-tenth of the available aperture was useless; the inalienable defect in the convergence of the rays prevented a proper combined action of the outermost zone and the central parts of the aperture, and therefore by those objectives it has never been possible to *realise* the amount [1] of resolving power indicated by theory with a given aperture. But in a well-constructed apochromatic objective—the secondary spectrum being removed, and the spherical aberration being *uniformly* corrected for different parts of the spectrum—there is a practically perfect focal concentration of the rays in the image.

2. *Increase of magnifying power by means of specially constructed eye-pieces* is also a most important feature of objectives of this class. The result of this is that great magnifying power can be obtained by objectives of relatively large focal lengths. We have always maintained the utility of high eye-piecing under proper conditions, and with suitable apertures and fine corrections in the objective; the physical brightness, we learn from Abbe, in every case depends only upon the aperture and the total magnifying power; and it is of no moment in what way the latter is produced—by means of focal length of the objective, length of tube, and focal length of eye-piece. But he has further shown us [2] that with the best objectives of the old construction, and with large apertures, the *limits* of a completely satisfactory clearness of image are reached when the *super*-amplification is four- to six-fold; that is, when the total magnifying power of the objective and eye-piece together is four to six times as great as that obtained with the objective when used by itself as a magnifying lens. On the other hand, with apochromatic objectives the available super-amplification—even with the greatest apertures—is at least twelve- to fifteen-fold, and considerably higher with medium and low objectives.

3. *Achromatism touches almost an ideal point in these objectives.* The images are practically free from colour over the entire area. This is of great value in photo-micrography. The correction errors of the ordinary achromatic systems are much more powerful as disturbing influences than in ordinary observation with the eye.

4. In spite of the removal of the secondary spectrum certain colour deviations of a tertiary nature remained, and are inevitable in all objectives of great aperture in which the front lens cannot be made achromatic by itself. With ordinary achromatic objectives, from the properties of the glass used, the amount of this is very unequal in the central and peripheral parts, but in the apochromatic object-glass it is approximately *constant for all parts of the opening*,

[1] Excepting when resolution is effected by light of extreme obliquity. If the outermost zone of the objective is corrected alone, and that only be employed, at that limit equally good resolution may be accomplished.

[2] 'On the Relation of Aperture to Power,' *Journ. R.M.S.* 1883, p. 803.

and *therefore it allows of correction by the eye-piece*, a special construction possessing *equal* but *opposite* differences of magnifying power for different colours. The eye-piece is so constructed as to completely secure the desired result, and, as we have stated above, images free from colour are obtained.

5. *The classification of the eye-pieces* for this system of objectives has been established by Abbe, and depends on the increase in the total magnifying power of the microscope obtained by means of the eye-piece as compared with that given by the objective alone. The number which denotes how many times an eye-piece increases the magnifying power of the objective, when used with a given body-tube, gives the proper measure of the eye-piece magnification, and at the same time the figures for rational numeration.[1]

From their properties these are known as 'compensating eye-pieces.'

The following is a fair typical selection of the objectives and eye-pieces furnished from the workshops of Carl Zeiss, of Jena, on this important system, viz. :

Apochromatic Objectives.

	Aperture	Focal Length	English Equivalent
Dry	0·30	24·0 mm.	1 inch.
	0·30	16·0 „	$\frac{2}{3}$ „
	0·65	12·0 „	$\frac{1}{2}$ „
	0·65	8·0 „	$\frac{1}{3}$ „
	0·95	6·0 „	$\frac{1}{4}$ „
	0·95	4·0 „	$\frac{1}{6}$ „
Water Immersion	1·25	2·5 „	$\frac{1}{10}$ „
Homogeneous Immersion	1·40	3·0 „	$\frac{1}{8}$ „
	1·40	2·0 „	$\frac{1}{12}$ „

Compensating Eye-pieces for English Bodies

2 4 8 12 18 27

It is of interest to note that Messrs. Powell and Lealand, on receiving the special glass from Germany proceeded immediately to the production of a $\frac{1}{12}$-inch objective with compensating eye-piece on a formula devised by Mr. T. Powell, which were supposed to be apochromatic. The workmanship was of the high class for which, in the manufacture of lenses, that firm have become distinguished; and this objective has, together with those subsequently produced, brought out admirably the quality of the work; for we now know that the perfect apochromatic objective requires fluorite lenses in its combinations to obtain the needful corrections. But without the use of these this firm came so near the earlier apochromatic objectives of Zeiss, for visual purposes, that it was not easy to discover their deficiency. This was due entirely to perfect workmanship. The same firm have since produced a remarkable lens on the same system, having a N.A. of 1·50, with a power of $\frac{1}{10}$th of an inch. Object-glasses are also now made by other makers, English, Euro-

[1] 'On Improvements of the Microscope with the aid of new kinds of optical glass' (Abbe), *Journ. R.M.S.* 1887, p. 25 *et seq.*

pean, and American, known as 'apochromatic'; but we doubt, in the majority of cases, if the apochromatism is attained, for it has only recently been made known that, in addition to the special glass used in their construction, the Abbe apochromatic sys[illegible] serted also the *fluorite lenses* referred to above, whic[illegible] affects the result. It is remarkable, however, how near [illegible] have brought their results to those of Abbe without th[illegible] of the fluorite lens. With this material employed i[illegible] struction Messrs. Powell and Lealand are making beau[illegible] glasses. We have recently used a new $\frac{1}{4}$-in. made by them, we have seen no successful rival.

CHAPTER II

THE PRINCIPLES AND THEORY OF VISION WITH THE COMPOUND MICROSCOPE

We are now prepared to enter upon the application of the optical principles which have been explained and illustrated in the foregoing pages to *the construction of microscopes*. These are distinguished as *simple* and *compound*, each kind having its peculiar advantages to the student of nature. Their essential difference consists in this that in the former, the rays of light which enter the eye of the observer proceed directly from the *object* itself, after having been subjected only to a change in their course, as we have shown by fig. 26, which fully explains the action of the simple lens; whilst in the compound microscope an enlarged *image* of the object is formed by one lens, which image is magnified to the observer by another, as if he were viewing the object itself. In the *compound* microscope not less than two lenses *must* be employed: one to form the enlarged image of the object, immediately over which it is placed, and hence called the *object-glass*; whilst the other again magnifies that image, and, being interposed between it and the eye of the observer, is called the *eye-glass*. A perfect object-glass, as we have seen, must consist of a combination of lenses, and the eye-glass is best combined with another lens interposed between itself and the object-glass, the two together forming what is termed an *eye-piece*. The compound microscope must be the subject of careful and detailed consideration; but it must be remembered that the shorter the focus of the simple magnifying lens, the smaller must be the diameter of the sphere of which it forms part; and, unless its aperture be proportionately reduced, the distinctness of the image will be destroyed by the spherical and chromatic aberrations necessarily resulting from its high curvature. Yet notwithstanding the loss of light and other drawbacks attendant on the use of single lenses of high power, they proved of great value to the older microscopists (among whom Leeuwenhoek should be specially named), on account of their freedom from the errors to which the compound microscope of the old construction was necessarily subject; and the amount of excellent work done by means of them surprises everyone who studies the history of microscopic inquiry. An important improvement on the single lens was introduced by Dr. Wollaston, who devised the *doublet*, still known by his name, which consists of two plano-convex lenses, whose focal lengths are in the proportion of one to three or nearly so, having their convex sides directed towards

ıe eye, and the lens of shortest focal length nearest the object. In r. Wollaston's original combination no perforated diaphragm (or top') was interposed, and the distance between the lenses was left be determined by experiment in each case. A great improvement ıs subsequently made, however, by the introduction of a 'stop' tween the lenses, and by the division of the power of the smaller ıs between two (especially when a very short focus is required), so to form a *triplet*, as first suggested by Mr. Holland.[1] When mbinations of this kind are well constructed, both the spherical d the chromatic aberrations are so much reduced that the angle aperture may be considerably enlarged without much sacrifice of tinctness; and hence for all, save very low powers, such 'doublets' d 'triplets' are far superior to single lenses. These combinations ık the place of single lenses among microscopists (in this country least), who were prosecuting minute investigations in anatomy d physiology prior to the vast improvements effected in the com- ınd microscope by the achromatisation of its object-glasses.

Another form of simple magnifier, possessing certain advantages ır the ordinary double-convex lens, is that commonly known by ı name of the 'Coddington' lens.[2] The first idea of it was given Dr. Wollaston, who proposed to apply two plano-convex or hemi- erical lenses by their plane side, with a 'stop' interposed, the tral aperture of which should be equal to one-fifth of the focal gth. The great advantage of such a lens is, that the oblique ıcils pass, like the central ones, at right angles to the surface, so t they are but little subject to aberration. The idea was further ıroved upon by Sir D. Brewster, who pointed out that the same l would be much better answered by taking a sphere of glass, and ıding a deep groove in its equatorial part, which should be then ıd with opaque matter, so as to limit the central aperture. Such ıns gives a large field of view, admits a considerable amount of ıt, and is equally good in all directions; but its power of definition y no means equal to that of an achromatic lens, or even of a blet. This form is chiefly useful, therefore, as a hand-magnifier, vhich neither high power nor perfect definition is required, its ıliar qualities rendering it superior to an ordinary lens for the s of objects for which a hand-magnifier of medium power is ıired. Many of the magnifiers sold as 'Coddington' lenses, ever, are not really portions of spheres, but are manufactured of ordinary double-convex lenses, and are therefore destitute of special advantages of the real 'Coddington.' The 'Stanhope' somewhat resembles the preceding in appearance, but differs ı it essentially in properties. It is nothing more than a double- vex lens, having two surfaces of unequal curvatures, separated ı each other by a considerable thickness of glass, the distance he two surfaces from each other being so adjusted that when the t convex is turned towards the eye minute objects placed *on* the

[1] *Transactions of the Society of Arts*, vol. xlix.

[2] This name, however, is most inappropriate, since Mr. Coddington neither was, ver claimed to be, the inventor of the mode of construction by which this lens stinguished.

other surface shall be in the focus of the lens. This is an easy mode of applying a rather high magnifying power to scales of butterflies' wings, and other similar flat and minute objects, which will readily adhere to the surface of the glass; and it also serves to detect the presence of the larger animalcules or of crystals in minute drops of fluid, to exhibit the 'eels' in paste or vinegar &c. A modified form of the 'Stanhope' lens, in which the surface remote from the eye is plane instead of convex, has been brought out in France under the name of 'Stanhoscope,' and has been especially applied to the enlargement of minute pictures photographed on its plane surface in the focus of its convex surface. A good 'Stanhoscope,' magnifying from 100 to 150 diameters, is a very convenient form of hand-magnifier for the recognition of diatoms, infusoria, etc., all that is required being to place a minute drop of the liquid to be examined on the plane surface of the lens and then to hold it up to the light. But no hand lenses we have yet seen will compare with the Steinheil 'loups' of six and ten diameters made by Zeiss, and Reichart's pocket loups.

For the ordinary purposes of microscopic dissection *single lenses* of from 3 inches to 1 inch focus answer very well. But when higher powers are required, and when the use of even the lower powers is continued for any length of time, great advantage is derived from the employment of achromatic combinations, now made expressly for this purpose by several opticians. The Steinheil combinations give much more light than single lenses, with much better definition, a very flat field, longer working distance (which is very important in minute dissection), and, as a consequence, greater 'focal depth' or 'penetration,' i.e. a clearer view of those parts of the object which lie above or below the exact local plane. And only those who have carried on a piece of minute and difficult dissection through several consecutive hours can appreciate the advantage in comfort and in *diminished fatigue of eye* which is gained by the substitution of one of these achromatic combinations for a single lens of equivalent focus, even where the use of the former reveals no detail that is not discernible by the latter.

Fig. 29.—The Brücke lens.

Although not strictly its position, it is convenient here to refer to what is known as the 'Brücke lens'; it is much used on the Continent, but does not appear in any English treatise we have seen. It has two lenses for the objective, and a concave eye lens. It is illustrated in fig. 29.

To remedy the inconvenience of the lens being too close to the object in all but low powers, Charles Chevalier, in his 'Manuel du Micrographe' (1839), proposed to place above a doublet a concave achromatic lens, the distance of which could be varied at pleasure. The effect of this combination is to increase the magnifying power and lengthen the focus. Thus arranged, this instrument will be the most powerful of all simple microscopes, and the space available for scalpels, needles, &c. will be much greater than

with a doublet alone. The further the concave lens is removed from the latter, the greater will be the amplification.[1]

This combination, applied to lenses for examining the eye and skin, allows the use of doublets which leave a considerable distance above the object, and it is this idea which has governed the construction of the Brücke lens.

'The lens has a very long focus, and the construction is that of the Galileo telescope as applied to opera-glasses, but the amplification of the objective is much greater than that usually obtained in opera-glasses. The focus is about 6 cm., and the power three to eight times. The latter power is obtained by lengthening the tube, by which means the distance between the two lenses is much enlarged, and the amplification increased without inconveniently modifying the focus.'

This lens may be used in place of the body of a compound microscope, when it is desired to dissect or to find small objects, or it can be adapted to a simple microscope or lens-holder, with from 3 to 8 cm. between the object and objective.

Compound microscope.—The compound microscope, in its most simple form, consists of only two lenses, the *object-glass* and the *eye-glass*. The former receives the light-rays direct from the object brought into near proximity to it, and forms an enlarged but *inverted* and *reversed* image at a greater distance on the other side; whilst the latter receives the rays which are diverging from this image, as if they proceeded from an object actually occupying its position and enlarged to its dimensions, and brings these to the eye, so altering their course as to make that image appear far larger to the eye, precisely as in the case of the simple microscope. It is obvious that, in the use of the very same lenses, a considerable variety of magnifying power may be obtained by merely altering their position in regard to each other and to the object. For if the eye-glass be carried farther from the object-glass, whilst the object is approximated nearer to the latter, the image will be formed at a greater distance from it, and its dimensions will consequently be augmented; whilst, on the other hand, if the eye-glass be brought nearer to the object-glass, and the object removed farther from it, the distance of the image will be a much smaller multiple of the distance of the object, and its dimensions proportionately diminished. We shall hereafter see that this mode of varying the magnifying power of compound microscopes may be turned to good account in more than one mode; but there are limits to the use which can be advantageously made of it. The amplification may also be varied by altering the magnifying power of the eye-glass; but here, too, there are relative limits to the increase; since defects of the object-glass which are not perceptible when its image is but moderately enlarged are brought into injurious prominence when the imperfect image is amplified to a much greater extent. Hence, in proportion as the object-glass approaches more nearly a perfect combination does it admit of higher eye-pieces. In practice, and with the old achromatic system, it is generally found

[1] Robin, C., *Traité du Microscope et des Injections*, 2nd ed. 8vo, pp. 33, 34. Paris, 1887.

much better to vary the power by employing object-glasses of different foci, an object-glass of *long* focus forming an image which is not at many times the distance of the object from the other side of the lens, and which, therefore, is not of many times its dimension whilst an object-glass of *short* focus requires that the object should be so nearly approximated to it that the distance of the image is a much higher multiple of the object, and its dimensions are proportionably larger. In whatever mode increased amplification may be obtained two things must always result from the change : the proportion of the surface of the object of which an image can be formed must be diminished, and the quantity of light spread over that image must be proportionably lessened. But, as we have stated, this is dependent on the aperture and total magnifying power, and not upon (amongst other things) the focal length of the eye-piece.

We shall facilitate the comprehension by the student of the principles of the modern form of a compound microscope by means of fig. 30. In this figure the optical portion, that is, the objective and eye-piece, are drawn to the full size, but the distance between these has, from the exigencies of space, been much curtailed. A low-power objective has been specially chosen for simplicity, and a compensating eye-piece (*vide* Chapter V.) has been introduced to show its form and mode of action.

The objective is a copy of an old Ross 1-inch of 1856. The incident front (that is, the lens on which the incident beams from the object first strike) is a convex of long radius ; the incident surface of the flint lens of the back combination is a concave of very long radius, being in fact about twenty inches.

The object F has only rays drawn from one side in order that a clearer perception of the path of the rays may be seen. This pair of rays passes from the arrow (object) through the combination of lenses forming the objective, giving an *inverted* real image at A B. This image, in fact, has a convex curve towards the eye-piece : this is a position that will tend to increase the curvature of the virtual image C D given by the eye-piece. *Three rays* are drawn through the eye-piece, which gives a magnified virtual image of the real image from the objective, in order to suggest that with the eye-piece there is a commencement, as it were, *de novo*, the inverted image (A B) at the diaphragm of the eye-piece being the subject of still further and often great magnification.

In addition to the two lenses of which the compound microscope may be considered to essentially consist, it was soon found needful to introduce another lens, or a combination of lenses, between the object-glass and the image formed by it, the purpose of this being to change the course of the rays in such a manner that the image may be formed of dimensions not too great for the whole of it to come within the range of the eye-glass. As it thus allows more of the object to be seen at once, it has been called the *field-glass* ; but it is now usually considered as belonging to the ocular end of the instrument, the *eye-glass* and the *field-glass* being together termed the *eye-piece*, or *ocular*. Various forms of this eye-piece have been proposed by different opticians, and one or another will be preferred



FIG. 30.—Path of a ray of light through a modern combination of lenses for compound microscope.

according to the purpose for which it may be required. That which, until the construction of the compensation eye-pieces by Abbe, was considered the most advantageous to employ with achromatic object-glasses, to the performance of which it is desired to give the greatest possible effect, was termed the *Huyghenian*, having been employed by Huyghens for his telescopes, although without the knowledge of all the advantages which its best construction renders it capable of affording. This eye-piece, with others, will be considered in detail in the chapter (v.) given in part to their consideration; but this eye-piece consists of two plano-convex lenses, with their plane sides towards the eye. A 'stop' or diaphragm, B B, must be placed between the two lenses, in the visual focus of the eye-glass, which is, of course, the position wherein the image of the object will be formed by the rays brought into convergence by their passage through the field-glass. Huyghens devised this arrangement merely to diminish the spherical aberration; but it was subsequently shown by Boscovich that the chromatic dispersion was also in great part corrected by it. With the apochromatic lenses of the highest and best quality, (see Chapter V.) no amount of obtainable eye-piecing, if it be of the 'compensation' form, can break down the image. The editor has tried in vain to break down the image formed by a 24 mm., a 12 mm., a 6 mm., and a 4 mm., all dry apochromatics by Zeiss, and especially with a $\frac{1}{4}$th by Powell and Lealand. It is, however, a matter of moment and interest to note that with *good* objectives of the ordinary achromatic construction of large N.A. the compensating eye-pieces give better results than Huyghenian.

But of the old form of achromatic object-glass it is true of the majority that they will not bear high eye-piecing. 'B' is a convenient and useful eye-piece. For viewing large flat objects, such as transverse sections of wood or of echinus-spines, under low magnifying powers, the eye-piece known as *Kellner's* may be employed, but there is little advantage to be gained. This construction will be fully described in Chapter V. A flat, well-illuminated field of as much as fourteen inches in diameter may thus be obtained with very little loss of light; but, on the other hand, there is a very serious falling off of defining power, which renders the Kellner eye-piece unsuitable for objects presenting minute structural details; and it is an additional objection that the smallest speck or smear upon the surface of the field-glass is made so unpleasantly obvious that the most careful cleansing of that surface is required every time that this eye-piece is used. Hence it is better fitted for the occasional display of objects of the character already specified than for the scientific requirements of the working microscopist.

A *solid* eye-piece made on the principle of the 'Stanhope' lens is sometimes used in place of the ordinary Huyghenian, when high magnifying power is required for testing the performance of objectives. The lower surface, which has the lesser convexity, serves as a 'field-glass'; whilst the image formed by this is magnified by the highly convex upper surface to which the eye is applied, the advantage supposed to be derived from this construction lying in the abolition of the plane surfaces of the two lenses of the ordinary eye-

piece. A 'positive' or Ramsden's eye-piece—in which the field-glass, whose convex side is turned upwards, is placed so much nearer the eye-glass that the image formed by the objective lies below instead of above it—was formerly used for the purpose of micrometry, a divided glass being fitted in the exact plane occupied by the image, so that its scale and the image are both magnified together by the lenses interposed between them and the eye. The same end, however, may be so readily attained with the Huyghenian eye-piece that no essential advantage is gained by the use of that of Ramsden, the field of which is distinct only in its centre.

Aperture in microscopic objectives and the principles of microscopic vision.—It is now of the utmost moment that we should understand clearly the meaning and importance of 'aperture' in microscopic objectives, and by that means be led to a perception of the principles of the most recent and only rational theory of microscopic vision. Within the last twenty years this entire subject has undergone a rigorous and exhaustive reinvestigation by one of the most competent and masterly mathematical and practical opticians in the world, Professor Abbe of Jena; and, as a result, some of the judgments and opinions, as well as what were supposed to be established truths, depending apparently upon the simplest principles, and not believed to be open to change, have been shown to be absolutely without foundation; while principles hitherto quite unknown and unsuspected have been shown to operate and to rest on clearly demonstrable mathematical and physical bases. The result has been a complete revolution of what were held to be fundamental principles of microscopic optics and the theory of vision with microscopic object-glasses.

One of the foremost errors relates to the mode in which microscopic images are formed. It was assumed that their formation took place on ordinary dioptric principles. As the camera or the telescope formed images, so it was assumed that the image in the compound microscope was brought about. The delicate and complex structure of an insect's scale or of a diatom were believed to form their images according to the same precise dioptric laws by which the image of the moon or Mars is formed in the telescope. Hence it was taken for granted that every function of the microscope was determined by the geometrically traceable relations of the refracted rays of light.

With the telescope what is known as its 'aperture' is simply estimated by the diameter of the object-glass. But a close examination in theory and practice of the conditions of vision with microscopic objectives shows that such an estimate of aperture is wholly wrong in principle. The front lens of a $\frac{1}{25}$-in. objective may be no more than the $\frac{1}{30}$th of an inch in diameter, while a 3-in. objective may have a diameter of half an inch. Yet it is the smaller lens that has by far the larger 'aperture.'

Light is dispersed from every point on the surface of an object in all directions up to 180°. Only an extremely narrow pencil of this can be received by the human eye, a large pencil of light emanating from the object being lost on each side of what the eye

receives. The apparent problem of practical optics is to be able, by means of lenses, to gather up and bring to a focus as many of the unadmitted rays as possible. The general manner in which lenses act in doing this we have endeavoured in an elementary manner to show.

Soon after achromatic object-glasses were first made, Dr. Goring found that the markings on special objects—such as the scales of the wings of insects—could be seen by some object-glasses, while with others, although the magnifying power was equal, it was impossible to discern them. In every case the greater 'angle' was shown to possess the greater 'resolving' or delineating power; and this led to the important conclusion that power of 'resolution' in a lens was dependent upon 'angular aperture.'

This, however, was at a time when only 'dry' objectives were in use; the immersion and homogeneous systems, as we use them, were unknown.

But (as we shall subsequently see), even with objectives employed only with air, the angle of the radiant pencil did not afford a true comparison; when immersion objectives were introduced—objectives in which water or cedar oil replaced the air between the objective and the upper surface of the cover of the mounted object—the use of *angles* of aperture became in the utmost degree misleading; for different media with different refractive indices were employed, and the *angle* of the radiant pencil was supposed not only to admit of a comparison of two apertures in the same medium, but also to be a standard of comparison when the media were different. It was, in short, believed that an angle of 180° in air represented a large excess of aperture in comparison with 96° in water and 82° in balsam or oil, denoting, in reality, what was believed to be the *maximum* aperture of any kind of objective, which could not, it was held, be exceeded, but only equalled, by 180° in water or oil; in other words, that a radiant pencil has exactly the *same* value, when the *angles* are equal, no matter what the refractive index of the medium through which the pencil might be passing.

But to a thorough physical and mathematical study of the question such as that in which Professor Abbe engaged, it soon became apparent that even in the same medium the only exact method of comparison for objectives—when the fundamental phenomena of optics (which the older opticians had disregarded) were taken into account—was not a comparison by the angles of the radiant pencils only, but a comparison by their sines; while, when the media are different, the indices of those media would be found to form an essential factor in the problem; for an angle of 180° in air is equal to 96° in water or 82° in oil; hence three angles might all have the same number of degrees and yet denote different values, according as they were in air, water, or oil.

Thus there might be large divergence of *aperture* in two or more cases while the *angle* was identical, and from this the greatest confusion was not only possible but was realised.

A solution of the difficulty was (as we have indicated above) discovered by Professor Abbe; and it is to Mr. Frank Crisp's

lucid exposition of Abbe's elaborate monographs that the English student is immensely indebted.[1]

The definition of 'aperture' in its legitimate sense of 'opening' is shown by Abbe to be obtained when we compare the diameter of the pencil *emergent* from the objective with the focal length of that objective.

It will be desirable to explain somewhat more in detail how this conclusion is arrived at, as given in Professor Abbe's papers.

Taking in the first case a *single*-lens microscope, the number of rays admitted within one meridional plane of the lens evidently increases as the diameter of the lens (all other circumstances remaining the same), for in the microscope we have at the back of the lens the same circumstances as are in front in the case of the telescope. The larger or smaller number of emergent rays will therefore be properly measured by the clear diameter; and, as no rays can *emerge* that have not first been *admitted*, this must also give the measure of the admitted rays.

Suppose now that the focal lengths of the lenses compared are not the same—what, then, is the proper measure of the rays admitted?

If the two lenses have equal openings but different focal lengths, they transmit the same number of rays to equal areas of an image at a definite distance, because they would admit the same number if an object were substituted for the image—that is, if the lens were used as a telescope-objective. But as the focal lengths are different, the amplification of the images is different also, and equal areas of these images correspond to different areas of the object from which the rays are collected. Therefore the higher-power lens, with the same opening as the lower power, will admit a *greater* number of rays in all from the same object, because it admits the *same* number as the latter from a *smaller* portion of the object. Thus, if the focal lengths of two lenses are as 2 : 1, and the first amplifies N diameters, the second will amplify 2 N with the same distance of the image, so that the rays which are collected *to* a given field of 1 mm. diameter of the image are admitted *from* a field of $\frac{1}{N}$ mm. in the first case and of $\frac{1}{2N}$ mm. in the second. Inasmuch as the 'opening' of the objective is estimated by the diameter (and not by the area), the higher-power lens admits *twice* as many rays as the lower power, because it admits the *same* number from a field of *half* the diameter, and in general the admission of rays with the same opening but different powers must be in the inverse ratio of the focal lengths.

In the case of the single lens, therefore, its aperture must be determined by *the ratio between the clear opening and the focal length*, in order to define the same thing as is denoted in the telescope by the *absolute* opening

[1] 'On the Estimation of Aperture in the Microscope' (Abbe), *Journ. R.M.S.* ser. ii. vol. i. 388; 'Notes on Aperture, Microscopical Vision, and the Value of wide-angled Immersion Objectives,' *ibid.* 303; 'The Aperture of Microscope Objectives,' *English Mechanic*

Consider now the compound objective—the most important case in the microscope. What is the opening of this composite system? We must adhere to the diameter of the admitted cone at that plane where it has its *ultimate maximum value*, which is obviously the diameter of the pencil at its emergence from the system, or, practically, the *clear, effective diameter of the back lens.* The emergent pencil from a microscope-objective converging to a relatively distant focus has its rays approximately parallel, and the conditions are once more similar to those of the telescope-objective on the side of the object. The diameter of this emergent pencil, whether it emerges from a single lens or from a composite system, must therefore always have the same signification. The influence of the power on focal length also remains the same as in the case of the single lens. An objective with a focal length equal to half that of another admits, with the same linear opening, twice as many rays as the latter, because the amplification of the image at one and the same distance is doubled, and the same number of rays consequently are admitted by the higher power from a field of half the diameter. And this will hold good whether the medium around the object is the same in the case of both objectives or different; for an immersion system and a dry system always give the *same* amplification when the focal length is the same.

Thus we arrive at the general proposition for all kinds of objectives. First, when the power is the same, the admission of rays varies with the diameter of the pencil at its emergence. Secondly, when the powers are different the *same admission* requires *different openings* in the proportion of the focal lengths, or, conversely, with the *same opening the admission is in inverse proportion* to the focal length—that is, the objective which has the wider pencil relatively to its focal length has the larger aperture.

Thus we see that, just as in the telescope the absolute diameter of the object-glass defines the aperture, so in the microscope the ratio between the utilised diameter of the back lens and the focal length of the objective defines its aperture.

This definition is clearly a definition of aperture in its primary and only legitimate meaning as 'opening'—that is, the capacity of the objective for admitting rays from the object and transmitting them to the image; and it at once solves the difficulty which has always been involved in the consideration of the apertures of immersion objectives.

So long as the angles were taken as the proper expression of aperture, it was difficult for those who were not well versed in optical matters to avoid regarding an angle of 180° in air as the maximum aperture that any objective could attain. Hence, water-immersion objectives of 96° and oil-immersion objectives of 82° were looked upon as being of much *less* aperture than a dry objective of 180°, whilst, in fact, they are all *equal*, that is, they all transmit the same rays from the object to the image. Therefore, 180° in water and 180° in oil are unequal, and both are much larger apertures than the 180° which is the maximum that the air objective can transmit.

If we compare a series of dry and oil-immersion ob ectives, and, commencing with very small air-angles, progress up 180° air-angle, then taking an oil-immersion of 82° and progre t agai 180° oil-angle, the ratio of opening to power progresse nt also, and attains its maximum, not in the case of the 180° (when it is exactly equivalent to the oil-angle c greatest at the oil-angle of 180°.

If we assume the objectives to have the same power we get rid of one of the factors of the ratio, and we na compare the diameters of the emergent beams, and can rep their relations by diagrams. Fig. 31 illustrates five cases of dine apertures of ¼-in. objectives—viz. those of dry objectives of 60°, 97°, and 180° air-angle, a water-immersion of 180° water-angle, and an oil-immersion of 180° oil-angle. The inner dotted circles in the two latter cases are of the same size as that corresponding to the 180° air-angle.

A dry objective of the full maximum air-angle of 180° is only able (whether the first surface is plane or concave) to utilise a diameter of back lens equal to twice the focal length, while an immersion lens of even only 100° (in glass) requires and utilises a *larger* diameter, i.e. it is able to transmit more rays from the object to the image than *any* dry objective is capable of transmitting. Whenever the angle of an immersion lens exceeds twice the critical angle for the immersion-fluid, i.e. 96° for water or 82° for oil, its aperture is in excess of that of a dry objective of 180°.


1
Numerical Aperture 1·52 = 180° oil-angle.
2
Numerical Aperture 1·33 = 180° water-angle.
3
Numerical Aperture 1·00 = 180° air-angle = 96° water-angle = 82° oil-angle.
4
Numerical Aperture ·75 = 97° air-angle.
5
Numerical Aperture ·50 = 60° air-angle.

FIG. 31.—Relative diameters of the (utilised) back lenses of various dry and immersion objectives of the same power (¼) from an air-angle of 60° to an oil-angle of 180°.

Having settled the principle, it was still necessary, however, to find a proper notation for comparing apertures. The astronomer can compare the apertures of his various telescopes by simply expressing them in inches; but this is obviously not available to the microscopist, who has to deal with the *ratio* of two varying quantities.

Professor Abbe here again conferred a boon upon microscopists by his discovery (in 1873, independently confirmed by Professor Helmholtz shortly afterwards) that a general relation existed between the pencil admitted into the front of the objective and that emerging

from the back of the objective, so that the ratio of the semi-diameter of the emergent pencil to the focal length of the objective could be expressed by the sine of half the angle of aperture (u) [1] multiplied by the refractive index of the medium (n) in front of the objective, or $n \sin u$ (n being 1·0 for air, 1·33 for water, and 1·5 for oil or balsam).



FIG. 32.—Illustration of the law of consequence for aplanatic systems.

Let O and O* (fig. 32) be the conjugate aplanatic foci of a wide-angled system; u, U the angles of inclination of *any two* rays admitted

[1] In the original translation of the papers of Professor Abbe from German into English the German mathematical symbols have been retained. In the summary of


A
N.A. of objective = μ sin φ = 1·5 × ·573 = ·86.
n sin u = 1·5 × ·573 = ·86 = N.A. of objective.
oil μ = 1·5
35°
35°
oil n = 1·5
glass μ = 1·5
glass n = 1·5
air n* = 1·0
60°
60°
air μ' = 1·0
n* sin u*
μ' sin φ'
Angular aperture of objective = 35° + 35° = 70° in glass which is equivalent to the angular aperture of the condenser = 60° + 60° = 120° in air.
N.A. of condenser = n* sin u* = 1·0 × ·86 = ·86.
μ' sin φ' = 1·0 × ·86 = ·86 = N.A. of condenser
B

FIG. A1.—Identity of $n \sin u$ (German math. form) with $\mu \sin \phi$ (English). Also N.A. and angular aperture.

Abbe's theories and demonstrations presented in the following pages the Editor has scarcely felt justified in altering this, especially as the German form of symbol ob

from the radiant, and u^*, U^* the angles of the same rays on their emergence; then we shall have always

$$\sin U^* : \sin u^* :: \sin U : \sin u;$$

or,

$$\frac{\sin U^*}{\sin U} = \frac{\sin u^*}{\sin u} = \text{const.} = c;$$

that is, the sines of the angles of the conjugate rays on both sides of an aplanatic system always yield one and the same quotient c, whatever rays may be considered, so long as the same system and the same foci are in question.

This proposition holds good for every arrangement of media, and refracting surfaces that may go to the composition of the system, and for every position of object and image. It is the law upon which depends the delineation of an image by means of wide-angled pencils.

When, then, the values in any given case of the expression $n \sin u$ (which is known as the "numerical aperture" and expressed by N.A.) has been ascertained, the objectives are instantly compared as regards their aperture, and, moreover, as 180° in air is equal to 1·0 (since $n = 1{\cdot}0$ and the sine of half 180° or 90° = 1·0), we see with equal readiness whether the aperture of the objective is smaller or larger than that corresponding to 180° in air.

Thus, suppose we desire to compare the relative aperture of three

tains in our Universities, and is thoroughly understood amongst University men. But to those unaccustomed to mathematical formulæ confusion might easily arise from the juxtaposition of different symbols meaning precisely the same thing. To meet the possible necessity of these this footnote is inserted with an accompanying diagram to illustrate the identity of '$n \sin u$' with '$\mu \sin \phi$.'

The student who has mastered Snell's Law of Sines, given and illustrated on p. 3 (fig. 1), will by a glance at the figure A1 on p. 48 understand the meaning and importance of the expression 'N.A.' (numerical aperture) and at the same time will grasp wherein it differs from "angular aperture" (*q.v.*). He will also perceive how it comes to pass that an angular aperture of 70° in *glass* is equivalent to an angular aperture of 120° in *air*.

In the figure the upper hemispherical lens represents the *front* of a homogeneous immersion objective. It is supposed to be focussed on an object in contact with the lower side of a cover-glass. Between the plane front of the lens and the upper surface of the cover-glass is a drop of oil of cedar-wood, whose refractive index is 1·3, being thus identical with the cover-glass and the front lens.

It is understood that no slip is used, and that there is nothing between the object and the front lens of the condenser.

In this case the axis A B is the *normal* (p. 5, fig. 2); on the left-hand side there is a ray which makes an angle of 35° with the normal in glass issuing into air on the right-hand side of the normal. By Snell's formula (p. 3)—

$$\mu \sin \phi = \mu' \sin \phi';$$

$$\sin \phi' = \frac{\mu \sin \phi}{\mu'} = \frac{1{\cdot}5 \times {\cdot}573}{1{\cdot}0} = {\cdot}86;$$

$$\phi' = 60^\circ \text{ (from Table I.)}$$

Therefore the ray on emerging from the under surface of the cover-glass will make an angle of 60° from the normal.

The dotted lines show the path of the ray *where the German symbols are used.*

$$n \sin u = n^* \sin u^*;$$

$$\sin u^* = \frac{n \sin u}{n^*} = \frac{1{\cdot}5 \times {\cdot}573}{1{\cdot}0} = {\cdot}86.$$

$$u^* = 60^\circ \text{ (from Table I.)}$$

***Numerical aperture*, therefore, is the sine of half the *angular aperture* multiplied by the refractive index of the medium.**

It will be observed that the rays passing through the oil of cedar enter the front lens without refraction; this is due to the fact that the media in which the rays are travelling are of the same refractive index, i.e. they are homogeneous.

objectives, one a dry objective, the second a water-immersion, and the third an oil-immersion. These would be compared on the angular aperture view as, say, 74° air-angle, 85° water-angle, and 118° balsam-angle; so that a calculation must be worked out to arrive at a due appreciation of the actual relation between them. Applying, however, 'numerical' aperture, which gives ·60 for the dry objective, ·90 for the water-immersion, and 1·30 for the oil-immersion, their relative apertures are immediately appreciated, and it is seen, for instance, that the aperture of the water-immersion is somewhat less than that of a dry objective of 180°, and that the aperture of the oil-immersion exceeds that of the latter by 30 per cent.

When these considerations have been appreciated, the advantage possessed by immersion in comparison with dry objectives is no longer obscured. Instead of this advantage consisting merely in increased working distance or absence of correction-collar, it is seen that a wide-angled immersion objective has a larger aperture than a dry objective of the maximum angle of 180°; so that for any of the purposes for which aperture is desired an immersion must necessarily be preferred to a dry objective.

1. There exists then a definite ratio between the linear opening and the focal length of a system, which must be entirely independent of the composition and arrangement of the system, and solely determined by the above-mentioned aperture equivalent of the admitted cone of rays. When the equivalent is the same we have always the same proportion of opening to focal length, whatever may be the particular arrangement of refracting media in the system.

2. If the objectives whose apertures are compared work in the *same* medium, and admit angles of, say, 60°, 90°, 180°, their apertures are not in the ratios of those numbers, but are as ·50, ·70, and 1·0. The 180°, for instance, does not represent *three* times the aperture of the 60°, but *twice* only.

3. If the objectives work in *different* media, as air and oil, the latter may have an aperture exceeding that of a dry objective of 180° angle. For with the dry objective the refractive index (n) and the sine of half the maximum angle (u) both $= 1$, so that $n \sin u = 1$ also, whilst with the immersion objective n is greater than 1 (say 1·5 for oil), and the angle u may therefore be much less than in the case of the dry objective, and yet the value of the expression $n \sin u$ (i.e. the aperture) may be greater than 1·0.

The two latter deductions are so directly opposed to what was accepted by the older opticians and microscopists that a closer if brief consideration of some of the points which bear upon this branch of the subject may here be serviceably summarised.

Take, first, the case of the medium being the same.

Difference of aperture involves a different *quantity of light* admitted to the objective provided all other circumstances are equal. Hence the question of aperture leads to the consideration of the *photometrical* equivalent of different apertures or aperture angles. It is not of the essence of the problem, but it affords an additional *illustration* of numerical aperture, and is thus of great service in its exposition. It is manifest that aperture cannot be based on quantity

of light alone—more light can always be obtained in the image by throwing more upon the object—but no increase in the amount of illumination can make a dry lens equal in performance as regards aperture to a wide-angled immersion lens.

The popular notion of a pencil of light may be illustrated by fig. 33, which assumes that there is equal intensity of emission in all directions, and that the intensity of a portion of the pencil taken close to the perpendicular is identical with that of another portion of equal angular extension, but more removed from the perpendicular. On this view, therefore, the *quantity of light* contained in any given pencils may be compared by simply comparing the contents of the solid cones.

When, however, *aperture* is considered, and the values of $n \sin u$ are worked out for particular cases, they are seen to differ from



FIG. 33.—Diagram showing erroneous inference as to the intensity of emitted rays.

those obtained by estimating in the above manner the amount of light in the solid cones, and some perplexity naturally arises from the supposition that the measure of the aperture of the objective does not correspond to that of the quantity of light which it admits.

All this arises from the mistaken assumption that a luminous pencil is properly represented by fig. 33.

In the last century (1760) Bouguet[1] and Lambert[2] established the important fact that with any surface of *uniform radiation* the intensity of the emitted *rays* is *not* the same in all directions. The *power of emission* and the intensity of the rays (i.e. the quantity of light emanating from a given surface-element within a cone of given narrow angle) varies in the proportion of the *cosine* of the angle of obliquity under which the ray is emitted; in other words, in the proportion of the *cosine* of the angle of deflection from the perpendicular to the luminous surface under



FIG. 34.—The intensity of emitted rays is not the same in all directions.

[1] *Traité d'Optique sur la Gradation de la Lumière*, 1760.
[2] *Photometria*, 1760.

which the ray is sent out. The rays are more intense in proportion as they are inclined to the surface which emits them, so that a pencil varies in proportion as it is taken close to or is removed from the perpendicular. A pencil is not, therefore, correctly represented by fig. 33, but by fig. 34, the density of the rays decreasing continuously from the vertical to the horizontal.

Owing to the different emission in different directions, the quantities of light emitted by an element in the same medium in cones of different angle such as w and w', fig. 35, are not in the ratio of the solid cones, as would be the case with equal emission, but in the ratio of the squares of the sines of the semi-angles, so that the squares of the sines of the semi-angles constitute the true measure of the quantity of light contained in any solid pencil.

When, therefore, the medium is the same, it is seen that there



FIG. 35.—The unequal emission of rays.

is no contradiction between the measure of the aperture of an objective ($n \sin u$) and that of the quantity of light admitted by it, the latter being $(n \sin u)^2$.

The simplest experimental proof of the unequal emission in different directions will be found in the fact that the sun, the moon, the porcelain globe of a lamp or any other bright spherical object, with so-called uniform radiation in all directions, is seen projected as a surface of *equal* brightness. If there were equal intensity of emission in all directions, what would be the necessary result? Compare two equal portions of the surface, one, a (fig. 36), perpendicular to the line of vision, and the other, b, greatly inclined. Every infinitesimal surface-element of b sends to the pupil of the eye a cone of the same angle u', as a similar point of a (the slight difference of the distance from the eye being disregarded). If the intensity of the rays were equal as supposed, the whole area b would send to the eye the same quantity of light as the equal area a, since both areas contain exactly the same number of elements. But the *whole* quantity of light from b would be projected upon a smaller area of the retina than that from a (as b appears under a smaller visual angle, being diminished according to the obliquity, or

1 : cos w). Consequently, if the assumption were true, b must ppear to be brighter than a, and the sphere would show increasing ightness from the centre to the circumference. C to the argin the increase ought to be very rapid, and the ness a rge multiple of that at the centre.

This, as is well known, is not the case, the projec phere showing equal brightness. The quantity of ligh mitted from b within a given small olid cone u' in an oblique direction must be less than that which is emitted from a within an equal solic one u in a perpendicular direction, a the intensity of the rays must decrease in the proportion of 1 : cos w wh the obliquity w increases.



FIG. 36.—Diagram of a bright spherical object emitting light.

As then in one and the sa medium the number of rays co by a pencil and the photom quantity of light are proportiona theorem of Lambert, establishe for more than a century, is sufficie t of itself to overthrow the very basis of the *angular* expression of aperture, and to prove that, when we are dealing with one and the *same medium* only, the *angle* is not the sufficient expression, but that it is the *sine of the semi-angle* which must be taken.

We may pass now to the case of the media being *different*, as air and oil, and comparing the aperture of a dry objective of 180° with that of an oil-immersion objective of 100°, the values of sin u (or the 'numerical' aperture) ive 1·0 for the former and 1·17 for the tter, which is therefore represented to ave a *larger* aperture than a dry objective of the greatest possible angle.

In this case also considerable perexity has arisen. It has been assumed at the total amount of light emitted om a radiant point under a given ed illumination must be the same, ether the point is in air, water, or oil, and that that being so, e 180° admitted by the dry objective must represent a maximum antity of light, a 'whole' which cannot be exceeded, but only nalled, by a water- or oil-immersion objective. The numerical erture notation giving figures in excess of 1·0 (which represents 0° in air) is consequently supposed to be clearly erroneous and sleading. Here the whole difficulty lies in the absolutely false sumption that there is identity of radiation in different media.

In 1864 R. Clausius established, by distinguished research, the proposition [1] that the *power of emission* of a body—in regard to heat as well as light—*is not the same in different media*, but varies in the ratio of the squares of the refractive indices, so that the whole emitted light from any surface-element of a self-luminous body is increased in the proportion of $1 : n^2$ when this body is brought from air into a denser medium of refractive index n. If a glowing body at a constant temperature, such as a bar of iron, could be immersed in a medium of 1·5 refractive index in such a way that the surface were in optical contact with the medium, and the eye of the observer immersed likewise in suitable conditions, the body would be seen *brighter in all directions* in the proportion of 9 : 4 than it appeared in air.

The whole hemisphere of radiation in air is indeed *less* than the whole hemisphere of radiation in water or oil, as the squares of the refractive indices of the media, viz. as 1·0, 1·77, and 2·25.

Thus it is seen that the *quantity of light* emitted from an object under a given illumination is *not* measured by the angle of the emitted cone at the radiant, nor can it be measured in any way by means of the angle *alone*. The quantity depends under all circumstances on *the product of the sine of the semi-angle and the refractive index of the medium in which the object is luminous*, and is expressed by the square of this product, or by the square of the 'numerical aperture' of the pencil.

It thus follows that the estimation of the *quantity of light* is found to be in complete accordance with the expression of *aperture*.[2]

We are now prepared to advance to another point. It was a view very commonly held until recently, that the superiority of immersion objectives over dry ones was confined to the case of the former being used with balsam-mounted objects.

If we have a pencil in air, say 170°, as shown in fig. 37, a dry objective of large aperture will be able to admit it. If, however, the object is in balsam, as in fig. 38, it is no longer possible for so large a pencil to emerge from the balsam. The rays shown by the dotted

FIG. 37.

lines in fig. 38 will be totally reflected by the cover-glass, and only those within a smaller angle of 82° will pass out. Although these are expanded into 180° on emerging into air, of which the objective takes up 170°, yet this 170° contains, it is supposed, less light than the 170° in fig. 37, as it has been 'diluted' by the refraction.

[1] 'Ueber die Concentration von Wärme- und Lichtstrahlen &c.' *Pogg. Annalen d. Physik*, cxxi. 1864.

[2] Fig. A 2 gives a good, practical illustration of the relative illuminating power of objectives of varying apertures, and at the same time affords a simple explanation of the reason why $(n \sin u)^2$ is a measure of this illuminating power. Let the circles A and B represent the backs of two objectives of the same power but of different apertures; then the radii C D and E F will represent the angle $n \sin u$ (or $\mu \sin \phi$) in fig. A 1 (p. 48, note). Now because the areas of circles are to one another in the

A dry objective was therefore supposed to be placed at a disadvantage when used upon balsam-mounted objects, its aperture being supposed to be 'cut down' by the balsam, and the advantage of the immersion objective was considered to rest on the fact that it restored, in the case of the balsam-mounted object, the same conditions as subsisted in the case of the dry-mounted object, allowing as large (but no larger) an aperture to be obtained with the former object as is obtained by the dry objective with the latter.

The error here lies in the assumption of the identity of radiation in air and balsam. If there were in fact any such identity, the

FIG. 38.

conclusion above referred to would, of course, be correct, for if in fig. 37 the *air* pencil of 170° was identical with the *balsam* pencil of 170° (shown by the *dotted lines* in fig. 38), there would necessarily be a relative loss of light in the latter case in consequence of so much of the pencil being reflected back at the cover-glass.

When, however, the increase of radiation with the increase in the refractive index of the medium is recognised, the mistake of the preceding view is appreciated. The 170° in *air* of fig. 37 is not equal to, but much less than, the 170° in *balsam* of fig. 38, and notwithstanding that a great part of the latter does not reach the

proportion of the squares of their radii, it follows that if we designate the radius by $n \sin u$ (or $\mu \sin \phi$), the area of the circle A will be to the area of the circle B as the square of the radius of A is to the square of the radius of B, or as $(n \sin u)^2$ is to $(n' \sin u')^2$.



FIG. A 2.—The backs of two objectives of the same power but different apertures.

The student will observe that the radius of B is twice that of the radius of A; consequently the area of B will be four times as great as that of A; which means that, since the numerical aperture of the objective B is twice as great as that of the objective A, its illuminating power will be four times as great.

objective in consequence of total reflection, yet the remainder (80°) which *does* reach it is the exact equivalent of the air-pencil of fig. 37, the two air-pencils of 170° being in all respects identical.

The immersion objective, therefore, which is able to receive the whole *balsam* pencil of 170° (dotted lines in fig. 38), takes up a *greater* quantity of light than the *air* pencil of fig. 37, and so not merely equals the dry objective but surpasses it.

Let it be specially noted that in dealing with the quantity of light in connection with aperture, the idea has not been that we have been engaged with what is in any sense essential, but to remove a difficulty felt by many. It must be clear to all that if a greater aperture signified nothing more than a greater quantity of light, that is to say, if there were no such *specific* difference of the rays which can be utilised by different apertures, as we have demonstrated above, the whole question would be of quite subordinate interest.

Another subject requiring some further elucidation here is the 'different angular distribution of the rays in different media.' The essence of the idea of 'aperture' is *relative opening*. However defined, its significance can only be appreciated by taking into account the image-forming pencil *emergent* from the objective, and the change in its diameter consequent upon the admission of different cones of light. This diameter affords a visible indication of the *number of rays* (not mere quantity of light photometrically, which can be readily varied) which are collected to a given area of the image, and which must have been gathered in by the lens from the conjugate area of the object. If the diameter of the emergent pencil is seen to be increased, whilst the amplification of the image and the focal length are unchanged, it is clear that the objective must have admitted *more rays* from every element of the object because it has collected more to every element of an equally *enlarged* image. Manifestly we get an accurate measure of what is *admitted* into an objective by being able to estimate what it *emits*. It is physically impossible that a system of lenses should emit more light than it has taken in.

Hence 'aperture' means the greater or less capacity of objectives for gathering-in rays from luminous objects.

When the admitted pencil is in the same medium, we *see* the additional portions of the solid cone from the radiant, which correspond to the additional portions of the enlarging opening. But if in any other case (e.g. where the medium is different) we see that a certain solid cone, A, from a radiant is transmitted through a certain opening, α, and that another solid cone of rays, B, cannot be transmitted through the same opening, α, but requires a wider one, β, whilst all other circumstances, except those of the radiant, have remained the same, we can only conclude that the pencil B must contain rays which are not contained in A, even if the admitted cone is not increased in size. For the additional portion $(\beta - \alpha)$ of the wider opening, β conveys rays to the image which are certainly not conveyed by the smaller opening α. From the radiant only can this surplus come, and the pencil B which requires the additional opening must embrace *more* rays, *even if it should not be of greater angle.*

A given objective may, in fact, collect the rays from a radiant *in*

air almost to the entire hemisphere, and it then utilises a definite opening double its focal length. But when the radiant is in balsam (without any other alteration), the same opening is seen to be utilised by the rays which are within a smaller cone of not more than 82°, and rays which are outside this cone require a surplus opening which is never required for rays in air.

This holds good whether there be refraction or no refraction at the front surface of the system; the difference is based solely on the difference of the medium. Consequently we arrive at the conclusion that the solid cone of 82° in balsam embraces the same rays which, in air, are embraced by the whole hemisphere, and every wider cone in balsam exceeding the 82° conveys *more* rays from the object than are admitted by the whole hemisphere of radiation in air.

It follows, therefore, that the same rays which in air are spread over the whole hemisphere are closed together or compressed in balsam within a narrower conical space of 41° around the perpendicular, and all rays which travel in balsam outside this cone constitute *a surplus of new rays*, which are never met with in air—that is, *are not emitted when the object is in air.* The loss which takes place in the latter case can never be compensated for by increase of illumination because the rays which are lost are *different* rays physically to those obtained by any illumination, however intense, in a medium like air.

In the paper of Professor Abbe there is an elaborate and careful elucidation of this change in the angular distribution of the radiating light when the medium is changed; but to Mr. Crisp's paper on the same subject, giving an exposition and simplification of Abbe's demonstration, the novice will look with the utmost profit.[1] The following extract will give clearness and emphasis to the above deductions of Abbe:—

'If we take the case of *refraction*, then one of the most fundamental of optical principles shows that the *same* rays which in air occupy the whole hemisphere are compressed in a medium of higher refractive index within a smaller angle, viz. twice the critical angle. If in fig. 39 the object is illuminated by an incident cone of rays of nearly 82° within the slide, and the slide has air above in the first case and oil in the second, it is obvious that the same ray which is incident on the object at nearly 41° will always emerge in air at an angle of nearly 90° (a'), and in oil at nearly 41° (a''), so that the same rays which in air are expanded over the whole hemisphere are compressed into 82° in oil, and, therefore, rays beyond 82° in oil must represent surplus rays in excess of those found in the air-hemisphere.



FIG. 39.—Comparative compression of light rays in two different media.

'If, on the other hand, the case of *diffraction* is considered, then Fraunhofer's law shows that the same diffracted beams which in air

[1] *Journ. R.M.S.* ser. ii. vol. i. p. 303.

occupy the whole hemisphere (fig. 40) are in oil compressed within an angle of 82° round the direct beam (fig. 41), so that there is room for additional beams.'

The unequal equivalent of equal angles becomes, therefore, a de-



FIG. 40.—Diffracted beams in air.



FIG. 41.—Diffracted beams in oil.

monstrated truth—a truth which is capable of experimental proof by every owner of a fair microscope.

Anyone possessing a dry object-glass of an aperture of 170°, for example, may readily do so. In this case, *a*, *a*, fig. 42, will represent



FIG. 42.

the pencil radiating from an object in air, and capable of being taken up by that objective. This pencil, on its emergence from the back lens of the combination, will present a diameter somewhat less than twice the focal length of the objective presented in fig. 43.



FIG. 43.

But let the object be now placed in Canada balsam and covered in the usual way; the *angle* of the pencil, by the greater refractive power of the medium, will be demonstrably reduced to 80°, as shown in fig. 44. But it will be found, on examination of the *emergent* pencil from the back lens, that this pencil occupies exactly the same diameter (fig. 43) as before. The medium in which the object is has not, of course, altered the *power* of the objective; and since the diameter of the emergent pencil is the same in both cases, the ratio of 'opening' to focal length, which is the aperture, is the same also. Hence it is seen in the simplest way that *different angles* in media of different refractive indices may

FIG. 44.

denote *equal apertures*, and *equal angles* in different media denote *different apertures*.

That 'immersion' objectives may have greater apertures than the maximum attainable by a dry objective is capable of equally simple proof by accessible experiment.

If an oil-immersion objective of 122° balsam angle be taken, and so illuminated that the whole aperture is filled with the incident rays, and if we use first an object mounted in air, we really find that we

have a *dry* object-glass of nearly 180° angular aperture. This is readily seen by fig. 45. By the arrangement presented in the figure the cover-glass is practically the first surface of the objective, for the front lens, the immersion fluid, and the cover-glass are all homogeneous, and of the same refractive index, and consequently they form a front lens of extra thickness. When the object is close to the cover-glass the pencil radiating from it will be very nearly 180°, and the emergent pencil will be seen to utilise so much of the back lens of the combination as is equal to twice the focal length of the objective, as shown in the *inner* circle of fig. 46.



FIG. 45.—Diagram illustrating difference of emerging pencil without and with balsam.

If now we run Canada balsam beneath the cover-glass so as to immerse the object, the pencil taken up by the objective is no longer 180°, but only 122°; but in spite of that the diameter of the emergent pencil is *larger* than it was when the angle of the pencil was 180° in air, and is represented by the outer circle in fig. 46. In both these cases the power is identical; it follows, therefore, that the greater diameter of the emergent pencil from the back of the combination denotes the greater *aperture* of the immersion objective over that of the dry one, although it possessed an *angle* of 180°. From this escape is impossible, and it is for this reason that opticians make the back lenses of their immersion object-glasses larger than those of dry ones of the same power.



FIG. 46.

Many further illustrations might be given, but none affording greater facility than the following, viz.: 'Select a good specimen of *Amphipleura pellucida* and use oblique illumination, bringing out clearly the striation.

'On removing the eye-piece, placing the pupil on the air-image of the diatom, and looking down on the lens, the direct incident beam will be seen emerging as a bright spot, and exactly opposite and *close to the margin* a faint bluish light (see fig. 47). If now a small piece of paper is placed on the back lens of the objective so as to just cover up the blue light, and the eye-piece is replaced, the diatom is still visible, but all the striation which was imaged by the blue marginal light has entirely disappeared. The latter must therefore consist of image-forming rays.'



FIG. 47.—Back of lens on removing eye-piece when *A. pellucida* has been resolved, showing spot of bright light and faint bluish spot opposite.

Enough has thus been advanced to enable the student of even the elementary principles of modern object-glass construction to

demonstrate for himself that immersion lenses not only possess an excess of aperture over dry lenses, but that the rays so in excess are image-forming.

The refractive indices of (cedar) oil, water, and air are respectively 1·52, 1·33, and 1·0. 'Angular aperture' claimed that the *angles* of the admitted pencils to lenses of these three constructions expressed equal 'apertures.' But this is a fallacy, now so palpable, but which has exerted an influence so deterrent on the progress of the construction of our higher object-glasses and condensers, that its final disappearance as an unjustified assumption which had crept into the area of theoretical and practical optics, unverified by facts and devoid of the wedding garment of deduction, is a triumph which will make the name of Abbe long and gratefully remembered.

The principle upon which increase of numerical aperture gives increased advantage to an object-glass manifestly needs careful study and elucidation. We have but to refer to the best work done by those who have employed the microscope to any scientific purpose for the past fifty years to discover that there has been an admission, which has steadily strengthened, that by enlargement of aperture an increase in the efficiency of the objective, when well made, was inevitable. During the last twenty-five years this has been especially manifest. To increase the aperture of an objective under the name of greater 'angle' has been *the* special aim of the optician and the constant and increasing desire of all workers with moderate and high powers.

The true explanation of this is quite independent of any consideration of apertures in excess of the maximum in air, and indeed of the whole question of immersion objectives. The old view that all high and excellent results depended on the *angle* at which the light emerged from the object, involving some assumed property of a special kind in the obliquity as such, has been most tenaciously held ; but it is an x in the problem which has not only never been demonstrated, but the scientific explanations of all the optical properties of lens combinations in the formation of images by means of numerical aperture, proves that it is hopeless to attempt to attach any value to angle *as* angle.

About twenty years ago it presented itself to Professor Abbe as a problem worthy of most careful inquiry as to why great 'angle' or obliquity as such gave to objectives an enhanced capacity in the disclosure of obscure structure. The first step was a consideration of the grounds on which the theory of the value of *angle* of aperture rested. But no such basis was found to exist ; no investigation of the question had been made. It was demonstrated that a pencil of 170° would show minuter structure than one of 80° in the same medium ; and from *this* a generalisation had been made that upon the obliquity of the 'angle' of light depended the delineating power. *It was taken as a self-evident proposition that the formation of the image in the microscope took place in every particular according to the same dioptric laws by which images are formed in the telescope*, and it was tacitly taken for granted that every function of the

microscope was determined by the geometrically traceable relations of the refracted rays of light.

A prolonged course of able and exhaustive experiments conducted by Abbe showed that, whilst the old view held good in certain cases capable of definite verification, yet that the vast majority of objects, and especially those with which the highest qualities of an objective are called into operation, the production of the microscopic image is wholly and absolutely dependent, not upon the obliquity of the rays *to the object*, as it had been so long and so stoutly maintained, but upon their obliquity *to the axis of the microscope*.

Such coarse objects as require only a few degrees of aperture to disclose them are dependent on 'shadow effects'; but when extremely minute and delicate structures are to be disclosed small apertures are absolutely useless, and mere increase of obliquity of pencil as such is powerless to alter the result. It can be effected only by increased numerical aperture, showing that the greater obliquity of the rays incident on, or remitted from, the object is not, and cannot be, *of itself* an element in the superior optical performance of greater aperture. If it were so, all the results of increased aperture would be secured by *inclining the object* to the axis of the microscope; but it may be readily tested that when a given object cannot be 'resolved,' or its structure delineated, by an objective with an aperture of 80° in the ordinary position, but *can* be resolved in the ordinary position by an objective with an aperture of 90°, *no inclination of the object* to the axis of the instrument will enable the objective of 80° to do the work easily done by one of 90°. This may be tested by anyone possessing the instruments.

As a matter of fact, this so-called but imaginary 'angular grip' is greater in a wide-angled dry lens than in one of 90° balsam-angle, and it is certainly cut down more and more when with one and the same objective preparations are observed in water, balsam, and cedar oil successively. If now the angles *quâ* angles are effective in *any* way, *something* must be *lost* by change of angle in this direction, and something ought to be gained by change in the reverse direction, other conditions remaining the same. It is needless to say that all experience and the entire course of proof and reasoning given above are diametrically opposed to such conclusions.

Similarly it will be manifest that the conception that 'solid vision' or perspective effect in a microscopic image is one of the consequences of oblique 'angular' illumination is equally invalid. It assumes that the different perspective views of a preparation examined with the microscope, which correspond to the different obliquities, produce the same effects as if they were seen separately by different eyes, as in the case with the binocular microscope. In reality, whenever we have the advantage of solid vision, owing to a different perspective projection of different images, in the microscope or otherwise, this is solely because the different images are seen by *different* eyes. In microscopic vision there is no difference of *projection* connected with different obliquities; in the binocular microscope there is a diversity of images which are depicted by pencils of

different obliquities at the object, which is a *certain kind* of perspective difference ; but the above and other observations and experiments show that even here there is essential divergence from the conditions of ordinary vision.

It is thus plain that whenever aperture is effective in delineation the mode in which it becomes so is *not* by means of the obliquity of the rays to the object ; while it has already been shown that increase of light, always concomitant with the use of immersion objectives, is a relative advantage, but no part of the explanation of the superior action of the combination of lenses. *Angle* is demonstrably not the true basis for the comparison of objectives ; it fails in regard to aperture in general, so far as it has relation to opening ; it fails equally in regard to the number of rays and the quantity of light admitted to the system of lenses ; while its failure in regard to the delineating power of objectives is everywhere seen and admitted.

At the same time it is plain that the cause of increased power of performance in the objective is directly connected with the larger *opening* or 'aperture' of the immersion and homogeneous systems. In other words, it becomes clear that *something* is admitted into the objectives with greater apertures which contributes to the formation of an image, such as objectives of lesser aperture *cannot form* because their 'openings' or 'apertures' cannot admit that 'something.'

What this is becomes explicable by the researches of Abbe. It is demonstrated that microscopic vision is *sui generis*. There is, and can be, *no* comparison between microscopic and macroscopic vision. The images of minute objects are not delineated microscopically by means of the ordinary laws of refraction ; they are not *dioptrical* results, but depend entirely on the laws of *diffraction*. These come within the scope of and demonstrate the undulatory theory of light, and involve a characteristic change which material particles or fine structural details, in proportion to their minuteness, effect in transmitted rays of light. The change consists generally in the breaking up of an incident ray into a group of rays with large angular dispersion within the range of which periodic alternations of dark and light occur.

If a piece of wire be held in a strong beam of divergent light so that its shadow fall upon a white surface, the shadow will not be sharp and black, but surrounded by luminous fringes having the colours of the spectrum, and the centre, where the black shadow of the wire should be, is a luminous line, as if the wire were transparent. This phenomenon, as is generally known, is due to the *inflection* of the diverging rays on either side of the wire. The inflected rays in passing over one edge of the wire meet the rays inflected by the other edge and 'interfere,' producing alternate increase and diminution of amplitude of oscillation or undulatory intensity, and giving rise to coloured fringes if white light is used, and if homogeneous light be employed giving origin to alternate bands of light and dark, the centre always being luminous.

Again, if a disc perforated with a very small hole in the centre be held in a pencil of diverging light, those undulations which pass

directly through the aperture interfere with those passing obliquely at the edge of the disc and produce, at certain distances, a dark spot, at other distances increased brightness, on that part of the shadow which is opposite the aperture in the disc; so that light is supplanted by darkness, and darkness changed to light, by the discord or concord of the luminous waves.

Independently of all experiment, the first principles of undulatory optics lead to these experimental conclusions. The laws of rectilinear propagation of the luminous rays of reflection and refraction are not *absolute* laws. They arise from, and depend upon, a certain *relation* between the wave-lengths and the absolute dimensions of the objects by which the waves are intercepted, or reflected, or refracted.

Taking as illustrative the waves of *sound*, an *acoustic* shadow is only produced if the obstacle be many times greater than the length of the sound-waves. If the obstacle is reduced, the waves pass completely round it and there is no shadow, or if the notes are of higher pitch, so that the waves are reduced, a smaller obstacle than before will produce the shadow. In the case of light there are similar phenomena. If the obstacles to the passage of light be large in comparison with the wave-lengths, shadow effects result; but if the linear dimensions of objects are reduced to *small multiples* of the wave-lengths of light, all shadows or similar effects of solidity must cease. As in the instances given above, light and dark, or maxima and minima of luminosity, interchange their normal positions by harmony or disharmony of luminous waves.

It is then by means of diffraction phenomena that Abbe is enabled to explain the formation of the images of objects containing delicate striæ or structure, and requiring large apertures for their complete or approximate delineation. In the interests of this exposition we must here for a moment diverge on slightly personal grounds. It has been the good fortune of the present editor to obtain the courteous consent of Dr. Abbe to read and criticise the whole of the present chapter; however careful and earnest a student of such complex and original work as Dr. Abbe has done and recorded in German and English during the last twenty years or more, it is impossible to be wholly satisfied with the most sympathetic and sincere desire to give such work a popular form unless it should have been perused and accepted by the author. Dr. Abbe has read the entire chapter, and, with many generous words besides, relieves the editor in his consciousness of great responsibility by saying that he distinctly approves of the 'lively interest and care which (the present editor) has bestowed on the exposition of his (Dr. Abbe's) views,' and that he feels 'the greatest satisfaction in seeing (his) views represented . . . so extensively and intensively.'

But beyond this, an original worker like Dr. Abbe would almost inevitably find, in the course of years, reason for slight verbal and other more serious modifications of his inferences, explanations, and views; and the Editor has great satisfaction in being able to put these modifications where they occur, with the approval of Dr. Abbe.

In the expositions of Dr. Abbe's views on the diffraction theory

of microscopic vision given up to this time, it has been usual to state that he held and taught that the microscopic image consists of *two superimposed images*, each having a distinct character as well as a different origin, and capable of being separated and examined apart from each other. The one called the 'absorption image' is a similitude of the object itself, an image of the main outlines of the larger parts; but by the *other* image all *minute* structures, striation, and delicate complexity of detail *whose elements lie so close together as to occasion diffraction phenomena* can alone be formed, because these *could* not be geometrically imaged. So that in case of an object with lines closer than the $\frac{1}{25000}$ of an inch apart, the image seen by the eye is formed, not simply by the central dioptric beam, but by the joint action of that and the superimposed diffraction images, and their exact union in the upper focal plane of the objective.

The first of these was held to be a *negative* image, representing geometrically the constituent parts of the object; but the second was considered a *positive* image because it delineates structure, the parts of which appear self-luminous on account of the diffraction phenomena which they cause. It was this 'diffraction image' that was said to be the instrument of what has so long been known as the 'resolving' power of lenses.

But Dr. Abbe, with the full light of further investigation and experience, does not hesitate to modify this explanation. He says: 'I no longer maintain in principle the distinction between the "absorption image" (or direct dioptrical image) and the "diffraction image," nor do I hold that the microscopical image of an object consists of two superimposed images of *different origin* or different mode of production.

'This distinction, which, in fact, I made in my first paper of 1873, arose from the limited experimental character of my first researches and the want of a more exhaustive theoretical consideration at that period. I was not then able to observe in the microscope the diffraction effect produced by relatively coarse objects because my experiments were not made with objectives of sufficiently long focus; hence it appeared that coarse objects (or the *outlines* of objects containing fine structural details) were depicted by the directly transmitted beam of light solely, without the co-operation of diffracted light.

'My views on this subject have undergone important modifications. Theoretical considerations have led me to the conclusion that there must always be the *same* conditions of the delineation *as long as the objects are depicted by means of transmitted or reflected light*, whether the objects are of coarse or very fine structure. Further experiments with a large microscope, having an objective of about twelve inches focal length, have enabled me to actually observe the diffraction effect and its influence on the image, viewing gratings of not more than forty lines per inch.[1]

[1] Diffraction effects may be observed without a microscope: they can be easily demonstrated by observing a lamp-flame through a linen pocket-handkerchief or a fine gauze wire blind. This can be done readily by placing the eye close to the linen or wire.

'My present views may be thus expressed: With coarse objects the diffracted (bent off) rays belonging to an incident ray or pencil are *all* confined within *a very narrow angular space around that incident ray*, and do not appear separated from this except with objectives of very long focus. The *whole* of such a narrow diffraction pencil is consequently always admitted to the objective *together* with the direct (incident) beam, whatever may be the direction of incidence, axial or oblique. According to the proposition of p. 72 (1) the image is in this case strictly similar to the object, i.e. the effect is the same as if we had a direct delineation by the incident cones of light alone, and as if the image did not depend at all upon the diffractive action of the object.

'If we have a preparation like a diatom—a relatively coarse object, including fine structural details—or another preparation containing coarse elements and fine ones in juxtaposition, the total diffraction effect may be separated (theoretically and practically) into two parts: (1) that which depends on, or corresponds with, the coarse object (e.g. the outlines of the diatom) or to the coarse elements; and (2) that depending upon, or resulting from, the fine structural detail or the minute elements. The foregoing consideration applies to (1): this constituent part of the total diffraction pencil of the preparation which is admitted to the objective *completely*, independently of the limiting action of the lens opening, and hence the corresponding parts of the object (outlines &c.) are depicted as if there were a direct delineation, i.e. in perfect similarity—even with low apertures. Those diffracted rays within the whole diffraction pencil which are due to the *minute* elements are strongly deflected from the incident beams to which they belong.'[1]

According to the less or greater aperture of the objective and the axial or oblique incidence of the illuminating pencil or cone, *this* part of the total diffraction pencil will be subject to a more or less incomplete admission to the objective, and the corresponding image will therefore show the characteristic traces of the diffraction image, that is to say, change of aspect with different apertures and different illumination, dissimilarity to the real structure, and so forth. Thus we have *practically*, in most cases, a composition of the microscopical image, consisting of two superimposed images of different behaviour. But the difference is not to be considered one of *principle*, so far as the *production* of the image is concerned; for it depends solely upon the different angular expression of the diffraction fans resulting from coarse and from extremely fine elements.[2]

Resuming, then, our illustration of diffraction phenomena as applied to the theory of microscopic vision, we would point out that perhaps the most serviceable illustration for our purpose is a plate of glass ruled with fine parallel lines. If the flame of a candle be so placed that its image may be seen through the centre of the plate, this

[1] Letter from Dr. Abbe.

[2] Thus it appears that both the 'absorption image' and the 'diffraction image' are now held to be equally of diffraction origin; but, whilst a lens of small aperture would give the former with facility, it would be powerless to reveal the latter because of its limited capacity to gather in the strongly deflected diffraction rays due to the minuter elements.

central image will be clear and uncoloured, but it will be flanked on either side by a row of coloured spectra of the flame which are fainter and more dim as they recede from the centre : fig. 48 illustrates this.

A similar phenomenon may also be produced by dust scattered over a glass plate and by other objects whose structure contains very minute particles, the light suffering a characteristic change in passing through such objects, that change consisting in the breaking up of a parallel beam of light into a group of rays diverging with wide angle, and forming a regular series of maxima and minima of intensity of light due to difference of phase of vibration.

FIG. 48.

In the same way in the microscope the diffraction pencil originating from a beam incident upon, for instance, a diatom appears as a fan of isolated rays, decreasing in intensity as they are further removed from the direction of the incident beam transmitted through the structure, the interference of the primary waves giving a number of successive maxima of light with dark interspaces.

With daylight illumination if a diaphragm opening be interposed between the mirror and a plate of ruled lines placed upon the stage, the appearance shown in fig. 49 will be observed at the back of the objective on removing the eye-piece and looking down the tube of the microscope. The central circle is an image of the diaphragm opening produced by the direct, so-called non-diffracted rays, while those on either side are the diffraction images produced by the rays which are bent off from the incident pencil. In homogeneous light the central and lateral images agree in size and form, but in white light the diffracted images are radially drawn out with the outer edges red and the inner blue (the reverse of the ordinary spectrum), forming, in fact, regular spectra, the distance separating each of which varies inversely as the closeness of the lines, being, for instance, with the same objective twice as far apart when the lines are twice as close.



FIG. 49.

The formation of the microscopical image is explained by the fact that the rays collected at the back of the objective, depicting there the direct and spectral images of the source of light, reach in their further course the plane which is conjugate to the object, and give rise there to an interference phenomenon (owing to the connections of the undulations), this interference effect giving the ultimate image which is observed by the eye-piece, and which therefore depends essentially on the number and distribution of the diffracted beams which enter the objective.

It would exceed the limits and the object of this handbook to attempt a theoretical demonstration of the action of diffraction spectra in forming the images of fine structure and striation so as to afford 'resolution.' Those who desire to pursue this part of the

subject may do so most profitably by the study of the only book in our language that deals exhaustively with the theory of modern microscopical optics, viz. the translation of Naegeli and Schwendener's 'Microscope in Theory and Practice,' translated and placed within the reach of English microscopists by the joint labour of Mr. Frank Crisp and Mr. John Mayall, jun. The experimental proof of the diffraction theory of microscopic vision lies within the range of our



FIG. 50.—Diffraction grating.



FIG. 51.—Diffraction image at back of lens without eye-piece.

purpose, and the following experiments will suffice to show those who possess the instruments, and desire the evidence, that to the action of diffraction spectra we are indebted for microscopical delineation.

The first experiment shows that with, for instance, the central beam, or any one of the spectral beams alone, only the contour of the object is seen, the addition of at least one diffraction spectrum being essential to the visibility of the structure.

Fig. 50 shows the appearance presented by an object composed of wide and narrow lines ruled on glass when viewed in the ordinary way with the eye-piece in place, and fig. 51 the appearance presented at the back of the objective when the eye-piece is removed, the



FIG. 52.



FIG. 53.

spectra being ranged on either side of the central (white) image, and at right angles to the direction of the lines; in accordance with theory, they are farther apart for the fine lines than for the wide ones.

If now, by a diaphragm at the back of the objective, like fig. 52, we cover up all the diffraction-spectra, allowing only the direct rays to reach the image, the object will appear to be wholly deprived of

fine details, only the outline remaining, and every delineation of minute structure disappearing just as if the microscope had suddenly lost its optical power (see fig. 53).

This illustrates a case of the *obliteration* of structure by obstructing the passage of the diffraction-spectra to the eye-piece.

The second experiment shows how the appearance of fine structure may be *created* by manipulating the spectra.



FIG. 54.



FIG. 55.

If a diaphragm such as that shown in fig. 54 is placed at the back of the objective, so as to cut off each alternate one of the upper row of spectra in fig. 50, that row will obviously become identical with the lower one, and if the theory holds good, we should find the image of the upper lines identical with that of the lower. On replacing the eye-piece we see that it is so : the upper set of lines are doubled in number, a new line appearing in the centre of the space between each of the old (upper) ones, and upper and lower sets having become to all appearance identical (fig. 55).

In the same way, if we stop off all but the outer spectra, as in fig. 56, the lines are apparently again doubled, and are seen as in fig. 57.



FIG. 56.



FIG. 57.

A case of apparent creation of structure similar in principle to the foregoing, though more striking, is afforded by a network of squares, such as fig. 58, having sides *parallel* to the page, which gives the spectra shown in fig. 59, consisting of vertical rows for the horizontal lines and horizontal rows for the vertical ones. But it is readily seen that two diagonal rows of spectra exist at right

angles to the two diagonals of the squares, just as would arise from sets of lines in the direction of the diagonals, so that if the theory holds good we ought to find, on obstructing all the other spectra and



FIG. 58.



FIG. 59.

allowing only the diagonal ones to pass to the eye-piece, that the vertical and horizontal lines have disappeared, and two new sets of lines at *right angles to the diagonals* in their place.



FIG. 60.



FIG. 61.

On inserting the diaphragm, fig. 60, and replacing the eye-piece, we find, in the place of the old network, the one shown in fig. 61,



FIG. 62.



FIG. 63.

the squares being, however, smaller in the proportion of $1 : \sqrt{2}$, as they should be in exact accordance with theory.

An object such as *Pleurosigma angulatum*, which gives six dif-

fraction spectra arranged as in fig. 62, should, according to theor show markings in a hexagonal arrangement. For there will be o set of lines at right angles to *b a e*, another set at right angles *c a f*, and a third at right angles to *g a d*. These three sets of lin will obviously produce the appearance shown in fig. 63.

A great variety of other appearances may be produced with th same arrangement of spectra. Any two adjacent spectra with t central beam (as *b c a*) will form equilateral triangles and gi hexagonal markings. Or by stopping off all but *g c e* (or *b d f*) again have the spectra in the form of equilateral triangles; but they are now further apart, the sides of the triangles in the t cases being as $\sqrt{3}:1$, the hexagons will be smaller and three tim as numerous. Their sides will also be arranged at a different ang to those of the first set. The hexagons may also be entire obliterated by admitting only the spectra *g c* or *g f* or *b f*, &c. whe new lines will appear parallel at right angles or obliquely incline to the median line.

By varying the combinations of the spectra, therefore, differe figures of varying size and positions are produced, all of which cann of course represent the true structure.

In practice, indeed, it has been proved that if the position an relative intensity of the spectra, as found in any particular case, given, what the resultant image will be can be reached by mathem tical calculations wholly, and with an exactness that may even some extent transcend the results of previous observation on t actual image of the object whose spectra formed the mathematician data.

If *P. angulatum* be illuminated by central light transmitte from an achromatic condenser, and examined by means of a hom geneous lens of large aperture, Mr. Stephenson points out[1] th under ordinary conditions it would show, on withdrawing the ey piece and looking down the tube, one bright central light from t lamp with six equidistant surrounding diffraction spectra, produce by the lines ('if, indeed, lines they be') in the object itself. But l a stop made of black paper, which *entirely* excludes the central bea of light, be placed at the back of the objective and close to the po terior lens; in the stop let six marginal openings be made throug which the diffraction spectra may pass. On examining the image w find that in lieu of the ordinary hexagonal markings the val appears of a beautiful blue colour on a black ground, and cover with circular spots, clearly defined, and admitting of the use of de eye-pieces.

This is precisely what we learn from Abbe that the diffracti theory involves. In support of this, the philosophical faculty of t University of Jena had proposed as a question to the mathematic students the effect produced in the microscope by these interferen phenomena. One problem was that of the appearance produced six equidistant spectra in a circle; they correspond precisely wi the spectra of *P. angulatum*, as accessible to us with our prese numerical aperture; and the diagram of the diffraction image, d

[1] *Journ. R.M.S.* vol. i. 1878, p. 186.

duced from theory, of what spectra of the given position and intensity of the proposed data should give is seen in fig. 64. But what seems quite as much to the purpose is, that Dr. Zeiss has produced a fine photograph of *P. angulatum*, given in Plate X., where it will be seen that the details shown in fig. 64 appear.

Let it be clearly understood that this does not pretend to be an interpretation of the markings of the diatom; it is only held by Abbe to be an accurate indication by calculation of what image the given diffraction spectra should produce. An optical glass and media for 'mounting' and 'immersion' of immensely greater refractive and dispersive indices—at present wholly inaccessible to us—must, he contends, be found and employed before *all* the diffraction spectra of *P. angulatum* could be admitted to form its absolute and



FIG. 64.

complete 'diffraction image'; but from such spectra as the objective employed can admit, it is maintained by Abbe that the mathematician can accurately show what the image will be. In the case of *P. angulatum* theory indicated the *optical, but not necessarily the structural* existence[1] of smaller markings, shown in fig. 64, between the circular spots. These had not been before *seen* by observers; and the mathematician who made the calculation (Dr. Eichhorn) had never seen the diatom under the microscope; but when Mr. Stephenson re-examined the object—stopping out the central beam as above described and allowing the six spectra only to pass—he saw the small markings, and showed them at a meeting of the Royal Microscopical Society to many experts who were there. They were small and faint, and no doubt purely optical; and, we learn from experiment, may readily escape observation; but by careful investigation they

[1] *Conf.* Abbe's recent note, pp. 72 *et seq.*

are as present to the observer as they are capable of being demonstrated by calculation to the mathematician.

Clearly, then, on these assumptions and with all other considerations put aside, our finest homogeneous objectives of greatest aperture inevitably fail to reveal to us the real structure of the finer kinds of diatom valves. We learn that *dissimilar* structures will give *identical microscopical images* when the *difference* of their diffractive effect is removed, and conversely *similar structures* may give *dissimilar images* when their diffractive images are made dissimilar. A purely dioptric image answers point for point to the object on the stage, and therefore enables a safe inference to be drawn as to the true nature of that object; but the diffraction or interference images of minute structure stand in no direct relation to the nature of the object, and are not of necessity conformable to it. As Dr. Abbe has already insisted, minute structural details are not imaged by the microscope geometrically or dioptrically, and cannot be interpreted as *images of material forms*, but only as *signs* of material differences of composition of the particles composing the object, so that nothing more can safely be inferred from the image as presented to the eye than the presence in the object of such structural peculiarities as will produce the specific diffraction phenomena on which the images depend.[1]

It follows, therefore, that the larger the number of diffracted rays admitted into the objective *the greater is the similarity between the image and the object.* But carefully observe—

(1) *Perfect similarity* between these depends always on the admission to, and utilisation by, the optical combination of *the whole* of the diffracted rays which the structure is competent to emit.

For the same reason the diffraction fan of *isolated corpuscles* or *flagella* in a clear field must be exactly identical to that of equal sized holes or slits of equal shape in a dark background, and theory shows that there must be a continuous and nearly uniform dissipation of diffracted light over the whole hemisphere, provided the diameter of the object is a small fraction of the wave-length of light; and this would be so even in a medium of highest known refractive index. *Such isolated objects can be seen, however minute they may be*; it is merely a question of contrast in the distribution of light, of good definition in the objective, and of sensibility of the retina. The diffraction theory does not put a limit to *visibility* with microscopic objectives; it simply proves, in theory and practice, what is the limit of visible *separation* in fine striation and structure.

In the visible flagellum of *Bacterium termo* only a fraction of a wave-length in diameter appears as of considerably increased diameter, even with a very wide aperture. The image seen is that of another thread, the composition of which theory can be employed to

[1] See Abbe's note, p. 65. But we cannot pass over in this connection the remarkable paper in the *Journ. Quekett Club*, ser. ii. vol. iv. on the 'Sub-stage Condenser,' by Mr. Nelson. His photo-micrographs illustrating the mutable diffraction effects of the 'small cone' of oblique illumination, as distinct from a 'solid central cone,' and the curious 'ghostly' diffraction images of the former, as distinct from the immutable diffraction images of the latter, deserve careful consideration. From p. 125 of the paper this matter is carefully discussed.

compute, which would give an exactly similar diffraction fan, but abruptly broken off at the limit of the aperture. Theory shows that a thread-shaped object which could yield such a particular diffraction effect must (without considering other differences) be *greater in breadth* than another one yielding the full continuous dissipation of light; in other words the actual thread, so inconceivably fine, belonging to the Bacterium has produced a 'diffraction effect' through the microscope, resulting in the appearance of a thread which is the 'diffraction image.' But this latter is greater in width than the actual thread or protoplasmic fibre would be could it be seen directly without the aid of diffraction.

(2) Whenever a *portion* of the total diffraction fan appertaining to a given structure is lost, the image will be more or less *incomplete and dissimilar* from the object; and in general the dissimilarity will be the greater the smaller the fraction of light admitted. With structures of every kind (regular and irregular) the image will lose more and more the indications of the minuter details, as the peripheral (more deflected) rays of the diffraction pencil are more and more excluded. The image then becomes that of a *different* structure, namely, of one the *whole of whose diffracted beams* would (if it physically existed) be represented by the *utilised* diffracted beams of the structure in question.

At this point it is suitable to point out that Dr. Abbe emphasises to the present editor the importance of interpreting the 'intercostal points' shown by Mr. Stephenson in *P. angulatum* (fig. 64) as not a revelation of *real* structure. 'The fact is that the image, which is obtained by stopping off the direct beam, will be *more dissimilar* from the real structure than the *ordinary* image. It has already been shown that the directly transmitted ray is a constituent and most essential part of the total diffraction pencil appertaining to the structure; it is the central *maximum* of this pencil. If this be stopped off a greater part of the total diffraction pencil is lost than otherwise, and the image, consequently, is a more incomplete one, and therefore more dissimilar than the ordinary image.

'*The interest of the experiment in question* is consequently confined to two points, viz.—

i. 'It is an exemplification of the general proposition that the *same* object affords different *images* if different *portions* of the total diffraction fan are admitted to the objective.

ii. 'The image in question shows to the observer what would be the *true aspect* of that structure which will split up an incident beam of light into six isolated maxima of second order of equal intensity, suppressing totally the (central) maximum of the first order, as fig. 65; a structure of such a particular and unusual diffraction effect is theoretically possible, although it may be probably impossible to realise it practically. Mr. Stephenson's experiment shows, in fact, the true projection of the hypothetical structure.

(3) 'As long as the elements of a structure are large multiples of the wave-length of light, the breaking up of the rays by diffraction is confined to smaller and smaller angles; that is, all diffracted rays of perceptible intensity will be comprised within a narrow cone

around the direction of the incident beam from which they originate. In such a case even small apertures are capable of admitting the *whole*. The images of such *coarse* objects will therefore be always perfectly similar to the object, and the result of the interference effect is the same as if there were no diffraction at all, and the object were a self-luminous one.

(4) 'When the elements of a structure are reduced in diameter to smaller and smaller multiples of the wave-length which corresponds to the medium in which the object is, the diffraction pencil originating from an incident beam has a wider and wider angular expansion (the diffracted rays are further apart); and when they are reduced to only a few wave-lengths, not even the hemisphere can embrace the *whole* diffraction effect which appertains to the structure. In this case the whole can only be obtained by shortening the wave-length, i.e. by increasing the refractive index of the surrounding medium to such a degree that the linear dimensions of the elements of the object become a large multiple of the *reduced* wave-length. With very minute structures, the diffraction fan which can be admitted in air, and even in water or balsam, is only a greater or less *central portion* of the whole possible diffraction fan corresponding to those structures, and which could be obtained if they were in a medium of much shorter wave-length. Under these circumstances no objective, however wide may be its aperture, can yield *a complete or strictly similar image*.'



FIG. 65.

It is at points of such extreme delicacy and moment as this that the diffraction hypothesis of Dr. Abbe is so liable to misapprehension and misinterpretation, and a further note from him relating to the *dissimilarity* of the image in the case of incomplete admission of the diffraction pencil will be of great value here.

i. 'In the case of regular *periodic* structures (i.e. equidistant striæ, rows of apertures, 'dots,' and so forth) the distance of the lines apart is, even with an incomplete admission of the diffracted light, always *depicted correctly*; that is to say, the number of the lines per inch is never changed, *provided* the direct beam (i.e. the central maximum of the diffraction fan) *is admitted to the objective and at least one of the next diffracted rays*, or, in other words, one of the next maxima of second order. The *range of dissimilarity*

ı this case confined to the proportion between the bright and the
ɛ interspaces of the striation and to the appearance of the con-
ɜ of the striæ.

'If not more than the said *two* rays of the total diffraction fan are
ıitted, the dark and the light intervals are *always* shown of
roximately *equal breadth*, even if the real proportion of both
rvals differs much from 1 : 1; and the dark and bright striæ show
ays *gradually* increasing and decreasing brightness; in other
ds, want of distinct contours.

'This phenomenon shows the typical picture of every regular
ıtion for the depiction of which not more than two diffraction
ı can be utilised. For example, *Amphipleura pellucida*, or any
r striation which is near to the limit of resolution for the optical
em in use, and, therefore, even with oblique light, brings only
diffracted beam into the objective.

ii. 'Whenever a structure gives rise to a diffraction fan of con-
rable angular extension, the observation with a central incident
n or axial light may lose a greater or smaller portion of the
le diffracted light if the angular expansion of the fan extends to
aperture of the objective in use. But oblique illumination *must*
ays involve a loss, and this loss is not confined to the external
ipheral) rays of the diffraction pencil (as is the case in central
t), but the portion *lost* will more and more extend to one full
: of the whole when the obliquity is gradually increased to the
ıost limit, so that the direct beam touches the edge of the aper-
:. It follows that the images which are obtained with *oblique*
t will always be incomplete and *not similar* to a geometrical
ection of the object; and generally (though not always) more dis-
ilar than those by central light in regard to the minuter details.

'Strictly similar images cannot be expected, except with a *central*
nination with a narrow incident pencil, because this is the
ssary condition for the possible admission of the whole of the
acted light.'

Let it be noted that these principles of the diffraction theory of
oscopical vision relate to structures of all kinds, whatever may
heir physical and geometrical composition. Irregular structures,
ted elements of any shape, equally produce diffraction effects,
rved either by transmitted or reflected light, and being either
sparent, semitransparent, or opaque.

The value of $a = n \sin u$ indicates the number of rays which
bjective can admit; the aperture equivalent measures the very
ıce of microscopical performance. It measures the degree in
h a given objective is competent to exhibit a true, complete
ıeation of structures of given minuteness, and conversely the
ortion of a in different objectives is the exact measure of the
rent *degree of minuteness* of structural details which they can
ı, either with perfect similarity of the image or with an equal
ee of incompleteness of the image, provided that the purely
trical conditions are the same.

'Resolving' power is thus a special function of aperture. The
; of visible separation in delicate structure and striation is

determined by the fact that no resolution can be effected unless least two diffraction pencils are admitted, and the admission of th we have seen is absolutely dependent on the aperture of the objecti

The rule given by Professor Abbe for determining the great number of lines per inch which can be resolved by oblique light w be found (taking any given colour as a basis) to be equal to *tw the number of undulations in an inch multiplied by the numeri aperture.*

To those who have studied this subject it will be seen that t 'numerical aperture' here takes the place of what was formerly t 'sine of half the angle of aperture'; and it has the effect of givi the proposition a broader generality. By using the 'sine of h the angle of aperture,' the proposition is only true with the additi that the number of undulations be calculated from the wave-leng within the special medium to which the angle of aperture relates.

In introducing the numerical aperture instead of the sine of t angle, the latter (the sine) is increased in the proportion of 1 : (n standing for the index of the medium), and that has the sa effect as increasing the other factor the number of undulations.

What the colour employed should be is only capable of individu determination, since the capacity for appreciating light varies wi different individuals.

If, for instance, we take ·43μ in the solar spectrum as bei sufficiently luminous for vision, we find the maximum—so far seeing is concerned—to be 118,000 to the inch (the object, in t case, being in air); but as the non-luminous chemical rays rema in the field after the departure of the visible spectrum, a phot graphic image of lines much closer together might be produced.



FIG. 66.

This important subject can scarcely be considered complete, e in outline, without a brief consideration, in their combined relati of apertures in excess of 180° in air and the special function t apertures possess.

1. Suppose any object composed of minute elements in reg arrangement, such as a diatom valve; and, to confine the consid tion to the most simple case, suppose it illuminated by a nar

axial pencil of incident rays. If this object is observed in air, the radiation from every point of the object is, in consequence of the diffraction effect, composed of an axial pencil S, fig. 66 (the direct continuation of the incident rays), and a number of bent-off pencils, S_1, S_2 . . . surrounding S.[1]

If, now, instead of air, the object is immersed in a medium of greater refractive index, n, it results from Fraunhofer's formula that the sine of the angle of deflection of the first, second, . . . bent-off



FIG. 67.

beam is *reduced* in the exact proportion of n, and the angle is reduced also—that is, the whole fan of the diffracted rays is *contracted* in comparison with its extension in air. Fig. 67 will represent the case of the same object in oil.

If now any dry objective (with a given angular semi-aperture u) is capable of gathering-in from air the first, or the first and second, diffraction beams on every side of the axial pencil, another objective with a more dense front medium of the refractive index, n, will be capable of admitting, from within the dense medium, exactly the *same* beams (no more and no less), if its *angular* semi-aperture, v, is *less* than u in the proportion :

$$\sin v : \sin u = 1 : n,$$

or

$$n \sin v = \sin u,$$

all other circumstances—object and illumination—remaining the same.

For example, a diatom for which the distance of the striæ is $0{\cdot}6\ \mu$, will give the *first* bent-off beam of green light ($\lambda = {\cdot}55\ \mu$) in *air* under an angle of 66·5°. This will be just admitted by a dry objective of 133° *angular* aperture. In *balsam* ($n = 1{\cdot}5$) the same pencil will be deflected by 37·5° only, and would be admitted, therefore, by an objective of not more than 75° balsam-angle. Again, if the distance of the lines should be greater, as $1{\cdot}2\ \mu$, the *second* deflected beam

[1] In figs. 66, 67, and 68 S_4 and S_6 are supposed to be identical with the surfaces, but are drawn at a slight inclination to them for the purpose of clearness in the diagrams.

would be emitted in *air* under an angle of 66·5°, but in *balsam* the *third* would attain the same obliquity. Whilst now the dry objective of 133° air-angle cannot admit more than the two first diffraction beams on each side of the axis, the immersion of 133° balsam-angle is capable of admitting from balsam three on each side under exactly the same illumination.[1]

It follows, therefore, that a balsam-angle of 75° denotes the same aperture as the larger air-angle of 133°, and a balsam-angle of 133° a much greater aperture than an air-angle of the same number of degrees, and in general two apertures of different objectives must be equal if the sines of the semi-angles are in the inverse ratio of the refractive index of the medium to which they relate—or, which is the same thing, if the product of the refractive index multiplied by sine of the angular semi-aperture ($n \sin u$) yields the same value for both, i.e. if they are of the same numerical aperture.

2. Suppose the same object to be observed by a dry objective of a given air-angle, at first in air uncovered, and then in balsam protected by a cover-glass. The first case would be represented by



FIG. 68.

fig. 66, and the second by fig. 68. As we have seen, the group of diffracted beams from the object in balsam is *contracted* in comparison to that in air in the ratio of the refractive index. But

[1] The following are the actual angles represented in the diagrams, viz.:

(Striæ = 2·2 μ, wave-length λ = ·55 μ, medium air n = 1.)

S_1 = 14° 30′
S_2 = 30° 0′
S_3 = 48° 36′
S_4 = 90° 0′.

(Striæ = 2·2 μ, wave-length λ = ·55 μ, medium balsam n = 1·5.)

S_1 = 9° 36′

rding to the law of refraction, this group, on passing to *air* by plane surface of the covering-glass, is *spread out*—the sines of ngles being compared—in the ratio of the same refractive index. sequently the various diffraction pencils, the first, second, . . . very side, after their *transmission into air*, have exactly the e obliquity which they have in the case of direct *emission in* from an uncovered object.

If now any dry objective of, say, 133° air-angle is capable of itting a certain number of these pencils from the uncovered ct, it will admit exactly the *same* pencils from the balsam-nted object. The contracted cone in balsam of 75° angular rture embraces all rays which are emitted in air within a cone 33°.

The aperture of an objective is not, therefore, cut down by nting the object in a dense medium, for no ray which could be en in from the uncovered object is lost by the balsam-mounting.

3. A comparison of figs. 66, 67, and 68 will show that a cone of within the balsam medium embraces *all* the diffracted rays ich are emitted from the object in air or transmitted from balsam ir. This, however, is not the totality of rays which are emitted the balsam. The formula of Fraunhofer shows that the number the emitted beams is *greater* in balsam than in air in the same io as the refractive index.

A structure the distance of whose elements equals 2·2 μ emits in sam *six* distinct beams on each side of the direct beam, but in air y *four* (see figs. 66, 67, and 68); the fifth and sixth are completely t in air. A dry objective of an angular aperture closely approaching)° will not even take in the fourth deflected beam, as this is de-ted at an angle of 90°. But any immersion-glass of a balsam-gle slightly exceeding 82° will take in the fourth, and if the sam-angle should exceed 112° it will take in the fifth beam also, vided the object is in balsam, and in optical continuity with the nt of the lens.

Thus, again, it is seen (as was before shown by the purely dioptric thod) that an immersion objective of balsam-angle exceeding 82° a wider aperture than any dry objective of maximum angle can e, for it is capable of gathering in from objects in a dense medium s which are not accessible to an air-angle of 180°.

It is, then, by the above facts and reasoning, placed beyond all ute—

1. That a wide-angled 'immersion' or 'homogeneous' objective esses an aperture in excess of 180° 'angular aperture' in air;

2. That the great value of this—always manifest practically—is y accounted for and explained by the *diffraction* theory of micro-ic vision; and

3. That 'dry' objectives, so far as regards the perfect delineation *ery minute structures*, can only be considered as representing an erfect phase of construction. When made by the best hands, n every precaution and care employed to secure the best possible rections, their defects do not lie in the direction of the presen-on of false or even partially erroneous and distorted images.

Their defects are their inevitable incapacity to open up details in structure that can be disclosed with relative ease by the *inclusion into* an oil immersion, and especially an 'apochromatic' objective of great aperture, of the all-revealing diffraction beams *excluded* by the dry lens of equivalent power.

With dry objectives splendid results have been attained both in low and high power work; but all the latter is being advanced upon by revision with lenses of greater aperture in a striking manner. For twenty years we have been urging our best English microscope makers to enlarge the 'angle' of our objectives, and employing them from a $\frac{1}{4}$-inch to a $\frac{1}{10}$-inch focus. We have seen them advance from dry to water immersion, and from this to oil; from $\frac{1}{25}$-inch, a $\frac{1}{35}$-inch, and a $\frac{1}{50}$-inch of N.A. 0·95 each, and respectively to water immersions of N.A. 1·04 and then to 'oil immersions' or homogeneous lenses of N.A. 1·38 for the $\frac{1}{25}$-inch and $\frac{1}{50}$-inch respectively, and ultimately by a $\frac{1}{20}$-inch with N.A. of 1·50; and from that we have progressed to the apochromatic objectives with compensating eye-pieces.

Now the objectives with which the earlier work done by the present editor and his colleague, Dr. Drysdale, was effected—to which allusion is made only as being the instance with which we have most practical familiarity—are still in our possession; what was revealed by them fifteen, twelve, or ten years ago we can exactly repeat to-day; and in the general features of the work—in the broad characteristics of the life histories of the saprophytic organisms, minute as they are, revision with objectives of N.A. 1·50 and other lenses of the best English and German makers, reveals no positive error, even in the *minutest* of the details then discovered and delineated. But the later lenses of great aperture and beautiful corrections have opened up *structure absolutely invisible before.*

Thus, for example, a minute oval organism from the $\frac{1}{3000}$th to the $\frac{1}{3000}$th of an inch in long diameter was known to possess a distinct nucleus; the long diameter of this was from the $\frac{1}{10}$th to the $\frac{1}{15}$th of the diameter of the whole body of the organism. In the observations of ten to fifteen years since the cyclic changes of the entire organism were clearly visible and constantly observed; but of the *nucleus* nothing could be made out save that it *appeared* to share the changes in self-division and genetic reproduction, *initiated* by the organism as a whole. But by lenses of N.A. 1·50 and the finest apochromatic objectives of Zeiss, especially a most beautifully corrected 3 mm. and 2 mm., structure of a remarkable kind has been demonstrated in the nucleus, and it has been shown that the *initiation* of the great cyclic changes takes place in the *nucleus*, and is then shared in by the organism as a whole. In short, we have discovered as much concerning the 'inaccessible' nucleus—which may be not more than, say, a twelfth of the long diameter of the whole organism—by means of *lower powers*, but *greater apertures*, as we were able to find concerning the complete body of the saprophyte with dry objectives.

But in spite of these facts there is a certain class of even high power work in biology from which the dry lens can never be dis-

missed. It must always be an indispensable instrument in a large part of the work done in the study of the life history of active living organisms; and whatever accessories in research on such subjects be employed, the main path of accurate and well correlated discovery must be by ultimate and consecutive reference to the changes of the *living* organism. But we cannot with any certainty do this with either a water immersion or a homogeneous objective. With an active organism under investigation, we desire, as far as practicable, to limit the area of its excursions; a cover-glass of not more than four-tenths or a quarter of an inch in diameter is large enough when objectives from a $\frac{1}{20}$ inch to a $\frac{1}{50}$ inch are used, or when the recent 2 mm. objective with 27 eye-piece is employed. To have oil or water on the top of the cover, between it and the front lens of the objective combination, is, with almost inevitable certainty, sooner or later, in following the object with counter movements of the stage, to reach the edge of the cover, and cause the oil or water above to mingle by capillarity with the minute drop of fluid under observation, and thus to involve the whole in catastrophe.

To do the main work of studying consecutively the life history of unknown organisms, dry objectives will and must be used; but in all cases such work must be supplemented by the use of objectives of great aperture. The details and relations of minute structure must be studied in one field, and their general origin and sequences in another. The latter will be 'continuous,' the former will be employed as necessity indicates. The diffraction theory of microscopic vision does not invalidate, but in reality, under definable conditions, directs the employment of 'narrow' apertures. All depends on the minuteness of microscopic detail. The law has been enunciated above: the minuter the dimensions of the structural elements, the wider *must be* the aperture: the larger the details of ultimate structure, the narrower the aperture that will *suffice*. This is true in regard to objects of every kind; there is no variation in the conditions of microscopical delineation.

The men engaged in microscopical research have different aims, nay, the same worker at different times differs in the object pursued. 'Ultimate structure' is not the *one* consideration of the microscopist: he often, as indicated above, has to take a comprehensive view of the whole object or objects of his research, apart from the most complex and delicate details.

It is folly to suppose that because great apertures have been proved theoretically and practically to be able to open out minute structure so perfectly, therefore there is no *raison d'être* for small apertures. Low amplification cannot render distinctly visible details beyond a certain limit of minuteness, and wide apertures cannot be utilised unless there is a concurrent linear amplification of the image which is competent to exhibit to the eye the smallest dimensions which are by optical law *within the reach and grasp* of such an aperture.

In the same way great amplification will be useless if we have small apertures which delineate details of dimensions only capable of being distinctly seen in an image of much lower amplification.

It will be 'empty amplification,' because there is nothing in the image which requires so much power for distinct recognition. If the *power* be deficient, aperture will not avail; if the aperture be wanting, nothing is gained by high power. If the angular aperture of the microscope is such that the delineation of fine lines, whose interspaces are one *micron*,[1] is just possible, it is fruitless labour to increase the amplification beyond what we know to be sufficient for their observation. We potentially differentiate what we are powerless to see.

Thus it may be inferred from the diffraction theory, as such, that wide aperture should accompany high amplification, and moderate aperture be the accompaniment of low or moderate amplification.

The circumstances on which what has been called 'penetration' in objectives is dependent will be shortly considered;[2] it may be stated here that theory and experience alike show that 'penetration' is reduced with increasing aperture under one and the same amplification. As we have indicated, there are many subjects of study and research presented to the biologist for which he needs as much 'penetration' as possible. This is always the case where the recognition of solid forms—as the infusoria, for example—is important. A fair vision of different planes at once is required.[3] Indeed the greater part of all morphological work is of this kind; here, then, in the words of Abbe, 'a proper economy of aperture is of equal importance with economy of power.'[4]

Whenever the depth of the object or objects under observation is not very restricted, and for the purposes of observation we require depth dimension, low and moderate powers must be used; 'and no greater aperture should therefore be used than is required for the effectiveness of these powers—an excess in such a case is a real damage.'[5]

Moreover, in biological work—constant application of the instrument to varied objects—lenses of moderate aperture and suitable power facilitate certainty of action and conserve labour. Increase of aperture involves a diminished working distance in the objective, and it is inseparable from a rapid increase of sensibility of the objectives for slight deviations from the conditions of perfect correction. If it be not *necessary* to encounter the possible difficulties these things involve, to do so is to lose valuable moments. These difficulties, of course, are diminished by the use of homogeneous, and especially apochromatic objectives, but even with these they are not, in practice, done away where the best results are sought.

Employ the full aperture suitable to the power used. This is the practical maxim taught in effect by the Abbe theory of microscopic vision.

It has been suggested that all objectives be made of relatively wide apertures, and that they be 'stopped down' by diaphragms when the work of 'lower apertures' has to be done. But this is

[1] A *micron* is $\mu = \frac{1}{1000}$ mm. *Vide Journ. R.M.S.* 1888, pp. 502 and 526; and *Nature*, vol. xxxviii. pp. 221, 244.

[2] See p. 83.

[3] Abbe's explanation of the reason of the non-stereoscopic perception of these is given (see pp. 93 *et seq.*).

[4] 'The Relation of Aperture to Power,' *Journ. R.M.S.* series ii. vol. ii. p. 304.

[5] *Ibid.*

not a suggestion that commends itself to the working biologist. If there were no other defects in such a method, the fact that the working distance remains unaltered would be fatal; and we may safely adopt the statement of Abbe,[1] that 'scientific work with the microscope will always require, not only high power objectives of the widest attainable apertures, but also carefully finished lower powers of small and very moderate apertures.'

We complete this section with a *table of numerical apertures*, which will be found on the following page. As already stated, the resolving powers are exactly proportional to the numerical apertures, and the expressions for this latter will allow the resolving power of different objectives to be compared, not only if the medium be the same in each, but also if it be different.

The first column gives the numerical apertures from ·40 to 1·52. The second, third, and fourth, the air-, water-, and oil- (or balsam-) angles of aperture, corresponding to every ·02 of N.A. from 47° air-angle to 180° balsam-angle. The theoretical resolving power in lines to the inch is shown in the sixth column; the line E of the spectrum about the middle of the green ($\lambda = 0{\cdot}5269\mu$), being taken.

The column giving 'illuminating power,' we have already seen, is of less importance; while it must be borne in mind in using the column of 'penetrating power' that several data besides $\frac{1}{a}$ go to make up the total depth of vision with the microscope.

Penetrating Power in Objectives.—Intelligibility and sequence, more than custom, suggest the consideration of this subject at this point. The true meaning and real value of 'depth of focus,' or what is known as 'penetrating power,' follows logically upon the above considerations.

That quality in an objective which was supposed to endow it with a capacity of visual range in a vertical direction, that is, in the direction of the axis of vision, has been called 'penetration,' it being supposed that by this 'property' parts of the object not in the focal plane could be specially presented, so as to enable their perspective and other relations with what lies precisely in the focal plane to be clearly traced out.

Concerning the manner in which this quality of the objective operated, there have been most diverse opinions; indeed, the whole matter was involved in obscurity. The remarkable insight and learning of Professor Abbe have, however, found for this important subject a sound scientific basis.

The delineation of *solid* objects by a system of lenses is, by virtue of the most general laws of optical delineation, subject to a peculiar disproportion in amplification. The linear amplification of the *depth*-dimension is, when both the object and the image are in the same medium (air), found to be always equal to the *square* of the linear amplification of the dimensions at right angles to the optical axis; but if the object be in a more highly refracting medium than air, it is equal to this square divided by the refractive index of the medium. In proportion to the lateral amplification there is

[1] 'The Relation of Aperture to Power,' *Journ. R.M.S.* series ii. vol. ii. p. 809.

I.—NUMERICAL APERTURE TABLE.

—	Numerical Aperture (N.A. = $n \sin u$)	Corresponding Angle ($2u$) for: Air ($n=1{\cdot}00$)	Water ($n=1{\cdot}33$)	Homogeneous Immersion ($n=1{\cdot}52$)	Limit of Resolving Power, in Lines to an Inch: White Light. ($\lambda=0{\cdot}5269\ \mu$, Line E.)	Mono-chromatic (Blue) Light. ($\lambda=0{\cdot}4861\ \mu$, Line F.)	Photo-graphy. ($\lambda=0{\cdot}4000\ \mu$, near Line h)	Illuminating Power (N.A.)²	Penetrating Power $\left(\frac{1}{\text{N.A.}}\right)$
Maximum aperture of homogeneous immersion with crown glass covers . . . . →	**1·52**	—	—	180° 0′	146,543	158,845	193,037	2·310	·658
Powell and Lealand's lenses constructed with the Abbe-Schott optical glass $\frac{1}{12}$-inch, $\frac{1}{6}$-inch, and $\frac{1}{25}$-inch objectives . . . . →	**1·51**	—	—	166° 51′	145,579	157,800	191,767	2·280	·662
Powell and Lealand's $\frac{1}{12}$ inch homogeneous objective . . . . . →	**1·50**	—	—	161° 23′	144,615	156,755	190.497	2·250	·667
	1·49	—	—	157° 12′	143,651	155,710	189,227	2·220	·671
	1·48	—	—	153° 39′	142,687	154,665	187,957	2·190	·676
	1·47	—	—	150° 32′	141,723	153,620	186,687	2·161	·680
	1·46	—	—	147° 42′	140,759	152,575	185,417	2·132	·685
	1·45	—	—	145° 6′	139,795	151,530	184,147	2·103	·690
	1·44	—	—	142° 39′	138,830	150,485	182,877	2·074	·694
	1·43	—	—	140° 22′	137,866	149,440	181,607	2·045	·699
Zeiss' homogeneous and apochromatic objectives; Powell and Lealand's apochromatic $\frac{1}{12}$ inch objective . . . . . →	**1·42**	—	—	138° 12′	136,902	148,395	180,337	2·016	·704
	1·41	—	—	136° 8′	135,938	147,350	179,067	1·988	·709
Powell and Lealand's $\frac{1}{50}$ inch and $\frac{1}{25}$ inch homogeneous objectives . . . . . →	**1·40**	—	—	134° 10′	134,974	146,305	177,797	1·960	·714
	1·39	—	—	132° 16′	134,010	145,260	176,527	1·932	·719
	1·38	—	—	130° 26′	133,046	144,215	175,257	1·904	·725
	1·37	—	—	128° 40′	132,082	143,170	173,987	1·877	·729
	1·36	—	—	126° 58′	131,118	142,125	172,717	1·850	·735
	1·35	—	—	125° 18′	130,154	141,080	171,447	1·823	·741
	1·34	—	—	123° 40′	129,189	140,035	170,177	1·796	·746
Maximum aperture for water immersion . →	**1·33**	—	180° 0′	122° 6′	128,225	138,989	168,907	1·769	·752
	1·32	—	165° 56′	120° 33′	127,261	137,944	167,637	1·742	·758
	1·31	—	160° 6′	119° 3′	126,297	136,899	166,367	1·716	·763
	1·30	—	155° 38′	117° 35′	125,333	135,854	165,097	1·690	·769
	1·29	—	151° 50′	116° 8′	124,369	134,809	163,827	1·664	·775
	1·28	—	148° 42′	114° 44′	123,405	133,764	162,557	1·638	·781
	[illegible]	—	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

Illumination ... ... 19th band by objectives of N.A. 1·4 achromatic . . . . . →	**1·19**	—	126° 58′	103° 2′	114,728	124,359	151,128	1·416	·840
	1·18	—	125° 3′	101° 50′	113,764	123,314	149,857	1·392	·847
	1·17	—	123° 13′	100° 38′	112,799	122,269	148,588	1·369	·855
	1·16	—	121° 26′	99° 29′	111,835	121,224	147,317	1·346	·862
	1·15	—	119° 41′	98° 20′	110,872	120,179	146,048	1·323	·870
	1·14	—	118° 0′	97° 11′	109,907	119,134	144,777	1·300	·877
	1·13	—	116° 20′	96° 2′	108,943	118,089	143,508	1·277	·885
	1·12	—	114° 44′	94° 55′	107,979	117,044	142,237	1·254	·893
	1·11	—	113° 9′	93° 47′	107,015	115,999	140,968	1·232	·901
	1·10	—	111° 36′	92° 43′	106,051	114,954	139,698	1·210	·909
	1·09	—	110° 5′	91° 38′	105,087	113,909	138,428	1·188	·917
	1·08	—	108° 36′	90° 34′	104,123	112,864	137,158	1·166	·926
	1·07	—	107° 8′	89° 30′	103,159	111,819	135,888	1·145	·935
	1·06	—	105° 42′	88° 27′	102,195	110,774	134,618	1·124	·943
	1·05	—	104° 16′	87° 24′	101,231	109,729	133,348	1·103	·952
	1·04	—	102° 53′	86° 21′	100,266	108,684	132,078	1·082	·962
	1·03	—	101° 30′	85° 19′	99,302	107,639	130,808	1·061	·971
	1·02	—	100° 10′	84° 18′	98,338	106,593	129,538	1·040	·980
	1·01	—	98° 50′	83° 17′	97,374	105,548	128,268	1·020	·990
Maximum aperture of 'Dry' or air objectives →	**1·00**	180° 0′	97° 31′	82° 17′	96,410	104,503	126,998	1·000	1·000
	0·99	163° 48′	96° 12′	81° 17′	95,446	103,458	125,728	·980	1·010
	0·98	157° 2′	94° 56′	80° 17′	94,482	102,413	124,458	·960	1·020
Limit of resolution of *Amphipleura pellucida*, 92,000 to 95,000 lines to the inch . . →	**0·97**	151° 52′	93° 40′	79° 18′	93,518	101,368	123,188	·941	1·031
	0·96	147° 29′	92° 24′	78° 20′	92,554	100,323	121,918	·922	1·042
In actual practice this diatom in a medium of 2·4 refractive index has been resolved to 93,000 striæ per inch. The transverse striæ may be easily resolved, and are just discoverable with a new apochromatic dry ½ N.A. 1·0 by Powell and Lealand.	**0·95**	143° 36′	91° 10′	77° 22′	91,590	99,278	120,648	·903	1·053
	0·94	140° 6′	89° 56′	76° 24′	90,625	98,233	119,378	·884	1·064
	0·93	136° 52′	88° 44′	75° 27′	89,661	97,188	118,108	·865	1·075
	0·92	133° 51′	87° 32′	74° 30′	88,697	96,143	116,838	·846	1·087
	0·91	131° 0′	86° 20′	73° 33′	87,733	95,098	115,568	·828	1·099
	0·90	128° 19′	85° 10′	72° 36′	86,769	94,053	114,298	·810	1·111
Limit of resolution of the form of *Navicula rhomboides* known as *Frustulia saxonica* and *N. crassinervis*, 78,000 to 87,000 lines to the inch. In *N. crassinervis* transverse striæ 80,500 to the inch have been seen with Powell and Lealand's dry $\frac{1}{12}$ N.A. 1·0 →	**0·89**	125° 45′	84° 0′	71° 40′	85,805	93,008	113,028	·792	1·124
	0·88	123° 17′	82° 51′	70° 44′	84,841	91,963	111,758	·774	1·136
	0·87	120° 55′	81° 42′	69° 49′	83,877	90,918	110,488	·757	1·149
	0·86	118° 38′	80° 34′	68° 54′	82,913	89,873	109,218	·740	1·163
	0·85	116° 25′	79° 37′	68° 0′	81,949	88,828	107,948	·723	1·176
	0·84	114° 17′	78° 20′	67° 6′	80,984	87,783	106,678	·706	1·190

NUMERICAL APERTURE TABLE—*continued.*

	Numerical Aperture (N.A. = $n \sin u$)	Corresponding Angle ($2u$) for Air (n=1·00)	Water (n=1·33)	Homogeneous Immersion (n=1·52)	Limit of Resolving Power in Lines to an Inch: White Light. (λ=0·5269 μ, Line E.)	Monochromatic (Blue) Light. (λ=0·4861 μ, Line F.)	Photography. (λ=0·4000 μ, near Line h.)	Illuminating Power (N.A.)²	Penetrating Power $\left(\frac{1}{\text{N.A.}}\right)$
Resolution of *Colletonema vulgare* in balsam. obj. apochr. $\frac{1}{4}$ ·95 N.A. and *Surirella gemma* (dry) into checks . . . . . →	**0·83**	112° 12′	77° 14′	66° 12′	80,020	86,738	105,408	·689	1·205
	0·82	110° 10′	76° 8′	65° 18′	79,056	85,693	104,138	·672	1·220
	0·81	108° 10′	75° 3′	64° 24′	78,092	84,648	102,868	·656	1·235
	0·80	106° 16′	73° 58′	63° 31′	77,128	83,603	101,598	·640	1·250
	0·79	104° 22′	72° 53′	62° 38′	76,164	82,558	100,328	·624	1·266
	0·78	102° 31′	71° 49′	61° 45′	75,200	81,513	99,058	·608	1·282
	0·77	100° 42′	70° 45′	60° 52′	74,236	80,468	97,788	·593	1·299
	0·76	98° 56′	69° 42′	60° 0′	73,272	79,423	96,518	·578	1·316
	0·75	97° 11′	68° 40′	59° 8′	72,308	78,378	95,248	·563	1·333
	0·74	95° 28′	67° 37′	58° 16′	71,343	77,333	93,979	·548	1·351
	0·73	93° 46′	66° 34′	57° 24′	70,379	76,288	92,709	·533	1·370
	0·72	92° 6′	65° 32′	56° 32′	69,415	75,242	91,439	·518	1·389
Resolution of *Surirella gemma*, 64,000 to 69,000 lines per inch . . . . . →	**0·71**	90° 28′	64° 32′	55° 41′	68,451	74,197	90,169	·504	1·408
	0·70	88° 51′	63° 31′	54° 50′	67,487	73,152	88,899	·490	1·429
	0·69	87° 16′	62° 30′	53° 59′	66,523	72,107	87,629	·476	1·449
	0·68	85° 41′	61° 30′	53° 9′	65,559	71,062	86,359	·462	1·471
	0·67	84° 8′	60° 30′	52° 18′	64,595	70,017	85,089	·449	1·493
	0·66	82° 36′	59° 30′	51° 28′	63,631	68,972	83,819	·436	1·515
	0·65	81° 6′	58° 30′	50° 38′	62,667	67,927	82,549	·423	1·538
Resolution of *N. rhomboides* from Cherryfield in balsam by apochr. $\frac{1}{2}$ in N.A. ·65 . →	**0·64**	79° 36′	57° 31′	49° 48′	61,702	66,882	81,279	·410	1·562
	0·63	78° 6′	56° 32′	48° 58′	60,738	65,837	80,009	·397	1·587
	0·62	76° 38′	55° 34′	48° 9′	59,774	64,792	78,739	·384	1·613
Resolution of *Pleurosigma fasciola*, 55,000 to 58,000 lines per inch . . . . →	**0·61**	75° 10′	54° 36′	47° 19′	58,810	63,747	77,469	·372	1·639
	0·60	73° 44′	53° 38′	46° 30′	57,846	62,702	76,199	·360	1·667
	0·59	72° 18′	52° 40′	45° 40′	56,881	61,657	74,929	·348	1·695
	0·58	70° 54′	51° 42′	44° 51′	55,918	60,612	73,659	·336	1·724
	0·57	69° 30′	50° 45′	44° 2′	54,954	59,567	72,389	·325	1·754
	0·56	68° 6′	49° 48′	43° 14′	53,990	58,522	71,119	·314	1·786

	0·42	49° 40′	36° 42′	32° 5′	40,432	43,891	53,333	·170	2·381
	0·40	47° 9′	35° 0′	30° 31′	38,564	41,801	50,799	·160	2·500
	0·38	44° 40′	33° 12′	28° 57′	36,636	39,711	48,259	·144	2·632
	0·36	42° 12′	31° 24′	27° 24′	34,708	37,621	45,719	·130	2·778
	0·35	40° 58′	30° 30′	26° 38′	33,744	36,576	44,449	·123	2·857
	0·34	39° 44′	29° 37′	25° 51′	32,779	35,531	43,179	·116	2·941
	0·32	37° 20′	27° 51′	24° 18′	30,851	33,441	40,639	·102	3·125
Resolution of *Nitzschia scalaris* in balsam with apochr. obj. 1 in N.A. ·30 . . . →	**0·30**	34° 56′	26° 4′	22° 46′	28,923	31,351	38,099	·090	3·333
	0·28	32° 32′	24° 18′	21° 14′	26,995	29,261	35,559	·078	3·571
	0·26	30° 9′	22° 33′	19° 42′	25,067	27,171	33,019	·068	3·846
	0·25	28° 58′	21° 40′	18° 56′	24,103	26,126	31,749	·063	4·000
	0·24	27° 46′	20° 48′	18° 10′	23,138	25,081	30,479	·058	4·167
	0·22	25° 26′	19° 2′	16° 38′	21,210	22,991	27,940	·048	4·545
	0·20	23° 4′	17° 18′	15° 7′	19,282	20,901	25,400	·040	5·000
	0·18	20° 44′	15° 34′	13° 36′	17,354	18,811	22,860	·032	5·555
	0·16	18° 24′	13° 50′	12° 5′	15,426	16,721	20,320	·026	6·250
	0·15	17° 14′	12° 58′	11° 19′	14,462	15,676	19,050	·023	6·667
	0·14	16° 5′	12° 6′	10° 34′	13,498	14,630	17,780	·020	7·143
	0·12	13° 47′	10° 22′	9° 4′	11,570	12,540	15,240	·014	8·333
	0·10	11° 29′	8° 38′	7° 34′	9,641	10,450	12,700	·010	10·000
	0·08	9° 11′	6° 54′	6° 3′	7,713	8,360	10,160	·006	12·500
	0·06	6° 53′	5° 10′	4° 32′	5,785	6,270	7,620	·004	16·667
	0·05	5° 44′	4° 18′	3° 46′	4,821	5,225	6,350	·003	20·000

Example illustrating the accompanying Table.

The apertures of four objectives, two of which are dry, one water-immersion, and one oil-immersion, would be compared on the angular aperture view as follows:

	Air	Air	Water	
	106°	157°	142°	
Their angular apertures are, however, as	·80	·98	1·26	or as their numerical apertures.

a progressive, and with high powers a rapidly increasing, *over-amplification* of the depth of the three-dimensional image. If a transverse section of an object is magnified 100 times in breadth the distance between the planes of parts lying one behind the other is magnified 10,000 times at the corresponding parts on the axis when the object is in air, 7500 times when it is in water, and 6600 times when it is in Canada balsam.

This excessive distortion in the case of high amplifications is not, however, *of itself* so complete a hindrance to correct appreciation of solid forms in the microscopical image as at first appears. The appreciation of solid form is not a matter of sensation only ; it is a mental act—a conception—and, therefore, the peculiarity of the optical image, however great the amplification, would not prevent the conception of the solidity of the object so long as salient points for the construction of a *three-dimensional* image were found. But for this the solid object, as such, must be simultaneously visible ; a single layer of inappreciable depth can convey no conception of the *three* space dimensions possessed by the object.

Owing to the disproportional amplification of the depth-dimension normal to the action of optical instruments, the visual space of the microscope loses more and more in depth as the amplification increases, and thus constantly approximates to a bare horizontal section of the object.

The visual space, which at one adjustment of the focus is plainly visible, is made up of two parts, the limits of which as regards the *depth* are determined in a very different manner.

First, *the accommodation of the eye* embraces a certain depth different planes being successively depicted with perfect sharpness of image on the retina, whilst the eye, adjusting itself by conscious or unconscious accommodation, obtains virtual images of greater or less distance of vision. This depth of accommodation, which plays the same part in microscopical as in ordinary vision, is wholly determined by the extent of power in this direction possessed by the particular eye, the limits being the greatest and the least distance of distinct vision. Its exact numerical measure is the difference between the *reciprocal* values of these two extreme distances. The depth of distinct vision is directly proportional to this numerical equivalent of the accommodation of the eye, directly proportional to the refractive medium of the object, and inversely proportional to the square of the amplification when referred always to the same image-distance. For example, a moderately short-sighted eye sees distinctly at 150 mm. as its shortest distance, and at 300 mm. as its longest distance ; then the numerical equivalent of the extent of accommodation would be equal to $\frac{1}{300}$ mm. ; the calculation for an object in air would give a depth of vision by accommodation amounting to

2·08	mm.	with 10	times amplification
0·23	,,	30	,,
0·02	,,	100	,,
0·0023	,,	300	,,
0·00021	,,	1000	,,
0·00002	,,	3000	,,

These figures are modified by the medium in which the object is placed and by the greater or less shortness and length of vision.

Secondly, the perception of depth is assisted by the insensibility of the eye to small defects in the union of the rays in the optic image, and therefore to small circles of confusion in the visual image. Transverse sections of the object which are a little above and below the exact focal adjustment are seen without prejudicial effects. *The total effect so obtained is the so-called penetration or depth of focus* of an objective. This may be determined numerically by defining the allowable magnitude of the circles of confusion in the microscopical image by the visual angle under which they appear to the eye. It is found that one minute of arc denotes the limit of sharply defined vision, two to three minutes for fairly distinct vision, and five to six minutes the limits of vision only just tolerable. This being determined, the focal depth depends only on the refractive index of the medium in which the object is placed, the amplification, and the angle of aperture, and it is directly proportional to the refractive index of the object medium, and inversely proportional to the 'numerical aperture' of the objective, as also to the first power of the amplification. These assume the visible angle of allowable indistinctness to be fixed at 5′, the aperture angle of the image-forming pencils to be 60° in air ; the depth of focus of an object in *air* will then be—

0·073	mm.	for 10	times amplification
0·024	,,	30	,,
0·0073	,,	100	,,
0·0024	,,	300	,,
0·00073	,,	1000	,,
0·00024	,,	3000	,,

By limiting or enlarging the allowable magnitude of indistinctness in the image we correspondingly modify these figures, as we should do with media of different refractive indices and increased aperture-angle.

It is plain, then, that the actual *depth of vision* must always be the exact sum of the *accommodation depth* and *focal depth*. The former expresses the object space through which the eye by the play of accommodation can penetrate and secure a sharp image ; the latter gives the amount by which this object-space is extended in its limits—reckoning both from above and below—because without perfect sharpness of image there is still a sufficient distinctness of vision.

As the amplification increases the over-amplification of the depth-dimension presents increasingly unfavourable relation between the depth and width of the object-space accessible to accommodation. When low powers are employed we have relatively great depth of vision, because we have large accommodation-depth ; but as we pass to medium powers, the accommodation-depth diminishes in rapid ratio, becoming equal to only a small depth of focus ; while when the magnifying power is greatly increased the accommodation-depth is a factor of no moment, and we have vision largely, indeed almost wholly, dependent on depth of focus.

The following table shows the total depth of vision from ten to 3,000 times :—

Amplification	Diameter of Field	Accommodation Depth	Focal Depth	Depth of Vision, Accommodation Depth, and Focal Depth	Ratio of Depth of Vision to Diameter of Field
	mm.	mm.	mm.	mm.	
10	25·0	2·08	0·073	2·153	$\frac{1}{11·6}$
30	8·3	0·23	0·024	0·254	$\frac{1}{32·7}$
100	2·5	0·02	0·0073	0·0273	$\frac{1}{91·6}$
300	0·83	0·0023	0·0024	0·0047	$\frac{1}{176·6}$
1000	0·25	0·00021	0·00073	0·00094	$\frac{1}{266}$
3000	0·083	0·00002	0·00024	0·00023	$\frac{1}{319}$

It has been pointed out by Abbe that this over-amplification of depth-dimension, though it limits the direct appreciation of solid forms, yet is of great value in extending the indirect recognition of space relations. When with increase of magnifying power the depth of the image becomes more and more flattened, the images of different planes stand out from each other more perfectly in the same ratio, and in the same degree are clearer and more distinct. With an increase of amplification the microscope acquires increasingly the property of an optical *microtome*, which presents to the observer's eye sections of a fineness and sharpness which would be impossible to a mechanical section. It enables the observer by a series of adjustments for consecutive planes, to *construe* the solid forms of the smallest natural objects with the same certainty as he is accustomed to *see* with the naked eye the objects with which it is concerned. This is a large advantage in the general scientific use of the instrument ; a greater gain, in fact, than could be expected from the application of stereoscopic observation.

Stereoscopic Binocular Vision.—This subject has been elaborately considered and partially expounded and demonstrated by Professor Abbe ; his exposition differs in some important particulars from that of the original author of this book, but in its present incomplete form it appears to the editor to be the wiser way to allow Dr. Carpenter's treatment of the subject to stand, and to place below it as complete a digest of Professor Abbe's theory and explanation of the same subject as the data before us will admit.

The admirable invention of the *stereoscope* by Professor Wheatstone has led to a general appreciation of the value of the *conjoint use of both eyes* in conveying to the mind a notion of the *solid forms* of objects, such as the use of either eye singly does not generate with the like certainty or effectiveness ; and after several attempts, which were attended with various degrees of success, the principle of

he stereoscope has now been applied to the microscope, with an dvantage which those only can truly estimate who (like the Author) ave been for some time accustomed to work with the stereoscopic inocular[1] upon objects that are peculiarly adapted to its powers. ls the result of this application cannot be rightly understood without some knowledge of one of the fundamental principles of binocular ision, a brief account of this will be here introduced. All vision epends in the first instance on the formation of a picture of the bject upon the retina of the eye, just as the camera obscura forms picture upon the ground glass placed in the focus of its lens. But he two images that are formed by the two eyes respectively of any olid object that is placed at no great distance in front of them are ar from being identical, the perspective projection of the object arying with the point of view from which it is seen. Of this the ader may easily convince himself by holding up a thin book in ich a position that its back shall be at a moderate distance in front f the nose, and by looking at the book, first with one eye and then ith the other; for he will find that the two views he thus obtains re essentially different, so that if he were to represent the book as e actually sees it with each eye, the two pictures would by no eans correspond. Yet on looking at the object with the two eyes njointly, there is no confusion between the images, nor does the ind dwell on either of them singly; but from the blending of the wo a conception is gained of a solid projecting body, such as could nly be otherwise acquired by the sense of touch. Now if, instead f looking at the solid object itself, we look with the *right* and *left* yes respectively at *pictures* of the object, corresponding to those hich would be formed by it on the retinæ of the two eyes if it were aced at a moderate distance in front of them, and these visual ctures are brought into coincidence, the same conception of a solid ojecting form is generated in the mind, as if the object itself were ere. The stereoscope—whether in the forms originally devised by ofessor Wheatstone or in the popular modification long subseently introduced by Sir D. Brewster—simply serves to bring to e two eyes, either by reflexion from mirrors or by refraction rough prisms or lenses, the two dissimilar pictures which would urately represent the solid object as seen by the two eyes respecely, these being thrown on the two retinæ in the precise positions y would have occupied if formed there direct from the solid ect, of which the mental image (if the pictures have been correctly en) is the precise counterpart. Thus in fig. 69 the upper pair of tures (A, B) when combined in the stereoscope suggest the idea of *rojecting* truncated pyramid, with the small square in the centre l the four sides sloping equally away from it; whilst the combiion of the lower pair, C, D (which are identical with the upper, are transferred to opposite sides), no less vividly brings to the id the visual conception of a *receding* pyramid, still with the

[1] It has become necessary to distinguish the binocular microscope which gives *stereoscopic* effects by the combination of two dissimilar pictures from a ocular which simply enables us to look with both eyes at images which are ntially identical (p. 106).

small square in the centre, but the four sides sloping equally towards it.

Thus we see that by simply *crossing* the pictures in the stereoscope, so as to bring before each eye the picture taken for the other, a 'conversion of relief' is produced in the resulting solid image, the projecting parts being made to recede and the receding parts brought into relief. In like manner, when several objects are combined in the same crossed pictures, their apparent relative distances are reversed, the remoter being brought nearer and the nearer carried backwards; so that (for example) a stereoscopic photograph



FIG. 69.

representing a man standing in front of a mass of ice shall, by the crossing of the pictures, make the figure appear as if imbedded in the ice. A like conversion of relief may also be made in the case of actual solid objects by the use of the *pseudoscope*, an instrument devised by Professor Wheatstone, which has the effect of reversing the perspective projections of objects seen through it by the two eyes respectively; so that the interior of a basin or jelly-mould is made to appear as a projecting solid, whilst the exterior is made to appear hollow. Hence it is now customary to speak of *stereoscopic* vision as that in which the conception of the true natural relief of an object is called up in the mind by the normal combination of the two perspective projections formed of it by the right and left eyes respectively; whilst by *pseudoscopic* vision we mean that 'conversion of relief' which is produced by the combination of two *reversed* perspective projections, whether these be obtained directly from the object (as by the pseudoscope) or from 'crossed' pictures (as in the stereoscope). It is by no means every solid object, however, or every pair of stereoscopic pictures which can become the subject of this conversion. The degree of facility with which the 'converted' form can be apprehended by the mind appears to have great influence on the readiness with which the change is produced. And while there are some objects—the interior of a plaster mask of a face, for example—which can always be 'converted' (or turned inside out) at

once, there are others which resist such conversion with more or less of persistence.[1]

Now it is easily shown theoretically that the picture of any projecting object seen through the microscope with only the *right* hand half of an objective having an even moderate angle of aperture, must differ sensibly from the picture of the same object received through the *left* hand of the same objective ; and, further, that the difference between such pictures must increase with the angular aperture of the objective. This difference may be practically made apparent by adapting a 'stop' to the objective in such a manner as to cover either the right or the left half of its aperture, and then by carefully tracing the outline of the object as seen through each half. But it is more satisfactorily brought into view by taking two photographic pictures of the object, through each lateral half of the objective ; for these pictures properly paired in the stereoscope give a magnified image of, bringing out on a large scale the solid form of the object from which they were taken. What is needed, therefore, to give the stereoscopic power to the microscope is a means of so bisecting the cone of rays transmitted by the objective that of its two lateral halves one shall be transmitted to the right and the other to the eye. If, however, the image thus formed by the *right* half of the objective of a compound microscope were seen by the *right* eye, and that formed by the *left* half were seen by the *left* eye, the resultant conception would be not *stereoscopic* but *pseudoscopic*, the projecting parts being made to appear receding, and *vice versa*. The reason of this is, that as the microscope itself reverses the picture, the rays proceeding through the *right* and the *left* hand halves of the objective must be made to cross to the *left* and the *right* eyes respectively, in order to correspond with the *direct* view of the object from the two sides ; for if this second reversal does not take place, the effect of the first reversal of the images produced by the microscope exactly corresponds with that produced by the 'crossing' of the pictures in the stereoscope, or by that reversal of the two perspective projections formed direct from the object, which is effected by the pseudoscope. It was from a want of due appreciation of this principle (the truth of which can now be practically demonstrated) that the earlier attempts at producing a stereoscopic binocular microscope tended rather to produce a 'pseudoscopic conversion' of the objects viewed by it than to represent them in this true relief.

In contradistinction to this explanation of binocular vision Dr. Abbe, as we have seen, has demonstrated that oblique vision in the microscope is wholly unlike ordinary vision ; there is, in fact, no perspective. The perspective shortening of lines and surfaces by oblique projection is entirely lost in the microscope, and, as a consequence, it is contended that the special dissimilarity which is the *raison d'être* of ordinary stereoscopic effects does not exist, but that an essentially different mode of dissimilarity is found between the two pictures. The outline or contour of a microscopic object is

[1] For a fuller discussion of this subject see the Author's *Mental Physiology*, §§ 168–170.

unaltered, whether viewed by an axial or an oblique pencil; there is no foreshortening, there is simply lateral displacement of the images of consecutive layers. But Abbe contends that, whilst the manner in which dissimilar pictures are formed in the binocular microscope is different from that by which they are brought about in ordinary stereoscopic vision, yet the activities of the brain and mind by which they are so blended as to give rise to sensations of solidity, depth, and perspective are practically identical.

The fact that lateral displacements of the image are seen in the microscope depends on a peculiar property of microscopic amplification, which is in strong contrast to the method of ordinary vision. It depends entirely on the fact, enunciated above, that the amplification of the depth is largely exaggerated. Hence solid vision in the binocular microscope is confined to large and coarse objects, the dimensions of which are large multiples of the wave-length. It therefore follows that when moderate or large apertures have to be employed—that is to say, whenever delineation requires the employment of oblique rays—the elements of the object are no longer depicted as solid objects seen by the naked eye or through the telescope would be depicted; nevertheless the brain arranges them so that the characteristics of solid vision are still presented.

Professor Abbe demonstrates [1] that in an aplanatic system pencils of different obliquities yield *identical* images of every plane object, or of a single layer of a solid object. This is true however large the aperture may be.

This carries with it, as we have said, a total absence of perspective and an essential geometrical difference between vision with the binocular microscope and vision with the unaided eye.

An object, not quite flat, as a curved diatom, when observed with an objective of wide aperture will present points of great indistinctness. This has been by some supposed to arise from the assumption that there was a dissimilarity between the images formed by the axial and oblique pencils; but this is not so. It is wholly explicable by the fact that the depth of the object is too great for the small depth of vision attendant upon a large aperture.

It will be seen, then, that so long as the depth of the object is within the limits of the depth of vision, corresponding to the aperture and amplification in use, we obtain a distinct *parallel projection* of all the successive layers in one common plane perpendicular to the axis of the microscope—a ground plan, as it were, of the object. Manifestly, then, since depth of vision decreases with increasing aperture, good delineation with these must be confined to *thinner objects* than can be successfully employed with objectives of narrow apertures.

Stereoscopic vision with the microscope, therefore, is due solely to difference of projection exhibited by the different parallactic displacements of the images of successive layers on the common ground plane and to the *perception of depth*, not to the delineation of the plane layers themselves. For, if there were dissimilar images per-

[1] *Journ. R.M.S.* series ii. vol. iv. pp. 21–24.

ceptible at different planes, the out-of-focus layers must appear confused and *no vision of depth* would be possible.

Now stereoscope vision requires, as shown by Dr. Carpenter, that the delineating pencils shall be so divided that one portion of the admitted cone of light is conducted to one eye and another portion to the other eye. If this division of the image is effected in a symmetrical way, the cross section of, *e.g.* a circle must be reduced to two semicircles representing one of these two arrangements seen in O and P, fig. 70.



FIG. 70.

Dr. Abbe's theory is that the only condition necessary for *orthoscopic* effect in any binocular system is that these semicircles or their equivalents should be depicted according to diagram O, fig. 70, and for *pseudoscopic* effect according to diagram P in the same figure; and he demonstrates that all other circumstances, such, e.g. as the crossing of the images, are wholly immaterial.

Orthoscopic vision is always obtained when the right half of the right pupil and the left half of the left pupil only are employed; pseudoscopic vision in the opposite conditions. 'It is quite indifferent whether the effect is obtained with crossing or non-crossing rays, whether the image be erect, or inverted, or semi-inverted, and whatever may be components of the optical arrangement.'

The observant reader will perceive that it is at this point that there is a radical divergence from the interpretation given by Dr. Carpenter, who, as we have seen above, insisted that orthoscopic vision is not to be obtained in a binocular with non-erecting eye-pieces unless the axes of the two halves of the admitted cone *cross each other*.

Of course we must keep clearly before us the fact that in microscopic vision it is not the object but its virtual image only that we see. This apparently solid *image* is placed in the binocular microscope under circumstances similar to those of common *objects* in ordinary vision. Clearly, then, it is the perspective projections of this *image* which require to be compared to the projections of solid objects in ordinary vision, in respect to which the criteria of orthoscopic and pseudoscopic vision have been defined. But it can be geometrically demonstrated that right-eye perspective of the apparently solid *image* is always obtained from the right-hand portion of the emergent pencils, left-eye perspective from the left-hand portion; *and it is quite immaterial, as regards this result, which portion of the emergent rays is admitted by the right or the left part of the objective.*

The manner in which the delineating *pencils* are transmitted through the system may be such as to require crossing over of the rays from the right-hand half of the objective to the left eye-piece, and *vice versa*. But it is not essential to binocular effect. In the Wenham and Nachet binocular (pp. 98, 99) crossing over *is* required because the inversion of the pencils is not changed by two reflexions. If the delineating pencils have been reflected an *even number* of times

FIG. 72.



FIG. 71

in the same plane, it will be necessary for the rays to cross; but if they have been reflected an odd number of times, it is not only unnecessary, but is destructive of orthoscopic effect, provided ordinary eye-pieces (non-erecting) are employed. Hence in the Stephenson binocular it is not only not required, but would give pseudoscopic effect.

Principal Forms of Binocular Microscopes.—The first binocular of a practical character was the arrangement of Professor J. L. Riddell, of New Orleans. It was devised in 1851 and constructed in 1852, and a description of its nature and its genesis was given by him in the second volume of the first series of the 'Quarterly Journal of Microscopical Science' in the year 1854.[1]

A representation of his original instrument is presented in fig. 71, and the arrangement of the prisms by which the binocular effect was obtained is shown in fig. 72.

It will be seen that the pencil of rays emerging from the back lens of the combination *l* is divided into two, each half passing respectively into the right and left prisms; the path of the rays is indicated at *a*, *b*, *c*, *d*, the object being at *o*.

To secure coincidence of the images in the field of view for varying widths between the eyes Professor Riddell devised (1) a means of regulating the inclination of the prisms by mounting them in hinged frames, so that, while their lower edges, near *a*, fig. 72, remain always in parallel contact, the inclination of the internal reflecting surfaces can be varied by the action of the milled head in front of the prism box; (2) the lower ends of the binocular tubes are connected by travelling sockets, moving on one and the same axis, on which are cut corresponding right- and left-handed screws, so that the width of the tubes may correspond with that of the prisms; and (3) the upper ends of the tubes are connected by racks, one acting above and the other below the same pinion, so that right- and left-handed movements are communicated by turning the pinion.



FIG. 73.—Arrangement of prisms in Nachet's stereoscopic binocular microscope.

This instrument could only be used in a vertical position, as shown in the figure (71); to obviate this considerable drawback Riddell mounted two right-angled prisms in brass caps, which could be slipped over the eye-pieces. This arrangement inverts the image in *both* planes, and it is seen through the instrument as in nature.

This system of binocular excited much interest in England im-

[1] P. 13.

mediately after its publication, and Mr. Wenham in London and MM. Nachet, of Paris, soon suggested and devised a variety of binocular systems.

Nachet's Binocular.—One of these (not now, we have reason to believe, advocated or employed by its inventor) was that devised by MM. Nachet, constructed on the method shown in fig. 73. The cone of rays issuing from the back lens of the objective meets the flat surface of a prism (p) placed above it, whose section is an equilateral triangle, and is divided by reflexion within this prism into two lateral halves, which cross each other in its interior. The rays $a\,b$ that form the right half of the cone, impinging very obliquely on the internal face of the prism, suffer total reflexion, emerging through its left side perpendicularly to its surface, and therefore undergoing no refraction: whilst the rays $a'\,b'$, forming the left half of the cone, are reflected in like manner towards the right. Each of these pencils is received by a lateral prism, which again changes its direction, so as to render it parallel to its original course, and thus the two halves $a\,b$ and $a'\,b'$ of the original pencil are completely separated from each other, the former being received into the left-hand body of the microscope (fig. 73), and the latter into its right-hand body. These two bodies are parallel; and, by means of an adjusting screw at their base, which alters the distance between the central and the lateral prisms, they can be separated from or approximated towards each other, so that the difference between their axes can be brought into exact coincidence with the distance between the axes of the eyes of the individual observer. This instrument gives true 'stereoscopic' projection to the conjoint image formed by the mental fusion of the two distinct pictures, and with low powers of moderate angular aperture its performance is highly satisfactory. There are, however, certain drawbacks to its general utility. First, every ray of each pencil suffers *two* reflexions, and has to pass through *four* surfaces: this necessarily involves a considerable loss of light, with a further liability to the impairment of the image by the smallest want of exactness in the form of either of the prisms. Secondly, the mechanical arrangements requisite for varying the distance of the bodies involve an additional liability to derangement in the adjustment of the prisms. Thirdly, the instrument can only be used for its own special purpose; so that the observer must also be provided with an ordinary single-bodied microscope for the examination of objects unsuited to the powers of his binocular. Fourthly, the parallelism of the bodies involves parallelism of the axes of the observer's eyes, the maintenance of which for any length of time is fatiguing.

Wenham's Stereoscopic Binocular.—All these objections are overcome in the admirable arrangement devised by the ingenuity of Mr. Wenham, in whose binocular the cone of rays proceeding upwards from the objective is divided by the interposition of a prism of the peculiar form shown in fig. 74, so placed in the tube which carries the objective (figs. 75, 76, a), as only to interrupt one half, $a\,c$, of the cone, the other half, $a\,b$, going on continuously to the eyepiece of the principal or right-hand body, R, in the axis of which the objective is placed. The interrupted half of the cone (figs. 74, 75, a),

on its entrance into the prism, is scarcely subjected to any *refraction*, since its axial ray is perpendicular to the surface it meets; but within the prism it is subjected to two *reflexions* at *b* and *c*, which send it forth again obliquely in the line *d* towards the eye-piece of the secondary or left-hand body (fig. 75, L); and since at its emergence its axial ray is again perpendicular to the surface of the glass, it suffers no more refraction on passing out of the prism than on entering it. By this arrangement the image received by the *right* eye is formed by the rays which have passed through the *left* half of the objective, and have come on without any interruption whatever; whilst the image received by the *left* eye is formed by the rays which have passed through the *right* half of the objective, and have been subjected to two reflexions within the prism, passing through only *two* surfaces of glass.

FIG. 74.—Wenham's prism.

The adjustment for the variation of distance between the axes of the eyes in different individuals is made by drawing out or pushing in the eye-pieces, which



FIG. 75.



FIG. 76.

Wenham's stereoscopic binocular microscope.

are moved consentaneously by means of a milled-head, as shown in fig. 76. Now, although it may be objected to Mr. Wenham's method (1) that, as the rays which pass through the prism and are obliquely reflected into the secondary body traverse a longer distance than

those which pass on uninterruptedly into the principal body, the picture formed by them will be somewhat larger than that which is formed by the other set; and (2) that the picture formed by the rays which have been subjected to the action of the prism must be inferior in distinctness to that formed by the uninterrupted half of the cone of rays; these objections are found to have no practical weight. For it is well known to those who have experimented upon the phenomena of stereoscopic vision (1) that a slight difference in the size of the two pictures is no bar to their perfect combination; and (2) that if one of the pictures be good, the full effect of relief is given to the image, even though the other picture be faint and imperfect, provided that the outlines of the latter are sufficiently distinct to represent its perspective projection. Hence if, instead of the two equally *half-good* pictures which are obtainable by MM. Nachet's original construction, we had in Mr. Wenham's one *good* and one *indifferent* picture, the latter would be decidedly preferable. But, in point of fact, the deterioration of the *second* picture in Mr. Wenham's arrangement is less considerable than that of *both* pictures in the original arrangement of MM. Nachet: so that the optical performance of the Wenham binocular is in every way superior. It has, in addition, these further advantages over the preceding: First, the greater comfort in using it (especially for some length of time together), which results from the convergence of the axes of the eyes at their usual angle for moderately near objects; secondly, that this binocular arrangement does not necessitate a special instrument, but may be applied to any microscope which is capable of carrying the weight of the secondary body, the prism being so fixed in a movable frame that it may in a moment be taken out of the tube or replaced therein, so that when it has been removed the principal body acts in every respect as an ordinary microscope, the entire cone of rays passing uninterruptedly into it; and thirdly, that the simplicity of its construction renders its derangement almost impossible.[1]



FIG. 77.—Riddell's binocular prisms, as applied by Mr. Stephenson.

Stephenson's Binocular.—A new form of stereoscopic binocular has been introduced by Mr. Stephenson,[2] which has certain distinctive features, and at the time Mr. Stephenson devised it he was entirely unaware that any part of the method he employed had been used by another. He had, however, independently conceived Riddell's device for dividing the beam as a part of his very ingenious instrument. This he discovered and acknowledged about three

[1] The Author cannot allow this opportunity to pass without expressing his sense of the liberality with which Mr. Wenham freely presented to the public this important invention, by which, there can be no doubt, he might have largely profited if he had chosen to retain the exclusive right to it.

[2] *Monthly Microscopical Journal*, vol. iv. (1870), p. 61, and vol. vii. (1872), p. 167.

years after the full description and completion of his binocular.[1] The cone of rays passing upwards from the object-glass meets a pair of prisms (A A, fig. 77) fixed in the tube of the microscope immediately above the posterior combination of the objective, so as to catch the light-rays on their emergence from it; these it divides into two halves and behaves as described in the Riddell prisms, which, in fact, they are. As the cone of rays is equally divided by the two prisms, and its two halves are similarly acted on, the two pictures are equally illuminated, and of the same size; while the close approximation of the prisms to the back lens of the objective enables even high powers to be used with very little loss of light or of definition, provided that the angles and surfaces of the prisms are worked with exactness; and as the two bodies can be made to converge at a smaller angle than in the Wenham arrangement, the observer looks through them with more comfort. But Mr. Stephenson's ingenious arrangement is liable to the great drawback of not being convertible (like Mr. Wenham's) into an ordinary monocular by the withdrawal of a prism, so that the use of this form of it will be probably restricted to those who desire to work with a binocular when employing high powers. In order to avoid slight errors arising from the impinging of the central ray of the cone, at its emergence from the objective, against the double edge of the prism-combination, Mr. Stephenson has devised a special form of sub-stage condenser (also made by Mr. Browning), which causes the illuminating rays to issue from the object in two separate pencils, which will strike the *surfaces* of the two prisms. This consists of two deep cylindrical lenses A and B, fig. 78, whose focal lengths are as 2·3 to 1, having their curved faces opposed to each other, as shown in section at C; the larger and less convex being placed with its plane side downwards, so as to receive light from the mirror, or (which is preferable) direct from a lamp. Under this combination slides a movable stop, with two circular openings, as shown in fig. 79. The lamp being placed in front of the instrument, the two apertures admit similar pencils of light from it, so that each eye receives a completely equal illumination, and no confusion can occur from the impinging of the rays on the lower edges of the prisms. With this arrangement the Podura markings are shown as figured by the late Richard Beck, while the curvatures of the scale come out with the distinctness peculiar to binocular vision.

FIG. 78.



FIG. 79.

[1] *Monthly Microscopical Journal*, vol. x. p. 41.

But one of the greatest advantages attendant on **Mr. Stephenson's** construction is its capability of being combined with an *erecting* arrangement, which renders it applicable to purposes for which the Wenham binocular cannot be conveniently used. By the interposition of a plane silvered mirror, or (still better) of a reflecting prism (fig. 80), above the tube containing the binocular prisms, each half of the cone of rays is so deflected that its image is reversed *vertically*, the rays entering the prism through the surface C B, being reflected by the surface A B, so as to pass out again by the surface A C in the direction of the dotted lines. Thus the right and the left half-cones are directed respectively into the right and the left bodies, which are inclined at a convenient angle, as shown in fig. 81; so that—the stage being horizontal—the instrument becomes a most useful compound dissecting microscope, and as thus arranged by Swift, with well adjusted rests for the hands, has but few equals for the purposes of minute dissections and delicate mounting operations; indeed, the value of the erecting binocular consists in its applicability to the picking out of very minute objects, such as *Diatoms*, *Polycystina*, or *Foraminifera*, and to the prosecution of minute dissections, especially when these have to be carried on in fluid. No one who has only thus worked *monocularly* can appreciate the guidance derivable from *binocular* vision when once the habit of working with it has been formed.

FIG. 80.—Stephenson's erecting prism.



FIG. 81.—Stephenson's erecting binocular.

Tolles' Binocular Eye-piece.—An ingenious eye-piece has been constructed by Mr. Tolles (Boston, U.S.A.), which, fitted into the body of a monocular microscope, converts it into an erecting stereoscopic binocular. This conversion is effected by the interposition of a system of prisms similar to that originally devised by **MM.** Nachet, but made on a larger scale, between an 'erector' (resembling that used in the eye-piece of a day-telescope) and a pair of ordinary Huyghenian eye-pieces, the *central* or dividing prism being placed at or near the plane of the secondary image formed by the erector, while the two eye-pieces are placed immediately above the two *lateral* prisms, and the combination thus making that division in the pencils forming the secondary image which in the

Nachet binocular it makes in the pencils emerging from the objective. As all the image-forming rays have to pass through the two surfaces of four lenses and two prisms, besides sustaining two internal reflexions in the latter, it is surprising that Professor H. L. Smith, while admitting a loss of light, should feel able to speak of the definition of this instrument as not inferior to that of either the Wenham or the Nachet binocular. It is obviously a great advantage that this eye-piece can be used with any microscope and with objectives of high power; but as its effectiveness must depend upon extraordinary accuracy of workmanship its cost must necessarily be great.[1]



FIG. 82.—Abbe's binocular eye-piece.

Abbe's Stereoscopic Eye-piece.—Fig. 82 represents this instrument in section. The body A A′ contains three prisms of crown glass, *a*, *b*, and *b′*. The two eye-pieces B, B′ are let into the top plate, the former being fixed, whilst the latter has a lateral sliding movement; the bottom plate carries the tube C for inserting the eye-piece into the microscope tube like an ordinary eye-piece.

The two prisms *a* and *b* are united so as to form a thick plate with parallel sides, their continuity, however, being broken by an

[1] See *American Journal of Science*, vol. xxxviii. (1864), p. 111, and vol. xxxix. (1865), p. 212; and *Monthly Microsc. Journal*, vol. vi. (1871), p. 45.

exceedingly thin stratum of air—less than 0·01 mm.—inclined to the axis at an angle of 38·5°. The cone of rays from the objective is divided into two parts, one being transmitted and the other reflected. The transmitted rays pass through *a*, *b* without deviation, and form an image of the object in the axial eye-piece β. The rays reflected at the angle shown in the figure pass through the second surface of the prism *b* (upon which they are incident at right angles), and emerging at an inclination of 13° with the horizontal are totally reflected into the eye-piece β' at an angle of 90° by the hypothenuse surface of the right-angled equilateral prism *b'*, the axis of which also makes an angle of 13° with the axis of the microscope.

Adjustment for different distances between the eyes is effected by the screw D, which moves the eye-piece β', together with the prism *b'*, in a parallel direction. The tubes of the eye-pieces can also be drawn out if greater separation is required.

The eye-pieces have the usual two lenses, but are of special construction in order to equalise the length of the direct axis and the doubly reflected axis, and in spite of this inequality obtain sharply defined images of equal amplification with the same focus.

Stereoscopic vision is obtained by halving the cones of rays above the eye-pieces. This is effected by stopping off half of the real image of the objective opening formed above the eye-pieces at the so-called 'eye-point' β or β', which represents the common cross-section of all the pencils emerging from the eye-piece. A cap with a semicircular diaphragm is fitted to the eye-piece (shown in the figure over β'), the straight edge of which is exactly in the optic axis of the eye-piece, and can be raised or lowered by screwing so as to obtain a uniform bisection of the cones of rays from every point of the field.

The height of the diaphragm is regulated once for all for the same length of the microscope-tube by finding the position for which the aperture-image (which on withdrawing the eye from the eye-piece is visible as a bright circle above it) shows no parallax against the straight edge of the diaphragm, i.e. so that on moving the eye laterally the image always appears to adhere to the edge.

In addition to the above caps with diaphragms the instrument is supplied with ordinary caps with circular apertures, as in β. They taper slightly and simply slide into the eye-piece, so that they can be readily changed. The special feature of the instrument is 1st, that it is capable of being used with the highest powers; and 2ndly, that it is not necessary to cover up half of each of the eye-piece tubes, thus losing half the total amount of light. It is sufficient if one only (the lateral one) is half obscured, leaving the other free. As the normal division of light between the two tubes is two-thirds (in the axial) and one-third (in the lateral), the total loss of light is reduced to one-sixth.

The field of view in the axial eye-piece in this arrangement in any case necessarily appears brighter than that of the lateral one seen with the same eye, and in regard to this Dr. Abbe remarks that the difference between the brightness of the two fields in binocular observation 'is not only no defect, but, on the contrary,

a decided advantage.' For experience has long proved that, to obtain a good stereoscopic effect, it is only necessary that one image should be as perfect and clear as possible, whilst the other may, without appreciable disadvantage, be of sensibly less perfection.

It might therefore be anticipated that this would apply (as in fact it does) in the same way to difference of luminosity. Moreover, an additional fact must be taken into account—that the two eyes, especially of microscopists, always show unequal sensibility to light as the result of constant unequal use. The less used eye, whose acuteness of vision is always less than that of the one more frequently exercised, shows a greater sensibility to light, and the difference is so considerable that the less luminous image of the lateral eye-piece, when viewed with the less exercised (generally the left) eye, seems even brighter than the other when viewed with the exercised eye. The unequal division of the light is therefore a welcome element, as it serves to equalise this physiological difference. The observer has only to take care that the less used eye is applied to the lateral eye-piece; and 3rdly, the ingenious arrangement whereby, by simply turning the caps with the diaphragms, orthoscopic or pseudoscopic effect can be produced instantaneously at pleasure. It is more particularly available for tubes of short length, for which the Wenham prism is inapplicable.

The stereoscopic binocular is put to its most advantageous use when applied either to *opaque* objects of whose solid forms we are desirous of gaining an exact appreciation or to *transparent* objects which have such a thickness as to make the accurate distinction between their nearer and their more remote planes a matter of importance. All stereoscopic vision with the microscope, so far as it is anything more than mere seeing with two eyes, depends, as already seen, exclusively upon the unequal inclination of the pencils which form the two images to the plane of the preparation, or the axis of the microscope. By uniform halving of the pencils—whether by prisms above the objective or by diaphragms over the eye-pieces—the difference in the directions of the illumination in regard to the preparation reaches approximately the half of the angle of aperture of the objective, provided that its whole aperture is filled with rays. By the one-sided halving we have been considering, the direct image is produced by a pencil the axis of which is perpendicular to the plane of the preparation, and the deflected image by one whose axis is inclined about a fourth of the angle of aperture.

With low powers, which allow of a relatively considerable depth-perspective, the slight difference of inclination, which remains in the latter case, is quite sufficient to produce a very marked difference in the perspective of the successive layers in the images. But with high powers the difference in the two images does not keep pace—even when both eye-pieces are half-covered—with the increase of the angle of aperture, so long as ordinary central illumination is used. For in this case the incident pencil does not fill the whole of the opening of the objective, but only a relatively small central part, which, as a rule, does not embrace more than 40° of angle, and in most cases cannot embrace more without the clearness of the microscopic image being affected and the focal

depth also being unnecessarily decreased. But as those parts o preparation which especially allow of solid conception are al formed by direct transmitted rays in observation with transm light, it follows that under these circumstances the difference o two images is founded, not on the whole aperture-angle of th jective, but on the much smaller angle of the incident and dir transmitted pencils, which only allow of relatively small differ of inclination of the image-forming rays to the preparation.

Fig. 83.

evident, however, that when objec of short focus and correspondingly angle are used, a considerably gr differentiation of the two images wit spect to parallax can be produced place of one axial illuminating pencil pencils are used oppositely inclined t axis in such a way that each of images is produced by one of the pe This kind of double illumination, th it cannot be obtained by the si mirror, can be easily produced by with the condenser a diaphragm wit openings (fig. 83), placed in the diaphragm stage under the denser. We then have it in our power to use, at pleasure, pe of narrower or wider aperture and of greater or less inclin towards the axis by making the openings of different width different distance apart.

With diaphragms of this form (which can easily be made o card-board) the larger aperture angles of high-power objectives be made use of to intensify the stereoscopic effect without empl wide pencils, which are prejudicial both as diminishing the clea of the image and the focal depth.

Of course with this method of illumination both eye-pieces be half covered in order that one image may receive light only

Fig. 84.

one of the two illuminating cones, and the other from the other. The division of light in both the aper images will then be as shown in fig. 84; and it is evi that in this case the brightness of the image for both together is exactly the same as would be given by of the two cones alone without any covering.

The method of illumination here referred to—which was or ally recommended by Mr. Stephenson for his binocular microsco has, in fact, proved itself to be by far the best when it is a que of using higher powers than about 300 times. It necessarily req very well corrected and properly adjusted objectives if the shar of the image is not to suffer; but if these conditions are satisfi yields most striking stereoscopic effects, even with objectiv 2 mm. and less focal length, provided the preparation under o vation presents within a small depth a sufficiently characte structure.

Non-Stereoscopic Binoculars.—The great comfort which is perienced by the microscopist from the conjoint use of both eye

to the invention of more than one arrangement by which this
nfort can be secured when those high powers are required which
not be employed with the ordinary stereoscopic binocular. This
ccomplished by Messrs. Powell and Lealand by taking advantage
the fact already adverted to, that when a pencil of rays falls
iquely upon the surface of a refracting medium a part of it is
ected without entering that medium at all. In the
ce usually occupied by the Wenham prism, they
erpose an inclined plate of glass with parallel sides,
ough which one portion of the rays proceeding up-
rds from the whole aperture of the objective passes
the *principal* body with very little change in its
rse, whilst another portion is reflected from its sur-
into a rectangular prism so placed as to direct it
iquely upwards into the *secondary* body (fig. 85).
hough there is a decided difference in brightness be-
en the two images, that formed by the reflected rays
ng the fainter, yet there is marvellously little loss of
nition in either, even when the 50th of an inch objec-
is used. The disc and prism are fixed in a short
e, which can be readily substituted in any ordinary
ocular microscope for the one containing the Wenham
m. Other arrangements were long since devised
Mr. Wenham,[1] and subsequently by Dr. Schröder, for securing
ocular vision with the highest powers. We have used the latter
these with perfect satisfaction, but all that is required is at the
posal of the student in the arrangement of Powell and Lealand.

FIG. 85.

To those who have used these forms of binocular habitually it
been a frequent source of surprise and perplexity that, although
oretically such a form as that of Powell and Lealand's is non-
reoscopic, yet objects studied with high powers have *appeared* as
a relief, and the effect upon the mind of stereoscopic vision has
n distinctly manifest. The Editor was conscious
his for many years in the use of the Powell and
land form, with even the $\frac{1}{50}$th of an inch power
he achromatic construction; at the time he inter-
ted it as a conceptual effect; but it always arose
en the pupils fell upon the outer halves of the
msden circles. The explanation, Dr. A. C.
rcer considers,[2] is due to Abbe. Since (fig. 86)
en the eye-pieces are at such a distance apart that
Ramsden circles correspond exactly with the
ils of the eyes, centre to centre, the object appears
. But if the eye-pieces be racked down, so as
e nearer together, the centres of the pupils fall
n the *outer* halves of the Ramsden circles, and we
e the conditions of orthoscopic effect; while if they be racked up
s to be more separated, the centres of the pupils fall on the *inner*
ves, and we have pseudoscopic effect.



FIG. 86.

[1] *Transactions of the Microsc. Soc.* N.S. vol. xiv. (1866), p. 105.
[2] *Journ. R. M. S.* ser. ii. vol. ii. p. 271.

The Optical Investigations of Gauss.—Before leaving this section of our subject, in which we have endeavoured, with as much clearness as we could command, to enable the general reader to comprehend with intelligibility *the principles of theoretical and applied optics* as they relate to the microscope, we believe we shall serve the higher interests of microscopy, and the wants or desires of the more advanced microscopical experts, if we endeavour to present in a form either devoid of technicality or with inevitable technicalities explained *a general outline and then an application of the famous dioptric investigations of Gauss*, an eminent German mathematician, who amongst many other brilliant labours in applied mathematics *expounded the laws of the refraction of light in the case of a co-axial system of spherical surfaces, having media of various refractive indices lying between them.*



FIG. 87.[1]

Although the assumptions upon which the formulæ of Gauss rest are not coincident with the conditions presented by the lens-combinations which are employed in the construction of modern objectives of great aperture, the results, nevertheless, furnish an admirable presentation of the path of the rays and the positions of cardinal points, even in the microscope as we know and use it.

We remember that the microscope is largely used in England and America by men who can only employ it in their more or less brief recessions from professional and commercial pursuits, but who often employ it with enthusiasm and intelligent purpose. Much scientific work may be done by such men, and it will promote the accomplishment of this, in our judgment, if the frequently expressed desire be met which will enable such students to understand

[1] This figure is greatly exaggerated for the sake of clearness.

in a general but thoroughly intelligent manner the principles involved in the employment of systems of lenses.

Many such either have scanty knowledge of algebra, or in the continuous pressure of other claims have lost much that they once possessed. We believe that in these cases the following exposition of the dioptric system of Gauss, with a following example worked out in full and with every step made clear, will be of real and practical value. Without some intelligible understanding of the ultimate principles of the microscope no results of the highest order can, at least with moderate and high-power lenses of the best modern construction, be anticipated. On this ground we commend the study to the earnest reader.

Let R N, S N′ (fig. 87) be the spherical surfaces of a lens of density greater than air, and let P R S p be the course of a ray of light passing through it; C, C′, the centres of the spherical surfaces.

Let P R, R S be produced to meet the perpendiculars through C and C′ in A and A′.

Let C R $= r$, C′ S $= r'$,[1] μ = index of refraction out of air into the medium. N N′ $= d$, the thickness of the lens. N R $= b$, N′ S $= b'$. These may be considered as straight lines.

Let the equation to P R be $y - b = m\,(x - \mathrm{O\,N})$ . . (1)

" " R S " $y - b = m'\,(x - \mathrm{O\,N})$ . . (2)

or, $y - b' = m'\,(x - \mathrm{O\,N'})$ . . (3)

" " S p " $y - b' = m''\,(x - \mathrm{O\,N'})$ . . (4)

From (2) and (3)

$$b' - b = m'\,(\mathrm{O\,N'} - \mathrm{O\,N}) = m'\,\mathrm{N'\,N} = m'\,d \quad . \quad . \quad (5)$$

Now $$\sin \mathrm{C\,R\,A} = \mu\,.\,\sin \mathrm{C\,R\,B};$$

or, $$\frac{\mathrm{C\,A}}{\mathrm{C\,R}}\,.\,\sin \mathrm{C\,A\,R} = \mu\,.\,\frac{\mathrm{C\,B}}{\mathrm{C\,R}}\,.\,\sin \mathrm{C\,B\,R}.$$

Now C A and C B are the values of y in equations (1) and (2) when $x = \mathrm{O\,C}$;

$$\therefore \mathrm{C\,A} = b + m\,(\mathrm{O\,C} - \mathrm{O\,N}) = b + m\,r;$$

and similarly $$\mathrm{C\,B} = b + m'\,r;$$

$$\therefore (b + m\,r)\,\sin \mathrm{C\,A\,R} = \mu\,(b + m'\,r)\,\sin \mathrm{C\,B\,R}.$$

Now C A R, C B R do not in general differ much from each other, so that for a first approximation we may consider them to be equal.

$$\therefore b + m\,r = \mu\,(b + m'\,r), \text{ i.e. } \mu\,m' = m - \frac{\mu - 1}{r}\,.\,b.$$

Let $$\frac{\mu - 1}{r} = u;\ \text{then } \mu\,m' = m - b\,u. \quad . \quad . \quad (6)$$

Similarly, $$\sin \mathrm{C'\,S\,B'} = \mu\,.\,\sin \mathrm{C'\,S\,A'};$$

or, $$\frac{\mathrm{C'\,B'}}{\mathrm{C'\,S}}\,.\,\sin \mathrm{C'\,B'\,S} = \frac{\mathrm{C'\,A'}}{\mathrm{C'\,S}}\,.\,\sin \mathrm{C'\,A'\,S};$$

[1] If either of the curvatures be turned in the opposite direction the sign of the corresponding r must be changed.

and, as before,

C′ B′ $= b' + m'' r'$, C′ A′ $= b' + m' r'$ from equations (4) and (3);

∴ as before we may take

$$b' + m'' r' = \mu (b' + m' r'), \text{ or } \mu m' = m'' - \frac{\mu - 1}{r'} b'.$$

Let $\frac{\mu - 1}{r'} = u'$, then $\mu m' = m'' - b' u'$ . . . (7)

From (5) and (6) $b' = b + \frac{m - b u}{\mu} d = b \left(1 - \frac{d u}{\mu}\right) + \frac{m d}{\mu}$.

„ this and (7) $m'' = \mu m' + b u' \left(1 - \frac{d u}{\mu}\right) + \frac{m d u'}{\mu}$

and from (6) $= m - b u + b u' \left(1 - \frac{d u}{\mu}\right) + \frac{m d u'}{\mu}$

$$= m \left(1 + \frac{d u'}{\mu}\right) + b \left(u' - u - \frac{d u u'}{\mu}\right).$$

Assume

$$\frac{d}{\mu} = h, \; 1 - \frac{d u}{\mu} = g, \; 1 + \frac{d u'}{\mu} = l, \; u' - u - \frac{d u u'}{\mu} = k$$

then $b' = g b + h m$, $m'' = k b + l m$, where $g l - h k = 1$ . . (8)

Now let X, Y be the coordinates of P, the point from which the ray of light proceeds;

then by (1) $b = Y - m (X - O N)$;

substituting in (8) $b' = g Y + m (h - g . \overline{X - O N})$;

$m'' = k Y + m (l - k \overline{X - O N})$;

whence

$$m = \frac{m'' - k Y}{l - k (X - O N)}; \; b' = g Y + (m'' - k Y) \frac{h - g (X - O N)}{l - k (X - O N)}.$$

Now substituting in (4) the equation to the refracted ray becomes

$$y - Y \left(g - k \frac{h - g (X - O N)}{l - k (X - O N)}\right)$$

$$= m'' \left(x - O N' + \frac{h - g (X - O N)}{l - k (X - O N)}\right);$$

or by (8)

$$y - \frac{Y}{l - k (X - O N)} = m'' \left(x - O N' + \frac{h - g (X - O N)}{l - k (X - O N)}\right) . \quad (9)$$

First: If X be taken such that $l - k (X - O N) = 1$, i.e. $X = O N - \frac{1 - l}{k} = O E$, suppose;

then when

$$x = O N' - h + g \frac{l - 1}{k} = O N' + \frac{1 - g}{k} = O E', \text{ suppose,}$$

$y = Y$, or P and p are equally distant from the axis.

Also, if $Y = 0$, $y = 0$; or if a ray proceed from E, it will after refraction pass through E'. Also $m = \dfrac{m'' - kY}{l - k(X - ON)} = m''$, that is, the ray will be equally inclined to the axis before and after refraction.

E and E' are called the 'principal points.'

$$\left.\begin{aligned} OE = ON - \frac{1-l}{k} &= ON + \frac{\dfrac{du'}{\mu}}{u' - u - \dfrac{du\,u'}{\mu}} \\ &= ON + \frac{du'}{\mu(u'-u) - du\,u'}; \\ OE' = ON' + \frac{1-g}{k} &= ON' + \frac{\dfrac{du}{\mu}}{u' - u - \dfrac{du\,u'}{\mu}} \\ &= ON' + \frac{du}{\mu(u'-u) - du\,u'}. \end{aligned}\right\}$$

Secondly: If $m'' = 0$, or the ray be parallel to the axis after refraction, we have from (8)

$b = -\dfrac{l}{k}m$, and the equation to the incident ray becomes

$$y + \frac{l}{k}m = m(x - ON), \text{ or } y = m\left(x - ON - \frac{l}{k}\right);$$

$$\therefore \text{ when } y = 0,\ x = ON + \frac{l}{k} = ON + \frac{1 + \dfrac{du'}{\mu}}{u' - u - \dfrac{du\,u'}{\mu}}$$

$$= OF, \text{ suppose.}$$

If $m = 0$, or the ray be parallel to the axis before refraction, we have from (8)

$b' = g\,b = \dfrac{g}{k}m''$, and the equation to the refracted ray becomes

$$y - \frac{g}{k}m'' = m''(x - ON'), \text{ or } y = m''\left(x - ON' + \frac{g}{k}\right);$$

$$\therefore \text{ when } y = 0,\ x = ON' - \frac{g}{k} = ON' - \frac{1 - \dfrac{du}{\mu}}{u' - u - \dfrac{du\,u'}{\mu}}$$

$$= OF', \text{ suppose.}$$

F and F' are called the 'focal points.'

$$\left.\begin{aligned} OF &= ON + \frac{\mu + du'}{\mu(u'-u) - du\,u} \\ OF' &= ON' - \frac{\mu - du}{\mu(u'-u) - du\,u'} \end{aligned}\right\}$$

The focal distance $-f = \mathrm{O\,F} - \mathrm{O\,E} = \mathrm{O\,E'} - \mathrm{O\,F'}$

$$= \frac{\mu}{\mu\,(u' - u) - d\,u\,u'} = \frac{1}{k}$$

Similarly, it may be shown that if there be two lenses, and subscript numbers refer to the first and second lens respectively, while E, E′, F, F′ refer to the entire system, and if

$$\hat{c} = \mathrm{O\,E_2} - \mathrm{O\,E_1'},$$

$$v_1 = -\frac{\mu_1}{f_1} = \mu_1\,(u_1' - u_1) - d_1\,u_1\,u_1',$$

$$v_2 = -\frac{\mu_2}{f_2} = \mu_2(u_2' - u_2) - d_2\,u_2\,u_2',$$

$$\left.\begin{aligned} \mathrm{O\,E} &= \mathrm{O\,E_1} + \frac{\mu_1\,\hat{c}\,v_2}{\mu_2\,v_1 + \mu_1\,v_2 + \hat{c}\,v_1\,v_2} \\ \mathrm{O\,E'} &= \mathrm{O\,E_2'} - \frac{\mu_2\,\hat{c}\,v_1}{\mu_2\,v_1 + \mu_1\,v_2 + \hat{c}\,v_1\,v_2} \end{aligned}\right\};$$

$$\left.\begin{aligned} \mathrm{O\,F} &= \mathrm{O\,E_1} + \frac{\mu_1\,(\mu_2 + \hat{c}\,v_2)}{\mu_2\,v_1 + \mu_1\,v_2 + \hat{c}\,v_1\,v_2} \\ \mathrm{O\,F'} &= \mathrm{O\,E_2'} - \frac{\mu_2(\mu_1 + \hat{c}\,v_1)}{\mu_2\,v_1 + \mu_1\,v_2 + \hat{c}\,v_1\,v_2} \end{aligned}\right\}.$$

We are now prepared to *work out an example of the Gauss system* by tracing a ray through two or more lenses on an axis, showing how any conjugate may be found through two or more lenses on that axis.[1]

The Gauss system of tracing a ray through two or more lenses on an axis illustrated by means of a worked-out example.

Two lenses, 1 and 2, fig. 88, or an axis $x\,y$ are given. No. 1 is a double convex of crown ½ inch thick, the refractive index μ being

[1] Remembering our object, and the assumed conditions of some for whom we write, we do not hesitate to preface this with the following notes to remind the reader of the sense attached to certain mathematical expressions.

∞ means infinity. A plane surface of a lens is considered a spherical surface of an infinite radius. Any number divided by $\infty = 0$; any number divided by $0 = \infty$; any number multiplied by $0 = 0$. ∞ plus, or minus, or multiplied by any number is still ∞.

The following are the rules for the treatment of algebraical signs:

In the *multiplication or division* of *like signs* the result is always *plus*; but if the signs are *dissimilar* it is always *minus*.

In addition, add all the terms together that have a plus sign; then all the terms with a minus sign; subtract the less from the greater and affix the sign of the greater. Example:

$$+ 3 - 4 + 2 - 5 = - 4.$$

In subtraction change the sign of the term to be subtracted and then add in accordance with the previous rule. Example:

$$\begin{array}{r} -3 \\ +2 \\ \hline -5 \end{array}$$

An example occurs in the annexed equations (x) and (xi), p. 114, of $- \div - = +$, but then the $+$ is changed into a $-$ by the negative sign in front of the fraction. In (xii), p. 114, however, there being a $+$ in front of the fraction, the result remains positive.

$\frac{3}{5}$, the radius of the surface A is $\frac{3}{4}$ and that of B 1 inch. No. 2 lens is a plano-concave of flint $\frac{1}{10}$ inch thick, the refractive index μ being $\frac{5}{3}$, the radius of the surface C is $\frac{3}{8}$, and the surface D is plane. The distance between the lenses, that is, from B to C measured on the axis, is $\frac{1}{4}$ inch. The problem is to find the conjugate focus of any given point V.

In order to accomplish this two points have first to be found with regard to each lens. These points are called principal points (see P P′, Q Q′ in fig. 88). When the radii of curvature r and r', d, the thickness, and μ_1 μ_2, the refractive indices of the respective lenses,[1] are known, the distance of these points from the vertices, i.e. the points where the axis cuts the surfaces of the lens, can be found. Thus by applying Professor Fuller's formulæ to lens 1 the distance of P from the vertex A can be determined—see p. 116 (i)—similarly P′ from B—p. 116 (ii). In the same way the points Q Q′ from C and D in lens 2 can be measured off—(v) (vi), p. 117.

It must be particularly noticed that in measuring off any distance if the number is + it must be measured from left to right, and if − from right to left. Thus in (i) p. 116 because the sign of ·158 is + P lies ·158 of an inch to the right of A. And in (ii) because ·21 is − P′ lies ·21 of an inch to the left of B. The same rule applies to the radii; thus the radius of A, being measured from the vertex to the centre or from left to right, is +; but the radius of B, being measured from the vertex to its centre or from right to left, is −. Similarly with the concave surface, C being measured from right to left is −.

In both the examples before us the points P P′, Q Q′ fall inside their respective lenses, but it does not follow that they will do so in every instance. In some forms of menisci, for example, they will fall outside the lens altogether.

With regard to the focus of the lens it follows the same rule; thus, f in lens 1 is measured to the left from P, and f' to the right from P′; similarly in lens 2, f'' is measured to the right from Q, and f''' to the left from Q′.

Having determined the focal length of each lens, the distance between the right hand principal point of the first lens P′ and the left hand principal point of the second lens Q must next be found. It manifestly is the distance of B from P′ + the distance B C between the lenses, Q being at the point C. Therefore

$$P'Q = \cdot21 + \cdot25 = \cdot46 = \tilde{c}.$$

When these three data have been obtained—that is, the focal length of each lens, and the distance between them—we are in a position to apply the formulæ (ix) and (x), p. 118, to find the principal points E and E′ of the combination.

[1] In the worked out example no distinction has been made between the r, r' of one lens and the r, r' of the other lens, as well as of μ and d, because when the principal points and focal length are determined for one lens those expressions are not again needed, so the same letters with different values assigned to them may be equally well used for the next lens. Too many different terms are apt to confuse the student, while those who are familiar with mathematical expressions will understand the arrangement.

In selecting the value of the focus to be put into the equations for both lenses, the last must be taken, that is, in lens 1 (iv), or +·947, and in lens 2 (viii), or −1·875.

It will be noticed that the value of E being negative, it will be measured ·314 inch to the left from P. Similarly, E′ is measured ·622 inch to the left from Q′.

ϕ also is 1·28 to the left from E, and ϕ' 1·28 to the right from E′.

These four points, E, E′ and ϕ, ϕ', are called the cardinal points of the combination.

Here it must be observed that in this work it has been necessary for want of space to restrict the problem to dry lenses, that is, to those cases where the ray emerges from the combination into air, the same medium in which it was travelling on immergence. It is on that account that the values of ϕ and ϕ' are the same.

Having now obtained the four cardinal points, we may at once proceed to find the conjugate of x.

Let x equal the distance of the point x from the focal plane ϕ, and y the distance of its conjugate from ϕ'. Then by formula (xiii)

$$x\,y = \phi^2, \text{ and as } x = 1 \text{ inch, } y = \frac{1{\cdot}6384}{1} = 1{\cdot}6384.$$

This numerically determines the position of the conjugate plane.

If the rays incident on the combination are parallel, then $x = \infty$, and $y = \frac{\phi^2}{\infty} = 0$, which means that y is coincident with ϕ'.

The following is the graphic method of finding the conjugate of V. From V, fig. 88, draw a line parallel to the axis to meet E′, and from the point where it meets E′ draw a line through N, the point where ϕ' cuts the axis, to W.

From V draw another line through M, the point where ϕ cuts the axis, to meet E, and from the point where it meets E draw a line parallel to the axis, cutting the other line in W. W will be the conjugate of V, which was required.

If it is required to find the conjugate of a ray passing through three lenses on an axis, two of the lenses must be combined and their four cardinal points found.

The principal points and the focal length of the third lens must then be calculated, and then combined in their turn by formulæ (ix), (x), (xi), and (xii), p. 118, with the cardinal points of the double combination. δ is taken as the distance of the first principal point of the combination, nearest the third lens, to the second principal point of the lens, nearest the combination. A fresh set of cardinal points is determined in this manner for the three lenses.

So also with four lenses; the cardinal points of each pair being found, they are combined by the same formulæ, and new cardinal points for the whole combination of four lenses are obtained. Similarly, the cardinal points of five, six, or any number of lenses can be found and the conjugate of any point localised.

Finally, no one need be discouraged by the appearance of the length of the calculation; the example is given in full, so that any-

ted only with
ions and deci-
ork it, or any
problem, out.
No. 1, for in-
numerators of
s are all very
the denomina-
four equations
e; so, too, in
s for No. 2 and
both lenses.
is the same as
and ϕ' as ϕ.
roblem is much
it looks.
onjugate of a
e *axis* is only
d if the prin-
and foci of
ave been de-
will not be
enter into the
ulation to find
, ϕ', the cardi-
the combina-

hod of proce-
llows: If x is
point, its dis-
f, the focus of
must first be
Call this dis-
en the distance
ugate from the
f', supposing
o be removed,
nd by formula

$$o = \frac{f^2}{x},$$

7, $x = 1{\cdot}65$;

$$\frac{17}{35} = {\cdot}543.$$

distance from

distance from
sitive, the dis-
en f' and o is
; so o is to the



FIG. 88.

Before proceeding it will be as well to examine other possible cases which might occur.

Suppose that x was at the point f, then x would equal 0, and $o = \infty$; that is, o would lie at an infinite distance from f'. If, on the other hand, the point x was to the right of f, x would be negative, and o would be also negative, because f^2 is always positive; o would then be measured off to the left of f', and the conjugate would be virtual. This means that there will be no real image, because the rays will be divergent on the f' side of the lens, as if they had come from some focus on the f side of the lens. But to return. The point o having been found to be the conjugate of x, due to the sole influence of No. 1 lens, we have next to measure the distance between o and f'', and, by applying the same formula, find the distance of its conjugate from f''', owing to the exclusive effect of No. 2 lens now replaced. This distance Of'' may be found thus:

$$P'o = P'f' + f'o = \cdot 947 + \cdot 543 = 1\cdot 49;$$
$$P'f'' = P'B + BC + Qf'' = \cdot 21 + \cdot 25 + 1\cdot 875 = 2\cdot 335;$$
$$P'f'' - P'o = of'' = 2\cdot 335 - 1\cdot 49 = \cdot 845.$$

Calling this distance O, then, by formula $y\,O = f'''^2$, we shall find the distance of y from f''', which we shall call y. $y = \frac{f''^2}{O} = \frac{3\cdot 515}{\cdot 845}$ $= 4\cdot 16$, which is positive; therefore y lies 4·16 inches from f''' to the right hand. y is therefore the conjugate of x, due to the influence of both lenses 1 and 2. Similarly, the conjugate of any point on the *axis* may be found through any number of lenses.

Lens No. 1 : *Data.*—Radius $A = \frac{3}{4} = r$; radius $B = -1 = r'$; foci, f, f'; thickness $= \frac{1}{2} = d$; $\mu = \frac{3}{2}$; P = principal point measured from A; P′ = principal point measured from B

$$u = \frac{\mu - 1}{r} = \frac{\frac{3}{2} - 1}{\frac{3}{4}} = \frac{2}{3}; \quad u' = \frac{\mu - 1}{r'} = \frac{\frac{3}{2} - 1}{-1} = -\frac{1}{2};$$

$$\mu(u' - u) = \frac{3}{2}\left(-\frac{1}{2} - \frac{2}{3}\right) = -\frac{7}{4}; \quad d\,u\,u' = \frac{1}{2} \times \frac{2}{3} \times -\frac{1}{2} = -\frac{1}{6};$$

$$\mu(u' - u) - d\,u\,u' = -\frac{7}{4} + \frac{1}{6} = -\frac{19}{12} = -1\cdot 583;$$

$$P = A + \frac{d\,u'}{\mu(u' - u) - d\,u\,u'} = A + \frac{\frac{1}{2} \times -\frac{1}{2}}{-\frac{19}{12}} = A + \frac{3}{19}$$

$$= A + \cdot 158 \quad . \quad . \quad . \quad . \quad . \quad . \text{(i)}$$

$$P' = B + \frac{d\,u}{\mu(u' - u) - d\,u\,u'} = B + \frac{\frac{1}{2} \times \frac{2}{3}}{-\frac{19}{12}} = B - \frac{4}{19}$$

$$= B - \cdot 21 \quad . \quad . \quad . \quad . \quad . \quad . \text{(ii)}$$

$$f = P + \frac{\mu}{\mu(u'-u) - d\,u\,u'} = P + \frac{\frac{3}{2}}{-\frac{19}{12}} = P - \frac{18}{19}$$

$$= P - \cdot 947 \quad . \quad . \quad . \quad . \quad . \quad \text{(iii)}$$

$$f' = P' - \frac{\mu}{\mu(u'-u) - d\,u\,u'} = P' - \frac{\frac{3}{2}}{-\frac{19}{12}} = P' + \frac{18}{19}$$

$$= P' + \cdot 947 \quad . \quad . \quad . \quad . \quad . \quad \text{(iv)}$$

Lens No. 2 : *Data.*—Radius $C = -\frac{9}{8} = r$; radius $D = \infty = r'$; foci, f'', f'''; thickness $= \frac{1}{10} = d$; $\mu = \frac{8}{5}$; Q = principal point measured from C; Q′ = principal point measured from D.

$$u = \frac{\mu - 1}{r} = \frac{\frac{8}{5} - 1}{-\frac{9}{8}} = -\frac{8}{15}; \; u' = \frac{\mu - 1}{r'} = \frac{\frac{8}{5} - 1}{\infty} = 0;$$

$$\mu(u'-u) = \frac{8}{5}\left(0 + \frac{8}{15}\right) = \frac{64}{75}; \; d\,u\,u' = \frac{1}{10} \times -\frac{8}{15} \times 0 = 0;$$

$$\mu(u'-u) - d\,u\,u' = \frac{64}{75} - 0 = \frac{64}{75} = \cdot 853;$$

$$Q = C + \frac{d\,u'}{\mu(u'-u) - d\,u\,u'} = C + \frac{0}{\frac{64}{75}} = C + 0 \quad . \quad . \quad \text{(v)}$$

$$Q' = D + \frac{d\,u}{\mu(u'-u) - d\,u\,u'} = D + \frac{\frac{1}{10} \times -\frac{8}{15}}{\frac{64}{75}} = D - \frac{1}{16}$$

$$= D - \cdot 0625 \quad . \quad . \quad . \quad . \quad . \quad \text{(vi)}$$

$$f'' = Q + \frac{\mu}{\mu(u'-u) - d\,u\,u'} = Q + \frac{\frac{8}{5}}{\frac{64}{75}} = Q + \frac{15}{8} = Q + 1 \cdot 875 \quad \text{(vii)}$$

$$f''' = Q' - \frac{\mu}{\mu(u'-u) - d\,u\,u'} = Q' - \frac{\frac{8}{5}}{\frac{64}{75}} = Q' - \frac{15}{8}$$

$$= Q' - 1 \cdot 875 \quad . \quad . \quad . \quad . \quad \text{(viii)}$$

Both Lenses.—**Distance apart = B C = $\frac{1}{4}$ = ·25 ; P′ Q = ·21 + ·25 = ·46 = δ ; f = focus of No. 1 lens = ·947 ; f' = focus of No. 2 lens = − 1·875.**

$$E = P + \frac{\delta f}{f + f' - \delta} = P + \frac{\cdot 46 \times \cdot 947}{\cdot 947 - 1 \cdot 875 - \cdot 46} = P + \frac{\cdot 436}{-1 \cdot 388}$$

$$= P - 314 \quad . \quad . \quad . \quad . \quad . \quad \text{(ix)}$$

$$E' = Q' - \frac{\delta f'}{f + f' - \delta} = Q' - \frac{\cdot 46 \times -1 \cdot 875}{\cdot 947 - 1 \cdot 875 - \cdot 46}$$

$$= Q' - \frac{-\cdot 862}{-1 \cdot 388} = Q' - \cdot 621 \quad . \quad . \quad . \quad \text{(x)}$$

$$\phi = E - \frac{ff'}{f + f' - \delta} = E - \frac{\cdot 947 \times -1 \cdot 875}{\cdot 947 - 1 \cdot 875 - \cdot 46}$$

$$= E - \frac{-1 \cdot 775}{-1 \cdot 388} = E - 1 \cdot 28 \quad . \quad . \quad . \quad \text{(xi)}$$

$$\phi' = E' + \frac{ff'}{f + f' - \delta} = E' + \frac{\cdot 947 \times -1 \cdot 875}{\cdot 947 - 1 \cdot 875 - \cdot 46}$$

$$= E' + \frac{-1 \cdot 775}{-1 \cdot 388} = E' + 1 \cdot 28 \quad . \quad . \quad . \quad \text{(xii)}$$

$$xy = \phi^2; \quad y = \frac{\phi^2}{x} = \frac{1 \cdot 6384}{x} \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(xiii)}$$

CHAPTER III

THE HISTORY AND EVOLUTION OF THE MICROSCOPE

THE historic progression of the modern microscope from its earliest inception to its most perfect form is not only full of interest, but is also full of the most valuable instruction to the practical microscopist. In regard to the details of this, our knowledge has been greatly enriched during recent years. The antiquarian knowledge and zeal in this matter possessed by Mr. John Mayall, jun., and the unique and valuable collection of microscopes made by Frank Crisp, Esq., LLB., ranging as they do through all the history of the instrument, from its earliest employment to its latest forms, have furnished us with a knowledge of the details of its history not possessed by our immediate predecessors.

We may obtain much insight into the nature of what is indispensable and desirable in the microscope, both on its mechanical and optical sides, by a thoughtful perusal of these details. It will do more to enable the student to infer what a good microscope should be than the most exhaustive account of the varieties of instrument at this time produced by the several makers (always well presented in their respective catalogues) can possibly do. Availing ourselves of the material placed at our disposal by the generosity of these gentlemen, we shall therefore trace the main points in the origin and progress of the microscope as we now know it.

Mr. Mayall[1] gives what we must consider unanswerable reasons for looking upon the microscope, 'as we know and employ it,' as a strictly modern invention. Its occurrence at the period when the spirit of modern scientific research was asserting itself, and when the necessity for all such aids to physical inquiry and experimental research were of the highest value, is as striking as it is full of interest.

It may be held as fairly established that magnifying lenses were not known to the ancients, the simplest optical instruments as we understand them having no place in their civilisation.

A large number of passages taken from ancient authors, and having an apparent or supposed reference to the employment of magnifying instruments, have been collected and carefully criticised, with the result that all such passages can be explained without involving this assumption.

We learn from Pliny the elder and others, that crystal globes filled with water were employed for cauterisation by focussing the

[1] *Cantor Lectures on the Microscope*, 1886, p. 1.

sun's rays as a burning-glass, and that these were used to produce ignition; but there is no trace of suggestion that these refracting globes could act as magnifying instruments.

Seneca ('Quest. Nat.' i. 6, § 5) states, however, that 'letters though small and indistinct are seen enlarged and more distinct through a globe of glass filled with water.' He also states that 'fruit appears larger when seen immersed in a vase of glass.' But he only concludes from this that all objects seen through water appear larger than they are.

In like manner it could be shown that Archimedes, Ptolemy, and others had no knowledge of the principles on which refraction took place at curved surfaces.

Nor is there any ancient mention of spectacles or other aids to vision. Optical phenomena were treated of; Aristotle and the Greek physician Alexander dealt with myopy and presbyopy; Plutarch treated of myopy, and Pliny on the sight. But no allusion is made to even the most simple optical aids; nor is there any reference to any such instruments by any Greek or Roman physician or author. In the fifth century of the Christian era the Greek physician Actius says that myopy is incurable; and similarly in the thirteenth century another Greek physician, Actuarius, says that it is an infirmity of sight for which art can do nothing. But since the end of the thirteenth century, which is after the invention of spectacles, they are frequently referred to in medical treatises and other works.

If we turn to the works of ancient artists we find amongst their cut gems some works which reveal extreme minuteness of detail and delicacy of execution, and some have contended that these could only have been executed by means of lenses. But it is the opinion of experts that there is no engraved work in our national collection in the gem department that could not have been engraved by a qualified modern engraver by means of unaided vision; and in reference to some very minute writing which it was stated by Pliny that Cicero saw, Solinus and Plutarch, as well as Pliny, allude to these marvels of workmanship for the purpose of proving that some men are naturally endowed with powers of vision quite exceptional in their excellence, no attempt being made to explain their minute details as the result of using magnifying lenses.

These and many other instances in which reference to lenses must have been made had they existed or been known are conclusive; for it is inconceivable that even simple dioptric lenses, to say nothing of spectacles, microscopes and telescopes, could have been known to the ancients without reference to them having been made by many writers, and especially by such men as Galen and Pliny.

The earliest known reference to the invention of spectacles is found in a manuscript dating from Florence in 1299, in which the writer says, 'I find myself so pressed by age that I can neither read nor write without those glasses they call spectacles, lately invented, to the great advantage of poor old men when their sight grows weak.'[1] Giordano da Rivalto in 1305 says that the invention

[1] Smith's *Optics*, Cambridge, 1738, 2 vols. ii. pp. 12, 13.

of spectacles dates back 'twenty years,' which would be about 1285. It is now known that they were invented by Salvino d'Armato degli Armati, a Florentine, who died in 1317. He kept the secret for profit, but it was discovered and published before his death. But there is a singular evidence that a lens used for the purpose of magnification was in existence as early as between 1513 and 1520 for at that time Raphael painted a portrait of Pope Leo X. which is in the Palazzo Pitti, Florence. In this picture the Pope is drawn holding a hand magnifier, evidently intended to examine carefully the pages of a book open before him. But no instruments comparable to the modern telescope and microscope arose earlier than the beginning of the seventeenth century and the closing years of the sixteenth century respectively.

It is, of course, known that there is in the British Museum a remarkable piece of rock crystal, which is oval in shape and ground to a plano-convex form, which was found by Mr. Layard during the excavations of Sargon's Palace at Nimroud, and which Sir David Brewster believed was a lens designed for the purpose of magnifying. If this could be established it would of course be of great interest, for it has been found possible to fix the date of its production with great probability as not later than 721–705 B.C.



FIG. 89.

FIG. 90.—An Assyrian 'lens' (?).

A drawing of this 'lens' in two aspects is shown in figs. 89 and 90; but Mr. Mayall gives strong and clear reasons for concluding that its lenticular character as a dioptric instrument has certainly not been made out. There are cloudy striæ in it, which would prove fatal for optical purposes, but would be even sought for if it had been intended as a decorative boss; while the grinding of the 'convex' surface is not smooth, but produced by a large number of irregular facets, making the curvature quite unfit for optical purposes. In truth, it may be fairly taken as established that there is no evidence of any kind to justify us in believing that lenses for optical purposes were known or used before the invention of spectacles.

From the simple spectacle-lens, the transition to lenses of shorter and shorter focus, and ultimately to the combination of lenses into a compound form, would be—in such an age as that in which the invention of spectacles arose—only a matter of time. But it is almost impossible to fix the exact date of the production of the first microscope, as distinguished from a mere magnifying lens.

There is nevertheless a consent on the part of those best able to judge that it must have been between 1590 and 1609; while it is probable (but by no means certain) that Hans and Zacharias Janssen,

spectacle makers, of Middleburg, Holland, were the inventors. But it would appear that the earliest microscope was constructed for observing objects by reflected light only.

At the Loan Collection of Scientific Instruments in London in 1876 an old microscope, which had been found at Middleburg, was shown, which, Professor Harting considered, might possibly have been made by the Janssens. It is drawn in fig. 91, and consists of a combination of a convex object-lens and a convex eye-lens, which form was not published as an actual construction until 1646 by Fontana, which, as Mr. Mayall points out, does not harmonise with the assumption that this instrument was constructed by one of the Janssens.

FIG. 91. 'Janssen's' compound microscope.

It is strictly a compound microscope, and the distance between the lenses can be regulated by two draw-tubes. There are three diaphragms, and the eye-lens lies in a wood cell, and is held there by a wire ring sprung in. The object-lens, *a*, is loose in the actual instrument, but was originally fixed in a similar way to *b*.

It cannot be an easy task—if it be even a possible one—to definitely determine upon the actual individual or individuals by whom the compound microscope was first invented. Recently some valuable evidence has been adduced claiming its sole invention for Galileo. In a memoir published in 1888[1] Professor G. Govi, who has made the question a subject of large and continuous research, certainly adduces evidence of a kind not easily waived.

Huyghens and, following him, many others assign the invention of the compound microscope to Cornelius Drebbel, a Dutchman, in the year 1621; but it has been suggested that he derived his knowledge from Zacharias Janssen or his father, Hans Janssen, spectacle makers, in Holland, about the year 1590; while Fontana, a Neapolitan, claimed the discovery for himself in 1618. It is said that the Janssens presented the first microscope to Charles Albert, Archduke of Austria; and Sir D. Brewster states, in his 'Treatise on the Microscope,' that one of their microscopes which they presented to Prince Maurice was in 1617 in the possession of Cornelius Drebbel, then Mathematician to the Court of James I., where 'he made microscopes and passed them off as his own invention.'

Nevertheless we are told by Viviani, an Italian mathematician, in his 'Life of Galileo,' that 'this great man was led to the discovery of the microscope from that of the telescope,' and that 'in 1612 he sent one to Sigismund, King of Poland.'

We now receive evidence through the researches of Govi that the invention was solely due to Galileo in the year 1610. Professor Govi understands by 'simple microscope' an instrument 'consisting of a single lens or mirror,' and by 'compound microscope' one 'con-

[1] *Atti R. Acad. Sci. Fis. Nat. Napoli*, vol. ii. series ii. 'Il microscopio composto inventato da Galileo,' *Journ. R.M.S.* Pt. IV. 1889, p. 574.

sisting of several lenses or a suitable combination of lenses and mirrors.'

In a pamphlet published in 1881, treating of the invention of the binocular telescope, Govi pointed out that Chorez, a spectacle maker, in 1625, used the Dutch telescope as a microscope, and stated that with it 'a mite appeared as large as a pea; so that one can distinguish its head, its feet, and its hair—a thing which seemed incredible to many until they witnessed it with admiration.'

To this quotation he added :—

'This transformation of the telescope into a microscope (or, as opticians in our own day would say, into a Brücke lens) was not an invention of the French optician. Galileo had accomplished it in the year 1610, and had announced it to the learned by one of his pupils, John Wodderborn, a Scotchman, in a work which the latter had just published against the mad 'Peregrinazione' of Horky. Here are the exact words of Wodderborn (p. 7) :—

'Ego nunc admirabilis huius perspicilli perfectiones explanare nō conabor: sensus ipse iudex est integerrimus circa obiectum proprium. Quid quod eminus mille passus et ultra cum neque videre iudicares obiectum, adhibito perspicillo, statim certo cognoscas, esse hunc Socratem Sophronici filium venientem, sed tempus nos docebit et quotidianæ nouarum rerum detectiones quam egregie perspicillum suo fungatur munere, nam in hoc tota omnis instrumenti sita est pulchritudo.

'Audiueram, paucis ante diebus authorem ipsum Excellentissimo D. Cremonino purpurato philosopho varia narrantem scitu dignissima et inter cætera quomodo ille minimorum animantium organa motus, et sensus ex perspicillo ad vnguem distinguat; in particulari autem de quodem insecto quod utrumque habet oculum membrana crassiuscula vestitum, quæ tamen septē foraminibus ad instar larvæ ferreæ militis cataphracti terebrata, viam præbet speciebus visibilium. En tibi [so says Wodderborn to Horky] nouum argumentum, quod perspicillum per concentrationem radiorum multiplicet obiectū; sed audi prius quid tibi dicturus sum: in cæteris animalibus eiusdem magnitudinis, vel minoris, quorum etiam aliqua splendidiores habent oculos, gemini tantum apparent cum suis superciliis aliisque partibus annexis.'

To this Govi adds :—

'I have wished to quote this passage of Wodderborn textually, so that the honour of having been the first to obtain from the Dutch telescope a *compound* microscope should remain with Galileo, which the later called *occhialino*, and that the glory of having reduced the *Keplerian* telescope to a microscope (in 1621) should rest with Drebbel. The apologists of the Tuscan philosopher, by attributing to him the invention of the microscope without specifying with what microscope they were dealing, defrauded Drebbel of a merit which really belongs to him; but the defenders of Drebbel would act unjustly in depriving Galileo of a discovery which incontestably was his.'

I turn now to Wodderborn's account, published in 1610 (the date of the dedication to Henry Wotton, English Ambassador at Venice, is October 16, 1610), which reads thus :—

'I will not now attempt to explain all the perfections of this wonderful *occhiale* ; our sense alone is a safe judge of the things which concern it. But what more can I say of it than that by pointing a glass to an object more than a thousand paces off, which does not even seem alive, you immediately recognise it to be Socrates, son of Sophronicus, who is approaching? But time and the daily discoveries of new things will teach us how admirably the glass does its work, for in that alone lies all the beauty of that instrument.

'I heard a few days back the author himself (Galileo) narrate to the Most Excellent Signor Cremonius various things most desirable to be known, and amongst others in what manner he perfectly distinguishes with his telescope the organs of motion and of the senses in the smaller animals ; and especially in a certain insect which has each eye covered by a rather thick membrane, which, however, perforated with seven holes, like the visor of a warrior, allows it sight. Here hast thou a new proof that the glass concentrating its rays enlarges the object ; but mind what I am about to tell thee, viz. in the other animals of the same size and even smaller, some of which have nevertheless brighter eyes, these appear only double with their eyebrows and the other adjacent parts.'

After reading this document Govi judges that it is impossible to refuse Galileo the credit of the invention of a *compound microscope* in 1610, and the application of it to examine some very minute animals ; and if he himself neither then nor for many years after made any mention of it publicly, this cannot take away from him or diminish the merit of the invention.

It is not to be believed, however, that Galileo after these first experiments quite forgot the microscope, for in preparing the 'Saggiatore' between the end of 1619 and the middle of October, 1622, he spoke thus to Lotario Sarsi Segensano (anagram of Oratio Grassi Salonense) :—

'I might tell Sarsi something new if anything new could be told him. Let him take any substance whatever, be it stone, or wood, or metal, and holding it in the sun examine it attentively, and he will see all the colours distributed in the most minute particles, and if he will make use of a telescope arranged so that one can see very near objects, he will see far more distinctly what I say.'

It will not therefore be surprising if, in 1624 (according to some letters from Rome, written by Girolamo Aleandro to the famous M. de Peiresc), two microscopes of Kuffler, or rather Drebbel, having been sent to the Cardinal of S. Susanna, who at first did not know how to use them, they were shown to Galileo, who was then in Rome, and he, as soon as he saw them, explained their use, as Aleandro writes to Peiresc on May 24, adding, 'Galileo told me that he had invented an *occhiale* which magnifies things as much as 50,000 times, so that one sees a fly as large as a hen.'

This assertion of Galileo, that he had invented a telescope which magnified 50,000 times, so that a fly appears as big as a hen must, without doubt, be referred to the year 1610, and from the measure given of the amplification by the solidity or volume the



linear amplification (as it is usually expressed now) would have, been equal to something less than the cubic root of 50,000, that is, about 36, and that is pretty fairly the relative size of a fly and a hen.

Aleandro's letter of May 24 (1624) does not state at what time Galileo saw the telescope and explained the use of it, but another letter of Faber's to Cesi, amongst the autograph letters in the possession of D. B. Boncompagni, says (May 11): 'I was yesterday evening at the house of our Signor Galileo, who lives near the Madalena; he gave the Cardinal di Zoller a magnificent eye-glass for the Duke of Bavaria. I saw a fly which Signor Galileo himself showed me. I was astounded, and told Signor Galileo that he was another creator, in that he shows things that until now we did not know had been created.' So that even on May 10, 1624, Galileo had not only seen the telescope of Drebbel, and explained the use of it, but had made one himself and sent it to the Duke of Bavaria.

We lack documents to show how this microscope of Galileo was made, that is, whether it had two convergent lenses like those of Drebbel. A letter of Peiresc of March 3, 1624, says that 'the effect of the glass is to show the object upside down . . . and so that the real natural motion of the animalcule, which, for example, goes from east to west, seems to go contrariwise, that is, from west to east,' or whether it was not rather composed of a convex and a concave lens, like that made earlier by him, and used in 1610, and then almost forgotten for fourteen years.

It is, however, very probable that this last was the one in question, for Peiresc, answering Aleandro on July 1, 1624, wrote:— 'But the *occhiale* mentioned by Signor Galileo, which makes flies like hens, is of his own invention, of which he made also a copy for Archduke Albert of pious memory, which used to be placed on the ground, where a fly would be seen the size of a hen, and the instrument was of no greater height than an ordinary dining-room table.' Which description answers far better to a Dutch telescope used as a microscope, in the same way exactly as Galileo had used it, rather than to a microscope with two convex lenses.

One cannot find any further particulars concerning Galileo's *occhialini* (so he had christened them in the year 1624), either in Bartholomew Imperiali's letter of September 5, 1624, in which he thanks Galileo for having given him one in *every way perfect*, or in that of Galileo to Cesi of September 23, 1624, accompanying the gift of an *occhialino*, or in Federico Cesi's answer of October 26, or in a letter of Bartholomeo Balbi to Galileo of October 25, 1624, which speaks of the longing with which Balbi is awaiting 'the little *occhiale* of the new invention,' or in that of Galileo to Cesar Marsili of December 17 in the same year, in which Galileo says to the learned Bolognese 'that he would have sent him an *occhialino* to see close the smallest things, but the instrument maker, who is making the tube, has not yet finished it.' This, however, is how Galileo speaks of it in his letter to Federico Cesi, written from

Florence on September 23, 1624, more than three months after his departure from Rome :—

'I send your Excellency an *occhialino*, by which to see close the smallest things, which I hope may give you no small pleasure and entertainment, as it does me. I have been long in sending it, because I could not perfect it before, having experienced some difficulty in finding the way of cutting the glasses perfectly. The object must be placed on the movable circle which is at the base, and moved to see it all, for that which one sees at one look is but a small part. And because the distance between the lens and the object must be most exact, in looking at objects which have relief one must be able to move the glass nearer or further, according as one is looking at this or that part ; therefore the little tube is made movable on its stand or guide, as we may wish to call it. It must also be used in very bright, clear weather, or even in the sun itself, remembering that the object must be sufficiently illuminated. I have contemplated very many animals with infinite admiration, amongst which the flea is most horrible, the gnat and the moth the most beautiful ; and it was with great satisfaction that I have seen how flies and other little animals manage to walk sticking to the glass and even feet upwards. But your Excellency will have the opportunity of observing thousands and thousands of other details of the most curious kind, of which I beg you to give me account. In fact, one may contemplate endlessly the greatness of Nature, and how subtilely she works, and with what unspeakable diligence.—P.S. The little tube is in two pieces, and you may lengthen it or shorten it at pleasure.'

It would be very strange, knowing Galileo's character, that in 1624, and after the attacks made on him for having perhaps a little too much allowed the Dutch telescope to be considered his invention, he should have been induced to imitate Drebbel's glass with the two convex lenses, and have wished to make them pass as his own invention, whilst he had always used, and continued to use to the end of his days, telescopes with a convex and a concave lens without showing that he had read or in the least appreciated the proposal made by Kepler, ever since 1611, to use two convex glasses in order to have telescopes with a large field and more powerful and convenient.

In any case it is impossible to form a decided opinion on such a matter, the data failing ; but the very fact that from 1624 onwards Galileo thought no more of the *occhialino* (probably because he found it less powerful and less useful than the *occhiale* of Drebbel), as he had not occupied himself with it or had scarcely remembered it from the year 1610 to 1624, seems sufficient to show that the *occhialino*, like the microscope of 1610, was a small Dutch telescope with two lenses, one convex and one concave, and not a reduced Keplerian telescope like that invented by Drebbel in 1621.

The name of microscope, like that of telescope, originated with the Academy of the Lincei, and it was Giovanni Faber who invented it, as shown by a letter of his to Cesi, written April 13, 1625, and which is amongst the Lincei letters in the possession of D. B. Boncompagni. Here is the passage in Faber's letter :—

'I only wish to say this more to your Excellency, that is, that

you will glance only at what I have written concerning the new inventions of Signor Galileo; if I have not put in everything, or if anything ought to be left unsaid, do as best you think. As I also mention his new *occhiale* to look at small things and call it microscope, let your Excellency see if you would like to add that, as the Lyceum gave to the first the name of telescope, so they have wished to give a convenient name to this also, and rightly so, because they are the first in Rome who had one. As soon as Signor Rikio's epigram is finished, it may be printed the next day; in the meantime I will get on with the rest. I humbly reverence your Excellency.—From Rome, April 13, 1625. Your Excellency's most humble servant, GIOVANNI FABER (Lynceo).'

The Abbé Rezzi, in a work of his on the invention of the microscope, thought that he might conclude from the passage of Wodderborn, reproduced above, that Galileo did not invent the compound microscope, but gave a convenient form to the simple microscope, and in this way as good as invented it, for the Latin word used by Wodderborn, *perspicillum*, 'signified at that time, it is clear,' Rezzi says, 'no other optical instrument than spectacles or the telescope, never the microscope, of which there is no mention whatever in any book published at that time, nor in any manuscript known till then.'

But Rezzi was not mindful that on October 16, 1610, the date of Wodderborn's essay, the name of microscope had not yet been invented, nor that of telescope, which, according to Faber, was the idea of Cesi, according to others of Giovanni Demisiano, of Cephalonia, at the end, perhaps, of 1610, but more probably at the time of Galileo's journey to Rome from March 29 to June 4, 1611. If, therefore, the word microscope had not yet been invented, and if the telescope, or the *occhiale*, as it was then called, was by all named *perspicillum*, one cannot see why Wodderborn's *perspicillum* cannot have been a *cannocchiale* (telescope) smaller than the usual ones, so that it could easily be used to look at near objects, but yet a *cannocchiale* with two lenses, one convex and one concave, like the others, and, therefore, a real *compound microscope*, although not mentioned by that name either by Wodderborn or others. And, besides that, how could it be that Wodderborn beginning to treat 'admirabilis huius perspicilli,' that is, of the *telescope* in the first line, should then have called *perspicillum* a single lens in the eleventh line of the same page? Rezzi's mistake is easily explained, remembering that he had not under his eyes Wodderborn's essay, but only knew a brief extract reported by Venturi.

It thus appears as in the highest degree probable that Galileo, in 1610, was the inventor of the compound microscope; it was subsequently invented, or introduced, and zealously adopted in Holland; and when Dutch invention penetrated into Italy in 1624 Galileo attempted a reclamation of his invention (which was undoubtedly distinct from that of Drebbel); but as these were not warmly seconded and responded to abroad he allowed the whole thing to pass. Nevertheless the facts Govi gives are as interesting as they are important.

In regard to the discovery of the simple lens Govi points out

that after the year 1000, minds having reopened to hope and intellects to study, there began to dawn some light of science, so that in 1276 a Franciscan monk, Roger Bacon, of Ilchester, in his 'Opus Majus,' dedicated and presented by him to Clement IV., could show many marvellous things, and amongst these the efficacy of *crystal* lenses, in order to show things larger, and in this wise he says make of them 'an instrument useful to old men and those whose sight is weakened, who in such a way will be able to see the letters sufficiently enlarged, however small they are.' As long as no documents anterior to him are discovered, Roger Bacon may be considered the first inventor of convergent lenses, and therefore of the *simple microscope*, however small the enlargement by his lenses may have been.

As, however, that man of rare genius, the initiator of experimental physics, had brought on himself the hatred of his contemporaries, they kept him for many years in prison, then shut him up in a convent of his order to the end of his long life of nearly eighty years. His writings had to be hidden, at least those treating on natural science, to save them from destruction, and so the invention of lenses, or the knowledge of their use to enlarge images and to alleviate the infirmities of sight, remained unknown or forgotten in the pages of the famous 'Opus Majus,' which only came to light in 1733 by the care of Samuel Jebb, a learned English doctor.

A Florentine, by name Salvino degli Armati, at the end of the thirteenth century (?1280) (in Bacon's lifetime), had therefore the glory of inventing spectacles, and it was a monk of Pisa, Alexander Spina, who suddenly charitably divulged the secret of their construction and use.



FIG. 92.—Descartes' simple microscope with reflector.

Perhaps Salvino degli Armati and Spina really discovered more than Roger Bacon had discovered; that is, they found out the use of converging lenses for long-sighted people, and of diverging lenses for short sight, whilst the English monk had only spoken of the lenses for long-sight, and perhaps they added to this first invention the capability of varying the focal lengths of the lenses according to need, and the other of fixing them on to the visor of a cap to keep them firm in front of the eyes, or to fasten them into two circles made of metal, or of bone joined by a small elastic bridge over the nose. However it may be, the discovery of spectacles, or, as it may be called, of the *simple microscope*, may be equally divided between Roger Bacon and Salvino degli Armati, leaving especially to the latter the invention of spectacles.

The earliest known illustration of a simple microscope is given by Descartes in his 'Dioptrique' in 1637: fig. 92 reproduces it. It is practically identical with one devised by Lieberkühn a century after and shown

on p. 138. A lens is mounted in a central aperture in a polished concave metal reflector. Descartes apparently devised another and much more pretentious instrument, but it appears impracticable and could never have existed save as a suggestion. But he appears to have been the first to publish figures and descriptions for grinding and polishing lenses.

In the Museo di Fisica there

FIG. 93.— Galileo's microscopes.

FIG. 94.—Campani's microscope (? 1686).

are two small microscopes which it is affirmed have been handed down from generation to generation since the dissolution of the Accademia del Cimento in 1667, with the tradition of having been constructed by Galileo. They are shown in fig. 93, but from the superiority of construction of these instruments it is very improbable that they belong to the days of Galileo, who died in 1642; and there is a specially interesting compound

microscope, by Giuseppe Campani, which was published first in 1686, which is presented in fig. 94 ; its close similarity to 'Galileo microscopes' is plainly apparent, making it still more improbable that these could be given a date prior to 1642.

In a journal of the travels of M. de Monconys, published in 1665, there is a description of his microscope which is of much interest. He states that the distance from the object to the first lens is one inch and a half ; the focus of the first lens is one inch ; the distance from the first lens to the second is fifteen inches ; the focus of the second lens, one inch and a half ; distance from the second to the third, one inch and eight lines ; the focus of the third lens, one inch and eight lines ; and the distance from the eye to the third lens, eight lines.

This would form the data of a practical compound microscope with a field lens ; and as Monconys had this instrument made in 1660 by the 'son-in-law of Viselius,' *it becomes probable in a very high degree that to him must be attributed the earliest device of a microscope with a field-lens.*

In 1665 Hooke published his 'Micrographia,' giving an account and a figure of his compound microscope. He adopted the field-lens employed by Monconys and gives details as to the mode and object

FIG 95.—Hooke's compound microscope (1665).

of its employment, which are at once interesting and instructive; for they show quite clearly that it was not employed by him to correct the spherical aberration of the eye-lens, but merely to increase the size of the field of view. He tells us that he used it 'only when he had occasion to see much of an object at once. . . . But whenever I had occasion to examine the small parts of a body more accurately I took out the middle glass (field-lens) and only made use of one eye-glass with the object-glass.'

Fig. 95 is a reproduction of the original drawing, and the general design appears to be claimed by Hooke. There is a ball-and-socket movement to the body, of which he writes: 'On the end of this arm (D, which slides on the pillar C C) was a small ball fitted into a kind of socket F, made in the side of the brass ring G, through which the small end of the tube was screwed, by means of which contrivance I could place and fix the tube in whatsoever posture I desired (which for many observations was exceedingly necessary), and adjusted it most exactly to any object.'

It need hardly be remarked that, useful as the ball-and-socket joint is for many purposes in microscopy, it is not advantageously employed in this instrument.

Hooke devised the powerful illuminating arrangement seen in the figure, and employed a stage for objects based on a practical knowledge of what was required. He described a useful method of estimating magnifying power, and was an industrious, wide, and thoroughly practical observer. But he worked without a mirror, and the screw-focussing arrangement seen in the drawing must have been as troublesome as it was faulty. But as a microscopist, Hooke gained a European fame, and gave a powerful stimulus to microscopy in England.

In 1668 a description was published in the 'Giornale dei Letterati' of a compound microscope by Eustachio Divini, which Fabri had previously commended. It was stated to be about 16½ inches high, and adjustable to four different lengths by draw-tubes, giving a range of

FIG. 96.—Divini's compound microscope.

magnification from 41 to 143 diameters. Instead of the usual bi-convex eye-lens, two plano-convex lenses were applied with their convex surfaces in contact, by which he claimed to obtain a much flatter field. Mr. Mayall found in the Museo Copernicano at Rome a microscope answering so closely to this description that he does not hesitate to refer its origin to Divini. He made the sketch of it given in fig. 96. But the optical construction had been tampered with and could not be estimated.



FIG. 97.—Chérubin d'Orléans' compound microscope.

Chérubin d'Orléans published, in 1671, a treatise containing a design for a microscope, of which fig. 97 is an illustration. The scrolls were of ebony, firmly attached to the base and to the collar encircling the fixed central portion of the body-tube. An exterior sliding tube carried the eye-piece above on the fixed tube, and a similar sliding tube carried the object-lens below, these sliding tubes serving to focus the image and regulate (within certain limits) the magnification. He also suggested a screw arrangement to be applied beneath the stage for focussing. He devised, or recommended, several combinations of lenses for the optical part of the microscope, and refers to combinations of three or four separate lenses, by which objects could be seen erect, which he considered 'much to be preferred.'

He also invented a binocular form of microscope and published it in his work, 'La Vision Parfaite,' in 1677. It consisted of two compound microscopes joined together in one setting, so as to be

...ssible to both eyes at once; a segment of each object-lens ...upposed to be of one-inch focus) was ground away to allow the ...nvergent axes starting from the two eyes to meet at about 16 ...ches distance at the common focus. Mechanism was provided for ...gulating the width of the axes to correspond with the observer's ...es.



FIG. 98.



FIG. 99.—Chérubin d'Orléans' binocular microscope (1685).

...ig. 98, showing the optical construction, is copied from the ...nal diagram ('La Vision Parfaite,' tab. i. fig. 2, p. 80). ... drawing of this binocular, as known to Zahn, was given in ...rst edition of his 'Oculus Artificialis' in 1685 (Fundamen III. ...3), and is reproduced in fig. 99.

... 1672 Sir Isaac Newton communicated to the Royal Society

a note and diagram for a reflecting microscope; we have, however, no evidence that it was ever constructed. But in 1673 Leeuwenhoek began to send to the Royal Society his microscopical discoveries. Nothing was known of the construction of his instruments, except that they were simple microscopes, even down to so late a period as 1709. We know, however, that his microscopes were mechanically rough, and that optically they consisted of simple bi-convex lenses, with worked surfaces mounted between two plates of thin metal with minute apertures through which the objects were directly seen. At his death Leeuwenhoek bequeathed a cabinet of twenty-six of his microscopes to the Royal Society; unhappily, they have mysteriously disappeared. But Mr. Mayall was enabled to figure one lodged in the museum of the Utrecht University, which is given in figs. 100 and 101 in full size. It is seen on both sides. The lens is seen in the upper third of the plate. It has a $\frac{1}{4}$-inch focus. The object is held in front of the lens, on the point of a short rod, with screw arrangements for adjusting the object under the lens.



FIG. 100. FIG. 101.

Leeuwenhoek's microscope.

Many modifications of this and the preceding instruments are found with some early English forms, but no important constructive or optical modification immediately presents itself. But some ingenious arrangements are found in the simple microscopes devised by Musschenbroek in the early years of the eighteenth century.

Grindl figured a microscope in his 'Micrographia Nova' in 1687, in which optical modifications arise. Divini had, as was stated, combined two plano-convex lenses, with their convex surfaces facing, to form an eye-piece: this idea was carried further in 1668 by a London optician, who used two pairs of these lenses; Grindl did this also, but in addition he used two similar (but smaller) lenses in the same manner as an objective. The form of the microscope itself was copied from that of Chérubin d'Orléans (fig. 97), but was modified by the application of an external screw.

In 1691 Bonanni modified preceding arrangements by devising a means of clipping the object between two plates pressed away from the object-lens by a spiral spring, the focussing being then effected by a 'screw barrel.'

This system of focussing was employed in a more practical form by Hartsoeker in 1694 and was adopted by Wilson in 1702. It became a very popular form for the microscope in the eighteenth century.

We are indebted to Bonanni also for originating a horizontal form of microscope, which is interesting and which, in a drawing of the instrument, is shown to possess a sub-stage *compound condenser fitted with focussing arrangements for illuminating transparent objects.*

In Hartsoeker's microscope 'the lens-carrier A B, fig. 102 (on which the cell P, containing the lens, is screwed), screws into the body O C, Q D at O Q ; the thin brass plates E and F fit within the body, the portions cut out allowing them to slide on the short pillars O C and Q D, and the spiral spring pressing them towards C D ; the object-slides, or an animalcule cage G H (hinged at *a b* to allow the



FIG. 102.—Hartsoeker's simple microscope (1694).

lid G to fit into H, enclosing the objects between strips of talc), slide between the plates E and F when in position, and the "screw barrel" I K fits into the screw-socket C D and regulates the focussing ; a condensing lens, N, fits on a second "screw-barrel," L M, which is applied in the screw socket of I K. This arrangement of the condenser is better than the plan adopted by Wilson, as it allows the illumination to be focussed on the object independently of the focal adjustment of the object to the magnifying lens ; whereas in Wilson's microscope, the condenser being mounted in I K, without facility of adjustment, remained at a fixed distance from the object, and hence the control of the illumination was very limited.'

In Harris's 'Lexicon Technicum' (1704, 2 vols. fol.), under the word microscope, Marshall's compound microscope (fig. 103) is described and figured. Several important innovations in microscopical construction were here embodied. (1) A fine-adjustment screw F


JOHN MARSHALL'S
New Invented
DOUBLE MICROSCOPE,
For Viewing the
CIRCULATION of the BLOOD
Made & Sold by him at the Archimedes &
Golden Spectacles in Ludgate Street.
B
X
W
K
A 1
A 2
H
I
G
F
E
D
C
N
O
P
Q
R
S
Z
B Lens delin. J Stuart sculp.

FIG. 103.

FIG. 104.—Hertel's microscope (1716).

is connected with the sliding socket E, supporting the arm D, in which the body-tube is screwed; the focussing could thus be controlled in a far more effective manner than by any system previously applied to a large microscope. The previous systems involved the direct movement of the body-tube either by rotating in a screw-socket (as in Hooke's) or by sliding in a cylindrical socket (as in Divini's and Chérubin's); in a few instances the object was moved in relation to the object-lens, but all these plans were more or less defective, especially with microscopes of large dimensions. Marshall's system was a distinct mechanical improvement, for the object could now be viewed during the actual process of focussing, as the image would remain steadily in the field. (2) A fork, N N, is here applied with a thumb-screw clamp, O, on the pillar itself. (3) Hooke's ball-and-socket joint, which was applied to the arm I, is here shifted to the lower end of the pillar, where it would give the movements of inclination to the whole microscope instead of to the body-tube only, as in Hooke's; the ball L could be tightly clamped by the screw collar M, in which slots were cut to give spring. (4) A condensing lens on jointed arms appears; this probably was the first application of such adjustments to the condenser. From the singular position of the candle beneath the condenser, we may infer, without doubt, that the mirror was still unknown as a microscopical accessory in England.

In fact, in no microscope up to this time has there been any trace of, or reference to, a mirror; but in 1716 Hertel employed it and introduced some other considerable modifications. The general appearance of the instrument as originally figured by Hertel is given in fig. 104. Not only have we the mirror below the stage, but also above the stage a concave metal mirror reflecting light through a condenser on the object, while the stage is movable on a pillar support. The body-tube is hinged and is inclined by a screw-sector mechanism.

In 1738 Dr. N. Lieberkühn devised, what had been employed in principle by Descartes a century before,[1] the instrument that has ever since been known by his name, and which is still of considerable value to the microscopist. Fig. 105 is a reproduction from the earliest drawing known of Lieberkühn's microscope. A A is a concave mirror of silver; from its form the light is reflected from it to a focus on the object C. The mirror is pierced in the centre at B and the lens, or object-glass, is inserted and adjusted, the eye being placed behind in the direction D at any point the single lens or a combination might require.



FIG. 105.—Lieberkühn's microscope.

'A Pocket Reflecting Microscope' was figured by Benjamin Martin in his 'Micrographia Nova' in 1742, having the interesting feature of a micrometer eye-piece depending on a screw with a

[1] See pp. 128–9.

certain number of threads to the inch, and by which accurate measurements could be taken. It was called a *reflecting* microscope because it had a mirror fitted into its cylindrical base; but it was, in reality, a compound refracting form, and appears to have a good claim to have been the original from whence the modern 'drum' microscopes were taken.

But Martin originated a large number of improvements both in the optical arrangements and the mechanism of the microscope, and was an excellent maker. He applied rack-and-pinion focussing adjustments, to the compound microscope he added inclining movements to the pillar carrying the stage and mirror, and he furnished the stage with rectangular movements.



FIG. 106.—Martin's large universal microscope as used by Quekett.

It was to this maker that the late Professor Quekett was indebted for an early microscope, of which he evidently to the last thought highly, and which he subsequently gave to the Royal Microscopical Society. A drawing of this instrument is given in fig. 106, and should be described in Quekett's own words. He says: 'It stands about two feet in height, and is supported on a tripod base, A; the central part or stem, B, is of triangular figure, having a rack at the back, upon which the stage, O, and frame, D, supporting the mirror, E, are capable of being moved up or down. The compound body, F, is three inches in diameter; it is composed of two tubes, the inner of which contains the eye-piece, and can be raised or depressed by rack and pinion, so as to increase or diminish the magnifying power. At the base of the triangular bar is a cradle joint, G, by which the instrument can be inclined by turning the screw-head, H [connected with an endless screw acting upon a worm-

wheel]. The arm, I, supporting the compound body, is supplied wi a rack and pinion, K, by which it can be moved backwards and f wards, and a joint is placed below it, upon which the body can turned into a horizontal position ; another bar carrying a stage a mirror can be attached by the screw, L N, so as to convert it intc horizontal microscope. The stage, O, is provided with all the us apparatus for clamping objects, and a condenser can be applied to under surface ; the stage itself may be removed, the arm, P, s porting it, turned round on the pivot C, and another stage exquisite workmanship placed in its stead, the under surface which is shown at Q.

'This stage is strictly a micrometer one, having rectangu movements and a fine adjustment, the movements being acco plished by fine-threaded screws, the milled heads of which graduated. The mirror, E, is a double one, and can be raised depressed by rack and pinion ; it is also capable of removal, and apparatus for holding large opaque objects, such as minerals, can substituted for it. The accessory instruments are very numero and amongst the more remarkable may be mentioned a tube, M, c taining a speculum, which can take the place of the tube, R, and form a reflecting microscope. The apparatus for holding animalcu or other live objects, which is represented at S, as well as a plate glass six inches in diameter, with four concave wells ground in can be applied to the stage, so that each well may be brought succession under the magnifying power. The lenses belonging this microscope are twenty-four in number ; they vary in fo length from four inches to one-tenth of an inch ; ten of them supplied with Lieberkühns. A small arm, capable of carrying sin lenses, can be applied at T, and when turned over the stage the strument becomes a single microscope ; there are four lenses suita for this purpose, their focal length varying from $\frac{1}{10}$th to $\frac{1}{40}$th of inch. The performance of all the lenses is excellent, and no pa appear to have been spared in their construction. There numerous other pieces of accessory apparatus, all remarkable for beauty of their workmanship.'[1]

Cuff designed and made a microscope, which Baker figured a described in his 'Employment for the Microscope' in 1753, wh possessed several conveniences and improvements. Not the le of these is that which gives greater delicacy to the fine adju ment than is found in any preceding model. It was subsequen further improved by the addition of a cradle joint at the bottom the pillar by Adams. Cuff also designed a simple form of micromet

There were three designs of microscopes by George Adams, London, in 1746 and 1771, which have many points of interest, scarcely contribute enough of distinctive improvement to the mod forms of the microscope to detain us long. That designed in 177 figured in the Adams 'Micrographia Illustrata,' and is reprodu in fig. 107.

In this instrument Adams claims to have embodied a number

[1] *A Practical Treatise on the Use of the Microscope*, 3rd ed. London, 1855, pp. 25, 26.


THE VARIABLE MICROSCOPE
By George Adams, N°. 60, Fleet Street, LONDON.
N°. 9
N°. 1
N°. 2
N°. 5
N°. 3
N°. 6
N°. 7
N°. 8
N°. 10
N°. 11
N°. 12
A
B
C
D
E
F
M
N
O
P
Q
Z

Fig. 107

improvements on all previous constructions. He applied 'two eye-glasses at A, a third near B, and a fourth in the conical part between B and C,' by which he increased 'the field of view and of light'; draw-tubes were at A and B, by which these lenses could be separated more or less. He also arranged the object-lenses, or 'buttons,' *a* and *b*, to be combined; seven 'buttons' were provided, 'also six silver specula ['Lieberkühns'] highly polished, each having a magnifier adapted to the focus of its concavity, one of which is represented at *e*,' and the 'buttons' could also be used with 'any one of these specula' by means of the adapter, *d*.

The body-tube, A B C, with its arm, F (in which it screwed at *f*), and stem attachment with the fine adjustment were clearly modified from a design which Cuff originated. The large ivory head, I, actuated a pinion and rack for raising or depressing the body-attachment on the stem. The stage and mirror were adjustable on the stem. The large ratchet-wheel controlled by the pinion-handle, S, gave the required inclination to the stem.

Nos. 1 and 2 were ivory and glass 'sliders' for objects, to be applied in the spring-stage No. 3 fitting at T; the 'hollow at K [No. 3] is to receive the glass tube No. 10.' No. 4 was a diaphragm fitting in the lower end of No. 3, 'to exclude some part of the light which is reflected from the mirror Q.' The forceps, No. 5, could be placed 'in one of the small holes near the extremities of the stage, or in the socket, R, at the end of the chain of balls No. 6.' No. 6 was an arm composed of a series of ball-and-socket joints, similar to the system employed by Musschenbroek, by Joblot, and by Lyonet, and was intended to be applied at W, when the stage was removed. No. 7 was a box of ivory in which discs of talc and brass rings were packed; No. 8, a hand-magnifier; No. 9, a sliding arm lens-carrier fitting on Z, when the instrument was required to be used as a simple microscope; No. 11, a rod of wire with spiral at the end for picking up soft objects from bottles &c.; and No. 12, an ivory disc, black on one side and white on the other, fitting at T, to carry opaque objects.

To use the instrument as a simple microscope the body-tube, A B C, was removed from the ring, F; the lens-carrier, No. 9, was placed on Z, and a lens with reflector, E, screwed in the ring, *c*; the ball-and-socket arm, No. 6, was applied at W, by the part X, and the object held by either of the forceps could be turned and viewed as desired. For dissections &c. the stage could be screwed on at F, and a glass plate applied at T.

One of the best examples of this design that Mr. Mayall has seen we learn has a nose-piece with a slide carrying three objectives—one of the first arrangement of 'triple nose-piece,' or, indeed, of changing nose-piece for objectives (as distinguished from simple lens-carriers) that has been met with.

A microscope devised by Dellebarre was made the subject of a special report to the 'Académie des Sciences' in June 1777, but there is nothing in it deserving special consideration in comparison with contemporary or even anterior forms as bearing upon the evolution of the microscope as we now know it. In fact, up to the time when achromatism exerted so powerful an influence upon the form

and construction of the instrument, there is no microscope that calls for further consideration save one—by an English maker named Jones—it was called Jones's 'Most Approved Compound Microscope and Apparatus,' and although, in principle, it does not differ from Adams's instrument, fig. 107, it yet presented differences of detail. Its date was 1798, and is seen in fig. 108, which is taken from the original figure in Adams's 'Essays on the Microscope.'



JONES'S *MOST IMPROVED COMPOUND MICROSCOPE AND APPARATUS.*

FIG. 108

The base is a folding tripod, and the stem inclines upon a compass-joint on the top of the pillar. Mr. Mayall justly remarks that this was the best system devised up to this date. The arm carrying the body-tube can be rotated on the top of the limb E, and is also provided with a rack and pinion D. An extra carrier, W, is provided for special purposes pivoting at S, so that objects will remain in the optic axis though the stage be moved in arc. There are also clips provided for the stage. There is a condenser at U, which slides on the stem by the socket *u*. The mirror also slides on the stem. There is provided a rotating multiple disc, P, of object-lenses, and a brass cell contains a high power, of $\frac{1}{30}$ or $\frac{1}{40}$ inch focus, which on the removal of the lens-disc can be screwed into the nose-piece.

There were also designed some interesting forms of reflecting microscope, to the details of which we can afford no space, their influence having been of no value in the development of the microscope as we know it. There was a reflecting microscope suggested by Sir

Isaac Newton in 1672, and one was devised on the principle of the Gregorian Telescope by Barker in 1736 ; another of the Cassegrainian form was made in 1738 by Smith, which was, perhaps, the most perfect of the Catoptric forms.

An outline of its construction and the path of the light-beams is given in fig. 109. It was for examining transparent objects and was similar to the Cassegrainian telescope, but with an extra long eye-piece tube to permit the focussing by movement of the eye-lens. The object was placed at M N ; the image was taken up by the concave, reflected on the convex, and again reflected to the eye-lens. He advised the use of a condensing lens for the illumination, to prevent 'the mixture of foreign rays with those of the object,' otherwise the instrument gave confused images of distant objects when it was used as a microscope.

Even without a condenser there are good images attainable with



FIG. 109.—Smith's reflecting microscope (1738).

this instrument, but with the condenser it would be, of course, improved.

We have not followed in any detail the forms of simple microscopes as they presented themselves, but in 1755 a form was made by Cuff that can only be regarded as the precursor of the most complete and perfect of our simple dissecting microscopes : it is shown in fig. 110. A disc of plane glass, C, or a concave, M, was applied, on the stage of which dissections &c. could be made ; a mirror, I, was fitted in a gimbal with a stem sliding in a socket in the pillar ; the lens-carrier, F, alone, or with Lieberkühn, F, screwed in a ring on the end of a horizontal arm, E, sliding through a socket, attached to a vertical rod, D, sliding and rotating in a socket at the back of the pillar for focussing &c. The pillar screwed on the lid of the box, within which the instrument was packed with sundry accessories.

It was to the discovery of achromatism as applied to microscopic object-glasses that we must attribute the strictly scientific value and

progress in development of this now extremely valuable and beautiful instrument. An exhaustive account of the earliest discovery and progressive application to our own day of achromatism, so far as it can be given in this treatise, will be found in the chapter on objectives. We can here only attempt, for the sake of completeness, a very broad outline of the facts.

Martin appears to have constructed an achromatic objective in 1759, but no results of practical value were obtained, Martin having formed the judgment that his achromatic microscope was not equal to a reflecting microscope with which he compared it. But it certainly gives him a place of interest in the history of the achromatism of object-glasses for the microscope.

FIG. 110.—Ellis's aquatic microscope (1755).

In 1762 Euler began to discuss the theory of achromatic microscopes, and in 1771, in his 'Dioptrica,' he entered upon the subject at more considerable length. A pupil of his, named Nicholas Fuss, published in St. Petersburg, in 1774, a volume entitled 'Detailed instruction for carrying lenses of different kinds to a greater degree of perfection, with a description of a microscope which may pass for the most perfect of its kind, taken from the dioptric theory of Leonard Euler, and made comprehensible to workmen by Nicholas Fuss.' This was translated into German by Klügel in 1778, but no result of these discussions of the theory of achromatism can be discovered earlier than 1791, when François Beeldsnyder made an achromatic objective which was presented by Harting to the museum of the University of Utrecht; but it was far from satisfactory. It

was composed of two biconvex crown-glass lenses, and a biconcave flint lens placed between them.

C. Chevalier tells us [1] that between 1800 and 1810 M. Charles, of the 'Institut,' Paris, made small achromatic lenses; but they were too imperfect to be of real service. In 1811 Fraunhofer made achromatic doublets with no great success; and in 1823–4 an achromatic microscope was made by the Messrs. Chevalier, with four doublet lenses arranged according to a plan devised by Sellique. Their 'Microscope d'Euler' followed, and in 1827 Amici constructed a horizontal microscope on achromatic principles, which was spoken well of. But while up to a very recent date it was common to assert that the first to suggest the plan of combining two, three, or four plano-convex achromatic doublets of similar foci, one above the other, to increase the power and aperture was Sellique in 1823, it is now known that this had been anticipated by Marzoli (ch. v. p. 302). Sellique's plan was carried into execution by the Messrs. Chevalier. The instrument embodying this plan is shown in fig. 111.



FIG. 111.—Sellique's achromatic microscope (1823–4).

In a report to the Académie Royale des Sciences, the well-known mathematician Fresnel says, concerning this microscope, that in comparing the objectives with those of one of Adams's best non-achromatic instruments —that up to a magnification of two hundred times—Sellique's was decidedly superior; but beyond that magnification there was no superiority in the achromatic form, and he preferred Adams's form for prolonged observations because it gave a larger field than Sellique's.

The mechanism of this microscope was similar to the English model of Jones, shown at fig. 108. The focussing was by rack and pinion acting on the stage, the pinion remaining stationary and not travelling on the rack. Two draw-tubes, A and B, were applied

[1] *Des Microscopes*, Paris, 1839, p. 86.

within the body-tube, C, the upper one having a biconcave lens, S, at the lower end, serving as an amplifier, which was probably the first application of a 'Barlow lens' to a microscope.

Illumination for opaque objects was accomplished by a lenticular prism, P, which was gimballed, and connected with a ring embracing the body-tube.

We learn from Fresnel that the range of magnification was from 40 to 1200 diameters. The object-glasses were composed either of two doublet systems for low-power work or of four doublet systems all screwed together for high-power work, and two oculars were provided of different power.

FIG. 112.—Tully's achromatic microscope.

It is interesting to place one of the earliest known English models of the achromatic microscope beside that of Sellique. It was made by Tully the optician, of London, who at Dr. Goring's instance had been working at the achromatising of the microscope. Sellique's is a manifest modification of one of the best forms as made by Adams, Jones, or Dollond. Tully, aided by Joseph J. Lister, discovered that great accuracy of workmanship and complete steadiness in the stand were needful for achromatic microscopes, and to this end he adopted struts, such as were used in telescopes, connecting the body-tube with the base. The instrument is shown in fig. 112. He also provided mechanical movements to the stage, but no fine adjustment was applied. There was a sub-stage provided with a rotating disc of graduated diaphragms. This microscope was made in all probability about the year 1826.

As compared with single lenses of equal power, from which so much light was inevitably stopped out by the small diaphragm that

it was needful to use in order to secure a fair image, the objectives used with this instrument gave a vast increase of light by permitting the employment of the full aperture.

An extremely interesting instrument by C. Chevalier, made very probably not long after 1824, and bearing much resemblance to that of Sellique, is shown in fig. 113. It is provided with a revolving disc of diaphragms applied below the dark chamber under the stage, and this is a plan which obtained a permanent place in the microscopes of the future.

FIG. 113.—C. Chevalier's achromatic microscope.

The report of Fresnel concerning Sellique's achromatic microscope determined Professor Amici, who for nine years had abandoned his experiments on achromatic object-glasses, to recommence them in 1826, and in 1827 he exhibited in Paris and in London a horizontal microscope. The real novelty shown in it was the application of a right-angled prism immediately above the objective to deflect the rays through the horizontal body-tube. The object-glasses were composed of three lenses superposed, each having a focus of three lines and a greatly increased aperture. It had also extra eye-pieces by means of which the amplification could be increased.

Meantime the subject of achromatism was engaging the attention of the most distinguished English mathematicians. Sir John Herschel, Sir George (then Professor) Airy, Professor Barlow, Mr. Coddington, and several others, worked with some vigour at the subject. Also, for some years, Joseph J. Lister had been earnestly working experimentally and mathematically on the same subject, and he discovered certain properties in an achromatic combination, which were of importance, although they had not been before observed.[1] In 1829 a paper from Lister was received and published by the Royal Society,[2] and putting the principles it laid down into practice, Lister was enabled to obtain a combination of lenses capable of transmitting a pencil of 50° with a large corrected field. This paper and its results exerted a very powerful influence on the immediate improvement of English achromatic object-glasses, and formed a

[1] *Vide* Objectives, Ch. V. p. 304.

[2] *Trans. Roy. Soc.* for 1829.



FIG. 114.—One of Ross's earliest forms.

permanent basis of advancement for the microscope, not o its optical, but also indirectly in its mechanical constructi refinements.

Fig. 115.—Pritchard's microscope with 'Continental' fine adjustment.

For convenie this point we m vance a little in c complete our bri line of the mec application of ac tism to object- Mr. A. Ross practically acq with the princi achromatism as to combinations o in working with fessor Barlow c subject, and havi plied Lister's pri with great succ discovered, as w already pointed Ch. I.,[1] that by c the object under nation by a thin glass or talc the tions were distu they had been ada an uncovered obje we have seen tha in 1837 that R vised a simple m correcting this. an indefatigable in the interests advancement of t chanical as well optical side of t croscope. Fig. 1 sents an early f one of Ross's earl croscopes, from an example, which is issued under Prit name. The st actuated in diag rections on either the stem, and its form coincides with one which Mr. Mayall assigns to Pritchard, which fig. 115 illustrates. It has the same kind

[1] P. 20.

movement and general construction, but it will be seen that it has also a curious spiral fine adjustment, which is plainly an uncovered 'Continental' form, either adopted in England from G. Oberhäuser, or it may have even preceded it. It is interesting to note, however, that the sub-stage arrangements in both these instances are the same as those employed by Wollaston in connection with his celebrated doublets, an account of which was given in the Philosophical Transactions of that date.[1]

The Ross form cannot be inclined, nor can the Pritchard; and 'the fine adjustment in the former is effected by means of a long screw passing up the pillar and acting on a triangular sheath, within which the stem is applied, to move with rack and pinion, the top of the stem being hollow to receive either the cross-arm support for the single lens or the limb of the compound body. The screw is actuated by a large, graduated, milled head above the tripod.'

The stage has supports, evidently to enable dissection to be effected without flexure by the weight or pressure of the hands. Rectangular mechanical movements are employed acting diagonally on either side of the stem by rather fine screws, so that the motions are slow; which is a desideratum not always found even in our best instruments to-day.

It was A. Ross, however, who successfully applied the long-lever system of fine adjustment acting on the nose-piece, and to which we shall again refer,[2] since it is the most perfect mode of accomplishing fine adjustment that we now know of, and in its most perfect form is used in the microscope of the highest class (that by Messrs. Powell and Lealand) made in the present day.

FIG. 116.—A Ross microscope.

But A. Ross at an early period worked out a 'Jackson' form of microscope, with the limb supporting the body-tube. He applied

[1] *Trans. Roy. Soc.* 1829.

[2] P. 161



Fig. 117.—H. Powell's microscope (1841).

a fine adjustment in this to act upon the nose-piece only, which, as we shall subsequently see, is a very inferior method. This instrument is shown in fig. 116. Ross tried various modifications of this fine adjustment and model, but from about 1841 he worked only at the long-lever method as applied to the nose-piece through the 'cross arm' and brought it to a high state of perfection. But the full possibilities of this method, as concerned its sensitiveness, were never utilised by Ross, and were subsequently pressed into service by Powell.

In 1841 Powell made a microscope with an extremely delicate fine adjustment applied to the stage. The mechanism and the workmanship were excellent (we give a drawing of the instrument at fig. 117), but the principle was by no means an advance in the direction of the wants of the modern microscopist. An adjustment which gave the object a movable place between the condenser and the objective was subversive of all ease in manipulation, and would have made some of the finer results of modern microscopy almost impossible. Our illumination needs, as we shall subsequently see, centring and focussing with the accuracy of the lens itself, but by this arrangement improved focussing of the image would involve inevitable derangement of the illumination.

Smith and Beck also made a fine instrument which embodied the 'Jackson' limb and fine adjustment. It is illustrated in fig. 118, being the first model made by this firm in this form, and it has many features of interest from the point of view of our present requirements. But after we have once secured steadiness, the crucial points in a microscope are the quality of the fine adjustment, and the delicacy, firmness, and ease with which we can centre, focus, and otherwise modify the sub-stage illumination. To the former certainly this model does not contribute.

We are now prepared to examine and endeavour to judge impartially from a practical point of view the merits of the principal English, Continental, and American models which are offered to the microscopical public. It is impossible, no less than it is undesirable, to attempt to describe all the microscopes of every maker, or even the principal forms made by the increasing multitude of opticians. We have sought no opticians' aid; we have carefully examined all the forms that lay any just claim to presenting an instrument which meets the full requirements of modern microscopy; and, although we have reason to know that the judgments we express are shared by the leading experts of this country, we take the sole responsibility for these judgments. Having sought for twenty years the best that could be produced in microscopes and objectives, our judgment is given with deliberation and wholly in the interests of science.

In examining the principal modern microscopes we shall point out whatever is of absolute importance or relative value; and the absence or presence of this in any form provisionally selected is all that the reader will need to enable him to become convinced of our estimate of the value of such an instrument, whether the form be illustrated in these pages or found in the catalogues of the makers.

With this object before us we shall facilitate its attainment by at once considering what are the *essentials* of a good microscope.

What are the attributes of the instrument without the possession of which it cannot meet modern requirements ?

I. **Steadiness** is absolutely indispensable : this would, in fact,



FIG. 118.—Smith and Beck's microscope.

ppear to be obvious. But we are bound to admit that it is, in hat sometimes claim to be stands of the first class, disregarded; nd when the height of the centre of gravity in the English and merican stands of the first class is considered, this is a fatal istake.

It is pointed out in the section on micrometry[1] and drawing hat the optic axis of the microscope should be ten inches from the ible; therefore a first-class microscope whose optic axis when laced horizontally is either more or less than this is found wanting a material point. But to possess this characteristic it must have high centre of gravity.

Now it is possible to secure steadiness by (1) weight or (2) esign. The Continental method has invariably been weight. The illar of the instrument is fixed in a cumbrous metal foot of horse-oe form, which bears so high a ratio to the whole remainder of e instrument that it is usually steady. This secures the end rtainly, but by coarse and unwieldy means. It promises little r the instrument as a whole.

What is wanted is the maximum of steadiness with the minimum weight.

Palpably, the mechanical compensation for the difficulty of an evated centre of gravity is an *extended base*. The leading fault many stands claiming the first rank is their narrowed bases. A road base, resting on three points only, and these plugged with ork, is the ideal for a perfect instrument.

II. Next in order to the *stand* of the microscope comes what is nown as **the body** of the instrument—the tube or tubes for receiv-ng the objective at one end and the eye-pieces at the other. The ibe of the monocular is always provided with an inner tube called e *draw-tube*. In a first-class instrument this latter should always provided with a rack-and-pinion motion, and should have a scale from two to three inches, divided into tenths or millimetres. This ables the operator the more accurately to adjust apochromatic objec-ves so sensitive, for their best action, to accurate adjustment of tube-ngth. In fact, it is always important to remember that objectives e corrected for a special tube-length; that is to say, for the forma-on of the image at a certain definite distance.

There are, however, two kinds of tube-length, (1) an *optical* and) a *mechanical*.

The optical tube-length is measured from the posterior principal cus of the objective to the anterior principal focus of the eye-piece.

The mechanical tube-length should be measured from the top of e tube into which the eye-piece fits, and upon which the bearings the eye-piece rest to the end of the nose-piece into which the jective is screwed.

Unfortunately different makers estimate tube-length differently, d take different points from which to make their measurements. ooking at the matter broadly, there are two estimates for tube-ngth in practical use: these are the English and the Continental.

What was formerly known as the English standard tube had an

[1] Chapter IV.

optical length for high and moderate power objectives of *ten inches*; with low powers, however, it was less. The mechanical tube-length was $8\frac{3}{4}$ inches.

Professor Abbe, in constructing his apochromatic objectives for the English body, has taken the mechanical tube-length at 9·8 inches = 250 mm.; and the optical tube-length at 10·6 inches = 270 mm. This has caused an increase in the length of the English standard tube, since all good microscopes are made to work with these objectives; and *the addition of a rack and pinion to the 'draw-tube'* becomes of great practical value.

The tube-length of the *Continental mechanical tube* is 6·3 inches = 160 mm., and the *optical tube-length* is 7·08 inches = 180 mm.

The question has been asked, 'Which is the better of these two differing tube-lengths?' So far as the image in the instrument is concerned, there is not much difference. It is of little importance whether the initial magnifying power of an objective be increased by a slightly lower eye-piece used at a longer distance or a slightly deeper (higher) eye-piece at a shorter distance. But it is of practical importance to note that *a small difference of tube-length produces a greater effect on adjustment with a short body than with a long one.* The principal difference, however, between the long and the short body as affording a datum for their respective values is that when a short body is used by a person having *normal accommodation of sight*, the stage of the microscope cannot be seen unless the head is removed from the eye-piece, whereas with the long body the eye need not be taken from the eye-piece at all, as the stage can be seen with the unused eye.

III. **Arrangements for focussing** stand next in order of importance. Every microscope of the first class is provided with two arrangements for focussing, one a *coarse adjustment*, acting rapidly, and the other a *fine adjustment*, which should act with great delicacy and precision. A good 'coarse adjustment' or primary movable part of the instrument is of great importance. The first requisite is that the body or movable part should move easily, smoothly, but without 'shake' in the groove or slot or whatever else it slides. We have found in practice that a bar shaped like a truncated prism sliding in a suitable groove acts best and longest. But a bar planed true and placed in a groove ploughed to suit it is not enough. The inevitable friction determines wear, and this brings with it a fatal 'shake.' All such grooves, which are usually V-shaped, *should be cut and sprung on one side*, so that by 'tightening up' the V's by means of screws the bar or limb is again firmly gripped. Further, the bar should not 'bear' for its whole length along the groove, but only on points at either end and in the middle. Powell introduced these prime essentials to a good 'coarse adjustment' half a century ago; yet what thousands of instruments in which these principles have not been applied have been, by sheer friction wear, soon changed into useless brass since then! But instruments made by this firm are as good after thirty years' use as they were when new.

Frequently bad workmanship is concealed by the free employment of what is known as 'optician's grease' and an over-tightening of the

pinion, driving its teeth into the rack, which, of course, speedily ends in disaster.

If we desire to practically test this part of a microscope, we must remove the pinion, take out the bar, clean off the 'optician's grease' with petroleum from both bar and groove, oil with watchmaker's oil, and replace the bar in the groove, and before refixing the pinion see if it slides smoothly and without lateral shake.

What has been said about the 'springing' of the bar in this special instance applies equally to all moving parts, in stage and sub-stage movements, and wherever constant friction is incurred; equally applicable, too, is the lubricant we suggest. An instrument left unused in its native 'grease' for twelve months becomes so immobile in most of its parts by the hardening of its 'normal' lubricant that motion becomes a peril to its future if persisted in in that condition.

If a 'coarse adjustment' be what it should be, all lower powers should be exclusively and perfectly focussed by it, and with the highest powers objects should be found and focussed up to the point of clear visibility.

Rack-and-pinion work for microscopes has been greatly improved by the adoption of the suggestion of Mr. John Mayall, jun., to em-

Fig. 119.—'Stepped' diagonal rack-work for coarse adjustment.



Fig. 120.—Less complex forms.

ploy a 'stepped' diagonal rack-work, which greatly increases the smoothness of the motion. Fig. 119 shows the arrangement as first applied with three racks, the teeth of each part being set out of line to the extent of one-third their pitch, and the spiral pinions being fitted to correspond with the racks. The effect is similar to what would be obtained by pitching the teeth of a single rack three times as finely, but at the same time retaining the strength due to the coarser rack.

On account of difficulty in the workmanship the racks were subsequently reduced to two, as in fig. 120, which still retains considerable advantage over the ordinary form.

There is a defect in either microscope or microscopist if the 'fine adjustment' is resorted to before the object is focussed into clear view, even with the highest powers.

The Fine Adjustment.—This part of the modern microscope possesses an importance not easily exaggerated, and deficiency or bad principle in the construction of this makes not only inferior,

but for critical purposes absolutely useless, what are otherwise instruments of excellent workmanship and real value.

There are two kinds of fine adjustment usually employed :—

i. Those which *simply move the nose-piece* which receives the objective.

ii. Those which *move the whole body*, or the whole body including the coarse adjustment.

Every construction of the second class has proved impracticable, and even pernicious. It inevitably breaks down just as the purchaser, by practice, begins to realise the value of perfect action. With a large experience of stands of every class, we are obliged to say that generally with one or two years of *work* it loses whatever value it at first possessed.

To this broad statement there are possibly two exceptions, inventions still *sub judice*, viz. Swift's side lever and Campbell's differential screw, to which we shall subsequently refer.

It is, however, upon this model, with all its radical and glaring imperfections, that the majority of Continental microscopes are built.

A screw of an extremely fine thread, and therefore of extremely shallow incision—a micrometer screw in fact—*has to bear the wear of lifting and lowering the entire weight of the body*, with its coarse adjustment, lenses, and so forth ; while the *sole object* of the adjustment should be to give a delicate, almost imperceptible, motion to the *object-glass alone*. It needs no great experience to foresee the inevitable result ; the screw loses its power to act, and something incomparably worse than a tolerable coarse adjustment is left in its place.

Yet it is the Continental model that has become the darling of English laboratories, and that still receives the appreciation of professors and their students. True they answer in the main the purposes sought—the exigencies of a limited course of practical instruction. But how many of those who receive it are the medical men of the future, and to whom a microscope—not of necessity a costly one—of the right construction would be of increasing value through a lifetime ?

Almost any instrument, however inferior, could be employed successfully with a $\frac{1}{4}$-inch objective of 'low angle' (to give it what has been called 'the needful penetration' for histological subjects !) to obtain an image corresponding to a figure in a text-book of, say, a Malpighian corpuscle, or a section of kidney, brain, or spinal cord. The quality of a fine adjustment is never tested by these means, for, in point of fact, a delicate fine adjustment is not even necessary. We write in the interests of microscopical research. It certainly may be taken for granted that the end sought is not simply to use the microscope to verify the illustrations of a text-book, a treatise, or a course of lectures ; without doubt it is a subsidiary purpose ; but the larger aim is to inspire in the young student confidence, enthusiasm, and anticipation in the methods and promise of histology and all that it touches. But for this there must be *potentiality* (without costliness) in the mechanical and optical character of the microscopes commended and approved.

A low-priced student's microscope of good workmanship and

perfect design could easily be devised if the demand for it arose. Indeed, during the past few years a certain class of students' microscopes have been improved greatly; this has been a concomitant of the science of bacteriology, which has compelled the use of the sub-stage condenser. We have said enough of the value of this instrument in a succeeding chapter, but until recent years histologists did not use it because it was not used in Germany or with German instruments! Its present use, nevertheless, has had the effect of improving the definition obtained by the objectives used by students generally. Some who perceive this, endeavour to attribute it to the improvement effected in modern objectives, but this is not the case; the objectives in many cases are not even new, and until the introduction of the Jena glass [1] the ordinary students' objectives were not really so good as the English objectives of thirty-five years ago. But it could easily be shown that one of these early objectives, used as it always was with a *condenser*, would surpass in the sharpness of its definition the majority of those now supplied to 'students' with Continental models.

FIG. 121.—Ross-Jackson model.

But it must not be supposed that it is *only* the Continental model that is deformed by the adoption of this radical error in the 'fine adjustment' with which we are dealing. Even during the last ten years it has been applied to some of the most imposing and expensive instruments made in England and America on what is known as the 'Jackson' model. This model has one supreme virtue, in the possession of a solid limb. This may take many distinct forms, but it is sufficiently represented in fig. 121, where it will be seen that the 'limb,' which is swung between the pillars, and which carries the body-tubes and the fine

[1] *Vide* Chapter I.

adjustment, is in one solid piece. If nothing were sacrificed this would be a boon. Formerly, this model was supplied with a fine adjustment which only moved the nose-piece, but on a principle which we shall see was wrong, and from its imperfections it was abandoned, and the solid Jackson arm was *cut*, and the whole body and its coarse adjustment was pivoted on the lever of the fine adjustment. Thus its normal virtue (a *solid* limb) was sacrificed, and a 'fine adjustment,' doomed to failure, was given to it.

A complex roller, a wedge, and a differential screw have in turn been since employed to redeem this instrument from the failure that had overtaken it. Partially, or completely, each has failed. The differential screw certainly comes theoretically nearest to success with this form of instrument. But at the outset this is the case only where it wholly abandons the lifting and lowering of the body-tube &c. by the action of a 'fine adjustment,' and its motion is only brought into operation upon the equivalent of a nose-piece. The form specially adopted for this instrument was devised by Dr. Hugo Schroeder, and is a remarkable arrangement, worthy of being understood. It is illustrated in figs. 122 and 123.



FIG. 122.

FIG. 123.

Schroeder's fine adjustment for the Jackson model.

The nose-piece, A, is attached to a tube which is fitted to slide accurately in adjustable bearings in the body-tube, B. The nose-piece tube has a short projecting arm, C, by means of which it is pressed upwards by a strong spiral spring mounted in a cylindrical box, L, outside the lower end of the body-tube. The arm, C, is moved against the spring by the differential-screw mechanism (with milled head, D), which is gimballed on a bracket, E, attached to the upper part of the body-tube.

The differential-screw mechanism consists of a steel rod, F (connected with D), which has two screw threads at the lower end, one working in a thread cut in the end of the inner tube, G, and the other in the block, H, which is soldered within the sheath, J. When the milled head is turned to the left, the block—and with it the sheath—moves downwards, while the rod itself, carrying the block and sheath, moves upwards. As the screws are cut respec-

tively to forty-five and fifty-two threads to the inch, the resultant motion is equivalent to the difference between the motion of the two screws—that is, to the motion of a screw of nearly 335 threads to the inch.

The end of the sheath is tipped with a small sphere, K, of polished steel, while the projecting arm of the nose-piece tube, against which the end works, has a corresponding concave bed of polished agate.

The great fault in this design is in its *mode* of adoption of what is otherwise the highly valuable principle of the 'differential screw.' As a fine adjustment it undoubtedly consists of too many parts or separate pieces. It is a kind of pencil-case which extends and contracts by means of a differential screw acting on the nose-piece. Then its mode of attachment to the body makes vibration inevitable; the micrometer screw is in an extremely bad position, giving the utmost leverage for vibratory action in using it, and at the same time, on account of its height from the table, must be worked by the arm entirely without rest. Complexity of parts and infelicity of arrangement make this device not only very costly, but by no means desirable.

We may now direct our attention to the *former of the two divisions* into which we have separated the various kinds of fine adjustment, viz. that in which the *nose-piece only is controlled* by the adjustment screw.

An early form of this was employed by Andrew Ross. It was applied to a microscope having a bar movement, the general form of which—so far as the bar and the application of the fine adjustment are concerned—is seen in fig. 131. It consisted of *a lever of the second order inserted within the bar*, and actuated by a micrometer screw with a milled head at one end, the fulcrum being at the other, and the nose-piece between them. This served admirably in the days of low-angled objectives: but there were two faults belonging to it: one was that the tube of the nose-piece had not a sufficient length of bearing and was liable to a lateral shake: the other was that the adjustment screw, being near the middle of the bar, involved tremor.

The application of this principle in its very highest and most perfectly practical form was adopted by Powell. His instrument also had a bar movement; but the bar being of relatively great length, he employed *a lever of the first order*, the micrometer-screw being at one end, the nose-piece at the other, and the fulcrum between them. The ratio of the arms of the lever was 2 : 1; consequently, as the screw has fifty threads to the inch, a complete revolution of the screw causes a movement of the objective of $\frac{1}{100}$th of an inch. The position of the screw is immediately behind the pivot on which the bar turns, and this precludes the possibility of the impartation of vibration to the body; and, as the nose-piece tube is very long, and only bears on three points at either end, this adjustment is the steadiest, the smoothest, and the most reliable for all objectives of any of the several devices which have come before us during the last twenty years. In fact this fine adjustment has held an unrivalled position for the past forty years (fig. 129).

The fine adjustment that was employed as its rival on the earlier

forms of the Jackson model was known as the *short-side lever*, and it was sometimes employed in the commoner bar-movement microscopes. Its position and character will be seen on the right-hand side of the body of the Beck-Jackson model, fig. 118. In the light of what we now need, we are bound to say to the intending purchaser of a microscope, 'Avoid it;' it is bad alike in design and construction. The screw is so placed that tremor is inevitable in the body when it is touched, while the nose-piece tube is so short that steadiness of movement does not belong to it. It is only that it was concurrent with the belief in 'low angles,' and consequent 'penetration,' in objectives (with which no critical work could be done), that it is possible to account for the toleration for so long in numbers of English microscopes of this wholly inefficient adjustment.



FIG. 124.—Swift's patent fine adjustment.

Swift's vertical side lever is one of the new forms of fine adjustment worthy of careful trial; it has in it elements of great merit. It can, however, only be applied to the Jackson model, and promises to redeem that instrument from what must otherwise have proved its extinction as a first-class microscope.

The first form of this adjustment was sound in principle and ingenious in construction. It is difficult to know why the inventor and patentee has abandoned it for another, the value of which as a modification has yet to be established.

The early form employed by Swift avoided what had been a sheer necessity of all successful fine adjustments of this type, viz. the accuracy and perfection of the fitting of the nose-piece tube. This was done, as shown in fig. 124, by attaching a vertical prism-shaped bar, A, to the nose-piece, and sliding this in V-grooves in a box at the back of the body. A horizontal micrometer screw with a milled head, F, acts on a vertical bent lever, D, on which a stud, E, fixed to the prism bar bears.

There is also an adjustment for tightening up the prism bar in the V-grooves, B B. Side shake and 'loss of time' are impossible with this form of adjustment; while the power to 'tighten up' by means of the capstan-headed screws

enables wear and tear to be compensated. It is obvious that the slowness of the motion is here controlled by three factors: (1) the length of the lever, D; (2) the distance of the lifting-stud, E, from the pivot or fulcrum; and the pitch of the screw-thread on F.

Manifestly, where a *side*-lever fine adjustment such as this is employed it should be placed on the *left*-hand side of the operator: we can readily focus with the left hand, and leave the right hand free for moving the slip and effecting other adjustments. Ambi-

FIG. 125.—Nelson's model with Swift's fine-adjustment screw to the left hand.



FIG. 126.

dexterity is not at present a common gift, and to have the right hand free is important. This was pointed out by Mr. Nelson when this fine adjustment was first introduced, and he had a student's microscope constructed with the micrometer milled head on the left side, as in fig. 125. It is manifest, however, that it would greatly improve this adjustment if the screw-pinion were carried right through and a milled head placed on both the right and the left sides of the body.

On what principle the makers have returned to the former plan of placing the head on the right hand of the operator is not easily explained; but this is the case, and it involves an awkwardness and inelegance in the manipulation of these instruments greatly to be regretted.

The later form of this fine adjustment consists in reverting to the plan—which we have seen such strong reason to condemn—of throwing upon the fine-adjustment screw the movement of the entire body. A Jackson limb fitted with this movement has two slides—one for coarse adjustment, which moves the entire body, including the fine-adjustment box; in front of this is a second box or excavation for the fine-adjustment movement of the body only. The mechanism is shown in fig. 126; it is precisely similar to that in fig. 124, with the exception that the stud on which the lever bears is fixed to the body-slide instead of to the nose-piece-slide.

By this very simple mechanism the fine adjustment is applied on the front of the coarse adjustment, and acts on the whole body-tube and not merely on the nose-piece.

There remains one other form of this adjustment to be considered; *it is a form of differential screw devised by the Rev. J. Campbell*, of Fetlar, Shetland. Its object is to supplant the direct-action screw, where the form of the microscope may appear to make that a necessity. This has been the case with the Continental model. It was applied by its inventor to a microscope made by himself, and was brought before the Quekett Club by Mr. E. M. Nelson.



FIG. 127.—Campbell's differential screw fine adjustment.

It is very simple, and is made by cutting two threads in the micrometer screw. Fig. 127 will illustrate the exact method. D is the milled head of the direct-acting screw. The upper part, S, of the screw has (say) twenty threads to the inch, and the lower part, T, twenty-five threads to the inch. B is the fixed socket forming part of the limb of the microscope, and H is the travelling socket connected with the support of the body-tube. The revolution of D causes the screw thread S to move up and down in B at the rate of twenty turns to the inch, whilst the screw thread T causes the travelling socket H to move in the reverse direction at the rate of twenty-five turns to the inch. The combined effect, therefore, of turning D twenty revolutions is to raise or lower T and with it the body tube $\frac{1}{5}$th of an inch, or $\frac{1}{100}$th of an inch for each revolution. The spiral spring below H keeps the bearings in close contact.

Of course any desired speed can be attained by proper combination of the threads: thus 32 and 30 would give $\frac{1}{480}$th of an inch for each revolution, and 31 and 30 would give $\frac{1}{930}$th of an inch.

This screw has provided for the Continental model what Swift's vertical lever has done for the Jackson model; Mr. Baker, of Holborn, has adopted it and with very satisfactory results; for it has passed through that most crucial of tests for a fine adjustment,

employment in photo-micrography, with excellent results; and hope that it may become the general fine adjustment for this m of microscope in place of the old form of direct-acting screw.

From the foregoing we learn that there are three types of micrope models for which a suitable fine adjustment has been found.

i. The bar movement model, for which Powell's first order of er is the perfect method.

ii. The Jackson model, for which Swift's vertical side lever is best form known.

iii. The Continental model, for which Campbell's differential w is the most smooth and delicate device yet suggested.

IV. The stage of the microscope will next call for considera-

What is known as a *mechanical stage* must be a part of every **t-class microscope; but by this we** mean one of perfect work-**nship and construction, otherwise it is an impediment** and not a

To this end we would say at the outset there must be thoroughly l-made movements *effected by rack and pinion and screw*. The loyment of levers, cams, and that class of stage-gear is in practice, critical purposes, a mere mechanical mockery. Better trust to educate the *fingers* to move the object than be beguiled by any practically tormenting delusions. They are simply impossible ccompaniments of a first-class microscope.

The principle upon which alone a perfect mechanical stage can constructed, so as to work smoothly without 'loss of time,' and ure constant use without failure, must be the employment of m-shaped plates sliding in sprung V-shaped grooves, and bearing r on four points.

We may test the mechanical quality of the movements of a stage, n the case of the coarse adjustment, by removing the parts, clean-them, and replacing them, when they should work smoothly and iout shake. Where the sliding parts are tightened into easily ng and merely ploughed grooves by pressing the pinion into the ; the desirable result of smooth working and instant responsive-of sliding plates to milled heads will not present itself.

But besides the perfect action of the sliding parts, a perfect hanical stage should have *equal speed of motion vertically and zontally*. A common fault is that the speed of the rack-work ng vertical motion is greatly in excess of that of the screw giving ral or horizontal motion. If, for example, a pinion has eight es, and the rack it works has twenty-four teeth to the inch, then e turns of the milled head (and pinion) would cause one inch of ement to the stage. In order, therefore, to get the same rate of ement in the lateral motion the screw should be so pitched as to move the stage through an inch with three revolutions of the ed head.

It is most desirable that *the pinions should be fixed*, not movable the movements of the stage, and the *milled heads* carrying the ective parts *should be as near to each other as possible*. The best is that of Turrell's, where one (a screw) is hollow, and the other inion) passes through it; this permits both to be turned at the

same time with one hand, giving a diagonal motion, as well as the separate rectangular ones, and gives great facility for instantly producing any motion required without removing the hand from its position; a most desirable attribute of a stage when the rapid movements of a living and minute organism are being followed.

It still further enhances such a stage if a pinion is carried right through the stage with a milled head at each end.

A *new form of mechanical stage was devised by Mr. Tolles*, and has been adopted in this country. We regret to say that, for working purposes, it is a most undesirable form: flexure is inevitable and steadiness is impossible. Its character will be understood from fig. 128.

It has three principal errors, viz.:

1. Plates so thin that they lack rigidity.
2. The upper plate is only supported on one side.
3. The Turrell milled heads are placed vertically on the top of the stage, a position in which their value is reduced to its lowest in actual work.



FIG. 128.—The Tolles mechanical stage adopted by Ross.

We have pointed out in Chapter IV. that the stage plates of a mechanical stage should be suitably *graduated to hundredths of an inch as a 'finder,'* and the principle on which they should be constructed and employed is given under that head in detail.

On the *upper stage plate* there should be a *ledge for the slip* to rest upon and a *stop at the left-hand side beyond which it cannot be pushed.* This should be removable, but capable of being replaced with absolute precision as to position.

The aperture in the stage should always be large, at least two inches in diameter. There ought always to be space enough above the ordinary slip when it is in position to permit of the easy insertion of the index finger, for by its proper use, focussing with the highest powers may be greatly facilitated. The object is to raise or lower the slip, as the objective approaches the object, so as to discover how nearly it may be to contact with the front lens of a high power in approaching focus. The focal distance should always be *felt* and not sought with the eye.

Let it be supposed that we are using a dry object-glass with a full aperture, and consequently short working distance. With the right hand the coarse adjustment is worked; with the elbow of the left arm on the table, the second finger of the left hand resting on an immovable part of the stage, which steadies the whole hand, the index finger should rest lightly on the edge of the slip, and the thumb be so placed as to graze the objective as it advances towards the slip. The touch of the thumb indicates whether the objective is an inch off or only a quarter of an inch away from the cover of the slip. The movement of the coarse adjustment may be rapid up to $\frac{1}{4}$th or $\frac{1}{3}$th of an inch, but after this there must be a cautious but steady advance. The body may be racked down until by gentle movement the slip is found to touch the front of the objective; then proceed cautiously by delicately lifting the slip from time to time, the ability to do so proving perfect safety until the focus of the object is obtained. In this way focussing becomes easy and rapid, a matter of touch, and not of discontinuous procedure to discover where the front of the lens is'—a search requiring a hand glass and often, with its cumbrousness, considerable loss of time. The above simple plan with brief practice will enable the operator to focus an object in the field with a $\frac{1}{25}$-inch objective in ten or twelve seconds.

If a *perfect mechanical stage* cannot be obtained, take no middle course, have *a firm, well-made plain one* with *a smoothly sliding ledge.* The stage should be large, and the ledge should glide with perfect ease and without catching when gently pushed from one corner. For this purpose the side-guides should be long, and only the ends of the bar should bear on the stage. The aperture should be as in the mechanical stage, and for the same reason.

Mr. Nelson suggested a stage of large size, which should have a $1\frac{1}{2}$ or $1\frac{3}{4}$ inch aperture bored in it, and then have the intervening brass between it and the front taken away, so that the stage assumes a horse-shoe form. This is thoroughly efficient, and the principle is seen in fig. 125.

It is a matter of great interest to English microscopists to note that their German collaborateurs in Germany and the leading German makers have not only surrendered to the sub-stage condenser, and even in its achromatic form, but that at length they have also adopted the mechanical stage; the form adopted by Zeiss is figured in the accompanying illustration (fig. 128 A).

It must, however, be noted that the usual Continental model adopts a *small stage* with *a $\frac{3}{8}$-inch aperture* and two *fixed spring clips* with *no sliding ledge*; that is, wanting almost everything required to do good modern work.

One of the most practical rules for the young microscopist in this relation is, 'Have your mounted slide in a fixed position, but never *clip* it if it can possibly be avoided.'

In addition to perfect rectangular movements a first-class microscope should have *concentric rotary motion to the stage.* This is usually effected by rack and pinion, but it is at times desirable to move it with greater rapidity than this admits of. In very well

made instruments the pinion engages the rack so lightly that this rapid motion may easily be given to it. In others the pinion can be disengaged and rapid movement effected.

The centre of rotation of the stage should be closely approximate to coincidence with the optic axis, so that in rotation the object should never be out of the field when a fairly high power is used. Elaborate rectangular centring gear has been used by some makers,



FIG. 128 A.—Zeiss's mechanical stage.

and is found in some high-class instruments; but this is not needful, for all that is really required is to rotate an object without losing it. In fact *exact* centring would have to be readjusted for every separate objective if it were needed. But any slight departure from the axial centre can be much more readily met by bringing the object into centre by the mechanical stage.

There are *three movements* in every microscope *which should be graduated*: these are (1) the milled head of the fine-adjustment screw: (2) the extension draw-tube carrying the eye-piece; and (3)

the rotation of the stage. Divided arcs are imposing, and to the multitude look 'scientific'; but in practice they are superfluous in the most complete instrument beyond those indicated.

There is a simple form of *super-stage* now employed by many, and we think with advantage, when the cost of a complete mechanical stage must be forgone. This consists of a clip to receive the object, made of glass or brass, so arranged that the bearings shall be glass and the friction reduced to a minimum.

Such a *super-stage* can be made to work with remarkable smoothness, and since some persons have not sufficient delicacy of touch to move so small and thin an object as a 3 × 1-inch slide upon the stage with steadiness and precision, it is in favour of the super-stage that it is larger, moves easily, and can be furnished with convenient points of hold-fast for the hands, and consequently is more manageable. Against its employment is the fact: 1st, that the slide is clipped into a rigid position; and 2ndly, that the aperture is too small to admit of the employment of the finger in moving the slide to assist in rapid focussing. But these are defects which might certainly be overcome.

V. The sub-stage is scarcely second in importance in a first-class microscope to the stage itself. It is intended to receive and enable us to use in the most efficient manner the optical and other apparatus employed to illuminate the objects suitably with the various powers found needful. Upon this much of the finest critical work with the modern microscope depends.

To accomplish this a good sub-stage must have rectangular movements, and a rack-and-pinion focussing adjustment.

The vertical and lateral movements need not be as elaborate as those of the stage, since only a small movement in each direction is required. The object is to secure a centring motion, a motion that will make the optical axis of the sub-stage combinations continuous with the optical axis of the objective. It must therefore be a steady motion; the sub-stage must move decisively, and must rigidly remain in the position in which it is left.

A bad sub-stage moves in jerks, and is liable to spring from the position intended to be final.

It is not needful that the motion should be in right lines; *motion in arcs* whose *tangents intersect* at *right angles* are quite as efficient. A steady, even, reliable motion that will enable *a centre to be found* is all that is required.

The focussing adjustment must be smooth, steady, and firm, acting readily and remaining rigid. The recent employment of achromatic condensers of wide apertures has led such critical workers as Mr. E. M. Nelson to suggest *a fine adjustment to the sub-stage*. There are times when it is a great luxury and a facile path to delicate and desirable results; but it may be quite simple, a direct-action screw of fine thread, or a cone which the revolution of a screw pushes horizontally forward upon the bottom of a sliding bar to which the sub-stage is fixed, or an inclined plane acting in a slot in the same way. In fact, any simple device for focussing the condenser more slowly than the rack-work will do, pushing the con-

denser up to, or causing it to recede from, the under surface of the slide. But no means should be employed for this end which will imperil the absolute *firmness* of the sub-stage, or else more will be lost than can be gained. The arrangement in Powell and Lealand's sub-stage is shown in fig. 130, p. 175.

It is almost a matter of compulsion to refer here to a recent arrangement known as *a swinging sub-stage*, which is, as its name implies, a sub-stage so arranged as to be capable of being moved *laterally out of the axis in an arc which has the object on the stage for its centre.*

The sole purpose of this is to secure *oblique illumination*, which practically, at the time the swinging sub-stage was devised, meant obtaining a more oblique pencil than the condensers then provided could command, and since this also meant sending into the object a small portion of a cone of light *in one azimuth*, many tacitly assumed that this alone was taken to be 'oblique illumination.' But whatever sends oblique light through an object into the objective is an oblique illuminator. Two condensers may have numerical apertures of 1·4 and 1·5 respectively; a stop behind the back lens in each has a narrow sector cut out, representing the conditions of the so-called 'oblique illuminators'; by the former we get an oil angle of 134° 10′, by the latter a similar angle of 161° 23′. These sectors of the cone of light of 67° 5′ and 80° 41′ respectively are in every sense 'oblique illuminators,' and the one more oblique than the other.

Whether or not it is needful or best to use such a sector is scarcely an open question; it is manifest that by taking the stop with its sector away from each condenser and sending in the *complete cone of light* formed by the condenser, we are still using *oblique illuminators, but the obliquity is in all azimuths.*

There can be no doubt that a large aperture in a condenser provides the microscopist with far greater wealth of resource than an oblique illuminator in one azimuth can ever give him. A condenser with an oil angle of 161° 23′ is much more valuable than even the semi-angle obtained by a mere section of a luminous cone. The power to utilise the entire cone is a gain of the highest order.

It will be manifest to all that we want concentration as well as obliquity. In the catadioptric illuminator of Mr. Stephenson, the one defect, as in discussing it we point out, is, in our judgment, *want of concentration*, due to the length of focus of its concave reflector.

Ordinary concentration depends upon the *power of the condenser.* If it is required to concentrate the light from the edge of the flame of a paraffin lamp upon an *Amphipleura pellucida*, the condenser must be at least a $\frac{1}{3}$th inch or $\frac{1}{6}$th inch in power, which will give an image of the flame nearly the same size as the object. The *amount of light* which is concentrated upon that object will of course depend upon the aperture of the condenser. An oblique cone of great intensity is here what is needed; the illuminating cone should be equal and conjugate to that which exists between the object and the objective.

Now it is certain that this condition cannot be met by an 'oblique

illuminator' of the kind commonly understood by that name; to get immersion contact, which is of course a *sine qua non*, we must employ a hemispherical button—or one greater than a hemisphere—placed in immersion contact with the under surface of the slide. This may be illuminated by a beam from a dry combination, made oblique by the sub-stage being swung out of the axis. Granted that the angle is attained which can be got with a condenser of great aperture, we manifestly obtain only a portion, and an attenuated and small portion, of the light given in every, or at will any, azimuth by the condenser.

Theoretically perfect illumination of an objective, for example, a $\frac{1}{8}$th of N.A. 1·4 or 1·5, would be obtained by using a precisely similar objective as a condenser, with its back lens stopped down by a slotted stop, the slot being of the size of the peripheral sector required to be illuminated. The cone of illumination would precisely equal that taken up by the objective, and would be of maximum intensity.

Now these conditions are more nearly approached by a high-class achromatic condenser of great aperture and of homogeneous construction than by *any* other means.

The *value* of oblique illumination is not here in question; what we believe clearly shown is that, however much may have been done by oblique illuminators dependent on swinging sub-stages, and the like, the same things can be *better done with immersion condensers of great apertures and perfect corrections.*

The swinging sub-stage, with these considerations—as well as all other 'oblique illuminators' of its order—is rather a defect in the microscope—unfruitful specialisation in fact—which does not promote the progress of either the instrument or the worker.

And this will apply to those complex forms of microscope known as 'radial,' 'concentric,' and those provided with stages that revolve or 'turn over' in an axis at right angles to the optical axis of the microscope.

In addition to the features enumerated hitherto, a complete sub-stage should also be provided with a rack-and-[illegible] motion: this is only really needed in order to use the [illegible]. For the purposes of its successful employment this is important, but otherwise its use is very limited.

VI. **The mirror** is also an indispensable part of a complete microscope. In a first-class stand it should be *plane* and *concave* and from 2½ to 3 inches in diameter. It may be mounted on either a single or a double crank arm. In any microscope if there is only one mirror it should be *concave*. This mirror, from its curve, has a focus, a point in which the reflected rays all meet, and the mirror should not be fixed, but so mounted that it may be focused on the object.

The plane mirror is sometimes found to give several reflections of a lamp flame at one time. It is due to some unrecognised unfavourable condition of the glass, and is undesirable for most purposes. It may be obviated or altogether overcome by covering the mirror with soft until a certain point is reached where all the images will be made

imposed. All mirrors should be so mounted as to admit of this rotation.

The present Editor is greatly in favour of *the employment of a rectangular prism* cut with care and precision. We get by this means total reflexion and no double reflexions; and he believes that finer images can be obtained by its means than with the plane mirror. It may be mounted in the *place of* the plane mirror—that is to say, the concave mirror may be as usual in its cell—and in the other cell, which would have received the plane mirror, the rectangular prism may be mounted and be capable of rotation as the plane mirror would have been.

It should, however, be noted that this applies only when the light is required to be reflected at an exact right angle. It is of the greatest service when the microscope is of necessity used in a rigidly upright position.

If it be used for angles other than right angles, there will be refraction as well as reflexion; and as the necessary decomposition of the light into a spectrum will accompany the refraction, care must be exercised to see that the rays emerging from the prism are at right angles to those incident to it, and that the areas of the square faces of the prism are sufficiently large to have inscribed within them a circle equal to the back lens of any condenser used.

Some employ what has been known as a '*white cloud illuminator*,' that is, a disc of plaster of Paris, or opal glass with a polished surface. But a disc of finely ground glass dropped into the diaphragm-holder of the condenser will give a precisely similar result.

Mr. A. Michael has, however, pointed out the curious fact that an *opalescent mirror* becomes an inexpensive and excellent substitute for a *polarising prism*.

Typical Modern Microscopes.—We are now in a position to carefully inspect the characteristics of the chief forms of microscope which the modern manufacturers of England, the Continent, and America offer to the microscopist.

We confine ourselves to the chief models, indicating more or less suggestively their merits or defects. We neither discuss all the instruments of any maker nor in every case even one instrument of some makers. This would involve simple repetition in the main features. The reader can compare for himself the microscope of any given maker from whose catalogue he proposes to select, and can discover by comparison *its incidence or otherwise with the type given here* to which it corresponds.

Beginning with the highest types we place first on the list *Powell and Lealand's No. I.* This instrument may claim a seniority over all the foremost instruments, because for nearly forty years it has practically remained the same. All its principal features were brought to their present perfection nearly forty years ago, while all other microscopes during this period have been redesigned and materially altered over and over again. This is no small commendation, for during that period, as the reader so well knows, the apertures of objectives have been enormously enlarged, and with this has come a great increase of focal sensibility. As a result the



FIG. 129.—Powell and Lealand's No. 1 stand.

majority of the microscopes of forty years ago are absolutely useles for the objectives of to-day, but the focussing and stage movement of Powell and Lealand's microscope still hold the first place.

Fig. 129 represents the instrument in its monocular form. Th foot of the stand is a tripod in one casting ; it has an extended bas of 7 × 9 inches, forming at once the steadiest and the lightest foc of any existing microscope. The feet are plugged with cork, an when the body is in a horizontal position the optic axis is (as i should be) 10 inches from the table.

The coarse adjustment is effected by a bar, consisting of a mas sive gun-metal truncated prism in form, which bears only on narrow part at the angles. It extends sufficiently to focus a 4 inch objective. The arm which carries the body is of unusual lengt for the type it represents ; but this gives a large radius from th optic centre of the instrument, and makes the complete rotation o the stage easy. Great efforts have been made to accomplish this i other instruments. The older Ross form from the shortness of th arm only allowed of a two-thirds rotation, and in the Jackson mode many different devices have been tried, the latest being the placin of the stage pinions in a vertical position above the stage (fig. 12 p. 166), which is an unquestionable error.

The rotation of the stage in the Powell and Lealand model is b means of a milled head most conveniently placed, and the divide circle is on a plate of silver.[1] It will also rapidly rotate by hand.

The arm is on a pivot, which allows it to be turned away fron the stage altogether, and, as we have already indicated, the lengt of the arm lent itself to the use of a longer lever for the fine adjust ment (p. 161). The milled head is placed behind the strong pivo of the arm, where vibration is impossible, and it is in an easy an natural position for the access of either hand.

The body may be, with great ease, *entirely removed from the arm* this makes the use of the binocular or monocular body or of a shor or long body a matter of choice, while it gives access for cleaning an other purposes to the nose-piece tube, as well as for the insertio and focussing of the lens used with an apertometer,[2] or an analysin prism. So also it is of service in low-power photo-micrography.

We have already referred to the stage of this instrument but it may be briefly stated that it is large, has complete rotation it has one inch of rectangular motion, being graduated to the $\frac{1}{100}$th inch for a finder. There is *the same speed* in the vertical and the lateral movements, and the pinions do not alter their positions. The aperture of the stage is amply large.

The ledge of the stage has a stop placed on its left-hand side ; this is held by a screw, but is removable at pleasure. Two massive brackets under the stage remove all possibility of *flexure.*

The sub-stage has rectangular movements by screw in either direc tion, as well as a rotary movement by pinion. The coarse adjust ment is by rack-work, and a *fine adjustment* is added when desired

[1] This is now made of platinum if desired, and thus tarnish is obviated.

[2] Chapter V. p. 387.

Fig. 130 illustrates this stage, showing its under side in order to enable the fine adjustment to be seen.

The vertical and upper horizontal milled heads are centring screws acting at right angles to each other, while the diagonal screw to the left is the milled head, which causes the stage to rotate, and it will be seen that at the end of the screw turned by A is a milled head controlling a screw spindle terminating in a steel cone, B. On rotating A, B turns and with a very slow motion forces up (or releases, as the case may be) a pin, C, inserted in the base plate, E, of the sub-stage. This motion of C carries with it the condenser. At right angles to, and forming part of E at the back an inner sliding plate works against a spring at the upper end between bearings F at each side, which are fixed upon the usual racked slide, D, of the sub-stage; the inner sliding plate is the essential addition to the usual racked slide in the application of the new fine adjustment to the sub-stage. The range of motion is about $\frac{1}{8}$ inch—the difference in radius between the smaller and larger ends of the steel cone.

FIG. 130.—Powell and Lealand's sub-stage with fine adjustment.

The mirror is plane and concave, with double-jointed arm.

The finish and workmanship of this instrument are of the highest order. The seen and the unseen receive equally scrupulous care. The present Editor has had one of these microscopes in constant, and often prolonged and continuous, use for over twenty years, and the most delicate work can be done with it to-day. It is nowhere defective, and the instrument has only once been 'tightened up' in some parts. Even in such small details as the springing of the sliding clip—the very best clip that can be used—the pivots of the mirror, and the carefully *sprung* conditions of all cylinders intended to receive apparatus, all are done with care and conscientiousness.

An instrument of this kind may be made to appear perfect to the eye, but at the same time may lack some most important elements as a finished instrument. But this is an instrument of the highest order as such, and at the same time a very fine specimen of highly finished brass work.

A note must be made before leaving this microscope upon the size of the tubes in the body and the sub-stage.

Powell and Lealand were the only makers whose gauge of tubing had a *raison d'être*; the size of the tube was such that it would take in a binocular body a Huyghenian 2-inch eye-piece, having the largest field-glass possible. The size of this field-glass depends on two factors.

1. The distance between the centres of the eyes.
2. The mechanical tube-length.

In order that the binocular may suit persons with 'narrow

FIG. 131.—The original Ross model.

centres' to their eyes, the distance between them should not be greater than $2\frac{1}{2}$ inches. The mechanical tube-length is $8\frac{3}{4}$ inches for

the standard tube. When the eye-pieces were 'home' in their places in the tubes they just touched each other, the inner sides of the binocular tubes being cut away; so under the above conditions a larger field than is thus obtained is simply impossible. The size of the field-glass determines the size of the eye-piece, and that was made to fix the diameter of the body-tube.

Very wisely these makers made the tube of the sub-stage the same size, so as to have one gauge of tubing throughout. This allows a Kellner or other eye-piece to be used as a condenser, thus reducing the number of adapters.

Lately this firm have altered their sub-stage tube to a gauge of 1½ inch, as recommended by the Royal Microscopical Society. This involves an adapter where the sub-stage apparatus was adapted to the old gauge, or when an eye-piece is used as a condenser; for 1½ inch is an impossible size for a binocular body-tube.

The Ross model, in its completest form as left by Andrew Ross (though not now made to so large an extent as formerly), deserves study.

It was a bar movement, with a foot formed of a triangular plate to which were bolted two parallel upright plates to carry the trunnions of the microscope. This base was defective in not being sufficiently extended to carry so large an instrument, with its centre of gravity so high. This instrument is illustrated in fig. 131. The coarse-adjustment bar was rectangular, which is theoretically inferior to a prism, but it is well sprung and works with great smoothness. The fine adjustment is a lever of the second order, with the milled head in the middle of the bar, which involves tremor, and the tube of the nose-piece is short, making shake possible.

FIG. 132.—Ross-Jackson model.

The stage movements are of unequal speed, the lateral movement being slower than the vertical. There is no finder, and the rotation of the stage is but partial. The sub-stage and mirror are good. It was a commanding

instrument in its day, and was of excellent workmanship and finish; but it was not equal to the strain of critical work with immersion objectives of great aperture. Nevertheless the defects of this stand could have been readily corrected. With a more extended base, a better arrangement of the fine adjustment, a mechanical stage constructed on better principles, and the rotation made complete and concentric—which it was not—this would have been, even for our present requirements, an admirable instrument.

This important firm were otherwise advised, however; and, instead of correcting the errors of the instrument whose history they had made, they designed an *entirely new model* in which a Jackson limb was substituted for the bar movement. Fig. 132 illustrates this form of the instrument, from which it will be seen that the foot also was changed for the worse by being cast in one piece; the base was not sufficiently extended, and the hinder part of the foot was too large, so that it sometimes rocked on *four* points, because the hinder part was too wide—a flat surface, in fact. A true tripod will stand firm on an uneven table, but this form will not. It is a form frequently used by various makers now, and is known as the 'bent claw.' It is a bad design, and may be, as it has been, easily thrown over laterally.

The introduction of the Jackson limb brought its inevitable troubles—notably, with the fine adjustment—to which we have fully referred under that head. But in the Ross-Jackson model the fine adjustment screw was placed behind the body (as the figure shows) which was an improvement; still the body and the coarse adjustment were both carried by the fine-adjustment lever and screw.

This form could not—as it did not—long prevail. Its existence was ephemeral, and in its place was put a modification of the form devised by Zentmayer, known subsequently as the Ross-Zentmayer model. This was the Ross-Jackson instrument with a 'swinging sub-stage.' This instrument is illustrated in fig. 133. It will be seen that the foot is a true tripod, consisting of a triangular base with two pillars rising from a cross-piece, which carried the trunnions.

We have already assessed the value of a swinging sub-stage, and found that in our judgment it is at best redundant.[1] No microscope is complete without a good condenser, all, and much more than all that can be done by a swinging sub-stage can be done with a slotted stop at the back of the condenser. This elaborate appendage is therefore without justification. Yet in the impatience for large illuminating apertures, *which were not at that time provided by condensers*, this phase of illumination was carried to a still greater and more elaborate development in the production of a *concentric microscope*. This was a Ross-Wenham, known as the *radial* microscope.

In the early days of this instrument, when no achromatic condenser exceeding 170° in air was to be obtained, in some very difficult researches needing all the great advantages that come from great aperture, the present Editor was able, with much labour, to get results with this instrument not otherwise attain-

[1] P. 169 *et seq.*



FIG. 133.

able, but which were none the less almost counterbalanced by the deficiency of its fine adjustment. Nevertheless since the advent of achromatic and apochromatic condensers with oil contact all this is changed.

FIG. 134.

FIG. 135.

The optic axis of this instrument is capable of being rotated in three planes at right angles to one another with the object as a centre, and in addition to this it has a swinging sub-stage. This will be seen and understood from the illustrations given in figs. 134–137.

FIG. 136.

Concerning the fine adjustment of this as a Jackson model primarily we have already written.

Another leading form of the first class is the No. 1 of Messrs. R. and J. Beck. The early ancestor of it was shown on page 154, but it has undergone important changes as it is now presented (fig. 138). It is a Jackson model, the foot being a good tripod, and the trunnions on pillars (as fig. 138 illustrates). It has a short lever fine adjustment, L, acting on a movable nose-piece, and placed in front of the body so that the body and coarse adjustment are carried by the fine-adjustment screw. The stage has a rotation, but not complete. The stage aperture is not so large as it should be; on a pivot attached to the limb the

entire stage can be rotated, so as to be set at any inclination, thus complying with the temporary need so elaborately met by the 'radial' form; and the angle can be recorded on the divided plate, R. But the stage may be inverted so that an object may be placed on its under part. The sub-stage proper has no rectangular centring movements, but these are supplied on a separate adapter. There are no specialities in the character of the swinging apparatus, save that the whole of this part of the stand can be raised or lowered on a dovetailed fitting in the optical axis of the instrument by the lever, Z, in order to raise or depress the centre of the arc of the swing to keep it concentric with the object, and by that means to compensate for various thicknesses of slip. The sub-stage apparatus is focussed by the milled head W. The entire bar is attached to an arc, J, working in the circular fitting, Y, and rotated by means of the milled head X—the amount of rotation being recorded by a graduated circle —and the sub-stage can be swung above the stage on either side for dark-ground illumination. The mirror fits in a tail-piece, V, or it can be fitted on to the swinging sub-stage, U. There is an

FIG. 137.

elaborate arrangement for the rotation of the entire instrument on its foot, which is graduated at B. It is not easy to see the practical purpose of this, as the object is not in the axis of rotation; but it is provided in order that 'the microscope may be turned round without being lifted from the table, and the amount of such rotation registered.'

The workmanship of these makers is of the highest order, and many of their pieces of apparatus have great structural merit. This their leading microscope is an imposing piece of fine work; but the model we have seen has defects against which the finest workmanship and ingenuity of device strive without satisfactory result.

Swift and Son formerly made two instruments of the first class, one having a bar movement similar to that of Andrew Ross, the other a Jackson similar to Beck's. The principal difference was that the foot was of the 'bent claw' form. We have already seen that by their invention of the vertical lever fine adjustment (figs. 124 and 126) Swift and Son have made possible a useful future for the Jackson limb; and their model of this form, with the exception of an incomplete stage rotation, has the stage and sub-stage movements; the



FIG. 138.—R. and J. Beck's No. 1 stand.



Fig. 189.—Zentmayer's microscope.

latter, however, depends for its action upon a loose ring opposed on one side by a spring which is counteracted at will by screws, so altering the position of the centre of the sub-stage. It is not the best form for so important a part of the instrument.

All the movable parts of Swift's instruments are sprung on Powell and Lealand's method, and the movements are smooth and sound.

There have been many stands devised by *American opticians* during the past twelve or fourteen years, but they have been based upon one or other of the great English models, and the modifications, whether for good or evil, have been adopted into the recent modifications of the older English types, and have been incidentally described. It should be remembered that Zentmayer, of Philadelphia, devised the model from which the Ross-Zentmayer was finally formed. Its principal feature was to obtain oblique illumination in one azimuth by the swinging stage. The fine adjustment of this instrument was most defective. Tolles, again, who wholly deserves the very high reputation he attained, made an instrument in which he mounted the stage on a disc, as is now the case with the Beck model (fig. 138). Near the edge of this disc the sub-stage is made to travel in a groove carrying the condenser, or dry combination, in an arc round the object as a centre. This was only another elaboration of the same swinging sub-stage.

In later constructions of this form, Tolles first used the mechanical stage actuated by two pinions vertical to the surface of the stage, and subsequently adapted by Ross (fig. 128). The fine adjustment in this instrument had the fatal defects characteristic of its form.

Bulloch, another American maker of note, made some modifications in the Zentmayer model, but they were in the interests of the swinging sub-stage, and, although no doubt ingenious, must pass with this transient form of the microscope.

An illustration of the leading form of Zentmayer's microscopes is seen in fig. 139.

It will be noted that, as in the case of the Ross form of it (fig. 133) its chief characteristic—no longer, if ever, a merit—is its swinging sub-stage. But this has the claim of being the first modern instrument to respond to the cry for swinging sub-stage, and certainly no better response has subsequently been made.

In the stage on the complete instrument is the ingenious arrangement of a glass super-stage, which has been so freely adopted in England on a certain class of instrument, and, in the absence of a complete mechanical stage, is the only substitute to be tolerated.

But another stage was made with this instrument, shown in fig. 140, with, however, some modifications in detail. This is not distinct from English forms of stage of long standing.

A modification of this stand was devised by Bulloch, seen in fig. 141. It presents no special point, save the employment of a Gillett condenser with the diaphragm drum *above the lenses*!

A later development of this form of instrument is given by the same maker some years later, and shown in fig. 142; but the chief difference consists in the adoption of a stage in which the milled heads stand *upon* the stage, which is the reverse of an advance.

An instrument made by Bausch and Lomb, and known as their *professional microscope*, is illustrated in fig. 143. It is on the same general plan, but the mirror and sub-stage bars can be moved independently of each other, or simultaneously when the arm on the mirror is placed in a recess in the sub-stage bar.

A speciality claimed for this form is a 'frictionless fine adjustment'; but it is one of the many which have the intolerable burden of lifting the entire body of the instrument to secure the delicate focal adjustment of the object-glass; and, although highly ingenious, is therefore, to our mind, wholly imperfect for the end in view.

Mr. George Wale, of America, devised a plan of some merit for certain classes of microscopes. The 'limb' which carries the body and the stage, instead of being swung by pivots—as ordinarily—on the two lateral supports (so that the balance of the microscope is greatly altered when it is much inclined), has a circular groove cut



FIG. 140.—Zentmayer's stage.

on either side, into which fits a circular ridge cast on the inner side of each support, as shown in fig. 144. The two supports, each having its own fore-foot, are cast separately (in iron), so as to meet to form the hinder foot, where they are held together by a strong pin; while by turning the milled head on the right support the two are drawn together by a screw, which thus regulates the pressure made by the two ridges that work into the two grooves on the limb. When this pressure is moderate, nothing can be more satisfactory than either the smoothness of the inclining movement or the balancing of the instrument in all positions; while, by a slight tightening of the screw, it can be firmly fixed either horizontally, vertically, or at any inclination. The 'coarse' adjustment is made by a smooth-working rack; but the fine adjustment is made to carry the whole weight of

the body and the coarse adjustment. This modification has also been adapted by Swift and Son to some of their many instruments.



FIG. 141.—Bulloch's stand.

We are now prepared to consider **second-class microscopes,** which, for practical purposes, are simply smaller forms of the first class, with some of the elaborate work omitted. Thus the stage

Fig. 142.—Bulloch's new Congress stand.

rotation is usually without a rack-and-pinion movement, while stan and stage are smaller. But in the best instruments the body-tube i



FIG. 143.—Bausch and Lomb's professional stand.

the same length, and they receive the same objectives and sub-stage fittings as No. 1.

As a model *we prefer Beck's 'small first-class' stand* to their large instrument. It has an excellent single pillar tripod foot, Turrell's arrangement of milled heads (like Powell and Lealand's stands) for

FIG. 144.—Mr. George Wale's instrument with new form of limb.

the mechanical movements of the stage, and rectangular movements for the sub-stage. This is a fine instrument, and would be admirable in every way with a more perfect fine adjustment. *Powell and Lealand's second-class instrument* is, in all essential particulars, built upon the principle of their No. 1 stand, though less elaborate.

In instruments of the second class there is by no means so great

a variety, there being not so great a demand for these as there is for those of the third class.

It will be useful to discuss the relative merit of the third in contrast with the first class ; but before doing so it will be well to examine some of the best instruments presented to the purchaser as belonging to this class.

Third-class Microscopes.—Powell and Lealand make one having a *quality* of work not second even to their large stand. It greatly resembles their second-class instrument. It is illustrated in fig. 145. The tube length is the same, but the stage and the foot are smaller than in the second-class instrument. There is no rotary movement to the sub-stage, and its centring is done by the crossing of sectors and not lines at right angles ; but this is in no way a defect. All the movements and adjustments are otherwise as in No. 1.

As a rule, third-class microscopes are without mechanical stages; in this respect Powell and Lealand's is an important exception, because it has a stage provided with the most perfect mechanism that can be employed.

Beck's third-class microscope is shown in fig. 146. It has a good flat tripod foot with a single pillar. The Jackson model is used, but a peculiar fine adjustment is employed, the lever being placed below the stage, the screw being placed immediately behind the pillar which supports the limb, and where it is easy of access. The body is not affected by vibration when it is touched.

The lever is of the second order, and it supports the body limb and coarse adjustment. In fact, save in its fine adjustment, this form approximates somewhat to the Continental model. The fine-adjustment lever is rather short, but it will be found to be steadier and slower than the direct-acting screw.

The stage is plain, without mechanical movements ; but it has a movable glass stage over the principal stage ; to this the slip is clipped and the whole super-stage of glass is moved with much ease over a fair area. The aperture in the glass stage is not large enough ; it should be cut right through to the front, which would much increase its usefulness.

This instrument also has a sub-stage with rack and centring movements.

Swift and Son's third-class microscope in its most suitable form dates from about the time of the vertical lever fine adjustment patented by that firm. It was first made from the designs of Mr. E. M. Nelson, and it presented three distinctive features :—

(1) The milled head of the fine adjustment was placed on the left-hand side of the limb.

(2) The stage was of a horse-shoe form, the aperture being entirely cut out to the front of the stage ; and

(3) The body-tube, which was of standard size, viz. 8¾ inches, was made in two pieces which not only secured portability, but also permitted the use of both long and short tubes.

This instrument is illustrated in fig. 125. It was also possessed of a cheaply made and fairly good centring sub-stage, to carry Powell and Lealand's dry achromatic combination fitted with a turn-

out rotary arm to carry stops. The sub-stage was made by adapting Swift's centring nose-piece, and providing it with a rack-and-pinion focussing arrangement, as illustrated in fig. 147. There was also a graduated stage-plate and sliding bar, a plan devised by Mr. Lewis

FIG. 145.

Wright for a finder. The eye-pieces were provided with rings, like Powell and Lealand's, outside the tube to govern the depth which each should slide into the draw-tube, by which means the diaphragm is in the same place whatever the depth of the eye-piece employed,



FIG. 146.—Messrs. R. and J. Beck's third-class microscope.

and it was constructed to do critical work with the highest powers.

Another form of this instrument has recently been introduced by the firm of Chas. Baker, of Holborn, London. It arose on a suggestion by Mr. Nelson, that this form should be adapted to the Campbell *differential screw fine adjustment*, making a good quality third-class microscope. It should be noted that the differential screw permits of slow action being obtained by means of *coarse threads*; it is therefore very strong. In the ordinary Continental form of direct-acting fine-adjustment screw, if the motion is *slow*, the thread *must* be fine. Hence in forms where the fine adjustment is made to lift the body, the differential screw is of great value. Fig. 148 illustrates this admirable instrument. It has a large tripod foot of the Powell and Lealand type, a pillar horse-shoe stage with a sliding bar, a condenser focussing by a spiral action, and a rack-and-pinion coarse adjustment to the body, with draw-tube arranged to work with apochromatic objectives made for either long or short tube.

FIG. 147.—Centring nose-piece and sub-stage.

FIG. 148.—Nelson's form.

This instrument has the peculiarity that the stage is 1½ inch below the trunnions, which has the effect of lowering the centre of gravity when the instrument is in a vertical or nearly vertical posi-

tion. When horizontal the optic axis is $8\frac{1}{2}$ inches from the table. The ends of the feet are plugged with cork.

It proved on testing that the Campbell differential screw was equal to the most critical work, and could be used in photo-micrography. As a result several additions were made, such as rack-and-pinion focussing and rectangular movements to the sub-stage and a rack-work arrangement to the draw-tube. Subsequently a larger and heavier instrument was made, having a $\frac{1}{4}$-inch more of horizontal height. In this model the milled head of the differential screw is placed below the arm, instead of above it, which is an improvement for photo-micrographic purposes, and no special detriment in ordinary work; and, if required, a differential-screw fine adjustment can be fitted to the sub-stage. A rotary stage is also sometimes put to this instrument, but those which we have seen have not given the aperture sufficient dimensions for modern focussing.

This instrument in its complete form as devised by Baker is shown in fig. 149. The stage has changed its form; but if the aperture be kept large enough this may be fully counterbalanced by the rotation given to it, and with the Campbell screw fitted behind the mirror for the fine adjustment of the condenser is a very attractive and useful microscope, and may be safely recommended to the amateur and the student.

There is not sufficient rack-work to focus the 70 mm. objective of Zeiss, but the nose-piece unscrews and the objective is held inside the tube by an adapter.

This larger form of the instrument is placed amongst microscopes of the third class because it is unprovided with a mechanical stage, but a supplementary and removable mechanical stage, devised by Mr. John Mayall and made by Baker, and Swift, and also by Zeiss, of Jena, can easily be added, as it is in the figure (149). This acts fairly well, and is a useful appendage for more delicate stage work.

Fourth-class Microscopes.—These should have a rack-and-pinion coarse adjustment and a direct-acting differential-screw fine adjustment, a plain stage and, if possible, a sliding tube sub-stage. Beck's 'Economic' is of this class, as is also the 'Star' microscope by the same makers. The former has the flat tripod, as fig. 150, representing this instrument, shows, and it may be obtained furnished with a glass super-stage. The present Editor can speak highly of this instrument for elementary class work, and especially with a glass stage. The 'Star' microscope is also a very remarkable instrument, sufficiently so to justify us in departing from a rule to point out that with two eye-pieces, two objectives—a $\frac{1}{2}$-inch and a $\frac{1}{6}$-inch—a sub-stage condenser, with an iris diaphragm, with the whole placed in a cabinet, is sold for 5*l.* 15*s.*

An instrument of the same class is made by Swift and Son; it is shown in fig. 151—a very common model, having rack-and-pinion coarse adjustment, direct-acting screw fine adjustment, and plain stage on a 'bent claw' foot. When first introduced these instruments were little better than the Hartnack instruments made in England, with inclining bodies on a claw foot, instead of a solid mass of metal. But they have been greatly improved in the past few years.

Microscopes are made also like the last, without rack-and-pinion coarse adjustment, by many makers, which might be classed as **fifth-**

FIG. 149.—Baker's modification of Nelson's form.

class instruments, while some are yet made *without a fine adjustment*; and it is a little notable that the best of this class was made by the late Hugh Powell, whose maxim was that a microscope with only a *good* coarse adjustment was to be preferred to one having only a fine adjustment with a sliding tube for the coarse adjustment.

This stand is of cast iron, with a flat tripod, having a singl pillar to which is jointed the Jackson body. The focussing is ad mirable ; the stage is of an excellent form, being $4\frac{1}{2} \times 3\frac{1}{2}$ inches



FIG. 150.—Beck's economic microscope.

and is supplied with a beautifully made sliding ledge, which wi move easily and firmly with pressure from one side only.

The stage is fastened to the upper side of two brackets which are cast in one piece with the limb; on the under side of these brackets there is another plate which holds the sub-stage tube.

This instrument is supplied with large plane and concave mirrors; and considering that it constitutes a sixth class of microscope has very much in its favour as a secondary instrument for the work-table. Like all these makers' instruments the feet are plugged with cork

FIG. 151.—Swift's fourth-class microscope.

and we know of some of these microscopes that have been in use for forty years, and are still the trusted 'journeymen' instruments of mounters and other workers of various orders in many departments of microscopy.

The Messrs. Beck also make a microscope of this kind called a 'histological dissecting microscope.' It is illustrated in fig. 152; the body is removable, and 'loups' or simple lenses can be used instead.

The two modes of use are seen in the figure. In this case, howeve the body does not incline; but in simplicity and price for an i strument of this class it deserves commendation.

Portable Microscopes.—Microscopes that may be readily tak from place to place, and which are yet provided with the arrang ments required for using the principal apparatus, are of importan in some investigations, and are desirable by the majority of those wl have a living interest in microscopic work.

The earliest, and still the best form of this kind of microsco was made by Powell and Lealand. As opened for use it is illustrat in fig. 153; but the tripod foot folds into what becomes practically a single bar, and is bent by means of a joint to occupy the least space. The body unscrews, and the whole lies in a very small space, giving at the same time fittings in the cabinet for lenses, condensers, and all needful apparatus. The coarse and fine adjustments to the body are as in the No. 1 stand, so are the stage movements; and the sub-stage



FIG. 152.—Beck's histological and dissecting microscope.

has rack-and-pinion movements and rectangular sector centrir while all the apparatus provided with the largest instrument can employed with it. We have used this instrument for delicate a critical work for fifteen years and there is no falling off in its quality and when packed with the additional apparatus required the case 12 × 7 × 3 inches.

Swift and Son subsequently made an instrument on similar lin The tripod and stage are packed practically as was Powell and Le land's, but the stage in this case is plain. It carries a very co venient achromatic condenser, to which we call attention in its prop

place; but its fine adjustments is so unsteady that it cannot be used with high powers or for critical work.

This instrument "set up" is seen in fig. 154, and it is packed

FIG. 153.—Powell and Lealand's portable microscope.

condition it is illustrated in fig. 155. The case in which the instrument is packed is $10\frac{1}{8} \times 6\frac{5}{16} \times 3\frac{5}{16}$ inches.

The Messrs. Beck were the next in order of time to make an instrument of this kind. This is illustrated in fig. 156. It differs

from the two preceding forms in being a Jackson model. The binocular body and the coarse adjustment have to be lifted and lowered by the fine adjustment whenever it is used. The stage is plain, but it rotates, and the sub-stage has no centring gear. The instrument packs into a box $10\frac{1}{2} \times 7\frac{1}{2} \times 3\frac{1}{2}$ inches. There is a condenser specially made for this instrument.

Mr. Rousselet has designed an admirable little instrument of portable form but of the sixth class. It is binocular. The tripod folds; the stage is plain, with a sliding ledge. The condenser focusses by

FIG. 154.—Swift's portable microscope.

means of a spiral tube, within which an inner tube slides, carrying stops, diaphragms, &c. The mirror is jointed so as to be used above the stage; and as its focus is only $1\frac{1}{2}$ inch can be used as a side reflector. It is also arranged so that eye-pieces with large field glasses may be employed. It packs in a box $10\frac{1}{2} \times 5\frac{1}{2} \times 3\frac{1}{2}$ and weighs six pounds complete.

Microscopes employed for the purpose of minute dissection are of considerable importance in certain kinds of work. Many instruments specially adapted are made, although the majority are arranged for simple lenses. But an instrument of great value arranged for

use with *compound lenses* has been devised by engraving the binocular of Mr. Stephenson. This instrument is illustrated in fig. 177. It is made by Swift and Son. The stage is a large, flat table, with special rests for the arms. The objective and binocular part of the body remain vertical and focus vertically by a rack-and-pinion coarse adjustment, there being no fine adjustment. The bodies above the binocular prisms are suitably inclined, mirrors being placed inside them to reflect the image. This reflexion also causes the erection of the image, which is valuable to the majority engaged in insect dissection or the dissection of very delicate and minute organisms or organs.

We have now to consider *the mind principles* [illegible] simple microscopes. That in the form of a bull's eye stand is the

FIG. 177

least complex form possible. This instrument holds an intermediate place between the hand-magnifier and the complete microscope, being, in fact, nothing more than a lens supported in such a manner as to be capable of being readily fixed in a variety of positions suitable for dissecting and for other manipulations. It consists of a circular brass foot, wherein is screwed a short tubular pillar, the top of which is 'sprung' at its upper end, so as to grasp a second tube also 'sprung,' by the drawing out of which the pillar may be elongated by about three inches. This carries at its upper end a jointed socket, through which a square bar about 3½ inches long slides rather stiffly: and one end of this bar carries another joint, to which is attached a ring for holding the lenses. By lengthening or shortening the pillar, by varying the angle which the square bar makes with its summit, and by sliding that bar through the socket, almost any po-

tion and elevation may be given to the lens that can be required for the purposes to which it may be most usefully applied, care being

FIG. 156.—Beck's portable microscope.

taken in all instances that the ring which carries the lens should (by means of its joint) be placed horizontally. At A is seen the position

which adapts it best for picking out minute shells or for other similar manipulations, the sand or dredgings to be examined being spread upon a piece of black paper and raised upon a book, a box, or some other support to such a height that when the lens is adjusted thereto the eye may be applied to it continuously without unnecessary fatigue. It will be found advantageous that the foot of the microscope should not stand upon the paper over which the objects are spread, as it is desirable to shake this from time to time in order

FIG. 157.—Swift's Stephenson's binocular, arranged for dissecting purposes.

to bring a fresh portion of the matters to be examined into view; and, generally speaking, it will be found convenient to place it on the opposite side of the object, rather than on the same side with the observer. At B is shown the position in which it may be most conveniently set for the dissection of objects contained in a plate or trough, the sides of which, being higher than the lens, would prevent the use of any magnifier mounted on a horizontal arm. The powers usually supplied with this instrument are one of an inch focus, and a second of either a half or a quarter of an inch. By unscrewing

the pillar, the whole is made to pack into a small, flat case, the extreme portability of which is a great recommendation. There is, however a form of mounting for this instrument, which was devised by Quekett, which has superior advantages. In the form illustrated we are obliged to mechanically arrange the horizontality of the lens which, of course, is important. In Quekett's form the loup or lens is so hung in a ring that it has a pendulous motion and with every change in the position or angle of the bar, the lens, by the action of gravity, become perfectly horizontal. This is by far the best form of mounting. Although the uses of this little instrument are greatly limited by its want of stage, mirror, &c. yet, for the class of purposes to which it is suited, it has advantages over perhaps every other form that has been devised. Where, on the other hand, portability may be altogether sacrificed, and the instrument is to be adapted to the making of large dissections under a low magnifying power, some such form as is represented in fig. 159—constructed by Messrs. Baker on the basis of that devised by Professor Huxley for the use of his Practical Class at South Kensington — will be found decidedly preferable. The framework of the instrument is solidly constructed in mahogany all its surfaces being blackened, and is so arranged as to give two uprights for the support of the stage and two oblique rests for the hands. Close to the summit of each of these uprights is a groove into which the stage-plate slides ; and this may be either a square of moderately thick glass or a plate of ebonite having a central perforation into which a disc of the same material may be fitted so as to lie flush with its surface, one of those being readily



FIG. 158.

substituted for the other, as may best suit the use to be made of it. The lens is carried on an arm working on a racked stem, which is raised or lowered by a milled-head pinion attached to a pillar at the further right-hand corner of the stage. The length of the rack is sufficient to allow the arm to be adjusted to any focal distance between two inches and a quarter of an inch. But as the height of the pillar is not sufficient to allow the use of a lens of three inches focus (which is very useful for large dissections), the arm carrying the lenses is made with a double bend, which, when its position is reversed, as in the dotted outline (which is readily done by unscrewing the milled head that attaches it to the top of the racked stem), gives the additional inch required. As in the Quekett microscope, a compound body may be easily fitted, if desired, to a separate arm capable of being pivoted on the same stem. The mirror frame is fixed to the wooden basis of the instrument, and places for the



FIG. 159.—Laboratory dissecting microscope.

lenses are made in grooves beneath the hand-supports. The advantages of this general design have now been satisfactorily demonstrated by the large use that has been made of it; but the details of its construction (such as the height and slope to be given to the hand-rests) may be easily adapted to individual requirements.

A very portable simple microscope stand has been designed by Mr. Ward to take a Steinheil × 10 aplanatic loup. It consists of a circular table on three legs; it has a mirror, one side of which is arranged for white cloud illumination; it also has a bull's-eye for opaque. The focussing is performed by a sliding arm, and the whole packs into the remarkably small area of a case whose outside dimensions are $3\frac{1}{2} \times 2\frac{1}{2} \times 1$ inches.

But the very best form of dissecting microscope *for loups or simple lenses* which we believe to be at present constructed is made by Zeiss. We illustrate this form, fig. 160. It has a large firm stage 4 inches square and $4\frac{1}{2}$ inches from the table, to which wooden arm-rests can



Fig. 160.—Zeiss dissecting microscope.

attached, or not, as may be desired. The stage has a large ning, 3 × 3½ inches, into which can be placed either a flat brass e, or a glass substitute, or a metal plate with a half-inch hole in Underneath the stage are black and white screens which can ily be turned aside. The arm which is focussed by an excel- spiral rack-work adjustment carries either a Zeiss dissecting roscope, which with and without its concave eye-lens yields six erent powers, varying from 15 to 100 diameters, or the arm will ive the very fine Zeiss-Steinheil *loupe*.

The instrument is provided with a large plane and concave ror on a jointed arm. The utility of this simple microscope is y great, and we do not hesitate to pronounce it the best thing its class we have ever seen.

A substantial and elaborate form of *dissecting microscope, devised*

FIG. 161.—Beck's binocular dissecting microscope.

the late Mr. R. Beck, is represented in fig. 161. From the angles square mahogany base there rise four strong brass pillars, which port at a height of four inches a brass plate 6½ inches square, having ntral aperture of one inch across ; upon this rests a circular brass e, of which the diameter is equal to the side of the preceding, which is attached to it by a revolving fitting that surrounds the tral aperture, and can be tightened by a large milled head eath ; whilst above this is a third plate, which slides easily over second, being held down upon it by springs which allow a move- nt of 1½ inch in any direction. The top plate has an aperture 1½ inch for the reception of various glasses and troughs suitable containing objects for dissection ; and into it can also be fitted ring-holder, suitable to receive and secure a glass slide of the inary size. By turning the large circular plate the object under ervation may be easily made to rotate, without disturbing its

relation to the optical portions of the instrument; whilst a traversing movement may be given to it in any direction by acting upon the smaller plate. The left-hand back pillar contains a triangular bar with rack-and-pinion movement for focal adjustment, which carries the horizontal arm for the support of the lenses; this arm can be turned away towards the left side, but it is provided with a stop which checks it in the opposite direction, when the lens is exactly over the centre of the stage-aperture. Beneath this aperture is a concave mirror, which, when not in use, lies in a recess in the mahogany base, so as to leave the space beneath the stage entirely free to receive a box containing apparatus; whilst from the right-hand back corner there can be raised a stem carrying a side condensing lens, with a ball-and-socket movement. In addition to the single lenses and special combinations ordinarily used for the purposes of dissection, a binocular arrangement was devised by Mr. R. Beck, on the principle applied by MM. Nachet, about the same date, in their stereo-pseudoscopic microscope. Adopting Mr. Wenham's method of allowing half the cone of rays to proceed to one eye without interruption, he caused the other half to be intercepted by a pair of prisms, and to be by them transmitted to the other eye. But we find its utility to be practically limited by the narrowness of its field of view, by its deficiency of light and of magnifying power, and by the inconvenience of the manner in which the eyes have to be applied to it.

The Continental Model.—Our one purpose in this treatise is to endeavour to promote what we believe to be the highest interests of the microscope as a mechanical and optical instrument, as well as to further its application to the ever-widening area of physical investigation to which, in research, it may be directed. To this end throughout the volume, and especially on the subject of the value and efficiency of apparatus and instruments, we have not hesitated to state definitely our judgment, and, where needed, the basis on which it rests. Incidentally we have expressed perhaps more than once our *disapproval*, and with ourselves that of many of the leading English and American microscopists, *of the form of microscope known as the Continental model*; and we cherish strong hopes in the interests of the science of microscopy that so enterprising and eminent a firm as that of Zeiss, of Jena, will bring out a model that will comport more completely with the needs of modern microscopical research than even the best of the models that they now produce. It is to this house, under the cultivated guidance of Dr. Abbe, that we are indebted for the splendid perfection to which the optical side of the microscope has been recently brought; and when we know that the 'Continental model' has in the hands of the firm of Zeiss passed from an instrument without inclination of the body into an instrument that does so incline, and from an instrument without sub-stage or condenser into one provided with the latter of these absolutely indispensable appendages, and finally from an instrument with a perfectly plain stage with 'clips' into what is now a stage with mechanical movements—we can but hope that these concessions to what has belonged to the best English models for over forty years may lead

to an entire reconstruction of the stand—a wholly new model—intended to meet all the requirements of modern high-class work in all departments, and with a fine adjustment of the most refined class. We cannot doubt, if this were so, that the same genius which has so nobly elevated the optical requirements of the instrument would act with equal success on its construction and mechanism.

We have written throughout this book too frankly of the eminent services of Messrs. Zeiss to the furtherance of the interests and progression of the microscope as a scientific instrument to be misunderstood in making a plain estimate of the quality of the *model* on which their elaborate and in some senses beautiful stands are built. It will be seen that we everywhere justify our judgments by plain and easily comprehended reasons, and the very eminence of the makers renders it incumbent that practical microscopists should, without a shade of bias, assess the value of a stand which is certainly not built on lines that contribute to a higher and still more efficient microscopy.

At the same time we do not blind ourselves to the fact that an English market for the 'Hartnack' model has had very much to do with the perpetuation of the errors which that form contains.

The reason of this it is not difficult to trace. *The inductive method* advanced but slowly, in practice, upon the professional activities and even the professional training of medical men. The country which was the home of Bacon and Newton, and Harvey and Hunter theoretically accepted, but was not quick to apply, the methods of induction to the work of its medical schools. Theory and empiricism held a powerful place in both the teaching and practice of medicine in England until the earlier years of the present century. Medicine was absolutely unaffected by Bacon until the latter half of the seventeenth century. It was not until the early years of this century that the modern school of medicine began its beneficent career. But at that time *the microscope*—one of the most powerful instruments which can be thought of in the application of experimental and deductive methods to the science of medicine—was looked upon and treated by the faculty as a philosophical toy, a mere plaything for the rich *dilettanti*. But in spite of this the microscope was brought gradually to a high state of perfection, and by the end of the first third of the century was remarkably advanced as a practical instrument, all its essentials being more or less completely developed. Meanwhile, on the Continent, the microscope was regarded by the Faculty as a scientific instrument of great and increasing value, being used to good purpose in making important discoveries in anatomy, histology, and biology generally.

This was gradually *realised in this country*, and there arose slowly a desire to employ the same instrument in England. But, although English instruments of the most practical and relatively perfect kind, representing the large experience of many careful amateurs, were easily accessible to our medical men in their own country—because it was on the Continent that the investigations referred to had been made—it was nothing less than the *Continental microscope* that was sought after and obtained. Because early

observations of a histological character (and therefore of a nature t lie beyond the sphere of the lay amateur) had been successfully mad with a certain form of microscop on the Continent, it was practi cally argued that this must be the most suitable instrument for such a purpose; but this was an inference made without knowledge of or reference to the well-known English models.



FIG. 162.

Let us carefully examine this instrument. The typical form was that made by Hartnack. Seen in its best primitive state, we have it in one of Zeiss' instruments represented in fig. 162. It is a non-inclining instrument with a short tube on a narrow horse-shoe foot, in which steadiness is obtained by sheer weight. It has a sliding tube as a coarse adjustment, and a direct-acting screw for the fine adjustment. The stage is small, and the aperture in it is relatively still smaller of no service in reaching the focus of an object by touch with a high power. It is provided with spring clips, and a diaphragm immediately below the stage, and a concave mirror.

A *sub-stage condenser* was rarely used, because up to a comparatively late date (1874) it was regarded by many on the Continent as a mere elegant plaything; its true value was not perceived.

On this model all the microscopes of the firm of Zeiss, of Jena, are constructed, as they are used almost exclusively on the Continent, and are regarded in many of the universities and medical schools, both here and in America, as possessing all the qualities required for the best biological research.

If we examine the finest of these instruments made up to 1885, we are impressed, as we

always are, with the beauty and care of the workmanship and finish of this firm; but there is the same heavy horse-shoe foot, steady enough while the instrument is *non-inclining*, only needlessly heavy, requiring common ingenuity alone to get equal steadiness with one-fourth the weight. But since this instrument has been adapted to the English form by being made to incline to any angle up to the horizontal, the foot but insecurely balances the instrument; it is not difficult as it is not uncommon to topple it over. Indeed, in their photo-micrographic outfit the Messrs. Zeiss practically see this, for they supply *another foot to which the microscope is clamped.*

It must not be forgotten that this want of balance is with the short, not the long body.

The diameter of the tube is small, being slightly over seven-eighths of an inch. That this is seen to be a disadvantage would appear certain, because the *photographic microscope model of Zeiss has a larger body-tube*; and in their recent 'Appendix' to their latest catalogue they admit that for certain purposes other stands made by them, 'owing to the limited diameter of their tubes, cut off the field;' a significant fact for those who would narrow the English body.

At this present date out of eighteen models ten are made with inclining bodies, and three have sliding coarse adjustment. But in the twelve models for 1889 ten incline, while only two are rigid, and eight have rack-work against four having sliding tubes for coarse adjustment. This is a manifest conformity of the primitive model to the English type.

The *direct-acting screw*, only slightly modified, obtains universally in these models. We have already plainly said that this is not sufficiently delicate in its action for critical work with an apochromatic objective of 1·4 or 1·5 numerical aperture, especially as a micrometer screw with a necessarily delicate thread is bound to carry the combined weight of the body, limb, coarse adjustment, and the opposing spring; that it will wear loose under the stress of constant work is inevitable, and thus its utility must be wholly gone.

The 1889 model has a new form of fine adjustment, the alteration being that the micrometer screw acts on a hardened steel point; this may cause it to work smoother, but as no weight is taken off, there is difficulty in discovering any reason for its admitting of more prolonged use without injurious wear.

The stage of this instrument, in common with all built on the same model, has three fundamental errors of design:—

i. The stage is so narrow that the edges of the 3 × 1 slips are, in some Continental stands, allowed to project over the edges. Messrs. Zeiss have profitably departed from this fault, by giving to their larger stands a stage in size more like the English type.

ii. The stages have an aperture so small as to limit their usefulness in focussing with high powers.

iii. Instead of a sliding ledge they provide, what still more efficiently militates against easy and rapid focussing, viz. spring clips. It is unfortunate that no stage on this model admits of the use of the finger to aid in reaching the focus. This gentle tilting up of the object, as we approach the focal point, would save hundreds

of cover-glasses and objective fronts; and we have reason to know that not a few are broken with this form of stage; but we have never seen put forward, and do not know, a single reason in justification of a small aperture in the stage.

Another important point is the absence of *rotation* in the ordinary Continental stand. True rotation is a strictly English feature, but its value is great, and it is an indispensable adjunct to practical work.

Messrs. Zeiss have introduced a substitute for a rotary stage; they have done this by making the body and limb *solid with the stage*, so that the whole rotates together.

Practically there is only *one* point in favour of such a movement, and that is, that the object remains exactly in the same position in regard to the field. But against this arrangement there is—

1. The liability of throwing the optic axis above the stage out of centre with that below the stage, and this though the workmanship be, as it is, of the highest order.

2. The rotation of a microscope object for ordinary examination is really unimportant, as there can be no top or bottom to it. Even for oblique illumination it is not required, as it is always easier to rotate the illuminating pencil. The only instances in which rotation of the object is important are: (*a*) *When the object is polarised*, and then it is a distinct disadvantage not to be able to rotate the object independently of the body which carries the analyser. In short, the stage rotating independently of the body would be preferable because, if it is required to rotate the object on a dark polarised field, the polarising and analysing prisms *can be set at the proper angles*, and then the object rotated without disturbing the relative positions of the prisms.

But this cannot be done with the arrangement of the Zeiss model, which rotates body and stage.

(*β*) *For photo-micrographic purposes.*—In this case in the Zeiss stand the head of the fine-adjustment screw is geared to the focussing rod; so, manifestly, rotation of the body becomes impossible.

Thus, by adopting rotation in the form chosen, the highest ends for which the microscope stage *should revolve* cannot be accomplished.

The sub-stage is often quite wanting in the common Continental forms. This was true of the Hartnack stands, with rare exceptions; the Nachet instruments were provided with an elementary form.

As we have seen, until quite recent times, the *condenser was regarded on the Continent as a superfluous, if not a foolish appliance*, but that prejudice has been killed by the light thrown on the whole question by (1) the chromatic (1873), and now (2) the achromatic condenser of Abbe. But even a *compound* condenser was in use in England in the year 1691, and the best work in England since the invention of achromatism has never been done without one.

In the mounting of the Abbe condenser every possible ingenuity has been displayed to make it do its work without a sub-stage; but a permanent centring and focussing sub-stage into which this optical arrangement could, *amongst others*, fit, might be made for half the labour, ingenuity, and cost. But rather than this, we have the con-

denser made to slide on the tail-piece, and to be jammed with a screw.

It has therefore neither centring nor focussing gear, but, striking as it may appear, a *diaphragm*, which cannot be used with, and is no part of, the condenser, *is supplied with mechanical centring* and rack-work focussing movements! That is to say, *the delicate centre of an optical combination may take care of itself*; but a diaphragm aperture must be centred by mechanism and focussed by rack!

We know that the idea involved in a rack-work diaphragm is the graduation in the angle of the cone of illumination from the plane mirror by racking a certain sized diaphragm up or down. But this can be better done by an iris diaphragm or, more perfectly still, by a wheel of diaphragms.

Now, in reality, nothing is so important as the centring and focussing of the condenser, after we are once provided with perfect objectives; so that whilst the iris diaphragm or a rotating wheel of diaphragms would meet all the case of the racking and centring of these, there is nothing in the best stands of what is doubtless the largest and most enlightened house for the manufacture of microscopes in the world, to supply the indispensable *needs* of the modern condenser.

We observe with pleasure advances in every direction to which we call attention to defects. The more recent instruments are marvels of ingenuity; we present, in fig. 163, the latest and finest form of Zeiss's best microscope.

There is no fault in the workmanship, it is the best possible. *The design only is faulty*; there is nothing to command commendation in any part of the model; and, seeing that the Messrs. Zeiss have now progressed so far as to furnish their first-class stand with the English mechanical movement, and even stage rotation, we can but believe that the advantages of these improvements will make plain the greater advantage that would accrue from an entirely new model.

The Purchase of a Microscope.—A desire to possess a good but not costly microscope is extremely common, but as a rule the intending purchaser has little knowledge of the instrument and does not profess to know what are the indispensable parts of such an apparatus, or what parts may, in the interests of economy and his special object, be dispensed with, leaving him still possessed of a sound and well-made instrument. We may briefly consider this matter.

The first question to be asked when a microscope is to be purchased is, 'What is the order of importance of the various parts of a microscope?' In answering this query it will be to some extent true that subjectivity of judgment will appear. But we believe that the following table of the relative order of importance of the parts of a microscope will commend itself to all workers of large and broad experience:—

1. A coarse adjustment by rack and pinion.
2. A sub-stage.
3. A fine adjustment.
4. Mechanical movements to sub-stage, i.e. focussing and centring.
5. Mechanical stage.

FIG. 103.—Zeiss's latest stand.

6. Rack-work to draw-tube.
7. Finder to stage.
8. Plain rotary stage.
9. Graduation and rack-work to rotary stage.
10. Fine adjustment to sub-stage.
11. Rotary sub-stage.
12. Centring to rotary stage.

This table gives in order the relative values of the several parts: thus, a microscope with a rack-and-pinion coarse adjustment and a sub-stage is to be prefered before a microscope with a rack-and-pinion coarse adjustment, a *fine adjustment*, but *no sub-stage*. Or, a microscope with a coarse adjustment by rack and pinion, a sub-stage, and a fine adjustment is to be preferred before one with the same coarse adjustment and a mechanical stage movement, but no sub-stage or fine adjustment; and so on. The last item is of least importance, and the importance of all the others is in the order of their numeration.

Another matter of some significance to the tiro is the relative value from the point of view of time consumed and, therefore, of prime cost, in producing the several kinds of microscopes. The No. 1 stands of half-a-dozen makers may be near the same cost, but may nevertheless have involved the consumption of very different quantities of the highest class of skilled labour in their production.

Manifestly the first thing to be looked at in a microscope making any pretensions to quality is the *character of the workmanship*; and this should carry with it the question, how much machine, and how much hand work and fitting, there is in it. Arcs graduated on silver, for example, are very attractive, and with many are most impressive; but they are simply machine work and quite inexpensive.

In the two great types of models, the bar movement and the Jackson limb, the bar movement involves more than double the actual hand fitting; while a fine adjustment with a movable nose-piece takes twice the fitting of one in which the whole body is moved by the fine-adjustment screw. In the same way a *mechanical stage* which is made of machine-planed plates, sliding in a machine-ploughed groove, is much less costly in time and quality of labour than a hand-made sprung stage. So a *sub-stage* having a movable ring pressed by two screws against a spring has very far less work, and work of a lower class, than one with a true rectangular centring movement.

It will follow, then, that a Jackson-limbed microscope with no movable nose-piece, with a machine-made mechanical stage, and a movable ring for sub-stage, will not have involved more, perhaps, than a third of the skilled work which must be expended on a well-made instrument of the same size with a bar movement. But, if we compare the range of prices as presented by English and American makers, we rarely find an equivalent difference in cost.

Then the tiro will be warned by this not to purchase a pretentious instrument with a bar movement and mechanical stage for, say, *5l.*

But *if a low-priced instrument is to be purchased*, if, as is almost certain, it be a Jackson model, see that it has a rack-work coarse adjustment, eschew the *short-lever nose-piece*, and have a differential

screw fine adjustment, a large plain stage, and an elementary centring sub-stage. Such an instrument should be obtained for 5*l.* 10*s.*

Although not frequently used, it would be doing our work imperfectly not to refer to **a special form of microscope devised for chemical purposes.** This is an *inverted microscope* originally constructed by MM. Nachet on the plan devised by Dr. J. Lawrence Smith, of Louisiana, U.S.A., for the purpose of viewing objects from their *under* side when heat or reagents are being applied to them,[1] has lately been improved by its constructor with a special view to



FIG. 164.—Nachet's chemical microscope.

meeting the requirements of observers engaged in the 'cultivation' of the minute organisms which act as ferments. The general arrangement of this instrument is shown in fig. 164. On the table which forms its base there rests a box containing a glass mirror, silvered on its upper surface, which is placed at such an angle as to reflect the light-rays received through the inverted objective mounted on the top of the box into the body fixed into its oblique face. Over the objective is placed the stage, above which again is the mirror for reflecting light downwards through the object placed upon it. The focal adjustment is made in the first place by means of a sliding tube which carries the objective, and then by the micrometer-screw,

[1] This idea was suggested at nearly the same time by Dr. Leeson, and was carried out in an instrument constructed for him by Messrs. Smith and Beck.

V, which raises or lowers the stage. The platform on which the optical apparatus rests can be moved in rectangular directions by the two milled heads, O, T, and is furnished with two graduated scales by means of which it may be brought with exactness into any position previously recorded, so that any point of the object may be immediately re-found—an arrangement of special value in cultivation experiments. On the stage is a circular glass cell, C, for holding the fluid to be examined; in the bottom of this is an aperture which is closed by a piece of thin cover-glass well cemented round its edges, thus allowing the use of high magnifying powers having a very short focus: while its top is ground flat, so that a cover of thin plate glass may be closely fitted to it by the intervention of a little

FIG. 165.—Bausch and Lomb's laboratory microscope, used for chemical work.

grease or glycerine, the whole being secured in its place by three small uprights. The cell is furnished also with two small glass taps, R, R, with which indiarubber tubes are connected. By this cell—which may be made to serve as a moist, a warm, and a gas-chamber—experiments on the rarefaction and compression of air, and on the absorption of gases, can be made with great facility. For 'cultivation' experiments smaller cells are provided, which are attached to brass plates so arranged as to have a fixed position on the stage.

The Bausch and Lomb Optical Company have now *combined the above with the ordinary vertical form of microscope*, the principle involved being (they believe) entirely new. This form of instrument is particularly adapted for chemical investigations, for the reason

that crystals may be studied as they lie in their natural position in any depth of fluid, and the head is sufficiently distant from the stage not to inhale any fumes.

Further than this, it is valuable in the examination of diatomaceæ and other objects in water which are heavier than it, and therefore sink to the bottom; also in the moist histological preparations, as

FIG. 166.—The same instrument changed into an ordinary form.

they adhere to the surface of the slide, and are therefore in one plane. It is also an excellent dissecting microscope, as it is partially erecting, offers no hindrance to manipulation with any power, and makes it convenient to observe the object directly. There are two forms, the 'Laboratory' and the 'University.' The Laboratory microscope, when used as an inverted instrument, is shown in fig. 165.

The mirror-bar swings on an axis in the plane of the stage to any point above or below it. The mirror and sub-stage are adjustable on the mirror-bar.

The sub-stage carries a revolving diaphragm, and is fixed on a pivot, so that it will swing in and out of the optic axis, allowing the polariser to be attached and ready for instant use. On the slide is the arm, to the lower side of which is fastened the prism box.

On the upper horizontal surface of this is the nose-piece, with an extra adapter for high powers, and in the oblique surface is a screw-socket for the body-tube.

To transform the instrument into an ordinary microscope (fig. 166), the tube is unscrewed, the milled head at the front of the arm loosened, which releases the prism box, and the arm is swung on its



FIG. 167.—The 'University' microscope as a chemical instrument.

axis from between the pillars into an upright position. The tube is now attached to the opposite side of the nose-piece, and after the stage-clips are reversed it is ready for work.

The 'University' microscope (figs. 167 and 168) is in its general construction similar to the preceding, except that the (single) pillar and the arm are not japanned, but are of brass, and that the instrument swings on an axis which is the same as that of the mirror-bar. The stage consists of a glass plate mounted in a brass ring.

The prism used for inversion is that suggested by Mr. J. Lawrence Smith in 1851, having four faces, with angles of 57°, 150°, 48°, and 105°, the rays being twice totally reflected.

Tank microscopes (also called aquarium microscopes) have, for

certain kinds of work, a value of their own. They may be used with low powers outside the glass or above the water; or the object-glass may be protected by a water-tight tube outside it, and with a disc of glass fixed (also water-tight) into that end of the tube which stands below the front lens of the objective, at a proper distance for the focus, may then be plunged into the aquarium. Indeed, the tube of the instrument may be so protected as to work for some depth, and have some range in the water of a good-sized tank.



Fig. 168.
The 'University' microscope fixed for upright use.

A beautiful instrument of this class has been devised by Mr. J. W. Stephenson for the examination of living objects in an aquarium. A brass bar is laid across the aquarium, as shown in the woodcut (fig. 169). To adjust it to aquaria of different widths the support on the left is made to slide along the bar, and it can be clamped at any given point by the upper milled head. The milled head at the side, by pressing on a loose plate, fastens the bar securely to the aquarium.

Between the ends of the bar slides an arm carrying a sprung socket, and the arm can be clamped at any given point of the bar. Through the socket is passed a glass cylinder, cemented to a brass collar at the upper end, and closed at the lower by a piece of cover-glass. Into this cylinder is screwed the body-tube of the microscope with eye-piece and objective, which are thus protected from the water of the aquarium. The microscope is focussed by rack and

pinion (milled head just below the eye-piece), and in addition the objective is screwed to a draw-tube, so that its position in the cylinder may be approximately regulated.

The arm of the socket is hinged to allow of the microscope being inclined in a plane parallel to the sides of the aquarium. The lower milled head clamps the hinge at any desired inclination.

The socket also rotates on the arm, so that the microscope can be inclined in a plane parallel to the front of the aquarium. Thus any point of the aquarium can be reached.

A very convenient form for some classes of botanical work with very low powers, and also for aquarium work of a general kind, was

FIG. 169.

devised by Ross and Co. It may be either monocular or binocular, and has a rack movement on a horizontal bar, giving it considerable range; and a rack focal movement on the upright bar and on the body, with an additional screw movement in a direction to and from the observer, so that all the principal movements are arranged in its construction. Its general character will be understood by the illustration given in fig. 170. It is extremely useful in the general study of small tanks.

Mr. C. Collins's aquarium microscope (fig. 171) differs from all other forms in that it is applied to the side of the aquarium itself. This is accomplished by making use of a simple pneumatic apparatus. The head of the 'sucker' is shown on the left of the drawing, with

an indiarubber ring surrounding a central piston. The ring is applied to the glass surface of the aquarium, and the air is exhausted by screwing round the head of the piston seen on the right. Two turns are sufficient to fasten the sucker securely. The rod to which the support of the body-tube is attached passes through the sucker-arm, and can be clamped at any height desired.

Professor E. Schultze has designed and Messrs. Klönne and Müller have made the microscope, fig. 172, for the observation of small aquatic organisms in an aquarium specially constructed for the purpose. There are three parts : (1) the stand, the greater part of which is nickel-plated ; (2) the aquarium ; (3) the illuminating mirror.



Fig. 170.

The stand consists essentially of a microscope-tube, which is supported in a horizontal position upon a tripod in such a way that it can be moved in three different directions by rack and pinion. The column of the tripod carries a rack and pinion, by which the tube is moved vertically. On the tube which carries the rack is a sliding piece with a second rack for the horizontal movement from right to left ; upon this slide the microscope is fixed in a horizontal position, and can be moved backwards and forwards in a tube provided with rack and pinion. There are therefore three movements—vertical, horizontal-lateral, and horizontal-sagittal—so that the organism

observed can be followed by the tube as it moves upon the glass wall of the aquarium.

The aquarium consists of a stand with a frame which carries the aquarium proper, 10 cm. in breadth and height and 10 mm. in thickness; this may be replaced by others. The frame is made of brass lacquered black. The aquarium itself consists of a horseshoe-shaped piece of glass, both sides of which are closed by plates of cover-glass, leaving the upper end open. It is thus possible to observe an organism upon either of the two thin sides with an objective giving a linear amplification of 200 to 300. To screen off the superfluous light and the numerous reflexions in the aquarium, the frame carries a diaphragm arrangement which can be applied on either side at pleasure. This consists of a sliding plate which moves the two horizontal guides; it is divided into three parts, and has an oblong

FIG. 171.—Collins's aquarium microscope, applied to the aquarium by a 'sucker.'

opening in one of the divisions. In this opening a thin plate slides, and can be clamped at any point. In this plate again is a circular aperture, which can be closed to a greater or less extent by various diaphragms kept in position by a small spring.

If an animal or other small organism is on the upper left-hand corner of the side turned towards the microscope, the sliding plate is first moved so that the vertical longitudinal opening lies in the left-hand third, the small plate is then set so that its opening lies in the upper third. If, on the other hand, the animal is on the right-hand side, the larger sliding plate is moved so that the longitudinal opening lies on the right, and if the animal is towards the bottom, the small slide with its opening is moved downwards. The two sliding plates are now so directed that light may be thrown by the mirror through the aquarium and upon the animal on the front side. The aperture can be further reduced by diaphragms.

The mirror is concave, 10 cm. in diameter, and fixed upon its stand with a ball-and-socket joint so that it can be adjusted in any position.

As an adjunct, and admirable aid to the student of the tank and pond, as well as a simple and easy means by which specific forms of microscopic life may be be found and readily taken, we call attention to the tank microscope of Mr. C. Rousselet. It is illustrated in fig. 173 and scarcely needs further description.

One of Zeiss's Steinheil 'loups' or aplanatic lenses, to which we have referred, is carried on a jointed arm, which is clamped to the tank,[1] the tank being nowhere deeper than the range of focus of the lens employed. The arm moves on a plane parallel to the side

FIG. 172.—Professor E. Schultze's aquarium microscope.

of the tank, and the lens is focussed by means of a rack and pinion, arranged upon the body of the clamp, as seen upon the left-hand corner of the figure. The following points will recommend themselves to those who are in the habit of looking at their captures with the pocket lens in the ordinary way :—

When an object of interest is found, it can be followed with the greatest ease and taken up with a pipette, both hands being free for this operation.

[1] We prefer to have a stand or 'rest' for the tank, and on one side of this a firm pillar to which (and not to the side of the aquarium) the jointed arm is clamped. This enables shallower and deeper tanks to be employed without shifting the rack carrying the 'loup.'

It so frequently happens that a minute object is lost simply by moving the pocket lens for an instant to take up the pipette; the above apparatus the lens remains in the position in which it has been placed.

Microscopes have been arranged in many ways to facilitate class demonstration in microscopic work, but we have seen none that is more simple, efficient, and inexpensive than that suggested by Mr. Beale. The instrument is made by attaching the outer tube on a wooden support to a horizontal board, which also carries a small lamp attached to it in the required position (fig. 174). The object having been fixed in its place, and the coarse adjustment made by sliding the body in the outer tube, these parts may then be immovably secured, nothing being left movable except the eye-tube, by sliding which in or out the fine adjustment may be effected. Thus

FIG. 173.—Rousselet's aquarium microscope.



FIG. 174.

the whole apparatus may be passed from hand to hand with the greatest facility, and without any probability of disarrangement, and every observer may readily 'focus' for himself, without any risk of injuring the object.

CHAPTER IV

ACCESSORY APPARATUS

THIS chapter on apparatus accessory to the microscope might b easily made to occupy the whole of the space we propose to devote t the entire remainder of the book ; the ingenuity of successive micr scopists and the variety of conditions presented by successive improv ments in the microscope itself have given origin to such a variet of appliances and accessory apparatus that it would be futile in practical handbook to attempt to figure and describe. We propos therefore, only to describe, and to explain the mode of successfull employing, the essential and the best accessories now in use, neglec ing, or only incidentally referring to, those which are either su planted, or which present modifications either not important in thei selves, or accounted for by the fact of their production by differe opticians.

I. **Micrometers and Methods of measuring minute Objects.**— is of the utmost importance to be able with accuracy, and as mu simplicity as possible, to measure the objects or parts of objects th are visible to us through the microscope.

The simplest mode of doing this is to project the magnifi image of the object by any of the methods described under 'Came Lucida and Drawing' (p. 233). If we carefully trace an outli of the image, and then, without disturbing any of the arrangemen remove the object from the stage, and replace it with a 'stage m crometer,' which is simply a slip of thin glass ruled to any desir scale, such as tenths, hundredths, thousandths of an inch and u wards. Trace now the projected image of this upon the same pap and the means are at once before us for making a comparison betwe the object and a *known scale*, both being magnified to the same e tent. The amount of magnification in no way affects the proble Thus, if the drawn picture of a certain object exactly fills the i terval between the drawing representing the ·01 inch, the obj measures the ·01 inch, and whether we are employing a magnifyi power of a hundred or a thousand diameters is not a factor th enters into our determination of the size of the object. In fact, drawings of microscopic objects are rendered much more practica valuable by having the magnified scale placed beneath them, so th measurements may at any time be made.

In favour of the above method of micro-measurement, it will noted (1) that no extra apparatus is required, (2) that it is extrem simple, and (3) that it is accurate.

The most efficient piece of apparatus for micro-measurement

without doubt the SCREW-MICROMETER EYE-PIECE; it was invented by Ramsden for telescopes, and if well constructed is a most valuable adjunct to the microscope. It is made by stretching across the field of an eye-piece two extremely fine parallel wires, one or both of which can be separated by the action of a micrometer screw, the circumference of the brass head of which is divided into a convenient number of parts, which successively pass by an index as the milled head is turned: it is seen in fig. 175, B. A portion of the field of view on one side is cut off at right angles to the filaments by a scale formed of a thin plate of brass having notches at its edge, whose distance corresponds to that of the threads of the screw, every fifth notch being made deeper than the rest to make the work of enumeration easier. In the original Ramsden eye-piece one filament was stationary, the object being brought into such a position that one of its edges appeared to touch the fixed wire, the other wire being moved by the micrometer screw until it appears to lie in contact



FIG. 175.—The micrometer eye-piece.

with the other edge of the object; the number of entire divisions on the scale then shows how many complete turns of the screw had been made in the separation of the wires, while the number of index-points on the edge of the milled head shows the value of the fraction of a turn that may have been made in addition. Usually a screw with 100 threads to the inch is employed, which gives to each division in the scale in the eye-piece the value of $\frac{1}{100}$th of an inch, whilst the edge of the milled head is usually divided into 100 parts.

Both wires or filaments have since been made to move, a screw and divided head being fixed to the wire that Ramsden made stationary. There is no advantage in this plan, and it involves needless complexity in calculation. The best method, there can be no doubt, is the one employed by Mr. Nelson, which is to have one thread fixed, but *not* in the *centre* of the eye-piece, but five notches in the scale from the centre on the side furthest from the screw-head. This not only permits of a much larger object being spanned, but also keeps the average of measurements in the middle of the 'field.' This is not only convenient but important, because the magnification is not uniform throughout the field. If the power

employed is high, in order to effect the span of the great magnification, one wire (the fixed *central* one) will be in the middle of the field, the other at the margin, and the comparison will not be true on account of the unequal magnification of the eye-piece throughout the field, whereas if the wire be placed five notches on one side, both measurements are brought more within the centre of the field.

Messrs. Zeiss now make a Ramsden *micrometer eye-piece*. It is provided with a glass plate with crossed lines, which together with the eye-piece are carried across the image formed by the objective



Fig. 176.

by means of the measuring screw, so that the adjustment always remains in the centre of the field of view.

Fig. 176 illustrates this instrument, complete and in longitudinal section.

Each division on the edge of the drum corresponds to 0·002 mm. Whole turns are counted on a numbered scale seen in the visual field, and the image may be measured up to 8 mm.

A modification of this instrument, facilitating both accuracy and simplicity, has recently been devised by Mr. Nelson, of which we think highly, and of which we give an illustration in fig. 177.

This screw micrometer eye-piece differs from those of the old form mainly in two respects: first, the optical part is compensated; secondly, the micrometer part with both webs can be made to traverse *en bloc* the field of the eye-piece by screw motion.

More particularly speaking, the instrument consists of two parts: one, a flat rectangular box containing the fixed and movable webs, the micrometer screw and divided head complete; the other part may be called an 'eye-piece adapter' with an outer case to hold the above-mentioned rectangular box.

The flat inner box has a screw attached to it which engages with a head on the exterior of the outer box. This gives about one inch of screw movement to the inner box, which causes the webs to traverse the field of the microscope. It must be remembered that this in no way affects the movement of the movable web from the fixed, which can alone be accomplished by turning the graduated micrometer head as in the old form.

The 'eye-piece adapter' portion of the instrument is, as its name implies, merely an adapter to take the optical part of positive compensating eye-pieces of various powers.

FIG. 177.—Nelson's new form of screw micrometer eye-piece.

Immediately below the web is an iris diaphragm. This permits a diaphragm to be used suitable to the power of the eye-piece employed. A guiding line at right angles to the webs has been added. Care must be taken to observe that when the movable web coincides precisely with the fixed web, the indicator on the graduated head stands at zero. If this is *not* the case, the finger screw must be loosed, which will liberate the graduated head, and then it can be placed in its proper position and fixed. This is of universal application to all screw micrometers.

Four points are gained by this arrangement :—

(1) The compensating eye-piece yields far better definition when measuring with apochromatic objectives than either the Huyghenian or Ramsden forms.

(2) Different-powered eye-pieces can be employed.

(3) By means of the screw which moves the micrometer webs across the field it is possible to perform measurements with the webs equidistant from the centre of the field, and thus eliminate errors due to distortion.

(4) The preceding advantage is secured without sacrificing the benefit of a fixed zero web.

To use the screw micrometer with success it should not be inserted, as the custom has been, like an ordinary eye-piece into the tube of the microscope, but *it should have a firm stand quite independently*, preventing actual contact with the body-tube.

Plate II. gives the mode of its employment, the illustration being

made from a photograph by Mr. Nelson. The micrometer eye-piece, it will be seen, is fitted into a stand wholly independent of the microscope. This consists of a strong upright, fitted into a massive tripod or circular foot. The foot in either case only rests on three points; the upright is capable of telescopic extension by a clamping tube; a short tube which takes the eye-piece is fixed to this upright by a compass joint.

To use it the object to be measured is placed in position, and the microscope inclined in the usual way. The ordinary eye-piece is removed, and the separate stand with the micrometer in its place is put in front of the microscope, the extension tube being raised or lowered until the tube at the top of it, carrying the micrometer, is made continuous with the tube of the microscope, as seen in the drawing. It is well to leave from $\frac{1}{8}$th to $\frac{3}{16}$ths of an inch of space between the body-tube and the micrometer tube. It will be now needful to employ corrections to compensate for the increased length of tube. If the objective be provided with a 'correction collar' the adjustment must be recorrected; but if it is not so provided the tube of the microscope must be shortened exactly as much as the tube carrying the micrometer will have lengthened it.

By this arrangement it will be found that manipulation can be effected without the vibration of the microscopical image which is inevitably the result of the revolving of the micrometer screw-head when the micrometer eye-piece is placed, as it usually has been, in the body-tube of the microscope. The consequence is that much more minute spaces can be measured, and with much greater accuracy. Mr. Nelson has repeatedly spanned the $\frac{1}{10000}$th of an inch by means of a stage micrometer in the focus of the objective: this was replaced by a mounted specimen of *Amphipleura pellucida*, and he has counted ninety-six lines in the $\frac{1}{10000}$th of an inch by making the movable wire pass successively over them until the fixed wire was reached. By similar means the Editor has measured single objects less than the $\frac{1}{100000}$th of an inch.

It will have been premised by the careful reader that the stage micrometer must be used in every set of measurements; at least we would strictly emphasise this as the only accurate and scientific method. It has been advised that a record of comparisons with the various lenses in the possession of the microscopist should be made once for all. We decidedly deprecate this method, unless it be in such utterly valueless work, as is sometimes done, where lenses are uncorrected and accuracy of tube-length forgotten or ignored. The correction of an objective and the tube-length ought to vary with every object, and therefore a comparison of the stage-micrometer and the screw-micrometer should be made with every set of measurements.

Moreover, the majority of stage micrometers exhibit very considerable discrepancies in the several intervals between the lines; it is well in the interests of accuracy to take the screw value of each under a high power, find the value of the average, and then note the particular space or spaces that may be in agreement with the average and always use it. An illustration will make this clear.

THE ARRANGEMENT OF MICROSCOPE WITH STAND FOR MICROMETER EYE-PIECE AS EMPLOYED TO SECURE STEADINESS AND ACCURACY IN MEASUREMENT.

GENOA
NATIONS

Zeiss provides a stage micrometer of 1 mm. divided into ·1 and ·01. The following are the actual values obtained for each of the ·05 divisions, viz.—

8·40
8·37
8·38
8·38
8·36
8·36
8·58
8·33
8·31
8·47
8·33
8·33
8·38
8·44
8·38
8·40
8·37
8·40
8·25
8·38
20)16·760
8·38 mean value.

In this instance it will be seen that the last division, 8·38, agrees with the mean, and is the best for all future use.[1]

Having thus obtained a screw-micrometer value for a certain known interval, the screw-micrometer value for any other object being known, the size of the object may be found by simple proportion: thus, viz. if 8·38 is the screw-micrometer value for ·05 mm. and 6·45 that for a certain object, the size of the object is

(i) $8{\cdot}38 : 6{\cdot}45 :: {\cdot}05 : x$ mm.;

$$x = \frac{6{\cdot}45 \times {\cdot}05}{8{\cdot}38} = {\cdot}0385 \text{ mm.}$$

If the answer is required in fractions of an English inch, all that we need remember is that 1 inch = 25·4 mm.; then

(ii) $8{\cdot}38 : 6{\cdot}45 :: \frac{{\cdot}05}{25{\cdot}4} : x$ inch;

$$x = \frac{6{\cdot}45 \times {\cdot}00197}{8{\cdot}38} = \frac{{\cdot}0127}{8{\cdot}38} = {\cdot}001515 \text{ inch.}$$

If the stage-micrometer is ruled in fractions of English inches, then suppose the screw-micrometer value for $\frac{1}{1000}$th inch = 4·257, and that for the object = 6·45 as before.

(iii) $4{\cdot}257 : 6{\cdot}45 :: {\cdot}001 : x$ inch;

$$x = \frac{6{\cdot}45 \times {\cdot}001}{4{\cdot}257} = {\cdot}001515 \text{ inch.}$$

[1] In the number given for screw value the whole number stands for a complete revolution or number of revolutions of the screw-head, and the decimal, the portion of a revolution read off beyond this.

If the answer is required in metrical measurement, then as 1 inch = 25·4 mm.

(iv) $4{\cdot}257 : 6{\cdot}45 :: (\cdot001 \times 25{\cdot}4) : x$ mm. ;

$$x = \frac{6{\cdot}45 \times {\cdot}0254}{4{\cdot}257} = \frac{{\cdot}1638}{4{\cdot}257} = {\cdot}0385 \text{ mm.}$$

In this connection it will be as well to give two examples of scale comparison which are sometimes required. Thus you have a certain interval on a metrical stage micrometer which you know to be accurate, and you wish to compare an English stage micrometer with this scale in order to find out which particular interval of $\frac{1}{1000}$ inch agrees with it. Suppose ·05 mm. = 8·38 screw value as above, then all that is necessary is to find the point to which the screw micrometer must be set in order that it may accurately span the $\frac{1}{1000}$ inch. Take 1 inch = 25·4 mm. as before ; then ·001 inch = ·0254.

(v) ·05 mm. : ·0254 mm. :: 8·38 : x screw value ;

$$x = \frac{{\cdot}0254 \times 8{\cdot}38}{{\cdot}05} = 4{\cdot}257 \text{ screw value.}$$

Conversely, if a metrical scale is to be compared with an accurate English one where ·001 inch = 4·257 screw value, then the screw value for ·05 mm. may be found thus : ·001 inch = ·0254 mm.

(vi) ·0254 mm. : ·05 mm. :: 4·257 : x screw value ;

$$x = \frac{{\cdot}05 \times 4{\cdot}257}{{\cdot}0254} = 8{\cdot}38 \text{ screw value for } {\cdot}05 \text{ mm.}$$

A cheap substitute for the screw-micrometer has been devised by Mr. G. Jackson. It consists in having a transparent arbitrary scale inserted into an ordinary Huyghenian eye-piece in the focus of the eye-lens, so that it will be in the same plane as the magnified image of the object to be measured. It is seen in fig. 178. The method of using it is precisely similar to that of the screw micrometer; the value of $\frac{1}{1000}$ inch or $\frac{1}{10}$ mm., as the case may be, is found in terms of the arbitrary scale. The value of the object in terms of the same scale is also found, and comparison made accordingly. All that need be done is to substitute the terms of the arbitrary scale for screw values in the preceding examples, and they will meet the case.



FIG. 178.—Jackson's eye-piece micrometer.

The arbitrary scale should be capable of movement by a screw,

otherwise the appliance is hardly as accurate as the first method of micrometry by simple drawing described above.

Of all the methods of micrometry the most accurate is that performed by photo-micrography. A negative of the object to be measured is taken, and then, without any alteration in tube- or camera-length, the magnified image of the stage micrometer is projected on the ground glass: this is spanned by means of a pair of spring dividers. The negative film is then scratched by these dividers. Then you are in a position to make the most accurate measurement the microscope is capable of yielding.

It is exceedingly important, when performing micrometric measurements, to remember that the precise edges of all objects in the microscope are never seen. Consequently it is impossible to ascertain from what point to what point the measurement is to be made.

This, while hardly affecting large and coarse objects, becomes supremely important with small objects.

Instead of a real edge to an object you get diffraction bands. These bands alter with focus, and also to a greater extent with the angle of the illuminating cone as well as with the aperture of the objective. Hence it ensues that the accurate micrometry of delicate objects presents one of the most difficult matters encountered in practical microscopy. At the present time opinions differ greatly as to the treatment of particular cases.

The following plan of Mr. Nelson's is the outcome of a long series of experiments :—

1. The focus and adjustment to be chosen may be termed that of the 'black dot' (see Elimination of errors of interpretation, p. 356); in other words, if the object were a slender filament it would be represented white with black edges. These black edges are due to diffraction. If the filament is very slender and the illuminating cone small, there may be seen a white diffraction edge outside the black one, and perhaps another faint black one outside that again.

2. Reduce, as far as possible, the extent of these diffraction bands by (*a*) using an objective with as large an aperture as possible; (*b*) by using as large an illuminating cone as possible.

3. Measure from the inner edge of the inner diffraction band to the inner edge of the inner diffraction band on the opposite side.

4. But if the diameter of a hole be required, then the measurement must be made from the outer edge of the outer black diffractive band to the outer edge of outer diffraction band on the opposite side. It must not be forgotten, however, that these rules only apply for a particular focus and a particular adjustment.

II. **The Camera Lucida and its Uses.**—There are a large number of contrivances devised for the purpose of enabling the observer to see the image of an object projected on a surface upon which he may trace its outlines, but they resolve themselves practically into two kinds, viz.

1. Those which project the microscopical image on to the surface provided for the drawing.

2. Those which project the pencil and paper into the field of the microscope.

We shall describe what we consider the most practical forms of each.

In point of antiquity *Wollaston's camera lucida* claims the post of honour; but to use it the microscope must be placed in a horizontal position. Its general form is shown in fig. 179. The rays on leaving the eye-piece, above which it is fixed by a collar, enter a prism, and after two internal reflexions pass upwards to the eye of the observer. It is easy to see a projection of the microscopic image with this instrument, but it is when we desire at the same time to see the paper and the fingers holding the pencil that the difficulty begins. The eye has to be held in such a position that the edge of the prism bisects the pupil, so that one-half of the pupil receives the microscopic image and the other half the images of the paper and the hand employed in drawing. If this bisection is not equal, too much of one image is seen at the expense of the other. This was in some sense supposed to be compensated by the use of lenses, as seen in the figure; but the difficulty of keeping the eye precisely in one position has caused this instrument to fall into disuse, several cameras being now devised free from this defect. It has nevertheless one special point in its favour—it does not invert the image, causing the right to be turned to the left, and *vice versa*. This is an advantage the value of which we shall subsequently see.

FIG. 179.

A simple camera was made by Soemmering by means of a small mirror or circular reflector, which is placed in the path of the emergent pencil at an angle of 45° to the optic axis, thus reflecting rays from the image upwards. The instrument is seen in fig. 180 and slides on to the eye-piece. The reflector must be smaller than the pupil of the eye, because it is through the peripheral portion of the pupil that the rays, not stopped out by the mirror, come from the paper and pencil. Hence, as in the case of Wollaston's camera, the pupil of the eye must be kept perfectly centred to the small reflector. As there is but one reflexion, the image is inverted but not transposed. To see the outline of the image as it is in the microscope, the drawing must be made upon tracing paper, and inverted, looking at it as a transparency from the wrong side.

FIG. 180.—Simple camera.

There is considerable variety in the experience of different microscopists as to the facility with which these two instruments can be used. The difference in all probability depends on the greater normal diameter of the pupils of the eyes of some observers in comparison with that of others.

Dr. Lionel Beale devised one of the simplest cameras, which has the advantage of being thoroughly efficient. It consists of a piece of tinted glass placed at an angle of 45° to the optic axis, in the path of the emergent pencil. The first surface of the glass reflects the magnified image upwards to the eye, the paper and

pencil being seen through the glass. In its simplest form it is seen in fig. 181. The glass is tinted to render the second reflexion from the internal surface of the glass inoperative. The reflexion of the image is identical with that of Soemmering's.

Fig. 182 shows a fitting adopted by Bausch and Lomb for the *neutral tint camera*. It is made of vulcanite, and the half ring to which the frame holding the neutral tint glass is fixed, fits on the cap of the eye-piece, and with sufficient grip.

Fig. 181.—Beale's camera.

Fig. 182.—Bausch and Lomb's fitting for Beale's neutral tint camera lucida.

Amongst the cameræ lucidæ which project the image of the paper and pencil into the microscope tube is first that devised by Amici, and adapted to the horizontal microscope by Chevalier. The eye looks through the microscope at the object (as in the ordinary view of it), instead of looking at its projection upon the paper, the image of the tracing point being projected upon the field—an arrangement which is in many respects more advantageous. This is effected by combining a perforated silver-on-glass mirror with a reflecting prism; and its action will be understood by the accompanying diagram (fig. 183). The ray *a b* proceeding from the object, after emerging from the eye-piece of the microscope, passes through the central perforation in the oblique mirror M, which is placed in front of it, and so directly onwards to the eye. On the other hand, the ray *a'*, proceeding upwards from the tracing point, enters the prism P, is reflected from its inclined surface to the inclined surface of the mirror M, and is by it reflected to the eye at *b'*, in such parallelism to the ray *b* proceeding from the object that the two blend into one image.

Fig. 183.

The Editor has used with great facility and success a camera devised by Dr. Hugo Schröder and produced by Messrs. Ross. It is figured at 184, and consists of a combination of a right-angled prism (fig. 185) A B C and a rhomboidal prism D E F G, so arranged that when adjusted very nearly in contact (i.e. separated by only a thin stratum of air) the faces B C and D E are parallel, and consequently between D E and B E′ they act together as a thick parallel plate of glass through which the drawing paper and pencil can be seen. The rhomboidal prism is so constructed that when the face G F is applied at right angles to the optic axis of the microscope, the axial ray H passes without refraction to I on the internal face E F; whence it is *totally* reflected to J in the face D G. At J a part of the ray is reflected to the eye by *ordinary* reflexion in the direction of J K, and a part transmitted to J′ on the face A C of the right-angled prism. Of the latter a portion is also reflected to K by ordinary reflexion at J′. The hypothenuse face A C is cut at such an angle that the reflexion from J′ coincides with that from J at the eye point K, thus utilising the secondary reflexion to strengthen the

FIG. 184.—Schröder's camera lucida.



FIG. 185.—Diagram explaining Schröder's camera lucida.

luminosity of the image. The angle G is arranged so that the extreme marginal ray H′ from the field of the B eye-piece strikes upon D G at a point just beyond the angle of total reflexion, the diffraction-bands at the limiting angle being faintly discernible at this edge of the field. This angle gives the greatest amount of light by *ordinary* reflexion, short of *total* reflexion.

In use, the microscope should be inclined at an angle of 45°, and the image focussed through the eye-piece as usual; the camera is then placed in position on the eye-piece, and pushed down until the image of the object is fully and well seen. The drawing paper must be fixed upon a table on a level with the stage immediately under the camera. The observer will then see the microscopical image projected on the paper, and the fingers carrying the pencil point will be clearly in view, the *whole* pupil of the eye being available for both images, the diaphragm on the instrument being considerably larger than the pupil. The eye may be removed as often as required, and if all is allowed to remain without alteration, the drawing may be left and recommenced, without the slightest shifting of the image.

If a vertical position of the microscope be needful, this may be

done by inclining the table and drawing paper to an angle of 45° either in front or at the side of the microscope. For accurate drawing, in all azimuths, the drawing paper should of course coincide with the plane of the optical image.

This camera may be used with a hand-magnifier, or with simple lenses used for dissection and other purposes.

Professor Abbe has also devised an instrument which we have used with complete success. The accompanying drawing (fig. 186) will at once show the simplicity of its action. The image of the paper and pencil coming, say, in a vertical direction (S_p fig. 186) is reflected by a large mirror in a horizontal direction, W, to a cube of glass which has a silvered diagonal plane with a small circular hole in it in the visual point of the eye-piece. The microscopic image is seen directly through this aperture in the silvering of the prism, while the silvered plane of the prism transmits the image of the paper and the operator's fingers and pencil. By the concentricity thus obtained of the bundle of rays reaching the eye from both the microscope and the paper, the image and the



FIG. 186.

pencil with which it is to be drawn are seen coincidentally without any straining of the eyes.

This instrument requires the paper to be placed in a plane parallel to that of the object; thus, if the microscope is vertical the paper must be horizontal, and *vice versa*, and it presents the image precisely as it is seen in the microscope. For the purpose of drawing simply, and where the observer has had no experience in the use of a camera lucida, we should be inclined to recommend this one as the instrument presenting to the tiro the greatest facility. But there is a use to be made of the camera lucida to which this one does not so readily lend itself, which is none the less of great importance; that is, the determining of the magnifying power of objectives. It is manifest that the distance between the paper and the eye of the observer cannot be so readily determined in this case as in those forms of the instrument where the image of the paper and pencil is seen direct.

With one or other of the foregoing contrivances, everyone may learn to draw an outline of the microscopic image; and it is extremely desirable for the sake of accuracy that every representation of an object should be based on such a delineation. Some persons will use one instrument more readily, some another, the fact being

that there is a sort of 'knack' in the use of each, which is commonly acquired by practice alone, so that a person accustomed to the use of any one of them does not at first work well with another. Although some persons at once acquire the power of seeing the image and the tracing point with equal distinctness, the case is more frequently otherwise; and hence no one should allow himself to be baffled by the failure of his first attempt. It will sometimes happen, especially when the Wollaston prism is employed, that the want of power to see the pencil is due to the faulty position of the eye, too large a part of it being over the prism itself. When once a good position has been obtained, the eye should be held there as steadily as possible, until the tracing shall have been completed. It is essential to keep in view that the proportion between the size of the tracing and that of the object is affected by the distance of the eye from the paper; and hence that if the microscope be placed upon a support of different height, or the eye-piece be elevated or depressed by a slight inclination given to the body, the scale will be altered. This it is, of course, peculiarly important to bear in mind when a series of tracings is being made of any set of objects which it is intended to delineate on a uniform scale.

A valuable adjunct to a camera lucida is a small paraffin lamp, seen to the left of Plate III., which illustrates the correct method of using the camera lucida; this lamp is simple and is capable of being raised or lowered, fitted with a paper shade, for a great deal of the success attendant on the use of the camera depends on the relative illumination of the microscopic image on the one side and of the paper and fingers and pencil of the executant on the other. It is not a matter to be determined by rules; personal equation, sometimes idiosyncrasy, determines how the light shall be regulated. Many finished micro-draughtsmen use a feeble light in the image, and a strong light on the hand and paper, and others equally successful manipulate in the precisely reverse way. But upon the adjustment of the respective sources of light to the personal comfort of the draughtsman will depend his success.

Care must be exercised in this work in the case of *critical images*. These must not be sacrificed either by racking the condenser into or out of focus, or by reducing its angle by a diaphragm. If the intensity of the light has to be reduced, it must be done by the interposition of glass screens, and this is beautifully provided in Abbe's camera. The illustration of how the various apparatus for the use of the camera lucida should be disposed, given in Plate III., may be profitably studied. Both mirror and bull's-eye are turned aside, and the hand and pencil are illuminated by the shaded lamp.

The lamp illuminating the image is seen, with such a screen of coloured glass as may be found needful, and the lamp illuminating the paper and pencil, and carefully shaded above, is also seen at the eye-piece end of the body-tube. Often, if the image is too bright, we find that bringing the lamp down to illuminate the paper more intensely suffices. If not, use screens; the illuminating cone must not be tampered with.

III. **The determination of magnifying power** is an important and independent branch of this subject. For this purpose, and for



Arrangement of the Microscope and Accessories for the Employment of the Camera Lucida.


PUBLIC LIBRARY
ASTOR

the reason given above, Beale's neutral tint camera[1] is eminently suitable—indeed, is the best. We can easily and accurately measure the path of the ray from the paper to the eye. What is necessary is to project the image of a stage micrometer on to an accurate scale placed ten inches from the eye-lens of the eye-piece. There must be complete accuracy in this matter.

We can best show how absolute magnifying power is thus determined by an example.

Suppose that the magnified image of two $\frac{1}{1000}$ths of an inch divisions of the stage micrometer spans $\frac{8}{10}$ths of an inch on a rule placed as required; then

(i) ·002 inch : ·8 inch :: 1 inch : x power;

$$x = \frac{\cdot 8 \times 1}{\cdot 002} = 400 \text{ diameters};$$

for it is obvious that under these conditions one inch bears the same proportion to the magnifying power that $\frac{2}{1000}$ths of an inch bears to $\frac{8}{10}$ths of an inch.

Suppose, now, as it sometimes happens, that the operator is provided with a metrical stage micrometer, but is without a metrical scale to compare it with, there being nothing but an ordinary foot-rule at hand.

Let it be assumed that the magnified image of two $\frac{1}{100}$ mm. when projected covers $\frac{8}{10}$ inch; then, as there are 25·4 mm. in one inch

(ii) ·02 mm. : (·8 inch × 25·4) :: 1 : x power;

$$x = \frac{\cdot 8 \times 25 \cdot 4 \times 1}{\cdot 02} = 1016 \text{ diameters.}$$

If the reverse is the case, viz. that you have an English stage micrometer and a metrical scale, then, if the magnified image of two $\frac{1}{1000}$ inch spans 18 mm.,

(iii) ·002 inch : $\frac{18}{25 \cdot 4}$ :: 1 : x;

$$x = \frac{\cdot 7086 \times 1}{\cdot 002} = 354 \cdot 3 \text{ diameters.}$$

The above results indicate the combined magnifying power of the objective and eye-piece taken at a distance of ten inches. The arbitrary distance of ten inches is selected as being the accommodation distance for normal vision.

The magnifying power, however, is very different in the case of a myopic observer. Let us investigate the case of one whose accommodation distance is five inches.

Here he will be obliged, in order to see the object distinctly, to form the virtual image from the eye-piece at a distance of five inches. To do this he must cause the objective conjugate focus to approach the eye-lens; consequently he must shorten his anterior objective focus. In other words, he must focus his objective nearer the object. This will have the effect of causing the posterior conjugate focus to recede from the objective towards the eye-lens, and the fact of bringing the inverted objective image nearer the eye-lens brings also the virtual image of the eye-lens nearer.

[1] Page 235.

Shortening the focus of the objective has the effect of increasing its power; but as this alteration is proportionately very little, the increase in power is very small; but the shortening of the eye-piece virtual from ten to five inches has the effect of nearly halving its power. Consequently the combined result of the eye-piece and objective in the case of halving the eye-piece virtual is to nearly halve the power of the microscope. The increase of the objective power is practically so small that it may be neglected.[1] In practice it is found by us that if the image is projected on a ground glass screen ten inches from the eye-piece, the image is nearly the same size whether focussed by ordinary or myopic sight. This is in harmony with Abbe's demonstration (pp. 25, 26, fig. 28) that both images are seen under the same visual angle. But, on the other hand, if a myopic sight compares the image with a scale, the magnification will be less than with ordinary vision.

To find the precise initial power of any lens, or to find the exact multiplying power of any eye-piece, is not so easy. A laborious calculation, involving the knowledge of the distances, thickness, and refractive indices of the lenses, is required. But a very approximate determination, sufficiently accurate for all practical purposes, may be easily made, especially if one has a photo-micrographic camera at hand. The principle is as follows.

Select a lens of medium power—a $\frac{1}{4}$-inch is very suitable. Now with the microscope in a horizontal position, and with a powerful illumination, project the image of the stage micrometer on to a screen distant five feet, measured from the back lens of the objective. If no photo-micrographic camera is at hand, it will be necessary to perform the experiment in a darkened room shading the illuminating source. Divide the magnifying power thus obtained by 6; the quotient will give the initial power of the lens at ten inches to a very near approximation.

The reason why the result is not perfectly accurate is that the ten inches must be measured from the posterior principal focus of the lens, and that is a point which is not given. But in the case of a power such as a $\frac{1}{4}$, it is, in practice, found to be very near the back lens of the objective. So by taking a long distance, such as five feet, the error introduced by a small displacement of the posterior principal focus does not materially amount to much.

There is a further error introduced by the approximation of the objective to the stage micrometer in order to focus the conjugate at such a distance, but this is small. We can see, therefore, that this error tends to slightly increase the initial magnifying power.

The initial power of the $\frac{1}{4}$ being found, and its combined magnifying power, with a given eye-piece, being known, the combined power divided by the initial power gives the multiplying power of the eye-piece. Care must be of course taken to notice the tube-length[2] when the combined power is measured. The initial power of any other lens may be found by dividing the combined power of

[1] *English Mechanic*, vol. xlvi. No. 1185. Article on measurements of magnifying power of microscope objectives by E. M. Nelson.

[2] *Ibid.* vol. xxxviii. No. 981, 'Optical Tube-length,' by Frank Crisp.

that lens with the eye-piece, whose multiplying power has been determined, by the multiplying power of that eye-piece.[1]

Nose-pieces.—The term nose-piece primarily means that part of a microscope into which the objective screws, but the term is also applied to various pieces of apparatus which can be fitted between the nose-piece of the microscope and the objective. There are, for instance, rotating, calotte, centring, changing, and analysing nose-pieces.

Nose-pieces, although thought to be so, are not a modern idea; our predecessors of a century ago employed similar means. Mr. Crisp has recently acquired a microscope, which possesses a double arm, at the end of which is a cell for receiving different lenses. This cell fits over the end of the nose-piece, and so keeps the several objectives which may be inserted in position. It dates, in all probability, from the end of the seventeenth or the early part of the eighteenth century.

FIG. 187.—Rotating disc of objectives.

But in the early days of the microscope rotating discs of objectives, as shown in fig. 187 (or, perhaps, older still, a long dovetailed slide of objectives, such as fig. 188 shows), were frequently employed.

It is continually desirable to be able to substitute one objective for another with as little expenditure of

FIG. 188.—Sliding plate of objectives.

time and trouble as possible, so as to be able to examine under a higher magnifying power the details of an object of which a general view has been obtained by means of a lower; or to use the lower for the purpose of *finding* a minute object (such as a particular diatom in the midst of a slideful) which we wish to submit to higher amplification. This was conveniently effected by the nose-piece of Mr. C. Brooke, which, being screwed into the object end of the body of the microscope, carries two objectives, either of which may be brought into position by turning the arm on a pivot. This is shown in fig. 189.

FIG. 189.—Brooke's nose-piece as made by Swift.

[1] *English Mechanic*, vol. xlvi. No. 1178, 'Measurement of Power,' by E. M. Nelson.

The most generally useful of all nose-pieces now in use are the rotating forms which enable one to carry two, three, or four objectives on the microscope at one time, and by mere rotation each is successively brought central to the optic axis, seen in figs. 190, 191, 192, as supplied by Messrs. Beck. It is almost unnecessary now to point out the disadvantage of those older and straight forms which involved the danger of knocking out the front lens of the objectives by bringing it into contact with some part of the stage while the other objective was being focussed. This objection has been entirely removed by the introduction of the bent form by Messrs. Powell and Lealand, and others, shown in figs. 189–192. There can be no doubt that for ordinary dry lens work some such device is imperative. Some, however, who do a very large amount of microscopical work prefer to use two microscopes; the one a third or fourth class microscope, with only a coarse adjustment and a 1-inch objective and mirror, the other having a coarse and fine adjustment and a $\frac{1}{4}$-inch objective with a simple form of condenser and plane mirror, all fine and higher power work being left for a special microscope.

The one drawback to the use of a rotating nose-piece is the extra



Fig. 190.



Fig. 191.



Fig. 192.

weight it throws upon the fine adjustment. As this subject is fully treated of under the heading of 'Microscope' no more will be said at present than that a double nose-piece is to be preferred to a triple, and a quadruple need not be entertained for a delicate instrument unless it is required to find out in how short a time a fine adjustment may be ruined; for let it be noted that a 2-inch, 1-inch, $\frac{1}{2}$-inch, and $\frac{1}{4}$-inch objective of English make weigh together $8\frac{1}{2}$ oz. without any nose-piece.

For the proper use of a rotating nose-piece the length of the objective mounts should be so arranged that when the objective is changed little focal adjustment will be necessary.

An excellent calotte nose-piece for four objectives is made by Zeiss; this is so arranged that only the optical portion of the objective is screwed into the nose-piece. This plan much lightens it, so that the nose-piece and the four lenses weigh $3\frac{3}{4}$ oz., or only 1 oz. more than an English $\frac{1}{4}$-inch with a screw collar, and $\frac{1}{2}$ oz. more than an English $\frac{1}{2}$-inch of wide angle.

A centring nose-piece has been made with the view of placing

any objective central to the axis of rotation of the stage. It is, of course, much cheaper to centre an objective by means of a nose-piece to the axis of rotation of the stage than to centre the rotary stage to the objective. This, like all other adapters, is an additional weight: but here there is very little to be gained by it, for if the rotary stage is well made any objective will be sufficiently centred for all practical purposes. Mr. Nelson, as we have seen (fig. 147), pointed out, at a time when the sub-stage was costly, that such a nose-piece turned upside down, with a turn-out rotating ring for stops &c. fitted below, made a very efficient rectangular centring sub-stage at a small cost. Sub-stages are now quite common and cheap, and centring nose-pieces are seldom used for any purpose.

Next to the rotating probably the *changing nose-piece* is the most important. We do not know from whom, and when, the idea of an arrangement by which an objective could be rapidly attached or detached originated; but certain it is that the idea is admirable, and one which is scarcely yet as fully appreciated as it should be. It will be quite impossible to go through a tithe of the appliances which have been invented for this purpose; it will be sufficient to lay down some principles and mention a few in which those principles are fulfilled.

The first principle is that the objective or nose-piece, adapter, or whatever else is used should 'face up.' This means that a flange turned true in the lathe should 'face up' to the flat side of the nose-piece, which has also been turned true. This 'facing up' should be made tight by a screw, inclined plane, or wedge, &c. Unless this is done you have no guarantee that the axis of the objective is parallel to that of the body. Therefore all those appliances which merely grip the objective, or an adapter screwed on to the objective, are simply of no value. Secondly, the appliance, whatever it is, should be light.



Fig. 193.— Zeiss's sliding-objective changer, with objective in position.

Nachet's changing nose-piece which fulfils none of these conditions cannot be called good. The nose-piece is large and heavy, even for the small objective it is intended to take, the screws of which are $\frac{7}{16}$ only in diameter against the $\frac{13}{16}$ of that of the Society. The objectives are held by a spring clip on a small flange. Of course, screw-collar adjustment with such a device would be simply impossible. Zeiss's sliding-objective changer is most elaborate and efficient, although, as we think, much heavier than it need be. It consists of a grooved slide which screws on to the nose-piece. On each objective is screwed an adapter to slide

into the grooved nose-piece. These adapters, which are wedge-shaped and 'face up,' have two novel features, the first being that they are each fitted with rectangular centring adjustments, which permit the objectives to be centred to one another; and the second is, that they have adapters to equalise the length of the objectives, so when a change of objectives is made little change of focal adjustment is required. Figs. 193, 194 show the nature of this arrangement. In Nelson's changing nose-piece a small ring with three studs is screwed on to the objective; a nose-piece is screwed on the microscope having three slots and three inclined planes. Therefore, by placing the studs into the slots and giving the objective a quarter of a turn, the studs run up the inclined planes, thus causing the flanges to face up tightly.

FIG. 194.—The objective detached from the body-slide.

Mr. Nelson has pointed out a far better and simpler method which dispenses with all extra apparatus.

Three portions of the thread in the nose-piece of the microscope itself are cut away, and also three portions on the screw of the objective. Those portions where the thread is left on the objective pass through those spaces in the nose-piece where it has been cut away. The screw engages just as if the whole screw were there and the objective faces up in the usual manner. This plan in no way injures either the microscope or the objectives for use in the ordinary way; thus uncut objectives will screw into the nose-piece, and cut objectives will screw into an uncut nose-piece. This plan is similar to that employed in closing the breach of guns, and it was seeing one of them in 1882 which suggested to Mr. Nelson to adapt the same principle to the microscope. Subsequently it has been found that in 1869 Mr. James Vogan had proposed much the same plan, only cutting away two portions instead of three; it is curious that such an excellent idea was allowed to drop.

An *analysing* nose-piece is that which carries a Nicol's analysing prism for polariscope purposes. In some the prism is fixed in the nose-piece, whereas it ought to be capable of rotation. Lastly we have a *revolving* nose-piece for the purpose of testing objectives. Mr. Nelson, in a paper read before the Quekett Microscopical Club, February 1885, stated that he had observed that certain objectives performed better when the object was placed in a definite azimuth. With a view to eliminate any possible alteration which might arise from the revolution of the object with regard to the light, he had designed a revolving nose-piece which enabled the objective itself to be revolved true to the optic axis when any imperfection in its performance in a particular azimuth could be immediately noted. This plan had, however, been previously in use by Professor Abbe for a similar purpose, but not, as we believe made public.

Finders.—A finder is a very important and valuable addition to a microscope. By its means the position of any particular object or part of an object in a mount can be noted so that it may be found again on any subsequent occasion. In working on a microscope without a finder it frequently happens that in the prosecution of special research, or in the examination of unknown objects, something is seen which it would be of the utmost value to recur to again; but the amount of time lost in transferring the object to a stand with a finder is so great that most experienced microscopists do all their search and general work on their best instruments with finders.

The usefulness of the finder has caused a large number to be devised, but, as in all cases, we only consider those which we believe embody the best practical principles.

The first, and by far the best, is the graduation of the stage plates of a mechanical stage by dividing an inch into 100 parts, both on the vertical and horizontal plates. The vertical stage-plate will then indicate the latitude, and the horizontal plate the longitude, of the object, the slip being always pressed close home against a prepared stop. For many years Messrs. Powell and Lealand have supplied their No. 1 stand with this kind of finder: and its permanent position, and ease in use, not only give greater facility in special researches, but in reality attach a new value to every slide in the cabinet. Such a worker at critical images as Mr. Nelson has written of must write 'logged' on the labels of his slides. A still better plan is to 'log' in books in which the slides are numbered. The result is that the labour of days and weeks can be in a moment recalled for demonstration; and so accurate is this method that an object as small as a *Bacterium termo* or a specified minute diatom in a thickly scattered mounting may be at once, and as often as we please, replaced in the field with even high powers.

These finders of course are only suitable for the microscope on which the 'log' was taken. It is beneficial, and even needful at times, to interchange specimens or refer an object to an expert at a distance. In that case a minute dot may be placed on the cover, or a single selected diatom or other object may be fixed upon and its latitude and longitude as read on the microscope of the sender marked on the slide. If the receiver then places this on his microscope and centres it, the differences in latitude and longitude may be noted, and will give the constants for the correction, which must be added to or subtracted from the figures given by the sender.

Mr. Nelson has made some very practical suggestions touching the improvement of finders. He suggests, what we heartily accord with—

1. That the stage-stop shall be always on the left hand of the stage.

2. That the zero of the horizontal graduation shall be on the left hand of the scale.

3. That the zero of the vertical graduation shall be on the top of the scale.

4. That when the finder is placed to 0, 0, a spot marked on the

bottom edge of a 3 × 1 inch brass template two inches from the stop shall be in the optic axis of the instrument. In other words, the latitude and longitude of the centre of a 3 × 1 inch glass slip shall be 50, 50.

5. That the divisions shall be in $\frac{1}{100}$th of an inch, and the scales one inch long.

If these very simple suggestions were adopted generally, an object found on one microscope could be easily found on any other. This, like the 'society's screw' for object-glasses and a universal sub-stage fitting, deserves, in the interests of international microscopy, the consideration of opticians.

In practical 'logging' the use of a hand lens will enable the observer to read by estimation very accurately; half a division can be very approximately judged of, and this is as close as will be required with the highest powers. We have found, for very delicate work, that we could log with advantage between the divisions thus: say 'long. 41'; but if slightly over but not an estimated half, '41 +'; if half, '41½'; if more than this but less than 42, it is logged '– 42' For logging purposes the lens we recommend is one of Zeiss' 'loups,' magnifying six diameters. They are admirable instruments, and are furnished with a handle, which may be used or not at the will of the worker.

The other finder we desire to consider is called after its inventor, and is known as 'Maltwood's finder.'[1]

It consists of a micro-photograph, one square inch in size, divided into 2500 little squares, so that each is $\frac{1}{50}$th inch square. Each square contains two numbers, one indicating the latitude and one the longitude. To log any object the slide containing the object must be removed and the slip holding the micro-photograph substituted for it, then the figure in the square which most nearly agrees with the centre of the field is noted. Of course, both the object and the Maltwood finder must be carefully made to abut against the stop.

There are two drawbacks to this finder.

1. The divisions are not fine enough, so that it is only suitable for low powers.

2. The removal of the slide, and its substitution by the Maltwood finder, renders it extremely unhandy when using an immersion objective, all the more so if the condenser happens to be immersed as well.

If the Maltwood finders are made alike, they are then, of course, interchangeable.

Dr. J. Pantocsek describes a finder,[2] which appears to have some advantage not possessed by that of Maltwood, which he considers in comparison 'time wasting' and 'minute.'

Two lines are drawn on the stage at right angles, intersecting in the optic axis; these are marked 0. Lines a millimetre apart are drawn parallel to those on the upper half and the left half of the finder, thus giving horizontal lines in the right upper quadrant, vertical lines in the left lower quadrant, and squares in the left upper one. Each ten of the lines is marked as shown in fig. 195.

[1] *Trans. of the Micro. Soc.* new series, vol. vi. 1858, p. 59.
[2] *Zeitschr. f. Wiss. Mikr.* vol. v. 1888, pp. 39–42; *J. R. M. S.* 1889, p. 121.

When the object is in the field mm is taken of the two lines on the left and upper sides of the slide respectively.

Diaphragms.—There are three kinds of diaphragms in use, the commonest form is that of a rotating disc of several aper-



Fig. [illegible]—[illegible]

tures graduated as to size. Secondly, a series of separate small discs of metal, with a single central aperture, which fit into a suitable carrier. Thirdly, there is what is known as the Iris diaphragm, which, in its new form, made with sixteen segments, has been brought to great perfection by Mr. Baker, and is also beautifully made by Zeiss, as shown in fig. 196. In whatever form the diaphragm may be which is for use with the mirror, it is important that it should not be placed too near the object, as then it does not lie in the path of the cone, but at its apex, and will not cut the cone unless it be exceedingly small. A very small diaphragm aperture is objectionable, as it is liable to introduce diffractional effects. Therefore it is better to use a larger aperture further away from the stage than a pin-hole near the stage. When a diaphragm is used in connection with a condenser it should be placed just behind the back lens, and never above the front lens. Calotte diaphragms placed close under the stage, and

Fig. 196.—Zeiss's Iris Diaphragm.

which have been much in use lately both here and on the Continent, are a mistake.[1]

A very good way of cutting down a cone from a mirror is to have the diaphragm fitted so that it can be made to advance or recede from the object. The advantage thus gained is that one aperture is made to do the duty of several. It also permits of careful adjustment.

The iris diaphragms have now been brought to such perfection, and are so comparatively inexpensive, that they have superseded for general work and ordinary purposes all others; but whatever diaphragm is used it should *work easily*. Iris diaphragms work sometimes so stiffly that the microscope may be moved before the diaphragm. So, too, with the diaphragm wheels, some require a pair of pliers before they can be rotated. This is easily accounted for when we examine the way in which they are fixed. The usual method is to screw the wheel to the under side of the metal stage. Now, if there are neither washers nor a shoulder to the screw, it is more than probable that when the diaphragm is rotated it will screw up and jamb. The purchaser may easily observe a matter of this kind.

Condensers for Sub-stage Illumination.[2]—This condenser is an absolutely indispensable part of a complete microscope. Its value cannot be over-rated, for the ability of the best lenses to do their best work, even in the most skilful hands, is determined by it. Perfection in the corrections of object-glasses is indispensable; but those who suppose and affirm that this is all that we need—that the objective is the microscope—cannot understand the nature of modern critical work. The importance of it could not have been realised in the sense in which we know it in the earlier dates of the history of the instrument; but at as early a period as 1691 we pointed out (p. 135) that a drawing of Bonanni's horizontal microscope showed the presence of a compound condenser. It is, in fact, of some interest to note how our modern condensers gradually arose.

The microscope that amongst the older forms (1694) appears most efficient and suited for the examination of objects by transmitted light was that of Hartsoeker, p. 135, fig. 102. It will be remembered that it not only was furnished with a condenser, but with a focussing arrangement to be used with it, which was not in any way affected by a change of focus in the object. This is a feature which, although not then important, is of the utmost importance now.

In the correction of dispersion in the lenses employed in the dioptric form of microscope so much difficulty was experienced that several efforts were made to produce catoptric forms of the instrument; the most successful of these was that of Dr. Smith, of Cambridge, in 1838; but this and all other forms of reflecting microscope had but a brief existence and passed for ever away. To the improvement of simple lenses much of the earlier progress of microscopic investigation is attributable; and that known as 'Wollaston's doublet,' devised in 1829, was a decided improvement in all respects. It consisted of two plano-convex lenses; but this was again improved

[1] Quekett, *Micro. Journ.* vol. iv. p. 121 *et seq.*

[2] The word 'condenser' throughout this work is applied to optical appliances for the sub-stage; what is known as the 'bull's-eye' is not called a 'condenser.'

by Pritchard, who altered the lens distances and placed a diaphragm between the lenses. When the object was illuminated with a condenser this formed what was the best dioptric microscope of pre-achromatic times.

Good results, within certain limits, may be obtained by means of the best Pritchard doublets. With a grain such the surface of a strong Podura scale may be seen as a surface symmetrically scored or engraved, but the Editor has never himself been able to reveal the 'exclamation' marks: and as this is the experience of other diffraction experts, it may be taken that no resolution of these was accomplished in pre-achromatic days; these lenses, in fact, overlapped the discovery of achromatism.

But the practical results of the use of achromatic lenses soon led the most experienced men in its theory and practice to perceive that if it were good for the lenses which formed the image it was also good for the condenser. Thus Sir David Brewster in 1831 advocated an achromatic condenser in these remarkable words, viz.: 'I have no hesitation in saying that the apparatus for illumination *requires to be as perfect as the apparatus for vision*, and on this account I would recommend that the *illuminating lens should be perfectly free from chromatic and spherical aberration*, and that the greatest care be taken to exclude all extraneous light both from the object and from the eye of the observer.' This is a judgment which every advance in the construction of the optical part of the instrument as used by the most accomplished and experienced experts has fully confirmed.

We have no knowledge, from an inspection of the parts of apparatus itself, of the construction of the compound sub-stage condenser of Bonanni (p. 135): it does not appear to have attracted much attention, and of course it was quite impossible to secure a critical image by its means. It was focussed on the *object* merely to obtain as bright an illumination as possible in order that the object might be seen at all.

In the condenser used by Smith in his catoptric microscope (p. 144) we have the earliest (1738) known condenser, by means of which a distinction between a 'critical' image—that is, an image in which a sharp, clear, bright definition is given throughout, free from all 'rottenness' of outline or detail—and an 'uncritical' or imperfect image could be made. It was not, apparently, at the time it was first used considered to be so important as we now know it to be; and it is probable that the mode of focussing the light upon the object by its means was to direct the instrument to the sky with one hand and to use the biconvex condenser with the other. In 1837 Sir D. Brewster writes of it with appreciation, saying 'that 'it performs wonderfully well, though both the specula have their polish considerably injured. It shows the lines on some of the test objects with very considerable sharpness.'

No advance was made on this condenser for nearly a *century*. In 1829 Wollaston recommends the focussing of the *image of the diaphragm* by means of a plano-convex lens of $\frac{1}{4}$ of an inch focus upon the object, and Goring in 1832 says concerning it: 'There is no

modification of daylight illumination superior to that invented by Dr. Wollaston.' But Sir D. Brewster objected to this, contending that the *source of light* itself should be focussed upon the object. He preferred a Herscheleian doublet placed in the optic axis of the microscope. But whilst there is a very clear difference between these authorities we can now see that both were right.

Goring, who was also a leader in the microscopy of his day, used diffused daylight, and as the lens he employed was a plano-convex of $\frac{3}{4}$ of an inch focus, the method of focussing the diaphragm was as good as any other, because the diaphragm was placed at a distance from the lens of at least five times its focus, so that the difference between diaphragm focus, and 'white cloud' focus, or the focussing of the image of a white cloud upon the object, was not very great. But Brewster was writing of a candle-flame when he insisted on the bringing of the condenser to a focus on the object, and in this he was, beyond all cavil, right.

In 1839 Andrew Ross gave some rules for the illumination of objects in the 'Penny Cyclopædia.' These were—

1. That the illuminating cone should equal the aperture of the objective, and no more.

2. With daylight, a white cloud being in focus, the object was to be placed nearly at the apex of the cone. The object was seen better sometimes above, and sometimes below the apex of the cone.

3. With lamplight a bull's-eye is to be used to parallelise the rays, so that they may be similar to those coming from a white cloud.

Of the old forms of condenser, that devised by Mr. Gillett was, there can be no doubt, the best. It was achromatic, and had an aperture of 80°. Fig. 197 illustrates it. It was fitted with a rotating ring of diaphragms placed close behind the lens combination. This was formed, as the figure shows, by a conical ring with apertures and stops, and on account of the large number of apertures and stops it would admit, which, provided they are carefully 'centred,' are of great value in practical work, as well as from the fact that they are so placed as not to interfere with the stage, makes this arrangement of diaphragms and stops an excellent one, and it is not clear why it has fallen into disuse.

Fig. 197.—Gillett's condenser, from 'Hogg on the Microscope.'

It had been the custom to recommend the use of this instrument racked *either within or without its focus*. Carpenter employed it without and Quekett within, and one or other of these methods was general. But in the use of good achromatic condensers with high-

power work it soon became manifest to practical workers that it is only when, as Sir David Brewster pointed out, *the source of light is focussed by the condenser on* the object that a really critical image was to be obtained. And Mr. Nelson readily demonstrated this fact even with the condenser Gillett had devised.

The next condenser of any moment is a most valuable one, and constitutes one of the great modern improvements of the microscope. It was an achromatic condenser of 170° devised and manufactured by Messrs. Powell and Lealand. We have used this instrument for twenty-five years on every variety of subject, and we do not hesitate to affirm that for general and ordinary critical work it is still unsurpassed. Fig. 198 illustrates this apparatus. The optical combination is a $\frac{1}{3}$th of an inch power, and it is therefore more suitable for objectives from a $\frac{1}{4}$th of an inch and upwards; but by removing the front lens it may be used with objectives as low as one inch.

FIG. 198.—Powell and Lealand's condenser.

Having given to this condenser so high a place amongst even those of our immediate times, it may be well to specify what the requirements are which a condenser employed in critical work with high powers *should* meet. It is needful that we should be able (1) to obtain at will the largest 'solid' cone of light devoid of spherical aberration.[1] Directly spherical aberration makes itself apparent the condenser fails; that is, when, on account of under-correction, the central rays are brought to a longer focus than the marginal rays, or when, because of over-correction, the marginal rays have a longer focus than the central.

But (2) it is also an absolute essential that if a condenser is to be of practical service it must have a working distance sufficiently large to enable it to be focussed through ordinary slips. It would be an advantage if all objects mounted for critical high-power work were mounted on slips of a fixed gauge, say ·06 inch, which would be 'medium,' ·05 inch being accounted 'thin,' and ·07 inch 'thick.'

It is plain, however, that to combine a large aperture with a great working distance the skill of the optician is fully taxed, for this can only be accomplished (*a*) by keeping the diameter of the lenses just large enough to transmit rays of the required angle and no more; (*b*) by working the convex lenses to their edge; (*c*) by making the flint lenses as thin as possible.

Now it is due to the eminent Firm whose condenser we have been considering with such appreciation, to say that the condenser referred to (*d*) transmits the largest 'solid' cone free from spherical aberration; (*e*) that it has the greatest working distance; (*f*) that its chromatic aberrations are perfectly balanced. In the pre-

[1] This is one of the many expressions which are inevitable to the practical use of apparatus; it is simply convenient, and means a *full* cone of light, a cone with none of its rays stopped out.

session of these three essential qualities it has stood unrivalled for upwards of thirty years.

The removal of the front lens of this condenser, which may be readily unscrewed, reduces it in power and angle, and therefore makes it suitable for objectives of lower power. This, however, is rather an adaptation involving compromise than an ideal condenser for low powers. When the highest class of work has to be done *it is needful to have condensers suited to the power of the objective used.*

A low-power condenser of much merit is made by Swift and Son; it begins, in its relation to low powers, where the condenser of Powell and Lealand leaves off. It consists of two doublets with a single front, and is much lower in both power and aperture than that of the latter makers; but by sliding off the front cap into which the front lens is burnished both power and aperture may be further reduced. It is achromatic, and is a practical and useful instrument capable of adaptation to any microscope. Fig. 199 is a general illustration of this appliance.



FIG. 199.—Swift's condenser.

A condenser having considerable value, and specially adapted to lenses of low power, and up to those of $\frac{1}{4}$ inch focus, has just been constructed and placed in our hands by Messrs. Powell and Lealand. It was made in response to the earnest suggestion of several leading microscopists, and in many respects fully answers its purpose. It is achromatic, has a numerical aperture of ·83, with an aplanatic aperture of ·5, and for dark-ground illumination is possessed of the highest qualities. Its power is a $\frac{2}{3}$ inch, and will prove a most useful adjunct to the photo-micrographer, since it will enable him to get a large image of the source of light on the object; but its aberrations are not so perfectly balanced as we could desire.

It is possessed of a new feature so far as the condenser of these makers is concerned, having permanently placed beneath the optical arrangement an *iris diaphragm*, and in addition the condenser mount is supplied with a series of diaphragms and stops which are placed in a turn-out-arm carrier; this provides the worker with facility as well as accuracy of method, since both of these can be used under the same adjustment. The aperture of the cone transmitted by the condenser with each diaphragm is engraved upon that diaphragm, and with the stops for dark ground; the aperture of the objective with which the stop will yield a dark ground is also engraved on it. This embodies the recommendations we have made below.

We give an illustration which is self-explanatory of this apparatus, fig. 200.

Before the introduction of the homogeneous system, and the production of such great apertures by Powell and Lealand as

a 1·5 in a $\frac{1}{6}$th, a $\frac{1}{12}$th, and a $\frac{1}{20}$th of an inch focus, the cone transmitted by Powell's dry achromatic condenser was as large as could be utilised. But with apertures such as these, and the subsequent introduction of the apochromatic system of lenses, much larger cones were required. To meet this necessity Powell and Lealand, at the urgent suggestion of English experts, made first a chromatic condenser on the homogeneous system; but this was subsequently succeeded by an achromatic instrument of great value on the same system. This combination consists of a duplex front with two doublet backs; it is nearly of the same power as their dry achromatic condenser, but is of much greater aperture. It has been brought still more recently to a very high state of per-

FIG. 200.—Powell and Lealand's new low-power condenser.

FIG. 201.

FIG. 202.



Powell and Lealand's high-power achromatic condenser.

fection, having an aperture of 1·40. It will work through a mounting slip of ·07, and for aperture and working distance is, like its dry predecessor, quite unapproached.

We present a general view of this instrument in figs. 201 and 202, but it will be found that other stops than those illustrated will be required, some of these being of little or no value; while the stops made with rings may be made much less expensively of the same form, but without the outer rings, having merely three points or arms to rest upon the edge of the socket which receives them.

In its original form it had the great disadvantage that the focussing had to be wholly disarranged to change a diaphragm, but it occurred to the present Editor that this could be obviated by a sliding tube carrying one ring which received the diaphragms. Originally this was fixed at B, fig. 202, the socket for the diaphragms being turned out from that position as in B, fig. 201. By placing this on a sliding tube we can slide the diaphragm carrier down, quite within reach of eye and hand, as at A B, fig. 201, without in the least disturbing the optical combination ; and when a diaphragm has been removed and another replaced in B, fig. 201, is turned in, and the whole is slidden up into position by means of A, as shown in fig. 202.

As these sheets are passing through the press, Messrs. Powell and Lealand have placed in our hands an entirely new condenser, strictly apochromatic, employing a fluorite lens in the combination, and presenting features in the highest degree desirable. We find its N.A. to be 0·95, its focal length long enough for a thick slip, its aplanatic aperture ·9. It will be of great value in critical work.

It is essential for ideal illumination with transmitted light (1) that the illuminating axial cone should be approximately equal to the aperture of the objective used ; (2) that the object should be placed at the apex of this cone.

If an objective breaks down with this ideal illumination, which is very probable, we must be content to sacrifice the ideal ; or, as is also exceedingly probable, the object under examination lacks contrast, the ideal method must be modified. But if we have a suitable object, and a perfect objective, it is the strong conviction of some leading experts that, as we increase the cone in aperture, we increase the perfect rendering of the image, until the point is reached where the cone from the condenser is equal to the aperture of the objective, and, whatever be the object used, it is advisable not to exceed this. With the most perfect objectives of the present day, we find in practice that the best results are obtained when a cone of light is used, which, on the removal of the eye-piece, is found to occupy three-quarters of the area of the back lens of the objective.

No condenser is sufficiently free from spherical aberration to transmit a cone equal to its *own* aperture. Condensers are all more or less under-corrected, and consequently focus their central rays at a greater distance than their marginal rays. If we rack up the condenser so that the marginal rays are focussed on the object, the focus of the rays which pass through the centre will be beyond the object.

It is well known to those practised in microscopy that in the case of a narrow cone, from a well-stopped-down condenser—that is, a condenser used with diaphragms of relatively small diameter—the illumination is at its greatest intensity when the object is at the apex of the illuminating cone, and if the condenser is racked either up or down the intensity of the illumination is rapidly diminished. But in the case of a condenser with great aperture, if it be racked up the marginal rays will have their full intensity, while those which passed through the central portion of the condenser will have a diminished intensity.

The extent to which this will take place will be wholly dependent

on the amount of under-correction present in the condenser. In some condensers the under-correction is so serious, that to obtain a wide, or even a moderate cone we so enfeeble the central cone as to reduce it almost to mere annular illumination, which is not a desirable quality.

It will be seen then that the aperture of the cone of light transmitted by a condenser plays a very important part in giving critical quality to an image with different objectives. We should therefore, to use a condenser accurately, be able to determine the aperture of the cone we are using.

We may measure the total aperture of a condenser just as we do that of an objective, viz. by means of Abbe's apertometer.[1] But the *effective* aperture cannot be measured in that way; that is to say, the aperture of the largest aplanatic cone, or cone free from spherical aberration the condenser is capable of giving, cannot be so discovered.

To do this place the condenser in the sub-stage and an objective on the nose-piece, focus *both* upon an object. Let the edge of the lamp-flame be used, and so arrange the focus of both optical combinations that the edge of the clear image of the lamp-flame falls centrally upon the object. Now move the object just out of the field, remove the eye-piece and examine the back of the objective, and if the aperture of the aplanatic illuminating cone is *greater* than that of the objective it will show the back lens to be full of light (fig. 203). Therefore, if the aperture of the objective is ·5, we know that the aplanatic illuminating cone cannot be less than ·5. If now



FIG. 203.



FIG. 204.



FIG. 205.



FIG. 206.

we close the diaphragm so that the image of it just appears at the back of the objective, we are able to determine the aperture of the illuminating cone with that given opening in the diaphragm; thus in fig. 204 it is a trifle less than ·5 N.A.

In a similar manner the apertures of the other diaphragm openings can be determined.

Now let the diaphragm be opened to the full aperture, and an objective with a wider aperture, say ·95, be used. It will perhaps be found that before we are able to fill the back of the objective with light by racking up the condenser two black spots will be formed on either side the middle of the disc. When we reach the disc of light that is largest (fig. 205), any further racking up causes the appearance shown in fig. 206. *The last point before the appearance of the black spots indicates the largest aplanatic aperture of the condenser, and is the limit of the condenser for critical work.*[2]

There are many other condensers of more or less merit and use-

[1] Chapter V.

[2] 'The Back of the Objective and the Condenser,' E. M. Nelson, *Eng. Mech.* vol. xlviii. No. 1234.

fulness, but we must confine our consideration to those that will prove of greatest value for their several purposes.

A condenser known as the 'Webster' was first made in 1865, and is still a very useful one for low powers. It is the same as that made by Swift,[1] but without the middle combination. Its angle is less, and its range is not so extensive; but its chief commendation in possessing these qualities is that, having one combination less than Swift's, it is of necessity lower in price, and on that account will be welcome to some workers.

In its present form it reverses its primary construction. It is now made with a double front and a single back, instead of a single front and a double back.

An *achromatic condenser* which has been very largely used in England and America, and which has secured a great deal of commendation, is that of Professor Abbe. The optical productions of Abbe are too well known and too valuable, as a rule, to make it needful to be other than perfectly frank concerning so important a piece of apparatus as this; and there can be no doubt that the wide popularity of this instrument is due, not so much to intrinsic merit, as to the fact that it has been employed by those chiefly who, previously ignorant of the value of *any* condenser, have at once perceived the enhanced value of the results yielded by its means.

To those who have made the scientific use of the microscope a careful study in England it has been a persistent source of regret that it has been so long and pertinaciously taught that the 'correct' histological microscope must be of the Hartnack type, and that it should be used with narrow-angled dry lenses, perhaps a ¼th-inch focus, and no illumination but that afforded by a small concave mirror, the focal point of which is extremely doubtful or unknown, and in practice wholly disregarded. No doubt a student instructed on these lines would be astonished indeed when he exchanged such a practice for the illumination and improved image afforded by an Abbe condenser.

Usually such exchange of illuminating method presages an exchange of instrument, for the scientifically imperfect and wholly unsatisfactory 'tool' that is in the majority of cases put into the hands of the medical student will not lend itself even to an Abbe condenser.

The fact is that a large part of the admiration that has been expressed for this condenser has resulted, not from a comparison of its results *with those of other high-class achromatic condensers*, but of images obtained without any sub-stage optical arrangements at all, placed in contrast with the results obtained by using this condenser against the same objective when used without its aid. But that even these images are entirely inferior to the images obtained by the higher order of achromatic condensers we only require the practical testimony of Professor Abbe to prove; for *he has since produced an achromatic condenser of much merit*, to which we give consideration below.

In its most perfect form this *chromatic* condenser of Abbe's consists of three single lenses, the front being hemispherical, and the

[1] Page 252, fig. 199.

two lower lenses form a Herscheleian doublet. This combination is shown in fig. 207, and the general form of the instrument as applied to Zeiss's own microscopes is shown in fig. 208.

The power of this condenser is low, and its aperture is very large (1·36); hence beyond the fact that it is not achromatised it has enormous spherical aberration. The distance between the foci of the central portion and of a narrow annular zone whose internal diameter is $\frac{5}{8}$th-inch is $\frac{1}{10}$th-inch. Its aplanatic aperture is therefore only ·5. Now, whilst it is a gain of no inconsiderable character to have an achromatised condenser, and one which, with greater or less enthusiasm, all workers admit, yet the point

FIG. 207.—Optical arrangement of Abbe's chromatic condenser.



FIG. 208.—Abbe's chromatic condenser as applied to the Zeiss microscopes.

of vital importance is that it should be aplanatic; the best condenser is always that which will transmit the largest aplanatic cone. At the close of this section we furnish a table of the relative qualities of the condensers of the best construction now accessible to the microscopist, and a reference to this will show that Powell and

Lealand's dry achromatic (fig. 198) with the *top removed* is in this respect as efficient as this form of Abbe's.

This condenser can be used either dry or homogeneously; but of course with objectives of greater aperture than 1·0 the base of the slide should always be in oil-contact with the condenser.

It gives the principal modifications from direct to oblique illumination with transmitted light by changing and moving a set of diaphragms placed in a movable fitting and the diaphragm may be moved eccentrically to the optical axis of the condenser by moving the milled head. It gives dark-ground illumination with objectives of ·5 N.A.; for such illumination, in fact, it is, perhaps, the best illuminator extant, and shows objects on a dark ground with sparkling brilliancy, and may be used with polarised light.

A chromatic condenser, somewhat similar in construction to this, and of low price, is made by Messrs. Powell and Lealand, but it is of much higher power, so that the distance between the foci for the central and peripheral rays is not so great, and on this account it yields a somewhat larger aplanatic cone. This instrument with its diaphragms is shown in fig. 209. It is more convenient in form, and can be handled and adjusted with greater facility, than that of Abbe. The size of their respective back lenses is significant in this regard, that of Powell's being $\frac{9}{16}$ inch, and that of Abbe's being $1\frac{3}{16}$ inch.



Fig. 209.—Powell and Lealand's chromatic oil condenser.

Fig. 210.

The diaphragms (fig. 210, A) have a central aperture, for the purpose of centring, and the movement is made by means of an outer sliding tube, *b*, with a slot at the top in which the arm A fits, and another arm, B, is placed at the lower end so as to give ready command of the rotation. This plan allows of the use of one or two oblique pencils incident 90° apart in azimuth. The condenser thus mounted is only intended as an oblique illuminator. It forms one of the best of the very cheap condensers when it is mounted in a plain tube mount with a ledge to hold the diaphragms. D is the optical part of the condenser placed immediately above the diaphragms and in oil-immersion contact with the base of the slide. The circular diaphragm is fixed into the inner tube attached to the sub-stage tube, C, just below the position of the arm A; the other diaphragm is screwed to it by a screw in the eccentric hole, shown in each. It will be seen that when the diaphragms are placed together in this manner the movement of the arm will produce the changes in the light as above mentioned.

As we intimated above, Professor Abbe has now produced an *achromatic condenser*, ostensibly for use in high-power photographic work, but in fact of much more general utility. It consists of a single front with two double backs, and it projects a sharp and perfectly achromatic image of the source of light in the plane of the object. Its power is low, being ½-inch focus, and it has a total aperture of 1·0. Its great superiority over the chromatic form is that it transmits a much larger aplanatic cone than that; for whereas the former gave



FIG. 211.—Abbe's achromatic condenser.

only an aplanatic cone of ·5, this instrument yields a similar cone of ·65. Like its predecessor it is large and heavy: and, with great deference and respect to our Continental neighbours, we would suggest that this is a too general characteristic; the back lens in this case is more than an inch in diameter, while barely ¾ of an inch is utilised when it is transmitting its largest cone. The instrument is represented in fig. 211, but a very excellent modification in fitting it to English microscopes has been made by Mr. Charles Baker, the optician, which is shown in fig. 212, where it will be seen that the fitting for diaphragms is conveniently placed, and an iris diaphragm can be used with great ease below this. This 'turn-out' arm carries a disc of metal to receive the diaphragms, stops, &c. Over this is fitted a ring into which screw adapters, which will allow other condensers to be used on the one mechanism.

FIG. 212.—Baker's fitting for Abbe's achromatic condenser used in English microscopes.

The metal disc should have a central aperture as large as the largest back lens of any of the combinations to be used with the mount. It should be thick enough to receive two stops or diaphragms at a time. This power to alter a diaphragm or stop so as

to secure any required arrangement of apertures and stops without in the least disturbing any of the adjustments of the condenser is a practical gain of a very valuable kind.

Diaphragms should be marked with the numerical aperture they yield, and stops should be marked with the numerical aperture of the cone they cut out. Empirical numbers are misleading and valueless. This special marking need not involve two sets of diaphragms with two condenser combinations, one for high and the other for low powers; the different numerical apertures for each may be marked on either side of the diaphragm or stop. Memory cannot fail if we make the *lower* side of the diaphragm indicate the apertures for the lower-power condenser, and *vice versa*.

We may note that for dark-ground work stops should be placed close to the back lens of the condenser, and in the case of a diaphragm—which is less important—an inch of distance should not be exceeded.

The iris diaphragm is for general purposes more convenient than the usual circular plate, but it has the drawback of being incapable of setting to any exact size. A delicate point in an image, caught with a certain-sized diaphragm, is not regained with ease and certainty with the iris,[1] and may involve much patience and labour; but a well-made *large* plate of graduated diaphragms will wholly remove this difficulty. Moreover, for testing object-glasses it is supremely important that a metal diaphragm be used, so that the conditions of illumination may be readily and accurately reproduced.

Messrs. Beck provide a condenser with a movable top, carrying front lenses of different power central with the backs. Its character will be readily seen in the illustration given in fig. 213. This combines a high-, low-, or medium-immersion or dry condenser in one piece of apparatus. The first lens when brought over the back combination has a low angle, and is intended for use without fluid for histological subjects. The next is a full-aperture lens, with which, by revolving the diaphragm, the angle can be varied from 180° downwards. The third lens, with full aperture of diaphragm, has an angle of 110° in glass = 1·25 N.A., and is truncated, cutting out the central rays. The fourth lens has also an aperture of 1·25, and is similar to No. 3, but the periphery is painted over so as to allow pencils only at right angles to pass. Ingenious as this arrangement is, it is likely to interfere with the corrections; and as the aperture is not exceptionally great, it calls here for no special notice.

FIG. 213.—Beck's variable condenser.

It may be of service to those who are unable or indisposed to spend considerable sums upon condensers to state that an excellent

[1] It will be urged that apertures can be exactly reproduced with the iris in photographic lenses; why cannot they, therefore, in the case of the microscope? The answer is (1) that with wide-angled condensers a very slight difference in the aperture makes a very great difference in the angle; a similar difference would be

achromatic condenser can be made by placing a Zeiss 'aplanatische Lupen' on Steinheil's formula in the sub-stage.[1] These are made in two different powers, viz. 1 inch and 1½ inch, and we can fully testify to their being the most useful hand-lenses for ordinary work that can be employed. Great credit is due to Dr. Zeiss for bringing out such excellent achromatic lenses at so low a price, and so meeting a want long and generally felt. An achromatic loup of this kind is almost an indispensable accompaniment of a microscopic outfit, and if a tube to receive it be arranged in the sub-stage these lenses make really excellent condensers for low powers. It need not have a centring sub-stage, but only a central fitting. It is not of course qualified to supplant the condenser of larger and more perfect instruments, but it is capable of raising students' and other simple microscopes to a much higher level.

Without a condenser the microscope is either (by construction) not a scientific instrument, or it is an instrument unscientifically used. It becomes a mere 'magnifying glass.' It is the adaptation for and use of a condenser—though as simple as a hemispherical lens fitted into a stage plate—that raises it to a microscope.

We have already referred to the nature of the mechanical arrangements needful for the condenser in a general way (Chapter III. p. 169); we may add here that the simplest form of sub-stage being a tube fixed centrally in the optic axis of the microscope, the simplest form of condenser-mount will be a tube sliding into this. It must not screw, it must push, and there should be a little below the back lens a shoulder to hold the diaphragms, stops, glasses, &c. Centring gear is *not* necessary with students' and elementary microscopes. The slight displacements due to varying centres of different objectives will with such microscopes prove of no moment if the sub-stage is once for all carefully fixed centrally in the axis.

What we require to do is to centre the image of the lamp flame, as seen with a low-power lens through the condenser, so that it stands in the middle of the field. This can be done by moving the lamp or the mirror, and until this is satisfactory the best results cannot be obtained. To obviate the inconvenience of having to remove the combination in order to alter a diaphragm[2] or stop, in this simple mount an internal sliding tube may be used, something like that described in the latest form of the apochromatic condenser of Powell and Lealand. It will be a further advantage to have a separate cell to fit into the bottom of the sliding tube to receive coloured glasses; a spiral slot-focussing arrangement may be added with advantage to this kind of mount, acting like a pocket pencil. For students' and elementary microscopes—now so often and so unwisely without condensers—this is a most inexpensive and most convenient arrangement.

inappreciable in the case of a photographic lens. (2) It is in small apertures such as are seldom used in photographic lenses where the difficulty arises in the case of the microscope. (3) It is in the small apertures that the iris fails to respond to the movement of the lever.

[1] *Journ. Roy. Micro. Soc.* series ii. vol. iii. on Zeiss' loup. E. M. Nelson.

[2] In the technical language or usage of microscopists a diaphragm means a hole or aperture; thus a 'large diaphragm' means that the opening in the diaphragm plate, disc, or iris is large. A 'stop' is an opaque disc stopping out central rays.

An epitome of its principal points may be of service.

1. A sub-stage tube fixed centrally to the body of the microscope.

2. A spiral slotted tube to push into 1.

3. A tube carrying the optical combination of the condenser sliding into 2, with a pin moving in the spiral slot.

4. A long tube carrying the diaphragm and slots sliding into 3.

5. A cell carrying coloured glasses sliding into the bottom of 4.

Condensers require special mounting for use with the polariscope. Then at least two 'turn-out' rotating rings are required to hold selenites. Swift makes an ingenious *multum in parvo* mount for employing, amongst other things, the condenser with the polariscope, to which we call attention in describing the polariscope. But we know of no plan equal to that found in the best stand of Powell and Lealand. The sub-stage has a double ring, one placed concentrically within the other. The inner one revolves by a milled head and receives the usual sub-stage apparatus. The outer one receives a mount of three selenites which revolve, and are placed on 'turn-out' arms. On the upper part of this mount of selenites is a screw, which receives the optical combination of their dry achromatic condenser. When this is screwed in its place we have a condenser of the first order, with a mount of three plates of selenites taking the place of a mount of diaphragms &c. Now from the *under* part of the sub-stage into the inner and revolving ring is fitted the polariser, and this leaves little to be desired in practice.

We would advise the microscopist to avoid condenser mounts which carry their own centring movements apart from the sub-stage. It is with regret that we find that this plan has been adopted in Abbe's new achromatic condenser. It is manifestly better to fit the rectangular movements to the sub-stage, and then they become available for all the apparatus employed with the sub-stage. A plan which requires that each piece of sub-stage apparatus which needs centring should be provided with separate fittings for this purpose can have nothing to recommend it.

We give on the adjoining page a list presenting the most important features of the most important condensers, which we believe will be of service to the student and worker.

The aplanatic aperture given in the table means the N.A. of the greatest solid cone a condenser is capable of transmitting, the source of light being the edge of the flame placed in the axis.

The cone transmitted by any condenser is assumed, for practical purposes, to be a solid one, so long as the image seen at the back of the object-glass when the eye-piece is removed (the condenser and flame being centred to the optic axis of the objective, and the source of light focussed by the condenser on the object) presents an unbroken disc of light.

The moment, however, the disc breaks, that is, black spots appear in it, or its periphery breaks away from its centre, then, as we have shown above, spherical aberration comes into play, and the limit of aperture for which that condenser is aplanatic has been exceeded.

The limit given in the table is for the edge of the flame as a source of light. When, however, a single point of light in the axis is the source, the condenser will be much more sensitive, and a lower

value for the aplanatic aperture than that given in the table will be obtained. But as a single point of light is seldom, if ever, practically used in microscopy, it was deemed better to place in the table a practical rather than a theoretical and probably truer result.

It has been stated that the best dark grounds are obtained when a stop is used which is of just a sufficient size to give a suitable dark field and no more.

When such a stop has been chosen, and excellent results are obtained with, say, balsam-mounted objects, and then in the place of this living animalcules in water be examined, it will probably be found that a dark field can no longer be obtained.

For animalcules in water and 'pond life' generally a stop larger than that employed for ordinary objects will be necessary.

Condenser	Total aperture N.A.	Aplanatic aperture N.A.	Power
1. Powell and Lealand's dry achromatic (1857)	·99	·8	⅛
2. „ „ top lens removed . .	—	·5	¼
3. „ „ bottom lens only . .	—	·24	⅜
4. Swift's achromatic	·92	·5	¼
5. „ „ top lens removed . .	—	·22	⅛
6. Abbe's chromatic (3 lenses) (1873) . .	1·36	·5	¼
7. „ „ top lens removed . .	—	·3	⅜
8. Powell and Lealand's chromatic (Abbe's formula)	1·3	·7	⅛
9. Powell and Lealand's oil achromatic (1886) .	1·4	1·1	⅛
10. „ „ used dry	1·0	·8	⅛
11. „ „ top lens removed . .	—	·4	¼
12. Abbe's achromatic (1888)	·98	·65	⅛
13. „ „ top lens removed . .	—	·28	⅛
14. Powell and Lealand's low-power achromatic (1889).	·83	·5	⅜
15. Powell and Lealand's Apochromatic (1891) .	·95	·9	⅜
16. Zeiss's 'aplanatische Lupen' large field (Steinheil formula)	—	·32	1

Other Illuminators.—In the course of the history of the microscope, a large number of special pieces of apparatus have been devised for the purpose of accomplishing some real or supposed end in illumination. Many of these have proved wholly impracticable and had a mere ephemeral existence; many more never accomplished the end for which they were supposed to be constructed; and a still larger number have been superseded by high-class condensers.

The great majority of these illuminators were devised for the production of oblique light. In the sense in which it was employed a few years ago, it is rendered needless by condensers of great aperture. All the obliquity at present needed can be obtained with Powell and Lealand's oil-achromatic condenser. But not to ignore those who may still desire it in its older form, we may say that it is found in its very best form in Stephenson's **catadioptric illuminator**. By its means a greater obliquity can be obtained than can be utilised even by our modern objectives. The general form of this instrument is seen in fig. 214, but the principle of its construction and operation will be understood by the diagram given in fig. 215. The illuminator

consists of a segment, C, D, E (cut from the edge inwards), of a plano-convex lens of crown glass of 1-inch radius of curvature, the lens having a diameter of 1·2 inch, and therefore a thickness of 0·2 inch, the upper surface being black. The segment has a length of 0·56 inch and a depth of 0·5 inch, and is therefore almost a square. The curved surface is silvered as in the catoptric lens described in 1879. It is cemented to a rectangular piece of flint glass, A, B, C, E, the refractive index of which is 1·652. The thickness of the flint being 0·34 inch makes the total thickness, when the two are cemented together, rather more than half an inch.

The object of the flint glass is twofold. In the first place, it disposes of three-fourths of the spherical aberration of a concave mirror of these dimensions, and enables one to use light which is practically parallel; and, in the second place, it has the very obvious one of securing greater aperture, which is the primary consideration.

FIG. 214.—Stephenson's catadioptric illuminator.



FIG. 215.

As fig. 215 shows, rays which enter the flint glass horizontally are reflected at the silvered surface of the crown-glass segment, and apertures are thus obtained ranging from 0·77 to 1·644, N.A. in flint and 1·512 N.A. in crown.

To obtain the smaller apertures, the plane surface of the under part of the flint is utilised by cementing to it a segment, F (rather more than half), of a plano-convex lens of radius 0·25 inch, with a focus in crown 0·04 inch above the upper surface of the flint, and, therefore, at the upper surface of a slide having a thickness of 0·04 inch. In order that the rays may be received from the mirror beneath (and not horizontally) a small right-angle reflecting prism, G, is placed with one of its sides opposite to and parallel with the receiving side of the flint-glass.

The aperture of the illuminator is only limited by the refractive

index of the flint-glass used. If it is desired to have a larger aperture than 1·644 N.A., it can be obtained by using a flint-glass of higher refractive index than 1·652. The aperture is always within half per cent. of the refractive index of the glass (on a slide of the same material 0·03 inch thick), so that if glass were used of the refractive index 1·721 the aperture of the illuminator would be 1·712 N.A., and so on to any extent with increasing densities. But when we use glass beyond about 1·65 we get into difficulties, as very dense glass is always more or less coloured, which, by quenching the more refrangible rays of the spectrum, has a tendency to diminish the effective aperture. It is, moreover, difficult to work, and involves the use of some fluid at least as refractive as itself. With flint of 1·65 we have monobromide of naphthaline to connect the lens and the slide, and the glass is practically colourless and easy to work; above all, we have an aperture which exceeds by 8 per cent. a balsam angle of 180°. To connect the ordinary crown-glass with the illuminator, the homogeneous medium (oil or otherwise) used with the objective can always be employed, but with flint-glass slides a more refractive fluid, such as oil of cassia or monobromide of naphthaline, is necessary.

The oil of cassia if pure will suffice for an aperture of, say, 1·62 N.A., and, in the opinion of most people, it has a less unpleasant smell; but for the full aperture of 1·644 this is insufficient, and monobromide, or some equally refractive medium, must be employed. Such solutions of biniodide of mercury, although inodorous, are objectionable for this purpose, from their chemical action, and for other reasons. The light obtained by this ingenious instrument is free from colour, since it is obtained by reflexion, but in actual use we find its weakness to lie in the fact that its light lacks *intensity*.

Of all the older oblique illuminators *Wenham's reflex illuminator* was probably the best in its day, although not easy to manage, and its results can now, of course, be surpassed by the best condenser. It is composed of a glass cylinder (fig. 216, *a*) half an inch long, and four-tenths of an inch in diameter; one side of which, starting from the bottom edge, is worked to a polished face at an angle of 64° with the base. The top of the cylinder is polished flat, whilst its lower surface is convex, being polished to a radius of $\frac{4}{10}$ of an inch; close beneath this last is set a plano-convex lens of $1\frac{1}{4}$-inch focus; and the combination is set eccentrically in a fitting, *i i*, adapted to be received into the sub-stage. The parallel rays, *fff*, reflected up into it from the mirror, are made to converge, by the convex surfaces at the base of the cylinder, at such an angle that if their course were continued through glass they would meet at the point *h*, above the glass slide *c*; but by impinging on the inclined polished surface, they are reflected to the flat segmental top, from which again they would be reflected obliquely downwards so as to meet in the point *h*, but for its being brought into 'immersion-contact' with the under side of the slide. Passing upwards through the slide, they meet in a point, *g*, a little above its upper surface, in the optic axis of the microscope, to which point the object must be brought; and by giving rotation either to the object or to the illuminator it may be illuminated from every azimuth. For convenience of centring, a

black half-cylinder, *c*, is so fixed by the side of the cylinder that if a dot upon its upper surface be brought into the centre of the field of view of a low-power objective, its focus, *g*, will lie in the optic axis. Some skill and practice are required to use this apparatus to advantage, but it will amply repay the trouble of mastering its difficulties. It is best suited to thin, flat objects; with those that are thick and irregular distortion is unavoidable. Although specially designed as a 'black-ground' illuminator, it may also be made useful in the resolution of difficult test-objects by *transmitted* light, the illuminator being lowered until a coloured spectrum appears in the field, the rays of which bring out their markings with remarkable distinctness. For use with either of these arrangements for 'black-ground' illumination, it is better that the objects should be mounted 'dry,' especially when they are to be viewed under 'immersion' objectives, balsam-mounted objects being thus seen better with dry-front objectives.



FIG. 216.—Wenham's reflex illuminator.

This was followed by 'disc' and 'button' illuminators. Mr. Wenham devised the simple illuminator shown in fig. 217. This consists of a semicircular *disc* of glass (somewhat resembling the half of a button), of half an inch in diameter, the sides of which are flattened, while the circular edge is rounded and well polished to a transverse radius of $\frac{1}{10}$th of an inch. This concentrates the light thrown upon any part of its circumference on to an object mounted on a slide of the usual thickness with whose under side it is brought into immersion-contact by the intervention of either water, glycerine, or a more refractive oil. As it should be so fitted to the microscope as to illuminate the object from any azimuth, it should have its flat sides grasped in a clip, which may either be mounted on the sub-stage or attached to the under side of the stage, in either case having its diametric section brought up to the under surface of the object-slide. By giving rotation to the object, the illuminator remaining fixed, the illuminating beam may be made to cross the



FIG. 217.—Wenham's disc illuminator.

former in any direction that is fitted to bring out its markings; then followed small hemispherical lenses of various foci attached by oil or other fluid to the base of the slide, and caused to receive oblique rays from the mirror, or a low-power objective, arranged by 'swinging' sub-stage to give various angles upon this lens. The difficulty with all these was (1) that a lens of different focus was needed for different powers; which, however, was reduced to its minimum by the use of, say, three lenses of different foci, greater than hemispheres, and so mounted on the rack that takes the sub-stage as to control or alter the position of the focal point by racking up or down; and (2) it is not always possible to get sufficient intensity of light by their means. It was the arrival of Abbe's chromatic condenser that put an end, for all practical purposes, to such devices. When it was employed with oil great obliquity with far greater intensity was the immediate result, and this, as we have seen, was surpassed by Powell's. This particular quality of oblique illumination was still further advanced by *Powell's 'truncated' form of their latest condenser*, which constitutes one of the most oblique illuminators extant; and that too with abundance of intense light. It is, of course, very chromatic. But we can obtain all desirable obliquity with all needful intensity with the Powell and Lealand achromatic oil-condenser with a slot, and that quite without colour. Hence it must be looked upon as the best oblique illuminator at present made. We have written enough to make the grounds of our strongly expressed judgment clear from a practical point of view, that, for the purpose of obtaining critical images, and getting the best results from object-glasses, 'swinging' sub-stages and concentric microscopes are needless, and may be mischievous elaborations.[1]

To give completeness to this part of our subject it is needful to refer to the SPOT-LENS and the PARABOLOID, although they have practically lost their importance to the microscopist.

A spot lens is a condenser with a permanent axial stop fixed in it to cut off the central rays for the purpose of obtaining a dark ground upon which the illuminated object lies. Obviously it is not a commendable accessory; it is a condenser, but having a *fixed* stop it can only be used for this mode of illumination; and, in this form, it can only be used critically with objectives of a certain definite aperture, because, in order to obtain a good dark-ground illumination the stop ought to be suited to the aperture of the objective employed. In other words, a spot lens only does in a limited and imperfect way for certain object-glasses what a good condenser with proper stops will do for all with which the spot lens can be employed. The fact is that the best recent condensers render needless much costly sub-stage apparatus, and, therefore, the younger microscopists may well afford a fine condenser at once.

The paraboloid, or **parabolic illuminator**, as devised by Mr. Wenham, and subsequently improved by Mr. Shadbolt, ingenious and beautiful instrument as it is, comes under the same category. It consists of a paraboloid of glass that reflects to its focus the rays which fall upon its internal surface. A diagrammatic section of

[1] Chapter III. p. 169.

this instrument, showing the course of the rays through it, is given in fig. 218, the shaded portion representing the paraboloid.[1] The parallel rays $r\ r'\ r''$ (fig. 219), entering its lower surface perpendicularly, pass on until they meet its parabolic surface, on which they fall at such an angle as to be totally reflected by it, and are all directed towards its focus, F. The top of the paraboloid being ground out into a spherical curve of which F is the centre, the rays in emerging from it undergo no refraction, since each falls perpendicularly upon the part of the surface through which it passes. A stop placed at S prevents any of the rays reflected upwards by the mirror from passing to the object, which, being placed at F, is illuminated by the rays reflected into it from all sides of the paraboloid. Those rays which pass through it diverge again at various angles; and if

FIG. 218.—Parabolic illuminator.



FIG. 219.

the least of these, G F H, be greater than the angle of aperture of the object-glass, none of them can enter it. The stop S is attached to a stem of wire, which passes vertically through the paraboloid and terminates in a knob beneath, as shown in fig. 218; and by means of this it may be pushed upwards so as to cut off the less divergent rays in their passage towards the object. It is claimed that this instrument has great capabilities of giving dark-ground illumination with lenses of 'wide apertures'; but that has application to the lenses contemporary with its introduction, and not to wide apertures as applied to the lenses of to-day. In comparison with what can be done with condensers it suffers greatly after we pass the $\frac{1}{2}$-inch objective, although it does give excellent results with

[1] A parabolic illuminator was first devised by Mr. Wenham, who, however, employed a silver speculum for the purpose. About the same time Mr. Shadbolt devised an annular condenser of glass for the same purpose (see *Trans. Microsc. Soc.* ser. i. vol. iii. 1852, pp. 85, 132). The two principles are combined in the glass paraboloid.

very low powers such as 1½-inch, 2-inch, and 3-inch objectives when employed to illuminate large objects such as whole insects, because this instrument gives more diffusion of light over the whole of a large object than a condenser does.

There is another paraboloid which, for completeness, we must briefly consider. In order to adapt the paraboloid for dark-ground illumination under objectives of wide angle of aperture, Mr. Wenham [1] long since constructed a *flat-topped* paraboloid, fitted to reflect only rays of such extreme obliquity that they would not pass out of the flat surface of the paraboloid into the under surface of the slide unless a film of either water or of some liquid of higher refractive index (such as turpentine or oil of cloves) were interposed between them. When thus enabled to enter the slide these rays pass on until they meet the cover, from which (in the case of dry-front objectives) they are reflected downwards upon the surface of the object, giving it a bright illumination on a perfectly dark field. The special value of this instrument, however, not being then understood, it was not constructed for sale; the same principle having been more recently taken up by Dr. Edmunds—an immersion-paraboloid was specially devised by him for use with immersion-objectives of wide aperture. But it utterly fails for this purpose. The object has to be mounted on the slip *dry*, and therefore the value of the immersion-objective at once is sacrificed, because the air-space between the object and the cover which is essential to this illuminator—destroys homogeneity and reduces the objective practically to an air-lens. It was believed that *Amphipleura pellucida* was resolved by its means with an oil objective, but this has not been, and we believe cannot be, established. By good and careful manipulation we have obtained faint resolution of *A. pellucida* with a *dry* lens, but an immersion lens used dry is so completely out of correction that it will resolve nothing.

Polarising Apparatus. In order to examine transparent objects by polarised light, it is necessary to employ some means of *polarising* the rays before they pass through the object, and to apply to them, in some part of their course between the object and the eye, an *analysing* medium. These two requirements may be provided for in different modes. The *polariser* may be either a bundle of plates of thin glass, used in place of the mirror, and polarising the rays by reflexion; or it may be a 'single image' or 'Nicol' prism of Iceland spar, which is so constructed as to transmit only one of the two rays into which a beam of ordinary light is made to divaricate by passing through this substance. Of these two methods the 'Nicol' prism is the one generally preferred, the objection to the reflecting polariser being that it cannot be made to rotate. This polarising prism is usually fixed in a tube (fig. 220, A), furnished with a large milled head at the bottom, by which it is made to rotate in a collar which screws into the sub-stage fitting. For the *analyser* a second 'Nicol' prism is usually employed; and this, fixed in a short tube, may be fitted either into a collar interposed between the lower end of the body and the objective, or into a cap

[1] *Trans. Microsc. Soc.* N.S. vol. iv. 1856.

placed over the eye-piece (fig. 220, B), in the stead of the ordinary eye-piece cap. The former arrangement, which is specially adapted for use with the binocular microscope, has the advantage of not limiting the field, but it stops a good deal of light; while in the latter the image is brighter, but a good deal of the margin of the field is cut off; and it is always important that the polarising prism should be large, so as not to act as a diaphragm to the condenser, thus cutting off the light when it is used; for the polarising apparatus may be worked in combination either with the achromatic condenser, by which means it may be employed with high-power objectives; or as a 'dark-ground' illuminator, which shows many objects—such as the horny polyparies of zoophytes—gorgeously projected in colours upon a dark field.



FIG. 220.

A, Fitting of polarising prism in sub-stage. B, Fitting of analysing prism above eye-piece.

For bringing out certain effects of colour by the use of polarised light it is, as already stated, desirable to interpose a plate of *selenite* between the polariser and the object: and it is advantageous that this should be made to revolve. A very convenient mode of effecting this is to mount the selenite plate in a revolving collar, which fits into the upper end of the tube that receives the polarising prism. In order to obtain the greatest variety of coloration with different objects, films of selenite of different thicknesses should be employed; and this may be accomplished by substituting one for another in the revolving collar. A still greater variety may be obtained by mounting three films, which separately give three different colours, in collars revolving in a frame resembling that in which hand-magnifiers are usually mounted, this frame being fitted into the sub-stage in such a manner that either a single selenite, or any combination of two selenites, or all three together, may be brought into the optic axis above the polarising prism (fig. 221). As many as thirteen different tints may thus be obtained. When the construction of the microscope does not readily admit of the connection of the selenite plate with the polarising prism, it is convenient to make use of a plate of brass (fig. 222) somewhat larger than the glass slides in which objects are ordinarily mounted, with a ledge near one edge for the slide to rest against and a large circular aperture into which a glass is fitted, having a film of selenite cemented to it; this 'selenite stage' or object-carrier being laid upon the stage of the

FIG. 221.

croscope, the slide containing the object is placed upon it, and, an ingenious modification contrived by Dr. Leeson, the ring into ıich the selenite plate is ted being made movable, e plate may be substituted r another, whilst rotation ıy be given to the ring by ɛans of a tangent-screw ted into the brass plate. ıe variety of tints given a selenite film under larised light is so greatly increased by the interposition of a tating film of mica, that two selenites—*red* and *blue*—with a mica m, are found to give the tire series of colours obinable from any number selenite films, either ɔarately or in combinaın with each other.

Fig. 222.

The compact appatus made by Swift as a neral sub-stage illumitor is useful and comndable, and is capable adaptation to most ıglish microscopes. It shown in fig. 223. The ecial advantage of this ndenser lies in its hav: the polarising prism, e selenite- and micans, the black-ground d oblique-light stops, d the moderator, all ought close under the ck lens of the achroatic ; whilst it combines itself all the most imrtant appliances which e sub-stage of a good ɔderate microscope can quire.



Fig. 223.—Swift's illuminating and polarising apparatus.

The use of monochroatic light is frequently irable in microscopic ork, especially blue light, hough of less moment an in pre-achromatic days. The usual method of obtaining loured light is to pass sunlight through coloured glass, or through coloured solution, such as the ammonio-sulphate of copper ; but this a most imperfect and unsatisfactory method, and does not give

*mono*chromatic light. The Messrs. Zeiss have constructed an apparatus (after Hartnack) for obtaining monochromatic light in a true form, which is illustrated in fig. 224.

By means of two prisms, P^1, P^2, of strong dispersive power a spectrum of considerable length is projected upon the object from beneath, so that with high powers the entire field is illuminated with a near approach to monochromatic light. The light enters the instrument through the slit *Sp*, which is adjustable in width by the screw S^2, and passes through the prisms and the lens at O, forming a spectrum at *Spk*, where the object on the stage is supposed to be situated.

By moving the slit by the screw S^1 the spectrum is caused to pass over the object, the different colours following in succession. The instrument may be used for low powers with ordinary daylight,



FIG. 224.

but for high powers sunlight must be employed. Moreover in practice it is needful to use a bull's-eye to focus the light on the slit *Sp*. But this instrument lacks the higher qualities required of it on account of the low angle of the combination O which acts as a condenser. We really want a pencil of monochromatic light, either parallel or slightly divergent, of such a size as to *fill the back lens* of a high-class condenser. If such a condenser as Powell's dry achromatic or later homogeneous achromatic of large aperture could be adapted to this instrument (which is no doubt possible) it might be of service to microscopists.

Sorby-Browning Micro-spectroscope.[1]—When the solar ray is decomposed into a coloured spectrum by a prism of sufficient disper-

[1] For general information on the spectroscope and its uses the student is referred to Professor Roscoe's *Lectures on Spectrum Analysis*, or the translation of Dr. Schellen's *Spectrum Analysis*, and *How to Use the Spectroscope*, by Mr. John Browning.

ive power, to which the light is admitted by a narrow slit, a multitude of dark lines make their appearance. The existence of hese was originally noticed by Wollaston; but as Fraunhofer first ubjected them to a thorough investigation and mapped them out, hey are known as *Fraunhofer lines*. The greater the dispersion iven by the multiplication of prisms in the spectroscope, the more of these lines are seen; and they bear considerable magnification. They result from the interruption or absorption of certain rays in he solar atmosphere, according to the law, first stated by Ångström, hat 'rays which a substance absorbs are precisely those which it mits when made self-luminous.' Kirchhoff showed that while the ncandescent vapours of sodium, potassium, lithium, &c. give a pectrum with characteristic *bright* lines, the same vapours intercept portions of the spectrum, so as to give *dark* lines at the points where he bright ones appeared, absorbing their own special colour, but llowing rays of other colours to pass through. Again, when ordinary light is made to pass through coloured bodies (solid, liquid, or aseous), or is reflected from their surfaces, so as to affect the eye with the sensation of colour, its spectrum is commonly found to exhibit absorption *bands*, which differ from the Fraunhofer lines, not only in their greater breadth, but in being more or less *nebulous*, or cloudy, so that they cannot be resolved into distinct lines by magnification, while too much dispersion thins them out to indistinctness. Now, it is by the character of these bands, and by their position in he spectrum, that the colours of different substances can be most accurately and scientifically compared, many colours whose impressions on the eye are so similar that they cannot be distinguished being eadily discriminated by their spectra. The purpose of the micro-spectroscope[1] is to apply the spectroscopic test to very minute quantities of coloured substances; and it fundamentally consists of an ordinary eye-piece (which can be fitted into any microscope) with certain special modifications. As originally devised by Dr. Sorby and worked out by Mr. Browning, the micro-spectroscope is constructed as follows (fig. 225): Above its eye-glass, which is achromatic, and made capable of focal adjustment by the milled head, B, there is placed a tube, A, containing a series of five prisms, two of flint glass (fig. 226, F F) interposed between three of crown (C C C), in such a manner that the emergent rays, *r r*, which have been separated by dispersion, leave the prisms much in the same direction as the immergent ray entered it. Below the eye-glass,

FIG. 225.—Micro-spectroscope.

FIG. 226.

[1] We do not make the change, lest complications should arise; but we think it would be more harmonious with analogy to call this instrument the *spectro-microscope*.

in the place of the ordinary stop, is a diaphragm with a narrow slit, which limits the admission of light (fig. 225); this can be adjusted in vertical position by the milled head, H, whilst the breadth of the slit is regulated by C. The foregoing, with an objective of suitable power, would be all that is needed for the examination of the spectra of objects placed on the stage of the microscope, whether opaque or transparent, solid or liquid, provided that they transmit a sufficient amount of light. But as it is of great importance to make exact comparisons of such artificial spectra, alike with the ordinary or natural spectrum, and with each other, provision is made for the formation of a second spectrum, by the insertion of a right-angled prism that covers one-half of this slit, and reflects upwards the light transmitted through an aperture seen on the right side of the eye-piece. For the production of the ordinary spectrum, it is only requisite to reflect light into this aperture from the small mirror, I, carried at the side; whilst for the production of the spectrum of any substance through which the light reflected from this mirror can be transmitted, it is only necessary to place the slide carrying the section or crystalline film, or the tube containing the solution, in the frame, D D, adapted to receive it. In either case this second spectrum is seen by the eye of the observer alongside of that produced by the object viewed through the body of the microscope, so that the two can be exactly compared.



Fig. 227.—Bright-line spectro-micrometer.

The exact position of the absorption bands is as important as that of the Fraunhofer lines; and some of the most conspicuous of the latter afford fixed points of reference, provided the same spectroscope be employed. The amount of dispersion determines whether the Fraunhofer lines and absorption bands are seen nearer or farther apart, their actual positions in the field of view varying according to the dispersion, while their relative positions are in constant proportion. The best contrivance for measuring the spectra of absorption bands is Browning's bright-line micrometer, shown in fig. 227. At R is a small mirror by which light from the lamp employed can be reflected through E D to the lens C, which, by means of a perforated stop, forms a bright pointed image on the surface of the upper prism, whence it is reflected to the eye of the observer. The rotation of a wheel worked by the milled head, M, carries this bright point

over the spectrum, and the exact amount of motion may be read off to $\frac{1}{10000}$th inch on the graduated circle of the wheel. To use this apparatus, the Fraunhofer lines must be viewed by sending bright daylight through the spectroscope, and the positions of the principal lines carefully measured, the reading on the micrometer-wheel being noted down. A spectrum map may then be drawn on cardboard, on a scale of equal parts, and the lines marked on it, as shown in the upper half of fig. 228. The lower half of the same figure shows an absorption spectrum, with its bands at certain distances from the Fraunhofer lines. The cardboard spectrum map, when once drawn, should be kept for reference.[1]

A beginner with the micro-spectroscope should first hold it up to the sky on a clear day, without the intervention of the microscope, and note the effects of opening and closing the slit by rotating the screw, C (fig. 225); the lines can only be well seen when the slit is reduced to a narrow opening. The screw H diminishes the length of the slit, and causes the spectrum to be seen as a broad or a narrow ribbon. The screw E (or in some patterns two small sliding-knobs) regulates the quantity of light admitted through the square aperture seen between the points of the springs, D D. Water tinged with



FIG. 228.—Upper half, map of solar spectrum, showing Fraunhofer lines. Lower half, absorption spectrum, showing position of bands in relation to lines.

port wine, madder, and blood are good fluids with which to commence this study of absorption bands.[2] As each colour varies in refrangibility, the focus must be adjusted by the screw B, fig. 225, according to the part of the spectrum that is examined. When it is desired to see the spectrum of an exceedingly minute object, or of a small portion only of a larger one, the prisms are to be removed by withdrawing the tube containing them; the slit should then be opened wide, and the object, or part of it, brought into the centre of the field; the vertical and horizontal slits can then be partly shut so as to enclose it; and if the prisms are then replaced, and a suitable objective employed, the required spectrum will be seen,

[1] Mr. Swift has devised an improved micro-spectroscope, in which the micrometric apparatus is combined with the ordinary spectroscopic eye-piece, and two spectra can be brought into the field at once. Other improvements devised by Dr. Sorby and a new form devised by Mr. F. H. Ward have been carried into execution by Mr. Hilger. (See *Journ. of Roy. Microsc. Soc.* vol. i. 1878, p. 826, and vol. ii. 1879, p. 81.)

[2] A series of specimens, in small tubes, for the study of absorption-spectra, is kept on sale by Mr. Browning; and the directions given in his *How to Work with the Micro-spectroscope* should be carefully attended to.

unaffected by adjacent objects. For ordinary observations objectives of from two inches to $\frac{3}{4}$-inch focus will be found most suitable; but for very minute quantities of material a higher power must be employed. Even a single red blood-corpuscle may be made to show the characteristic absorption bands represented (after Professor Stokes) in fig. 229.[1]



FIG. 229.

For the study of coloured liquids in test-tubes or small cells, the binocular spectrum microscope, described by Dr. Sorby in the 'Proceedings of the Royal Society,' No. 92, 1867, p. 33, is extremely convenient.

The spectral ocular by Zeiss is another and a very perfect form of the micro-spectroscope. This is an opinion expressed by Dr. Sorby and other experts, and it is manifest in the character of the instrument. Fig. 230 represents a sectional view of the instrument. It will be seen that the lower part is an ordinary eye-piece with its



FIG. 230.



FIG. 231.

two lenses, but in place of the ordinary diaphragm there is a slit, adjustable in length and breadth, shown in fig. 231. By studying

[1] For further information on 'The Spectrum Method of Detecting Blood,' see an important paper by Dr. Sorby in *Monthly Microsc. Journ.* vol. vi. 1871, p. 9.

this figure the method of adjustment, with two screws, F and H and the projecting lever, which carries a reflecting prism, can be readily understood. The upper part of the instrument swings about the pivot, K, so that by opening the slit the eye-piece can be used for focussing an object, the slit being the diaphragm. The upper portion contains the prisms, and also a scale in the tube, N, which is illuminated by the mirror, O. The image of the scale is reflected from the upper surface of the last prism to the eye, and when properly adjusted gives the wave-length of the light in any part of the spectrum. There is also a supplementary stage, not shown in the figure, upon which a specimen can be placed, and its light thrown up through the slit by reflection from the prism on the lever shown in fig. 230, alongside of the light from the object on the stage of the microscope, thus enabling the spectra from the two sources to be directly compared.

The Method of Using the Micro-spectroscope.—The objects to be investigated are of two sorts, liquid and solid. Colouring substances as chlorophyll, the colouring matter of hair, blood, &c. will frequently come under micro-spectroscopic investigation in the form of a solution. In general we need scarcely say anything concerning the preparation of the solution. In reference to the chlorophyll of the phanerogams especially, the particular part of the plant from which the preparation is to be made, as, for instance, the foliage leaves, is put for a short time in boiling water, then quickly dried by means of bibulous paper, and then immersed for a longer time in absolute alcohol, ether, or benzole in a dark place, for the purpose of extracting the chlorophyll colouring matter. The concentration of the solution thus produced, which influences the intensity of the absorption spectrum and the number and length of the absorption bands, depends naturally upon the time during which the material is in the extracting medium, as well as on the quantity of the material.

Commonly also a solution of less concentration will give the same intensity of spectrum if a sufficiently thick layer of it be used. The solution can generally be examined in an ordinary test-tube. The test-tube is filled and carefully corked and then laid on the stage of the microscope, or held before the opening of the comparison prism, as the case may be. For the latter purpose (bringing liquids before the opening of the comparison prism) a small open trough of glass, with two parallel glass plates, is very useful. For exact investigations, however, the trough-flask is preferable. It is a flask whose two sides, back and front, are parallel, furnished with a carefully fitted ground-glass stopper. It should be filled quite full of the solution and then laid with its broad side on the stage. It is especially indispensable when we wish to study the combination spectrum of two solutions. In that case two flasks are filled each with a different solution and both laid upon the stage one upon the other. For the purpose of examining small quantities of any liquid, a sufficient depth being obtained with very little material, vertical glass tubes attached to horizontal plates are used, as proposed by Mr. Sorby and shown in fig. 232. The narrow tubes are made of various lengths from sections of barometer tubing, in order to present different

thicknesses of the contained fluid, the broad tube being higher on one side than the other, and thus constituting a wedge-shaped cell, which, when filled and closed by a thin cover-glass, will present a varying thickness of fluid for study and comparison. If the object to be investigated is not a solution but a preparation of the kind which we commonly employ in microscopic inquiries, we must first of all bring it into the focus of the objective system. To do this we must first remove the tube bearing the prisms, open the slit somewhat, and use the apparatus as a simple ocular. If one has to deal with a small object which would not entirely fill the slit, but so that rays of light might come in by it and disturb the spectrum, he should turn the comparison prism so as to shut up some of the slit, without, however, letting in the light upon it, and then bring the object up near to it, and from the other side push up the shortening apparatus as close as is necessary. On the other hand, should the object consist of a number of single minute grains, which would cause to be drawn across the spectrum, in the direction of its length, perpendicular to the Fraunhofer lines, a like number of dark lines, one must adjust the microscope so that the object will be a little out of focus, somewhat above or below the true focus. In this way we shall get a uniform spectrum. The spectrum can also be improved in some other cases by likewise throwing the object somewhat out of focus.

Fig. 232.

Illumination by Reflexion.—Objects of almost every description will require at times to be examined and studied by what is called reflected light ; the light in this case is thrown down upon the object by various devices, and is reflected upwards through the objective. This has been called 'opaque illumination,' which, however, is not a comprehensive, nor even an accurate designation. Only a small proportion of the objects examined in this way are opaque ; the same diatom, for example, may often with advantage be examined with transmitted light, being transparent, and again by means of an illumination thrown upon, and reflected up from, its surface ; also a condenser with a central stop when used for a dark ground shows objects by reflected light, but it is manifestly not 'opaque illumination.' The designation of this method of illumination is consequently more accommodating than accurate.

There are two very simple means of obtaining this superficial illumination when low powers are employed. The first is the 'bull's-eye' (which is nowhere in this work called a 'condenser' ; this would, as it often has done, lead to confusion) ; it is enough to designate it as we have done. It is a plano-convex lens of short focus, two or three inches in diameter, mounted upon a separate stand, in such a manner as to permit of its being placed in a great variety of positions. The mounting shown in fig. 233 is one of the best that can be adopted :

ıe which carries the lens is borne at the bottom upon a swivel hich allows it to be turned in any azimuth; whilst it may ıed at any angle to the horizon, by the revolution of the al tube to which it is attached, around the other horizontal ich projects from the stem; by the sliding of one of these thin the other, again, the horizontal arm may be lengthened ened; the lens may be secured in any position (as its weight drag it down when it is inclined, unless the tubes be made the one into the other, more stiffly than is convenient) by f a tightening collar milled at its edges; and finally the al arm is attached to socket which slides up n upon a vertical stem. plane side of the e should be turned the object. Some pists like to have ıll's-eye attached to rt of the microscope; ıis is done, care must ı to attach it to a fixed the microscope, and ither the mechanical to the body, as is so ne. If it is fixed to chanical stage, when ct is moved the light uire to be readjusted, othing of the probable to the stage by the f the bull's-eye. If it to the body the light displaced when the he objective is altered. the bull's-eye should ve a weighted separate r be attached to the foot of the microscope.[1] optical effect of such a e differs according to



FIG. 233.—The bull's-eye.

of it turned towards the light and the condition of the rays ıll upon it. The position of *least* spherical aberration is when *x* side is turned towards *parallel* or towards the *least diverging* nsequently, when used by daylight, its *plane* side should be owards the *object*, and the same position should be given to it is used for procuring converging rays from a lamp, this being our or five times farther off on one side than the object is on r. But it may also be employed for the purpose of reducing rging rays of the lamp to parallelism, for use either with the

[1] sselet's bull's-eye attachment to lamp is convenient and inexpensive.—*Journ. Mub*, 1890.

paraboloid, or with the parabolic speculum to be presently described; and the *plane* side is then to be turned towards the lamp, which must be placed at such a distance from the bull's-eye that the rays which have passed through the latter shall form an inverted image of the lamp flame on the wall or a distant screen. For viewing minute objects under high powers, a smaller lens may be used to obtain a further concentration of the rays already brought into convergence by the bull's-eye. An ingenious and effective mode of using the bull's-eye, for the illumination of very minute objects under higher power objectives, has been devised by Mr. James Smith. The microscope being in position for observation, the lamp should be placed either in the front or at the side (as most convenient), so that its flame, turned edgeways to the stage, should be at a somewhat *lower level*, and at a distance of about three inches. The bull's-eye should be placed between the stage and the lamp, with its plane surface uppermost, and with its convex surface a little *above* the stage. The light entering its convex surface near the margin turned towards the lamp falls on its plane surface at an angle so oblique as to be almost totally reflected towards the opposite margin of the convex surface, by which it is condensed on to the object on the stage, on which it should cast a sharp and brilliant wedge of light. The adjustment is best made by first placing a slip of white card on the stage, and, when this is well illuminated, substituting the object-slide for it, making the final adjustment while the object is being viewed under the microscope. No difficulty is experienced in getting good results with powers of from 200 to 300 diameters, but higher powers require careful manipulation and yield but doubtful results.

The second simple method of securing this illumination is to have the concave mirror of the microscope capable of being used above the stage[1] so that the source of light may by its means be focussed on the object. Neither of these plans will answer for other than low powers, where there is plenty of room for the light to pass between the objective and the object. The ingenious use of the bull's-eye employed by Mr. James Smith, as detailed above, increases the possibility of magnification, but it needs practice and care.

An illuminator not so well known, or at least so much used as its merits justified, is Powell and Lealand's small bull's-eye of ¾-inch focus, which slides into an adapter fixed into the sub-stage, and susceptible of its rack-motion up and down. The object is placed on a super-stage and lies considerably above, but parallel with the ordinary stage. The bull's-eye, capable thus of being raised or lowered, and of being moved by sliding away from or close to the mounted object, has its plane side placed against the edge, and at right angles to the plane of the slip. By this means illumination of great obliquity can be obtained, and very surprising effects secured even with high powers. It was much used by the Editor and Dr. Drysdale in their earlier work on the saprophytic organisms, and in the days before homogeneous lenses, helped us over many difficulties of detail. It was the first illumination to actually resolve the *Amphipleura pellucida*. It could be very easily obtained with a student's microscope provided

[1] See *Journ. Roy. Microsc. Soc.* vol. iii. 1880, p. 898

age,[1] for on this the bull's-eye could be placed
e slip without any special apparatus or fitting.
ular method of 'opaque illumination' is by
l form of mirror, generally of polished silver,
', and fixed as in the case of the bull's-eye,
ons, to an immovable part of the microscope.
ploying this reflector, as provided with Powell
and, is seen in Plate III. The arm of the
to an immovable part of the stand, and is thus
ing up or down of the body. The lamp placed
server is set at such a height that its beams
flector; this, by means of a ball-and-socket
anipulated until the full image of the flame is
he object. For the same purpose a *parabolic*

4. FIG. 235.

employed mounted either on the objective,
fig. 234, or on an adapter, as in Crouch's,
ere a collar is interposed between the lower
the microscope and the objective seen at A.
able plan, for it increases the distance between
Wenham binocular prism; and as the bin-
ted for the kind of object usually examined
is increased distance acting detrimentally on
binocular prisms, and causing the available
ie focus of objectives of very low power to be
h of such collar, is to be avoided.
out doubt is to attach the speculum to a fixed
s done in the Powell and Lealand, the Ross,

he parabolic reflector was devised by Dr. Sorby,
very useful in certain investigations, such as
ture of metals. It consists of a parabolic
of which, in a semi-cylindrical tube open in

[1] Chapter II. p. 198, fig. 148.

front, is placed a small plane reflector which covers half of the objective, and throws the light directly down upon the object and back through the other half. It is shown in fig. 236 with the cylinder in place, and in the dotted lines with the same turned out. This arrangement allows of two kinds of illumination, oblique and direct, being readily used, as the plane reflector is attached to an arm so that it can be swung out of the way when not required, as shown in the figure.



FIG. 236.—Sorby's modification of the parabolic reflector.

Dr. Sorby was able to get results in the examination of polished sections of steel not otherwise attainable.

No opaque illumination, however, has yet surpassed the venerable **Lieberkühn**; the best experts freely admit that the finest critical images to be obtained by this method of illumination are secured by the Lieberkühn. This mode of illuminating opaque objects is by means of a small concave speculum reflecting directly down upon them to a focus the light reflected up to it from the mirror; it was formerly much in use, but is now comparatively seldom employed. This concave speculum, termed a 'Lieberkühn' from the celebrated microscopist who invented it, is made to fit upon the end of the objective, having a perforation in its centre for the passage of the rays from the object to the lens; and in order that it may receive



FIG. 237.

its light from a mirror beneath (fig. 237, A), the object must be so mounted as only to stop out the central portion of the rays that are reflected upwards. The curvature of the speculum is so adapted to the focus of the objective that, when the latter is duly adjusted, the rays reflected up to it from the mirror shall be made to converge strongly upon the part of the object that is in focus; a separate speculum is consequently required for every objective.

PLATE IV.



THE METHOD OF USING THE SILVER SIDE-REFLECTOR.

PUBLIC

It has two manifest drawbacks: the first one, *that of requiring a separate Lieberkühn for each objective*, is a difficulty which in the nature of things cannot be overcome. The radius of the Lieberkühn must alter with the focus of the objective employed, and each should have a certain amount of play on the objective to allow for slight alterations of focus, for if we employ parallel rays it is obvious that the Lieberkühn will focus nearer to the object than if divergent rays are used. This is met by an allowance being made to compensate it on the tube which slides the Lieberkühn on to the nose of the objective.

The second drawback has reference to the special way in which objects have to be mounted in order to be suitable for the Lieberkühn. This could be easily avoided if professional and other mounters would attend to the following simple suggestions :—

1. Slides should never be covered with paper ; it is without use, and fails as an ornament ; and opaque glass slips should be entirely avoided.

2. The ring of cement should not be made of greater width than is necessary for security.

3. A stop of paper or varnish should never be placed behind an object.

Let every opaque mount be also a transparent one, since it is often most useful to examine an opaque object afterwards by transmitted light. The stop should always be a separate one ; this may be a disc on a pin held in the sub-stage, or, what is still simpler, a piece of moderately thick 'cover' glass, cut to the 3 × 1 inch size, or rather shorter, should have a small disc of Brunswick black put on it centrally on the 'turn-table'[1] and this may be placed under the slide when the Lieberkühn is to be used. There may be two or three such slips with stops of different sizes ; in this way every mount may be examined either with the Lieberkühn or by directly transmitted light, and of course by having a larger stop the same object may be examined by any kind of reflected light. Many a valuable preparation has been spoiled by placing a stop on it which cannot be removed.

4. It would be a most appreciable benefit to the cause of microscopy, as we have already hinted, if a uniform gauge of thickness of slip and diameter of cover-glass were adopted. For the thickness of the slip, the $\frac{1}{20}$th of an inch would prove most suitable, and for the diameter of the cover-glass $\frac{3}{4}$ of an inch would be most convenient, and if the thickness of the cover-glass were uniformly from ·006 to ·008 the gain would be still greater. Certainly no mount ought to be finished without the thickness of the cover-glass being marked in diamond point upon it, and a narrow ring of shellac cement should be put round every cover-glass where there is even a probability that a homogeneous lens will be admissible in examining the object mounted.

Very minute cover-glasses—such as those $\frac{3}{160}$ths of an inch in diameter—are to be wholly condemned. They do not allow the contions required by modern microscopy, being adverse to the employment of oil-immersion lenses in anything like the most efficient way.

Lieberkühns can be used with objectives as high as $\frac{1}{4}$ of an

[1] Chapter VII.

inch focus of ·77 N.A. For higher powers than this a perfectly flat speculum may replace the conical form, being illuminated by a condenser with a stop, and racked up well within its focus. The oblique annular ring of light falls on the flat speculum, and is then reflected on the object.

Fig. 238.—Beck's light-modifier.

Illumination for Lieberkühn may be either from the flat of the lamp-flame, reflected by the plane mirror, or by the edge of the flame, the rays being rendered parallel by a bull's-eye, and reflected from the plane mirror to the Lieberkühn.

Very often this kind of illumination is so intense that it requires modifying. It is useful for this and many other purposes in illuminating objects to have a *small frame, mounted like an ordinary bull's-eye stand, into which a plate of blue glass may be inserted and placed between the light and the mirror.* Two inches by four inches is a very useful size for such a screen, and two or three plates may be kept of various depths of colour, so that they may be changed as circumstances require.

Messrs. Beck make a small and useful *light-modifier*, which can be also used for this purpose, which is illustrated in fig. 238; but what is required is not merely a *tinted glass*, but a combination of different tints resulting in a correct blue not otherwise attainable.

There is one other kind of reflected illumination employed, produced by the **vertical illuminator**, which, although it has been in use for some years, has received an accession of value from the employment of immersion lenses. It is produced by a device which secures vertical illumination invented by Professor H. L. Smith, of Geneva, U.S.A.

The principle of this illuminator is to employ the objective as its own illuminator. This may be done in several ways.

1. That of Professor Smith is to place a speculum with an aperture in it in the body of the microscope at an angle of 45° to the optic axis; opposite this speculum is an aperture in the tube for light to enter. It will be understood by figs. 239 and 240, which represent a longitudinal section of the nose-piece at C of the vertical illuminator at *e*, and of part of the objective at *d*. *a* is the aperture for admitting the light to the speculum *b*. The path of the beam is depicted, and it will be seen that on being reflected from the speculum it passes through the combination of lenses, making the objective

a 'condenser,' and is brought to a focus on the object, which is the focus of the objective. The rays now proceed from the illuminated object once more, through the objective upwards, and pass through the central aperture in the speculum to the eye-piece and the eye.

2. Tolles, instead of this, places a small right-angled prism just at the back of the front lens of the objective. But this only gives oblique illumination in one azimuth, and from experience we are obliged to express dissatisfaction with its performance.

3. Messrs. R. and J. Beck, in place of a speculum pierced, employ a disc of cover-glass. The cover-glass is mounted on a pin, B, fig. 240, in order that it may be rotated and oblique light obtained by the milled head, *f*, A, fig. 240. We believe that it would be far better in practice to fix the cover-glass at the angle of 45°. But it will be seen that by this plan total reflexion may be obtained in one direction and transmission to the eye in another.



Fig. 239.



Fig. 240.

4. Powell and Lealand's method is to fix a piece of glass, *worked* at, at an angle of 45° to the optic axis, with a rotating diaphragm in front of the aperture admitting the light.

To use these instruments the edge of the lamp flame should be placed in front of the reflector, so that the rays may be reflected on to the back lens of the objective in a line parallel to the optic axis. The distance from the lamp to the reflector must exactly equal the distance from the reflector to the diaphragm of the eye-piece in a positive eye-piece, or the eye-lens of a negative eye-piece, otherwise the rays will not be focussed on the object.

This illumination is only suitable for objects mounted dry on the cover, and with immersion lenses. No good result was ever obtained until the immersion lenses were brought into use.

Of all the light which is caused to pass out of the front lens of the objective, through the oil and into the cover-glass, that which has an obliquity less than the critical angle of glass (41°) passes

through the cover and object and is lost; but all the light which is of *greater* obliquity than the critical angle for glass is totally reflected from the *under surface of the cover-glass*, and comes back through the oil and the objective to the eye-piece and the eye; they are, in fact, all optically continuous, so that the upper surface of the cover-glass has ceased to exist optically, the only reflexion being from its inner surface. It is here, therefore, that the oil-immersion system gives a new value to this illuminator by this means, enabling it to utilise a larger aperture otherwise unavailing.

When this illumination is employed, if the eye-piece be removed and the back of the objective be examined, it will be seen that all that portion of the back of the objective whose aperture exceeds 1·0 is brilliantly illuminated. This annulus represents, and is produced by, the excess of aperture beyond the equivalent angle of 180°, of which it is also a measure. The internal dark space is of the exact diameter of that of a dry objective of the same focus, and is the maximum space which it can itself utilise on a dry object by transmitted light.

By means of this instrument carefully used, the most stubborn frustules of difficult tests and the most crucial lined objects have been resolved; while it is eminently serviceable in determining whether any dry-mounted object is in optical contact with the cover-glass or not. If it be not so it is invisible with the vertical illuminator. So also it is instructive to examine the backs of objectives of various apertures with this mode of illumination. A dry objective will be wholly without the bright annulus, while an immersion of 1·1 N.A. will have a narrow annulus, and that of 1·4 or 1·5 a broad and still broader one. In this way, by practice, a fair approximation of the aperture of an objective may be obtained.

It is not the *absolute* size of the annulus, but the relation of the size of the annulus to that of the whole back, that must be estimated. Thus a $\frac{1}{8}$th of N.A. 1·2 will have as broad an annulus as a $\frac{1}{12}$th of 1·4 N.A., but the diameter of the back of the $\frac{1}{8}$th is, of course, much larger than that of the $\frac{1}{12}$th, and this involves the necessity of a relative comparison.



Fig. 241.

In examining objects with those higher powers which focus extremely close to the covering glass the slightest inadvertence is likely to lead to a fracture of the glass, and perhaps to the destruction of a valuable slide. This is a serious matter with Möller's diatom type slide, or Nobert's test lines, or with many others that are expensive or perhaps impossible to replace. To remove this source of danger, *Mr. Stephenson contrived the* **safety stage**, shown in fig. 241. The frame on which the slide carrying the object rests is hinged at its upper part, and kept in its true position by slight springs, which give way directly the slide is pressed by the objective. It is found that springs firm enough to ensure the steadiness required for high powers may yet be sufficiently flexible to give way before very thin glass is endangered, and a glance at the stage shows if it is made to deviate from the normal position in which its upper and lower edges are parallel.

ished with most microscopes affords a ready means. These
ated by means of a joint upon a pin, which fits into a hole
the corner of the stage itself or in the object-platform; the
nserted by press-
pin that projects
of the blades,
it is separated
other; and the
ose again by their
sticity, so as to
he object when
ure is withdrawn.
g the wire stem
ears the forceps
its socket, and by
hat socket verti-
n its joint, and
nt horizontally
pin, the object
brought into the
isely in the posi-
ired; and it may
ed round and
that all sides of
be examined, by
iving a twisting
it to the wire
The other ex-



Fig. 242.—Stage-forceps.

Fig. 243.—Stage-forceps.



Fig. 244.
Three-pronged forceps, screw adjustment.

Fig. 245.—The stage-vice.

of the stem often bears a small brass box filled with cork,
orated with holes in its side, seen in fig. 243; this affords a
old to common pins, to the heads of which small objects can
ned by gum, or to which discs of card &c. may be attached,

disc-holder, fig. 246, or it may simply drop into a stage fitting, as in the figure.

For the examination of objects which cannot be conveniently held in the stage-forceps, but which can be temporarily or permanently attached to discs, no means is comparable to the *disc-holder* of Mr. R. Beck (fig. 246) in regard to the facility it affords for presenting them in every variety of position. The object being attached by gum (having a small quantity of glycerine mixed with it) or by gold size to the surface of a small blackened metallic disc, this is fitted by a short stem projecting from its under surface into a cylindrical holder; and the holder carrying the disc can be made to rotate around a vertical axis by turning the milled head on the right, which acts on it by means of a small chain that works through the horizontal tubular stem; whilst it can be made to incline to one side or to the other, until its plane becomes vertical, by turning the whole movement on the horizontal axis of its cylindrical socket.[1] The supporting plate being perforated by a large aperture, the object may be illuminated by the Lieberkühn if desired. The discs are inserted into the holder, or are removed from it, by a pair of forceps constructed for the purpose; and they may be safely put away, by inserting their stems into a plate perforated with holes. Several such plates, with intervening guards to prevent them from coming into too close apposition, may be packed into a small box. To the value of this little piece of apparatus the Author can bear the strongest testimony from his own experience, having found his study of the *Foraminifera* greatly facilitated by it.



FIG. 246.—Beck's disc-holder.

Glass Stage-plate.—Every microscope should be furnished with a piece of plate glass, about 3½ in. by 2 in., to one margin of which a narrow strip of glass is cemented, so as to form a ledge. This is extremely useful, both for laying objects upon (the ledge preventing them—together with their covers, if used—from sliding down when the microscope is inclined), and for preserving the stage from injury by the spilling of sea-water or other saline or corrosive liquids, when such are in use. Such a plate not only serves for the examination of transparent, but also of opaque objects; for if the condensing lens be so adjusted as to throw a side light upon an object laid upon it, either the diaphragm plate or a slip of black paper will afford a dark background; whilst objects mounted on the small black discs suitable to the Lieberkühn may conveniently rest on it, instead of being held in the stage-forceps.

Growing Slides and Stages.—A number of contrivances have been devised of late years for the purpose of watching the life histories of minute aquatic organisms, and of 'cultivating' such as develop and

[1] A small pair of forceps adapted to take up minute objects may be fitted into the cylindrical holder in place of a disc.

multiply themselves in particular fluids. One of the simplest and most effective, that of Mr. Botterill, represented in fig. 247, consists of a slip of ebonite, three inches by one, with a central aperture of three-fourths of an inch at its under side; this aperture is reduced by a projecting shoulder, whereon is cemented a disc of thin glass, which thus forms the bottom of a cell hollowed in the thickness of the ebonite slide. On each side of this central cell a small lateral cell communicating with it, and about a fourth of an inch in diameter, is drilled out to the same depth; this serves for the reception of a supply

Fig. 247.

of water or other fluid, which is imparted, as required, to the central 'growing' cell, which is completed by placing a thin glass cover over the objects introduced into it, with the interposition of a ring of thin paper, or (if a greater thickness be required) of a ring of cardboard or vulcanite. If the fluid be introduced into one of the lateral cells, and be drawn off from the others – either by the use, from time to time, of the small glass syringe to be hereafter described, or by threads so arranged as to produce a continuous drip *into* one and *from* the other—a constantly renewed supply is furnished to the central cell, which it enters on one side, and leaves on the other, by capillary attraction.



Fig. 248.

Dr. Lewis' and Dr. Maddox's growing slide is shown in fig. 248. Two semicircles of asphalte varnish are brushed on the slide, one being rather larger than the other, so that the ends of one half-circle might overlap the other, but not so closely as not to permit the entrance and exit of air. When nearly dry a minute quantity of growing fluid was placed in the centre, upon which a few spores were sown, a cover-glass being placed over it, which adhered to the semi-dried varnish. The slide was placed under a bell-glass, kept damp by being lined with moist blotting-paper.

Dr. Maddox's growing slide will be understood from the annexed sketch, fig. 249. The shaded parts are pieces of tinfoil fastened with

shellac glue to a glass slide. The minute fungi or spores to be grown are placed on a glass cover large enough to cover the tinfoil, with a droplet of the fluid required. This, after examination to see that no extraneous matter is introduced, is placed over the tinfoil, and the edges fastened with wax softened with oil, leaving free the spaces, X X, for entrance of air. Growing slides of this description could be made cheaply with thin glass instead of tinfoil.



FIG. 249.—Maddox's growing stage.

Dallinger and Drysdale's Moist Stage for Continuous Observations. It is needful in working out the life histories of minute forms to be able to keep the organisms in a normal and undisturbed condition for sometimes weeks at a time: only a small drop of fluid containing the organism can be under observation, and this, without proper provision, is constantly evaporating. To prevent this, and still to employ very high powers in prolonged study of a given organism, is the object of this device. It consists of a plain glass stage, fig. 250, *a*, *a*, so fitted as to slide on in the place of the ordinary sliding stage of a Powell and Lealand or Ross stand. It is thus susceptible of the mechanical motions common to those stages. Its foundation, fig. 250, *a*, *a*, is plate glass, about the tenth of an inch thick, in order to give it firmness. But this is too thick to work through with a condenser and high powers, and therefore a circular



FIG. 250.—Dallinger and Drysdale's moist continuous growing stage.

aperture, *b*, is cut through it, and a thin piece of good glass, *c*, *d*, *e*, *f*, is fixed over the under surface of it with Canada balsam: this may be as thin as the condenser may require. At the end of the arm *a*, which extends some distance beyond the stage to the right of the reader, but when the arrangement is set up on the microscope to the left of the operator, a brass socket with a ring attached is fixed with marine glue. It is marked in the drawing *g*, *g*, *g*. The object of this ring is to hold a glass vessel, fig. 251, about 1¾ or 2 inches

t simply drops in, and the top, *a*, being slightly larger than
g, fig. 250, it is prevented from slipping through.
ıs suppose the stage to be in its position on the microscope,
vessel, fig. 251, inserted in this manner into *g*, fig. 250. A
good, new linen is now cut to the shape drawn in fig. 254,
a being long enough to reach to the end of the glass stage,
ı at *b* bent over, leaving the part in the
ig. 251, which is inserted into *g*, fig. 250.
ion is indicated in fig. 250, by the dotted
h, *h*, &c. But before it is laid upon the
ircular aperture, *d*, fig. 254 is cut out, which
much larger in diameter than the covering
ich it is intended to use. We therefore
mall covers.



Fig. 251.

glass with the flap of linen in it is now filled
ter, and the linen is wetted and wrung so as
ip, and the whole is very soon, by capillary
onstantly and evenly wet. A drop of the
be examined must now be placed at *k*, fig.
the covering glass, *i*, must be laid on. It will be seen that
ı broad, clear space between the covering glass and the linen.
want to form a chamber into which the object-glass can
ed, and which shall enclose a portion of the constantly wet
ıd be to a very large extent air-tight.
sequence will be that the evaporation
he chamber will be always greater in
from the linen, on account of its con-
ınewal, than it can be from the film of



Fig. 252.

ed, the moisture in the chamber is so
ıder favourable circumstances that it
ıcreases than allows a diminution of
of fluid. The manner in which we effect this is simple. A
glass tubing, about 1½ inch in diameter, is cut to about ¾ of
ın length. At one end of this a piece of thin sheet caou-
s firmly stretched, and a small hole is made in its centre.
gives a drawing of it; *a* is the piece of glass tubing, *b* is
ched elastic film, which is securely tied on by means of *a*
ı the glass at *d*, and *c* is the aperture. The bottom edge, *e*,
e carefully ground. This is laid in the position in which it
at in the drawing, on the linen of the stage, the aperture *c*
er the centre of the covering glass. The object-glass is now
own *through the small hole*, *c*, fig. 252, and adjusted to focus.
ıtchouc should be thin enough to afford no impediment to
n of the fine adjustment, when it will be seen that it clasps
ct-glass by its elasticity at the aperture; and the gentle
forces the under edge of the chamber upon the linen, so
le or no air is admitted, while if the under edge of the
be carefully ground it will suffer the stage, linen and all,
under it when the milled heads for working the mechanical
ı in action.

A drawing of the apparatus in working order is given in perpendicular section at fig. 253. The parts *a*, *a* in this figure represent the glass stage corresponding to *a*, *a*, fig. 250; *b* in both figures stands for the round aperture in the thick glass; *b*, in fig. 253, corresponds to the thin glass which covers this aperture, marked *c*, *d*, *e*, *f* in fig. 250, but in the form of this device now used by the Editor the thin glass floor is cemented to the *bottom* of the plate glass, *a*, *a*, thus making a cell equal to the thickness of the whole stage. The linen is marked in dotted lines in both figures: *d*, fig. 253, represents the covering glass, *i*, in fig. 250; *e*, *e*, fig. 253, is the piece of glass tubing, shown in fig. 252; *f*, *f*, fig. 253, is the stretched caoutchouc seen at *b* in fig. 252, with the object-glass *g*, penetrating and tightly filling up the aperture *c* in the figure, thus forming the moist chamber, *ch*, *ch*, by enclosing parts *h*, *h*, fig. 253, of the linen, which from the glass vessel to the left of the stage is by capillarity always renewing its moisture; and with *h*, fig. 253, sunk as a cell, by the attachment of the thin glass floor to the under side of the stage, as described above, this annular flap of linen overhangs, but does not lie upon, the floor on which the drop of fluid with its living inhabitants is placed. This is a great security against accidental flooding.



FIG. 253.

It will be seen that the instrument must be horizontal; but there is no inconvenience arising from this if it be placed on a sufficiently low support, and it will be found in practice that it may be worked



FIG. 254.

for a long time without any other change in the arrangement than the screwing up or down of the fine adjustment. The difficulties in working are few, and can be best discovered and overcome in practice.

Dr. Dallinger's Thermo-static Stage for Continuous Observations at High Temperatures.—It frequently happens that either for the purpose of experiment, or the study of special organisms, the student

needs a similar continuous stage to the above, but one in which varying temperatures may be obtained and kept at any point static at the will of the operator. This is very satisfactorily accomplished by the following device : The stage was made as described above, but it was made hollow and water-tight. The whole stage is seen in perspective in fig. 255. At A, *a b* are two grooved pieces of solid metal which permit the stage to slide on to the stage of an ordinary microscope, and partake of the mechanical movements effected by the milled heads; B is a vessel for water with a thermometer *a* of sufficient delicacy for indicating the temperature; *b* is a mercurial regulator, carefully made, but of the usual pattern; *c* brings



Fig. 255.

the gas from the main; *d* conveys as much of the gas as is allowed to escape from between the top of the mercury, and the bottom of the gas delivery tube to the burner *e*. The regulation of this apparatus so as to obtain a static temperature, as is well known, is a matter of detail depending chiefly on the careful use of the mercurial screw-plug *f*, and the height and intensity of the burner *e*. A temperature quite as accurate as is needed can be obtained for the purpose required.

The stage A is placed in position on the instrument, and two openings in this hollow stage at *c d* (A) are connected with two similar openings in the water vessel, viz. *g h* (B). The whole is carefully filled with water and raised to the required temperature and regulated.

The manner in which it accomplishes the end desired is as follows. On the centre of the stage (A) will be seen a small cylinder of glass;

this is ground at the end placed on the stage, and covered with a sort of drumhead of india-rubber at the upper end. By examining C with a lens it will be seen that a cell is counter-sunk into the upper plate of the hollow stage at *e''*, and a thin plate of glass is cemented on to this. At *e* another disc of glass is cemented water-tight, so that a film of warm water circulates between the upper and under surfaces of this glass aperture. A glass cup is placed in the jacketed receptacle *f* (A and C), and this also is filled with water. A piece of linen is now laid on the stage (A, *g*) with an aperture cut in its centre slightly less than the counter-sunk cell in which the glass disc *e''* is fixed, and a flap from it is allowed to fall over into the glass vessel *f* (A and C). Thus by capillarity the water is carried constantly over the entire face of the linen. But the glass cylinder seen in A is made of a much larger aperture than the cell and the opening in the linen, and consequently a large annulus of the linen is enclosed within the cylinder. The drop of fluid to be examined is placed on the small circular glass plate and covered with the thinnest glass, the drum-head cylinder is placed in position, the point of a high-power lens is gently forced upon the top of the india-rubber through a small aperture, thus forcing the lower ground surface of the cylinder upon the linen, and making the space within the closed cylinder practically air-tight, but still admitting of capillary action in the linen. Thus the enclosed air becomes saturated.

By complete circulation the water in the vessel *e* (A) is but slightly below that within the jacket of the stage, and thus the vapour as well as the stage are near the same thermal point.

For the admission of illumination and for allowing the use of various illuminating apparatus, a large bevelled aperture *e* (C) is made between the lower and upper plates of the stage jacket, which is found to supply all the accommodation needed.

There are many other forms of hot stage having various special purposes, and some of general application; a good account of these will be found in the 'Journal Roy. Micro. Soc.' vol. vii. ser. ii. pp. 299–316.



FIG. 256.

The Live-box and Compressors.—What is now so well known even to the tiro as the 'live-box' was originally devised by Tully, and it was afterwards improved by Varley, who in the place of a level disc of glass for the floor, as well as the top of the 'box,' bevelled a piece of thick glass and burnished it into the top of the tube, where it formed the floor of this 'animalcule cage': this prevented the draining off of the water at the edge by capillary attraction. But in that form a

condenser cannot be used successfully with it, and therefore a dark ground cannot be employed. But as it is Rotiferæ and Infusoria generally that constitute the *raison d'être* for this piece of apparatus, and as a dark ground gives results of high value—to say nothing of their beauty—with these forms, it lost much of its value.

The whole piece of apparatus is seen at A, fig. 256. A section of it is seen at B. A modification was subsequently made by Swift, which is seen at C, where the glass floor-plate is seen to be burnished into the brass plate, and the cover-glass is made to slide down upon it on a tube. But in this still greater difficulty arose, when the focus of the lens was shorter than the length of the tube; then, indeed, the motion of the 'box' was limited to the difference in diameter between the cell in which the glasses were sunk and the object-glass—in fact only low powers could be employed with it.

Mr. Rousselet has overcome this difficulty by a device which is shown in fig. 257.

In this the glass plate bevelled for the floor is somewhat reduced in diameter, but the outer ring is enlarged sufficiently to allow any high power to focus to the very edge of this glass floor. An object lying anywhere over the floor can be reached by the condenser from

Fig. 257.

below, and by both high and low powers from above, and when well made it acts well as a compressor. A drop of water so small that a rotifer may be unable to swim out of the field of view of a $\frac{1}{4}$-inch objective can be readily arranged with it; and a little practice enables the operator to employ it for many useful purposes in the study of 'pond life.'

The compressor or **compressorium** is a more elaborate device, somewhat after the same kind, but arranged to give the operator more accurate control over the amount of pressure to which the object is subjected. Mr. Rousselet has constructed one of very efficient form. The bevelled glass in this also is kept small, with respect to the size of the cover-glass, and it acts with perfectly parallel pressure between the two glasses, which in delicate work is of considerable importance.

The cover-glass is held on an arm which screws down on a vertical post against a spring; as the screw is raised the spring raises the cover-glass, and by an ingenious spring catch it is kept central with the glass-plate floor. This can nevertheless be released, and the entire cover can be turned aside to put on a fresh object, clean and so forth. It is simple, light, and, being parallel, can be used with the highest powers.

An extremely handy *reversible compressor* is seen in fig. 258: it is the device of Mr. W. Rowland. It is made of german silver, and

the rings have two glass covers cemented to them ; the lower plate is attached to a rod turning in a pocket, while the upper one pivots on a milled head which clamps if required or releases it when required for more easy cleaning. Varying pressures of the cover-glasses are obtained by turning the milled head in the centre of the plate, and the socket fits in the stage in the same position as the stage forceps &c.

It is sometimes required, in very delicate work on very minute



Fig. 258.—Mr. Rowland's reversible compressor.

organisms, to compress them very slowly and with great care while we are examining them with high powers. The cover-glass is of necessity thin, and the pressure from the minute dimensions of the object must be very considerable in order to act upon the organism at all. For this purpose we have found a somewhat heavy compressor made by Powell and Lealand of great value. A strong brass plate forms its base, and a lever arm carrying the cover-glass of the compressor is raised and lowered with a fine screw. The cover-glass may be cemented on to two or three separate fronts which screw on, and may carry cover-glass of different thicknesses. The cover, to prevent flexure, is small, but will work easily with any of the modern high-power lenses. The whole body of the ring to which the cover-glass is attached is very solid and strong. A glass slip of



Fig. 259.—Professor Delage's parallel compressor.

the ordinary size slips in, and is clamped by a spring on the base, and upon this the cover-glass is brought down in compression. An object the 5000th of an inch in thickness can be readily held and compressed by its means, but the fronts must be turned with great care, and the cover-glasses used for cementing on must be much larger than the aperture in the ring, so that a large surface may be cemented.

Recently Professor Y. Delage has devised a very admirable form of compressor for the most delicate observations (figs. 259, 260) in which the pressure is effected by the action of a screw on an inclined plane A, and working against the spring R. When the screw is turned on one side, the upper part of the compressor can be raised on the

Fig. 260.—Professor Delage's parallel compressor.

pivots B B', as shown in fig. 260. The frame holding the upper plate has a gimbal motion on the pivot D (and the corresponding one on the opposite side), and the frame can be detached by pressing the pin C and the corresponding one on the opposite side, causing the frame-holder to spring open slightly. The two glasses being oblong and lying crossed, it is easy to add a drop of liquid during compression. The compressor can be reversed, and in that case rests on the three small pillars, which are high enough to allow the milled head of the screw to clear the stage.

The zoöphyte trough is a larger live-box differently constructed. The form that has proved one of the best up to our own day was introduced by Mr. Lister in 1834, and is well known. It is depicted in fig. 261, being formed of slips of glass, and has a loose horizontal plate of glass equal to the inside length of the trough, so that it may be moved freely within it, also a slip of glass that will lie on the bottom and fill it, with the exception of the thickness of this loose plate. To use it, the slip is put upon the bottom, the loose plate is placed in front of it with its bottom edge touching the inside of the front glass, a small ivory wedge is inserted between the front glass of the trough and the upper part of the loose vertical plate, which it serves to press backwards; but this pressure



Fig. 261.

is kept in check by a small strip of bent whalebone,[1] which is placed between the vertical plate and the back glass of the trough. By moving the ivory wedge up and down the amount of space left between the upper part of the vertical plate and the front glass of the trough can be precisely regulated, and as their lower margins are always in close apposition, it is evident the one will incline to the other with a constant diminution of the distance between them from above downwards. An object dropped into this space will descend until it rests between the two surfaces of glass, and it can be placed in a position of great convenience for observation.

By very little contrivance these troughs with their contents may be kept, when not under examination, in much larger aquaria, obtaining the advantage of aëration and coolness.

Mr. Botterill devised a trough which is made of two plates of vulcanite or metal which screw together, and between them are two plates of glass, of the proper size, of any desired thickness, kept apart by half a ring of vulcanised indiarubber, the whole being screwed tightly enough together by three milled heads to prevent leakage. But leakage or the fracture of glasses is not uncommon with this otherwise convenient form.

An excellent, though shallow, trough was made by Mr. C. G. Dunning, which we illustrate in fig. 262. The lower plate or trough proper is made of metal, 3 inches long by 1½ wide and about $\frac{1}{16}$ thick, with an oval or oblong perforation in the centre, and the under side is recessed, as shown in fig. 262, B. In this recess is fixed by means of Canada balsam or shellac a piece of stout covering glass, forming the bottom of the cell, the recess being sufficiently deep to prevent the thin glass bottom from coming into actual contact with the stage of the microscope or with the table when it is not in use. Two pieces are provided near the bottom edge of the cell: the cover (fig. 262, C) is formed of a piece of thin brass, rather shorter than the trough, but about the same width; it has an opening formed in it to correspond with that in the trough, and under this opening is cemented a piece of cover-glass. The cover plate is notched at the two bottom corners, and at the two top corners are formed a couple of projecting ears. In order to use this apparatus it must be laid flat upon the table, and filled quite full of water. The object



FIG. 262.

[1] Watch-spring or other elastic metal should not be used on account of oxidation.

to be examined is then placed in the cell, and may be properly arranged therein; the cover is then lowered gently down, the two notches at the bottom edges being first placed against the pins; in this way the superfluous water will be driven out and the whole apparatus may be wiped dry. The capillary attraction, assisted by the weight of the cover, will be found sufficient to prevent any leakage; and the pins at the bottom prevent the cover from sliding down when the microscope is inclined. This zoophyte trough possesses two important qualities: first, it does not leak; second, it is not readily broken without gross carelessness. The shallowness may be overcome by placing an ebonite plate with the required aperture between the two mounted glasses.

Infusoria, minute Algæ, &c. however, can be well seen by placing a drop of the water containing them on an ordinary slide, and laying a thin piece of covering glass on the top; and objects of somewhat greater thickness can be examined by placing a loop or ring of fine cotton-thread upon an ordinary slide, to keep the covering glass at a small distance from it; and the object to be examined being placed on the slide with a drop of water, the covering glass is gently pressed down till it touches the ring. Still thicker objects may be viewed in the various forms of 'cells' hereafter to be described, and as, when the cells are filled with fluid, their glass covers will adhere by capillary attraction, provided the superfluous moisture that surrounds their edges be removed by blotting-paper, they will remain in place when the microscope is inclined. An *annular cell*, that may be used either as a 'live-box' or as a 'growing slide,' has lately been devised by Mr. Weber (U.S.A.). It is a slip of plate-glass, of the usual size and ordinary thickness, out of which a circular 'cell' of $\frac{3}{4}$-inch diameter is ground, in such a manner that its bottom is *convex* instead of concave, its shallowest part being in the centre and the deepest round the margin. A small drop of the fluid to be examined being placed upon the central convexity (the highest part of which should be almost flush with the general surface of the plate), and the thin glass cover being placed upon it, the drop spreads itself out in a thin film, without finding its way into the deep furrow around it; and thus it holds-on the covering glass by capillary attraction, while the furrow serves as an air-chamber. If the cover be cemented down by a ring of gold size or dammar, so that the evaporation of the fluid is prevented, either animal or vegetable life may thus be maintained for some days, or, if the two should be balanced (as in an aquarium), for some weeks.

Dipping Tubes.– In every operation in which small quantities of liquid, or small objects contained in liquid, have to be dealt with by the microscopist, he will find it a very great convenience to be provided with a set of tubes of the forms represented in fig. 263, but of somewhat larger dimensions. These were formerly designated as 'fishing tubes,' the purpose for which they were originally devised having been the fishing out of water-fleas, aquatic insect-larvæ, the larger animalcules, or other living objects distinguishable either by the unaided eye or by the assistance of a magnifying glass from the vessels that may contain them. But they are equally

applicable, of course, to the selection of minute plants; and they may be turned to many other no less useful purposes, some of which will be specified hereafter. When it is desired to secure an object which can be seen either with the eye alone or with a magnifying glass, one of these tubes is passed down into the liquid, its upper orifice having been previously closed by the forefinger, until its lower orifice is immediately above the object; the finger being then removed, the liquid suddenly rises into the tube, probably carrying the object up with it; and if this is seen to be the case, by putting the finger again on the top of the tube, its contents remain in it when the tube is lifted out, and may be deposited on a slip of glass, or on the lower disc of the aquatic box, or, if too copious for either receptacle, may be discharged into a large glass cell. In thus fishing in jars for any but minute objects, it will be generally found convenient to employ the open-mouthed tube C; those with smaller orifices, A, B, being employed for 'fishing' for animalcules &c. in small bottles or tubes, or for selecting minute objects from the cell into which the water taken up by the tube C has been discharged. It will be found very convenient to have the tops of these last blown into small funnels, which shall be covered with thin sheet india-rubber, or topped with indiarubber nipples, which by compression and expansion can then be regulated with the greatest nicety.

Fig. 263.—Dipping tubes.


Fig. 264.—Glass syringe.

In dealing with minute aquatic objects, and in a great variety of other manipulations, *a small glass syringe* of the pattern represented in fig. 264, and of about double the dimensions, will be found extremely convenient. When this is firmly held between the fore and middle fingers, and the thumb is inserted into the ring at the summit of the piston-rod, such complete command is gained over the piston that its motion may be regulated with the greatest nicety; and thus minute quantities of fluid may be removed or added in the various operations which have to be performed in the preparation and mounting of objects; or any minute object may be selected (by the aid of the simple microscope, if necessary) from amongst a number in the same drop, and transferred to a separate slip. A set of such syringes, with points drawn to different degrees of fineness, and bent to different curvatures, will be found to be among the most useful 'tools' that the working microscopist can have at his command. It will also be found

if a dipping tube with a glass bulb have an indiarubber hollow
or teat attached to the top of it, it will act, for the majority of
oses, as well as a syringe.

orceps.—Another instrument so indispensable to the microscopist
be commonly considered an appendage to the microscope is the
ps for taking up minute objects; many forms of this have been
ed, of which one of the most convenient is represented in fig. 265,
mething less than the actual size. As the forceps, in marine re-
hes, have continually to be plunged into sea-water, it is better
they should be made of brass or of german silver than of steel,
the latter rusts far more readily; and as they are not intended
dissecting forceps) to take a firm grasp of the object, but merely
old it, they may be made very light, and their spring portion



Fig. 265.

ler. As it is essential, however, to their utility that their
s should meet accurately, it is well that one of the blades should
rnished with a guide-pin passing through a hole in the other.

Most microscopists have at some time experienced the danger
is imminent to their instruments and mountings when exhibit
lelicate objects with high power in mixed assemblies, arising
the inadvertency or want of knowledge of some visitor, who
do terrible mischief by innocently using the coarse adjustment.
rs. Ross made an arrangement by which the coarse adjustment
l be 'locked' at a given point: but an equally useful, and simpler
od was long ago devised by Messrs. Powell and Lealand, who
a deep ring, as is shown in fig. 266: this ring has two pins and
ew projecting inwards. When the screw
ithdrawn the rings can be slipped over
milled heads of the coarse adjustment,
by screwing the small screw 'home' the
cannot be withdrawn; but as they are
upon the milled heads, the latter can-
be brought into action: the rings simply
lve upon the heads without bringing
into play.

Other forms of the same appliance have
made by this firm; and Messrs. Beck
made these rings with slight modifica-
s more recently. They are the most
ent means of counteracting the danger
lent on public exhibition of delicate
cts under high powers.

Fig. 266.—Powell and Lealand's protecting ring for coarse adjustment.

The foregoing constitute, it is believed, all the most important
s of apparatus which can be considered in the light of accessories
he microscope. Those which have been contrived to afford
ities for the preparation and mounting of objects will be de-
ed in a future chapter (Chapter VI.).

CHAPTER V

OBJECTIVES, EYE-PIECES, THE APERTOMETER

It is manifest that everything in the form and construction as well as in the nature of the optical and mechanical accessories of the microscope, exists for, and to make more efficient, the special work of the *objective*, or image-forming lens combination, which constitutes the basis of the optical properties of this instrument.

The development of the modern objective, as we have already seen, has been very gradual; but there are definite epochs of very marked and important improvement. Our aim in the study of objectives is practical, not antiquarian, and we may avoid elaborate researches on the subject of *non-achromatic lenses*, and *reflecting speculæ*, which have been sufficiently indicated in the third chapter of this volume. We may also pass over the earlier attempts at achromatism; *the true history of the modern objective begins from the time that its achromatism had been finally worked out.*

The first movement of a definite character towards this object was made, it has been recently shown,[1] so early as 1808 to 1811 by Bernardino Marzoli, who was Curator of the Physical Laboratory of the Lyceum of Brescia. Mr. Mayall discovered a reference to this effort to make achromatic lenses, and through the courtesy of the President of the Athenæum of Brescia discovered that Marzoli was an amateur optician, and that he had taken deep interest in the application of achromatism to the microscope, and that a paper of his on the subject had been published in the 'Commentarj' for the year 1808, and that he had exhibited his achromatic objectives at Milan in 1811 and obtained the award of a silver medal for their merits under the authority of the Istituto Reale delle Scienze of that city. One of these objectives was found to have been 'religiously preserved,' and was generously presented in 1890 to the Royal Microscopical Society of London. With it was forwarded the 'Processo Verbale,' or official record of the awards, notifying Marzoli's exhibits and the award of a silver medal, and the actual *diploma*, dated August 20, 1811, signed by the Italian Minister of the Interior.

Marzoli's objective was a cemented combination, having the plane side of the flint presented to the object; and if this was a part of the intended construction, of which there appears small room for doubt, Marzoli preceded Chevalier in this, as we shall subsequently see, very practical improvement.

[1] *Journ. Roy. Mic. Soc.* 1890, p. 420.

It has been, however, customary to accredit the first practicable attempts to achromatise object-glasses to M. Selligues. In 1823 this optician was the first known in France to superimpose two, three, or four achromatised plano-convex 'doublets,' that is to say, pairs of lenses. These objectives had their convex surfaces presented to the object, which gave them four times as much spherical aberration as would have been the case had their positions been reversed,[1] and, as we have just seen, Marzoli reversed them. This necessitated an excessive reduction of the apertures, which, nevertheless, still too manifestly displayed an obtrusive aberration. Still the conception of an achromatised combination had been embodied in an initial manner. In 1825 M. Chevalier perceived the exact nature of the mistake made by M. Selligues, and made the lenses of less focal length and more achromatic, and inverted them, placing the plane side of the flint towards the object.

It is somewhat important, as it is interesting, to note that the idea of the superposition of a combination of lenses did not originate from theoretical considerations of the optical principles involved. It is scarcely conceivable that where there was manifest ignorance of the position of a plano-convex lens for least spherical aberration (a principle now thoroughly understood) there could have been insight enough either to detect the presence of the two aplanatic foci or to discover a method of balancing them by inductive reasoning. Everything in the history points to happy accident as the primal step in achromatised objectives, and this, with very high probability, applies to Marzoli's work as to that of Chevalier.

The form of three superimposed similar achromatic doublets is precisely the combination of the French 'buttons,' which have been sold in thousands until quite recently, many of them being mounted as English objectives.

At the suggestion of Dr. Goring, Mr. Tully, in this country, without any knowledge of what was being done on the Continent, made an achromatic objective in 1824. This was a single combination, being an achromatic uncemented triplet. It was, in fact, a miniature telescope object-glass, and is illustrated in fig. 267. Two lenses made on this principle by Tully, having $\frac{4}{10}$ and $\frac{2}{10}$ foci, were found in practice too thick, and in many ways imperfect; and he was induced to make another single triplet of $\frac{9}{10}$ focus and 18° aperture, and its performance was said to be nearly equal to that of the $\frac{2}{10}$.



FIG. 267.—Tully's achromatic triples.

Subsequently a doublet was placed in front of a similar triplet of somewhat shorter focus, forming a double combination objective of 38° aperture. This was pronounced to be a great advance upon all preceding combinations, even those which had been produced upon the Continent.

A note of Lister's at this time upon the objectives of Chevalier is of interest. He found them much stopped down, and, in one

[1] Chapter I.

instance, he opened the stop and improved the effect. Lister says: 'The French optician knows nothing of the value of aperture, but he has shown us that fine performance is not confined to triple objectives; and in successfully combining two achromatics, he has given an important hint -probably without being himself acquainted with its worth—that I hope will lead to the acquisition of a penetrating[1] power greater than could ever be reached with one alone.'



Fig. 268.—The two aplanatic foci of an optical combination.

At this time Professor Amici, of Modena, one of the leading minds who assisted in giving its form to the modern microscope, had been baffled by the difficulties presented by the problem of achromatism, and had laid it aside in favour of the reflecting microscope, but he now returned to the practical reconsideration of the production of an achromatic lens. As a result he appears to have constructed objectives of greater aperture than those of Chevalier. He visited London in 1827, and brought with him specimens of his work, which produced a most favourable impression, and subsequently he made an objective of ¼-inch focus.

Meantime, in this country, Mr. Lister brought about an important epoch in the evolution of the achromatic object-glass by the discovery of the two aplanatic foci of a combination. It had occupied his mind for several years, but in January 1830 a very important paper was read to, and published by, the Royal Society, written by him, in which he points out how the aberrations of one doublet may be neutralised by a second.

As the basis of a microscopic objective, he considers it eminently desirable that the flint lens shall be plano-concave, and that it shall be joined by a permanent cement to the convex lens.

For an achromatic object-glass so constructed he made the general inference that it will have on one side of it two foci in its axis, for the rays proceeding from which the spherical aberration will be truly corrected at a moderate aperture; that for the space between these two points its spherical aberration will be over-corrected, and beyond them either way under-corrected.

Thus, let *a*, *b*, fig. 268, represent such an object-glass, and be roughly considered as a plano-convex lens, with a curve, *a c b*, running through it, at which the spherical and chromatic errors are corrected which are generated at the two outer surfaces, and let the glass be thus free from aberration for rays, *f*, *d*, *e*, *g*, issuing from the radiant point, *f*, *h e* being a perpendicular to the convex

[1] 'Penetrating' meant 'resolving' power in those days; he alludes, therefore, to increase of aperture.

ver-corrected. But if f still approaches the glass, the
incidence continues to increase with the increasing diver-
the ray, till it will exceed that of emergence, which has in
while been diminishing, and at length the spherical error
by them will recover its original proportion to the oppo-
of the curve of correction. When f has reached this point
ich the angle of incidence does not exceed that of emergence
as it had at first come short of it) the rays again pass
free from spherical aberration.

e carried hence towards the glass, or outwards from its
place, the angle of incidence in the former case, or of
e in the latter, becomes disproportionately effective, and
y the aberration exceeds the correction.

far Lister's discoveries were affected by Amici's work it is
impossible to say; there can be but little doubt that some
is due to it, but it is equally clear that a profound know-
he optics of that time was the only foundation upon which
in Lister's paper could have been built. He was a man of
n and an enthusiast, and it was inevitable that he should
werful influence upon the early history of the optics of the
e. This is the more certain when we remember how few
men at that time who knew in any practical sense what a
e was; and we find that in 1831, being unable to find any
who cared to experiment sufficiently, Lister taught himself
lens-grinding, and he made an objective whose front was
is pair, with a triple middle combination, and the back a
vex doublet. He declared this to be the best lens of its
e time, and it had a working distance of ·11.

f the immediate consequences of the publication of Lister's
the rapid production by professional opticians of achromatic
. The data supplied by Lister proved to be of the highest
he actual production of these, and the progress of improve-

be 0·18 mm. thick, the correctional collar should be set to the division marked 0·18.

In England, on the contrary, the divisions are entirely empirical, so that the operator has to discover for himself the proper adjustment. It is not to be supposed, however, that the English method is unscientific, for when an operator becomes expert he would never for an instant think of adjusting by any other indication than that afforded by his own eye and experience. This is a very important point because the interpretation of structure, to a great extent, depends on accurate adjustment of the objective, and it would be folly to suppose that an eminent observer would surrender his judgment to the predetermination of theory embodied in what must be the imperfections in even the most conscientious and thorough work which gives a practical form to such theory. In fact, it is the test of accurate manipulation that, however the collar correction be disturbed, the microscopist will, in getting a critical image of the same object, always, by the quality of the image he obtains, bring the correction to within the merest fraction of the same position, although the correction collar and its divisions are never looked at until the desired image is obtained.

The fact that the over-correction caused by the cover-glass was discovered in England, and that means were at once found for its correction, while no similar steps were taken on the Continent, is a sufficient evidence of the advanced position of this country in practical optics at that time.

This subject of under- and over-correction is one of large importance, and it may be well at this point to enable the tiro to clearly understand, by evidence, its nature, although *what* it is has been fully shown in Chapter I. Take a single lens, the field-lens of a Huyghenian eye-piece will serve admirably, and hold it a couple of yards from a lamp flame; the rays passing through the *peripheral* portion of the lens will be found by experiment with a card to be brought to a focus *at a point on the axis nearer the lens than those passing through the centre*. This is *under-correction*. The same experiment should be repeated with the plane side and the convex side of the lens alternately turned to the flame. In the former case, when the image of the flame is at its best focus, it will be surrounded by a coma, and even the portion of the flame which is in focus will lack brightness. But with the *convex side towards the flame* it will be found that in the image on the card the coma is greatly reduced, and the image of the flame brightened. The reason for this is, as already stated, that the spherical aberration is four times as great when the convex side of the lens is towards the card.

The practice of these simple tests will be most instructive to those unfamiliar with the optical principles on which an objective is constructed. They make plain that an *over-corrected lens is one which brings its peripheral rays to a longer focus than its central*. But a cover-glass produces over-correction, therefore the means employed to neutralise the error is by the under-correction of the objective. If, however, the objective employed should be unpro-

l with such means of correction, the eye-piece must be brought
r the objective, which will effect the same result.[1]
till confining our consideration to the year 1837, we find that a
er improvement was made by Lister, who employed a triple
combination. This consisted of two crown plano-convexes with
t plano-concave between them. The result of this was the
ase of the aperture of an inch-focus objective to 22°.
n illustration of the mode of construction of
lenses is given in fig. 271, which is drawn
an early ½-inch objective by Andrew Ross,
ig bayonet-catch correction adjustment. In
a ½-inch of 44°, a ¼-inch of 63°, and a ⅛-inch
° were made upon the same lines.



Fig. 271.—An early ½-in. combination by A. Ross.

n 1841 the Royal Microscopical Society
ed a microscope from each of the before-
ioned leading opticians. The objectives
ied with these are still extant, represent-
rith moral certainty the very best work of
everal makers; they are consequently valu-
as reliable specimens of the best work of the period.
he objectives supplied by James Smith have the peculiarity of
separating lenses.
he lowest power is about 1¼-inch focus. When this is used
a diaphragm is slid over the front to limit the aperture, but
re unable to say what that limit was, since the diaphragm has
lost. By placing another front where the diaphragm would
been, the new combination becomes an $\frac{4}{10}$-inch focus, while
nother front may be substituted, making the objective a ½-inch
. This latter front consists of two pairs, and it is provided
a graduated screw-collar adjustment which separates these
, but the arrangement is of a very primitive order.
his object-glass will divide the podura marks in a milky field
a full cone, and the field is much curved.
here is also a separating 1¼-inch and ⅔-inch which is good,
the $\frac{4}{10}$-inch and the ½-inch may be considered fair.
he lenses supplied by Andrew Ross are a good 2-inch and a
1-inch, but we have seen a better than this of about the same
d.
ugh Powell supplied a 1-inch of good quality, and a ½, ¼, ⅛,
ch fairly good. The apertures of the ⅛ and the $\frac{1}{16}$-inch are
urse very low.
n the whole it may be said that the corrections are well
ced in the lower lenses, and the apertures moderate; but when
me to the higher powers it is the deficiency of aperture that
nes so oppressively apparent. In 1844 Amici made a ⅛-inch
tive of 112° and brought it to England. It was understood
extra dense flint was employed in the construction of this
tive; but this is perishable; and Mr. Ross altered slightly the
s of Amici's construction, and with ordinary flint succeeded

[1] 'Under-correction is also known as "positive aberration"; over-correction as
itive aberration.'

in extending the aperture of a $\frac{1}{8}$-inch objective to 85°, or ·68 N.A.; and a $\frac{1}{12}$-inch objective to 135°, or ·93 N.A. Of this latter it was affirmed that it was 'the largest angular pencil that could be passed through a microscope object-glass.'

In 1850 object-glasses were made with a *triple back combination*; these were attributed to Lister; but it is also affirmed that they were the previous device of Amici. It may well be a disputed point, for it is quite certain that this device brought the dry achromatic objective potentially to its highest perfection. The combination is illustrated in fig. 272, and under the conditions of its construction it may be well doubted if anything will ever surpass the results obtained by English opticians in achromatic objectives constructed with this triple front, double middle, and triple back combinations. It may be noticed that Tully's objective had a triple back, but it was not the result of intended construction; it was a fortunate combination the real value of which was neither understood nor appreciated, and as a consequence its existence was evanescent.



FIG. 272.—A triple-back combination by Lister (or Amici ?).

In this same year Wenham produced another modification of the achromatic objective of considerable value, but more to the manufacturer than the user of the microscope. It consisted of *a single front*; the combination is seen in fig. 273, which it will be seen is a simpler construction, but this did not affect in the least the price of the objectives produced. Subsequently, however, the form was adopted on the Continent for low-priced objectives, which led to a reduction of the cost of English objectives of the same construction.



FIG. 273.—A single-front combination by Wenham.

Manifestly, the single front lessened the risk of technical errors, but we have never been able yet to find a single front dry achromatic objective which has shown any superiority over a similar one possessing a triple front.

The single front employed with two combinations at the back was the form in which the celebrated *water-immersion objectives* of Powell and Lealand were made. It was by one of these that the striæ on *Amphipleura pellucida* were first resolved. Indeed, what is known as the *water-immersion system of objectives*, devised by Professor Amici, was the next advance upon the old form; but it was an advance the optical principles of which were certainly not at the time understood.

In Paris, Prazmowski and Hartnack brought these objectives to great perfection, and were enabled to take the premier place against all competitors at the exhibition of 1867. The next year, however, Powell and Lealand adopted the system, and in turn they distanced the Paris opticians and produced some of the finest objectives ever made. Their 'New Formula' water-immersions were made after the fine model of Tolles referred to below, and had a duplex front, a double middle, and a triple back. In 1877, when the water-

immersion system touched its highest point, apertures as great as 1·23 were reached; and in America, Spencer, Tolles, and Wales produced some extremely fine lenses of large aperture.

During the year 1869 Wenham experimented with and suggested[1] the employment of a *duplex front*; that is so say, a front combination made up of two uncorrected lenses in contradistinction to an achromatised pair. An illustration of the plan suggested is given in fig. 274, which hardly appears to us as a practicable form, and which certainly was never brought to perfection or put into practice.



Fig. 274.—A suggested combination by Wenham, 1869.

But in the month of August 1873 Tolles actually made, on wholly independent lines, a duplex front formula for a ¼-glycerine immersion of 110° balsam angle, which passed into the possession of the Army Medical Museum at Washington. There can be little doubt but this objective would have produced a much deeper impression but for the fact that it was in advance of its immediate time.

Tolles, as we have hinted above, used the duplex front in the construction of some of his immersion objectives, and was followed in this by the best English makers, and in the case of a celebrated ¼-inch, purchased by Mr. Crisp, Tolles was able to reach a balsam angle of 96°.

At the time that the water-immersion lenses were being constructed by rival opticians with increasing perfection the great theory of Professor Abbe concerning microscopic vision, the importance of diffraction spectra, and the relation of aperture to power[1] was entirely unknown. In the absence of this knowledge wholly mistaken value was attached to *power per se* in the objective.

With a focus as short as the $\frac{1}{25}$-inch, it was not uncommon to find apertures less than 1·2, while objectives of $\frac{1}{35}$, $\frac{1}{50}$, $\frac{1}{50}$, and even higher powers, were made with extremely reduced apertures. This was done in the interests of the common belief that 'power'—devoid of its suitable concurrent aperture—could do what was so keenly wanted.

This impression, however, was far from universally relied on; there were several earnest workers, who, without being able to explain, as Abbe subsequently did, why it was so, still urged the opticians, in the manufacture of every new power, especially the higher ones, to produce the largest possible amount of aperture; and the evidence of this is still to be found in the objectives they then succeeded in obtaining. But there can be no doubt that a reckless desire for magnifying power, all other considerations apart, greatly obtained; and the opticians were able to encourage it, for it is far easier to construct an objective of high power and low aperture than it is to make a low power with a large aperture.

Thus a ½-inch of 0·65 N.A. will be far more expensive and probably not as well corrected as ⅛ of 0·7 N.A. The ½-inch objective,

[1] *Monthly Micro. Journ.* vol. i. p. 172.

even if a good one, is sure to exhibit spherical aberration, while the ⅛ of low aperture will show many minute objects with considerable clearness, especially if a comparatively narrow illuminating cone be used.

This difference becomes still more conspicuous as the difference between aperture and power grows relatively greater, until we obtain ultimately an amplification more than useless from its utter inability, on account of deficiency of aperture, to grasp details.[1]

Up to 1874, however, there was an entire absence of knowledge, even on the part of the leaders in microscopic theory, art, and practice, as to the real optical principles that enabled us to see a microscopic image, and consequently to understand the essential requirements to be aimed at in the best form of microscope. But in 1877 Abbe's great diffraction theory of microscopic vision appeared, which has led to changes of incomparable value in the principles of construction of objectives and eye-pieces, and, as a consequence, has to some considerable extent given a new character to the entire instrument. Its promulgation has indeed inaugurated an entirely new epoch in the construction and use of the microscope.

The general character and the details of Abbe's theory are given in the second chapter of this treatise; but its practical bearing upon the theory and application of the optical part of the instrument were soon manifest; for in 1878 the *homogeneous system of immersion objectives*[2] *was introduced* as a logical outcome of the diffraction theory of microscopic vision. A formula for a ⅛-inch objective on this system was prepared by Abbe, to whom, we learn from himself, it had been suggested by Mr. J. W. Stephenson, of the Royal Microscopical Society.[3] It has been already shown[4] that the homogeneous system was so called because it employed the oil of cedar wood to unite the front lens of the objective to the cover-glass of the object, in the same way as water had been employed in the ordinary *immersion system*; but as there was a practical identity between the refractive and dispersive indices of the oil, and those of the crown glass of the front lens, the rays of light passed through what was essentially a homogeneous substance in their path across from the balsam-mounted object to the front lens; and a *homogeneous system* of objectives took the place of the previous water immersions.

This was the first great step in advance in optical construction and application following the theory of Abbe.

As often happens in matters of this kind, there had been an apparent anticipation of this system of lenses by Amici as far back as 1844; but it is very apparent that Amici employed the oil of aniseed without any clear knowledge of the principles involved in the homogeneous system; being wholly unaware of either the increase of aperture involved or the cause of it. But this cannot be said of Tolles, of New York. We have pointed out that as early as 1873 he made a $\frac{1}{10}$-inch, and subsequently in the same year a ¼-inch objective, each with a duplex front to work in soft balsam, and with a N.A. of 1·27. These objectives were examined by the late Dr.

[1] *Vide* Chapter II. [2] *Ibid.*
[3] P. 27; also *Journ. Roy. Microsc. Soc.* vol. ii. 1879, p. 257. [4] Chapter I.

Woodward, of the Army Medical Department, New York, and with that examination were allowed to cease. For Tolles as an original deviser of a practical homogeneous system this was unfortunate; for the actual introduction of the system in a form capable of universal application, and worked out in all its details in an entirely independent manner, we are wholly indebted to Abbe.

The principle was not nevertheless so readily and warmly adopted in England on its first introduction as might have been anticipated. This arose partly, however, from the fact that water immersions had been brought to so high a point of excellence by Messrs. Powell and Lealand that the early homogeneous objectives were not possessed of more aperture, and were not sensibly superior to the best immersions made in England.



Fig. 274.—Section of Powell and Lealand's water immersion objective.

The homogeneous objectives were made with duplex fronts and two double backs. A general diagram of their mode of construction is given in fig. 275.

So long as crown glass was employed in their manufacture, and the anterior front lens was a hemisphere, it appeared that N.A. 1·35 to 1·37 was the aperture limit they could be made to reach. Messrs. Powell and Lealand, however, *by making the anterior front lens of greater than a hemisphere* increased the aperture of a [illegible] to N.A. 1·52.

This front, from being greater than a hemisphere, presented difficulty in mounting; this was at first overcome by cementing its plane surface to a thin piece of glass which was then fixed in the metal. Eventually, however, this form of construction was changed by these makers in a very ingenious manner so as to avoid their entirely *inverted* the combination and accomplished the end in *making the front of flint*. By this means they obtained apertures which have not as yet been equalled by any other maker, reaching in a $\frac{1}{8}$, a $\frac{1}{12}$, and a $\frac{1}{16}$, a N.A. of 1·52, out of a theoretically possible aperture of 1·52. Professor Abbe has since it is true made an objective with a numerical aperture of 1·63, but this requires the objects to be mounted and studied in a medium of corresponding refractive index, and consequently, in the present state of our knowledge of the subject of media, not applicable to the investigation of ordinary organic structures—certainly not of living tissue.

These objectives fully occupied the microscopic world, when the most important epoch since the discovery and application of achromatism was inaugurated.

We have already pointed out in detail[1] that it was the great defect of the ordinary crown and flint achromatics that *two colours only could be combined* and that the other colours caused out of focus images, which appeared as fringes round the object. This was what was known as *the residuary secondary spectrum*.

In like manner, it has been shown that it was not possible in the flint and crown achromatic to combine two colours in the same

[1] Chapter I.

of the objective, so that if two given colours are combined in the intermediate zone, they will not be combined in the peripheral and the central portions of the objective.

These phenomena, it has been pointed out,[1] arise from what is known as the *irrationality of the spectrum*. To correct this we have seen that Drs. Abbe, Schott, and Zeiss directed their attention to the devising of vitreous compounds which should have their dispersive powers proportional to their refractive indices for the various parts of the spectrum. Only by these means could the outstanding errors of achromatism be corrected.

It is therefore a fact that the old flint and crown objectives, whether for the microscope, the telescope, or the photographic camera, are, strictly speaking, neither achromatic nor aplanatic.

Glass whose properties far more nearly approximated the theoretical requirements than any previously attainable having been manufactured by the Jena opticians,[2] Abbe was able to produce objectives entirely cleansed of the *secondary spectrum*. From calculations of a most elaborate and exhaustive kind made by Dr. Abbe, objectives are made by Zeiss which not only combine three parts of the spectrum instead of two, as formerly, but which are also aplanatic for two colours instead of for one. This higher stage of achromatism Abbe has called *apochromatism*.

A general plan of the construction of an apochromatic objective as made by Zeiss is shown in fig. 276, which, it will be understood, is diagrammatic, but sufficiently illustrates the elaborate corrections by which the perfect results given by these objectives are accomplished. But, in addition to their form of construction and the special optical glass of which they are composed, it is now known that they owe much of their high quality to the use of fluorite lenses amongst the combination. Fluorite is a mineral which has lower refractive and dispersive indices than any glass that has yet been composed, and therefore, by its introduction, the optician can reduce the spherical and chromatic aberrations greatly below that reached by achromatic combinations of the known type.



FIG. 276.—Diagram of apochromatic combination.

It is a somewhat depressing fact that fluorite is very difficult to procure in the clear condition needful for the optician, but from what we have seen the optician can do in the manufacture of glass, we may hope that an equivalent of this mineral in all optical qualities may be discovered.

The medium for mounting and immersion contact has, of course, to be of a corresponding refractive and dispersive index in all objectives of great aperture, and it is insisted by Abbe that the glass of which the mount is made, both slip and cover, must, when the limit of refraction by crown glass is passed by the objective, be of flint glass. This he presents as a *sine qud non* in the case of the new objective just made by the house of Zeiss, and a specimen of which has been generously given by the Firm to the Royal Microscopical Society. This glass has a numerical

[1] Chapter I. [2] Chapter II.

perture of 1·63; it is too early to criticise its qualities, but in subsequent chapter on the present state of our knowledge as to ie ultimate structure of diatoms, we are enabled to present the sults of some of the photo-micrographs produced by its means. ut it may be noted that very much will depend upon the N.A. of e illuminating cone which can be employed with it—not theoreti-lly, but practically.

On the whole, and for the purposes of practical biological inves-gation, it is to the dry apochromatics that we are most indebted, d from their use we shall derive the largest benefit.

As no subject is really of more importance than a clear under-nding of the difference of action of chromatic, achromatic, and ochromatic lenses, we venture to present a diagrammatic illustra-



1. 2. 3.

FIG. 277.

on, which, while not strictly accurate, will carry with it no error, s a popular illustration of this important subject.

In fig. 277, 1, 2, 3, we have representations, as truly as they can e drawn, of *zones of equal light*; that is to say, the peripheral zone ill transmit an amount of light equal to that given either by the termediate zone or the central circle. Let them therefore be lled *equilucent* zones.

If we assign a numerical value for the visual intensity of the hole spectrum, say 100, made up of the following parts, viz.

Red	15
Orange yellow	40
Yellow green	30
Blue	15

en if in any one of the equilucent zones the whole spectrum is ought to a focus, we shall have for that zone 100 as its effective value.

But the entire object-glass is divided, as in the diagram, into ree equilucent zones; consequently 300 will represent the value of e whole lens, provided the whole of the spectrum is brought to the me focus.

By referring to the diagrams we see that in a non-achromatic ns (fig. 277, 3) we shall get only 40, because only one part of the ectrum is brought to the focus in its intermediate zone; and as herical aberration causes the light which passes through the other

zones to be brought to *other foci*, they for all practical purposes might be stopped out.

In the achromatic lens we have (fig. 277, 1) in the intermediate zone two parts of the spectrum combined, as 40 + 30 = 70, and one in each of the other zones *is also brought to the same focus*, say 30 in the outer zone, and 40 in the centre circle. The result is that the whole achromatic lens gives a total of light on the principle stated above of 30 + 70 + 40 = 140. In the apochromatic system, however (fig. 277, 2) we find in the intermediate zone three parts of the spectrum united; that is to say, 40 + 30 + 15 = 85; and two in each of the others, say, 40 + 30 = 70. Thus an apochromatic objective will give 70 + 85 + 70 = 225.

Recalling the suppositions we have made for the purpose of this graphic presentation of a difficult subject, it will be seen that a non-achromatic objective would give 40, an achromatic 140, and an apochromatic 225, out of a possible total of 300.

This illustration might be exceeded in severe accuracy, but scarcely in simplicity, and it sufficiently explains from this point of view alone the vast gain of the apochromatic system.

It is interesting to note that, while the microscope in its earlier form took its powerful position by borrowing achromatism from the telescope, it has now led the way to the apochromatised state, which without doubt it will be the work of the optician in constructing the telescope of the immediate future to follow.

We would beg the reader to bear in mind in the purchase of objectives that, whilst the vitreous compounds with which Abbe's beautiful objectives are constructed are now accessible to all opticians, and whilst without these Abbe's objectives could never have been constructed, yet *it does not by any means follow that because an objective is* MADE *with* the Abbe-Schott glass *it is therefore apochromatic; the secondary spectrum must be removed, and the spherico-chromatic aberration balanced*, or it is 'apochromatic' only by misnomer. It is another feature of these objectives, which it is important to note, that they are so constructed that the upper focal points of all the objectives *lie in one plane*. Now as the lower focal points of the eye-pieces are also in one plane, it follows that, whatever eye-piece or whatever objective is used, the optical tube-length will remain the same.

Professor Abbe has found [1] that in the wide-aperture objective of high power there is an outstanding error which there are no means of removing in the objective alone, but, as we have already explained, this is left to be balanced by an over-corrected eye-piece. As this peculiarity pertains only to the higher powers, a corresponding error had to be intentionally introduced into the lower powers in order that the same over-corrected eye-pieces might be available for use with them.

It appears worthy of note in this relation that one of the best forms for the combination of three lenses is that known as Steinheil's formula, which consists of a bi-convex lens encased in two concavo-convex lenses. It will be observed by reference to the figure illustrat-

[1] Chapter II.

g the apochromatic lens construction (fig. 276) that this is largely ade use of. In some instances the encasing lenses possess sufficient nsity with regard to the central bi-convex lens to altogether over-ower it, the result being a bi-convex triple with a negative focus.

It is another distinctive feature of the 3 mm. objective that it s a *triplex front*; thus Zeiss's 3 mm. (= $\frac{1}{8}$-inch focus) has the ors from three uncorrected lenses balanced by two triple backs, nine lenses taken together.

The foci of the set of apochromatic lenses now made by Zeiss integral divisions of what may be termed a unit lens of 24 mm.; he chooses as a means of avoiding the inconveniences inseparable m the use of the decimal system.[1] The unit lens is therefore a tle higher than 1 inch in power. In the series of dry lenses there two powers of the same aperture. Thus 24 mm. and 16 mm., rresponding to English 1 inch and $\frac{2}{3}$ inch, each has an aperture ·3; a 12 mm. and 8 mm. = English $\frac{1}{2}$ inch, and $\frac{1}{3}$ inch, have ch an aperture of ·65; while a 6 mm. and a 4 mm. = $\frac{1}{4}$ inch and inch, have both an aperture of ·95.

There are also water-immersions; a 2·5 mm. = $\frac{1}{10}$ inch, with .A., 1·25, and two oil-immersions respectively 3 mm. and 2 mm. $\frac{1}{8}$ inch and $\frac{1}{12}$ inch, both being made either with 1·3 or 4 N.A.

Apart from these, intended to be used for photographic pur-ses without an eye-piece, is a 70 mm. = a 3-inch, also a 35 mm. 1$\frac{1}{2}$-inch objective.

With the exception of the 6 mm., 4 mm., and 2·5 mm. objectives hich have the screw-collar adjustment, this series have rigid mounts, orrection being secured by alteration of the tube-length.

The performance of these lenses, as they are now made, is of the ery highest order. They present to the most experienced eye unsur-assed images. They are corrected with a delicate perfection which ly this system, coupled with technical execution of the first order, n possibly be made to produce. The optical polish, the centring, e setting, and the brasswork certainly have never been surpassed.

It is a matter also worthy of note that Zeiss's apochromatic ries of objectives *are true to their designations as powers*. The -inch is such, and not a $\frac{4}{10}$-inch designated $\frac{1}{2}$-inch. This was ually true of the early achromatics. A. Ross produced a $\frac{1}{4}$-inch der that name. One now before us, made fifty years ago, has an itial power of 41; and that of a $\frac{1}{4}$-inch has an initial power of 21. ut modern achromatics of fair aperture are always greatly in cess of their designated power; $\frac{2}{3}$ are nearly $\frac{1}{2}$-inch. A $\frac{1}{4}$-inch er 40° has an initial power of 25, and is a $\frac{4}{10}$-inch; $\frac{4}{10}$-inch jectives are in reality $\frac{1}{4}$-inch; and $\frac{1}{4}$-inch objectives of 90° and pwards have initial powers of 50 instead of 40, which they should ve, so that they are in reality $\frac{1}{5}$ths; some in fact—by no means ncommon—have an initial power of 60, and are actually $\frac{1}{6}$th-inch jectives.

[1] Although the foci of the lenses are expressed in integers, with the single exception of the water immersion 2·5 mm., there are inconvenient decimal fractions in the itial magnifying power of all the series except those of 2·5 and 2 mm. focus.

This is explicable enough from the maker's point of view; it is far easier to put *power* into an object-glass *than aperture*. It is easier to make a $\frac{1}{8}$-inch of 100° than a $\frac{1}{4}$ with 100°; the result is that low powers with suitably wide apertures are costly.

In the Zeiss apochromatic series of objectives the 24 mm. of ·3 N.A. and 12 mm. of ·65 N.A. may be considered as lenses of the very highest order; the relation of their aperture to their power is such that everything which a keen and trained eye is capable of taking cognisance of *is resolved when the objective is yielding a magnification equal to twelve times its initial power*; for this purpose an objective must have 0·26 N.A. for each hundred diameters of *combined* magnification. Under these conditions an object is seen in the most perfect manner possible.

It may be well for the student to prove this, which may be readily done.

Take a suitable object, such as a well-prepared proboscis of a blow-fly, and examine it under critical illumination with the 24 mm. ·3 N.A. (= 1 inch) objective, and a 12 compensating eye-piece. Note with close attention every particular of the image: the resolution of the points of the minute hairs, the form of the edges of the cut suctorial tubes, the extent of the surface taken into the 'field,' and the relation of all the parts to the whole.

Now change the objective for the 16 mm. ·3 N.A. (= $\frac{2}{3}$, but with the same aperture). Nothing more is to be seen; the most dexterous manipulation cannot bring out a single fresh detail; the resolution is in no sense carried farther; the cut suctorial tubes were in fact, in our judgment, better seen with a lower power, while with it all of course a smaller extent of the object occupies the 'field.'

It can in fact be scarcely doubted that the picture presented by the $\frac{2}{3}$ is a distinct retrogression in every sense compared with that presented by the 1 inch when both are equally well made and have equal apertures, viz. ·3. But beyond all this, *whatever may be done* by the 16 mm. ·3 N.A. can be accomplished in an equally satisfactory manner by removing the 12 eye-piece and replacing it with practically no other alteration by an 18 eye-piece; and still higher results can be obtained without the slightest detriment to the image by using an eye-piece of 27.

Not less interesting and convincing will it be to examine the same object with a 12 mm. ·65 N.A. (= $\frac{1}{2}$-inch), and an A Zeiss achromatic of ·20 N.A. (= $\frac{2}{3}$rds inch) using a 12 eye-piece. Those who may still retain some conviction as to the value of 'low-angled glasses to secure penetration' can want no further evidence than such a simple experiment affords of its entire fallacy.

For those who prefer it a true histological object may be selected. We choose a portion of a frog's bladder treated with nitrate of silver, in which are some convoluted vessels, enclosed in a muscular sheath which had contracted.

This object is presented by photo-micrograph in figs. 7 and 8 of the frontispiece. In fig. 7 the vessel in the frog's bladder is seen by a Zeiss A ·2 N.A., magnified 140 diameters. The object of the photograph is to expose the fallacy which underlies the generally

accepted statement that low-angled glasses are the most suitable for histological purposes. The assumption is founded on the fact that the penetration of a lens varies inversely as its aperture, and it is taken for granted that 'depth of focus' will be obtained, not to be secured by large apertures, and therefore it is taken for granted that we are enabled to see into the structure of tissues.

In examining the illustration (which will with advantage permit the use of a lens) it will be seen that scarcely an endothelium cell can be clearly seen. A sharp outline is nowhere manifest, because the image of one cell is confused with the outlines of others upon which it is superposed. We have seen that there is no perspective proper in a microscopic image; therefore it is better to use high apertures in objectives, and obtain a clear view of one plane at one time and train the mind to appreciate perspective by means of focal adjustment.

It will be admitted that no clear idea of what an endothelium cell is can be obtained from fig. 7.

But fig. 8 (frontispiece) represents the same structure slightly less magnified (× 138) by means of an apochromatic $\frac{1}{2}$ N.A. ·65. Here only the upper surface of the tube is seen; but the endothelium cells can be clearly traced, and a sharp definition is given to every cell. The circular elastic tissue is also displayed, while the whole image has an increased sharpness and perfection.

Thus, with the objective (A ·20 N.A. = $\frac{2}{3}$rds inch) of lower aperture the endothelium cells *can be seen*; but when the image is compared with that of the objective of wider aperture (·65 N.A.), the former image is found to be dim and ill-defined. The muscular sheath is so ill-defined that it would not be noticed at all if it had not been clearly revealed by the objective of wider aperture. But, on the other hand, the objective of greater aperture not only shows the muscular sheath, but it also shows the elongated nuclei of the muscle cells; and at the same time brings out the convoluted vessels lying in the muscular sheath as plainly as if it were an object of sufficient dimensions to lie upon the table appealing to the unaided eye.

We have pointed out in the proper place,[1] that although 'penetrating power' varies inversely as the numerical aperture, it also varies inversely as the *square* of the power.

Now, from what we know of histological teaching in this country, we do not hesitate to say that a histologist would not have attempted to examine the above object with even a Zeiss A objective. He would have advised the use of '*the* $\frac{1}{4}$-inch,' of perhaps ·65 aperture; but by so doing he would have secured only one-third of the penetrating power *qud* aperture and one-seventh of the penetrating power *qud* power.

It is manifest, then, that pursuing this course in the histological laboratory defeats the end sought, and which it is so desirable to attain.

It is absolutely unwise to use a higher *power* than is needful. A $\frac{1}{4}$-inch where a $\frac{1}{2}$-inch would answer involves loss in many ways,

[1] Chapter I.

and would never be resorted to *if the aperture of the lenses employed were as great as the power used legitimately permitted.*[1]

A given structure to be seen at all must have a given aperture; to obtain this, as objectives now made for laboratory purposes run, they are obliged to use *too high a power*. The result is that in seeking to avoid what is accounted the loss of 'penetrating power' at an inverse ratio to the aperture, it is forgotten that we are losing it inversely as the *square* of the power!

Moreover, the two apochromatic objectives we have already referred to as test lenses are equally able to show the value of apochromatism, not so much on account of the removal of the secondary spectrum as for the reduction of the aberrations dependent on the irrationality of the spectrum in ordinary achromatics.

Use the 12 mm. ·65 N.A. objective. Place a diatom in balsam in the focus of it on a dark ground; the diatom will shine with a silvery whiteness, and the image will be wholly free from fog.

Now take one of the best achromatics obtainable of ½-inch focus of 80° (almost certainly a $\frac{4}{10}$ in power) and examine the same diatom in the same circumstances; it will be bathed in fog. If, however, the achromatic objective is an exceptionally good one, and we reduce its aperture to 60°, we shall get a fair picture of the diatom—one indeed that was considered critical until that with the apochromatic was seen. But in comparison it is dull and yellowish. From which it follows that an exceptionally fine achromatic $\frac{4}{10}$-inch of 60° or ·5 N.A. will not suffer comparison of the image it yields with that of an apochromatic ½-inch of ·65 N.A.

Speaking generally on the whole question, then, it would be the utmost folly for histologists or opticians to shut their eyes to the magnificent character of the series of dry apochromatics of Zeiss, ranging from 1 inch (24 mm.) to ⅛-inch (4 mm. ·95 N.A.), and more recently ⅛-inch. They are the most perfect and efficient series of objectives ever placed in the hands of the worker; and unless English lenses on a truly apochromatic principle and equal quality are produced, it must be to the detriment of either the opticians or the workers of this country.

Nor need it be supposed that the production of objectives approximate to these must be *costly*; great steps have been taken lately in the reduction of their cost. A remarkable instance of this is provided by the production of two objectives by E. Leitz, of Germany; they have lately come into our hands; they are but semi-apochromatic. The one is low, having an initial power of 14, with an aperture of 30°; the other is practically a ⅛-inch of ·88 N.A. The low power has surpassed every achromatic of its kind we have met with, and the higher power can, without hesitancy, be spoken of as an exceedingly good glass; nevertheless the price of these two objectives is *together* less than the price charged for the lower power, if made in England on *achromatic* principles, would certainly be! Yet Reichert has even surpassed this, and we feel that we shall be doing a great service to students of small means in calling their attention to the following remarkable and low-priced objectives: Leitz No. 2

[1] Chapter II.

1¼) N.A. ·2 ; Leitz No. 3 (less than ⅔rds) N.A. ·26 ; Reichert No. 6 ⅔th) N.A. ·81 ; Reichert 18ᵇ (1/12th) N.A. 1·24. The Reichert No. 6 is a lens whose low price is astonishing, when the perfection of the performance of all that we have seen is taken into account, for it is the rival of even true apochromatics. This fact is of importance to the medical student and to the opticians generally. By apochromatised objectives of the highest order the work of present and future microscopy will be done—that is inevitable. To thoroughly understand what its very best results, theoretically and practically, must be becomes the imperative aim of the optician who would be abreast of the direct wants of his time ; and to produce the nearest to these in objectives and eye-pieces at the lowest possible price is, apart from all other issues, to be a direct benefactor of true science.

The Eye-piece.—The eye-piece, sometimes called the *ocular*, is an optical combination, the purpose of which is so to refract the diverging pencils of rays which form the real object-image that they may all arrive at the pupil of the observer's eye. They have also to form a virtual image of the real image which is presented to them as the object. For this purpose a combination is indispensable, but this may be varied. There are ordinary and special eye-pieces. Those in ordinary use separate into two divisions : (1) positive eye-pieces and (2) negative eye-pieces. These are easily distinguished : with a *positive* eye-piece we can obtain a *virtual image* of an object by using it as a simple microscope, because its focus is exterior to itself. This is not easy with the *negative eye-piece*, because its focus is within itself.

The eye-piece in common use is negative, and is generally known as Huyghens', and sometimes as Campani's. Hooke appears to have been the first (1665) to have applied the field-lens to the eye-lens of the microscope, although there is a high probability that such a lens was first used by Monconys ; but how far he was indebted for this to the compound eye-piece attributed to Huyghens cannot now be determined.

This instrument as commonly used consists of an eye-lens and a field-lens, each being plano-convex, having their convex sides towards the object, their foci being in the ratio of 3 : 1, and the distance between them being equal to half the sum of their focal lengths, a diaphragm being placed in the focus of the eye-lens. The general form of a Huyghenian eye-piece is shown in longitudinal section in fig. 278. This makes a very convenient form of eye-piece of 5 and 10 magnifying power ; but when the power much exceeds this last amount, the eye-lens becomes of deep curvature and short focus, so that the eye must be placed uncomfortably near the eye-lens. This, however, is its chief defect, and it may fairly be considered the best ordinary eye-piece.

Perhaps the best form of the Huyghenian eye-piece is that devised by Sir G. B. Airy : its field-glass is a meniscus with radii 11 : 4 the convexity towards the object-glass. The eye-lens is a crossed convex 6 : 1 the flatter side to the eye, the distance between them being twice the focus of the eye-lens, focus of field-

lens being three times that of the eye-lens, the diaphragm being in focus.[1]

Another negative eye-piece is that known as the *Kellner*, or *orthoscopic*. This consists of a bi-convex field-glass, and an achromatic doublet meniscus (bi-convex and bi-concave) eye-lens. A vertical section of one so constructed is seen in fig. 279. These eye-pieces usually magnify ten times, and the advantage they are supposed to give consists in a large field of view; but they are not good in practice for this very reason, they take in a field of view greater than the

FIG. 278.—Huyghenian eye-piece.

FIG. 279.—Kellner eye-piece.

objective can stand, and as a rule even the centre of the field will not bear comparison in sharpness with the Huyghenian form.

It is a suggestion of Mr. Nelson's that a crossed convex 6 : 1 field-lens and a meniscus and concave-convex doublet eye-lens might work well for this form of eye-piece.

Positive Eye-pieces.—In the early compound microscopes the eye-pieces were all positive; that is to say, they consisted of a single bi-convex eye-lens and no field-glass. The definition with this must have been most imperfect; the addition of a field-lens, though it were a bi-convex, not in the correct ratio of focus, nor the theoretically best distance, must have been considered a great advance.



FIG. 280.

In this way matters rested, however, until the theoretically perfect Huyghenian form was devised. Nothing has yet displaced this combination or successfully altered its formula. Object-glasses have been used as eye-pieces and all forms of *loups* or simple microscopic lenses have been employed for the same purpose. Solid eye-pieces have also been used both in England and America, but with no results that surpassed a well-made Huyghenian combination; but the best form of all of the combinations which have been tried by us as positive single eye-pieces are the Steinheil *triple loups*; a section of one of these is

[1] It is a curious fact that in practice the usual formula for the Huyghenian eye-piece is radius of field-lens twice that of eye-lens, and the distance between them equal to half the sum of their foci.

en in fig. 280. But a positive eye-piece was devised by Ramsden, nsisting of two plano-convex lenses of equal foci; the distance is to e equal to two-thirds the focal length of one. The diaphragm will course be exterior.

Abbe's Compensating Eye-pieces.—We have already given a neral description of the nature and action in connection with the ochromatic objectives of this form of eye-piece.[1] In the section ove on objectives we have referred to the fact that these eye-pieces e *over-corrected*; this may be easily seen by observing the colour the edge of the diaphragm, which is an orange yellow. If we mpare this with the colour in the same position with a Huyghenian e-piece, this will be blue, being seen through the simple uncorrected e-lens.

There are three kinds of compensating eye-piece as designed by bbe. These are

1. Searcher eye-pieces
2. Working „
3. Projection „

1. *The searcher* forms are negatives of very low power, intended ly for the purpose of finding an object; they consist of a single ld-lens and a doublet eye-lens.

The working forms are both positive and negative. The 4 power a negative form resembling the searcher in that for the short be; the eye-piece for the long tube has a triplet eye-lens; but ie remainder, viz. 8, 12, 18, and 27, when first introduced, were all sitives; they were subsequently, however, changed for negatives. Having used both, we are glad to learn that the positives are being gain introduced. It may be convenient to have the 8 a negative ike the 4, but with regard to the 12, 18, 27, it is important that hey should be positives.

These positive forms are on a totally new plan, being composed f a triple with a single plano-convex over it; the diaphragm is, f course, exterior to the lens. With these the definition is of the nest quality throughout the field; they present the admirable ndition that with the deeper powers the proper position of the eye further from the eye-lens, which makes it as easy to use an eye-iece of as great a power as 18 or 27 as one of 4 or 8.

The field of these eye-pieces has, as we believe, been very wisely mited to five or six inches. The attempt on the part of English opti-ians to give to our eye-pieces fields reaching eighteen inches is an error. microscopic objective with the lowest aperture has the field greatly excess of any other optical instrument; and to deal with such centric pencils as must be engaged by an eye-piece with a field f eighteen inches is a strain not justified by what is gained.

The powers of the working eye-pieces are also arranged in a new ay. The multiplying powers for the long tube are 4, 8, 12, 18, 27; will be seen at once, therefore, that they bear no definite ratio to ie another, and if we seek to simplify the focal lengths, we are by ie employment of the metrical system confronted with decimal

[1] Chapter I., p. 33.

fractions. But without further elaboration it may be well to say that 12 is the most generally useful eye-piece, and if only one compensating eye-piece is to be selected, there can be no question, from a practical point of view, but this is the best to employ. The 4 is too low, and the 27 is too high for general purposes, and the 8 and 18 are sufficiently near the 12 to give the latter the advantage in general work. We cannot, however, refrain from the expression of the opinion that a series of 5, 10, 20, or 6, 12, 24 powers would be in many senses more useful, and would offer facilities in application not secured by the series of Abbe now in use.

It may be well to give further emphasis to the fact that this construction of eye piece is not only essential to the proper work of apochromatic objectives, but they greatly enhance the images given by ordinary achromatic lenses ; and it may be noted that the 8, 12, and 18 eye-pieces for the short tube are identical with 12, 18, 27 for the long tube.

The projection eye-piece is mainly intended for photo-micrography, but it is also useful for drawing and exhibition purposes. It is a negative, with a single field-lens and a triple projection-lens. The projection-lens is fitted with a spiral focussing arrangement in order that the diaphragm which limits the field may be focussed on to the screen or paper. The field of this eye-piece is small, but its definition is exquisitely sharp.

It may not be generally known that good photo-micrographs can be obtained by projection with the ordinary compensating working eye-pieces, but this is a fact worthy of note.

It will perhaps be of practical utility if we append a table indicating the focus of the compensating eye-pieces when used with the *long* and the *short body*.

Focus of Eye-pieces for long Body.

Power. . .	2	4	8	12	18	27
Focus in mm. .	135	67·5	33·7	22·5	15	10
„ inches .	5·3	2·6	1·3	·88	·59	·39

Focus of Eye-pieces for short Body.

Power. . .	1	2	4	6	8	12	18
Focus in mm. .	180	90	45	30	22·5	15	10
„ inches .	7·08	3·54	1·77	1·18	·88	·59	·39

Projection Eye-pieces.—2 for short and 3 for long bodies = 90 mm. or 3·54 inches; 4 for short and 6 for long bodies = 45 mm. or 1·77 in.

Special Eye-pieces.—The most important of these, the *micrometer eye-piece*, we have already considered, so far as its application to micrometry is concerned.[1] Its optical character may be properly considered here. If it is a negative eye-piece the micrometer is placed in the focus of the eye-lens, but if a positive combination it is placed

[1] Chapter IV.

the focus of the eye-piece itself. The Ramsden form described ove is thoroughly suited for this purpose, but a negative form is nerally employed, the micrometer being placed inside the eye-piece the diaphragm, i.e. the focus of the eye-lens.

In order that the micrometer may be susceptible of focus for rious sights, it is necessary that the eye-lens in the case of a gative eye-piece, and the whole eye-piece in the case of a positive e, should be mounted in a sliding tube; and one with a spiral slot ll be preferable, since it makes the work of focussing both facile d accurate.

If only one micrometer eye-piece is used it should be of medium wer, such as 1½-inch focus; but it is an inexpensive and a useful an to have an additional set of lenses to screw on to the same mount, as to make the eye-piece, say, a ⅔-inch focus.

Spectroscopic, polarising, goniometer, and binocular eye-pieces e each treated under their respective subjects.

The index eye-piece is one which has a pointer placed at the dia-ragm, so constructed that it can be turned in or out of the field, d is used to point to the position of an object. It is of limited ility, for with low powers it is scarcely needed; we can readily dicate by description, to another, the position of an object in a ld every object of which is in view. With a high power, on the her hand, it is very difficult to use such a 'finger.'

A better plan when the magnification is great is to have *a series diaphragms of different apertures* to drop into the eye-piece and minish the field of view. This not only makes the object to be ointed out more easily accessible to the eye, but—as we have by any years of observation proved—it aids in close observation upon inute objects by cutting off a large area of light without altering he intensity of what remains, and so makes close observation more sy.

As it is directly associated with the eye-piece, we shall find no tter place to note the curious and hitherto unexplained fact, that hen resolving striæ or lines with oblique light the effect is much rengthened *by placing a Nicol's analysing prism over the eye-ece.*

Testing Object-glasses.—It will have been noted by the attentive ader that many of the more important qualities of objectives e determined by the principles of their construction, and become fact questions simply of the quality of the workmanship involved producing the optical and mechanical parts of the object-glass.

The quality of the workmanship may be tested by technical eans described below, and by that subtil power which comes with perience. This can only be imparted through the paths of labour d experiment, by which in every case it is reached. But, granted at an object has been illuminated in an intelligent and satisfactory anner, the first complete view of the image (which must of course a thoroughly familiar one) will enable the expert to come to a nclusion as to the quality of a given objective. The character of e image to the expert determines at once the character of the ns. This is the more absolute if a series of eye-pieces (up to the

most powerful that can be obtained) are at hand. Nothing tests the quality of an objective so uncompromisingly as a deep eye-piece. For *brilliancy* of image a moderate power of eye-piece is of course best; but the capacity of the object-glass is clearly commensurate with its ability to endure high eye-pieces without loss of character, and even sharpness in the image. Unless the objective be of high quality, the sharpness of the image gradually disappears as the more powerful eye-pieces are used, until at last either all or part of the image breaks up into the 'rotten' details of a coarse lithograph.

A lens finely corrected (with large aperture) will bear the deepest eye-piecing with no detriment. The 24 mm. and the 12 mm. of Zeiss will suffer any eye-piecing accessible to the microscopist without the smallest surrender of the sharpness of the image. We have in fact tried in vain to 'break the image' yielded by these objectives 'down.'

This mode of testing is of course to a large extent subjective, or at least is controlled by incommunicable judgments. It is most important therefore to have a mode of judgment that shall be accessible to the beginner and the interested amateur. Dr. Abbe has proposed a method which is at least accessible to all.

In ordinary practice microscope objectives, if tested at all by their possessors, are simply subjected to a comparison of performance with other lenses tried upon the same 'test objects.'

The relative excellence of the image seen through each lens may, however, depend in a great part upon fortunate illumination, and not a little upon the experience and manipulative skill of the observer; besides which any trustworthy estimate of the performance of the lens under examination involves the consideration of a suitable test-object, as well as the magnifying power and aperture of the objective. It is knowing what is meant by a 'critical image,' and being able to discover whether or not a given objective will yield it. Clearly all tests of optical instruments, which are not capable of *numerical expression*, must be comparative. *Magnifying power* can be measured numerically; it is not comparative. In the same way *resolving power* is mathematically measurable; so is *penetrating power*. But *definition* and *brilliancy of image*, and evidence of *centring*, can have no numerical expression; they are consequently comparative.

The structure of the test-object should be well known, and the value of its 'markings'—if intended to indicate microscopical dimensions—should be accurately ascertained, care being taken that the minuteness of dimensions and general delicacy and perfection of the test-object should be adapted to the power of the lens. A fairly correct estimate of the relative performance of lenses of moderate magnifying power may doubtless be thus made by a competent observer; but it is not possible from any comparisons of this kind to determine what may or ought to be the ultimate limit of optical performance, or whether any particular lens under examination has actually reached this limit.

Assuming the manipulation of the instrument and the illumination of the object to be as perfect as possible, and further that the test object has been selected with due appreciation of the requirements of perfect

optical delineation, a fair comparison can only be drawn between objectives of the same magnifying power and aperture. Which of two or more objectives gives the better image may be readily enough ascertained by such comparison, but the values thus ascertained hold good only for the particular class of objects examined. The best performance realised with a given magnifying power may possibly exceed expectation, yet still be below what might, and therefore ought to be obtained.

On the other hand, extravagant expectations may induce a belief in performances which cannot be realised. The employment of the test-objects most in use is moreover calculated to lead to an entirely one-sided estimation of the actual working power of an objective—as, for example, when 'resolving power' is estimated by its extreme limits rather than by its general efficiency, or 'defining power' by extent of amplification rather than by clearness of outline. So that an observer is tempted to affirm that he can discern through his pet lens what no eye can see or lens show. This happens chiefly with the inexperienced beginner, but not unfrequently also with the more experienced worker who advocates the use of great amplification, in whose mind separation of detail means analysis of structure, and optically void interspaces prove the non-existence of anything which he does not see.

As much time is often lost by frequent repetition of these competitive examinations (which, after all, lead to no better result than that the observer finds or fancies that one lens performs in his hands more or less satisfactorily than some other lens) it seems worth while to consider the value of a mode of testing which can be readily applied whatever its value may be. A short and easy method of testing an objective—not by comparison with others only, but by itself and on its own merits—affords not only the most direct and positive evidence of its qualities to those who are more concerned in proving these instruments than using them, but also yields to the genuine worker the satisfying conviction that his labour is not frustrated by faulty construction and performance of his instrument. It is, however, to be borne in mind that the microscopist, in any scrutiny of the quality of his lenses which he may attempt, has no other object in view than to acquire such insight into the optical conditions of good performance as will enable him to make the best use of his intrument, and acquire confidence in his interpretation of what he sees as well as manipulative skill in examining microscopical objects. To the constructor and expert of optical science are left the severer investigations of optical effects and causes, the difficulties of technical construction, the invention of new lens-combinations, and the numerous methods of testing their labours by delicate and exhaustive processes which require special aptitude, and lie entirely outside the sphere of the microscopist's usual work.

Professor Abbe's mode of testing objectives is explained in his 'Beiträge zur Theorie des Mikroskops.'

The process, in our judgment, requires large experience and much skill to be of practical service; but it is based on the following principle:—

In any combination of lenses of which an objective is composed the geometrical delineations of the image of any object will be more or less complete and accurate according as the pencils of light coming from the object are more or less perfectly focussed on the conjugate focal plane of the objective. On this depend fine definition and exact distribution of light and shade. The accuracy of this focussing function will be best ascertained by analysing the course of isolated pencils directed upon different parts or zones of the aperture, and observing the union of the several images in the focal plane. For this purpose it is necessary to bring under view the collective action of each part of the aperture, central or peripheral, while at the same time the image which each part singly and separately forms must be distinguishable and capable of comparison with the other images.

1. The illumination must therefore be so regulated that each zone of the aperture shall be represented by an image formed in the upper focal plane of the objective (i.e. close behind or above its back lens), so that only one narrow track of light be allowed to pass for each zone, the tracts representing the several zones being kept as far as possible apart from each other.

Thus, supposing the working surface of the front lens of an objective to be $\frac{1}{4}$ inch in diameter, the image of the pencil of light let in should not occupy a larger space than $\frac{1}{16}$ inch. When two pencils are employed, one of these should fall so as to extend from the centre of the field to $\frac{1}{16}$ inch outside of it, and the other should fall on the opposite side of the axis in the outer periphery of the field, leaving thus a space of $\frac{1}{16}$ inch clear between its own inner margin and the centre of the field, as in fig. 281, where the objective images of the pencils occupy each a quarter of the diameter of the whole field.

Fig. 281.



Fig. 282.

If three pencils of light be employed, the first should fall so as to extend from the centre of the field to $\frac{1}{25}$ inch outside of it; the second should occupy a zone on the opposite side of it, between the $\frac{1}{25}$ and $\frac{1}{17}$ inch (measured from the centre); and the third the peripheral zone on the same side as the first in fig. 282.

This arrangement places the pencils of light in their most sensitive position and exposes most vividly any existing defect in correction, since the course of the rays is such that the pencils meet in the focal plane of the image at the widest possible angle. As many distinct images will be perceived as there may be zones or portions of the front face of the objective put in operation by separate pencils of light. If the objective be perfect all these images should blend with one setting of focus into a single clear, colourless picture. Such a fusion of images into one is, however, prevented by faults of the image-forming process, which (so far as they arise from spherical aberration) do not allow this coincidence of several images from different parts of the field to take place at the same time, and (so far as they arise from dispersion of colour) produce coloured fringes on the edges bordering the dark and light lines of the test-object and the edges of each separate image, as also of the corresponding co-

incident images in other parts of the field. It is to be borne in mind that the errors which are apparent with two or three such pencils of light must necessarily be multiplied when the whole area of an objective of faulty construction is in action. This would appear to us to be the strongest reason for utilising the whole area, because what we are seeking is the *defects*—the errors of the objective—and to make these as plain as possible is a *sine quâ non*. Dr. Abbe proceeds, however, to consider—

2. The means by which such isolated pencils can be obtained.

As a special illuminating apparatus, the condenser of Professor Abbe is recommended, or even a hemispherical lens. But we are convinced that the illuminating apparatus should be as nearly aplanatic as it can be. This is certainly not true of Abbe's chromatic condenser or a hemispherical lens. The reason is obvious: the spherical aberration wholly prevents the rays passing through the holes in the diaphragm from being focussed on the object—the silvered plate of lines—*at the same time*. In the lower focal plane of the illuminating lens must be fitted diaphragms (easily made of blackened cardboard) pierced with two or three openings of such a size that the images, as formed by the objective, may occupy a fourth or sixth part of the diameter of the whole aperture (i.e. of the field seen when looking down the tube of the instrument, after removing the ocular, upon the objective image). The required size of these holes, which depends, first, on the focal length of the illuminating lens, and, secondly, on the aperture of the objective, may be thus found. A test object being first sharply focussed, card diaphragms having holes of various sizes (two or three of the same size in each card) must be tried until one size is found, the image of which in the posterior focal plane of the objective shall be about a fourth to a sixth part of the diameter of the field of the objective. Holes having the dimensions thus experimentally found to give the required size of image must then be pierced in a card, in such a position as will produce images situate in the field, as shown by figs. 281, 282; the card is then fixed in its place below the condenser. We are strongly, however, inclined to believe, partly from experiment, that better results would be obtained by putting sections of annular slits at the *back of the objective*. If the condenser be fitted so as to revolve round the axis of the instrument, and also carry with it the ring or tube to which the card diaphragm is fixed, the pencils of light admitted through the holes will, by simply turning the condenser round, sweep the face of the lens in as many zones as there are holes. Supposing the condenser to be carried on a rotating sub-stage, no additional arrangement is required besides the diaphragm-carrier. Thus, for example, if a Collins condenser fitting in a rotating sub-stage be used, all that is required is to substitute for the diaphragm which carries the stops and apertures as arranged by the maker, a diaphragm pierced with, say, three openings of $\frac{3}{4}$-inch diameter, in which circles of card may be dropped, the card being pierced with holes of different sizes according to the directions given above. We doubt, however, if any sub-stage will revolve with sufficient accuracy for so delicate a test.

Another plan adopted by Dr. Fripp, and found very convenient in practice, is to mount a condensing lens (Professor Abbe's in this case) upon a short piece of tube, which fits in the rotating sub-stage. On opposite sides of this tube, and at a distance from the lower lens equal to the focal distance of the combinations, slits are cut out through which a slip of stout cardboard can be passed across and below the lens. In the cardboard, holes of various sizes, and at various distances from each other, may be pierced according to pleasure. By simply passing the slip through the tube, the pencils of light admitted through the holes (which form images of these holes in the upper focal plane of the objective) are made to traverse the field of view, and by rotating the sub-stage the whole face of the lens is swept, and thus searched in any direction required. But here, again, the spherical aberration of an uncorrected condenser would, with an objective of large aperture, cause the oblique pencils under some conditions to pass under the object; and alteration of focus will not properly alter this—at least without a disturbance of the focus of the objective.

When an instrument is not provided with a rotating sub-stage, it is sufficient to mount the condenser on a piece of tubing, which may slide in the setting always provided for the diaphragm on the under side of the stage.

Card diaphragms for experiment may be placed upon the top of a thin piece of tube (open at both ends) made to slide inside that which carries the condenser, and removable at will. By rotating this inner tube the pencils of light will be made to sweep round in the field, and thus permit each part of the central or peripheral zones to be brought into play. Against the accurate value of this, again, the spherical aberration of an uncorrected condenser would strongly operate.

Abbe's Test-plate.—This test-plate is intended for the examination of objectives with reference to their corrections for spherical and chromatic aberration, and for estimating the thickness of the cover-glass for which the spherical aberration is best corrected.



FIG. 283.

The test-plate consists of a series of cover-glasses, ranging in thickness from 0·09 mm. to 0·24 mm., silvered on the under surface, and cemented side by side on a slide, the thickness of each being marked on the silver film. Groups of parallel lines are cut through the films, and these are so coarsely ruled that they are easily resolved by the lowest powers; yet from the extreme thinness of the silver they also form a very delicate test for objectives of even the highest

power and widest aperture. The test-plate in its natural size is seen in fig. 283, and one of the circles enlarged is seen in fig. 284.

To examine an objective of large aperture, the discs must be focussed in succession, observing in each case the quality of the image in the centre of the field, and the variation produced by using alternately central and very oblique illumination.

FIG. 284.

When the objective is perfectly corrected for spherical aberration for the particular thickness of cover-glass under examination, the outlines of the lines in the centre of the field will be perfectly sharp by oblique illumination, and without any nebulous doubling or indistinctness of the minute irregularities of the edges. If, after exactly adjusting the objective for oblique light, central illumination is used, no alteration of the focus should be necessary to show the outlines with equal sharpness.

If an objective fulfils these conditions with any one of the discs it is free from spherical aberration when used with cover-glasses of that thickness. On the other hand, if every disc shows nebulous doubling, or an indistinct appearance of the edges of the lines with oblique illumination, or if the objective requires a different focal adjustment to get equal sharpness with central as with oblique light, then the spherical correction of the objective is more or less imperfect.

Nebulous doubling with oblique illumination indicates over-correction of the marginal zone; indistinctness of the edges without marked nebulosity indicates under-correction of this zone; an alteration of the focus for oblique and central illumination (that is, a difference of plane between the image in the peripheral and central portions of the objective) points to an absence of concurrent action of the separate zones, which may be due to either an average under- or over-correction, or to irregularity in the convergence of the rays.

The test of chromatic correction is based on the character of the colour-bands which are visible by oblique illumination. With good correction the edges of the lines in the centre of the field should show only narrow colour-bands in the complementary colours of the secondary spectrum, namely, on one side yellow-green to apple-green, and on the other, violet to rose. The more perfect the correction of the spherical aberration, the clearer this colour-band appears.

To obtain obliquity of illumination extending to the marginal zone of the objective, and a rapid interchange from oblique to central light, Abbe's illuminating apparatus is manifestly defective on account of its spherical aberration. We want at least his achromatic condenser. For the examination of ordinary immersion objectives, the apertures of which are, as a rule, greater than 180° in arc (1·00 A.N.), and those homogeneous immersion objectives which considerably exceed this, it will be necessary to bring the under surface of the test-plate into contact with the upper lens of the illuminator by means of cedar oil, even if water-immersion objectives are used. We may add, as a matter of experience, that

having once centred the light and the condenser, we hold, with deference to Dr. Abbe, that the light should on no account be touched, which to obtain obliquity he advises by mirror changes. We believe that this should be secured solely by the movement of the diaphragm.

For the examination of objectives of smaller aperture (less than 40° to 50°) we may obtain all the necessary data for the estimation of the spherical and chromatic corrections by placing the concave mirror so far laterally that its edge is nearly in the line of the optic axis, the incident cone of rays then only filling one-half of the aperture of the objective, by which means the sharpness of the outlines and the character of the colour-bands can be easily estimated.

It is of fundamental importance in employing the test-plate to have brilliant illumination and to use an eye-piece of high power. With oblique illumination the light must always be thrown perpendicularly to the direction of the lines.

When from practice the eye has learnt to recognise the finer differences in the quality of the outlines of the image, this method of investigation gives very trustworthy results. Differences in the thickness of cover-glasses of 0·01 or 0·02 mm. can be recognised with objectives of 2 or 3 mm. focus. The quality of the image outside the axis is not dependent on spherical and chromatic correction in the strict sense of the term.

Indistinctness of the outlines towards the borders of the field of view arises, as a rule, from unequal magnification of the different zones of the objective; colour-bands in the peripheral portion (with good colour-correction in the middle) are always caused by unequal magnification of the different coloured images. Imperfections of this kind, improperly called 'curvature of the field,' are shown to a greater or less extent in the best objectives, when their aperture is considerable.

Testing an objective does not mean seeing the most delicate points in an object; it rather means the manner in which an object of some size is defined.

A test for low powers up to $\frac{1}{3}$ of 80° or N.A. ·65 is an object on a dark ground. Nothing is so sensitive. One of the *Polycistinæ* because it takes light well, is good. For higher powers a coarse diatom, a *Triceratium fimbriatum*, is excellent; for unless an objective is well corrected the image will be fringed and surrounded with scattered light, and the aberration produced by the cover-glass is plainly manifest, and by accurate correction can be done away.

Error of centring is one of the special defects of objectives which the Abbe method of testing does not cover. But if we place a sensitive object in a certain direction, and when the best adjustments have given the best image rotate that object through an angle of 90°, only a well-centred objective will give an unaltered image throughout. If not well-centred it will at certain parts grow fainter or sharper. The most useful image for this purpose with medium powers is a hair of *Polyxenus lagurus* mounted in balsam (frontispiece, fig. 6).

For higher powers nothing surpasses a podura scale. In this particular it has always been of great value to opticians. It should

be strongly marked, and must be in optical contact with the cover-glass; this may be tested by means of an oil-immersion and the 'vertical illuminator' (p. 284).

The objectives of widest aperture are not readily tested because there is no condenser sufficiently aplanatic to do it exhaustively. The best that can be done is to take a diatom, such as a Coscinodiscus, in balsam with strong 'secondaries' (Plate I. figs. 3 and 4), with the largest aplanatic cone that can be obtained, which at present can be best accomplished with Powell and Lealand's achromatic condenser of 1·4 N.A. It must be a good objective indeed that does not show signs of breaking down under this strain; and there is extreme susceptibility to cover correction to which close attention must be paid. An illuminating cone of N.A. 1·0 is probably just below the point of over-strain with the best lenses at present at our disposal.

Testing lenses, therefore, resolves itself into two methods, viz.

1. For low and medium powers, dark ground with a Polycistina, or a diatom according to the power.

2. *Centring* for medium powers (an ordeal not needful for very low powers) should be by means of a hair of *Polyxenus lagurus*.

3. Centring for high powers by means of podura scale.

4. Definition Coscinodiscus asteromphalus with wide-angled cone obtaining sharp, brilliant, and clear view of 'secondaries.'

The apertometer, as its name implies, is an instrument for measuring the *aperture of a microscopic objective*. As correct ideas of aperture have only obtained during the past few years, it may be inferred that apertometers constructed before the definition of aperture was given and accepted were crude and practically useless.

The controversy on the 'aperture question,' which was in full operation some eighteen years since, is not an altogether satisfactory page in the history of the modern microscope, and for many reasons it is well to pass it unobservantly by. It will suffice to state that during its progress an apertometer was devised by R. B. Tolles, of America, which accurately measured the true aperture of an objective. About the same time Professor Abbe gave his attention to the subject, and with the result, as we have seen, that he has given a definite and permanent meaning to *numerical aperture*, making it, as we have seen, the equivalent of the mathematical expression n sine u, n being the refractive index of the medium and u half the angle of aperture.[1]

The application of this formula to, and its general bearing upon, the diffraction theory of microscopic vision has been given in its proper place; but as the aim of this manual is thoroughly practical we shall be pardoned for even a small measure of repetition in endeavouring to explain the use of this formula in such a manner that only a knowledge of simple arithmetic will be required to enable the student to work out any of the problems which are likely to arise in his practical work.

[1] A knowledge of the meaning of the trigonometrical expression 'sine' is not necessary in solving any of the following questions. As the values are all found in tables it is only necessary to caution those who are unacquainted with the use of mathematical tables to see that they have the 'natural sine' and not the 'log sine.'

We can best accomplish this by illustration.

i. If a certain dry objective has an angular aperture of 60°, what is its N.A. ? (i.e. numerical aperture).

All that is needful is to find the value of n sine u ; in this case n = the refractive index of the medium, which is air, is 1 ; and u, which is half of 60°, = 30° opposite 30° in a table of natural sines,[1] is ·5 ; sine u, therefore, = ·5, which multiplied by 1 gives ·5 as the N.A. of a dry objective having 60° of angular aperture.

ii. What is the N.A. of a water-immersion whose angular aperture = 44° ?

n here = 1·33, the refractive index of water ; and u, or half 44°, is 22°. Sine 22° from tables = ·375, which multiplied by 1·33 = ·5 (nearly), which is the N.A. required.

iii. What is the N.A. of an oil-immersion objective having 38½° of angular aperture ?

n the refractive index of oil, which is equal to that of crown glass, is 1·52 ; u = 19¼ and sine u from tables = ·329, which multiplied by 1·52 = ·5.

Thus it is seen that a dry objective of 60°, a water-immersion of 44°, and an oil-immersion of 38½° all have the same N.A. of ·5.

It will be well, perhaps, to give the converse of this method.

iv. If a dry objective is ·5 N.A., what is its angular aperture ?

Here because n sine u = ·5, sine $u = \frac{\cdot 5}{n}$; the objective being dry $n = 1$, therefore sine u = ·5. Opposite ·5 in the table of natural sines is 30° ; hence u = 30°. But as u is half the angular aperture of the objective, $2u$ or 60° = the angular aperture required.

v. What is the angular aperture of a water-immersion objective whose N.A. = ·5 ?

Here n = 1·33, n sine u = ·5 ; sine $u = \frac{\cdot 5}{n} = \frac{\cdot 5}{1 \cdot 33} = \cdot 376$; u = 22° (nearly) from tables of sines ; $\therefore$ $2u$ = 44°, the angle required.

vi. What is the angular aperture of an oil-immersion objective of ·5 N.A. ?

Here n = 1·52, n sine u = ·5, sine $u = \frac{\cdot 5}{n} = \frac{\cdot 5}{1 \cdot 52} = \cdot 329$; u = 19¼° (by tables of sines) ; and $2u$ = 38½, the angle required.

We may yet further by a simple illustration explain the use of n sine u.

In the accompanying diagram, fig. 285, let n' represent a vessel of glass ; let the line A be perpendicular to the surface of the water C D ; suppose now that a pencil of light impinges on the surface of the water at the point where the perpendicular meets it, making an angle of 30° with the perpendicular. This pencil in penetrating the water will be refracted or bent towards the perpendicular. The problem is to find the angle this pencil of light will make with the perpendicular in the water.

To do this we must remember that n sine u on the air side is

[1] *Vide* Appendix A to this volume.

ıl to n' sine u' on the water side. Thus on the air side $n = 1$, 30°, and by the tables of sines sine 30° = ·5 ; consequently on air side we have n sine u = ·5.

On the water side $n' = 1{\cdot}33$, and u' is to be found. But as ine $u' = n$ sine u, sine $u' = \frac{n \text{ sine } u}{n'} = \frac{\cdot 5}{1{\cdot}33} = \cdot 376$; which (as tables show) is the natural sine of an angle of 22° (nearly) ; con-ıently $u' = 22°$; so the pencil of light in passing out of air into er has been bent 8° from its original direction. Conversely a cil in water making an angle of 22° with the perpendicular ıld on emerging from the water be bent in air 8° *further away* ı the perpendicular, and so make an angle of 30° with it.

Now if we suppose that these cils of light *revolve round the* ɔendicular, *cones would be de-ɔed*, and we can readily see ; a solid cone of 60° in air is exact equivalent of a solid ɔ of 44° in water.

If we further suppose that the er in the vessel is replaced by ır *oil*, the pencil in air remain-the same as before, will, when nters the oil, be bent more ı it was in the water, because oil has a higher refractive ex than water ; n in this case qual to 1·52.

The exact position of the cil can be determined in the e manner as in the previous ·. On the air side, as before, ine $u = \cdot 5$; on the oil side sine $u' = n$ sine u; sine $u' =$ ne u $= \frac{\cdot 5}{1{\cdot}52} = \cdot 329$, which (by tables) is the natural sine of °. It follows that the pencil been bent in the cedar oil $10\frac{3}{4}°$ of its original course, and a e of 60° in air becomes a cone of ·° in cedar oil or crown glass.

Finally, it is instructive to e the result when an incident ıcil in air makes an angle o with the perpendicular ; n sin ɔecomes unity, and u in water °, in oil 41° (nearly) ; conse-



Fig. 285.

ıntly a cone of either $97\frac{1}{2}°$ in water, or $82\frac{1}{2}°$ in oil or crown glass, *he exact equivalent of the whole hemispherical radiant in air.* In

other words, and to vary the mode in which this great truth has been before stated, the theoretical maximum aperture for a dry lens is equivalent to a water-immersion of $97\frac{1}{2}°$, and an oil-immersion of $82\frac{1}{4}°$ angular aperture.

The last problem that need occupy us is to find the angular aperture of an oil-immersion which shall be equivalent to a water-immersion of 180° angular aperture.

vii. On the water side $n = 1{\cdot}33$, $u = 90°$, sine $90° = 1$, n sine $u = 1{\cdot}33$. On the oil side $n' = 1{\cdot}52$ and u' has to be found.

$$\text{As } n' \text{ sine } u' = n \text{ sine } u, \text{ sine } u' = \frac{n \text{ sine } u}{n'} = \frac{1{\cdot}33}{1{\cdot}52} = {\cdot}875; u' = 61°$$

(nearly) by the tables; $2u' = 122°$ (nearly), the angle required.

It thus appears (1) that dry and immersion objectives having different angular apertures, if of the same *equivalent aperture*, are designated by the same term. Thus objectives of 60° in air, or 44° in water, or $38\frac{1}{2}°$ in oil, have identically the same aperture, and are known by the same designation of ·5 N.A.

(2) The penetrating power of any objective is proportional to $\frac{1}{\text{N.A.}}$, and its illuminating power to $(\text{N.A.})^2$ Therefore, if we double the N.A. we halve the penetrating power, and increase the illuminating power four times.

In comparing the penetrating and illuminating powers of objectives, however, care must be taken to avoid a popular error, by making them between objectives of different foci.

It cannot, for example, be said that a $\frac{1}{4}$-inch objective of ·8 N.A. has half the penetrating power of a $\frac{1}{2}$-inch of ·4 N.A. Neither can it be said that it has four times the illuminating power. What is meant is that a $\frac{1}{4}$-inch of ·8 N.A. has half the penetrating and four times the illuminating power of a $\frac{1}{4}$-inch objective of ·4 N.A.

But because penetrating and illuminating powers diminish as the square of the foci, a $\frac{1}{5}$-inch objective of ·6 N.A. has four times the illuminating and nearly four times the penetrating power of a $\frac{1}{4}$-inch of ·6 N.A.

The old nomenclature, in use before numerical aperture was so happily introduced, did not of course admit of comparisons of penetrating and illuminating powers by inspection; which, however, is a manifest advantage, contributing to accuracy and precision in important directions.

(3) It may be well, for the sake of completeness, to repeat[1] here that the resolving power of an objective is directly proportional to its numerical aperture. If we double the N.A. we also double the resolving power; and this not simply with objectives of the same foci, as in the case of penetrating and illuminating powers. Thus it is not only true that a $\frac{1}{5}$-inch objective of ·6 N.A. resolves twice as many lines to the inch as a $\frac{1}{2}$-inch of ·3 N.A., but so also does a $\frac{1}{8}$-inch of 1·4 N.A. resolve twice, and only twice, as many as a $\frac{1}{4}$-inch of ·7 N.A.

Within certain limits, then, the advantage lies with long foci of

[1] Chapter I.

le angle, because we thus secure the greatest resolving power h the greatest penetrating and illuminating powers.

From what has here been shown, then, it becomes evident that employment of the microscope as an instrument of precision is gely due to Abbe's work, and that the introduction of numerical rture, with its strictly accurate meaning, has been a practical n of untold value. But this has been greatly enriched by his ing introduced a thoroughly simple and useful *apertometer*. This olves the same principle as that of Tolles, but it is carried out in mpler manner.

Abbe's instrument is presented in fig. 286. It will be seen that onsists of a flat cylinder of glass, about three inches in diameter half an inch thick, with a large chord cut off so that the portion is somewhat more than a semicircle; the part where the segment ut is bevelled from above downwards to an angle of 45°, and it be seen that there is a small disc with an aperture in it denoting centre of the semicircle. This instrument is used as follows.



FIG. 286.—Abbe's apertometer.

The microscope is placed in a vertical position, and the apertoer is placed upon the stage with its circular part to the front the chord to the back. Diffused light, either from sun or lamp, ssumed to be in front and on both sides. Suppose the lens to measured is a dry $\frac{1}{4}$-inch; then with a 1-inch eye-piece having a ge field, the centre disc with its aperture on the apertometer is ught into focus. The eye-piece and the draw-tube are now oved, leaving the focal arrangement undisturbed, and a lens plied with the apertometer is screwed into the end of the drawe. This lens with the eye-piece in the draw-tube forms a lowrer compound microscope. This is now inserted into the bodye, and the back lens of the objective whose aperture we desire neasure is brought into focus. In the image of the back lens l be seen stretched across, as it were, the image of the circular t of the apertometer. It will appear as a bright band, because light which enters normally at the surface is reflected by the elled part of the chord in a vertical direction, so that in reality an of 180° in air is formed. There are two sliding screens seen

on either side of the figure of the apertometer; they slide on the vertical circular portion of the instrument. The images of these screens can be seen in the image of the bright band. *These screens should now be moved so that their edges just touch the periphery of the back lens.* They act, as it were, as a diaphragm to cut the fan and reduce it, so that its angle just equals the aperture of the objective and no more.

This angle is now determined by the arc of glass between the screens; thus we get an angle in *glass* the exact equivalent of the aperture of the objective. As the numerical apertures of these arcs are engraved on the apertometer they can be read off by inspection. Nevertheless a difficulty is experienced, from the fact that it is not easy to determine the exact point at which the edge of the screen touches the periphery of the back lens, or, as we prefer to designate it, *the limit of aperture*, for curious as this expression may appear we have found at times that the back lens of an objective is *larger* than the *aperture* of the objective *requires*. In that case the edges of the screen refuse to touch the periphery.

On the whole we have found that a far better way of employing this instrument is to *use it in connection with a graduated rotary stage*, the edge of the flame of a paraffin lamp being the illuminator.

Thus: Set the lamp in a direction at right angles to the *chord* of the apertometer, and suppose that the index of the stage is at 0°. The edge of the flame will be seen in the centre of the bright band. The sliding screens being dispensed with, *rotation of the stage will cause* the image of the flame to travel towards the edge of the aperture; rotation is continued until the image of the flame is half extinguished *by the edge of the aperture*, the arc is then read, and the same thing is repeated on the other side, and the mean of the readings is taken.

If the stage rotates truly, and if the instrument is properly set up, the reading on the one side ought to be identical with that on the other.

Suppose that the sum of the readings on both sides = 60°, the mean reading is consequently 30°, which is the semi-angle of aperture of the lens in *glass*. From this datum we have to determine the N.A. of the dry $\frac{1}{4}$-inch as well as its angular aperture in air.[1]

(i) As before, N.A. $= n$ sine u, and n sine $u = n'$ sine u'; which means that the aperture on the air side is equal to the aperture on the glass side; $n = 1$ for air; $n' = 1{\cdot}615$, the refractive index of the apertometer; u' is the mean angle measured, which in this case is 30°; and n sine u has to be found.

Now sine 30° = ·5 (by the tables); n' sine $u' = 1{\cdot}615 \times$ sine 30° $= 1{\cdot}615 \times {\cdot}5 = {\cdot}8 = n$ sine u = the N.A. required.

(ii) Again, to find the *angular aperture* or $2u$. As before, n sine $u = n'$ sine u' and sine $u = \frac{n' \text{ sine } u'}{n} = \frac{1{\cdot}615 \times {\cdot}5}{1} = {\cdot}8$; $u = 53°$ nearly (by the tables); $2u = 106°$, which is the angle required.

[1] *Vide* p. 2 *et seq.*

(iii) If it be a *water-immersion* we have to deal with, suppose he mean angle = 45° = u' ; sine 45° = ·707 (by the tables) ; n = 1·33 ; and n' = 1·615.

n sine u = n' sine u' = 1·615 × ·707 = 1·14, the N.A. required.

(iv) Again, sine $u = \frac{n' \text{ sine } u'}{n} = \frac{1{\cdot}615 \times {\cdot}707}{1{\cdot}33} = {\cdot}86$; $u = 59\frac{1}{4}°$ by the tables); and $2u = 118\frac{1}{2}°$, the angle required.

(v) In the case of an *oil-immersion*, suppose the mean angle = 60° = u; sine 60° = ·866 (by the tables) ; n = 1·52 ; n' = 1·615 ; sine u = n' sine u' = 1·615 × ·866 = 1·4, which is the N.A. equired.

(vi) Again, sine $u = \frac{n' \text{ sine } u'}{n} = \frac{1{\cdot}615 \times {\cdot}866}{1{\cdot}52} = {\cdot}92.$

u = 67° (by the tables), $2u$ = 134°, the angle required.

It is manifest that if the refractive index of the apertometer quals that of the oil of cedar, the mean angle measured is the semi-ngle of aperture of the objective, and its sine multiplied by that efractive index is the numerical aperture.

This will be found the more accurate and universally applicable ethod of measuring the apertures of objectives, as the extinction f the light shows precisely when the limit of aperture is reached.

Powell and Lealand's stands lend themselves admirably for use ith the apertometer. The body being removable the lens can be aced in the upper part of the nose-piece, and any measurement an be accurately made. We would advise every microscopist to aster the use of this admirable instrument, and to demonstrate for imself the aperture capacity of his lenses that he may know with recision their true resolving powers.

CHAPTER VI

PRACTICAL MICROSCOPY: MANIPULATION AND PRESERVATION OF THE MICROSCOPE

WITHOUT attempting to occupy space with a discussion of the question of the right of 'microscopy' to be considered a science, we may venture to affirm that it will be but a recognition of practical facts if we claim as a definition of *microscopy* that it expresses and is intended to carry with it all that belongs to the science and art of the microscope as a scientific instrument, having regard equally to its theoretical principles and its practical working. Hence 'practical microscopy' will mean a discourse on, or discussion of, the methods of employing the microscope and all its simplest and more complex appliances in the most perfect manner, based alike and equally upon theoretical knowledge and practical experience.

On this condition a 'microscopist' means (or at least implies) one who, understanding 'microscopy,' applies his theoretical and practical knowledge, either to the further improvement and perfection of the instrument, or to such branches of scientific research as he may profitably employ his 'microscopy' in prosecuting. He is, in fact, a man employing specialised theoretical knowledge and practical skill to a particular scientific end.

But a '*microscopical society*' has a noble *raison d'être*, because it is established, on the one hand, to promote—without consideration of nationality or origin—improvements in the theory and practical construction of both the optical and mechanical parts of the microscope, and to endeavour to widen its application as a scientific instrument to every department of human knowledge, recording, investigating, and discussing every refinement and extension of its application to every department of science, whether old or new.

In this sense no more practical definition of a 'microscopical society' can be given than is contained in the invaluable pages of the 'Journal of the Royal Microscopical Society' from the end of 1880 to the present day; and no better justification for the existence of such a society can be needed than is afforded by the work done directly or indirectly by it, in inciting to and promoting the theoretical and practical progression of the instrument and its ever-widening applications to the expanding areas of natural knowledge.

In this chapter we propose to discuss the best practical methods of using the instrument and its appliances, the theory concerning which has already been discussed, while the mode of applying this

wledge to biological and other investigations is entered upon in subsequent chapters of the book.

To begin his work with success—if his object be genuine work—student must be provided with some room, or portion of a room, :h he can hold sacred to his purpose. Unless special investiga- s are undertaken, it is not a large area that is required, but a e commanding, if possible, a north aspect, and which can be nged to readily exclude the daylight and command complete :ness.

The first requirement will be a *suitable table.*

This should be thoroughly *firm*, and it should be *rectangular in* e. A round table, if small especially, is most undesirable, as it s no support for the arms on either side of the instrument; and prolonged work this is not only a serious, but an absolutely l defect.

In a rectangular table the centre may be kept clear for micro- ical work, while there are two corners at the back, one on the and the other on the right hand. The former may be used for locked case or glass shade for protecting the instrument when in use; and when it is in use it in no way interferes with the ulness of the table. In the same way the right-hand corner be used for the cabinet of objects which is being worked, or the ratus needful for use.

The most important part of the table—that is, the middle, from t to back—should be kept quite clear for the purposes of mani- tion, and a sufficient space should be kept clear on either side of instrument for resting the arms, and no loose pieces of apparatus ld ever be deposited within those spaces. This soon becomes a it in practice, for experience teaches—sometimes painfully by the itting destruction of a more or less valuable appliance.

The spaces to the right beyond that left for the arm of the ator may be used for the work immediately in hand—especially second and simpler microscope. An instrument with only a se adjustment and a 1-inch or a $\frac{2}{3}$-inch objective will suffice, or od dissecting-stand will answer every purpose. Those who do h practical work will find such a plan more rapid and more ient than the cumbrous method of a rotary nose-piece, especially re critical work has to be done.

When work is being done in a darkened room there should be he extreme right a small lamp with a paper shade. (Special les for this purpose can be obtained from Baker, of Holborn.) light may be kept low or used for general illumination when ired—it is never obtrusive, and always at hand.

A similar space on the left hand should be reserved for a small d stand fitted with a flat cylindrical glass shade with a knob on top. The stand should be suitably arranged to hold two eye- es, three objectives, one condenser, a bottle of cedar-oil (fitted a suitable pointed dipper), and a box containing the condenser- s. This is a most useful arrangement for such a table; and it d not have a diameter greater than nine inches.

The size for the top of such a table should be $4\frac{1}{2} \times 3$ feet, and as

no work, such as mounting or dissecting, may be supposed to be done at this table, it is well to cover the surface with morocco, that being very pleasant and suitable to work upon.

It should be remembered that for a full-sized microscope a depth of three feet is required for comfortable work. When the microscope is set up for drawing,[1] the lamp being used direct, 2 ft. 5 in. is the narrowest limit in which this can be accomplished.

Another point of much importance is the *height of the table*. Ordinary tables, being about 2 ft. 4 in. high, are too low even for large microscopes. *Two* or *three* inches higher than this will be found to greatly facilitate all the work to be done. It is best to have the table made completely, on thoroughly solid square legs, to the height of 2 ft. 7 in.; but we may employ the glass blocks employed underneath piano feet as an expedient. It is further important to have the table quite open underneath, and not with nests of drawers on either side, because with this particular table it will be frequently required that two persons may sit side by side, which is only possible with a clear space beneath.



FIG. 287.—Microscopist's table.
(Scale, ½ inch to 1 foot.)

1. Case for microscope; 2. Cabinet for objects; 3. Microscope lamp; 4. Lamp with shade; 5. Stand of apparatus; 6. Book; 7. Large microscope; 8. Second microscope; 9. Writing pad; 10. Bull's-eye stand; 11. Light-modifier.

The accompanying illustration (fig. 287), with the appended references, will make quite clear the character of the table which we recommend, as well as the mode of using it.

The table above described is supposed to be employed wholly for general purposes of observation or research on wholly or partially mounted objects. But the microscopist who aims at more than this will require an arrangement for dissecting, mounting, and arranging histological and other preparations, and in some cases a special table for general purposes of microscopical biology. These are certainly not essentials, especially if the work done is a mere occasional occupation; but where anything like continuity or periodical regularity of occupation with such work is intended, it will be of great service.

A dissecting and mounting table is indeed of inestimable value to those who affect complete order and cleanliness in the accomplishment of such work.

We have found in practice that a table firmly made, with a height of 2 ft. 6 in., semicircular in form, and a little more than half the circle in area on the outside, with the arc of another circle cut out from it to receive the person sitting at work—much after the fashion of the jeweller's bench—serves admirably. A rough sugges-

[1] Chapter IV. p. 288.

of this is given in fig. 288, which presents the plan of the top
e table. The whole area beneath should be unoccupied, but at
d B drawers may be put, not extending more than four inches
r the under surface of the top of the table: On the side B a
le of shallow drawers, with everything required in the form of
els, needles, scissors, forceps, pipettes, life-slides, &c. in the upper
and *pliers, cutting pliers, small shears, files* of various coarse-
s and finenesses, &c. in the other; on the A side a single
er containing *slips, covers* of various thicknesses, *bone, tin*,
, and other *cells* of all (assorted) sizes, *watch-glasses, staining*
or *slabs, lifters* (if used), *saw* with fine teeth, *hones* of various
ss, *pewter plate* for grinding and polishing glass, &c., *platinum*
dle, camera lucida, three 'No. 2' sable brushes (water-
ır), &c.



FIG. 288.—Dissecting and mounting table.

n this way all that is needed for dissection or mounting will be
in reach without moving from the chair; and if by an arrange-
which most moderately ingenious manipulators could accom-
each of the articles in the drawers has a fixed place, there will
o difficulty in finding by touch what is wanted.

The table top may be of pitch pine stained black, or, still better,
very hard wood finished smoothly, but 'grey.'

The space in the figure immediately in front of the operator
be cut out to a convenient size and thickness, a thick plate-
slab whose edges on the right and left sides shall be slightly
led, so that it may slide firmly into a prepared space cut into
surface of the table and occupy this space, the surface being
tly level with the surface of the table. This plate of glass should
ade black on its under side, so as to present *a uniform black*
ace. This is often of great value in certain kinds of work.
ally useful is a *purely white* unabsorbent surface, and a slab of
e *porcelain* may be easily obtained of the same size and be made
exactly into the same place.

In using this table for dissection the arms have complete rest,

and 1 in the figure would represent the position of the dissecting microscope.

2 is a suitable position for a small easily managed *microtome* for general (chiefly botanical) purposes. We find that of Ryder [1] to answer this purpose admirably.

3 is a small vessel of spirit (dilute) for use with the section knife.

4 is a stand of *mounting media*, in suitable bottles, as *Canada balsam* in paraffin, or xylol, glycerine, &c. as well as small bottles of *reagents* for botanical or zoölogical histology &c.

5 is a nest of apertures in which to place partly mounted objects, to protect them from dust, while the balsam, dammar, &c. may be hardening on the cover so as to be in a suitable state for final mounting. A slide may go over the sloping front of this and wholly exclude dust.

6 is a stand of cements, varnishes, &c. such as are needful; and

7 is a turn-table.

For the work of dissection, when the subject requires reflected light, one of the desiderata is a mode of illumination at once convenient and intense. Mr. Frank R. Cheshire, F.L.S. &c., whose work on 'Bees and Bee-keeping' is a proof of knowledge and practice of minute anatomy, adopts an old plan which we have always found admirable. It is illustrated in fig. 289. Rays of light from a lamp are parallelised by a bull's-eye full upon an Abraham's prism and focussed upon the object. The prism may be mounted on a long many-jointed arm and is of most varied usefulness. A Stephenson's binocular is, we believe, employed by this gentleman, but it will serve admirably for any form of dissecting instrument.



FIG. 289.—Mode of illumination for dissection.

For the more general purpose of the private laboratory *a plain, firm table* 4 feet 6 inches × 3 feet in area, of a suitable height for the worker, should be fitted as follows, viz.: if fig. 290 represent the rough plan of the table, 1 and 2 are gas fittings attached to the main to supply *blowpipe*, *Bunsen's burner*, &c.

4 is a small tube of metal attached to the water main, with a tap, and bent in the form of an inverted ∩, with the attached leg of the ∩ the longer. This affords a pleasant stream of water for washing dissections &c.; *and if the open end be made with a screw, and have a suitably made piece of tubing fitted, to screw on to it, this latter may be attached to an indiarubber tube, at the other end of which we may fasten fine glass nozzles*, which will act *as wash bottles of the finest bore*, and serve with the finest dissecting work.

5 is a glass trough for waste, with a perforated aperture, 6, connected with a waste-pipe, through which the waste water &c. flows innocuously away.

3 represents the position of a Thoma microtome, and A B are two well-framed flat slides, which may be drawn out eighteen inches, or

[1] *Journ. R.M.S.* new series, 1887, p. 682.

lly in. They are found at times to be of great service, space is somewhat confined.

ble may be fitted de (the left) at a set of drawers es for receiving apparatus and with larger of stains, and re- ardening, mace- other materials; door covers the inner side of be readily fitted drop-bottles[1] all the stains, and similar ma- constant use. e labelled with ls saturated in a solid paraffin in



FIG. 290.—Laboratory table for microscopical work.

, and after the turpentine has evaporated firmly fixed on the y are very permanent, and, indeed, better than anything ied save where the name of the contents is enamelled or on the bottle.

been already t that there tions of re- which the has to be in tly vertical This was the he researches saprophytic made con- the present d Dr. J. J. It must e the case ain forms of life stages



FIG. 291.—Tripod for using microscope in an upright position.

ed for prolonged or continuous observations on the deve- the minuter forms of life.

cases the table is quite unsuitable, and special stands employed that from their form give great stability to the , and afford the body and head of the observer as much nd ease in using the instrument in this awkward position btained.

VII. p. 445.

[1] *Micro. Journ.* vols. x. to xviii.; *Journ. R.M.S.* vol. iii. p. 1; vol. v. 7; vol. vi. p. 198; vol. vii. p. 185; vol. viii. p. 177.

This is best done by means of a firmly made tripod, with a V-shaped piece at the top made to receive the feet of the microscope. Fig. 291 is an outline of the construction. The three legs of the tripod are well made and firmly braced together with metal rods. A, A is the bed for the tripod feet of Powell and Lealand's large stand. B is a table which slides to the level of A, A, or down to its present position. This is mainly to receive the lamp.

By this arrangement the body can so place itself as to command the instrument fully, and there is an arrangement at the two sides,

FIG. 292.—Using the microscope in an upright position.

A, A, to receive supports on which the arms may rest when any other manipulation than that involved in working the fine adjustment and the milled heads of the stage is required. The manner of using this arrangement is seen in fig. 292. In that case, however, the whole is employed for the making of a camera lucida drawing with a $\frac{1}{2}\frac{1}{6}$-inch objective. But the position of the basal tripod, the microscope upon it, the position of the lamp (partly seen in the immediate foreground to the left), and the relative ease with which the entire instrument is at the command of the observer will be manifest.

In order to use the microscope successfully, we must have an illumination the intensity of which we can fully rely on. *Daylight*

ualities that involve advantages at times, and under special es, in its employment, *but this is the exception rather than* /hat is needed is a well-made lamp with a flat flame: ld be able to control with great ease as to height and m the microscope. Nothing is equal practically to a l-inch paraffin lamp; this gives the whitest light artifi- ible save the higher intensities of the incandescent electric there is nothing at present accessible to the student of The employment of the *edge* of the flame of a well-made p used with as no present is much yel- ot so easy in

he best form ical lamp is a some import- all the atten- reader to the form of lamp accomplish se. This is a ged by Mr. the drawing given in fig. lamp burns has an ordi- wick burner. r is rectangu- $5\frac{1}{2} \times 4 \times 1\frac{1}{8}$; ree distinct st, it will hold to burn for a 2nd, permits be lowered le; 3rd, radi- at conducted chimney and oil boiling. placed at one reservoir to flame to be

FIG. 293.—Lamp devised by Mr. E. M. Nelson.

near the stage of the microscope, which is exceedingly some kinds of illumination, especially with reflected light, gher powers, and for Powell and Lealand's super-stage

for filling the reservoir is placed at the diagonal corner nce. The chimney is metal with an ordinary 3 × 1 front; the diameter of the flame-chamber should not ch, and the grooves holding the glass slip should project the flame-chamber; the aperture should be only $1\frac{1}{2}$ inch

long; length of chimney should be 7 inches. Chimney should be dead-black inside. This chimney serves four purposes: 1st, image of flame is not distorted by striæ and specks common to ordinary



FIG. 294.

lamp chimneys; 2nd, prevents reflexion from inner surface of chimney, which causes a double image of flame; 3rd, prevents scattered light in room; 4th, is not readily broken; slips can be easily replaced.[1]

[1] It is very important to remove the metal chimney after use, or at least not to leave it on when not in use, since the evaporating paraffin gathers round it and causes undesirable scent when the lamp is again lit.

By rotation of chimney either the edge or flat side of the flame may be used. The bull's-eye is of Herschel's form, viz. a meniscus and crossed convex; it is mounted on an arm which rotates centrally with the lamp flame. The arm is slotted so that the bull's-eye may be focussed to the flame; it can be fixed by a clamping screw. The bull's-eye may also be elevated or depressed and fixed by a clamping screw, not shown in the illustration. The bull's-eye having once been focussed is permanently clamped, and it is brought into or taken out of position simply by rotation of the arm. There should be a groove in the pillar with a steadying pin on the lamp to prevent rotation during elevation or depression.

The form of the clamping screw is important; it should be at the upper part of the tube, and not at the lower, as shown in the figure This keeps the screw clean from oil, which always, to a greater or less extent, exudes over paraffin lamps. The screw should be of that form which closes a pinching ring round the rod, and not merely a screw which screws on to the rod and bruises it. This lamp, if made, as it should be, with a japanned tin reservoir and a cast-iron tripod foot (fig. 295), is quite inexpensive. There is no justification for a circular foot, except that it can be readily and well finished in the lathe with better apparent results and less labour than other forms.

A small lamp is made by Messrs. R. and J. Beck. We illustrate it in fig. 294.

The base, A, consists of a heavy ring, into which a square brass rod, B, is screwed. The square rod carries a socket, C, with an arm, D, to which the lamp is attached.

On each side of the burner, and attached to the arm, D, is an upright rod, G, to one of which the chimney is fixed, independent of the reservoir of the lamp, thus enabling the observer to revolve the burner and reservoir, and obtain either the edge or the flat side of the flame without altering the position of the chimney. The chimney, F, is made of thin brass, with two openings opposite to each other, into which slide 3×1 glass slips of either white, blue, or opal glass, the latter serving as a reflector; but we do not consider the reflexion here accomplished as other than an error; it causes double reflexion and confuses the condensed image.

A semicircle swings from the two uprights, G, to which it is attached by the pins, H, placed level with the middle of the flame; to this semicircle is fixed a dovetailed bar, L, carrying a sliding fitting, O, which bears a Herschel bull's-eye, P. This is complex and therefore costly.

The bull's-eye is fixed at any inclination by a milled head working in a slotted piece of brass, K, fixed to the arm, D.

For use with the microscope in an upright position, when prolonged investigations have to take place, the lamp becomes even of more importance than under ordinary circumstances. The present Editor devised a somewhat elaborate apparatus of this kind, which he always employs in this kind of observation.[1] But the essential part of it is only an arrangement by which a milled-head movement of

[1] *Monthly Micro. Journ.* vol. xv. p. 165.

the entire lamp may take place to the right or the left of server, as well as a similar power to elevate or depress the f of the flame. When the microscope is fixed, and the recta prism for illumination (in place of the mirror) is fixed at right the centring of the lamp flame upon the object is more readil by means of *motion in the lamp*. A very simple form of thi has been made for the Editor by Mr. Charles Baker, of Ho it is seen in fig. 295, being an ordinary lamp, except that the head to the right as v the flame racks up and the entire lamp, and the head behind, and at angles to this, works and pinion (shown in t graving) carrying the lamp to the right or the middle position. Th would be better, if the s did not object to the c be made with a metal re or at least to have an a ment by means of whi bull's-eye (with a catch its focus from the flame so affixed as to be carri and down and to right a with the lamp.

FIG. 295.

When the microsc fixed in its upright p and the prism is arran give direct and not obli flexion, the lamp fla means of a card, is ar as nearly right for t flexion of the image flame into the centre field as may be, and t little movement in one c milled heads will bring curately into the field.

We may arrange the scope for ordinary trans light, that is, for light caused to pass through the object in object-glass, by placing it upon the table, arranged as a directed; the instrument is then sloped to the required p and a condenser, suitable to the power to be employed,[1] is p the sub-stage. The lamp is now put into the right position, bull's-eye, on the left of the observer.** The condenser is t described below (p. 351), to be 'centred'; when the ob

[1] *Vide* Chapter IV. p. 248.

ıy be changed as desired, and the eye-piece altered to suit. But should be carefully noted, that if apochromatic powers are being ed, there must be accurate adjustment of the tube length if the st results are to be obtained; and with any serious increase of e power of the objective a condenser of higher aperture and shorter cus must be used.

Often, however, as good or better results may be obtained with- t the employment of the mirror at all, the light being sent directly rough the condenser from the lamp flame. The mode of arrange- ent for this kind of manipulation is presented in Plate V., where will be observed that the microscope is inclined more towards the rizontal to suit the observer; the lamp is directly in front of the b-stage, the mirror is turned aside, and a frame (fixed upon a bull's- e stand) carrying screens of coloured glass is placed between e lamp flame and the con- nser (sub-stage).

By this means the light sent into the condenser d upon the object, and is en treated as is the case or centring) when the irror is used.



FIG. 296.—Edge of lamp flame in centre and focus of bull's-eye.

The first step in the rection of efficiency in the use of the microscope is to understand e *principles of illumination*, and a knowledge of the various effects oduced by the bull's-eye lies on the threshold of this.

Having given details as to the forms of *lamp* which are of most rvice, we assume that a paraffin lamp with ½-inch wick is used.

If we place the edge of this flame (E, fig. 296) in the centre and act focus of the bull's-eye B, A shows the effect of doing so.

If a piece of card were held in the path of the rays proceeding om B, the picture as shown at would not be seen—instead of an enlarged and inverted image the flame. The image at A is otained by placing the eye in e rays and by looking directly the bull's-eye.



FIG. 297.—Altered relations between lamp flame and bull's-eye.

The light is so intense that it more pleasant to take the field ns of a 2-inch eye-piece and ace it in the path of the rays cussing the image of the bull's- e on a card. It should be oticed with care that the *iameter* of the disc A depends upon the diameter of the bull's- e B; but the intensity of the light in A depends on the focal ngth of B. The shorter the focus, the more intense will be the ght.

We are here assuming throughout that the field lens is at a fixed istance from the bull's-eye B.

But if we *move the flame*, E—still central—*within* the focus of B, we get the result shown in D, fig. 297. But by moving E *without* the focus of B we get the picture H, while K is the picture when E is focussed *but not centred.*

A common error, one repeatedly met with, is that of placing a concave mirror C (fig. 298) so that the flame E is in its *principal focus.* The result of this is that *parallel rays* are sent to B. These rays are brought to a focus at a distance from B about equal to twice the radius of the curvature of B and then scattered; a totally different result from what is aimed at. If the concave mirror, C, is to be of any use in illumination, it must be placed so that E is *not at its principal focus*, but at its *centre of curvature.*



FIG. 298.—Result of placing flame in principal focus of concave mirror.

The bull's-eye gives an illustration of what is of wider application. The method of obtaining a critical image with a condenser by means of transmitted light is shown in fig. 299. E is the edge of the flame, S represents the sub-stage condenser, and F the object. F is thus the focal conjugate of E, and F and E are in the principal axis of S; that is to say, these are the relations which exist when a condenser is focussed on and centred to an object. Let this be understood as the law, and there can be but little difficulty remaining in getting the best results from a condenser.



FIG. 299.—Mode of obtaining critical image.

Fig. 300 illustrates another method of getting the same result. We may illuminate a condenser with light direct from the flame, as in fig. 299, or we may interpose the mirror, as in fig. 300. M is the plane mirror and, properly used, exactly the same result may be obtained as in the former case. It is, however, slightly more difficult to set up, but will, on the whole, be preferable.



FIG. 300.—Another method of getting critical image.

Nothing can be of more moment to the beginner than to understand the practical use of the condenser. We must direct the student



MODE OF OBTAINING TRANSMITTED LIGHT DIRECT WITHOUT THE AID OF THE MIRROR.



; has been stated concerning it in Chapter IV. But the g should be carefully considered. Fig. 301 shows a sub-ndenser, S, and an objective, O, ussed on the same point. The er has an aperture equal to that objective. Now if the eye-removed, and we look at the ıs of the objective, it will be be full of light, as at R. The ing, but with the aperture of lenser cut down by a stop, is seen in fig. 302. Now only a the back of the objective is filled with light, as at T in the ustration.

FIG. 301.—Condenser and object-glass with the same aperture.

' it does not follow, because : lens of the objective is full of in fig. 301, that therefore *the* ght to be full of light. The y shows the *bright image of the he flame*, and it is *in that alone itical picture can be found.* If lenser be racked either within ıut the focus, the *whole field me illuminated*, but at the same time a far smaller portion bjective will be utilised. On removing the eye-piece and ng the back lens of the objective, pictures like D, H, fig. 297, een—D when within, and H when without the focus.



FIG. 302.—The same, with the aperture of the condenser cut down.

condition represented in fig. 301 at R and O is the severest ch can can be applied to the microscopic objective; that is o fill the whole objective with light and so test the *marginal ral portions at the same time.*



FIG. 303.—Illumination for 'diffused daylight.'

; to obtain the state of illumination known as 'diffused day-ith the simple mirror when no condenser is used is frequently a most inaccurate manner. The correct method of doing own in fig. 303. F is the plane of the object, C is the con-ror, the mirror being placed at the distance of its principal m the object. But the manner in which it is usually done, nt of thought or knowledge, or both, is shown in fig. 304,

where it is manifest that there is a total disregard of the true point of the mirror and its incidence on the plane of the ol From the impracticability of this diagram as a representation working plan of illumination, we may see at once the importan



Fig. 304.—Erroneous method of arrangement for 'diffused daylight.'

having the mirror fixed upon a *sliding tube*, so that its focal l may be adjusted.

It is also important here to note that in *daylight illumina*



Fig. 305.—Light from the open sky falls upon the mirror in all directions.

a *plane mirror* gives a *cone of illumination*, as in fig. 305, when th is ample sky-room; but a *window* acts as a *limiting diaphragm*.

In regard to the parallelism of the *direct solar rays* there is course no question. But the parallelism of that portion of the so

which goes to form the firmament in our own higher atmo-
e is so completely broken up by refraction and reflexion
gst the subtil particles of this higher atmosphere that the rays
i constitute our daylight fall from every point of the visible
ns (though with greatly diminished intensity). That is to say,
ve at disposal a light source extending over 180°, *while the sun extends over a visual angle of but half a degree.* Being thus
unded by an illimitable and self-luminous expanse of ether un-
ions, the question is no longer of parallel rays only, but of light
ating from an outer circle above the earth upon every point of
rth's surface ; and a mirror exposed to such a luminous atmo-
e must both receive and reflect from all sides and upon all

If, however, it be placed under the stage of a microscope,
rtical light is intercepted, and there remains nothing but the
e incidence as the starting-point of the theory of illumination
nverging light ; for it scarcely needs repetition that obliquity
cidence gives inevitable rise to obliquity of reflexion ; and it
oes equally clear that in order to strike the object the *light always fall obliquely on the mirror.*

hen it follows from what has been said that the light falling
the open sky upon a mirror falls in all conceivable directions.
fig. 305 shows the lines 1 to 7, including an angle of 30°. If
ng intervene the light of that sky surface must fall upon the
r, *a b*, and be reflected on O. The intermediate rays, 2, 3, 4,
form the *converging illuminating pencil*, with of course an in-
of others filling up the spaces between.

n other words, every point of a mirror is a radiant of a whole
sphere, and *this is equally true whether the mirror be plane, re, or convex*, so long as they are exposed to a boundless sky.
efore a plane, concave, or convex mirror will give a cone of
ination of which the object is its apex, no matter what the in-
tion or distance of the mirror. The angle of the cone will be
ngle the mirror subtends at the object – subject of course to its
eing cut down by a stop.

As a matter of fact, the
dless sky is an abstraction
h is never obtained in prac-
therefore it practically does
e a difference whether the
e or concave mirror is used,
whether the latter is focussed
he object or not.

The dotted lines in fig. 306
rays falling on six different
ts on a plane mirror; the
inuous lines show the re-
ons of these rays on the ob-



FIG. 306.—With the open sky, light is focussed at all points.

The heavy lines from
r extremity of the mirror to the object show the maximum
e of cone that mirror will give in that particular position.

The influence of a limitation (as by means of a window) should

therefore be considered. The extent to which it is limiting, so as its influence upon the illuminating cone is concerned, is shown by an examination of the back of the lens of the objective when the eye-piece is removed. Fig. 307 shows the back of the objective when the plane mirror is used, and fig. 301, R, when the concave mirror is used, as in fig. 303. The beginner should study these experiments by repeating them.

The correct method of illuminating *to obtain a dark ground* with the object luminous is shown in fig. 308. This may also be used when, by means of that shown by fig. 299, there is not enough of the field illuminated even when the flat of the flame is used. Of course it will be understood that for the dark-ground result a suitable stop is inserted beneath the sub-stage condenser.

FIG. 307.—Image at the back of the objective when daylight and a plane mirror are used.



FIG. 308.—Illumination for dark ground (with stop beneath the condenser).

It has been shown by many illustrations on many subjects that certain results in critical work can be obtained with the bull's-eye which are not so accessible without its use. But Mr. T. F. Smith has made this clear regarding the structure of certain diatoms.

This, there can be no doubt, is due to the fact that the parallel rays, falling on the sub-stage condenser, *shorten its focus* and increase the angle of the cone of illumination. It will be noticed that when the bull's-eye is introduced the condenser will need racking-up. At the same time we prefer illumination as in fig. 299 or 300, except in cases where illuminating cones of maximum angles are required. Thus it will be little needed with transmitted light except when oil-immersion objectives of large aperture are used, because illuminating cones up to ·8 N.A. can be obtained with good condensers by the method shown in fig. 299. But when the microscope is of necessity used upright the rectangular prism or the plane mirror must be used, fig. 300.



FIG. 309.—Same result with concave mirror.

The arrangement at fig. 308 is sometimes useful for photomicrography when it is *otherwise impossible* to illuminate the whole field. But in ordinary cases it is better to contract the field than use a bull's-eye, as it invariably impairs the definition.

In regard to this last figure it will be understood that (as before) E represents the edge of the flame, B the bull's-eye, M the mirror, S the condenser under the stage, and F the plane of the object.

The same result as the above may be obtained by the concave mirror (as shown in fig. 309) instead of the bull's-eye. But this is a very difficult arrangement, yielding the best results only with great application and care.

But the supreme folly of using a concave mirror *and a bull's-eye* is shown in fig. 310, where C is the concave mirror and (as before) S the sub-stage condenser; this secures a result—as will be seen by the relation of the light to the condenser (S)—which is as far from what is sought and desirable as it can well be. While another lesson of great importance may be learnt from fig. 311, which illustrates *the error of not having the edge of the flame* E *in the principal focus of the bull's-eye* B. The rays converge on the condenser S, so that it will become in all probability impossible to focus it on the object. This is a lateral lesson on the value of having the bull's-eye fixed to the lamp, so that both may be moved together; and here *should* be a notch in the slot or arm which carries the bull's-eye to denote when the flame of the lamp is in its principal focus.



FIG. 310.—Absurdity of using a bull's-eye and a concave mirror.



FIG. 311.—Absurdity of using a bull's-eye with the edge of the lamp flame not in its principal focus.

The above are fundamental principles of illumination, and if the student is to succeed as a manipulator he must demonstrate and re-demonstrate them, and become master of their details and what they collaterally teach.

We may, however, with much advantage give them a larger and more detailed application to the practical setting up of a dark-ground illumination, as in fig. 308.

Let an object such as a *triceratium* (diatom) be taken, and suppose that the objective employed is a $\frac{2}{3}$-inch of ·28 N.A. We must first adjust the lamp and bull's-eye, as in fig. 296, and get the edge of the lamp flame extended to a disc as at A.

Now let a small aperture be put into the condenser and a triceratium on the stage and the $\frac{2}{3}$-objective on the nose-piece.

The microscope being put into position, the lamp should be placed on the left-hand side of it—a lamp with a fixed bull's-eye is assumed—and it should now be arranged as to height, so that the rays from the bull's-eye should fall fairly on the plane mirror, this

latter being inclined so as to reflect the beam on the back of the sub-stage condenser.

Now with any kind of light, focus, and place in the centre of the field, the *triceratium*, as in fig. 312; then rack the condenser until the small aperture in its diaphragm comes into focus; centre this to the *triceratium*, as in fig. 313. Rack the condenser closer up until the bull's-eye is in focus, as in fig. 314.

Here it happens that the bull's-eye is not in the centre, and it is *not uniformly filled with light*, as in fig. 296, A, *but has instead two crescents of light.*

This is a case which frequently repeats itself, but it is of course not inevitable. The bull's-eye may be more or less filled with light,



FIG. 312.

FIG. 313.



FIG. 314.



FIG. 315.

and may or may not be more nearly centred. In this case we have next to centre the image of the bull's-eye to the triceratium by moving the mirror, as in fig. 315.

But it will be noticed that this centring of the image of the bull's-eye *does not rectify the diffusion of the light.* This will be at once done by moving the lamp with attached bull's-eye; this motion requires to be a kind of rotation in azimuth round the wick as an axis. *The relative positions of the lamp and bull's-eye* must *on no account be altered*, and it is understood that the lamp was adjusted to the picture A in fig. 296 by inspection and without the microscope. A very slight movement in azimuth, however, is enough to effect the desired end (fig. 316), and all that now remains is to open the full aperture of the condenser and put in the smallest stop; if this does not stop out all the light, a larger one must be tried; but it is of the greatest importance that the smallest stop possible be used, a very little difference in the size of the stop making a remarkable difference in the quality of the picture. Hence the need of a large and varied supply of stops with all condensers.



FIG. 316.

On account of some residual spherical aberration the condenser will probably have to be racked up slightly to obtain the greatest intensity of light.

In fig. 316 the expanded edge of the flame covers the *triceratium.* When the whole aperture of the condenser is opened the *size of that disc will not be altered*, its *intensity only* will be *increased.* When the stop is placed at the back of the condenser, only in that part of the field represented by the disc of light will the object be illuminated on a dark ground. If, therefore, the disc of light does not cover the object or objects,

bring the lamp nearer the mirror. The size of the disc of light depends on three things :—

α. The diameter of the bull's-eye.

β. The length of the path of the rays from the bull's-eye to the sub-stage condenser.

γ. The magnifying power of the condenser.

If α and γ are constants, the only way of varying the size of the dark field is by β.

In the same way the *intensity of the light* in the disc depends on three things.

A. The initial intensity of the illumination.

B. The angular aperture of the bull's-eye.

C. The angular aperture of the sub-stage condenser.

If the student will thoroughly and practically understand the above series of single demonstrations, and ponder such inevitable variations as practice will bring in regard to them, the 'difficulties of illumination' will have practically passed away.

There are two kinds of microscopical work—one, the more usual and comparatively easy, is the examination of an object to see *something which is known*. The other is the examination of an object in search of the unknown. Thus some blood may be examined for the purpose of finding a white corpuscle. It matters little what is the quality of either the lens or the illumination or the microscope, or whether the room is darkened or not, because the observer knows that there is such a thing as a white corpuscle. It is quite immaterial as to whether the observer had ever seen one or not; so long as he possesses the knowledge that there is such a thing, the finding of it, even under unfavourable conditions, will be an easy task.

But if the observer has not that knowledge, he may examine blood many times, under favourable conditions, and yet not notice the presence of a white corpuscle, and that, too, with one immediately in the centre of the field; this, moreover, is a large object.

It is only those in the habit of searching for new things who can appreciate the enormous difficulty in first recognising a new point. Therefore when critical work is undertaken care should be exercised to have the conditions as favourable as possible.

When working with artificial light all naked lights in the room should be avoided.

It is quite unreasonable to expect the retina to remain highly sensitive if, whenever the eye is removed from the eye-piece, it is exposed to the glare of a naked gas flame.

At the same time there should be ample light on the microscope table, as it is not at all necessary or desirable that the work should be insufficiently illuminated. All that is required is that the lamps should have shades and be placed at such a height that the direct rays do not enter the observer's eye.

If these precautions are taken, several hours continued work may be carried on without any injurious effect.

Some observers use only the left eye, some the right, others the right or left indiscriminately.

It seems immaterial which is used, it being merely a matter of habit, as those who are accustomed to use one particular eye feel awkward with the other. But in continuous work extending over many months of long daily observation it is a great gain to use the binocular, especially with high powers. The effect of years of work with optical instruments on those possessed with strong normal sight seems to be an increase in the defining perception accompanied with a decrease of the perception of brightness. Those accustomed to use one particular eye with microscopical work, and who have done much work, would, if they looked at, say, the moon with that eye, see more detail in it than if the other eye were used; at the same time it would not appear as bright.

If there is too much light, as there often is, when large-angled illuminating cones are used, it is as well to interpose between the lamp and the microscope a piece or pieces of blue glass; this softens the light and removes the objectionable yellowness; a feature of illumination not due to the light from the edge of a paraffin lamp, which, as we have stated, is not particularly yellow. *Great yellowness* is a sign of *imperfect achromatism* in an objective. We may with precisely the same conditions find the images yielded by two objectives of the same power and aperture differ, in so much as one is yellow and dim and the other white and bright; other things being equal, the white and bright image is to be preferred. It is necessary to say 'other things being equal,' because an objective which gives a bright and a white image may nevertheless be inferior to the one giving the yellow and dim picture. Thus if the planes of the lenses of which the objective is composed are not at right angles to the optic axis there will be serious defects in the image, although it is bright and white. This fault is known in practice as an error of centring, which also means the error of not placing the axes of the lenses in the same straight line; so both faults are described by the same term.

It should be understood that neither blue glass nor ammonio-cupric solution will yield monochromatic illumination. If the light passing through these media be examined by the spectroscope, red, yellow, and green will be seen. Some specimens of blue glass pass more red than others. Out of a number of samples the best result was obtained by using two thicknesses of cobalt 'pot' glass, which gave two bands in the red. If a greater thickness were used the light became too dim. The ammonio-cupric solution merely dims down the whole spectrum. When a sufficient thickness of solution is used to cut out all the red light, then the light is too enfeebled to be of any use visually, and also, what one would not expect, photographic exposure is greatly prolonged.

It would seem that true monochromatic illumination obtained by absorbing media does not exist. Neither does the manipulation of the source of illumination by means of chemical substances apparently give satisfactory results.

Coloured light derived from a polariscope and a selenite is not monochromatic.

There are two ways of obtaining true monochromatic illumi-

nation. One which would be extremely simple would be to condense a powerful beam on a diffraction grating ruled on a speculum. The costliness of the apparatus is a bar to this method.

Equally perfect monochromatic illumination can be obtained by prismatic dispersion. Hartnack designed such an apparatus,[1] which was an ordinary spectroscope.

But it never came into popular use because with any ordinary artificial light, such as that from a paraffin lamp, the light was excessively dim, although it is powerful enough with an electric arc. The only use it has served is to give oblique illumination, with sunlight from a heliostat. The following is a method of approximating to monochromatic illumination used by Mr. Nelson which answers admirably with an ordinary ½-inch wick paraffin lamp.

He places the edge of the flame in the principal focus of a lens known as a Wray 5 × 4 RR, working at $\frac{f}{5{\cdot}6}$. In the parallel beam from this lens and close to it he places an equilateral prism of dense flint set at minimum deviation. Close to the prism he places another Wray 5 × 4 RR, working at $\frac{f}{5{\cdot}6}$. If a cardboard screen be held at the principal focus of this lens, there will be seen three images of the edge of the flame, red, green, and blue, brilliantly illuminated. A slit $\frac{1}{16}$ inch in diameter is cut in the cardboard screen, through which the required colour is allowed to pass to the mirror of the microscope, thence to the sub-stage condenser. For visual work green is the best, but for photographic work blue would be chosen unless orthochromatic work required a colour lower down the spectrum.

For critical work, such as testing lenses or forcing out the greatest resolution with the widest-angled oil-immersion lenses, daylight illumination is inadmissible.

When daylight illumination is used a northern aspect, or at least one away from direct sunlight, is to be preferred.

It is a good plan where it is possible, to arrange the table so that the window is at the observer's left hand. The microscope should be placed in a direction parallel to the window, and the light reflected by the mirror through a right angle. A screen may be placed parallel to the window which just allows the mirror of the microscope to project beyond it. This cuts off direct light from the stage and from the observer's eyes.

A concave mirror with the object in its principal focus is the best for diffused daylight illumination. The diaphragm should not be close to the stage. When delicate microscopical work is carried on, it is important to remember that the human eye can work best when the body is in a state of ease. If there is any strain on the muscles of the body, or if the observer is in a cramped position, vision will be impaired. Consequently, where permissible, a microscope should always be *inclined*, and the observer seated in such a way that the eye can be brought to the eye-piece in a perfectly natural and com-

[1] Chapter IV. p. 272, fig. 224.

fortable manner. The body should also be steadied by resting the arms on the table.

It is advisable to use the bull's-eye as little as possible; *even with dark-ground illumination* the flat of the flame is preferable, reserving the bull's-eye for those cases where the flat of the flame will *not cover* enough of the object. Generally speaking, if the whole field is required to be illuminated on a dark ground, a bull's-eye will be necessary; but for an object such as a single diatom the lamp flame will usually be large enough.

In examining diatoms or other objects, such at the karyokinetic figures in very minute nuclei of microscopic organisms, or other obscure and undetermined parts of such forms of life, it is most important, amongst other means, to resort to the use of large solid cones; what they teach and suggest can scarcely be neglected by the searcher for the unknown. Professor Abbe does not advise their employment as in any way final; he says that 'the resulting image produced by means of a broad illuminating beam is always a mixture of a multitude of partial images which are more or less different and dissimilar from the object itself;' and he does not conceive that there is any ground for expectation 'that this mixture should come nearer to a strictly correct projection of the object . . . than the image which is projected by a narrow axial illuminating pencil.' This is a weighty judgment, and should receive full consideration. At the same time the use of wide and solid cones is so full of suggestive results that we must employ them, with all possible control by other means of the images they present. This is the more a necessity since Mr. Nelson has been able to obtain the most wonderful results with narrow cones, 'true ghosts' and 'false ghosts,' the presence of 'intercostal markings' in the image of a fly's eye (!), and many complex and false images with the coarser diatoms. But with wide cones he has proved that these false images *cannot* be produced; and that when the true image is reached by a wide cone, the image is not altered by any change of focus, but simply fades in and out of focus 'as a daisy under a 4-inch objective.'

Mr. Nelson has photographed all these results, and we have seen them demonstrated. When theory and practice are thus at variance we must pause for further light.

If it is required to accentuate a known structure, *such as the perforated membrane of a diatom*, it can be done by annular illumination, which means the same arrangement as for dark ground, but with a stop insufficiently large to shut out all the light. This method is not to be recommended when a structure is unknown, as it is also liable to give false images. It must be remarked that diatom and other delicate structure when illuminated with a *narrow-angled cone* gives on slight focal alterations a *variety* of patterns like a kaleidoscope; with a wide-angled cone a single structure gives a single focus, i.e. it goes completely out of focus on focal alteration. When a large-angled and a wide-angled objective are used a change of pattern only occurs when the structure is fine. This practical observation has its value and must not be forgotten.

To properly display objects under a microscope is to a certain ex-

be obtained in any other way. The diatoms should be
d worked at in this manner most carefully and for a long
e same identical specimens should be then viewed with
d light. This lesson if conscientiously learnt will teach a
ow to appreciate form by focal alteration. This is a most
lesson, and, if several days are spent in mastering it, they
from thrown away. Diatoms, especially the larger forms,
ery well *when mounted dry on cover* by means of a $\frac{1}{4}$-inch
nd a *Lieberkühn*; the bull's-eye and the plane mirror should
Some objects are so transparent, or become so transparent
lium in which they are mounted, that they will not bear a
inating cone, the brightness of the illumination destroying
st. It will illustrate this when we recall that dirt on an
which is quite invisible in a strong light becomes im-
apparent in a feeble light. Thus animalcules require a
of illumination when they are being examined, particularly
ach objective; for a general view of 'pond life' a $1\frac{1}{2}$-inch
vith a dark-ground illumination, employing a binocular, is
ble. Stained bacteria in tissue are best seen with a *large*
s pointed out by Dr. Robert Koch, and is directly supported
be as suitable in his directions for the use of the Abbe
1 The brilliancy of the illumination obliterated the thin
ch is in a medium whose refractive index is similar to
e bacteria, which are opaque with pigment, then stand
. A bacterium not in tissue is always better seen by
a large cone, provided that the objective is properly
The very minute hairs on the lining membrane of the
tongue, if examined by a $\frac{2}{3}$ objective and a narrow cone,
ckened, shorter, more blunted, and often split into two
is is shown in figs. 2 and 3 in the frontispiece. Fig. 3 is
mage magnified 510 diameters. A lens should be used to
his.

save that a cone of small angle, i.e. of 0·1, was used for illumination.

The first alteration which thrusts itself upon the eye is the *doubling* of the hairs, which are in the least degree out of focus. But further, it will be noted that there is a bright line with a dark edge round the hairs which are precisely in focus; this is a diffraction effect, always, in our experience, present in objects illuminated by cones of insufficient angle, and it can be easily made to disappear by widening the cone. As the illuminating cone is enlarged they become sharper and longer, and their edges become more definite. But nothing is gained, but the rather a distinct loss is incurred, by making the illuminating cone larger than the objective cone.

As an example of erroneous interpretation, the representation of the pygidium of a flea by some leading sources of information of a few years ago may be instanced. It was a special test of many authors, and has been carefully figured; this shows that it is not an accidental error, which it might have been if it were merely an ordinary object; it is an error depending in all probability on a faulty system of illumination. Moreover, the error cannot be attributed to the object-glasses of the time, as it is a low-power object, and the low powers of that day were quite as good as those lately in use. In the descriptions and in the drawings, often beautifully executed, the hairs proceeding from the centre of the wheel-like discs are represented as being 'stiff and longish bristles,' thick at one end and tapering off to a point. And the small hairs round are described as 'minute spines'; in the drawing they are like the spinous hairs of an insect and have the usual socket-joint at the base. In reality the 'stiff and longish bristle' is an extremely long and delicate filament, totally unlike a bristle, being not tapered but of nearly uniform thickness. The 'minute spines' are in reality very curious hairs, and, as far as we at present know, unlike any others. They are delicate, lambent, bulbous hairs. What they most resemble are the tentacles of a sea-anemone, and there are two tubes discoverable which are important and comparatively large objects. There appears to be considerable probability that this interesting object upon the last ring of the body of the flea, and known as its 'pygidium,' acts as an auditory instrument.[1] In the examination of ordinary stained histological and pathological sections by transmitted light, unless some very delicate point is sought, the condenser should have a stop so that when the back of the objective is examined the stop is seen cutting into the back of the objective by about a third. This in some instances may be increased to a half by diminishing the cone, but it is not advisable to use anything less than a half unless it is absolutely necessary. Thus, to put it in round numbers, an illuminating cone ·2 N.A. is very suitable for ordinary work with the apochromatic 1-inch and $\frac{2}{3}$ objectives, and one of ·4 N.A. for the $\frac{1}{2}$ and $\frac{1}{3}$ and one of ·6 N.A. for the $\frac{1}{4}$ and $\frac{1}{6}$. It is a good plan to have one or two stops cut to give special cones, the N.A. of which should be engraved on them. This subject is one of great importance, as more than nine-tenths

[1] *Micros. Journ.* April 24, 1885, 'Pygidium of Flea' (E. M. Nelson).

l be surrounded by a luminous border, which will give it appearance, and its fine point will be blurred out. Now iris until the last trace of that glaziness disappears. The l appear as a different object, its outline being perfectly clear rp. If the eye-piece is removed about two-thirds of the ob- ack will be full of light. Now, without disturbing any of the ents, replace the 1-inch by the $\frac{1}{2}$, and it will be found that the s or false light will have returned. Let the iris be further until the last trace of it disappears; now, on examination of : of the objective, two-thirds of it will be found full of light, and th the $\frac{1}{4}$. We call the attention of the student to these facts g a direct bearing upon the question of the comparative effects and small illuminating cones, and with no idea of offering z opinions to those of Professor Abbe, we have no direct it; but we record these facts as factors in and for the ion of the question. It is perhaps better to test the $\frac{1}{4}$ on the more minute hairs which are studded over the delicate embrane. The same results will be obtained. Thus it would o suggest itself that this 'glaziness' depends on the *relation erture of the illuminating cone to that of the objective cone.* omatic objectives behave precisely as achromatic objectives espect. Of course, if the hair becomes pale and indistinct on ing of the iris, it shows that there is uncorrected spherical on in the objective; another objective must therefore be used; eness has nothing whatever to do with the glaze or false light ed above.

hoto-micrographs of bacteria one frequently sees a white halo em. This in our hands has always resulted from the photo- aph having been taken with too small a cone of illumination. icrography with a small cone is quite easy, as great contrast ecured. With a large cone the difficulties begin—difficulties tment, difficulties of lens correction, difficulties of exposure,

whole insects are seen best with the Lieberkühn, and the binocular should be used for both.

Some of this class of objects are best seen under *double illumination*; that is, a *dark ground with a condenser* and light *thrown from above with a silver side-reflector*, as the Lieberkühn cannot be used in conjunction with an achromatic condenser. It is a good plan with low-power Lieberkühn work to interpose between the slip and the ledge a strip of plain glass $\frac{1}{2}$-inch wide: *this prevents the ledge stopping out light* from the Lieberkühn when it is larger in diameter than the slip.

Polarised light used with a condenser is very useful for insect work. For very low-power work—such as the usual botanical sections—it is a good plan to give up the cone, and place a piece of fine ground glass at the back of the condenser; and with lamp light it is as well to combine a piece of blue glass with it. With objectives of greater angle than ·6 N.A. it is usually difficult to get satisfactory illumination with a dark ground. The best that can be done is to use an oil-immersion condenser with a suitable stop: this will give a good dark ground up to ·65 N.A., but it will fail if the object is dry on the cover. Generally speaking, the only way of accomplishing this with objectives of wider aperture is to reduce the aperture of the objective by a stop placed at the back.

When a condenser is united by a film of oil to a slip, *if the slip is thin, the oil invariably runs down when the condenser is focussed.* The following is a method by which this may be entirely prevented. A piece of thick cover-glass about ·02 inch, and 1 inch square, has a strip of thicker glass $\frac{1}{8}$-inch broad, cemented by shellac to one edge. This piece of glass is oiled to the slip, the ledge being hooked over the top of the slide; this not only prevents its slipping down, but also keeps the oil from creeping out at the bottom, which would be the case if the two edges of the glass coincided.[1] This is illustrated in fig. 317.



Thin slip of glass with ledge to place glass slip with oil contact, so as to vary the thickness of a slide.



Slide *in situ* on thin slip with ledge.

FIG. 317.

In its proper place we have dealt with the suitable relation of aperture to power, and have pointed out the irresistible nature of the contentions and teachings of Abbe on the subject. Here a direct practical presentation of the matter may be of service to the student.

A normal unaided human eye can divide $\frac{1}{100}$ inch at ten inches. Consequently a microscope with a power of 200 should be capable of showing structure as fine as $\frac{1}{20000}$ inch. Now as this power can be made up by a $\frac{1}{2}$-inch objective and a 1-inch eye-piece, it follows that sufficient aperture ought to be given to the $\frac{1}{2}$-inch to enable it to resolve 50,000 lines per inch. This[2] will be ·52 N.A. The inch

[1] *Q. M. C. Journal*, November 1885.

[2] In reality it will require more, because an axial cone is assumed to be used instead of an oblique beam.

objective should have half this aperture, and the $\frac{1}{4}$ double, and the $\frac{1}{2}$ four times as much, if perfect vision is required; in other words, ·26 N.A. for every 100 diameters.[1] These ideals have (as we have before indicated) been realised, notably by the Zeiss apochromatics, the 1-inch and the $\frac{1}{2}$-inch[2] resolving everything capable of being appreciated by the eye when the 12 compensating eye-piece is used. The $\frac{1}{4}$-inch is also a near approach to the ideal, as it has been very wisely kept a dry lens. The $\frac{1}{8}$ with a 6 eye-piece also attains the ideal. This relation of aperture to power is very significant, and should be carefully pondered by those who still desire low apertures as only perfect form of objectives.

It is as well to mention that objectives may be arranged in two series—one the 2, 1, $\frac{1}{2}$, $\frac{1}{4}$, and $\frac{1}{8}$, the other $1\frac{1}{2}$, $\frac{2}{3}$, $\frac{1}{3}$, $\frac{1}{6}$, $\frac{1}{12}$. One of these series will form a complete battery, as it is unnecessary to have objectives differing from the next in the series by less than double the power.

The most usual combination is perhaps the 1 and the $\frac{1}{4}$ of one series, or the $\frac{2}{3}$ and the $\frac{1}{6}$ of the other. Of these two preference might rather be given to the last. The only exception would be the addition of a $1\frac{1}{2}$-inch for pond life.

Eye-pieces should also double the power thus: 5, 10, and 20 (uncompensated), or 6, 12, and 27 (compensated), the most useful of the three being the 10 (uncompensated) and the 12 (compensated). As there is no 6-power compensated eye-piece for the long tube, a 4 for the short tube admirably answers the purpose.

In addition to the explanations already given on the subject of testing objectives, it may be useful here to note that the qualities of an objective are seven in number:—

1. Magnifying power (initial).
2. Aperture or N.A.
3. Resolving power.
4. Penetrating power
5. Illuminating power.
6. Flatness of field.
7. Defining power.

1. *Magnifying power.*—No test is required, as the initial magnifying power can be directly measured.

2. *Aperture* or N.A. can be directly measured; no test is therefore necessary.

3. *Resolving power*, being directly proportional to N.A., is synonymous with it. No test is needful because N.A. can be measured.

4. *Penetrating power* is the reciprocal of the resolving power of $\frac{1}{\text{N.A.}}$. No test needed.

5 *Illuminating power* is the square of the numerical aperture $(\text{N.A.})^2$. No test is necessary.

[1] *English Mechanic*, vol. xxxviii. 1883, No. 979.—E. M. Nelson.

[2] This lens, with an 8 compensating eye-piece, will resolve a *Pleurosigma angulatum* with an axial cone: this is the lowest power with which it has ever been done.

6. *Flatness of field* is, in the strict meaning of the term, an optical impossibility. The best thing therefore is to contract the visible field as is done in the compensating eye-pieces. (Tests: For low powers a micro-photograph; for medium and high powers a stage micrometer.

7. *Defining power* depends on (*a*) the reduction of spherical aberration, (*b*) the reduction of chromatic aberration, (*c*) the perfect centring of the lenses—by which is meant (i.) the alignment of their optic axes, (ii.) the parallelism of their planes, (iii.) the setting of their planes at right angles to the optic axis.

Defining power can only be tested by a critical image. The following is a list of suitable objects of which a critical image is to be obtained, using a solid axial cone of illumination equal to at least three-fourths of the aperture of the objective.

Very low powers (3-, 2-, and 1½-inch).—Wing of *Agrion pulchellum* ♂ (dragon-fly).

Low powers (1 and ⅔).—Proboscis of blow-fly.

Medium powers (½, $\frac{4}{10}$, ⅓, and low-angled ¼).—Minute hairs on proboscis of blow-fly; hair of pencil-tail (*Polyxenus lagurus*); diatoms on a dark ground. This last is a most sensitive test; unless the objective is good there is sure to be false light.

Medium powers (with wide aperture).—*Pleurosigma formosum*; *Navicula lyra* in balsam or styrax; *Pleurosigma angulatum* dry on cover; bacteria and micrococci stained.

High powers (wide apertures and oil-immersion ⅛ and $\frac{1}{12}$.—The *secondary structure of diatoms*, especially the fracture through the perforations. *Navicula rhomboides from cherry field* in balsam or styrax; bacteria and micrococci stained.

Test with a 10 or 12 eye-piece, and take into account the general whiteness and brilliancy of the picture.

The podura scale is not mentioned as a test, as it may be very misleading in unskilled hands. One great point in testing objectives is to know your object. Care must be exercised to ascertain by means of vertical illuminator if objects such as diatoms dry on the cover are in optical contact with the cover-glass. Testing objectives is an art which can only be acquired in time and with experience gained by seeing large numbers of objectives.

In the manipulation of the microscope it is not uncommon to observe the operator *rolling* the milled head of the *fine adjustment* instead of firmly grasping it between the finger and thumb and governing, to the minutest fraction of arc, the amount of alteration he desires. It is undesirable and an entirely inexpert procedure to roll the milled head, and cannot yield the fine results which a delicate mastery of this part of the instrument necessitates and implies. To use aright the fine adjustment of a first-class microscope is not the first and easiest thing mastered by the tiro.

Beyond the correct and judicious use of the microscope and all its appliances, there is the matter of the *elimination of errors of interpretation* to be carefully considered.

The correctness of the conclusions which the microscopist will draw regarding the nature of any object from the visual appearances

be corrected, it is obvious, by general advance in scientific ledge; but the history of them affords a useful warning against conclusions drawn from a too cursory examination. If the ry of almost *any* scientific investigation were fully made known ould generally appear that the stability and completeness of the lusions finally arrived at had only been attained after many ifications, or even entire alterations, of doctrine. And it is efore of such great importance as to be almost essential to the ctness of our conclusions that they should not be finally formed announced until they have been tested in every conceivable e. It is due to science that it should be burdened with as few facts and false doctrines as possible. It is due to other truth-ers that they should not be misled, to the great waste of their and pains, by our errors. And it is due to ourselves that we ld not commit our reputation to the chance of impairment by premature formation and publication of conclusions which may t once reversed by other observers better informed than our-s, or may be proved to be fallacious at some future time, per-even by our own more extended and careful researches. The *ension of the judyment whenever there seems room for doubt* is son inculcated by all those philosophers who have gained the est repute for practical wisdom; and it is one which the micro-ist cannot too soon learn or too constantly practise. Besides these ral warnings, however, certain special cautions should be given to young microscopist with regard to errors into which he is liable e led even when the very best instruments are employed.

Errors of interpretation arising from the imperfection of the *adjustment* are not at all uncommon amongst microscopists, some of the most serious arise from the use of small cones of nination. With lenses of high power, and especially with those arge numerical aperture, it very seldom happens that all the s of an object, however minute and flat it may be, can be in s together; and hence, when the focal adjustment is exactly e for one part, everything that is not in exact focus is not only e or less indistinct, but is often wrongly represented. The in-inctness of outline will sometimes present the appearance of a acid border, which like the diffraction-band may be mistaken actual substance. But the most common error is that which is luced by the reversal of the lights and shadows resulting from the active powers of the object itself; thus, the bi-concavity of the od-discs of human (and other mammalian) blood occasions their

centres to appear *dark* when in the focus of the microscope, through the divergence of the rays which it occasions; but when they are brought a little within the focus by a slight approximation of the object-glass the centres appear brighter than the peripheral parts of the discs. The student should be warned against supposing that in all cases the most *positive* and *striking* appearance is the truest, for this is often not the case. Mr. Slack's *optical illusion*, or *silica-crack slide*,[1] illustrates an error of this description. A drop of water holding colloid silica in solution is allowed to evaporate on a glass slide, and when quite dry is covered with thin glass to keep it clean. The silica deposited in this way is curiously cracked, and the *finest* of these cracks can be made to present a very positive and deceptive appearance of being raised bodies like glass threads. It is also easy to obtain diffraction-lines at their edges, giving an appearance of duplicity to that which is really single.

A very important and very frequent source of error, which sometimes operates even on experienced microscopists, lies in the refractive influence exerted by certain peculiarities in the internal structure of objects upon the rays of light transmitted through them, this influence being of a nature to give rise to appearances in the image, which suggest to the observer an idea of their cause that may be altogether different from the reality. Of this fallacy we have a 'pregnant instance' in the misinterpretation of the nature of the *lacunæ* and *canaliculi* of bone, which were long supposed to be solid corpuscles with radiating filaments of peculiar opacity, instead of being, as is now universally admitted, minute chambers with diverging passages excavated in the solid osseous substance. When Canada balsam fills up the excavations, being nearly of the same refractive power with the bone itself, it obliterates them altogether. So, again, if a person who is unaccustomed to the use of the microscope should have his attention directed to a preparation mounted in liquid or in balsam that might chance to contain *air-bubbles*, he will be almost certain to be so much more strongly impressed by the appearances of these than by that of the object, that his first remark will be upon the number of strange-looking black rings which he sees, and his first inquiry will be in regard to their meaning.

Although no experienced microscopist could now be led astray by such obvious fallacies as those alluded to, it is necessary to notice them as warnings to those who have still to go through the same education. The best method of learning to appreciate the class of appearances in question is the comparison of the aspect of globules of oil in water with that of globules of water in oil, or of bubbles of air in water or Canada balsam. This comparison may be very readily made by shaking up some oil with water to which a little gum has been added, so as to form an emulsion, or by simply placing a drop of oil of turpentine (coloured with magenta or carmine) and a drop of water together upon a slide, laying a thin glass cover over them, and then moving the cover backwards and

[1] *Monthly Microscopical Journal*, vol. v. 1872, p. 14.

forwards several times on the slide. Equally instructive are the appearances of an air-bubble in water and Canada balsam.

The figures which illustrate the appearance at various points of the focus of an air-bubble in water and Canada balsam, and of a fat-globule in water, may be thus illustrated, viz. a diaphragm of about $\frac{2}{3}$ of a mm. being placed at a distance of 5 mm. beneath the stage, and the concave mirror exactly centred.

Air-bubbles in water.—No. 1 (fig. 318) represents the different appearances of an air-bubble in water. On focussing the objective



FIG. 318.—Air-bubbles in (1) water, (2) Canada balsam; (3) fat-globules in water.

to the middle of the bubble (B), the centre of the image is seen to be very bright—brighter than the rest of the field. It is surrounded by a greyish zone, and a somewhat broad black ring interrupted by one or more brighter circles. Round the black ring are again one or more concentric circles (of diffraction), brighter than the field.

On focussing to the bottom of the bubble (A) the central white circle diminishes and becomes brighter: its margin is sharper, and it is surrounded by a very broad black ring, which has on its periphery one or more diffraction circles.

When the objective is focussed to the upper surface of the

bubble (C) the central circle increases in size, and is surrounded by a greater or less number of rings of various shades of grey, around which is again found a black ring, but narrower than those in the previous positions of the objective (A and B). The outer circles of diffraction are also much more numerous.

Air-bubbles in Canada Balsam.—Canada balsam being of a higher refractive index than water, the limiting angle instead of being 48° 35′ is 41° only, so that the rays which are incident much less obliquely on the surface of separation undergo total reflexion, and it will be only those rays which face very close to the lower pole of the bubble that will reach the eye, and the black marginal zone will therefore be much larger. This is shown in fig. 319, No 2.

When the objective is focussed to the bottom of the bubble (A′), we have a small central circle, brighter than the rest of the field, all the rest of the bubble being black, with the exception of some peripheral diffraction rings. On focussing to the centre (B′) or upper part (C′) of the bubble, we have substantially the same appearances as in B and C, with the exception of the smaller size of the central circle.

Fat-globules in water (fig. 318, No. 3).—These illustrate the case of a highly refracting body in a medium of less refractive power.

When the objective is adjusted to the bottom of the globule A″, it appears as a grey disc a little darker than the field, and separated from the rest of the field by a darkish ring.

Focussing to the middle of the bubble (B″), the central disc becomes somewhat brighter, and is surrounded by a narrow black ring, bordered within and without by diffraction circles.

On further removing the objective the dark ring increases in size, and when the upper part of the objective is in focus, we have (C″) a small white central disc, brighter than the rest of the field, and sharply limited by a broad, dark ring which is blacker towards the centre.

These appearances are the converse of those presented by the air-bubble. That, as we saw, has a black ring and a white centre, which are the sharper as the objective is approached to the lower pole of the bubble. The fat-globule has, however, a dark ring which is the broader, and a centre which is the sharper, according as the objective is brought nearer to the upper pole.

These considerations, apart from their enabling us to distinguish between air-bubbles and fat-globules, and preventing their being confounded with the histological elements, enable two general principles to be established, viz. bodies which are of greater refractive power than the surrounding medium have a white centre which is sharper and smaller, and a black ring which is larger when the objective is withdrawn; whilst those which are of less refractive power have a centre which is whiter and smaller, and a black ring which is broader and darker when the objective is lowered.

Monochromatic Light.—The same phenomena are observed by yellow monochromatic light, except that the diffraction fringes are more distinct, further apart, and in greater numbers than with ordinary light.

ıere is no source of fallacy to a certain class of workers so
ɔe guarded against as that arising from errors in the inter-
concerning movement as such, *and especially concerning*
ıent exhibited by certain very minute particles of matter in
suspension in fluids. The movement was first observed in
ranular particles which exist in great abundance in the
ɔf pollen grains of plants known as the *fovilla*, and which
ɔe by crushing the pollen. It was first supposed that they
some special vital movement analogous to the motion of the
ɔa of animals. But it was discovered in 1827, by Dr. Robert
ıat inorganic substances in a state of fine trituration would
ıame result; and it is now known that all substances in a
y fine state of powder are affected in the same manner, one
ɔst remarkable being the movement visible in the contents
ıid cavities in quartz in the oldest rocks. These have
retained their dancing motion for æons. A good illustra-
amboge, which can be easily rubbed from a water-colour
n a glass slip and covered, and will at once show the
istic movement; so will carmine, indigo, and other similarly
es. But the metals which are from seven to twenty times
as water require to be reduced to a state of minuteness
es greater; but, triturated finely enough, these also show
ment for a long time known, from the name of its discoverer,
ian movement, but now more generally called *pedesis*.
ıovement is chiefly of an *oscillatory* nature, but the particles
e backwards and forwards on their axes, and gradually (if
ly watched) *change their places* in the field of view. It is an
r characteristic movement, and could not be mistaken for
motion by an observer acquainted with both; but the
ıust familiarise himself with this kind of motion or he will
r unable to distinguish certain kinds of motion in minute
ms in certain stages of their life from this movement, and

pedesis) extremely well. But none of the particles he has examined are so active as those of pumice-stone that has been ground up in an agate mortar; for these are seen under the microscope to leap and swarm with an incessant quivering movement, so rapid that it is impossible to follow the course of a particle which probably changes its direction of motion fifteen or twenty times in a second. The distance through which a particle moves at any one bound is usually less than $\frac{1}{3000}$th of an inch. This 'Brownian movement' (as it is commonly termed) is not due to evaporation of the liquid, for it continues without the least abatement of energy in a drop of aqueous fluid that is completely surrounded by oil, and is therefore cut off from all possibility of evaporation; and it has been known to continue for many years in a small quantity of fluid enclosed between two glasses in an air-tight case; and for the same reason it can scarcely be connected with the chemical change. But the observations of Professor Jevons (*loc. cit.*) show that it is greatly affected by the admixture of various substances with water, being, for example, increased by a small admixture of gum, while it is checked by an extremely minute admixture of sulphuric acid or of various saline compounds, these (as Professor Jevons points out) being all such as increase the conducting power of water for electricity. The rate of subsidence of finely divided clays or other particles suspended in water thus greatly depends upon the activity of their 'Brownian movement,' for when this is brought to a stand the particles aggregate and sink, so that the liquid clears itself.[1]

Pedetic motion depends on, that is, is affected by—

1. The *size* of the particles.

2. *The specific gravity of the particles.* Metals, or particles of vermilion, of similar size to particles of silica or gamboge, move much more slowly and less frequently.

3. *The nature of the liquid.* No liquid stops pedesis, but liquids which have a chemical action on the substance do. This action may be very slow, still it tends to agglomerate the particles. For instance, barium sulphate, when precipitated from the cold solution, takes a long time to settle; whereas, when warm and in presence of hydrochloric acid, agglomeration soon occurs. Iron precipitated as hydrate in presence of salts of ammonium, and mud in salt water, are other instances. The motion does not cease, but the particles adhere together and move very slowly.

But besides the right appreciation of the nature of pedesis, there is the utmost caution required in the interpretation of the *rapidity of movement, and kind of movement* which living and motile forms effect.

The observation of the phenomena of motion under the microscope[2] has led to many false views as to the nature of these movements. If, for instance, swarm-spores are seen to traverse the field of view in one second, it might be thought that they race through the water at the speed of an arrow, whereas they in reality traverse in that time only a third part of a millimetre, which is somewhat more than

[1] See also the Rev. J. Delsaulx 'On the Thermo-dynamic Origin of the Brownian Motions' in *Monthly Journ. of Microsc. Sci.* vol. xviii. 1877.

[2] *Das Mikroskop*, Naegeli and Schwendener, p. 258 (Eng. edit.).

a metre in a hour. It must not, therefore, be forgotten that the rapidity of motion of microscopical objects is only an apparent one, and that its accurate estimation is only possible by taking as our standard the actual ratio between time and space. If we wish, for the sake of exact comparison, to estimate the magnitude of the moving bodies, we may always do so; the ascertainment of the real rapidity remains, however, with each successive motion, the principal matter.

If a screw-shaped spiral object, of slight thickness, revolves on its axis in the focal plane, at the same time moving forward, it presents the deceptive appearance of a serpentine motion. Thus it is that the horizontal projections of an object of this kind, corresponding to the successive moments of time, appear exactly as if the movement were a true serpentine one. As an example of an appearance of this nature, we may mention the alleged serpentine motion of Spirillum and Vibrio.

Similar illusions are also produced by swarm-spores and spermatozoa; they appear to describe serpentine lines while in reality they move in a spiral. It was formerly thought that a number of different appearances of motion must be distinguished, whereas modern observers have recognised most of them as consisting of a forward movement combined with rotation, where the revolution takes place sometimes round a central, and sometimes round an eccentric, axis. To this category belong, for instance, the supposed oscillations of the *oscillaricæ*, whose changes of level, when thus in motion, were formerly unnoticed.

In addition to these characteristics of a spiral motion it must, of course, be ascertained whether it is right- or left-handed. To distinguish this in spherical or cylindrical bodies, which revolve round a central axis, is by no means easy, and in many cases, if the object is very small and the contents homogeneous, it is quite impossible. The slight variations from cylindrical or spherical form, as they occur in each cell, are therefore just sufficient to admit of our perceiving whether any rotation does take place. The discovery of the direction of the rotation is only possible when fixed points whose position to the axis of the spiral is known can be followed in their motion round the axis. The same holds good also, *mutatis mutandis*, of spirally wound threads, spiral vessels, &c.; we must be able to distinguish clearly which are the sides of the windings turned towards or turned away from us.

Fig. 319.—A spiral in motion.

If the course of the windings is very irregular, as in fig. 319, a little practice and care are needed to distinguish a spiral line as such in small objects. The microscopical image might easily lead us to the conclusion that we were examining a cylindrical body composed of bells or funnels inserted one in another. The spirally thickened threads, for instance, as they originate from the epidermis cells of many seeds, were thus inter-

preted, although here and there by the side of the irregular spirals quite regular ones are also observed.

Moreover, it must not be forgotten that in the microscopical image a spiral line always appears wound in the same manner as when seen with the naked eye, while in a mirror (the inversion being only a half one) a right-handed screw is obviously represented as left-handed, and conversely. If, therefore, the microscopical image is observed in a mirror, as in drawing with the Sömmering mirror, or if the image-forming pencils are anywhere turned aside by a single reflexion, a similar inversion takes place from right-handed to left-handed, and this inversion is again cancelled by a second reflexion, in some microscopes. All this is, of course, well known, and to the practised observer self-evident; nevertheless many microscopists have shown that they are still entirely in the dark about matters of this kind.

One of Professor Abbe's experiments *on diffraction phenomena* proves that when the diffraction spectra of the first order are stopped out, while those of the second are admitted, the appearance of the structure will be double the fineness of the actual structure which is causing the interference.[1]

Upon this law there appears to depend a number of possible fallacies, errors which may arise from either its misapprehension or misinterpretation. At least these appear to us, from a practical point of view, to be of sufficient importance to need either caution or a fuller exposition of the great law of Abbe in regard to them.

If, for example, figs. 320, 321, and 322 may be taken to represent a square grating having 25,000 holes per linear inch at the focus of an objective at P, P D the dioptric beam, P^1 P^1 diffraction spectra of the first order, and P^2 P^2 those of the second order, then if the objective is aplanatic all those spectra will be brought to an identical focal conjugate; and the image of the grating will be a counterpart of the structure, characteristic of such a group of spectra. Let us suppose our objective to be over-corrected, as in fig. 321, then when the grating is focussed at P *the spectra of the first order only will be brought to the focal conjugate*; the image, however, will not be materially affected on that account, as the diffraction elements of the first order are alone sufficient to give a truthful representation of the 25,000 per inch grating. If, however, the objective be raised so that the grating lies at P' *the diffraction elements of the second order only are brought to the focal conjugate*: consequently by the hypothesis the image will have 50,000 holes per linear inch, or double that of the original. In other words, placing a grating at the longer focus of an over-corrected objective is apparently tantamount to cutting out the diffraction spectra of the first order by a stop at the back of the objective.



FIG. 320.



FIG. 321.

[1] See Chapter II.

The effect of this is to give an impression that there is a strong rating with 25,000 holes per linear inch ; and over it *another* grating with 50,000 holes per linear inch. The raising the focus so as to bring P to P′ necessarily gives the idea of the fine structure being superimposed on the coarse. Therefore the microscopist should beware whenever he notices a structure of double fineness over another one lest he has a condition of things similar to fig. 321. The following is a test which may be applied to confirm the genuineness of any such structure. First measure by means of the divided head of the fine-adjustment screw as accurately as possible, the movement required to bring P to P′ in fig. 321 ; next by means of the draw-tube increase the distance between the eye-piece and the objective : this will have the effect of increasing the over-correction of the objective, and a state of things will be obtained as in fig. 322. Hence it will require a larger movement of the fine-adjustment screw to bring P to P′. This will make the distance between the 50,000 grating and the 25,000 grating appear greater than it was before. *If this takes place the* 50,000 *grating is a mere diffraction ghost.*



Fig. 322.

A precisely similar condition of things exists with an under-corrected objective, only in that case the false finer grating will appear below the original coarse grating, and to increase the distance between them the draw-tube must be shortened.[1]

It may therefore be of service to give an example of the use of the numerical aperture table as a check in the interpretation of structure.

Fig. 323 gives six illustrations of the back of an objective (the eye-piece being removed) of ·83 N.A., or 112° in air : D stands for



Fig. 323.

dioptric beam ; 1 for diffraction spectrum of the first order ; 2 for diffraction spectrum of the second order.

[1] It is well to note here that we have seen a photo-micrograph by Mr. Comber of a diatom surface which is uneven. In those parts in correct focus the structure is single, but in the parts where the focus is withdrawn it is doubled.

When the back of an objective of ·83 N.A. shows an arrangement as in

No. 1	then, although the structure will be invisible, it cannot be coarser than . . .	40,000	per inch.
No. 2	„ „ „	80,000	„
No. 3	then the structure does not differ greatly from	40,000	„
No. 4	„ „ „	80,000	„
No. 5	„ „ „	20,000	„
No. 6	„ „ „	40,000	„

It will be understood by the student that the *preservation of the microscope* and its apparatus is a matter that must largely depend upon his own action. The stand should be kept from dust, generally wiped with a soft chamois leather after use, and when needful a minute quantity of watchmaker's oil may be put to a joint working stiffly. There is no better way to preserve this stand than to keep it either under a bell-glass or in a cabinet which is easily accessible.

All objectives should be examined after use, and all oils or other fluids carefully wiped away from them with old cambric which has been thoroughly washed with soda, well rinsed and not 'ironed' or finished in any way, but simply dried.

If chemical reagents are employed the cessation of their use should become the moment for wiping the lenses employed with care; and all processes involving the use of the vapours of volatile acids, or which develop sulphuretted hydrogen, chlorine, &c. must never take place in a room in which a microscope of any value is placed.

Dry elder-pith and Japanese paper are by some workers suggested for cleaning the front lenses of homogeneous objectives; but while these are excellent, especially the former, we find nothing better than the simple cambric we suggest.

Two or three good chamois leathers should be kept by the worker for specific purposes and not interchanged. Cleanliness, care, delicacy of touch, and a purpose to be accurate in all that he does or seeks to do, are essentials of the successful microscopist.

It may be noted that dust on the eye-piece can be detected in a dim light, and can be discovered by closing the iris diaphragm. The lens of the eye-piece on which the dust appears may be localised by rotation; and this should be done before wiping. In reference to dust on the back of the objective, it should be observed that if the eye-piece be removed, dust sometimes appears to be upon it which comes really from the focus of the sub-stage condenser, and is, in fact, not on the back of the objective at all. To find this condition, remove the light modifier (if in use), for the dust may be on it, and rotate the condenser; else there will be needless and injurious rubbing of the back-lens of the objective.

With oil-immersion objectives dust or air-bubbles in the oil must be carefully avoided.

If chamois leather be used for cleaning the lenses, it should be previously well beaten and shaken, and then kept constantly in a well-made box.

CHAPTER VII

PREPARATION, MOUNTING, AND COLLECTION OF OBJECTS

UNDER this head it is intended to give an account of those materials, instruments, and appliances of various kinds, which have been found most serviceable to microscopists engaged in general biological research, and to describe the most approved methods of employing them in the preparation and mounting of objects for the display of the minute structures thus brought to our knowledge. Not only is it of the greatest advantage that the discoveries made by microscopic research should—as far as possible—be embodied (so to speak) in 'preparations,' which shall enable them to be studied by everyone who may desire to do so, but it is now universally admitted that such 'preparations' often show so much more than can be seen in the fresh organism that no examination of it can be considered as complete in which the methods most suitable to each particular case have not been put in practice. It must be obvious that in a comprehensive treatise like the present such a *general* treatment of this subject is all that can be attempted, excepting in a few instances of peculiar interest; and as the histological student can find all the guidance he needs in the numerous manuals now prepared for his instruction, the Author will not feel it requisite to furnish him with the *special* directions that are readily accessible to him elsewhere.

MATERIALS, INSTRUMENTS, AND APPLIANCES.

Glass Slides.—The kind of glass best suited for mounting objects is that which is known as 'patent plate,' and it is now almost invariably cut, by the common consent of microscopists in this country, into slips measuring 3 in. by 1 inch. For objects too large to be mounted on these the size of 3 in. by 1½ in. may be adopted. Such slips may be purchased, accurately cut to size, and ground at the edges, for so little more than the cost of the glass that few persons to whom time is an object would trouble themselves to prepare them; it being only when glass slides of some unusual dimensions are required, or when it is desired to construct 'built-up cells,' that a facility in cutting glass with a glazier's diamond becomes useful. The glass slides prepared for use should be free from veins, air-bubbles, or other flaws, at least in the central part on which the object is placed; and any whose defects render them unsuitable for ordinary purposes should be selected and laid aside for uses to which the

working microscopist will find no difficulty in putting them. As the slips vary considerably in thickness, it will be advantageous to determine on a gauge for *thin*, *thick*, and *medium* glass. The first may be employed for mounting delicate objects to be viewed by the high powers with which the apochromatic and achromatic condensers are to be used, so as to allow plenty of room for the focal point of an optical combination with great aperture to be fixed readily upon the plane of the object; the second should be set aside for the attachment of objects which are to be ground down, and for which, therefore, a stronger mounting than usual is desirable; and the third are to be used for mounting ordinary objects. Great care should be taken in washing the slides, and in removing from them every trace of greasiness by the use of a little soda or potass solution. If this should not suffice they may be immersed in the solution recommended by Dr. Seiler, composed of 2 oz. of bichromate of potass, 3 fl. oz. of sulphuric acid, and 25 oz. of water, and afterwards thoroughly rinsed. (The same solution may be advantageously used for cleansing cover-glasses.) Before they are put away the slides should be wiped perfectly dry, first with an ordinary 'glass cloth,' and afterwards with an old cambric handkerchief; and before being used, each slide should be washed in methylated spirit to ensure freedom from greasiness. Where slides that have been already employed for mounting preparations are again brought into use, great care should be taken in completely removing all trace of adherent varnish or cement—first by scraping (care being taken not to scratch the glass), then by using an appropriate solvent, and then by rubbing the slide with a mixture of equal parts of alcohol, benzole, and liquor sodæ, finishing with clean water.

Thin Glass.—The older microscopists were obliged to employ thin laminæ of *talc* for covering objects to be viewed with lenses of short focus; but this material, which was in many respects objectionable, is entirely superseded by the thin glass manufactured by Messrs. Chance, of Birmingham, which may be obtained of various degrees of thickness, down to the $\frac{1}{500}$th of an inch. This glass, being unannealed, is very hard and brittle, and much care and some dexterity are required in cutting it; hence covers should be purchased, as required, from the dealers, who usually keep them in several sizes and supply any others to order. Save the fact that 'cover-glass' is made by Messrs. Chance, there is no definite information as to the mode of its manufacture and the conditions upon which it is most satisfactorily produced. It would be an advantage to the microscopist to possess information on this point. The different thicknesses are usually ranked as 1, 2, and 3; the first, which should not exceed in thickness the ·006 in., being used for covering objects to be viewed with *low* powers; the second, which should not exceed ·005 in. in thickness, for objects to be viewed with *medium* powers; and the third, which ought never to exceed ·004 in. in thickness, for objects which either require or may be capable of being used with *high* powers. It must, however, be remembered that the achromatic objectives of great power and great aperture (1·5) will require much thinner covers than even this. The thinnest glass is of course most difficult to

handle safely, and is most liable to fracture from accidents of various kinds; and hence it should only be employed for the purpose for which it is absolutely needed. The thickest pieces, again, may be most advantageously employed as covers for large cells, in which objects are mounted in fluid to be viewed by the low powers whose performance is not sensibly affected by the aberration thus produced. The working microscopist will find it desirable to provide himself with some means of measuring the thickness of his cover-glass; and this is especially needed if he is in the habit of employing objectives without adjustment, which are corrected to a particular standard. A small screw-gauge of steel, made for measuring the thickness of rolled plates of brass, and sold at the tool-shops, answers this purpose very well; but Ross's *lever of contact* (fig. 324), devised for this express purpose, is in many respects preferable. This consists of a small horizontal table of brass, mounted upon a stand, and having at one end an arc graduated into twenty divisions, each of which represents the $\frac{1}{1000}$th of an inch, so that the entire arc measures the $\frac{1}{50}$th of an inch; at the other end is a pivot on which moves a long and



FIG. 324.—Ross's lever of contact.

delicate lever of steel, whose extremity points to the graduated arc, whilst it has very near its pivot a sort of projecting tooth, which bears it against a vertical plate of steel that is screwed to the horizontal table. The piece of thin glass to be measured being inserted between the vertical plate and the projecting tooth of the lever, its thickness in thousandths of an inch is given by the number on the graduated arc to which the extremity of the lever points. Thus, if the number be 8, the thickness of the glass is ·008, or the $\frac{1}{125}$th of an inch. It will be found convenient to sort the covers according to their thicknesses, and to keep the sortings apart, so that there may be a suitable thickness of cover for each object. But it is well to remember that, with the exception of objects to which from their size or nature it is impossible to apply high powers, it is better to mount the object so that if it be required or desirable high powers may be used upon it.

Another simple and very efficient cover-glass tester is made by Zeiss, of Jena, and illustrated in fig. 325. It will be seen that the measurement is effected by a clip projecting from a box, between the jaws of which the cover to be measured is placed; the reading is given by an indicator moving over a divided circle on the upper face of the box. The divisions show hundredths of a millimètre, and the instrument measures to upwards of 5 mm.

It is well to keep assorted measured and cleaned cover-glasses in small separate wide-stoppered bottles of methylated spirit, each bottle being labelled with the gauge of thickness of the covers it contains. What is then required is a simple apparatus for cleaning the delicate covers with the least risk of breakage. This can be well accomplished by having two blocks of boxwood, shaped so as to be easily held one in each hand, turned with perfect trueness on the faces opposite to the respective handles, so that when the surfaces so flattened are laid upon and pressed towards each other they are everywhere in perfect contact. They should be from two to four inches in diameter, and these flattened surfaces should each have very tightly stretched upon them a firm, even-textured, moderately thick piece of chamois leather. If covers be slightly moistened—even breathed upon—and laid on one of these blocks and pressed down with the other, breath, or moisture applied by a small camel-hair brush to the upper surface of the cover, may be applied, and a few twists of these blocks upon each other when firmly pressed together will effectually clean without breaking the thinner covers. It will be often needful to treat both sides of the covers thus, as one side generally adheres while the other is subject to the friction.

FIG. 325.—Zeiss's cover-glass tester.

For cleaning slips and covers by hand, finishing should be done with old fine cambric handkerchiefs. These should not be washed with soap, but with common soda and hot water, plenty of the latter being subsequently employed to get rid of every trace of the alkali. But when dry these cloths must not be 'ironed' or smoothed in any way, the 'rough-dry' surface acting admirably for wiping delicate glass.

Varnishes and Cements.—There are three very distinct purposes for which cements which possess the power of holding firmly to glass, and of resisting not merely water but other preservative liquids, are required by the microscopist, these being (1) the attachment of the glass covers to the slides or cells containing the object, (2) the formation of thin 'cells' of cement only, and (3) the attachment of the 'glass plate' or 'tube-cells' to the slides. The two former of these purposes are answered by liquid cements or *varnishes*, which may be applied without heat; the last requires a *solid cement* of greater tenacity, which can only be used in the melted state. Among the many such cements that have been recommended by different workers, two or three will be selected by the worker for general purposes, and perhaps three or four for special purposes, and the remainder will be in practice neglected. We do not hesitate to say

that the two cements on which the most complete trust may be reposed are *japanner's gold size* and *Bell's cement*. This opinion is the result of over twenty years of special observation.

A *good varnish* may easily, in a general way, be tested: when it is thoroughly hard and old, if scraped off it comes away in shreds; unsafe varnishes break under the scraper in flakes and dust. To those who put up valuable preparations and objects of value the risk should never be run of using a new and unknown varnish or cement. Neither appearance nor facility nor cheapness in use should for one moment weigh against a varnish or cement of known and tested worth.

Japanner's gold-size may be obtained from the colour shops. It may be used for closing-in mounted objects of almost any description. It takes a peculiarly firm hold of glass, and when dry it becomes extremely tough without brittleness. When new it is very liquid and 'runs' rather too freely; so that it is often advantageous to leave open for a time the bottle containing it until the varnish is somewhat thickened. By keeping it still longer, with occasional exposure to air, it is rendered much more viscid, and though such 'old' gold-size is not fit for ordinary use, yet one or two coats of it may be advantageously laid over the films of newer varnish, for securing the thicker covers of large cells. Whenever any other varnish or cement is used, either in making a cell or in closing it in, the rings of these should be covered with one or two layers of gold-size extending beyond it on either side, so as to form a continuous film extending from the marginal ring of the cover to the adjacent portion of the glass slide.

Asphalte Varnish.—This is a black varnish made by dissolving half a drachm of caoutchouc in mineral naphtha, and then adding 4 oz. of asphaltum, using heat if necessary for its solution. It is very important that the asphaltum should be genuine, and the other materials of the best quality. Some use asphalte as a substitute for gold-size; but the Author's experience leads him to recommend that it should only be employed either for making shallow 'cement cells' or for finishing off preparations already secured with gold-size. For the former purpose it may advantageously be slightly thickened by evaporation.

Bell's cement is sold by J. Bell and Co. chemists, Oxford Street, London; they are the sole makers and retain the secret of its composition. It is of great service for glycerin mounts; but the edge of the cover should be ringed with glycerin jelly before this cement is applied. It is an extremely useful and reliable varnish, which is extremely easy of manipulation. It can be readily dissolved in either ether or chloroform.

Canada balsam is the oleo-resin from *Abies balsamea* and *Pinus canadensis*; it is so brittle when hardened by time that it cannot be safely used as a cement, except for the special purpose of attaching hard specimens to glass, in order that they may be reduced by grinding &c. Although fresh, soft balsam may be hardened by heating it on the slide to which the object is to be attached, yet it may be preferably hardened *en masse* by exposing it in a shallow vessel to

the prolonged but moderate heat of an oven, until so much of it volatile oil has been driven off that it becomes *almost* (but not quite) resinous on cooling. If, when a drop is spread out on a glass and allowed to become quite cold, it is found to be so hard as to be readily indented by the thumb-nail, and yet not so hard as to chip, it is in the best condition to be used for cementing. If too hard it will require a little more hardening on the slide, to which it may be transferred in the liquid state, being brought to it by the heat of a water-bath; if too hard it may be dissolved in chloroform or benzole for use as a mounting 'medium'; we do not recommend this for mounts with glycerin.

Brunswick black is a very useful cement, obtainable of the optician's as prepared for the use of microscopists. It is one of the best cements for the purpose of ringing mounts, and it may be recommended for turning cells. We have already stated that we do not, as a rule, recommend opaque or black ground mounting; but when this is desired or needful no better 'ground' can be obtained than by putting on the centre of the slide a disc of Brunswick black the size of the outside of the cell or cover-glass, and while it is wet putting a thin cover-glass upon it. The cover-glass becomes quickly fixed and a pleasant surface is formed to receive the object which it is intended to mount. Should it be desirable to have the floor of the opaque cell dead instead of bright, this can be quickly accomplished with a little emery-powder and water applied to the surface by a flattened block of tin fixed in boxwood.

Brunswick black is soluble in oil of turpentine, and it dries quickly.

Glue and honey mixed in equal parts is very valuable for special purposes and softens with heat.

Shellac cement is made by keeping small pieces of picked shellac in a bottle of rectified spirit, and shaking it from time to time. It cannot be recommended as a substitute for any of the preceding, but it may be employed to put a thin film upon the edge of *all* mounts—however closed and finished—that are to be used with homogeneous lenses. It is a sure protection against the otherwise injurious action of the cedar oil. Hollis's liquid glue may also be employed with confidence for this purpose.

Sealing-wax varnish, which is made by digesting powdered sealing-wax at a gentle heat in alcohol, should never be used as a cement; it is serviceable only as a varnish, and resists cedar oil.

Venice turpentine is the liquid resinous exudation of *Abies larix*. It must be dissolved in enough alcohol to filter readily, and after filtering must be placed in an evaporating dish, and by means of a sand-bath must be reduced by evaporation one-fourth.

This cement is used for closing glycerin mounts. Square covers are used, and we find it best to edge the cover with glycerin jelly. A piece of copper wire of No. 10 to No. 12 gauge is taken, and one end of it is bent just the length of one of the sides of the cover at right angles to the length of the wire. This end is now heated in a spirit lamp, plunged into the cement, which adheres in fair quantity, and is instantly brought down upon the slide and the margin of the

. The fluid turpentine distributes itself evenly along the cover l and hardens at once. We have no long experience of it, some of its characteristics we are inclined to believe it will useful cement for this purpose.

glue, which is composed of shellac, caoutchouc, and is distinguished by its extraordinary tenacity, and by its sisting solvents of almost every kind. Different qualities stance are made for the several purposes to which it is ap- the one most suitable to the wants of the microscopist n commerce as G K 4. The special value of this cement, nly be applied hot, is in attaching to glass slides the glass s which thus form 'cells' for the reception of objects nted in fluid, no other cement being comparable to it hacity or for durability. The manner of so using it will esc. y described.

ou *coloured* varnishes are used to give a finish to mounted s, or to mark on the covering glasses of large preparations containing special kinds of noteworthy structure. A g *black* varnish of this kind is made by working up very po dered lamp-black with gold-size. For *red*, sealing-wax sh may be used; but it is very liable to chip and leave the glass hardened by time. The red varnish specially prepared for scopic purposes by Messrs. Thompson and Capper, of Liverpool, likely to stand better. For white, 'zinc cement' answers well, is made of benzole, gum dammar, oxide of zinc, and turpentine. t is inexpensive, and either in Cole's or Ziegler's formula may tained at the optician's. Blue or green pigments may be worked ith this if cements of those colours be desired.

or attaching labels to slides either of glass or wood, and for down small objects to be mounted 'dry' (such as *foraminifera*, of insects, &c.), the Author has found nothing preferable to a r thick mucilage of gum arabic, to which enough glycerin has added to prevent it from drying hard, with a few drops of some tial oil to prevent the development of mould. The following ila has also been recommended: Dissolve 2 oz. of gum arabic oz. of water, and then add ¼ oz. of soaked gelatin (for the ion of which the action of heat will be required), 30 drops of rin, and a lump of camphor. The further advantage is gained ne addition of a slightly increased proportion of glycerin to r of the foregoing, that the gum can be very readily softened by , so that covers may be easily removed (to be cleansed if sary) and the arrangement of objects (where many are mounted her) altered.

lls for Dry-mounting.—Where the object to be mounted 'dry' ot immersed either in fluid or in any 'medium') is so thin as to re that the cover should be but little raised above the slide, ment cell' answers this purpose very well; and if the ap- ion of a gentle warmth be not injurious, the pressing down of over on the softened cement will help both to fix it and to nt the varnish applied round its border from running in. e a somewhat deeper cell is required, Prof. H. L. Smith

(U.S.A.) suggests the following specially for the mounting of diatoms. A sheet of thin writing paper dipped into thick shellac varnish is hung up to dry; and rings are then cut out from it by punches of two different sizes. One of these rings being laid on a glass slide, and the cover, with the object dried upon it, laid on the ring, it is to be held in its place by the forceps or spring-clip, and the slide gently warmed so as to cause a slight adhesion of the cover to the ring, and of the ring to the slide; and this adhesion may then be rendered complete by laying another glass slide on the cover and pressing the two slides together, with the aid of a continued gentle heat. Still deeper cells may be made with rings punched out of tinfoil of various thicknesses and cemented with shellac varnish on either side. And if yet deeper cells are needed, they may be made of turned rings of vulcanite or ebonite, cemented in the same manner. There is, however, a tendency in shellac-formed cells to throw off a cloudiness inside the cell, usually called 'sweating,' which is very undesirable. It has been found that a ring of solid paraffin to which the cover is attached, if first 'ringed' with the same material, and afterwards with a finishing varnish, makes a useful and permanently clean dry shallow cell; or paper may be saturated with paraffin and treated as described for shellac.

Cement-cells.—Cells for mounting *thin* objects in any watery medium may be readily made with asphalte or Brunswick black varnish by the use of Mr. Shadbolt's 'turn-table' or one of its modifications (p. 391). The glass slide being placed under its spring, in such a manner that its two edges shall be equidistant from the centre (a guide to which position is afforded by the circles traced on the brass), and its four corners equally projecting beyond the circular margin of the plate, a camel's-hair pencil dipped in the varnish is held in the right hand, so that its point comes into contact with the glass over whichever of the circles may be selected as the guide to the size of the ring. The turn-table being made to rotate by the application of the left forefinger to the milled head beneath, a ring of varnish, of a suitable breadth, is made upon the glass; and if this be set aside in a horizontal position, it will be found, when hard, to present a very level surface. If a greater thickness be desired than a single application will conveniently make, a second layer may be afterwards laid on. It will be found convenient to make a considerable number of such cells at once, and to keep a stock of them ready prepared for use. If the surface of any ring should not be sufficiently level for a covering glass to lie flat upon it, a slight rubbing upon a piece of fine emery paper laid upon a flat table (the ring being held downwards) will make it so.

Ring-cells.—For mounting objects of greater thickness it is desirable to use cells made by cementing rings, either of glass or metal to the glass slides, with marine glue. Glass rings of any size, diameter, thickness, and breadth are made by cutting transverse sections of thick-walled tubes, the surfaces of these sections being ground flat and parallel. Not only may round cells (fig. 326, A, B) of various sizes be made by this simple method, but, by flattening the tube (when hot) from which they are cut, the sections may be made quad-

are, or oblong (C, D). For intermediate thicknesses
t-cells and glass ring-cells, the Editor has found no
enient than the rings stamped out of tin, of various
hese, after being cemented to the slides, should have
ade perfectly flat by rubbing on a piece of fine grit
-file, and then smoothed on a Water-of-Ayr stone;
the glass covers will be found to adhere with great
ebonite and bone-cells are cheap, and also easy of
They are specially useful for dry mounts.
des and cells which are to be attached to each other
ated on the mounting plate; and some small cuttings
re then to be placed either upon that surface of the
be attached, or upon that portion of the slide on
e, the former being perhaps preferable. When they
they may be
he surface of
means of a
and in this
ted glue may
spread, care
pick out any
itty particles
ent sometimes
n the surface
is thus com-
with liquefied
to be taken
r of forceps,
d deposited in
on the slide;
to be firmly
with a stick
handle of the
h a piece of
to squeeze out
s glue from
ny air-bubbles
between the
slide, these



FIG. 326.—Glass ring-cells.

le be got rid of by pressure, or by slightly moving
de to side; but if their presence results, as is some-
from deficiency of cement at that point, the cell
off again, and more glue applied at the required
es, in spite of care, the glue becomes hardened and
verheating; and as it will not then stick well to
referable not to attempt to proceed, but to lift off
e slide, to let it cool, scrape off the overheated glue,
the process. When the cementing has been satis-
olished, the slides should be allowed to cool gradually
re the firm adhesion of the glue; and this is readily
n the first instance, by pushing each, as it is finished,

towards one of the extremities of the plate. If two plates are in use, the heated plate may then be readily moved away upon the ring which supports it, the other being brought down in its place; and as the heated plate will be some little time in cooling, the firm attachment of the cells will be secured. If, on the other hand, there be only a single plate, and the operator desire to proceed at once in mounting more cells, the slides already completed should be carefully removed from it, and laid upon a *wooden* surface, the slow conduction of which will prevent them from cooling too fast. Before they are quite cold, the superfluous glue should be scraped from the glass with a small chisel or awl, and the surface should then be carefully cleansed with a solution of potash, which may be rubbed upon it with a piece of rag covering a stick shaped like a chisel. The cells should next be washed with a hard brush and soap and water, and may be finally cleansed by rubbing with a little weak spirit and a soft cloth. In cases in which *appearance* is not of much consequence, and especially in those in which the cell is to be used for mounting large opaque objects, it is decidedly preferable not to scrape off the glue too closely round the edges of attachment, as the 'hold' is much firmer, and the probability of the penetration of air or fluid much less, if the immediate margin of glue be left both outside and inside the cell. To those to whom *time* is of value, it is recommended that all cells which require marine glue cementing be purchased from the dealers in microscopic apparatus, and it is well to note that all cells cemented with marine glue should be well 'payed,' as the nautical expression is, or well surrounded with shellac varnish, or gold-size as indicated by the nature of the enclosed fluid. Many media, saline fluids especially, work their way between the cell and the slide, and at length destroy the marine glue.



FIG. 327.—Plate-glass cells.

Plate-glass Cells.—Where large shallow cells with flat bottoms are required (as for mounting *zoophytes*, small *medusæ*, &c.), they may be made by drilling holes in pieces of plate-glass of various sizes, shapes, and thicknesses (fig. 327, A), which are then cemented to glass slides with marine glue. By drilling two holes at a suitable distance, and cutting out the piece between them, any required elongation of the cavity may be obtained (B, C, D).

Sunk-cells. This name is given to round or oval hollows, excavated by grinding in the substance of glass slides, which for this

purpose, should be thicker than ordinary. They are shown in fig. 328, A, B, C. Such cells have the advantage not only of comparative cheapness, but also of durability, as they are not liable to injury by a sudden jar, such as sometimes causes the detachment of a cemented plate or ring. For objects whose shape adapts them to the form and depth of the cavity, such cells will be found very convenient. It naturally suggests itself as an objection to the use of such cells that the concavity of their bottom must so deflect the light-rays as to distort or obscure the image; but as the cavity is filled either with water or some other liquid of higher refractive power, the deflection is so slight as to be practically inoperative. Before mounting objects in such cells the microscopist should see that their concave surfaces are free from scratches or roughnesses.



FIG. 328.—Plate-glass sunk-cells.

Built-up Cells.—When cells are required of forms or dimensions, not otherwise procurable, they may be *built up* of separate pieces of glass cemented together. Large *shallow* cells, suitable for mounting zoophytes or similar flat objects, may be easily constructed after the following method: A piece of plate-glass, of a thickness that shall give the desired depth to the cell, is to be cut to the dimensions of its outside wall; and a strip is then to be cut off with the diamond from each of its edges, of such breadth as shall leave the interior piece equal in its dimensions to the cavity of the cell that is desired. This piece being rejected, the four strips are then to be cemented upon the glass slide in their original position, so that the diamond-cuts shall fit together with the most exact precision; and the upper surface is then to be ground flat with emery upon a pewter plate and left rough. The perfect construction of large *deep* cells of this kind, as shown in fig. 329, A, B, how-



FIG. 329.—Built-up cells.

ever, requires a nicety of workmanship which few amateurs possess, and the expenditure of more time than microscopists generally have to spare ; and as it is consequently preferable to obtain them ready-made, directions for making them need not be here given.

Wooden Slides for Opaque Objects.—Such 'dry' objects as *foraminifera*, the capsules of *mosses*, parts of *insects*, and the like, may be conveniently mounted in a very simple form of wooden slide (first devised by the Author and now come into general use), which also serves as a protective 'cell.' Let a number of slips of mahogany or cedar be provided, each of the 3-inch by 1-inch size, and of any thickness that may be found convenient, with a corresponding number of slips of card of the same dimensions, and of pieces of *dead*-black paper rather larger than the aperture of the slide. A piece of this paper being gummed to the middle of the card, and some stiff gum having been previously spread over one side of the wooden slide (care being taken that there is no superfluity of it immediately around the aperture), this is to be laid down upon the card, and subjected to pressure.[1] An extremely neat 'cell' will thus be formed for the reception of the object, as we see in fig. 330, the depth of which will be determined by the thickness of the slide, and the diameter by the size of the perforation ; and it will be found convenient to provide slides of various thicknesses, with apertures of different sizes. The cell should always be deep enough for its wall to rise above the object ; but, on the other hand, it should not be too deep for its walls to interfere with the oblique incidence of the light upon any object that may be near its periphery. The object, if flat or small, may be attached by gum-mucilage ; if, however, it be large, and the part of it to be attached have an irregular surface, it is desirable to form a 'bed' to this by gum thickened with starch. If, on the other hand, it should be desired to mount the object edgeways (as when the *mouth* of a *foraminifer* is to be brought into view), the *side* of the object may be attached with a little gum to the *wall* of the cell. The complete protection thus given to the object is the great recommendation of this method. But this is by no means its only convenience. It allows the slides not only to range in the ordinary cabinets, but also to be laid one against or over another, and to be packed closely in cases, or secured by elastic bands ; which plan is extremely convenient not merely for the saving of space, but also for preserving the objects from dust. Should any more special protection be required, a thin glass cover may be laid over the top of the cell, and secured there either by a rim of gum or by a perforated paper cover attached to the slide ; and if

Fig. 330.—Slip made of wood.

[1] It will be found a very convenient plan to prepare a large number of such slides at once, and this may be done in a marvellously short time if the slips of card have been previously cut to the exact size in a bookbinder's press. The slides, when put together, should be placed in pairs, back to back, and every pair should have each of its ends embraced by a spring-press (fig. 336) until dry.

ɔ desired to pack these covered slides together, it is only ɔo interpose *guards* of card somewhat thicker than the ɜ.

hle.—This simple instrument (fig. 331), devised by Mr. ɜ almost indispensable to the microscopist who desires to ɐeparations that are mounted in any 'medium' beneath vers; since it not only serves for the making of those lls' in which thin, transparent objects can be best ı any kind of 'medium,' but also enables him to apply for the securing of circular cover-glasses not only with ɹtness and quickness, but also with greater certainty than ıe hand alone. The only special precaution to be observed of this in- s that the , not the d be 'cen- ich can be ıe, if *several* circles have ed on the able, by

FIG. 331.—Shadbolt's turn-table.

e cover-glass correspond with the one having its own A number of ingenious modifications have been devised ıple instrument with a view to secure exact centring. practicable and inexpensive of these is an application of Griffith's device shown in its improved form in fig. 332. ıtre of the table marked ɛs has a straight spring o it beneath. The slide, ed between the two pins ı this centre, is partially gainst the spring and rward, when the spring etween the two pins and ɹed pin, D, at the upper e slide, centring it per- ɹidth. The fourth pin, E, ɹt end, 1½ in. from the ɔor length, and allows the e always placed in the ɹve position. The recent ɛnts add much to the he table. One of them is a countersunk decentring pin, C, which may be seen at the upper right-hand side of The axle of the wheel passes through the table and is underneath with a short bar with which the decentring be turned, forcing the pin against the slide, pushing it of centre as may be desired. Another improvement is in ə end-pin a screw, which may be turned down out of the ired.



FIG. 332.—Griffith's turn-table.

ing Plate and Water-bath.—Whenever heat has to be

applied either in the cementing of cells or in the mounting of objects, it is desirable that the slide should not be exposed direct to the flame, but that it should be laid upon a surface of regulated temperature. As cementing with marine glue or hardened Canada balsam requires a heat above that of boiling water, it must be supplied by a plate of metal; and the Author's experience leads him to recommend that this should be a piece of iron not less than six inches square and half an inch thick, and that it should be supported, not on legs of its own, but on the ring of a retort-stand, so that by raising or lowering the ring any desired amount of heat may be imparted to it by the lamp or gas-flame beneath. The



FIG. 333.—Apparatus for preparing mounting media, paraffin, &c. for imbedding by heat.

advantage of a plate of this size and thickness consists in the *gradational* temperature which its different parts afford, and in the slowness of its cooling when removed from the lamp. When many cells are being cemented at once, it is convenient to have two such plates that one may be cooling while the other is being heated.

It is also needful to have a smaller plate, much thinner, of brass, having a groove cut in it into which the ordinary 3 × 1 in. mounting slip can easily slide, but so grooved as to leave a space between a ledge on each side on which the slip rests, and the main surface of the brass under the slip. In this way there is always a film of

heated air between the main surface of the heated brass and that of the glass, giving more facility for rapid and delicate heating. This may be either as separate 'table' or a plate fitted to a retort-stand.

Beyond this, however, heat of various kinds, dry and moist, of variable but determinate temperatures, will be required for various purposes, especially for melting the various mounting media, such as gelatin, agar agar, &c. and also, as we shall shortly see, for the preparation of imbedding waxes for section cutting and a variety of other purposes. One of the many pieces of apparatus which have been devised to combine as large a number of the requirements of the mounter in one construction as can be conveniently done was devised by Dr. P. Mayer and his colleagues. It is illustrated in fig. 333.

W is the bath; Z the tube by which it is filled with water; 1, 2, 3, 4 are glass tubes; *a* is a pot for melting and clarifying the paraffin, and which may be replaced by others for other needful purposes; *b* and *c* are half-cylinders with handles for imbedding; *t* is a thermometer bent at a right angle; the horizontal leg ends in the air-bath, which can be closed with a glass plate which is of service for biological as well as mounting purposes. The temperature in the air-bath will be always about 10° less than the water-bath. It serves well for evaporating chloroform &c.; *t* is the thermometer for the water-bath; R is a Reichert's thermo-regulator. The variation in temperature is less than 1° C.; *r* is the tube in which the gas and air mix, and *f* a mica chimney. There is a small independent and removable water-bath, *v*, fitted with water by means of rubber tubes attached to lateral openings. It is supplied with a thermometer, *t*, is warmed on the platform, F, and is intended chiefly for fixing objects which are small in the right position in the bedding or wax, usually known as 'orienting' objects, under a simple lens or dissecting microscope.

Slide-forceps, Spring-clip, and Spring-press.—For holding slides to which heat is being applied, especially while cementing objects to be ground down into thin sections, the wooden *slide-forceps*, seen in fig. 334, will be found extremely convenient. This,



FIG. 334.—Slide-forceps.

by its elasticity, affords a secure grasp to a slide of any ordinary thickness, the wooden blades being separated by pressure upon the brass studs; while the lower stud, with the bent piece of brass at the junction of the blades, affords a level support to the forceps, which thus, while resting upon the table, keeps the heated glass from contact with its surface. For holding down cover-glasses whilst the balsam or other medium is cooling, if the elasticity of the object should tend to make them spring up, the wire spring-clip (fig. 335), sold at a cheap rate by dealers in microscopic apparatus, will be

found extremely convenient. Or if a stronger pressure be required, recourse may be had to a simple spring-press made by a slight alteration of the 'American clothes peg' which is now in general use in this country for a variety of purposes, all that is necessary being to rub down the opposed surfaces of the 'clip' with a flat file, so that they shall be parallel to each other when an ordinary slide with its cover is interposed between them (fig. 336). One of these convenient little implements may also be easily made to serve the purpose of a slide-forceps by cutting back the upper edge of the



FIG. 335.—Spring-clip.



FIG. 336.—Spring-press.

clip, and filing the lower to such a plane that when it rests on its flat side it shall hold the slide parallel to the surface of the table, as in fig. 334.

Mounting Instrument.—A simple mode of applying graduated pressure concurrently with the heat of a lamp, which will be found very convenient in the mounting of certain classes of objects, is afforded by the mounting instrument devised by Mr. James Smith. This consists of a plate of brass turned up at its edges, of the proper size to allow the ordinary glass slide to lie loosely in the bed thus formed; this plate has a large perforation in its centre, in order to allow heat to be directly applied to the slide from beneath; and it is attached by a stout wire to a handle shown in fig. 337. Close to this handle there is attached by a joint an upper wire, which lies nearly parallel to the first, but makes a downward turn just above the centre of the slide-plate, and is terminated by an ivory knob; this wire is pressed upwards by a spring beneath it, whilst, on the



FIG. 337.—Smith's mounting instrument.

other hand, it is made to approximate the lower by a milled head turning on a screw, so as to bring its ivory knob to bear with greater or less force on the covering glass. The special use of this arrangement will be explained hereafter.

Dissecting Apparatus.—The mode of making a dissection for microscopic purposes must be determined by the size and character of the object. Generally speaking, it will be found advantageous to carry on the dissection under water, with which alcohol should be mingled where the substance has been long immersed in spirit. The

size and depth of the vessel should be proportioned to the dimensions of the object to be dissected ; since, for the ready access of the hands and dissecting instruments, it is convenient that the object should neither be far from its walls nor lie under any great depth of water. Where there is no occasion that the bottom of the vessel should be transparent, no kind of dissecting trough is more convenient than that which everyone may readily make for himself, of any dimension he may desire, by taking a piece of sheet gutta-percha of adequate

FIG. 338.—Swift's Stephenson binocular dissecting microscope.

size and stoutness, warming it sufficiently to render it flexible, and then turning up its four sides, drawing out one corner into a sort of spout, which serves to pour away its contents when it needs emptying. The dark colour of this substance enables it to furnish a background, which assists the observer in distinguishing delicate membranes, fibres, &c. especially when magnifying lenses are employed ; and it is hard enough (without being too hard) to allow of pins being fixed into it, both for securing the object and for keeping apart such portions as it is useful to put on the stretch. When glass or earthen-

ware troughs are employed, a piece of sheet-cork loaded with lead must be provided to answer the same purposes. In carrying on dissections in such a trough, it is frequently desirable to concentrate additional light upon the part which is being operated on by means of the smaller condensing lens ; and when a low magnifying power is wanted it may be supplied either by a single lens, mounted after the manner of Ross's simple microscope, or by a pair of spectacles mounted with the 'semi-lenses' ordinarily used for stereoscopes.[1] Portions of the body under dissection being floated off when detached may be conveniently taken up from the trough by placing a slip of glass beneath them (which is often the only mode in which delicate membranes can be satisfactorily spread out), and may be then placed under the microscope for minute examination, being first covered with thin glass, beneath the edges of which is to be introduced a little of the liquid wherein the dissection is being carried on. Where the body under dissection is so transparent that more advantage is gained by transmitting light through it than by looking at it as an opaque object, the trough should have a glass bottom; and for this purpose, unless the body be of unusual size, some of the glass cells already described (figs. 327–328) will usually answer very well. The finest dissections may often be best made upon ordinary slips of glass, care being taken to keep the object sufficiently surrounded by fluid. For work of this kind no instrument is more generally serviceable than the erecting binocular form of stand as recently modified for dissecting purposes by Swift. It is an instrument which combines conveniences and supplies wants which only a worker at dissection could have known. It is illustrated in fig. 338, and will be thoroughly suitable for all the work in which it will be required, from diatom mounting to the most delicate dissections. The supports for the hands on either side of the stage have an extremely suitable curve, and the instrument lends itself admirably to the work.

The *instruments* used in microscopic dissection are for the most part of the same kind as those which are needed in ordinary minute anatomical research, such as scalpels, scissors, forceps, &c. ; the fine instruments used in operations upon the eye, however, will commonly be found most suitable. A pair of delicate scissors, curved to one side, is extremely convenient for cutting open tubular parts; these should have their points blunted, but other scissors should have fine points. A pair of very fine-pointed scissors (fig. 339), one leg of which is fixed in a light handle, and the other kept apart from it by a spring, so as to close by the pressure of the



Fig. 339.—Spring scissors.

[1] These may be recommended as useful in a great variety of manipulations which are best performed under a low magnifying power, with the conjoint use of both eyes. Where a high power is needed, recourse may be advantageously had to Messrs. Beck's 3-inch achromatic binocular magnifier, which is constructed on the same principle, allowing the object to be brought very near the eyes, without requiring any uncomfortable convergence of their axes.

finger and to open of itself, will be found (if the blades be well sharpened) much superior to any kind of knives for cutting through delicate tissues with as little disturbance of them as possible. A pair of small straight forceps with fine points, and another pair of curved forceps, will be found useful in addition to the ordinary dissecting forceps.

Of all the instruments contrived for delicate dissections, however, none are more serviceable than those which the microscopist may make for himself out of ordinary *needles*. These should be fixed in light wooden handles (the cedar sticks used for camel-hair pencils, or the handles of steel penholders, or small porcupine quills will answer extremely well) in such a manner that their points should not project far, since they will otherwise have too much 'spring'; much may be done by their mere *tearing* action; but if it be desired to use them as *cutting* instruments, all that is necessary is to harden and temper them, and then give them an edge upon a hone. It will sometimes be desirable to give a finer point to such needles than they originally possess; this also may be done upon a hone. A needle with its point bent to a right angle, or nearly so, is often useful; and this may be shaped by simply heating the point in a lamp or candle, giving to it the required turn with a pair of pliers, and then hardening the point again by re-heating it and plunging it into cold water or tallow.

Section-cutting.—The young microscopist will do well to practise the cutting of thin sections of soft vegetable and animal substances with a sharp razor; considerable practice is needed, however, to make effectual use of it, and some individuals acquire a degree of dexterity which others never succeed in attaining. The making of hand-sections will be greatly facilitated by the previous use of the hardening and imbedding processes to be hereafter described; but the best of them cannot be supposed to approach in quality good sections cut by a microtome. For the preliminary examination of any soft structure, such a pair of scissors as is represented in fig. 340 will often be found very useful; since, owing to the curvature of the blades,[1] the two extremities of a section taken from a flat

FIG. 340.—Curved scissors for cutting thin sections.

FIG. 341.

surface will generally be found to thin away, although the middle of it may be too thick to exhibit any structure; but the cutting instrument seen in fig. 341 is still more serviceable: it cuts with precision and becomes with its firm spring, as it were, part of

[1] It is difficult to convey by a drawing the idea of the real curvature of this instrument, the blades of which, when it is held in front view, curve, not to either side, but towards the observer, these scissors being, as the French instrument-makers say, *courbés sur le plat*.

the operator's fingers. In fact, the only instruments which we have found *essential*, with the exception of ophthalmic needles in very fine work, are shown in the two figures 340 and 341. The two-bladed knife contrived by Professor Valentin was formerly much used for cutting microscopic sections of soft tissues; but as such sections can be cut far more effectively by the methods to be presently described, a mere mention of this instrument will here suffice.



FIG. 342.—Simple microtome.

Microtome.—There is a large class of substances, of moderate hardness, both animal and vegetable, of which extremely thin and uniform slices can be made by a sharp cutting instrument, if they be properly held and supported, and the thickness of the section be regulated by a mechanical contrivance; such are, in particular, the stems and roots of plants, and the horns, hoofs, cartilages, and similarly firm structures of animals. Various costly machines have been devised for this purpose, some of them characterised by great ingenuity of contrivance and beauty of workmanship; but most of the purposes to which these are adapted will be found to be answered by a very simple and inexpensive little instrument, which may either be held in the hand, or (as is preferable) may be firmly attached by means of a T-shaped piece of wood (fig. 342) to the end of a table or work-bench, or may be provided with a clamp for firm attachment to the work-table, as in fig. 343. This instrument essentially consists of an upright hollow cylinder of brass, with a kind of piston which is pushed from below upwards by a fine-threaded or 'micrometer' screw turned by a large milled head; at the upper end the cylinder terminates in a brass table, which is planed to a flat surface, or (which is preferable) has a piece of plate glass cemented to it, to

FIG. 343.—Microtome.

on of a turn as may very slightly elevate the substance to be as to make it project in an almost insensible degree above the nd this projecting part is to be sliced off with a knife pre- dipped in water or, preferably, methylated spirit and water in parts. For many purposes an ordinary razor will answer ntly well; but thinner and more uniform sections can be cut pecial knife, having its edge parallel to its back, its sides r concave, and its back with a uniform thickness of rather an $\frac{1}{4}$-inch. Such a knife should be four or five inches long, and broad, and should be set in a firm handle about four inches The motion given to its edge should be a combination of *g* and *pressing*. (It will be generally found that better s are made by working the knife *from* the operator than s him). When one slice has been thus taken off, it should be d from the blade by dipping it into spirit and water, or by e of a camel-hair brush; the milled head should be again ed, and another section taken, and so on. Different sub- will be found both to *bear* and to *require* different degrees kness, and the amount that suits each can only be found by It is advantageous to have the large milled head graduated, rnished with a fixed index, so that this amount having been etermined, the screw shall be so turned as to always produce ct elevation required. Where the substance of which it is to obtain sections by this instrument is of too small a size or soft a texture to be held firmly in the manner just described, be placed between the two vertical halves of a piece of carrot able size to be pressed into the cylinder, and the carrot with ject it grasps is then to be sliced in the manner already ed, the small section of the latter being carefully taken off ife, or floated away from it, on each occasion, to prevent it eing lost among the lamellæ of carrot which are removed at ne time. Vertical sections of many leaves may be successfully

with which the scientific mind can concern itself. The cutting, staining, and mounting of the most delicate organic tissues in almost every conceivable state has thrown a light upon histological and pathological matters, the present and prospective value of which we can scarcely estimate too highly; while some of the profoundest and most interesting questions of biology are opening themselves to renewed research by its means.

Throughout this chapter we only seek to give the possessor of a good microscope a fair outline of the principal methods employed, and clues to the finest processes in detail, for histological, pathological, and embryological work. For full details we may refer him to the more or less exhaustive handbooks which the several subjects have called forth. But we are at the same time convinced that if the student be but rightly directed as to instruments, and the best way of employing them, and at the same time have the best general processes concisely indicated to him, he will soon discover what to him will be the most facile and satisfactory method of obtaining the best results. In the hands of an original worker prescriptions are only satisfactory starting-points to better methods. We shall therefore describe one microtome which we believe, on the whole, to be the best, and sufficiently indicate the character and peculiarities of two or three others to enable the student, as we believe, to judge for himself in consideration of his future purpose as to which will best serve him in the object he has in view.

It will be as well, however, to note that extremely *thin* sections are not the supreme purpose of microtomes. Good sections, treated with success from beginning to end, are the first consideration. The tenuity of a section must be guided by the character of a tissue. Nevertheless nothing is gained by cutting a tissue thicker than is necessary to hold its elements together. When we have this, and no more, we can with certain success employ the highest aperture it will admit of, and penetrate all its substance as fully as with a low power and narrow aperture, and with vastly more satisfactory results.

Manifestly a tissue with injected arteries or veins must be thick enough to contain some of these vessels with their branches entire. If we require to study the hepatic cells or the renal tubules we must give depth enough in the sections to include these. But it will be found that the hardening and embedding agents contract greatly, without distorting, the anatomical elements, and sections much thinner than would be normally required to completely disclose what is sought may be often successfully made in tissues so prepared.

It is none the less true that a mere race for extreme attenuation in sections is in every sense undesirable; and for *extremely* thin sections—say the $\frac{1}{8000}$th of an inch in thickness, or less—only small sections should be attempted.

Here it may be advisable to state that the standard unit in microscopy as accepted by the Council of the Royal Microscopical Society,[1] is the $\frac{1}{1000}$th of a millimètre, which is indicated by the sign μ, being known as a *micron*.

[1] *Journ. Roy. Microsc. Soc.* ser. ii. vol. vii. pp. 502, 526; *Nat.* xxxviii. p. 221.

The choice of microtomes, English, Continental, and American, is very large, and high merit is characteristic of many. But one of these, devised by Thoma and made by Jung, of Heidelberg, entered the field early, having from the first been based on thoroughly sound, practical principles; and as a result it has been susceptible of and has lent itself to every improvement suggested by the advancing refinements of this beautiful art of microtomy. In its latest form we describe and illustrate it, satisfied that it will in an almost perfect manner meet the general wants of the biologist's laboratory.

This microtome is based upon the model of Rivet; but that has been immensely expanded in detail. The body of the instrument consists of three plates, the middle plate, M, and the side plates, S and O, fig. 344. These are fastened to the bottom plate by screws. It supports the knife-slide, MS, which rests at three points on a planed and polished track; whilst on the side of the knife-slide two other

FIG. 344.—Jung's Thoma microtome.

points slide upon the middle plate. Thus in the angle in which the block carrying the knife slides there are five points of contact on polished surfaces, the block itself having weight enough to keep the whole steady, so that at a touch it glides to and fro with a firmness and precision that could scarcely be attained in any other way.

The plate O is an inclined plane, its highest point being in the direction of M. The inclination of the angle is 1 : 20; it supports the object-holder, OS, which rests in its place exactly as does the knife-holder, MS.

This plate also bears the scale *Th*, which, by means of a vernier on the object-holder, enables the thickness of the section to be read off.

The bottom plate is at once a base and a receiver for the dripping spirit, oil, &c.

For fastening the knife a thumb-screw, C, fig. 344, serves; but in the instrument designed by the Zoological Station, Naples, this is

replaced by a single head-screw, E, fig. 345, which is provided with holes and tightened by means of a lever; and to give greater freedom to the use of the knife there are several holes drilled and tapped into which this screw fits.

The knives, of the form A, fig. 344, are generally screwed directly to the knife-slide, and are capable of the best adjustment for the most delicate and largest sections to be made in the direction of its length.

The knife, however, is also made upon another model, E, fig. 345; it then has a special holder *a*, and is secured in conical apertures by the screws *b*, b^1, and firmly held; and as *b* or b^1 is screwed farther, the edge may be adjusted towards a horizontal position.

For deep objects requiring considerable length to cut from, there are plates provided for elevating the knives and the knife-holders.

FIG. 345.—The Thoma microtome with special knife.

The exigencies of section-cutting have given rise to *a great variety of section-holders* in this instrument. The simplest is seen in OS, fig. 344, which is a pair of jaws clamped by screws and fixed upon the pivot *St* by the milled head *a*. At *n* is the vernier, which indicates the position on the mm. scale, *Th*, and *t* is an agate highly polished upon which the micrometer screw *m* works to drive forward the object-carrier, OS.

The Zoological Station at Naples employs a holder specially designed for use with paraffin; the object is soldered with paraffin on to the cylinder, *b y*, fig. 345. This may be shifted vertically and horizontally by means of the small screw *u*, and it is fastened by means of the milled head, *m*. By the spring *n* it may be displaced over 90°, and as great an inclination can be taken in a plane perpendicular to this by the supporting metal frames by means of the

spring *p*. In this way every desired inclination of the object to the knife can be readily secured.

Fig. 346 presents the same object-holder, but instead of the cylinder a simple pair of jaws with the screw *m* to secure objects of

FIG. 346.—Object-holder with jaws.

every variety. A cylinder-holder as in fig. 349 can be placed in these jaws from which the benefits of the Neapolitan holder can be secured. But fig. 346 shows a still greater improvement which can be applied to both object-holders, viz. *a perpendicular displacement by means of a cog and spring* governing the height of the mass from which the sections are to be cut.

The elevator in this case is supported on one side by the prism P, and on the other by the rod C; these are joined by the bridge *b*,



FIG. 347.—Object-holder movable about two horizontal axes at right angles to each other.

to which a cogged bar is fastened, into which a spring catches, which is moved by the lever V, allowing a perpendicular displacement of the object of 12 mm. At O is the millimètre scale on which the perpendicular displacement can be read off by means of the index *x*.

An object-holder movable about two horizontal axes situated perpendicularly to each other is seen in fig. 347. These positions are fixed by the milled heads b^1, b; e shows the jaws for holding the object, into which, however, cylinders like fig. 349 may be introduced. This object-holder has a perpendicular displacement controlled by a screw. The part, K, which supports the chief axis of the jaws is fitted on to the triangular prism S*t*, the lower part of which is furnished with hinges; on the hinge the screw V moves, which at its upper end lies close to K, and is sustained in this position by the steel plate g, so that K is carried up and down with it, and this movement is read off by a scale under S.

Fig. 348 presents *an object-holder intended to analyse by diversified section* objects which are wedged or fan-shaped in form on a fixed axis, but may be applied to other purposes.



Fig. 348.—Object-holder for analysis by diversified section.

B is a prism-shaped, semicircularly bent bar, moving in the slot $F F^1$; at b and b^1 the jaws occupy the position common to those of the ordinary form.

On the circumference of B a spiral is cut, which becomes slightly visible at g; into this spiral a screw passes at H, which is turned by the milled head S, which can alter the position of the arc to the horizontal to the extent of 1 mm.; and the amount of the change of position can be read off on the graduated circle K.

In a fixed position the middle of this section-holder is the plane of action of the knife. If an object be fixed in the jaws so that the fixed axis of it lies in this plane, it will only be required that the screw S be brought into action to obtain wedge-shaped sections of whatever thickness is required, which will all be made in this axis.

The set of cylinders which may be used with these and other jaws is represented in fig. 349: $b y$ is the cylinder, G the compressing screw for it, the mass W being held in the jaws.

The object slide with its vernier may be slidden up the incline; but it is much more accurate to control its movement with the

micrometer-screw. The point of it in fig. 345, *t*, works on the polished plane of an agate cone. The thread in which the screw works is held firmly in its place by the milled head W in *Sch.* It may stretch up as far as O, being refastened by W.

The screw *m* is so cut that a single rotation moves the slide on the $\frac{300}{1000}$ mm., which in the inclination of the plane of 1 : 20 gives



FIG. 349.—Cylinder for use with jaws.

an elevation of the object of $\frac{15}{1000}$ mm. The barrel or drum, K, situated on the axis of the screw, is divided into fifteen parts; consequently the interval of each division corresponds to an elevation of $\frac{1}{1000}$ mm.

There is also an action by means of a spring which gives the ear as well as the eye cognisance of the amount of elevation which has taken place, which greatly relieves the eye. This, however, can be brought into action or not at the option of the operator.



FIG. 350.—Freezing apparatus for the Thoma microtome.

Besides these object-holders a freezing apparatus can be added which is simply placed on the object-slide as shown in fig. 350.

The freezing is effected by ether-spray. A specially favourable effect is obtained if the cylinder *g* is mica and not glass. A layer of water freezes in from thirty to thirty-five seconds.

In fig. 351 is shown a similar arrangement as an independent

instrument. A is the plate on which the preparation is laid, *g* the mica cylinder, and B the under-setting of it in which the ether tubes for the production of the spray are fixed. No. 1 tube is from the bellows; No. 2 carries air to the ether bottle; No. 3 is for the spray point of the ether bottle itself; and No. 4 is the overflow for excess of ether.

The glass plate G serves as the knife-rest; *b* is divided in order to determine the thickness of the sections (1 division = $\frac{1}{200}$ mm.); C is the micrometer-screw which raises the object; R is the screw which fixes the clamp to a table; D is the knife commonly used; and E a stilet for clearing the spray points without enlarging the openings.

Fig. 350 is the same instrument capable of being used with the microtome instead of separately.



FIG. 351.—Independent freezing apparatus.

An arrangement of this machine for cutting large objects has also been devised which is illustrated in fig. 352.

The knife is to be placed considerably higher in front than behind, in order to lessen the pressure on the objects. In order to satisfy all demands, the knife-rest is adjustable.

The knife is so arranged that the whole length of blade can be used, and then the screw *c* is fairly tightly screwed down. As strong knives, even of a length of 36 cm., easily give, a knife-support has been constructed: this is fastened by the screw *c'* to the carrier. The support is arranged parallel with the back of the knife M; if the extremity *n* be slightly pressed backwards, so that it touches the knife, it is then fixed in this position by the screw *o* (scarcely evident in the illustration).

This done, the spirit-vessel S*p* can be arranged in a position which will not interfere with the free movement of the knife. In



FIG. 352.—Jung's sliding microtome for very large objects.

order that a stream of spirit may follow the knife over the object, the following arrangement is adopted. The spirit-vessel S*p* turns round an axis on the column *h*; to it is joined the arm L, which carries in front the fine tube *r* (connected with *tt'*), and also the rod *p*; the latter is movable perpendicularly, and to its lower end a bridge or grip with two small rollers *i* and *i'* is fastened. The rod *p* is so placed that on each side of the metal strip *b*, screwed on to the knife-support, there is one of the rollers. By the adjusting screws S*t*, the whole apparatus is so arranged that, when the knife-carrier is in motion, no other friction occurs than that of the rollers on the strip *b b b*.

The vessel is filled by screwing off the head Z. As the tube *r* acts as a siphon, it is necessary when the cock is turned on to blow down the tube. The stream of spirit should be directed at a right angle to the knife, and about the middle of the object. This done, the object O*b*, by means of the screw K, is firmly grasped in the fangs of the object-carrier; the correct direction for the position of the knife is given to its surface by the screws at *f* and f_1, and then the axes of the fangs are tightened up by the levers *q* and *q'*. If the height of the object is not quite correct, adjustment is made by the screw *m*. By turning the screws S, S, the holder is fixed.

V is a wheel with cranked axle E*w*, and this by means of a cat-gut band moves the knife.

For the *rapid* production of *ribbons of sections*, however, the instrument *par excellence* is the Cambridge rocking microtome. It is illustrated in fig. 353.

The principle is the employment of a rotary instead of a sliding movement of the parts. Two uprights are cast on the base-plate, and are provided with slots at the top, into which the razor is placed and clamped by two screws with milled heads. The inner face of the slot is so made as to give the razor that inclination which has in practice been found most advantageous. The razor is thus clamped between a flat surface and a screw acting in the middle of the blade, and the edge of the razor is consequently in no way injured.

The imbedded object is cemented with paraffin into a brass tube which fits tightly on to the end of a cast-iron lever. This tube can be made to slide backwards or forwards, so as to bring the imbedded object near to the razor ready for adjusting. The cast-iron lever is pivoted at about 3 in. from the end of the tube. To the other end of this lever is attached a cord by which the motion is given, and the object to be cut brought across the edge of the razor. The bearings of the pivot are V-shaped grooves, which themselves form part of another pivoted system.

Immediately under the first pair of V's is another pair of inverted V's, which rest on a rod fixed to two uprights cast on the base-plate. A horizontal arm projects at right angles to the plane of the two sets of V's, the whole being parts of the same casting. On the end of the horizontal arm is a boss with a hole in it, through which a screw passes freely. The bottom of the boss is turned out spherically, and into it fits a spherical nut working on the screw. The nut is prevented from turning by a pin passing loosely through a slot

he boss. The bottom of the screw rests on a pin fixed in the e-plate.

It will be seen that the effect of turning the screw is to raise or



FIG. 353.—The Cambridge rocking microtome.

lower the end of the horizontal arm, and therefore to move backwards or forwards the upper pair of V's, and with them the lever and object to be cut. The top of the screw is provided with a milled head, which may be used to adjust the object to the cutting distance. The distance between the centres of the two pivoted systems is 1 in. and the distance of the screw from the fixed rod is $6\frac{1}{4}$ in. The thread of the screw is 25 to the inch; thus, if the screw is turned once round, the object to be cut will be moved forward $\frac{1}{25}$ of $\frac{1}{6\frac{1}{4}}$, or $\frac{1}{156}$ in.

The turning of the screw is effected automatically as follows: A wheel with a milling on the edge is fixed to the bottom of the screw; an arm to which a pawl is attached rotates about the pin which supports the screw. This arm is moved backwards and forwards by hand or by a cord attached to any convenient motor. When the arm is moved forward the pawl engages in the milling and turns the wheel; when the arm is moved back the pawl slips over the milling without turning the wheel. A stop acting against the pawl itself prevents any possibility of the wheel turning, by its own momentum, more than the required amount. The arm is always moved backwards and forwards, between two stops, a definite amount, but the amount the wheel is turned is varied by an adjustable sector, which engages a pin fixed to the pawl and prevents the pawl from engaging the milling of the wheel. By adjusting the position of this sector, the feed can be varied from nothing to about $\frac{5}{32}$ of a turn; and hence, since the screw has 25 threads to the inch, the thickness of the sections cut can be varied from a minimum, depending on the perfection with which the razor is sharpened, to a maximum of $\frac{5}{32}$ of $\frac{1}{25}$ of $\frac{1}{6\frac{1}{4}}$, or $\frac{1}{1000}$ of a turn. The practical minimum thickness obtainable with a good razor is approximately $\frac{1}{4000}$ inch. The value of the teeth on the milled wheel are as follows:—

1 tooth of the milled wheel	= $\frac{1}{40000}$	in.	= ·000625 mm.
2 teeth " "	= $\frac{1}{20000}$	in.	= ·001250 mm.
4 " " "	= $\frac{1}{10000}$	in.	= ·0025 mm.
16 " " "	= $\frac{1}{2500}$	in.	= ·01 mm.

The movement of the lever which carries the imbedded object is effected by a string attached to one end of the lever. This string passes under a pulley and is fastened to the arm carrying the pawl. Attached to the other end of the lever is a spring pulling downwards. When the arm is moved forward the feed takes place, the string is pulled, the imbedded object is raised past the razor, and the spring is stretched. When the arm is allowed to move back, the spring draws the imbedded object across the edge of the razor, and the section is cut. The string is attached to the lever by a screw which allows the position of the imbedded object to be adjusted, so that at the end of the forward stroke it is only just past the edge of the razor. This is an important adjustment, as it causes the razor to commence the cut when the object is travelling slowly, and produces the most favourable conditions for the sections to adhere to each other.

The following are perhaps the most prominent advantages of this

instrument: (1) the price is low, one-sixth that of the original form. (2) Less skill is required from the operator, for the endless silk band is superseded, and the troublesome and difficult operation of lifting the first sections from the razor on to the silk band is entirely avoided. The ribbon of sections now falls of its own weight direct from the razor on to a piece of paper or glass slide placed to receive them, and by occasionally moving the paper forward any length of ribbon can be obtained. (3) The razor is fixed at what has in practice been found the most advantageous inclination and angle for cutting; and thus an unnecessary adjustment and waste of time are avoided. (4) The imbedded object is with great ease and quickness brought up to or away from the edge of the razor; first, for large amounts by sliding backwards or forwards the brass tube on the cast-iron lever, then for smaller amounts by turning round the screw, when the pawl is out of gear, by means of a small milled head placed on the top for this purpose. (5) There are no delicate working parts which can get out of order, and the whole instrument is easily taken apart for packing and is very portable.

But it is needful also to describe one or more of the best instruments designed specially for cutting sections by congelation, or freezing of the imbedding mass. Dr. R. A. Hayes designed an ether freezing microtome with the object of affording to those who have occasional need to cut sections of tissues for pathological investigations &c. the means of doing so quickly, conveniently, and



FIG. 354.—Dr. Hayes's ether freezing microtome.

accurately. It is illustrated in fig. 354. It is very compact, solidly constructed, and simple in plan. It freezes rapidly, and permits sections of large surface to be made with precision; sections 1 in. × $\frac{5}{8}$ in. having been cut by it without difficulty.

It consists of a solid cast-iron base, A, 10 in. × 4½ in., which rests upon a mahogany block. Extending the whole length of the upper surface of the base is a V-shaped gutter, on the planed sides of which slides a heavy metal block, B, on the flat top of which the razor is secured (any ordinary razor can be used), the tang being grasped

between two flat pieces of iron, which are pressed together by a winged nut, C. The razor by this arrangement can be secured at any desired angle to the direction of its motion to and fro.

The freezing-chamber is formed by a short vulcanite cylinder, D, its lower end being screwed into a brass base, E. To its upper end is fastened by two bayonet-catches a brass plate, F, on which the tissue to be cut is placed. Inside the cylinder, D, and rising from the base, E, is an ordinary spray, the air and ether being supplied through tubes, *g* and H, passing outside, through the base. There is also an opening in the floor of the chamber communicating with the tube, to allow the overflow of ether in case of any accumulation inside the cylinder; any such overflow may be returned by the tube to the ether supply bottle, K. The freezing-chamber is secured to the top of the micrometer-screw arrangement, Z, which is of the simplest form, but has a perfectly smooth and regular motion. The nut is divided to indicate a section 0·01 mm. in thickness, but half this thickness can be cut without difficulty.

The method of using the microtome is very simple. The slide and block, D, having been carefully rubbed clean and well oiled, the razor is clamped at any desired angle, the bottle, K, is filled with ether (good, dry methylated ether answers perfectly), and the piece of tissue to be cut, having been previously saturated with thick gum solution, is placed upon the plate F, and the spray which plays upon the under surface of the plate F set working by the hand-pump, M; in a short time the tissue will be frozen quite through, and if a number of sections are required an occasional stroke or two of the pump will keep the gum in proper condition for cutting. The sections are easily cut, as in other microtomes of this class, by alternate movements of the screw Z and stroke of the razor.

The instrument may also be used for cutting tissue imbedded in paraffin or other mass, the object to be cut being secured in position, either by being gently heated at its under surface and pressed on the plate F, to which it firmly adheres on cooling, or by a simple clamping arrangement, which can be substituted for the freezing-chamber. When used in this way large numbers of sections may be cut in series by attaching to the razor a light support to receive the sections as they are cut.

Another most serviceable and admirable, because inexpensive and efficient, microtome, especially for freezing purposes, was devised by Mr. Cathcart; and it is now presented in a simplified and improved condition. The instrument is illustrated in fig. 355.

In this form the clamping arrangements are much more perfect than in the old form; the principal screw and its milled head are larger and more convenient; the freezing-plate is circular, and is provided with an arrangement for preventing the ether with which the freezing is effected from reaching the upper side of the plate; and the instrument is now so modified that it can be used for ordinary imbedding as well as freezing.

The increased size of the screw gives a more steady movement than was possessed by the older and smaller microtome, while the greater circumference of the screw-head enables an operator to im-

part a finer movement to the screw. The relation between the pitch of the screw and the circumference of its head is such that if the



FIG. 355.—Cathcart's freezing microtome.

edge be moved forward a quarter of an inch, an object will be raised one-thousandth of an inch; and if it be moved an eighth of an inch, the object will be raised a two-thousandth of an inch.

In the original instrument the plate was supported on two pillars, in order that as little heat as possible might be conveyed to the freezing-plate from the body of the instrument. In the new instrument the size of the three supporting pillars and screws is so much reduced that the conducting surface is not greater than in the old microtome. The arrangement for cutting imbedded sections consists of a tube which fits the principal well of the microtome, and within which fits a hinged part similar to an ordinary vice. With the instrument are provided the means of preparing paraffin blocks for imbedding sections.

FIG. 356.
Holder for Cathcart's microtome.

When it is intended to use the microtome for imbedding, the ether spray, spray-bellows, and ether-bottle should be removed, and

the freezing-tube, having been raised as far as possible by means of the principal screw, should then be withdrawn from the well. The imbedding tube, fig. 356, is now placed in the well, and, having been pushed down until it rests upon the point of the large screw, it may be lowered to a convenient height by working the large screw backwards.

Mr. Cathcart recommends in freezing with this instrument that a few drops of mucilage (1 part gum to 3 parts water) be placed on the zinc plate, and that a piece of the tissue be cut, of about a quarter of an inch in thickness, and pressed into the gum; the ether-bottle, filled with anhydrous methylated ether, is taken and the spray points pushed into their socket. All spirit must of course have been previously removed by soaking for a night in water. The tissue should afterwards be soaked in gum for a like time before being cut. The operator must now work the spray-bellows briskly until the gum begins to freeze; after this, work more gently. Raise the tissue by turning the milled head, and cut by sliding the knife along the glass plates.

Preparation and Mounting of Objects.

Imbedding Processes.—The preparation of soft organic substances for section-cutting by 'imbedding' may be made in two modes, the choice between which will depend upon the consistency of the substance. If (1) it be compact, like a piece of liver or kidney, it only needs to be *surrounded* by the imbedding mass, which will afford it *as a whole* the requisite support. But if (2) it be partly occupied, like a piece of lung, by interstitial cavities, it must be *penetrated* by the imbedding substance, so that *every part* may be duly supported.

The former is *simple* imbedding; and it may be readily effected by immersing the object to be cut in some such substance as molten wax, which on becoming cold will acquire a consistency, neither too brittle nor too soft, which will permit of thin slices being cut. But in the second class of cases, where it is necessary to fill all natural cavities and interstices with the imbedding material, so that the most delicate organ may retain its tissues, and even its separate cells *in situ* in each section, it is much more complex.

It may be effected by a similar process of infiltration as is employed in simple imbedding, only made more complete by the previous preparation of the tissue, employing materials in which to previously soak it which are solvent of the imbedding material, and which will therefore secure more thorough infiltration. Or the same thing may be accomplished by a process of evaporation. A substance may be used which in a fluid state is capable of penetrating the most delicate cavities of a tissue, which after the evaporation of the solvent will leave the imbedded object with a consistency which will admit of cutting.

For simple imbedding the use of carrot or pith will suffice; in using the latter, when the cylinder of pith has been cut longitudinally, and a cavity has to be made to receive the object, the cavity should be made by *pressure*; a blunt ivory point will suffice to effect this. If the cells of pith be *cut out*, we lose the firmness of enclosure that is always the result of having obtained the cavity by pressure,

because when the object is enclosed between the two half-cylinders of pith and plugged (if necessary) to the shape or size of the microtome-well or holder, the pith should then be *moistened* with alcohol, or other suitable fluid, and the compressed pith-cells driven together to make space for the tissue tend by capillarity to regain their form and position as the alcohol penetrates them ; but this could not have been the case had the cavity been *cut out*. In this way the object enclosed is firmly held in all directions, and may be readily divided into sections.

For simple imbedding in wax or paraffin it is necessary to provide a cylinder of metal, or a box or tray of cardboard or paper, into which to pour the melted composition for imbedding. But a still better plan is to employ sets of two pieces of type-metal, cast in rectangular form of various heights and capable of being placed together as in fig. 356 A ; in this way a suitable box is formed, and the end of the shorter arm being triangularly enlarged outwards, it is closed sufficiently to retain the wax. Placed in this way, with the short arms nearer to or farther from each other, as a less or greater imbedding mass is required, they are set on a plate of glass which has been wetted with glycerin and gently warmed. The melted paraffin or composition is now poured into this mould until a certain desired level of the wax is reached, and when the wax has cooled to a consistency capable of receiving and retaining in its place the mass to be imbedded, it is placed in a desired position on the surface of the cool wax and the remainder of the mould is filled up with melted wax.



FIG. 356 A.—Type-metal case for imbedding.

It often happens that it is most desirable to place an object or a tissue in a special position in the imbedding mass, so that sections in a given direction may be secured. In this case we have to use some method of 'orienting' the object, and in some cases this requires the use of at least a fixed hand lens or even a microscope. It is frequently a very difficult matter to properly orient very small objects, such as spherical eggs, so that sections may pass through any desired plane. In working on the embryology of the common shrimp, Mr. J. S. Kingsley found the following process very convenient. Impregnation with paraffin is accomplished in the usual way, and then the eggs (in numbers) in melted paraffin are placed in a shallow watch-crystal. They immediately sink to the bottom, and then the whole is allowed to cool. The crystal, glass upwards, is now placed on the stage, and the eggs examined under a lens.

In this way one can readily see exactly how any egg lies, and then with a knife it may be cut out with the surrounding paraffin, and in such a way that it can readily be fastened to the block in any desired position After all which have been dropped in a suitable

position are thus cut out, the paraffin is again melted, and after stilling the eggs the cutting is continued as before.

A more general method is to take a common flat medicine bottle, as in fig. 357, fitted with a cork through which two tubes pass, or, if the mouth is small, one tube may be fastened into a hole drilled into the bottle. One of these tubes, A, is connected with hot and cold water; the other, B, is a discharge-pipe for the water entering the bottle by A, and raising or lowering its temperature as warm or cold water is allowed to flow in. On the smooth, flat side of the bottle four pieces of glass rods or strips are cemented fast, so as to inclose a rectangular space, C, which forms a receptacle for the melted paraffin.

Fig. 357. — Arrangement for the orientation of objects in paraffin.

As long as the warm water circulates through the bottle the paraffin remains fluid and objects in it may be arranged under the microscope by light from above or below, and can be oriented with reference to the sides of the paraffin receptacle or with reference to lines drawn upon the surface of the bottle. When the cold water is allowed to enter in place of the warm, the paraffin congeals rapidly, and may be easily removed as one piece. The discharge-pipe should open near the upper surface of the bottle, to draw off any air which may accumulate there.

In using the Thoma form of microtome where the object is held in jaws, the imbedding mass must of course be cast a suitable shape, and placed directly in the jaws, or be cemented to slices of cork which may be placed in contact with the jaws.

After sections have been cut and are placed upon the thin cover for mounting, it is very desirable to be able easily to free the sections from the imbedding mass that may be clinging to it. This may be done by means of turpentine, creosote, xylol, or oil of cloves. But in simple imbedding, where the interpenetration of the cavities of the object is not the special aim, a still more efficient method is to prepare the object before imbedding it by covering it with a film of some substance which prevents the immediate contact of the imbedding mass with the object, and which can be even more easily removed than the paraffin. This may be done with collodion, into which the prepared tissue is plunged for a short time and taken out and allowed to evaporate. The oil of cloves used for clearing the section will dissolve it, and the cast of wax will fall away.

Imbedding Masses. These may be procured ready prepared for two or three temperatures, made up according to the formulæ of some of the most experienced biologists. The composition of the imbedding mass is of large importance. The temperature of the laboratory must determine the melting-point of the paraffin; by

affins of various melting-points we can obtain accurately
ie consistency we need for laboratories of different tem-
r for the same laboratory at different periods of the year.
for example, a paraffin with a melting-point of 136° F.
wo parts of this with one part of a paraffin having a
nt of 110° F., we shall have a mass that will cut satisfac-
emperature of 70° F.; while the paraffin with the lower
nt will serve well for a temperature of 60° F. We
. to work in lower or higher temperatures than these.
ixing equal parts by weight of pure vaselin and the
lting at 136° F., an imbedding mass that will cut well at
ie obtained.

imbedding mass which is extremely useful may be made
together equal parts by weight of white wax and olive
rill work well from 60° F. to 65° F. For a higher tem-
an this add a little more wax; for a lower temperature, a
il.

to prepare delicate tissues &c. by complete impregnation
n before imbedding, it is needful to use a suitable solvent.
e chloroform, creosote, oil of cloves, or oil of turpentine.
mbedding, the material to be imbedded would have been
nd otherwise prepared; the mode in which this may be
ie described subsequently in this chapter. Let it be
at the object is taken immediately from alcohol of full
From this it is to be transferred to creosote, oil of cloves,
m, oil of turpentine answering sufficiently well for larger
hen this has completely replaced the spirit, the body is to
d for some little time in a hot saturated solution of
oil of turpentine. When it has lain sufficiently long in
horoughly penetrated, it is to be immersed in the melted
ich should not be more heated than is necessary to keep
id; and it should be moved about in this for some little
asional gentle squeeze being given to it with the forceps
solution may be replaced as completely as possible by the
raffin. When hardened by cooling, the substance thus
ay be 'imbedded' in the moulds in the manner already
he coating with gum being of course omitted. When
has perfectly solidified, the mould is to be lifted off its
m, and the block taken out is then ready for cutting.
e section-knife, care should be taken to keep it constantly
methylated spirit, and it is desirable that each section
emoved from it before another is taken, except of course
onnexion of each section with the preceding is sought
tained, when sections united successively together in
an be readily effected, all that is needful being the right
he imbedding material involving the adhesion of each to
they are successively cut, and a section smoother on the
cutting blade.

n as an imbedding mass.—This is a preparation of pure
It may be obtained in cakes of a tough, pliant nature,
consistency suitable for section-cutting. It is soluble in

ether and alcohol. Small pieces of the celloidin tablets are dissolved readily in equal parts of absolute alcohol and ether; the properly hardened tissue, having been dehydrated in strong alcohol, is removed to a mixture of equal parts of alcohol and ether, where it must remain two or three hours, and longer if convenient. It is then transferred to a *thin* solution of celloidin in a well-stoppered bottle or other tightly closed vessel, where it should remain ten or twelve hours at least, and can only be benefited by a very prolonged bath. A much thicker solution of celloidin must be prepared and at hand. Take out the organ or tissue from the thin solution, and suffer the celloidin to evaporate until a film is formed. This is preferably done on a piece of leather. Surround it now with the thick celloidin, and wait until again a film has formed, and then the whole is thrown into strong alcohol, where it may remain until it is desired to cut sections.

Sections are best cut with the razor moistened with alcohol, and they may be floated into the same fluid.

To mount, it is not needful to remove the celloidin if we employ glycerin, glycerin jelly, or Farrant's medium (*q.v.*); but if we desire to mount in balsam the section should be dehydrated with 95 per cent. of alcohol, and cleared with oil of origanum or oil of clove.

Imbedding by Congelation or Freezing.—From the amount of water they contain, perfectly fresh tissues may be frozen without being enclosed in any medium, and as readily cut; but the inevitable formation of ice crystals cuts and tears delicate anatomical elements. A fluid mass that will freeze without crystallising, and when frozen permits the action of the knife, is what is needed. Gum arabic is precisely suited in this case. The substance to be cut (which may either be fresh, or have been hardened by some of the processes to be hereafter described, must be thoroughly penetrated by a thick solution of gum. If the substance to be cut has been immersed in alcohol, this must be completely removed in the first instance by immersion in water for from six to twenty-four hours, according to the size of the mass; for the gum will not penetrate any part which is still alcoholised. The substance should be then immersed in the gum-solution for from twelve to twenty-four hours before it is frozen, in order that every part may be permeated by the gum, and no water be left to form crystals of ice.

With the ether-spray microtome, which is simpler and easier to work than the ice-freezing instrument, the freezing is produced by the rapid evaporation of the liquid injected into the freezing-chamber. The substance to be cut is to be introduced into the well, as soon as the gum begins to harden at its periphery, and should be held in place until fixed by the advancing congelation. In cutting the sections no wetting of the knife is necessary, as it is kept sufficiently wetted by the thawing gum. The sections should be placed in methylated spirit diluted with twice its volume of water; and this soon not only dissolves out the gum, but removes any air-bubbles the section may contain. If the section is to be at once mounted (which should always be done if it be very delicate and liable to be spoiled by manipulation), it should be placed on the slide before it has thawed

and washed by forming around it a little pool of dilute spirit, which may be readily changed two or three times by the glass syringe. Sections cut by the freezing process may for the most part be mounted in glycerin jelly, for which no other preparation will be needed than the use (if desired) of the staining process hereafter to be described. But if, for the sake of rendering the sections more transparent, mounting them in Canada balsam or dammar is preferred, they must be treated first with strong spirit, then with absolute alcohol, and then with either oil of cloves or oil of turpentine. It is claimed by Dr. Rutherford, as the special advantage of the freezing process, that 'delicate organs, such as the retina, the embryo, villi of the intestines, lung, trachea with its ciliated epithelium, may all be readily cut without fear of their being destroyed by the imbedding agents.' When imbedded in paraffin, very delicate structures are more liable to damage, the villi of the intestine, for instance, being often denuded of their epithelium, and sometimes themselves torn.

Celloidin as a Congelation Mass.—Dr. A. Hill, of Downing College, Cambridge, has for years employed celloidin as a freezing substance with beautiful results. A similar process, differing somewhat in details, was, however, published by J. W. Barrett ('Journ. Anat. and Phys.' No. 7, 1885). Dr Hill has at the Editor's request favoured him with the following description of his method, and some of his exquisite mountings of brain tissue accomplished by its means.

As originally recommended the celloidin is set in 80 per cent. alcohol and cut under spirit, but under these circumstances it presents a tough, resilient, and disagreeable substance to the razor, whereas there is no substance or tissue more satisfactory to cut than celloidin saturated with water and frozen. For this method pieces of tissue are placed after appropriate hardening in absolute alcohol. The alcohol is replaced once or twice by a mixture of absolute alcohol three parts, ether one part. Into the bottle containing the tissue a piece of Schering's celloidin is then dropped, next day another piece, and so on until the solution of celloidin flows with difficulty. To obtain this result requires about a fortnight, and the process may of course be cut short by using a strong solution of celloidin in the first instance; but the longer process amply repays for the trouble by ensuring complete penetration of the celloidin into the tissue and yielding when set a homogeneous mass not liable to curl up when cut. Tissue and celloidin solution are then poured out together into a shallow basin, which is covered by a glass plate. Evaporation takes place slowly, and in three to four days a firm, uniform mass is obtained. A block of celloidin with the tissue imbedded is cut out and thrown into water for two hours, at the end of which time it may be placed in gum and ether frozen and cut at once or preserved for an indefinite period in aseptic gum or spirit. The celloidin may be set much more expeditiously by pouring it into a paper boat which is placed in a vessel of chloroform. In this way the celloidin is set in a very short time with, as far as can be estimated, no loss of bulk.

The sections when cut and stained must be dehydrated in strong spirit, immersed for a few moments in absolute alcohol, and cleared in oil of thyme, oil of bergamot, or turpentine and creosote (ten parts

to one part heated together), but not in oil of cloves, the celloidin being soluble in the latter reagent.

Grinding and Polishing Sections of Hard Substances.—Substances which are too hard to be sliced in a microtome—such as bones, teeth, shells, corals, fossils of all kinds, and even some dense vegetable tissues—can only be reduced to the requisite thinness for microscopical examination by grinding down thick sections until they become so thin as to be transparent. General directions for making such preparations will be here given ;[1] but those special details of management which particular substances may require will be given when these are respectively described. The first thing to be done will usually be to procure a *section* of the substance, as thin as it can be safely cut. Most substances not siliceous may be divided by the fine saws used by artisans for cutting brass ; and these may be best worked either by a mechanical arrangement such as that devised by Dr. Matthews,[2] or, if by hand, between 'guides,' such as are attached for this purpose to Hailes's and some other microtomes. But there are some bodies (such as the enamel of teeth, and porcellaneous shells), which, though merely calcareous, are so hard as to make it very difficult and tedious to divide them in this mode ; and it is much the quicker operation to *slit* them with a disc of soft iron (resembling that used by the lapidary) charged at its edge with diamond-dust, which disc may be driven in an ordinary lathe. Where waste of material is of no account, a very expeditious method of obtaining pieces fit to grind down is to detach them from the mass with a strong pair of 'cutting pincers,' or, if they be of small dimensions, with 'cutting pliers' ; and a flat surface must then be given to it, either by holding them to the side of an ordinary grindstone, or by rubbing on a plate of lead (cast or planed to a perfect level) charged with emery, or by a strong-toothed file, the former being the most suitable for the *hardest* substances, the latter for the *toughest*. There are certain substances, especially calcareous fossils of wood, bone, and teeth, in which the greatest care is required in the performance of these preliminary operations, on account of their extreme friability ; the vibration produced by the working of the saw or the file, or by grinding on a rough surface, being sufficient to disintegrate even a thick mass, so that it falls to pieces under the hand ; such specimens, therefore, it is requisite to treat with great caution, dividing them by the smooth action of the wheel, and then rubbing them down upon nothing rougher than a very fine 'grit,' or on the 'corundum files' now sold in the tool-shops, which are made by imbedding corundum of various degrees of fineness in a hard, resinous substance. Where (as often happens) such specimens are sufficiently porous to admit of the penetration of Canada balsam, it will be desirable, after soaking them in turpentine for a while, to lay some liquid balsam upon the parts through which the section is to pass, and then to place the specimen before the fire or in an oven

[1] The following directions do not apply to *siliceous* substances, as sections of these can only be prepared by those who possess a regular lapidary's apparatus, and have been specially instructed in the use of it.

[2] *Journ Quekett Microsc. Club*, vol. vi. 1880, p. 88.

has been prepared for permanent attachment to the glass.
e method which it is generally most convenient to pursue
rd to small bodies ; and there are many which can scarcely
in any other way than by attaching a number of them to
at once in such a manner as to make them mutually sup-
another.[1]

ode in which the operation is then to be proceeded with,
pon whether the section is to be ultimately set up in Canada
is to be mounted 'dry,' or in fluid. In the former case
ing is the plan to be pursued :—The flattened surface is to
d by rubbing it with water on a 'Water-of-Ayr' stone, or
or 'Turkey' stone, or on an 'Arkansas' stone ; the first of
is the best for all ordinary purposes, but the two latter,
h harder, may be employed for substances which resist it.[2]
s has been sufficiently accomplished, the section is to be
with hard Canada balsam to a slip of thick, well-annealed
l as the success of the final result will often depend upon
teness of its adhesion to this, the means of most effectually
hat adhesion will now be described in detail. The slide
n placed on the cover of the water-bath, and the previously
balsam having been softened by the immersion of the jar
it in the bath itself, a sufficient quantity of this should
the slide to form, when spread out by liquefaction, a thick
ewhat larger than the surface of the object to be attached.
should then be allowed to cool in order that the hardness
lsam should be tested. If too soft, as indicated by its

a making horizontal and vertical sections of *Foraminifera*, as it would
e to slice them through, they must be laid close together in a bed of
nada balsam on a slip of glass, in such positions that when rubbed down
section shall traverse them in the desired directions ; and one flat surface
thus obtained for each, this must be turned downwards, and the other
away. The following ingenious plan was suggested by Dr. Wallich (*Ann.*
. July 1861, p. 58) for turning a number of minute objects together, and
g the tediousness and difficulty of turning each one separately: The

ready yielding to the thumb-nail, it should be heated a little more, care being taken not to make it boil so as to form bubbles; if too hard, which will be shown by its chipping, it should be re-melted and diluted with more fluid balsam, and then set aside to cool as before. When it is found to be of the right consistence, the section should be laid upon its surface with the polished side downwards; the slip of glass is next to be gradually warmed until the balsam is softened, special care being taken to avoid the formation of bubbles; and the section is then to be gently pressed down upon the liquefied balsam, the pressure being at first applied rather on one side than over its whole area, so as to drive the superfluous balsam in a sort of wave towards the other side, and an equable pressure being finally made over the whole. If this be carefully done, even a very large section may be attached to glass without the intervention of any air-bubbles. If, however, they should present themselves, and they cannot be expelled by increasing the pressure over the part beneath which they are, or by slightly shifting the section from side to side, it is better to take the section entirely off, to melt a little fresh balsam upon the glass, and then to lay the section upon it as before.

When the section has been thus secured to the glass, and the attached part thoroughly saturated (if it be porous) with hard Canada balsam, it may be readily reduced in thickness, either by grinding or filing, as before, or, if the thickness be excessive, by taking off the chief part of it at once by the slitting wheel. So soon, however, as it approaches the thinness of a piece of ordinary card, it should be rubbed down with water on one of the smooth stones previously named, the glass slip being held beneath the fingers with its face downwards, and the pressure being applied with such equality that the thickness of the section shall be (as nearly as can be discerned) equal over its entire surface. As soon as it begins to be translucent, it should be placed under the microscope (particular regard being had to the method of illumination so as not to flood the object with light), and note taken of any inequality; and then when it is again laid upon the stone, such inequality may be brought down by making special pressure with the forefinger upon the part of the slide above it. When the thinness of the section is such as to cause the water to spread around it between the glass and the stone, an excess of thickness on either side may often be detected by noticing the smaller distance to which the liquid extends. In proportion as the substance attached to the glass is ground away, the superfluous balsam which may have exuded around it will be brought into contact with the stone; and this should be removed with a knife, care being taken, however, that a margin be still left round the edge of the section. As the section approaches the degree of thinness which is most suitable for the display of its organisation, great care must be taken that the grinding process be not carried too far; and frequent recourse should be had to the microscope, which it is convenient to have always at hand when work of this kind is being carried on. There are many substances whose intimate structure can only be displayed in its highest perfection, when a very little

more reduction would destroy the section altogether; and every microscopist who has occupied himself in making such preparations can tell of the number which he has sacrificed in order to attain this perfection. Hence, if the amount of material be limited, it is advisable to stop short as soon as a *good* section has been made, and to lay it aside—'letting well alone'—whilst the attempt is being made to procure a *better* one; if this should fail, another attempt may be made, and so on, until either success has been attained or the whole of the material has been consumed; the *first* section, however, still remaining, whereas, if the first, like every subsequent section, be sacrificed in the attempt to obtain perfection, no trace will be left 'to show what once has been.' In judging of the appearance of a section in this stage under the microscope, it is to be remembered that its transparence will subsequently be considerably increased by mounting in Canada balsam: this is particularly the case with fossils to which a deep hue has been given by the infiltration of some colouring matter, and with any substances whose particles have a molecular aggregation that is rather amorphous than crystalline. When a sufficient thinness has been attained, the section may generally be mounted in Canada balsam; and the mode in which this must be managed will be detailed hereafter.

By a slight variation in the foregoing process, sections may be made of structures, in which (as in corals) *hard and soft parts are combined*, so as to show both to advantage. Small pieces of the substance are first to be stained thoroughly and are then to be 'dehydrated' by alcohol. A thin solution of copal in chloroform is to be prepared, in which the pieces are to be immersed; and this solution is to be concentrated by slow evaporation, until it can be drawn out in threads which become brittle on cooling. The pieces are then to be taken out, and laid aside to harden; and when the copal has become so firm that the edge of the finger-nail makes no impression, they are to be cut into slices and ground down attached to glass in the manner already described, the sections being finally mounted in Canada balsam. The sections (attached to glass) may be partially or completely decalcified, the soft parts remaining *in situ*, by first dissolving out the copal with chloroform; when, after being well washed in water, they should be again stained, and mounted either in weak spirit, or (after having been dehydrated) in Canada balsam.[1]

A different mode of procedure, however, must be adopted when it is desired to obtain sections of bone, tooth, or other finely tubular structures, *un*penetrated by Canada balsam. If tolerably thin sections of them can be cut in the first instance, or if they are of a size and shape to be held in the hand whilst they are being roughly ground down, there will be no occasion to attach them to glass at all; it is frequently convenient to do this at first, however, for the purpose of obtaining a 'hold' upon the specimen; but the surface which has been thus attached must afterwards be completely rubbed away in

[1] See Koch in *Zoologischer Anzeig.* Bd. i. p. 36. The Author, having seen (by the kindness of Mr. H. N. Moseley) some sections of corals prepared by this process, can testify to its complete success.

order to bring into view a stratum which the Canada balsam shall not have penetrated. As none but substances possessing considerable toughness, such as bones and teeth, can be treated in this manner, and as these are the substances which are most quickly reduced by a coarse file, and are least liable to be injured by its action, it will be generally found possible to reduce the sections nearly to the required thinness by laying them upon a piece of cork or soft wood held in a vice, and operating upon them first with a coarser and then with a finer file. When this cannot safely be carried farther, the section must be rubbed down upon that one of the fine stones already mentioned which is found best to suit it; as long as the section is tolerably thick, the finger may be used to press and move it; but as soon as the finger itself begins to come into contact with the stone, it must be guarded by a flat slice of cork, or by a piece of gutta-percha a little larger than the object. Under either of these, the section may be rubbed down to the desired thinness; but even the most careful working on the finest-grained stone will leave its surface covered with scratches, which not only detract from its appearance, but prevent the details of its internal structure from being as readily made out as they can be in a polished section. This polish may be imparted by rubbing the section with putty-powder (peroxide of tin) and water upon a leather strap, made by covering the surface of a board with buff-leather, having three or four thicknesses of cloth, flannel, or soft leather beneath it: this operation must be performed on both sides of the section, until all the marks of the scratches left by the stone shall have been rubbed out, when the specimen will be fit for mounting 'dry' after having been carefully cleansed from any adhering particles of putty-powder.

Greater facility in the grinding of hard sections, as well as superiority of result, is attainable by simple mechanical means.

A cutting machine will greatly facilitate the process of preparing rock slices. The thickness of each slice must be mainly regulated by the nature of the rock, the rule being to make it as thin as can be conveniently cut, so as to save labour in grinding down afterwards. Perhaps the thickness of a shilling may be taken as a fair average.



FIG. 358.—Hand machine for cutting hard sections.

This thickness may be still further reduced by cutting and polishing a face of the specimen, cementing that on glass, and then cutting as close as possible to the cemented surface. The thin slice thus left on the glass can then be ground down with comparative ease.

The first (fig. 358) is a hand machine. The specimen is cemented to the carrier, *a*, which is movable on the axis, *b*, and can also be rotated in two directions. The object is pressed by the weight, *c*, against the steel disc, *d*, which is revolved by the wheel, *e*, acting on a smaller toothed wheel on the axis of *d*.

The second (fig. 359) is intended to be worked by the foot. The parts *a*, *b*, *c*, and *d* are the same as before. The wheel and treadle at *f* and *g* work the pulley, *e*, by which the steel disc, *d*, is revolved; *h*

FIG. 359.—Treadle machine for cutting hard sections.

is part of the cover for the disc, to prevent the emery flying about. A box beneath also catches the powder that falls.

(This arrangement is also supplied with fig. 358, though not shown in the woodcut.) A second wheel at *i*, with a cord passing over *k*, actuates a vertical spindle, *l*, which rotates a horizontal cast-iron plate at *m* for polishing.

Decalcification.—When it is desired to examine the structure of the organic matrix in which the calcareous salts are deposited that give hardness to many animal and to a few vegetable structures (such as the true corallines), these salts must be dissolved away by the

action of some mineral acid, which may be either nitric or hydrochloric. This should be employed in a very dilute state, in order that it may make as little change as possible in the soft tissue it leaves behind. When the lime is in the state of carbonate (as, for example, in the skeletons of *echinoderms*), the body to be decalcified should be placed in a glass jar or wide-mouthed bottle holding from 4 to 6 oz. of water, and the acid should be added drop by drop, until the disengagement of air-bubbles shows that it is taking effect; and the solvent process should be allowed to take place very gradually, more acid being added as required. When, on the other hand, much of the lime is in the state of phosphate, as in bones and teeth, the strength of the acid solvent must be increased; and for the hardening of the softer parts of the organic matrix, it is desirable that chromic acid should be used. In the case of small bones, or delicate portions of large (such as the cochlea of the ear), a $\frac{1}{2}$ per cent. solution of chromic acid will itself serve as the solvent; but, larger masses require either nitric or hydrochloric acid in addition, to the extent of 2 per cent. of the former or 5 per cent. of the latter. By some the chromic and the nitric or muriatic acid are mixed in the first instance; while by others it is recommended that the bone should lie first in the chromic acid solution for a week or ten days, and that the second acid should be then added. If the softening be not completed in a month, more acid must be added. When thoroughly decalcified, the bone should be transferred to rectified spirit; and it may then be either sliced in the microtome, or torn into shreds for the demonstration of its lamellæ. Acid solvents may also be employed in removing the outer parts of calcareous skeletons, for the display of their internal cavities (a plan which the Author has often found very useful in the study of *Foraminifera*); or for getting rid of them entirely, so as to bring into complete view any 'internal cast' which may have been formed by the silicification of its originally soft contents. It has been in this mode, even more than by the cutting of thin sections, that the structure of *Eozoön canadense* has been elucidated by Professor Dawson and the Author. For the first of these purposes, strong acid should be applied (under the dissecting microscope) with a fine camel's-hair pencil; and another such pencil charged with water should be at hand, to enable the observer to stop the solvent action whenever he thinks it has been carried far enough. For the second it is better that the acid should only be strong enough for the *slow* solution of the shelly substance, as the too rapid disengagement of bubbles often produces displacement of delicate parts of the substituted mineral; whilst, if the acid be too strong, the 'internal cast' may be altogether dissolved away.

Bush suggests nitric acid as the best of all agents for decalcification, insomuch as it does not cause 'swelling up,' nor injuriously attack the tissue elements.

One volume of chemically pure nitric acid of specific gravity 1·25 diluted with ten volumes of water may be employed for large and tough bones; but it may be diluted to 1 per cent. for young bones.

The method given is that fresh bones should be laid on a 95 per cent. solution of alcohol for three days; they must then be placed in

the nitric acid, which must be changed daily for eight days. They must not remain after the decalcification is complete, or staining will ensue. On removal the bones must be washed for a couple of hours in running water and placed again in 95 per cent. alcohol, and in a few days placed again in fresh alcohol.

Desilicification.—It is desirable to be able to remove siliceous as well as calcareous elements from objects. To do this a glass vessel should be carefully coated with paraffin internally, to prevent the action of the acid used taking place on the sides of the vessel. The subject to be cleared of its silica is placed in alcohol in the coated vessel, and hydrofluoric acid is added drop by drop. As the mucous membranes are fiercely attacked by this acid, great care must be exercised in its use; but small sponges and other similar siliceous objects by remaining a few hours or a day in this are wholly deprived of their silica, while the tissues do not suffer.

Preparation of Vegetable Substances.—Little preparation is required, beyond steeping for a short time in distilled water to get rid of saline or other impurities, for mounting in preservative media specimens of the minuter forms of vegetable life, or portions of the larger kinds of *algæ*, *fungi*, or other succulent cryptogams. But the woody structures of *phanerogams* are often so consolidated by gummy, resinous, or other deposits that sections of them should not be cut until they have been *softened* by being partially or wholly freed from these. Accordingly, pieces of stems or roots should be soaked for some days in water, with the aid of a gentle heat if they are very dense, and should then be steeped for some days in methylated spirit, after which they should again be transferred to water. The same treatment may be applied to hard-coated seeds, the 'stones' of fruit, 'vegetable ivory,' and other like substances. Some vegetable substances, on the other hand, are too soft to be cut sufficiently thin without previous *hardening*, either by allowing them to lose some of their moisture by evaporation, or by drawing it out by steeping them in spirit. Either treatment answers very well with such substances as that which forms the tuber of the potato, sections of which display the starch-grains *in situ*. Where, on the other hand, it is desired to preserve colour, spirit must not be used; and recourse may be had to gum-imbedding, which is particularly serviceable where the substance is penetrated by air-cavities, as is the case with the stem of the *rush*, the thick leaves of the *water-lily* &c. But where the *staining* processs is to be employed, the substance should be previously bleached by the action of chlorine (preferably by Labarraque's chlorinated soda), and then treated with alcohol for a few hours.

Hardening Agents.—The methods of imbedding and freezing have become so perfect, and have such universal application, that this process of hardening, which at an early period in the art of microtomy was of so much importance, has fallen into a matter of second-rate importance.

Hardening processes may act either by coagulating the albumen of the tissues, without entering into chemical combination therewith, as is the case with alcohol, nitric acid, and picric acid, or they may produce the results effected by their employment by entering in some

manner into chemical combination with the components of the tissues. To this latter group belong osmic acid, chromic acid, and chloride of palladium. The latter group produces effects in the tissues that do not lend themselves to successful staining, although they admit of delicate sections.

Alcohol.—This should be used strong. Most operators advise, for certain purposes at least, absolute alcohol; but Mr. Arthur Cole, whose experience is very large, says that this should not be used for hardening purposes, either with animal or vegetable tissues. He affirms that methylated spirit should always be employed, for the 'water in alcohol renders it useless for hardening.' Large quantities of spirit should be employed in proportion to the object, and many weeks may be required to harden large specimens.

Picric acid is used for the same purposes as chromic acid; its hardening power is not so great, but it does not shrivel the tissues as much, its action is more rapid, and it may be advantageously used where 'decalcification' is necessary. As it is but slightly soluble in water, a cold-water solution must be saturated; and the quantity of liquid should be large in proportion to that of the substance to be acted on. Picric acid is used, in combination with carmine or anilin blue, as a staining material.

Osmic Acid.—This agent is one of peculiar value to the microscopist whose studies lie among the lower forms of animal and vegetable life; as its application immediately kills them, without producing any retraction or shrinking of their parts, and not only preserves their tissues, but brings out differences in those which might otherwise escape observation. It is sold in the solid state in sealed tubes, and is most conveniently kept as a 1 per cent. solution in distilled water. The solution should be preserved in well-stoppered bottles secluded from the light; and should be used with great caution, as it gives forth a pungent vapour which is very irritating to the eyes and nostrils. It is recommended by Dr. Pelletan,[1] M. Certes,[2] and M. Raphael Blanchard[3] for fixing and preserving animalcules (*Infusoria* and *Rotifera*), *Desmidieæ*, *Diatomaceæ*, *Bacteria*, *Vibriones*, &c.; by Dr. Vignal[4] for *Noctiluca*; by Mr. T. Jeffrey Parker[5] for *Entomostraca* and other small *Crustacea*; and it has been successfully used also in the preparation of *insect* structures. To the histologist its special value lies in its blackening of fatty matters and the medullary substance of nerve-fibres. And the embryologist finds it of peculiar value in giving firmness and distinctness to the delicate textures with which he has to deal. Various degrees of dilution of the 1 per cent. solution will be needed for these different purposes. Mr. Parker further states (*loc. cit.*) that he has found this agent very serviceable in the preparation of delicate vegetable structures. 'The acid seems to be taken up by each granule of the protoplasm, and these to be

[1] *Journ. of Roy. Microsc. Soc.* vol. i. 1878, p. 189.
[2] *Ibid.* vol. ii. 1879, p. 331; and *Comptes Rendus*, 1879, p. 433.
[3] *Ibid.* vol. ii. 1879, p. 463.
[4] Robin's *Archives de Physiologie*, tome xiv. 1878, p. 586.
[5] *Journ. of Roy. Microsc. Soc.* vol. ii. 1879, p. 381.

tissues are pinned on a cork lining a wide-mouthed bottle in
h is contained a small quantity of the acid either in a solid or
e form, and should be kept there until the tissues begin to
brown. Without any intermediate process such tissues may be
ed at once with picro-carmine (*q.v.*)

Osmic acid stains all fatty structures opaquely black, and should
be employed where these are present.

Professor J. N. Langley, of Trinity College, Cambridge, has
oyed osmic acid vapour in the preparation of certain mucous
ds with very fine results. As we have seen, the use of osmic
vapour to fix and harden tissues has been some time in use ;
its employment in the case of mucous glands preserved for the
ose of microscopic sections is due to Professor Langley.

By this means (1) the mucous granules can be preserved in a
or less spherical form, (2) they are stained with most reagents
more deeply than any other part of the tissue. The success of
nethod depends much upon the detail, and apparently to some
nt upon the gland. Professor Langley's best results have been
ined with the orbital gland of the dog. The following is the
od, viz. a fine needle with a silk thread is passed through a
l lobule of the fresh gland of an animal which has been killed
bleeding whilst under the influence of an anæsthetic, or which
been killed by decapitation ; the lobule is cut out, lowered by the
thread passing through it into a bottle half full of 2 per cent.
c acid. When the lobule is a short distance from the surface of
fluid, the stopper is inserted, which, as it clamps the thread,
s the piece of gland from touching the fluid. In a day the tissue,
hardened throughout, is washed for a few minutes with water,
d in 30 per cent. alcohol and in 50 per cent. alcohol for about a
ter of an hour, in 75 per cent. alcohol and in 95 per cent. alcohol
bout half an hour, in absolute alcohol for one to two hours, in
ol for half an hour to an hour, and then imbedded in hard
fin. Serial sections are cut, and then either (*a*) fixed on a glass

swollen up to form a clear mass, or being shrunken to irregular, small clumps. By the method given above the mucous granules in the stained specimen are very obvious, and further in a stimulated gland many of the alveoli show an inner zone of granules stained deep blue and an outer zone stained of a brownish tint. Even in the unsuccessful preparations, in which the granules are not separately distinguishable, the mucous portion of the cell is unusually well marked in stained specimens.

In the mucous cells of the mucous membrane of various lower vertebrates in which granules can be made out in the fresh state, the granules can often be preserved by the vapour of osmic acid. For certain special points in other glands, particularly in the parotid, the method is useful, but this together with further details with regard to its employment on mucous cells I propose to deal with after making further observations.

Bichromate of potass, in a 2 per cent. watery solution, may be used where very slow and prolonged hardening is required. With the addition of 1 per cent. of sulphate of soda, it constitutes *Müller's fluid*, which may be conveniently used to harden large pieces that may be left in it for several weeks; the fluid should be changed every other day for a fortnight, and weekly for the second fortnight. The hardened substance, after being well washed, is to be treated with spirit, as in the preceding case.

The best formula for this fluid is 2 oz. bichromate potass, 1 oz. sodium sulphide to one Winchester quart of water.

Staining Processes.—Much and increasing attention has been given of late years to the use of agents, which, either by simply dyeing or by chemically acting on organic substances in different modes and degrees, serve to differentiate the different parts of organs or tissues of complex structure, and to render more distinct such delicate features in preparations mounted in transparent media as might otherwise escape notice. One of the chief ends of staining animal tissues is to obtain a clear stain of the *nuclear* parts—the nuclei and their surrounding cell-protoplasm—as distinct from the non-nucleated parts of the same tissue. The agents which merely *dye* the tissues are for the most part colouring matters of vegetable or animal origin; those which act upon them *chemically* are mineral substances. The staining processes may be used either before or after section-cutting, according to circumstances. Where the substance is in mass, and is not readily penetrable by the staining fluid (which is especially liable to be the case where it has been hardened in chromic acid), it is generally better to stain the sections *after* cutting, if they hold sufficiently well together to bear being transferred from one fluid to another; and if the substance is to be imbedded in gum, and cut with the freezing microtome, it is generally preferable to stain the sections *after* they have been cut, as the processes necessary for the removal of the gum would be likely also to remove the dye. But where the substance to be cut has to be penetrated by wax or paraffin, it is better that the staining should be effected in the first instance. As a general rule, it is better that where the substance is to be stained *en masse* the

staining fluid should be weak and its action slow, because in that mode the stain is more equably diffused. When, on the other hand, the process is made use of with thin sections, it is convenient that the action should be more rapid, and the staining fluid may therefore be stronger; but unless its operation be carefully watched, so as to be stopped at the right stage, the whole tissue may be deeply dyed, and the value of the *selective* staining altogether lost.

It will generally be found convenient to carry on the staining of thin sections either in watch-glasses or in small shallow glass or porcelain vessels; but care must be taken not to place many sections together so as to lie one upon another, as this will prevent the staining from being uniform. Very useful receivers for sections that are to undergo staining are the solid glass blocks, now procurable at very small cost at the optician's, which are about $1\frac{1}{2}$ inch square and $\frac{3}{4}$ inch thick, and they have a shallow, saucer-like excavation on their upper surface into which sections may be placed, a flat glass cover being laid over the whole. Small delicate sections may often be stained upon the glass slides if they be mounted upon the slide, but where it can be effected at all, it is far preferable to mount upon the cover-glass. This section being placed and fixed upon the cover by processes shortly to be described, the paraffin is removed by turpentine, creosote or other means, and the whole placed, and kept in gentle motion, in 95 per cent. of alcohol; for a short time it is then held in 75 per cent. alcohol, and at once a drop of the stain dissolved in 75 per cent. alcohol is placed upon the section. It should then be put in a chamber where the moisture in the surrounding atmosphere should make the evaporation of the drop or so of stain very slow, or even impossible; here it should remain for from twelve to twenty-four hours. It should now be taken and a jet from a small wash-bottle containing 75 per cent. alcohol should be made to stream upon the slip, washing away the loose staining fluid thoroughly, after which dehydrate in strong alcohol and clear in cedar oil, mounting in xylol balsam (*q.v.*).

If, however, a watery stain has been used, after getting rid of the paraffin by turpentine, and washing this off with alcohol, we dip and waive the cover in *water*; this washes off the watery stain; then alcohol of increasing strengths is used until dehydration is effected as above.

If it be inconvenient or dangerous to manipulate the cover-glass by itself, it may be attached, for the purposes of manipulation, to a narrow, long slip of glass, on its upper surface, by a delicate point of wax.

It is customary to recommend the use of 'section lifters' in order to raise the delicate sections out of the fluid in which they finally are placed into the position in which they are to be mounted. For very large sections they are probably essential; but from personal experience, supported by the most accomplished histological mounters of our time, we believe them to be adverse to, rather than promotive of, good section-mounting. One of the many patterns recommended is shown in fig. 360, where it will be seen that one end of the 'lifter' is perforated, for the purpose of drainage, and the other is plain. It

must be manifest that the *less* we have to manipulate such delicate sections as we are now considering, the better; to get a section on and off the 'lifter' is a needless process. We should, as stated above, *mount on the cover-glass*, and this cover should be the only lifter employed.



FIG. 360.

Although it will involve a slight displacement in the contemplated order, we will, on account of its practical usefulness in this place, describe how this should be done.

The cover must be carefully cleaned, and properly selected as to size and tenuity. By means of a needle or the handle of an ivory dissecting-knife the turpentine in which the section is resting prior to mounting is gently disturbed, in a good-sized vessel or saucer, until the section desired is in its proper position on the cover. Now lay the cover, section upwards, on fresh blotting-paper, to take off the superfluous turpentine from the free side of the cover, and then hold the edge of the slip at an angle, more or less acute, with the section towards the blotting-paper, but never suffering the former to touch the lattter; when this has removed the superfluous turpentine from the section, lay the cover section upwards, on a glass slip, put on (say) the benzole balsam until it stands in an evenly diffused mound covering the section, and lay it aside absolutely protected from dust for twenty-four hours in order that the benzole may evaporate.

Now take it out, place upon the centre of the section one small drop of fresh benzole balsam, and turn the cover over on to a warm slip, being careful to have guides to the position on the slip on which it should be fixed; and in an hour or so we may clean off superfluous balsam and finish the slide.

To those who mount much this will prove the quicker plan, as, for fine results, it is undoubtedly the better.

It would be impossible in this treatise even to attempt to enumerate the principal stains now employed in the botanical and zoological laboratories where histology is pursued.

It will be the utmost we can find space for if we indicate those which we, from experience, have found most useful.[1]

Hæmatoxylin.—We believe this to be, in spite of some of its defects, one of the best, if not on the whole the best, of all stains. It is well known that it is the active principle in the extract of logwood. It is not readily or easily extracted; but it may be obtained in the market prepared.

An aqueous solution of it may be made in either of the following ways, viz.—

[1] For fuller information see the *Microtomist's Vade Mecum*, B. Lee; Cole's *Studies*; *Practical Histology*, Fearnley; *Botanical Micro-chemistry*, Poulson.



(α) Dissolve ·35 grm. hæmatoxylin in 10 grms. water. Dissolve 3 grms. alum in 30 grms. water. To the hæmatoxylin solution add a few drops of the solution of alum. It makes a beautiful violet fluid which stains nuclei a deep blue.

(β) Take 60 grms. of dried extract of hæmatoxylin, 180 grms. of powdered alum, and work them thoroughly together with a pestle and mortar, adding by degrees 300 c.c. of distilled water. Mix the whole carefully and then filter, after which add 20 c.c of absolute alcohol. It should be kept some time, well stoppered, and in a cool place before being used.

An alcoholic solution may be prepared by making the three following saturated solutions, viz. (1) calcic chloride in 70 per cent. alcohol, (2) powdered alum in the same, and (3) hæmatoxylin in absolute alcohol. Mix one part of the calcic chloride solution with eight parts of the alum solution, and add the hæmatoxylin solution drop by drop until a deep purple colour is attained. The colour becomes richer by time.

To stain with either of these solutions take a few minims of the one chosen and place in a dram of distilled water, then filter into a glass block as described above. Be provided with a 5 per cent. solution of sodium bicarbonate, and if the tissue has been hardened in any chromium or acid medium it must be placed in the bicarbonate before being put in the stain. In fact, tissues or sections must always be *cleared* of all trace of acid before being put in the stain; when this is accomplished they must be washed in distilled water at from 30° to 40° C. Place the sections now in the hollow of the block containing the filtered solution of hæmatoxylin for a period which may vary from five minutes to many hours; in the latter case the vessel containing the stain should be kept in a moist chamber.

From what has been already stated it will be understood that, after staining, all sections to be mounted in balsam must be dehydrated, or deprived of all water, which may be readily effected by thirty minutes in methylated spirit; they must then be *cleared* in oil of cloves until the section sinks in the oil, when it is transferred to turpentine and mounted.

If a logwood staining has been carried to excess it may be greatly reduced, and indeed brought to a desirable intensity, by being placed from a few seconds to a few minutes in the following solution, viz.

1 per cent. hydrochloric acid in distilled water .	1 part
Absolute alcohol	2 parts

This acts in the same way with tissues over-stained with carmine. Logwood stains vegetable sections with extreme delicacy and great beauty.

Dr. A. Hill, of Downing College, Cambridge, has employed with beautiful results an original method for applying Weigert's hæmatoxylin stain to nerve-cells, and to him the Editor is indebted for these otherwise unpublished details. As ordinarily used it is considered to be one of the virtues of Weigert's well-known staining method that the medullated nerve-fibres are stained a deep violet, while the grey matter through which they run merely takes on a brownish

tint. The object of Pal's modification of Weigert's stain is to render the grey matter still fainter in colour. Dr. Hill has shown, however, that it is possible to render nerve-cells and non-medullated fibres extremely susceptible to the stain by treating them beforehand with carmine alum or simply alum solution. To produce a successful result Weigert's staining method must be somewhat modified and the steps of the process about to be described rigidly followed: (1) Pieces of brain or spinal cord must be placed for six weeks in bichromate of ammonia to harden (2 to 2½ per cent.). (2) The bichromate is washed out with abundance of 30 per cent. spirit, changed daily until the solution takes no colour from the tissue. (3) The tissue is further hardened in strong alcohol. (4) Pieces of tissue of convenient size are placed for an hour in water to remove the spirit and then for two days in carmine alum solution. The best way to make carmine alum solution, which is a most useful stain for many purposes, is to place in a shallow dish carmine, potash, alum, and distilled water, boiling the mixture for three hours, the water being restored to its original level from time to time as it evaporates. Both carmine and alum should be *in excess*, i.e. in larger quantity than the water will dissolve. When cold the solution is decanted and filtered. (5) The tissue is then cut into sections which are placed for twenty-four hours in a solution of acetate of copper half saturated; for convenience a saturated solution is kept and mixed with an equal volume of distilled water before use. (6) From the acetate of copper the sections are placed in the hæmatoxylin mixture for eight hours, the mixture being maintained at a temperature of 40° C. *circ.* At the end of this time the sections are stained black and covered with a precipitate of hæmatoxylin. (7) The sections are then decolourised to exactly the right degree in a solution of ferricyanide of potassium. It is well to have a basin of water at hand into which the sections are placed from time to time to ascertain the progress of the decolorisation. If the sections are imbedded in celloidin it may always be safely assumed that the matrix of the tissue and the imbedding celloidin will be decolourised at the same time.

This method gives extremely good results when applied to the cerebellum or to groups of large nerve-cells such as constitute the nucleus of the third and other motor cranial nerves; a photo-micrograph of a section of the cerebellum of a lamb prepared by Dr. Hill is given at fig. 4 of the frontispiece. It was photographed ×77 diams. with a 1-inch apochromatic objective of N.A. 3, and sufficiently illustrates the value of Dr. Hill's method.

Weigert's hæmatoxylin solution:—

	Crystallised hæmatoxylin . .	1 gramme.
Dissolved in	absolute alcohol	10 c.c.
Add	distilled water	90 c.c.

Let the mixture come to the boil.

Weigert's decolourising mixture:—

Ferricyanide of potassium . .	2½ grammes.
Borax	2 grammes.
Water	200 c.c.

sential that the fluid should have a slight alkaline reaction. ery difficult to get perfectly good nuclear stains with carmine ase of tissues that have been treated with chromic and other Tissues hardened with picric acid or alcohol stain beautifully . The presence of too much alkali is injurious; the want of the other hand, causes the dye to act on the tissues generally, us negatives its differentiating effect. Dr. Beale directs it to pared as follows :—Ten grains of carmine in small fragments be placed in a test-tube, and half a drachm of strong liquor niæ added; by agitation and the heat of a spirit-lamp the e is soon dissolved, and the liquid, after boiling for a few s, is to be allowed to cool. After the lapse of an hour, much excess of ammonia will have escaped; and the solution is then nixed with 2 oz. of distilled water, 2 oz. of pure glycerin, and f alcohol. The whole may be passed through a filter, or after llowed to stand for some time the perfectly clear supernatant ay be poured off and kept for use. If, after long keeping, of the carmine should be deposited through the escape of mmonia, the addition of a drop or two of liquor ammoniæ dissolve it. Carmine is used as a *general* stain in 'double g'; and a suitable fluid for this purpose is made by mixing grains of carmine with two drachms of borax, and four fluid of water, and pouring off the clear supernatant fluid. To stain of carmine, the section should be immersed for a few s in a mixture of five drops of glacial acetic acid and one ounce er.

stain sections with this, first wash in distilled water, then in r cent. solution of sodium bicarbonate, and once more in d water. Transfer now to the carmine fluid, and leave from inute onwards until the stain is sufficient, then place in ated spirit and wash carefully. The sections may now be in spirit until required for mounting.

Mr. A. Cole has effected some extremely beautiful vegetable stains with another preparation of *borax carmine*.

i. Take 10 grains of borax and dissolve in 1 oz. of distilled water and add 4 drachms of glycerin and 4 drachms of alcohol.

ii. Take 10 grains of carmine and dissolve in 20 minims of liq. ammon. fort. and 30 minims of distilled water in a test-tube supplied with gentle heat. Let it cool, then thoroughly mix i. and ii.; filter and keep in a well-stoppered bottle.

Next make a saturated solution of iodin green in alcohol.

Bleach the sections in chlorinated soda solution. Wash or twenty-four hours in frequently changed water; stain in the carmine solution ten to thirty minutes; place now in methylated spirit until no more colour comes out. Wash in clean spirit; add enough of the iodin green solution to render this spirit bright green. Here the sections may remain until needed for mounting; then they must be taken out, washed in clean spirit, after which clear in oil of cloves and mount in balsam.

Picro-carminate of ammonia, known as *picro-carmine*, is a very excellent staining material, which is applicable to a great variety of purposes. Being somewhat difficult to prepare, it is best purchased ready for use (from Martindale, New Cavendish Street). Use a 2 per cent. filtered solution and let the section remain in from half an hour to twelve or more hours; wash rapidly in water and mount in Farrants' solution, glycerin, or balsam. This dye, used alone, produces a double staining, the nuclei fixing upon the carmine, while the other tissues are coloured yellow by the picric acid. If the sections be placed in methylated spirit, they may be kept without loss of colour and may be afterwards subjected to other processes. If placed in water the picric acid stain is removed, while the carmine is left.

Magenta has nearly the same *selective* staining property as carmine, and is useful in the examination of specimens for which rapid action and sharp definition are required. But, like other anilin dyes, it is liable to fade, and should, therefore, not be employed for permanent preparations. Ordinary magenta fluid may be prepared by dissolving 1½ grain of magenta crystals in 7 fl. oz. of distilled water, and adding ½ fl. oz. of rectified spirit. The colour of a section stained with this may be preserved for some time by immersing it in a ¼ per cent. watery solution of corrosive sublimate.

Eosin, which dyes the tissues generally of a beautiful garnet-red colour, should be used in a strong watery solution, and the sections must be well washed in water after staining. Its chief use is in 'double staining.'

For *blue* and *green* staining the various *anilin* dyes are principally used. They are, for the most part, however, rather fugitive in their effects, not forming durable combinations with the tissues they stain. Some of them are soluble in water, others only in spirit; and the selection between the dyes of these two classes will have to be guided by the mode in which the preparations are treated. These dyes are for the most part best fixed by benzole; and as the sections treated with this fluid may be at once mounted in Canada balsam, there is greater probability of their colours being preserved. Besides blue and green, the anilin series furnishes a deep rich *brown*,



nown as Bismarck's brown ; and a *blue-black*, which has been re-ommended for staining nerve-cells.

A good *blue* stain (tending to purple) is also given by the sub-ance termed *indigo carmine*, which is particularly recommended r sections of the brain and spinal cord that have been hardened chromic acid. A saturated solution of the powder in distilled ater having been prepared, this may either be used with the ad-ition of about 4 per cent. of oxalic acid, or, if an alcoholic fluid be referred, methylated spirit may be added to the aqueous solution, he mixture being filtered to remove any colouring matter that may ave been precipitated. If sections thus stained have an excess of olour, this may be removed by the action of a saturated solution of xalic acid in alcohol.

A beautiful *green* hue is given by treating with a saturated olution of picric acid in water sections previously stained with nilin blue, or the two agents may be used together, four or five parts f a saturated solution of the latter being added to a saturated queous solution of the former. This *picro-anilin*, it is believed, ay be relied on for permanence, and it acts well in double staining rith picro-carmine.

Two *chemical* agents, nitrate of silver and chloride of gold, are uch used by histologists for bringing out particular tissues, the ormer being especially valuable for the staining of the epithelium ells, the latter for staining nerve-cells, connective-tissue corpuscles, endon-cells, and cartilage-cells. The most advantageous use of these an only be made by the careful observance of the directions which vill be found in treatises on practical histology.

Molybdate of ammonia is recommended as affording a cool, blue-rey or neutral-tint *general* stain, which affords a pleasant 'ground'. o parts strongly coloured by bright, *selective* stains.

Staining Bacteria.—It is needful to employ somewhat special-sed methods for staining the saprophytic, pathogenic, and other chizomycetes. Some of these stain admirably, but others, especially he somewhat larger forms, are much altered, and unless observa-ions are controlled with accurate and constant observations on the rganisms in a living condition the most egregious errors may arise.

(1) Take half a dozen cases of putrescence in which solid tissues re decomposing, but which are in different states of decomposition. 'rom each take out with a pipette a small quantity, and transfer to carefully prepared and well-filtered decoction of veal in a small lass vessel, at the temperature of the respective putrefactions ; leave his for half an hour. Then with a fine pipette take out a minute rop from each vessel and diffuse each drop upon a cover-glass ; let vaporation go on in a warm room for twenty minutes, then fix the ilm of saprophytes by means of fairly strong osmic acid vapour p. 429) ; float the cover with the surface of bacteria downwards on a essel of violet of methylanilin for an hour or less, drain the edge f the cover-glasses on blotting-paper, and mount in glycerin.

(2) Now take drops of the fluid from the several vessels and in a noist, growing cell examine the living forms, and compare these with our dried and stained preparations.

(3) By another method, which will apply also to the bacillus of

tuberculosis, a layer of sputum or of putrefactive fluid may be spread as before upon a cover-glass, dried in an air-oven at about 100° F. Mix 1 c.c. of concentrated solution of methyl-blue in alcohol, 0·2 c.c. of 10 per cent. solution of potash and 200 c.c. of distilled water. Into this put the cover with its surface of bacteria and leave for twenty-four hours; the film will be coloured blue; place a few drops of a solution of vesuvin all over the film, which drives out the methyl-blue from all but the bacteria. Finish with alcohol and oil of cloves, and mount in balsam.

For the same purpose Professor Heneage Gibbes gives a method which has proved of great value. Take of rosanilin hydrochloride 3 grms. methyl blue 1 grm.; rub them up in a glass mortar. Then dissolve anilin oil, 3 c.c., in rectified spirit, 15 c.c.; add the spirit slowly to the stains until all is dissolved, then slowly add distilled water, 15 c.c. Keep in a stoppered bottle.

In the usual way dry the sputum &c. on a cover-glass; a few drops of the stain are poured into a test-tube and warmed. As soon as steam rises pour into a watch-glass and float the cover-glass on the warm stain; allow it to remain four or five minutes; or if we do not heat the stain but use it cold, let it remain for at least half an hour. Wash in methylated spirit until no colour comes off; drain, and then dry in an air-oven, and mount in balsam.

Staining Bacteria in Tissues.—To 100 parts of solution of caustic potash of 1 : 10,000 add 30 parts of saturated alcoholic solution of methyl-blue. Filter. Stain section for one or two hours, wash out with acetic acid of ½ per cent. followed by water. Dehydrate with absolute alcohol clear with cedar oil, and mount in balsam.

Double and Multiple Staining.– It is needful to allude to this mode of staining tissues, because during the last ten years it has received much attention, and also because of its apparent potentiality as an aid to histological research, and the extreme beauty of the preparations that may be made by its means. But in point of fact, as a means of investigation, it is of little value. It differentiates tissues, but not in a manner that will make any further knowledge of them at all possible. For class and popular purposes it will obtain; but it has, so far as can be at present seen, no future for the investigator.

Very beautiful effects are doubtless produced by the simultaneous or successive action of two or three staining fluids, which will respectively pick out (so to speak) the parts of a section for which they have special affinities. Thus, if a section through the base of the tongue of a cat or dog be stained with picro-carmine, rosein, and iodin green, the muscle-fibres will take the first, the connective tissue and protoplasm of cells will be coloured by the second, while the third will lay hold of the nuclei in the superficial epithelium, serous glands, and non-striated muscle in the vessels; and, further, the mucous glands will show a purple formed by the combined action of the red and green (Gibbes).[1] A very striking contrast of the like kind is shown in the double staining of the frond of a fern with log-wood and anilin blue, the *sori* taking the latter, and standing out

[1] See his *Practical Histology*, Chapter V.; and his paper in *Journ. of Roy. Microsc. Soc.* vol. iii. 1880, p. 390.

brilliantly on the general surface tinged by the former. The effects produced by using one stain *after* the other are generally much better than those obtained by simultaneous staining. The selective action of a second stain is not prevented by a previous general staining; for the dye which gives the latter seems to be more weakly held by the parts which take the former, so as to be (as it were) displaced by it. Thus, if a section of a stem be stained throughout by solution of eosin (2 grains to 1 oz.), and be then placed, after washing in strong alcohol, in a ½-grain solution of Nicholson's blue made neutral, the blue will in no long time entirely drive out the red; but by carefully watching the process, it will be seen that the different tissues will change colour in different times, the softer cells giving up their red and taking in the blue more quickly than the harder; so that, by stopping the process at the right point (which must be determined by taking out a section, dipping it in alcohol, and examining it under the microscope), the two kinds of cells are beautifully differentiated by their colouring.[1] The best effects are usually produced by carmine and indigo carmine, logwood and picro-carmine, carmine or logwood and anilin blue or anilin green. But very much has yet to be learnt on this subject; and the further investigation of it will be likely to produce results that will amply repay the time and labour bestowed.

It will be enough to give a practical illustration of some of the methods. Make a dilute solution of picro-carmine (about ten drops to a watch-glass of water). Stain in it for about half an hour, wash out for an hour in water acidulated with a few drops of acetic or picric acid, and then double stain either with *rosein and anilin blue*, or with *anilin violet and anilin blue*, or with *anilin violet and anilin green*, or with *rosein and anilin green*.

A process of *differential staining* of bacillus tuberculosis which was devised by MM. Pittion and Roux was presented recently (1889) to the Société de Médecine de Lyon, and has met with high commendation. It requires three solutions :—

A. Ten parts of fuchsin dissolved in 100 parts of absolute alcohol.

B. Three parts of liquid ammonia dissolved in 100 parts of distilled water.

C. Alcohol 50 parts, water 30 parts, nitric acid 20 parts, anilin green to saturation. In preparing this solution dissolve the green in the alcohol, add the water, and lastly the acid.

It is used thus, viz. to 10 parts of solution B add one part of solution A, and heat until vapour shows itself, then immerse the whole cover-glass prepared as in the ordinary way for staining. One minute suffices to stain the bacilli. Wash with plenty of water, and after rinsing with distilled water drop on the film side of the cover-glass a small quantity of solution C, which is not to remain more than forty seconds. Wash off with plenty of water, dry, and mount in xylol balsam.

The bacilli will be found to be stained a fine rose-red upon a pale green ground.

Chemical Testing.—It is often requisite, alike in biological and

[1] See *Journ. of Roy. Microsc. Soc.* vol. iii. 1880, p. 694.

in mineralogical investigations, to apply chemical tests in minute quantity to objects under microscopic examination. Various contrivances have been devised for this purpose; but the Author would recommend, from his own experience, the small glass syringe already described, or preferably the drop bottles, pp. 446–7, with a fine-pointed nozzle, as the most convenient instrument. One of its advantages is the very precise regulation of the quantity of the test to be deposited which can be obtained by the dexterous use of it; whilst another consists in the power of withdrawing any excess. Care must be taken in using it to avoid the contact of the test-liquid with the packing of the piston. Whatever method is employed, great care should be taken to avoid carrying away from the slide to which the test-liquid is applied any loose particles which may lie upon it, and which may be thus transferred to some other object, to the great perplexity of the microscopist. For testing inorganic substances the ordinary chemical reagents are of course to be employed; but certain special tests are required in biological investigation, the following being those most frequently required:—

α. Solution of *iodin* in water (1 gr. of iodin, 3 grs. of iodide of potassium, 1 oz. of distilled water) turns *starch* blue and *cellulose* brown; it also gives an intense brown to *albuminous* substances.

β. *Chlor-iodide of zinc* is made by dissolving zinc in pure hydrochloric acid, evaporating to the density of sulphuric acid, in contact with metallic zinc, and adding as much potassic iodide as the solution will take up. Finally saturate with iodin crystals.

This is extremely useful for the detection of pure cellulose. The zinc chloride converts cellulose into amyloid, which is then turned blue by free iodin. Wood-cells, cork-cells, the extine of pollen grains, and all lignified or corky membranes, are coloured yellow. Starch colours blue, but is rapidly disorganised.

A very weak solution will instantly detect tannin, the cell contents in which it forms a part becoming reddish or violet.

γ. Solution of *caustic potass or soda* (the latter being generally preferable) has a remarkable solvent effect upon many organic substances, both animal and vegetable, and is extremely useful in rendering some structures transparent, whilst others are brought into view, its special action being upon *horny* textures, whose component cells are thus rendered more clearly distinguishable.

δ. Dilute *sulphuric acid* (one of acid to two or three parts of water) gives to *cellulose* that has been previously dyed with iodin a blue or purple hue; also, when mixed with a solution of sugar, it gives a rose-red hue, more or less deep, with *nitrogenous* substances and with bile (Pettenkofer's test).

Sulphuric acid causes starch grains to swell and similarly affects cellulose.

ε. Concentrated *nitric acid* gives to *albuminous* substances an intense yellow.

ζ. *Acid nitrate of mercury* (Millon's test) colours albuminous substances red.

η. *Acetic Acid*, which should be kept both concentrated and diluted with from three to five parts of water, is very useful to the animal

onsequently renders more opaque such textures as contain them. pacity, however, may be removed by the addition of a small ity of soda.

reservative Media.—We have now to consider the various s of preserving the preparations that have been made by the al methods indicated above, and shall first treat of such as are able to those minute animal and vegetable organisms, and to sections or dissections of large structures, which are suitable ing mounted as *transparent* objects. A broad distinction may the first place laid down between *resinous* and *aqueous* pre- tive media; to the former belong only Canada balsam and nar, whilst the latter include all the mixtures of which water component, while partly dehydrating media, such as glycerin lcohol, occupy an intermediate position. The choice between ree kinds of media will partly depend upon the nature of the sses to which the object may have been previously subjected artly upon the degree of transparence which may be advantage- imparted to it. Sections of substances which have been not imbedded in, but penetrated by paraffin, wax, or cacao-butter, ave been stained (if desired) previously to cutting, are, as a rule, conveniently mounted in Canada balsam or dammar; since an be at once transferred to either of these from the menstruum hich the imbedding material has been dissolved out. The dur- y of this method of mounting makes it preferable in all cases to it is suitable, the exception being where it renders a very section *too* transparent, which is specially liable to happen with nar. When it is desired to mount in either of these media ns of structures that have been imbedded in gum or gelatin, substances must first be completely dissolved out by steeping ater; the sections must then be 'dehydrated' by subjecting to mixtures of spirit and water progressively increased in gth to absolute alcohol; and after this has been effected they

being thus formed of which it was often difficult to get rid), or the mounted slide was afterwards subjected to a more moderate heat of long continuance, the balsam would remain soft, and the cover liable to displacement. This is avoided by the method now generally adopted of previously getting rid of the turpentine by protracted exposure of the balsam to a heat not sufficient to boil it, and dissolving the resin thus obtained either in benzole or chloroform, but far preferably the former, the solution being made of such viscidity as will allow it to 'run' freely. Either of these solvents evaporates so much more quickly than turpentine that the balsam left behind hardens in a comparatively short time. *Xylol-balsam* is also of great value, being by some mounters preferred to any other. It is made of equal volumes of xylol and balsam. The *natural* balsam, however, may be preferably used (with care to avoid the liberation of bubbles by overheating) in mounting sections already cemented to the slides by hardened balsam, and also for mounting the chitinous textures of insects, which it has a peculiar power of rendering transparent, and which seem to be penetrated by it more thoroughly than they are by the artificially prepared solution. The solution of dammar in benzole is very convenient to work with, and hardens quickly.

The following are the principal *aqueous* media whose value has been best tested by general and protracted experience :—

α. Fresh specimens of minute protophytes can often be very well preserved in *distilled water* saturated with camphor, the complete exclusion of air serving both to check their living actions and to prevent decomposing changes. When the preservation of colour is not a special object about a tenth part of alcohol may be added, and this will be found a suitable medium for the preservation of many delicate animal textures.

β. Aqueous Solution of Carbolic Acid.—Even the very small quantity of this agent which cold water will take up has a powerful preservative effect, and the solution may be advantageously employed for mounting preparations of many delicate structures, both animal and vegetable.

γ. The same may be said of *salicylic* acid, which has been very successfully employed for delicate preparations in the small proportion that will dissolve in cold water. For coarser structures a stronger solution is preferable; and this may be made by combining with the acid a small quantity either of borax dissolved in glycerin or of acetate of potass.

δ. Where the preservation of minute histological detail is not so much desired as the exhibition of larger structural features of objects to be viewed by reflected light nothing is better than *dilute spirit*, the proportion most generally serviceable being one of alcohol to four or five of water, and an even weaker mixture serving to prevent further change in tissues already hardened by strong alcohol.

ε. Salt solution 0·75 per cent. sodium chloride in water.

ζ. Fruit juice, white of an egg.—Simply filter.

η. Syrup in which is dissolved 1 to 5 per cent. of chloral hydrate, or 1 per cent. of carbolic acid.

θ. Chloral Hydrate. A 5 per cent. solution in water, or 12 grains

chloral hydrate to 1 fluid ounce of camphor water. (Mount in strong glycerin jelly.)

ι. *Corrosive Sublimate and Salt.*—Use bichloride of mercury one part; common salt two parts, water 200 parts. This is very useful. It preserves well muscular fibre, nerves, and epithelia, and with very slight change is preservative of spermatic fluid.

κ. *Gum and Syrup.*—Gum-mucilage (B.P.) five parts, syrup three parts. Add 5 grains of pure carbolic acid to each ounce of the medium.

B.P. Gum-mucilage is made by putting 4 oz. of picked gum acacia in 6 oz. of distilled water until dissolved.

Syrup is made by dissolving a pound of loaf sugar in a pint of distilled water and boiling.

λ. *The glycerin jelly* prepared after the manner of Mr. Lawrence may be strongly recommended as suitable for a great variety of objects, animal as well as vegetable, subject to the cautions already given :—'Take any quantity of Nelson's gelatin, and let it soak for two or three hours in cold water, pour off the superfluous water, and heat the soaked gelatin until melted. To each fluid ounce of the gelatin add one drachm of alcohol and mix well; then add a fluid drachm of the white of an egg. Mix well while the gelatin is fluid, but cool. Now boil until the albumen coagulates, and the gelatin is quite clear. Filter through fine flannel, and to each fluid ounce of the clarified gelatin add six fluid drachms of Price's pure glycerin, and mix well. For the six fluid drachms of glycerin a mixture of two parts of glycerin to four of camphor-water may be substituted. The objects intended to be mounted in this medium are best prepared by being immersed for some time in a mixture of one part of glycerin with one part of diluted alcohol (one of alcohol to six of water).'[1] A small quantity of absolute phenol may be added to it with advantage. When used, the jelly must be liquefied by gentle warmth, and it is useful to warm both the slide and the cover-glass previously to mounting. This takes the place of what was formerly known as Dean's medium, in which honey was used to prevent the hardening of the gelatin.

μ. For objects which would be injured by the small amount of heat required to liquefy the last-mentioned medium, the *glycerin and gum* medium of Mr. Farrants will be found very useful. This is made by dissolving four parts (by weight) of picked gum arabic in four parts of cold distilled water, and then adding two parts of glycerin. The solution must be made without the aid of heat, the mixture being occasionally stirred, but not shaken, whilst it is proceeding; after it has been completed the liquid should be strained (if not perfectly free from impurity) through fine cambric previously well washed out by a current of clean cold water; and it should be kept in a bottle closed with a glass stopper or cap (not with cork) containing a small piece of camphor. The great advantage of this medium is that it can be used cold, and yet soon viscifies without cracking; it is well suited to preserve delicate animal as well as vegetable tissues, and in most cases increases their transparence.

[1] A very pure glycerin jelly, of which the Author has made considerable use, is prepared by Mr. Rimmington, chemist, Bradford, Yorkshire.

Of late years *glycerin* has been largely used as a preservative, either alone, according to the method of Dr. Beale, or diluted with water, or mixed with gelatinous substances. It is much more favourable to the preservation of colour than most other media, and is therefore specially useful as a constituent of fluids used for mounting vegetable objects in their natural aspects. It has also the property of increasing the transparence of animal structures, though in a less degree than resinous substances, and may thus be advantageously employed as a component of media for mounting objects that are rendered too transparent by balsam or dammar. Two cautions should be given in regard to the employment of glycerin: *first*, that, as it has a solvent power for carbonate of lime, it should not be used for mounting any object having a calcareous skeleton; and *second*, that, in proportion as it increases the transparence of organic substances, it diminishes the reflecting power of their surfaces, and should never be employed, therefore, in the mounting of objects to be viewed by *reflected* light, although many objects mounted in the media to be presently specified are beautifully shown by 'dark-ground' illumination.

1. A mixture of one part of glycerin and two parts of camphor-water may be used for the preservation of many vegetable structures.

2. For preserving soft and delicate marine animals which are shrivelled up, so to speak, by stronger agents, the Author has found a mixture of one part of glycerin and one of spirit with eight or ten parts of sea-water the most suitable preservative.

3. For preserving minute vegetable preparations the following method, devised by Hantzsch, is said to be peculiarly efficient: A mixture is made of three parts of pure alcohol, two parts of distilled water, and one part of glycerin; and the object, laid in a cement-cell, is to be covered with a drop of this liquid, and then put aside under a bell-glass. The alcohol and water soon evaporate, so that the glycerin alone is left: and another drop of the liquid is then to be added, and a second evaporation permitted, the process being repeated, if necessary, until enough glycerin is left to fill the cell, which is then to be covered and closed in the usual mode.[1]

Canada balsam is one of the most universally employed mounting media; very old hard balsam should be dissolved in enough pure benzole to make a thin solution, which should be carefully filtered.

Dammar.—Dissolve gum-dammar with heat in a mixture of equal parts of benzole and turpentine, and evaporate to a syrupy consistency. This is pleasant to use, but treacherous. The preparations often subsequently 'closed.'

Gum Styrax.—This is a resin which must be dissolved in benzole, choloroform, or ether. It should have the consistency of olive oil; all the benzole must be evaporated before putting the cover on the

[1] See the Rev. W. W. Spicer's *Handy-book to the Collection and Preparation of Freshwater and Marine Algæ, &c.* pp. 57–59. 'Nothing,' says Mr. Spicer, 'can exceed the beauty of the preparations of *Desmidiaceæ* prepared after Herr Hantzsch's method, the form of the plant and the colouring of the endochrome having undergone no change whatever.'

lip ; its refractive index is said to be then 1·583. Its value is in he mounting of diatoms, where a marked difference between the efractive index of the siliceous frustules and the medium in which hey are mounted facilitates the discovery of obscure details. There is . marked increase of visibility in proportion as the mounting medium as a refractive index higher than the object (diatom) mounted.

Now the refractive index of the silex of diatoms is 1·43. But Canada balsam is 1·52 : hence the 'index of visibility' in obscure markings is 9, while styrax by comparison is 15.

Monobromide of naphthalin is another of the media which nay be used with a high refractive index. It is colourless and oil-ike, soluble in alcohol and ether. It has a refractive index of ·658, and therefore a splendid index of visibility above balsam or tyrax ; but after a lapse of many months some change takes place vhich leaves the preparation as apparently perfect as before, but aving lost all the benefit of great refractive index.

The cover-glass should be run round with a ring of wax, then vith a ring of Heller's porcelain cement, and be finally closed with hellac.

But with the exception of some media of very high refractive ndex not by any means easy to use, devised by Professor H. L. Smith, there is no medium of such high value as that suggested and ·ery successfully employed by Mr. J. W. Stephenson, viz.

Phosphorus.—Its refractive index is 2·1, and its consequent ncrease of visibility is of immense value in some objects.

Phosphorus, it need hardly be said, is difficult and somewhat langerous to handle on account of its spontaneous combustion in ir, and the severe nature of the burns it inflicts. But it is with light practice by no means an unmanageable medium.

To prepare it, take a 2-drachm bottle with no contraction for the eck. Make a cylinder of wood that will just fit the inside of the eck. Fold some filter paper down and around this cylinder so that t will just fit tightly into the neck of the bottle, to the bottom of vhich it is forced, and the cylinder of wood withdrawn, leaving the ilter in its place. Now moisten the filter carefully with a few drops of bisulphide of carbon, and a piece of stick phosphorus from a quarter to three-eighths of an inch long should be placed in the filter, nd the bottle corked. The vapour of the bisulphide instantly acts n the phosphorus, and in about half an hour it will be in a fluid tate remaining in the filter. By releasing the cork and taking old of the filter tube with a pair of pliers and slowly drawing it pwards a partial vacuum is formed beneath it, and the pressure of he air on the surface of the fluid phosphorus forces it through the ilter, leaving the now brilliant fluid in the bottle.

With care, rapidity, and firmness withdraw the filter and plunge *nstantly* into a vessel of water close at hand.

In mounting we assume that the best course as advised above as been adopted, and that the diatoms to be mounted are either rranged or diffused upon the cover-glass.

Make a ring upon the slip of glue and honey cement (p. 382) sed warm and allowed to cool. It is now a stiff jelly. Lay the

cover in its place, with the diatoms downwards, touching the ring at one side, but raised by a fine wire on the side next the operator. A pipette may also be used made of glass tubing an eighth of an inch in external diameter, drawn to a fine point at one end, and somewhat enlarged at the other, and to which an indiarubber cap or nipple is fastened air-tight. This pipette must be passed through the centre of a cork fitting the bottle of phosphorus solution, and the fine end should plunge into the fluid and nearly touch the bottom of the bottle. By squeezing the rubber cap before the insertion of the pipette and releasing it after the point is well down, a small quantity of phosphorus rises in the pipette. It is withdrawn and inserted rapidly beneath the tilted end of the cover; the slightest pressure on the cap ejects enough phosphorus to fill the space between the cover and the slide; gently and firmly press it down and ring it with warm glue and honey.

In half an hour points of superfluous phosphorus may have exuded. With a pair of tweezers wet a piece of blotting-paper with bisulphide and absorb these away, plunging the paper at once into water. The slides should now be put aside for a day or two, then they may receive two or three ring-coatings of gold-size, and finally be finished with sealing-wax or shellac varnish.

It often is quite impossible to predicate beforehand what preservative medium will answer best for a particular kind of preparation; and it is consequently desirable, where there is no lack of material, to mount similar objects in two or three different ways, marking on each slide the method employed, and comparing the specimens from time to time, so as to judge the condition of each.



Fig. 361.
Dropping-bottle.

In dealing with the small quantities of fluid media required in mounting microscopic objects, it is essential for the operator to be provided with the means of transferring very small quantities from the vessels containing them to the slide, as well as of taking up from the slide what may be lying superfluous upon it. Where some one fluid, such as diluted alcohol or the carbolic acid solution, is in continual use, it will be found very convenient to keep it in the small dropping-bottle represented in fig. 361. The stopper is perforated, and is elongated below into a fine tube, whilst it expands above into a bulbous funnel, the mouth of which is covered with a piece of thin vulcanised indiarubber tied firmly round its lip. If pressure be made on this cover with the point of the finger, and the end of the tube be immersed in the liquid in the bottle, this will rise into it on the removal of the finger; if, then, the funnel be inverted, and the pressure be reapplied, some of the residual air will be forced out, so that by again immersing the end of the tube, and removing the pressure, more fluid will enter. This operation may be repeated as often as may be necessary, until the bulb is entirely filled; and when it is thus charged with fluid, as much or as little as may be needed is then

readily expelled from it by the pressure of the finger on the cover, the bulb being always refilled if care be taken to immerse the lower end of the tube before the pressure is withdrawn. We speak from large experience of the value of this little implement, which is very clean, simple, and useful. But the small pipettes now used so commonly for filling the stylographic pens, fitted into the centre of a cork and placed in any wide-mouthed bottle, will be found to be, though less elegant, equally useful and much less costly.

Solutions of Canada balsam and gum-dammar in volatile fluids are best kept in wide-mouthed *capped* jars, the liquid being taken out on a pointed glass rod, cut to such a length as will enable it to stand in the jar when its cap is in place. Great care should be taken to keep the inside of the cap and the part of the neck of the jar on which it fits *quite clean*, so as to prevent the fixation of the neck by the adhesion between these two surfaces. Should such adhesion take place, the cautious application of the heat of a spirit-lamp will usually make the cap removable. In taking out the liquid care should be taken not to drop it prematurely from the rod —a mischance which may be avoided by not taking up more than it will properly carry, and by holding it in a horizontal position, after drawing it out of the bottle, until its point is just over the slip or cover on which the liquid is to be deposited.

A bottle for use with reagents, enabling the operator to pour out only the quantity he desires, is invaluable. Small capped and stoppered bottles, the stoppers of which are *tubes*, and the well-fitting caps of which prevent evaporation, are very valuable for aqueous and thin fluids. We illustrate this bottle in fig. 362. All that is needful is to take the bottle, with the cap off, in the warm hand, and by slight expansion a drop or more as required is exuded. These bottles are easily procurable.

Fig. 362.—Expansion drop-bottle.

Fig. 363.
German drop-bottle.

But we like still better the small German bottles, shown in fig. 363, containing about 30 grammes, in which two deep grooves are cut on opposite sides of the stopper, so arranged that by giving the stopper half a turn one groove is connected with a hole in the neck of the bottle: this will be seen at *a* in fig. 363; the air travels down this groove, and by inverting the bottle the fluid enters the other groove of the stopper and finds its way to a third groove cut in the inside of the neck and extending to the lip. The figure shows the bottle complete.

Mounting Thin Sections.—The thin sections cut by the micro-

tome, or membranes obtained by dissection, do not require to be placed in cells when mounted in any viscid medium ; since its tenacity will serve to keep off injurious pressure by the cover-glass. When the preparation has been previously immersed in aqueous liquids, and is to be mounted in glycerin, glycerin jelly, or Farrants' medium, the best mode of placing it on the cover is to float it in a saucer or shallow capsule of water, to place the cover beneath it, and, when the object lies in a suitable position above it, to raise the cover cautiously, holding the object in place by a needle, until it is entirely out of the water ; and the small quantity of liquid still surrounding the object is to be carefully drawn off by blotting-paper, care being taken not to touch the object with it (as its fibres are apt to adhere) or to leave any loose fibres on the slide. Before the object is covered, it should be looked at under a dissecting or mounting microscope, for the purpose of improving (if desirable) its disposition on the slide, and of removing any foreign particles that may be accidentally present. A drop of the medium (liquefied, if necessary, by a gentle warmth) is then to be placed upon it, and another drop placed on the slip and allowed to spread out. The cover being then taken up with a pair of forceps must be inverted over the object, and brought to touch the slide at one part of its margin, the slide being itself inclined in the direction of the place of contact, so that the medium accumulates there in a little pool. By gently letting down the cover, a little wave of the medium is pressed before it, and, if enough of the medium has been deposited, the whole space beneath the cover will be filled, and the object completely saturated. If air-bubbles should unfortunately show themselves, the cover must be raised at one margin, and a further quantity of the medium deposited.

If, again, there are no air-bubbles, but the medium does not extend itself to the edge of the cover, the cover need not be raised, but a little may be deposited at its edge, whence it will soon be drawn in by capillary attraction, especially if a gentle warmth be applied to the slide. It will then be advantageous again to examine the preparation under the dissecting microscope ; for it will often happen that an opportunity may thus be found of spreading it better by the application of gentle pressure to one part or another of the covering-glass, which may be done without injurious effect either with a stiff needle or by a pointed stick ; a method whose peculiar value, when viscid media are employed, was first pointed out by Dr. Beale. The slide should then be set aside for a few days, after which its mounting may be completed. Any excess of the medium must first be removed. If glycerin has been employed, much of it may be drawn off by blotting-paper (taking care not to touch the edge of the cover, as it will be very easily displaced) ; and the remainder may be washed away with a camel's-hair brush dipped in water, which may be thus carried to the edge of the cover. The water having been drawn off, a narrow ring of liquefied glycerin jelly may be made *around—not on*—the margin of the cover (according to the suggestion of Dr. S. Marsh) for the purpose of fixing it before the cement is applied ; and when this has set, the slide may be placed on the turn-

able, and the preparation 'sealed' by a ring either of dammar or f Bell's cement, which should be carried a little *over* the edge of the over, and outside the margin of the ring of glycerin jelly. This ringing' should be repeated two or three times; and if the pre- aration is to be viewed with 'oil-immersion' lenses, it should be inished off with a coat of Hollis's glue, which is not attacked by edar oil. Until the cover has been perfectly secured, a slide carrying glycerin preparation should never be placed in an inclined posi- ion, as its cover will be almost sure to slide by its own weight. If lycerin jelly or Farrant's medium has been employed, less caution eed be used, as the cover-glass, after a few days' setting, will adhere ith sufficient firmness to resist displacement. The superfluous edium having been removed by the cautious use of a knife, the slide nd the margin of the cover may be completely cleansed by a camel's- air brush dipped in warm water; and, when quite dried, the slide, laced on the turn-table, may be sealed with gold size,—any other ment being afterwards added, either for additional security or for ppearance.'

It is well in mounting in glycerin jelly to soak the object in lute glycerin, and we prefer to 'ring' with benzole and balsam hich should harden. Then coat the ring with shellac varnish two three times and permanently finish with thin coats of gold-size.

When, on the other hand, the section or other preparation is to mounted in a resinous medium, it must have been previously pre- ared for this in the modes already described, which will present it to e mounter either in turpentine or some other essential oil, or in cohol. From either of these it may be transferred to the cover in e manner already described.

Mounting Objects in 'Natural' Balsam.—Although it is pre- rable for histological purposes to employ a solution of hardened lsam, yet as there are many objects for mounting for which the use the 'natural' balsam is preferable, it will be well to give some rections for its use. When sections of hard substances have been ound down on the slides to which they have been cemented, it is uch better that they should be mounted without being detached, nless they have become clogged with the abraded particles, and require be cleansed out—as is sometimes the case with sections of the ells, spines, &c. of echinoderms, when the balsam by which they ve been cemented is too soft. If the detachment of a specimen be sirable, it may be loosened by heat, and lifted off with a camel's- ir brush dipped in oil of turpentine. But, where time is not an ject, it is far better to place the slide to steep in ether or loroform in a capped jar until the object then falls off of itself by the lution of its cement. It may be thoroughly cleansed by boiling it methylated spirit, and afterwards laid upon a piece of blotting- per to dry, after which it may be mounted in fresh balsam on a ide, just as if it had remained attached. The slide having been armed on the water-bath lid, a sufficient quantity of balsam should dropped on the object, and care should be taken that this, if pre- ously loosened, should be thoroughly penetrated by it. If any air- bbles arise, they should be broken with the needle-point. The

cover having been similarly warmed, a drop of balsam should be placed on it, and made to spread over its surface; and the cover should then be turned over and let down on the object in the manner already described. If this operation be performed over the water-bath, instead of over the spirit lamp, there will be little risk of the formation of air-bubbles. However large the section may be, care should be taken that the balsam is well spread both over its surface and that of its cover; and by attending to the precaution of making it accumulate on one side by sloping the slide, and letting down the cover so as to drive a wave before it to the opposite side, very large sections may thus be mounted without a single air-bubble. (The Author has thus mounted sections of *Eozoön* three inches square.) In mounting minute balsam objects, such as *diatoms*, *polycystinæ*, *sponge-spicules*, and the beautiful minute spines of *ophiurida*, no better plan can be adopted than to arrange these objects carefully upon the cover, either by 'scattering' or 'arrangement,' and then to drop on to the whole cover and its arranged objects as much balsam as the cover will receive without overflow; this should stand free from dust for some hours, after which the partly hardened balsam may receive a small drop of fresh balsam, and being placed upon the slip in proper position, may by the use of gentle heat be pressed finally into position. When the chitinous textures of insects are to be thus mounted, they must be first softened by steeping in oil of turpentine; and a large drop of balsam being placed on a warmed slide, the object taken up in the forceps is to be plunged in it, and the cover (balsamed as before) let down upon it. It is with objects of this class that the *spring-clip* and the *spring-press* prove most useful in holding down the cover until the balsam has hardened sufficiently to prevent its being lifted by the elasticity of the object. Various objects (such as the palates of gasteropods) which have been prepared by dissection in water or weak spirit may be advantageously mounted in balsam; for which purpose they must be first dehydrated, and then transferred from rectified spirit into turpentine. *Carbolic acid* has been recommended by Dr. Ralph[1] as most efficient in drawing out water from specimens to be mounted in balsam or dammar, which afterwards readily take its place. Sections of horns, hoofs, &c. which afford most beautiful objects for the polariscope, are best mounted in natural balsam, which has a remarkable power of increasing their transparence. It is better to set aside in a warm place the slides which have been thus mounted before attempting to clean off the superfluous balsam in order that the covers may be fixed by the gradual hardening of what lies beneath them.

Mounting Objects in Aqueous Liquids.—By far the greater number of preparations which are to be preserved in liquid, however, should be mounted in a cell of some kind, which forms a *well* of suitable depth, wherein the preservative liquid may be retained. This is *absolutely necessary* in the case of all objects whose thickness is such as to prevent the glass cover from coming into close approximation with the slide; and it is *desirable* whenever that approxima-

[1] See the account of Dr. Ralph's method in *Journ. Roy. Microsc. Soc.* vol. iii. 1880, p. 858.

tion is not such as to cause the cover to be drawn to the glass slide by capillary attraction, or whenever the cover is *sensibly* kept apart from the slide by the thickness of any portion of the object. Hence it is only in the case of objects of the most extreme tenuity that the cell can be advantageously dispensed with; the danger of *not* employing it, in many cases in which there is no difficulty in mounting the object without it, being that after a time the cement is apt to run in beneath the cover, which process is pretty sure to continue when it may have once commenced. When cement-cells are employed for this purpose, care must be taken that the surface of the ring is perfectly flat, so that when the cover-glass is laid on, no tilting is produced by pressure on any part of its margin. As a general rule, it is desirable that the object to be mounted should be steeped for a little time previously in the preservative fluid employed. A sufficient quantity of this fluid being deposited to overfill the cell, the object is to be introduced into it either with the forceps or the dipping tube; and the slide should then be examined on the dissecting microscope that its entire freedom from foreign particles and from air-bubbles may be assured, and that its disposition may be corrected if necessary. The cover should then be laid on very cautiously, so as not to displace the object; which in this case is best done by keeping the drop highest in the centre, and keeping the cover parallel to the slide whilst it is being lowered, so as to expel the superfluous fluid *all round*. This being taken up by the syringe, the cement ring and the margin of the cover are to be dried with blotting-paper, especial care being taken to avoid drawing off too much liquid, which will cause the gold-size to run in. It is generally best to apply the first coat of gold-size *thin*, with a very small and flexible brush worked with the hand; this will dry sufficiently in an hour or two to hold the cover whilst being 'ringed' on the turn-table. And it is safer to apply a third coat a day or two afterwards; *old* gold-size, which lies thickly, being then applied so as to raise the ring to the level of the surface of the cover. As experience shows that preparations thus mounted, which have remained in perfectly good order for several years, may be afterwards spoiled by leakage, the Author strongly recommends that to prevent the loss of valuable specimens an additional coating of gold-size be laid on from time to time. But a device of much greater value in all fluid mounting is that adopted by Mr. Enock,[1] who puts a metallic ring of angular section (Γ) round the outside of the cell, slightly overlapping the cover-glass and enclosing the rim made good with cement: this proves perfect.

Mounting of Objects in Deep Cells.—The objects which require deep cells are, as a rule, such as are to be viewed by reflected light, and are usually of sufficient size and substance to allow of air being entangled in their tissues. This is especially liable to occur where they have undergone the process of decalcification, which will very probably leave behind it bubbles of carbonic acid. For the extraction of such bubbles the use of an air-pump is commonly recommended; but the Author has seldom found this answer the purpose satisfactorily,

[1] *Quekett Journ.* second series, vol. i. p. 40.

and is much disposed to place confidence in a method lately recommended—steeping the specimen in a stoppered jar filled with freshly *boiled water*, which has great power of drawing into itself either air or carbonic acid. Where the structure is one which is not injured by alcohol, prolonged steeping in this will often have the same effect. The next point of importance is to select a cover of a size exactly suitable to that of the ring, of whose breadth it should cover about two-thirds, leaving an adequate margin uncovered for the attachment of the cement. And the perfect flatness of that ring should then be carefully tested, since on this mainly depends the security of the mounting. It is to secure this that we prefer rings of tin or bone, to those of glass, for cells of moderate depth; for their surface can be easily made perfectly flat by grinding with water, first on a piece of grit, and then on a Water-of-Ayr stone, these stones having been previously reduced to a plane surface, or still better with a good flat file. If glass rings are not found to be 'true,' they must be ground down with fine emery on a plate of lead. When the cell has been thus finished off, it must be carefully cleaned out by dropping into it some of the mounting fluid; and should be then examined under the dissecting microscope for minute air-bubbles, which often cling to the bottom or sides. These having been got rid of by the needle, the cell should be finally filled with the preservative liquid, and the object immersed in it, care being taken that no air-bubbles are carried down beneath it. The cell being completely filled so that the liquid is running over its side, the cover may then be lowered down upon it as in the preceding case; or, if the cell be quadrangular, the cover may be sloped so as to rest one margin on its wall, and fresh liquid may be thrown in by the syringe, while the other edge is lowered. When the cover is in place, and the liquid expelled from it has been taken up by the syringe, it should again be examined under a lens for air-bubbles; and if any of these troublesome intruders should present themselves beneath the cover, the slide should be inclined, so as to cause them to rise towards the highest part of its circumference, and the cover slipped away from that part, so as to admit of the introduction of a little additional fluid by the pipette or syringe; and when this has taken the place of the air-bubbles the cover may be slipped back into its place. The surface of the ring and the edge of the cover must then be thoroughly dried with blotting-paper, care being taken that the fluid be not drawn away from between the cover and the edge of the cell on which it rests. These minutiæ having been attended to, the closure of the cell may be at once effected by carrying a thin layer of gold-size or dammar around and upon the edge of the glass cover, taking care that it touches every point of it, and fills the angular channel which is left along its margin. The Author has found it advantageous, however, to delay closing the cell for some little time after the superfluous fluid has been drawn off; for as soon as evaporation from beneath the edge of the cover begins to diminish the quantity of fluid in the cell, air-bubbles often begin to make their appearance which were previously hidden in the recesses of the object; and in the course of half an hour a considerable number are often collected. The cover should

hen be slipped aside, fresh fluid introduced, the air-bubbles removed, nd the cover put on again; and this operation should be repeated ntil it fails to draw forth any more air-bubbles. It will of course e observed that if the evaporation of fluid should proceed far air-ubbles will *enter* beneath the cover; but these will show themselves n the *surface* of the fluid; whereas those which arise from the bject itself are found in the deeper parts of the cell. When all these ave been successfully disposed of, the cell may be 'sealed' and ringed' in the manner already described.

Importance of Cleanliness.—The success of the result of any of he foregoing operations is greatly detracted from if, in consequence f the adhesion of foreign substances to the glasses whereon the bjects are mounted, or to the implements used in the manipulations, ny extraneous particles are brought into view with the object itself. ome such will occasionally present themselves, even under careful anagement; especially fibres of silk, wool, cotton, or linen, from he handkerchiefs, &c. with which the glass slides may have been iped; fibres of the blotting-paper employed to absorb superfluous uid; and grains of starch, which often remain obstinately adherent o the thin glass covers kept in it. But a careless and uncleanly anipulator will allow his objects to contract many other impurities han these; and especially to be contaminated by particles of dust loating through the air, the access of which may be readily prevented by proper precautions. It is desirable to have at hand a well-closed upboard furnished with shelves, or a cabinet of well-fitted drawers, or a number of bell-glasses upon a flat table, for the purpose of ecuring glasses, objects, &c. from this contamination in the intervals of the work of preparation; and the more readily accessible these receptacles are, the more use will the microscopist be likely to make of them. Great care ought, of course, to be taken that the media employed for mounting should be freed by effectual filtration from all floating particles, and that they should be kept in well-closed bottles.

Labelling and Keeping Mounted Objects.—The object of labels on mounted objects is of course to give clear and instant indication of the nature of the mount. But we must, if our cabinets have anything like scientific pretensions, not only know what the object may be, but some (perhaps many) other particulars about it. In fact, a thoroughly scientific cabinet must not rely on the labels on the mounts for all the information which it is desirable and even essential to have concerning them. One of the desiderata of every label should be the presence of a *number*, and this number should be at once placed in a book, arranged in columns to suit the requirements of the student, and most of the details should be placed in this book in association with the number.

For this to be of permanent service, however, the label on which the number is placed should be as permanent and immovable as the slip itself. We know of cabinets in which *only* numbers are marked on slides, and all details are recorded in 'the book.' We do not advise this; but all who keep cabinets know how in the course of years paper labels become displaced and lost, and in many instances the value of slides is greatly diminished.

What is wanted is a *permanently fixed* label, capable of receiving the chief points of character as well as the name and number of an object.

The present Editor has found the following plan to be hitherto, after fourteen years' trial, quite faultless.

Let the slips which are to be used for mounting have the two ends of the upper surface finely ground; at one end the ground surface may be three-quarters of an inch, and at the other end half an inch. On the ground surface we can write with a hard pencil as clearly and sharply as with a fine pen on cardboard.

On the broader ground surface let the principal facts as to the nature of the object be written and the number of the slide with a Faber pencil marked H H H H. On the narrower and opposite ground surface should be written what the object is mounted in, how stained, or whence obtained, the date of mounting &c.

Now when all this is written take *thin* covers, cut respectively $1 \times \frac{3}{4}$ inch and $1 \times \frac{1}{2}$ inch, and by means of benzole balsam, applied with or without heat, the ground surfaces should have these thin glasses put on over the writing and the entire ground surfaces; the result of course will be that the transparency of what was a ground and opaque surface will be wholly restored, and the writing will be clear and ineffaceable. If the bottom of the trays of the cabinets be whitened it will render still more easy the instant reading of the contents of the label.

The grinding of the slips is by no means difficult, and could not be costly if there arose a demand for them.

It is easy, however, to do all that is required. A block of wood to receive the slide in an excavation of its own shape and size, and a piece of wood half an inch thick, of the exact length ($1\frac{1}{4}$ inch) of the space between the labels, enables a lead 'buff' to be freely used with fine emery and the work is speedily done. Of course the finer the emery the finer the surface; and the finer the surface the more delicate the writing may be made. The label may in fact be as ornate and elegant as we please. Nor need we be confined to an oblong shape. Oval or round spaces could be ground on the slips and thin covers of corresponding size could be accordingly used. This method gives a little more trouble and is slightly more expensive, but in elegance and above all in durability we believe it has no equal.

For the preservation of objects, the pasteboard boxes now made at a very reasonable cost, with wooden racks, to contain six, twelve, or twenty-four slides, will be found extremely useful. For the management of a large collection the following has proved itself to be thoroughly practical, and can be universally employed. The species, genus, and character of the slides may be disregarded. Place the slides in the cabinet just as they come, numbering each consecutively. The exterior of *cabinets* should show from what number to what number the cabinet contains: thus, 527 to 842. The porcelain slab on the *drawer* may indicate from what number to what number the drawer contains: thus, 527 to 539. Now a number of notebooks should be procured, so that there may be a separate notebook for each subject; the size of the notebook must be regulated to the importance of the special department the collector has taken up.

Thus a diatomist would have probably a thick ledger for his diatom collection, whereas an entomologist would have a thin notebook for his diatoms and a thick ledger for his insects, and so on. The notebooks might be distinguished from one another by a letter of the alphabet.

In the event of a second notebook being required for the same subject or class of objects, it might be identified by doubling the letter; thus, D D. Now a large *index notebook* will be required in which one line is given to each slide. This notebook contains merely the number of the slide and the letter and page of the special notebook wherein all about the slide will be found. Thus:—

649, F 127.

This means that in notebook F on page 127 we shall find an account of slide No. 649.

On turning to notebook F we find (say) that the subject is geology. The following will be a facsimile of the page:—

Slide No. 649 127

Section of porphyry from Peterhead, Aug. 1886.—The quartz crystals in this section have minute cavities containing a liquid CO_2. In each cavity there is a bubble; some of these bubbles are extremely minute, and exhibit rapid Brownian movement. A good example of which is—

No. 2 (referring to a second microscope when used), 46–51.

A large bubble with no Brownian movement.

No. 2 (microscope), 44–47.

Section too thick for oil immersion.

Best seen dry ¼ ·95 N.A. deep eye-piece; condenser aperture ·6 N.A.

At the back of each notebook there is an alphabetical index. In this instance if we look up porphyry we shall find 127, and if we look up quartz (cavities in) we shall find 127, and if we look up carbonic acid (in quartz) we shall find 127, and if we look up bubbles (in quartz) we shall find 127.

By this means the collector can find a slide if he know the subject, and also the subject if he have the slide.

This is the only scientific method we know of dealing with a microscopical collection; it is one of the greatest practical mistakes to make the cabinet its own index. It always ends in supreme confusion. But for the purposes of the man of science a large cabinet made with a view to the reception of his own slides is far preferable. The majority of slides are 3+1 inches; but all are not, some geological and mineralogical sections, sections of coal, &c. are often much larger. Many objects, again, are in deeper cells than the ordinary cabinet drawer or slide-box will admit of; all this may be provided for, and if money be not a special object, a design with two or three special and smaller cabinets may be made for the reception of special series of mounts.[1]

[1] It will be understood that there are many forms of cabinet which space prevents our describing; they are made suitable for the pocket, for postal transmission, &c., and may be readily seen at the opticians'.

Collection of Objects.

A large proportion of the objects with which the microscopist is concerned is derived from the minute parts of those larger organisms, whether vegetable or animal, the collection of which does not require any other methods than those pursued by the ordinary naturalist. With regard to such, therefore, no special directions are required. But there are several most interesting and important groups both of plants and animals, which are themselves, on account of their minuteness, essentially *microscopic*; and the collection of these requires peculiar methods and implements, which are, however, very simple, the chief element of success lying in the knowledge *where* to look and *what* to look for. In the present place, *general* directions only will be given; the particular details relating to the several groups being reserved for the account to be hereafter given of each.

Of the microscopic organisms in question, those which inhabit fresh water must be sought for in pools, ditches, or streams through which some of them freely move; whilst others attach themselves to the stems and leaves of aquatic plants, or even to pieces of stick or decaying leaves, &c. that may be floating on the surface or submerged beneath it; while others, again, are to be sought for in the muddy sediments at the bottom. Of those which have the power of free motion, some keep near the surface, whilst others swim in the deeper waters; but the situation of many depends entirely upon the light, since they rise to the surface in sunshine, and subside again afterwards. The collector will therefore require a means of obtaining samples of water at different depths, and of drawing to himself portions of the larger bodies to which the microscopic organisms may be attached. For these purposes nothing is so convenient as the *pond-stick*, which is made in two lengths, one of them sliding within the other, so as when closed to serve as a walking-stick. Into the extremity of this may be fitted, by means of a screw socket, (1) a cutting-hook or curved knife, for bringing up portions of larger plants in order to obtain the minute forms of vegetable or animal life that may be parasitic upon them; (2) a broad collar, with a screw in its interior, into which is fitted one of the screw-topped bottles made by the York Glass Company; (3) a ring or hoop for a muslin ring-net. When the bottle is used for collecting at the surface, it should be moved sideways with its mouth partly below the water; but if it be desired to bring up a sample of the liquid from below, or to draw into the bottle any bodies that may be loosely attached to the submerged plants, the bottle is to be plunged into the water with its mouth downwards, carried into the situation in which it is desired that it should be filled, and then suddenly turned with its mouth upwards. By unscrewing the bottle from the collar, and screwing on its cover, the contents may be securely preserved. The net should be a bag of fine muslin, which may be simply sewn to a ring of stout wire. But it is desirable for many purposes that the muslin should be made removable; and this may be provided for by the substitution of a wooden hoop grooved on its outside, for the wire ring; the muslin being strained upon it by a ring of

ulcanised indiarubber, which lies in the groove, and which may be eadily slipped off and on, so as to allow a fresh piece of muslin to be ut in the place of that which has been last used. At the end of the uslin bag is tied a small rimmed tube-bottle of thin clear glass hree inches long by one inch in diameter. In this, objects can be irly seen. The collector should also be furnished with a number f bottles, into which he may transfer the samples thus obtained, nd none are so convenient as the screw-topped bottles made in all zes by the York Glass Company. It is well that the bottles should e fitted into cases, to avoid the risk of breakage. When animalcules re being collected, the bottles should not be above two-thirds lled, so that adequate air-space may be left. Whilst engaged in ie search for microscopic objects, it is desirable for the collector to ossess a means of at once recognising the forms which he may ather, where this is possible, in order that he may decide whether the athering' is or is not worth preserving; and for this purpose we know nothing better, unless a small travelling microscope be required, than couple of Steinheil loups, magnifying six and ten diameters.

Mr. J. D. Hardy suggests what we have found of great use, viz. *flat bottle*, as a very valuable piece of apparatus for collecting.[1] It is ade by cutting a ⊔-shaped piece out of a flat and solid piece of india- ubber, about 6 inches long by 2¾ inches broad, and ¾ inch thick; gainst each side is cemented (by means of Miller's caoutchouc ement) a piece of good thin plate-glass, and the bottle is complete. small portion cut from the inner piece makes a naturally fitting ork. One or two more, and smaller, bottles can be made with the emaining indiarubber. It is essential that the material should be least ¾ inch thick in order to make a wide bottle, and allow pond- eeds to be put inside without difficulty and pressure. A flat bottle is ade by Mr. Stanley, London Bridge, which we have good reason to rite favourably of. It is ground on its outer surfaces, and internal regularities almost wholly disappear when filled with water; an bjective from 3 inches to 1½ inch may be well employed with it.

Even with the best ordinary round dipping bottles it is very ifficult to see minute animals clearly, whilst with this flat bottle ne can see at a glance almost everything the dip contains, and very object can be examined with the pocket lens with ease.

For collecting purposes the objects sought in pond or stream are ivisible into free-swimming, and attached or fixed to water plants &c.

The free-swimming are to be secured with the net, the bottle tached to which should be examined after each sweep of the net; nd the flat bottle may be also filled for examination. The mud at ie bottom of the pond must not be stirred by the net, since of ourse it obscures the objects.

The infusoria, rotifera, &c. are best found with the flat bottle. ollect a lot of the 'weeds' growing in pond or stream, and place iese in the bottle; then Mr. Rousselet says: 'The tree-like colo- es of Vorticellæ; Epistylis, Zoöthamium, and Carchesium, the umpet-shaped Stentors, the crown Rotifer Stephanoceros, the ibes of Melicerta, Lyminas, the various Polyzoa, also Hydra, nd many more, can at once be seen with the naked eye, when

[1] *Q.M. Journ.* ser. ii. vol. ii. p. 55.

present, and in this way the good branches can be selected. Some creatures, however, such as the beautiful floscules, cannot be seen easily, even with the lens, not so much on account of their small size, as of the perfect transparency of their bodies. Experience will soon teach one how to see which branches are likely to prove prolific. As a general rule, old-looking but still sound and green branches will be the best. The Water Milfoil (Myriophyllum) is decidedly the best of water plants to examine and collect, on account of the ease with which its leaves can subsequently be placed under the microscope. Anacharis is much more difficult of manipulation, and I mostly only take it now to aërate my aquaria.

In placing a weed in the flat bottle, do not put in more than one branch at a time, otherwise the branches will only obscure each other and render examination more difficult.

When searching for Polyzoa, such as Lophopus, Plumatella, Fredericella, it is advisable to examine the rootlets of trees growing at the edge of the water, and also to drag up weeds from the middle of the pond or canal by means of a loaded hook and line.

A good collection thus made is transferred to small aquaria 6 to 8 inches high, 5 to 6 inches long, and 1 to 1½ inch wide; these we have used for at least ten years and can attest their great value in making the best possible use of a good day's collecting, and studying in the most intelligent way the objects collected.

Rotifers can generally be kept a week or a fortnight, some species much longer; their lives, as well as those of Polyzoa can be prolonged by feeding them about twice daily with a green soup made by crushing some anacharis, or other green weed, in a small mortar in a little water, which is then filtered through muslin. They can be seen to feed on this under the microscope, their tiny stomachs soon becoming filled with little balls of chlorophyll.

Under favourable conditions Melicerta, Stephanoceros, the Floscules, and also Asplanchna, and other forms, breed and multiply in the aquarium, and can then be preserved for a considerable time.

A little mud taken from a pond in winter or early spring, and put in a tank at home, will often produce an unexpected number and variety of rotifers and infusoria, which are hatched from winter eggs and dormant germs.[1]

There must of course be a balance in every tank between the animal and vegetable life, or aëration must be artificially maintained. So also food must be obtainable by the organisms, however small. But experience alone is the perfect teacher in this matter.

The same general method is to be followed in the collection of such *marine* forms of vegetable and animal life as inhabit the neighbourhood of the shore, and can be reached by the pond-stick. But there are many which need to be brought up from the bottom by means of the *dredge*, and many others which swim freely through the waters of the ocean, and are only to be captured by the *tow-net*. As the former is part of the ordinary equipment of every marine naturalist, whether he concern himself with the microscope or not, the mode of using it need not be here described; but the

[1] On some Methods of Collecting and Keeping Pond Life for the Microscope,' from the *Trans. Middlesex Nat. Hist. Soc.*

efore it is again immersed. It is by this simple method that ine *animalcules*, the living forms of *Radiolaria*, the smaller *tusoids* (with their allies *Beroe* and *Cydippe*), *Noctiluca*, the -swimming larvæ of *Echinodermata* some of the most curious he *Tunicata*, the larvæ of *Mollusca*, *Turbellaria*, and *Annelida*, e curious adult forms of these classes, *Entomostraca*, and the æ of higher *Crustacea*, are obtained by the naturalist; and great increase in our knowledge of these forms which has been ied within recent years is mainly due to the assiduous use ch has been made of it by qualified observers. It is important ear in mind that, for the collection of all the more delicate of organisms just named (such, for instance, as *echinoderm larvæ*), essential that the boat should be rowed so slowly that the net move *gently* through the water, so as to avoid crushing its soft tents against its sides. Those of firmer structure (such as the *omostraca*), on the other hand, may be obtained by the use of a -net attached to the stern of a sailing-vessel, or even of a mer, in much more rapid motion.[1] When this method is em- red, it will be found advantageous to make the net of conical n, and to attach to its deepest part a wide-mouthed bottle, ch may be prevented from sinking too deeply by suspending it n a cork float: into this bottle many of the minute animals ght by the net will be carried by the current produced by the ion of the vessel through the water, and they will be thus oved from liability to injury. It will also be useful to attach to ring an inner net, the cone of which, more obtuse than that of outer, is cut off at some little distance from the apex; this es as a kind of valve, to prevent objects once caught from being hed out again. The net is to be drawn in from time to time, the bottle to be thrust up through the hole in the inner cone; its contents being transferred to a screw-capped bottle for mination, the net may be again immersed. This form of net,

CHAPTER VIII

MICROSCOPIC FORMS OF VEGETABLE LIFE—THALLOPHYTES

THOSE who desire to make themselves familiar with microscopic appearances, and to acquire dexterity in microscopic manipulation, cannot do better than educate themselves for more difficult inquiries by the study of those humblest types of vegetation which present organic structure under its most elementary aspect. And such as desire to search out the nature and conditions of living action will find in the study of its simplest manifestations the best clue to the analysis of those intricate and diversified combinations under which it presents itself in the highest animal organisms. For it has now been put beyond question that the fundamental phenomena of life are identical in plants and in animals, and that the living substance which exhibits them is of a nature essentially the same throughout both kingdoms. The determination of this general fact, which forms the basis of the science of BIOLOGY, is the most important result of modern microscopic inquiry; and the illustration of it will be kept constantly in view, in the exposition now to be given of the chief applications of the microscope to the study of those minute *protophytes* (or simplest forms of plant-life), with whose form and structure, and with whose very existence in many cases, we can only acquaint ourselves by its aid.

It was formerly supposed that *living action* could only be exhibited by *organised structure*. But we now know that all the essential functions of life may be carried on by minute 'jelly-specks,' in whose apparently homogeneous semi-fluid substance nothing like 'organisation' can be detected; and, further, that even in the very highest organisms, which present us with the greatest variety of 'differentiated' structures, the essential part of the life-work is done by the same material—these structures merely furnishing the mechanism (so to speak) through which its wonderful properties exert themselves. Hence this substance,[1] known in vegetable

[1] Attention was drawn in 1835 by Dujardin (the French zoologist to whom we owe the transfer of the *Foraminifera* from the highest to the lowest place among invertebrate animals) to the fact that the bodies of some of the lowest members of the animal kingdom consist of a structureless, semi-fluid, contractile substance, to which he gave the name *sarcode* (rudimentary flesh). In 1851 the eminent botanist Von Mohl showed that a similar substance forms the essential constituent of the cells of plants, and termed it *protoplasm* (primitive plastic or organisable material). And in 1863 it was pointed out by Prof. Max Schultze, who had made a special study of the rhizopod group, that the 'sarcode' of animals and the 'protoplasm' of plants are *identical*. See his memoir *Ueber das Protoplasma der Rhizopoden und Pflanzenzellen*.

nutrient material obtained from without ; 2, its power of
ous movement, which shows itself in an extraordinary variety
ns, sometimes slow and progressive, sometimes rapid, some-
ave-like and continuous, and sometimes rhythmical with
intervals of rest. When examined under a sufficiently high
ing power, multitudes of minute granules are usually seen to
sed through it, which have been termed 'microsomes.'
sm, whether living or dead, has a great power of absorbing
but the distinction between these two states is singularly
by its behaviour in regard to any colouring matter which the
ay contain. Thus, if living protoplasm be treated with a
of carmine, it will remain unstained so long as it retains
ity. But if the protoplasm be dead, the carmine will at once
its whole substance, and stain it throughout with a colour
ore intense than that of the solution ; thus furnishing (as
; pointed out by Dr. Beale) a ready means of distinguishing
minal matter' or protoplasmic component of the tissues of
nimals, from the 'formed material' which is the most con-
part of their structure.

those minute and simple forms of life with which the micro-
ings us into acquaintance essentially consist of particles of
sm, each kind having usually a tolerably definite size and
nd showing (at least in some stage of its existence) some-
stinctive in its habit of life. And it is rather according to
nner in which they respectively live, grow, and multiply,
account of any structural peculiarities, that they are assigned
vegetable or to the animal kingdom respectively. It is
ble, in the present state of our knowledge, to lay down any
line of demarcation between the two kingdoms ; since there
ngle character by which the animal or vegetable nature of
anism can be tested. Probably the one which is most
y applicable among those that most closely approximate to

ence of which animal life would be impossible, is certainly the *prominent* attribute of the *vegetable*. We shall find that the *protozoa* (or simplest animals) are supported as exclusively either upon other protozoa or upon protophytes, as are the highest animals upon the flesh of other animals or upon the products of the vegetable kingdom; whilst many *protophytes*, in common with the highest plants, draw *their* nourishment from the atmosphere or the water in which they live, and, like them, are distinguished by their power of decomposing carbonic acid (CO_2) under the influence of light—setting free its oxygen, and combining its carbon with the elements of water to form the carbohydrates (starch, cellulose, &c.), and with those of atmospheric ammonia to form nitrogenous (albuminoid) compounds. And we shall find, moreover, that even such *protozoa* as have neither stomach nor mouth receive their alimentary matter direct into the very substance of their bodies, in which it undergoes a kind of digestion; whilst *protophytes* absorb through their external surface only, and take in no solid particles of any description. With regard to *motion*, which was formerly considered the distinctive attribute of animality, we now know, not merely that many protophytes (perhaps all, at some period or other of their lives) possess a power of spontaneous movement, but also that the instruments of motion (when these can be discovered) are of the very same character in the plant as in the animal, being little hair-like filaments, termed *cilia* (from the Latin word *cilium*, an eye-lash), or longer whip-like *flagella*, by whose rhythmical vibrations the body of which they form part is propelled in definite directions. The peculiar contractility of these organs seems to be an intensification of that of the general protoplasmic substance, of which they are special extensions.

There are certain plants, however, which resemble animals in their dependence upon organic compounds prepared by other organisms, being themselves unable to effect that fixation of carbon by the decomposition of the CO_2 of the atmosphere, which is the first stage in their production. Such is the case, among *phanerogams* (flowering plants), with the leafless 'parasites' which draw their support from the tissues of their 'hosts.' And it is the case also, among the lower *cryptogams*, with the entire group of FUNGI; which, however, in a large number of cases, depend rather for their nutritive materials upon organic matter in a state of decomposition, many of them having the power of promoting that process by their *zymotic* (fermentative) action. Among animals, again, there are several in whose tissues are found organic compounds, such as chlorophyll, starch, and cellulose, which are characteristically vegetable; but it has not yet been proved that they *generate* these compounds for themselves by the decomposition of CO_2.

The plan of organisation recognisable throughout the vegetable kingdom presents this remarkable feature of uniformity, that the fabric, alike in the highest and most complicated plants and in the lowest and simplest forms of vegetation, consists of nothing else than an aggregation of the bodies termed *cells*, every one of which (save in the forms that lie near the border-ground between animal

etable life) has its little particle of protoplasm enclosed by a
f the substance termed *cellulose*—a non-nitrogenous substance
l in chemical composition with starch. The entire mass of
which any vegetable organism is composed has been gene-
om one ancestral cell by processes of multiplication to be
ly described; and the difference between the fabrics of the
nd of the highest plants essentially consists in this, that whilst
ls produced by the repeated multiplication of the ancestral
he protophyte are all mere repetitions of it and of one another,
ving *by* and *for* itself, those produced by the like multi-
n of the ancestral cell in the oak or palm not only remain in
connection, but go through a progressive 'differentiation,'
inary type of the cell undergoing various modifications to be
ed in their proper place. A composite structure is thus de-
, which is made up of a number of distinct 'organs' (stem,
roots, flowers, &c.), each of them characterised by specialities
rely of external form, but of internal structure; and each
ning actions peculiar to itself, which contribute to the life
plant *as a whole*. Hence, as was first definitely stated by
en, it is in the *life-history of the individual cell* that we
e true basis of the study of vegetable life in general.

have now to consider in more detail the structure and life-
of the typical plant-cell, and shall begin by treating of the *cell-*
This cell-wall is composed, as long as the cell is in a living state,
substance known as *cellulose*, one of the group of compounds
'carbohydrates,' and bearing the definite chemical composi-
$H_{10}O_5$. From a physical point of view it consists of particles
llæ of cellulose surrounded by water. With regard to the mode
rth of the cell-wall, two hypotheses have been proposed: one,
is formed by *apposition*, that is, by the constant addition of
ayers to the inner surface of the cell-wall; the other that it
es by *intussusception*, or the intercalation of fresh particles of
e between those already in existence. Our present state of
dge does not enable us to decide definitely between these two
s.

e *contents* of the plant-cell, which may be collectively termed
toplasm (answering to the 'endosarc' of rhizopods), or, when
y coloured throughout (as in many *algæ*), the *endochrome*,
in the first place of an outer layer of protoplasmic substance
he *ectoplasm*, *primordial utricle*, or *parietal utricle*. This is an
ely thin and delicate layer, so that it escapes attention so long
mains in contact with the cell-wall; and it is only brought
ew when separated from this, either by developmental changes
6), or by the influence of reagents which cause it to con-
y drawing forth part of its contents (fig. 364, C). It is not
r defined on its internal face, but passes gradationally into the
nass of protoplasm, from which it is chiefly distinguishable by
sence of granules; and it is shown by the effects of reagents
e the *albuminous* composition of protoplasm. It may thus be
ed as the slightly condensed external film of the protoplasmic
vith which its inner surface is in contact; and it essentially

corresponds with the 'ectosarc' of *Amœba* or any other rhizopod. The 'ectoplasm' and 'cellulose wall' can be readily distinguished from each other by chemical tests; and also by the action of carmine, which stains the protoplasmic substance (when dead) without affecting the cellulose wall. The further contents of the cell consist of a watery fluid called 'cell-sap,' which holds in solution sugar, vegetable acids, saline matters, &c.; the peculiar body termed the 'nucleus'; and chlorophyll corpuscles (enclosing starch granules), oil particles, &c. In the young state of the cell the whole cavity is occupied by the protoplasmic substance, which is, however, viscid and granular near the cell-wall, but more watery towards the interior. With the enlargement of the cell and the imbibition of water, clear spaces termed *vacuoles*, filled with watery cell-sap, are seen in the protoplasmic substance; and these progressively increase in size and number, until they come to occupy a considerable portion of the cavity, the protoplasm stretching across it as an irregular network of bands. When, as usually happens, the 'nucleus' lies imbedded in the outer protoplasmic layer, these bands are gradually withdrawn into it, so that the separate vacuoles unite into one large general vacuole which is filled with watery cell-sap. But where the 'nucleus' is situated nearer to the centre of the cell, part of the protoplasm collects around it, and bands or threads of protoplasm stretch thence to various parts of the parietal layer. It is by the contractility of the protoplasmic layer that the curious 'cyclosis' hereafter to be described is carried on within the plant-cell, which is the most interesting to the microscopist of all its manifestations of vital activity. The *nucleus* is a small body, usually of lenticular or subglobose form (fig. 364, A, *a*), and of albuminous composition, that lies imbedded in protoplasmic substance, either on the cell-wall or nearer the centre of the cavity. It is not, however, constantly present even in the higher forms of cell-structure; for in those cells whose active life has been completed, the nucleus is usually absent, having probably been resolved again into the protoplasm from which it was originally formed. And in the cells of some of the lower cryptogams it has not at present been distinguished with certainty at any stage of their existence. Cells containing a number of nuclei, or '*multi-nucleated cells*,' are not uncommon. They occur, for example, in many algæ, in the 'suspensor' and 'embryo-sac' of the ovule of phanerogams, and in the 'laticiferous' tubes. Within the nucleus are often seen one or more small distinct particles termed *nucleoli* (fig. 364, A, *b*), which can be best distinguished by the strong coloration they receive from a twenty-four hours' immersion in carmine, and subsequent washing in water slightly acidulated with acetic acid. Though in some points the precise function of the nucleus is still unknown, there can be no doubt of its peculiar relation to the vital activity of the cell; for, in the nucleated cells which exhibit 'cyclosis,' it may be observed that if the nucleus remains attached to the cell-wall, it constitutes a centre from which the protoplasmic streams diverge, and to which they return; whilst if it retains its freedom to wander about, the course of the streams alters in conformity with its position. But it is in the multiplication of cells by binary subdivision which will be

ntly described, that the speciality of the nucleus as *the centre* ? *vital activity of the cell* is most strongly manifested. The *ophyll corpuscles*, which are limited to the cells of the parts of s acted on by light, are specialised particles of protoplasm through h a green colouring matter is diffused; and it is by them that ork of decomposing CO_2, and of 'fixing' its carbon by union the oxygen and hydrogen of water into *starch*, is effected. The cteristic green of chlorophyll often gives place to other colours, h seem to be produced from it by chemical action. *Starch grains* lways formed in the first instance in the interior of the chloro- corpuscles, and gradually increase in size until they take the s of the corpuscles that produced them. So long as they con- to grow, they are always imbedded in the protoplasm of the and it is only when fully formed that they lie free within its y.

ut although these component parts may be made out without lifficulty in a large proportion of vegetable cells, yet they cannot stinguished in some of those humble organisms which are st to the border-line between the two kingdoms. For in them nd the 'cell-wall' very imperfectly differentiated from the 'cell- nts'; the former not having by any means the firmness of a ct membrane, and the latter not possessing the liquidity which here characterises them. And in some instances the cell is sented only by a mass of endoplasm, so viscid as to retain its nal form without any limitary membrane, though the superficial seems to have a firmer consistence than the interior substances; his may or may not be surrounded by a gelatinous-looking ope, which is equally far from possessing a membranous firmness, et is the only representative of the cellulose wall. This viscid plasm consists, as elsewhere, of a colourless protoplasm, through n minute colouring particles may be diffused, sometimes uni- y, sometimes in local aggregations, leaving parts of the proto- n uncoloured. The superficial layer in particular is frequently ute of colour; and the partial solidification of its surface gives e character of an 'ectoplasm.' Such individualised masses of plasm, destitute of a true cell-wall, have sometimes been d *primordial cells*. The nucleus, as already mentioned, is ently sometimes absent from the cells of the lower proto- s. It is an extremely curious feature in the cell life of certain phytes that they not only move like animalcules by cilia or la, but that they exhibit the rhythmically contracting vacuoles n are specially characteristic of *protozoic* organisms.

e far as we yet know, every vegetable cell derives its existence a pre-existing cell; and this derivation may take place (in the ary process of growth and extension, as distinguished from al multiplication') in one of two modes: either (1) *binary vision* of the parent-cell, or (2) *free-cell formation* within the t-cell. The first stage of the former process consists in the ation and transverse constriction of the nucleus; and this con- on becomes deeper and deeper, until the nucleus divides itself wo halves (fig. 364, B, *a*, *a'*). These then separating from

each other, the endoplasm of the parent-cell collects round the two new centres, so as to divide itself into two distinct masses (C, *a*, *a'*); and by the investment of these two secondary 'endoplasms' with cellulose-walls a complete pair of new cells (D, *a*, *a'*) is formed within the cavity of the parent-cell. The process of *free-cell formation* which is very common among protophytes (being that by which 'zoöspores,' or 'swarm-spores,' are commonly produced, is seen among phanerogams in the production of a number of cells at once within the cavity of the 'embryo-sac,' which may itself be considered as a distended parent-cell. The endoplasm, in the former of these cases, instead of dividing itself into two halves, usually breaks up into numerous segments corresponding with one another in size and form (fig. 375), each of which, escaping from the parent-cavity, becomes an independent cell, without any investing cell-wall of cellulose, hence a 'primordial cell,' endowed with a power of rapid motion by means of cilia or flagella. In the second case the endoplasm groups itself, more or less completely, round several centres, each of which has its own nucleus, formed by subdivision of the nucleus of the parent-cell; and these secondary cells, in various stages of development, lie free within the cavity of the parent-cell, imbedded in its residual endoplasm, each proceeding to complete



FIG. 364.—*Binary subdivision of cells* in endosperm of seed of scarlet-runner: A, ordinary cell, with nucleus *a*, and nucleolus *b*, imbedded in its protoplasm; B, cell showing subdivision of nucleus into two halves, *a* and *a'*; C, cell in same stage, showing contraction of endoplasm (produced by addition of water), into two separate masses round the two segments of original nucleus; D, two complete cells within mother-cell, divided by a partition.



FIG. 365.—Successive stages of *free-cell formation* in embryo-sac of seed of scarlet-runner: *a*, *a*, *a*, completed cells, each having its proper cell-wall, nucleus, and endoplasm, lying in a protoplasmic mass, through which are dispersed nuclei and cells in various stages of development.

' in any *phanerogamic* plant has its origin in the fertilisa-
ighly specialised 'germ-cell' (contained within the ovule)
tents of a 'sperm-cell' (the pollen-grain), so do we find,
save the lowest *cryptogams*, a provision for the union of
ts of two highly specialised cells, the 'germ-cells' being
y the access of motile protoplasmic bodies (antherozoids),
ɔm the cavities of the 'sperm-cells' within which they
oped. But although the sexual process can be traced
ı under this form into the group of thallophytes, we
: the lower types of that group a yet simpler mode of
about; for there is strong reason to regard the act of
ɔn' which takes place in the Conjugatæ and in some fungi
ə light, and to look upon the 'zygospore,'[1] which is its
product, as the originator (like the fertilised embryo-cell
ıerogamic seed) of a 'new generation.'

ttention has recently been paid by Strasburger (see his
ɔer Zellbildung und Zelltheilung') and others to the con-
: the endoplasm and to the processes connected with cell-
On both these subjects it is impossible here to give more
ɔarest outlines. Strasburger distinguishes between the
ifferentiated parts of the protoplasm of the living cell :—
lasm outside the nucleus he terms the 'cytoplasm'; the
ıich constitutes the nucleus is the 'nucleoplasm'; that
rs into the composition of the chlorophyll corpuscles and
d substances is the 'chromatoplasm.' Each of these
ons of protoplasm is composed of a hyaline matrix or

ı 'spore' has been long used by cryptogamists to designate the minute re-
rticles (such as those set free from the 'fructification' of ferns, mosses
re supposed—in the absence of all knowledge of their sexual relations—
valents of the seeds of flowering plants. But it is now known that such
(so to speak) very different values in different cases, being, in by far the
ion of cryptogams, but the remote descendants of the fertilised cell which
ate product of the sexual act under any of its forms. This cell, which will

'hyaloplasm' and of imbedded granular structures or 'microsomes.' A distinct substance, known as 'nuclein,' absent from the cytoplasm, appears to enter into the composition of the nucleus. The division of the nucleus may take place either directly, when the process is known as 'fragmentation'; or indirectly. In the process of indirect division, the protoplasm of which the nucleus is composed undergoes a great variety of changes, in the course of which it assumes the beautiful appearance known as the 'nuclear spindle,'



FIG. 366.—Division of the pollen-mother-cells of *Fritillaria persica*. (From Strasburger and Hillhouse's 'Practical Botany,' published by Sonnenschein.)

consisting of an equatorial disc, the 'nuclear plate,' and delicate 'spindle-fibres' which converge towards the two poles of the spindle. To follow out all these processes requires very high magnifying powers of the microscope, great skill in manipulation, and the use of very delicate staining reagents.

The older conception of the vegetable cell regarded it as a completely closed vesicle, the endoplasm of which is entirely shut off from contact with that of the adjacent cells. Recent observa-

equire the modification of this conception. It has been shown
many cases the cell-wall is perforated by very minute orifices,
h which excessively fine strings of protoplasm pass from one
vity to another (fig. 367). This *continuity of protoplasm* has been
ed in some seaweeds and other algæ, in the endosperm of the
and in the pulvinus or motile organ of the leaves of the
ive Plant, and is probably a widely extended phenomenon. In
tter case it is undoubtedly connected with the remarkable
menon of sensitiveness or irritability displayed by the leaves.
the lowest forms of vegetation every single cell is not only
le of living in a state of isolation from the rest, but even
lly does so; and thus the plant may be said to be *unicel-*
every cell having an independent 'individuality.' There are
, again, in which amorphous masses are made up by the aggre-
of cells, which, though quite capable of living independently,
attached to each other by the mutual fusion (so to speak) of
gelatinous invest-
; and there are
, moreover, in
a definite adhe-
xists between the
and in which
r plant-like struc-
are thus formed,
thstanding that
cell is but a repe-
of every other,
capable of living
endently if de-
d, so as still to
r to the designa-
f a 'unicellular'
ngle-celled plant.
different condi-
we shall find to
out of the mode



FIG. 367.—Continuity of protoplasm. (From Vines's 'Physiology of Plants.' Cambridge University Press.)

ich each particular species multiplies by binary subdivision;
here the cells of the new pair that is produced by division
previous cell undergo a *complete* separation from one another,
will henceforth live independently; but if, instead of under-
this complete fission, they should be held together by the
ening gelatinous envelope, a shapeless mass results from re-
d subdivisions not taking place on any determinate plan;
f, moreover, the binary subdivision should always take place
e direction only, a long, narrow filament (fig. 374, D), or
two directions only, a broad, flat, leaf-like expansion (G),
e generated. To such extended fabrics the term 'unicellular'
s can scarcely be applied with propriety; since they may
ilt up of many thousands or millions of distinct cells, which
no disposition to separate from each other spontaneously.
they correspond with those which are strictly unicellular, as to

the *absence of differentiation* either in structure or in function between their component cells, each one of these being a repetition of the rest, and no relation of mutual dependence existing among them ; and all such simple organisms, therefore, may still be included under the general term of **thallophytes.**

Excluding *lichens*, for the reasons to be stated hereafter, botanists now rank these thallophytes under two series : *algæ*, which form chlorophyll, and can support themselves upon air, water, and mineral matters ; and *fungi*, which, not forming chlorophyll for themselves, depend for their nutriment upon materials drawn from other organisms. Each series contains a very large variety of forms, which, when traced from below upwards, present gradationally increasing complexities of structure ; and these gradations show themselves especially in the provisions made for the generative process. Thus, in some forms, a 'zygospore' is produced by the fusion of the contents of two cells, which neither present any sexual difference, the one from the other, nor can be distinguished in any way from the rest. In the next highest forms, while the 'conjugating' cells are still apparently undifferentiated from the rest of the structure, a sexual difference shows itself between them ; the contents of one cell (male) passing over into the cavity of the other (female), within which the 'zygospore' is formed. The next stage in the ascent is the resolution of the contents of the male cell into motile bodies ('antherozoids'), which, escaping from it, move freely through the water, and find their way to the female cell, whose contents, fertilised by coalescence with the material they bring, form an 'oöspore.' In the lower forms of this stage, again, the generative cells are not distinguishable from the rest until the contents begin to show their characteristically sexual aspect ; but in the higher they are developed in special organs, constituting a true 'fructification.' This must, however, be distinguished from organs which, though commonly spoken of as the 'fructification,' have no real analogy with the generative apparatus of flowering plants, their function being merely to give origin to *gonidial*[1] cells or groups of cells, which simply *multiply* the parent stock, in the same manner that many flowering plants (such as the potato) can be propagated by the artificial separation of their leaf-buds. It frequently happens among cryptogams that this *gonidial* fructification is by far the more conspicuous, the *sexual* fructification being often so obscure that it cannot be detected at all without great difficulty ; and we shall presently see that there are some thallophytes in which the production of *gonids* seems to go on indefinitely, no form of sexual generation having been detected

[1] The term *gonids*, originally applied to certain green cells in the lichen-crust that are capable, when detached, of reproducing the vegetative portion of the plant, is used by some writers as a designation of the *non-sexual spores* of cryptogams generally, which it is very important to discriminate from the generative 'oöspheres.' If possessed of *motile* powers, they are spoken of as 'zoöspores,' or sometimes (on account of the appearance they present when a number are set free at once) as 'swarm-spores.' In contradistinction to 'motile' gonids or 'zoöspores,' those which show no movement are often termed *resting* spores, or *hypnospores* ; but such may be either sexual *oöspheres* or non-sexual *gonids*, the latter, like the former, often 'encysting' themselves in a firm envelope, and then remaining dormant for long periods of time.

in them. These general statements will now be illustrated by sketches of the life-history of some of those humble thallophytes which present the phenomena of cell-division, conjugation, and gonidial multiplication, under their simplest and most instructive aspect.

The first of these lowly forms of life to which we call the attention of the reader is *Palmoglœa macrococca* (Ktz.),[1] one of those humble kinds of vegetation which spreads itself as a green slime over damp stones, walls, &c. When this slime is examined with the microscope, it is found to consist of a multitude of green cells (fig. 368, A), each surrounded by a gelatinous envelope; the cell, which does not seem to have any distinct membranous wall, is filled with a granular 'endochrome,' consisting of green particles diffused through colourless protoplasm; and in the midst of this a nucleus may sometimes be distinguished, but can always be brought into view by tincture of iodine, which turns the 'endochrome' to a



FIG. 368.—Development of *Palmoglœa macrococca*.

brownish hue, and makes the nucleus (G) dark brown. Other cells are seen (B), which are considerably elongated, some of them beginning to present a sort of hour-glass contraction across the middle; and when cells in this condition are treated with tincture of iodine, the nucleus is seen to be undergoing the like elongation and constriction (H). A more advanced state of the process of subdivision is seen at C, in which the constriction has proceeded to the extent of completely cutting off the two halves of the cell, as well as of the nucleus (I) from each other, though they still remain in mutual contact; in a yet later stage they are found detached from each other (D), though still included within the same gelatinous envelope. Each new cell then begins to secrete its own gelatinous envelope, so that by its intervention the two are usually soon separated from each other (E). Sometimes, however, this is not the case, the process of subdivision being quickly repeated before there is time for

[1] [Most of the species of Kützing's genus *Palmoglœa* are now regarded as belonging to the *Desmidiaceæ*, and are included under the genus *Mesotænium*.—ED.]

the production of the gelatinous envelope, so that a series of cells (F) hanging on one to another is produced. There appears to be no definite limit to this kind of multiplication, and extensive areas may be quickly covered, in circumstances favourable to the growth of the plant, by the products of the binary subdivision of one original cell. This, as already shown, is really an act of *growth*, which continues indefinitely so long as moisture is abundant and the temperature low. But under the influence of heat and dryness the process of cell-multiplication gives place to that of 'conjugation,' in which two cells, apparently similar in all respects, fuse together for the production of a 'zygospore,' which (like the seed of a flowering plant) can endure being reduced to a quiescent state for an unlimited time, and may be so completely dried up as to seem



FIG. 369.—Development of *Protococcus pluvialis*.

like a particle of dust, yet resumes its vegetative activity whenever placed in the conditions favourable to it. The conjugating process commences by the putting forth of protrusions from the boundaries of two adjacent cells, which meet, fuse together (thereby showing the want of firmness of their 'ectoplasms'), and form a connecting bridge between their cavities (K). The fusion extends before long through a large part of the contiguous sides of the two cells (L); and at last becomes so complete that the combined mass (M) shows no trace of its double origin. It soon forms for itself a firm cellulose envelope, which bursts when the 'zygospore' is wetted; and the contained cell begins life as a *new generation*, speedily multiplying, like the former ones, by binary subdivision. It is curious to observe that during this conjugating process a production of oil particles takes place in the cells; these are at first small and distant, but

gradually become larger, and approximate more closely to each other, and at last coalesce so as to form oil-drops of various sizes, the green granular matter disappearing; and the colour of the conjugated body changes, with the advance of this process, from green to a light yellowish brown. When the zygospore begins to vegetate, on the other hand, a converse change occurs; the oil-globules disappear, and green granular matter takes their place. This is precisely what happens in the formation of the seed among some of the higher plants; for starchy substances are transformed into oil, which is stored up in the seed for the nutrition of the embryo, and is applied during germination to the purposes which are at other times answered by them.

If this (as seems probable) constitutes the entire life-cycle of *Palmoglœa*, it affords no example of that curious 'motile' stage which is exhibited by most algal protophytes in some stage of their existence, and which constitutes a large part of the life-history of the minute unicellular organism now to be described, **Protococcus pluvialis**,[1] fig. 369), which is not uncommon in collections of rain-water. Not only has this protophyte, in its motile condition, been very commonly regarded as an animalcule, but its different states have been described under several different names. In the first place, the *colour* of its cells varies considerably; since, although they are usually *green* at the period of their most active life, they are sometimes *red*; and their red form has received the distinguishing appellation of *Hæmatococcus* (fig. 373). Very commonly the red colouring matter forms only a central mass of greater or less size, having the appearance of a nucleus (as shown at E, fig. 369); and sometimes it is reduced to a single granular point, which has been described by Professor Ehrenberg as the *eye-spot* of these so-called animalcules. It is quite certain that the red colouring substance is very nearly related in its chemical character to the green, and that the one may be converted into the other, though the conditions under which this

[1] The Author had under his own observation an extraordinary abundance of what he now feels satisfied must have been this protophyte in an open rain-water cistern which had been newly cleaned out. His notice was attracted to it by seeing the surface of the water covered with a green froth whenever the sun shone upon it. On examining a portion of this froth under the microscope he found that the water was crowded with green cells in active motion; and although the only bodies at all resembling them of which he could find any description were the so-called animalcules constituting the genus *Chlamydomonas* of Prof. Ehrenberg, and very little was known at that time of the 'motile' conditions of *plants* of this description, yet of the vegetable nature of these bodies he could not entertain the smallest doubt. They appeared in freshly collected rain-water, and could not, therefore, be deriving their support from organic matter; under the influence of light they were obviously decomposing carbonic acid and liberating oxygen; and this influence he found to be essential to the continuance of their growth and development, which took place entirely upon the vegetative plan. Not many days after the protophyte first appeared in the water, a few wheel-animalcules presented themselves; these fed greedily upon it, and increased so rapidly (the weather being very warm) that they speedily became almost as crowded as the cells of the *Protococcus* had been; and it was probably due in part to their voracity that the plant soon became less abundant, and before long disappeared altogether. Had the Author been then aware of its assumption of the 'still' condition, he might have found it at the bottom of the cistern after it had ceased to present itself at the surface. The account of this plant given above is derived from that of Dr. Cohn, in the *Nova Acta Acad. Nat. Curios.* (Bonn, 1850), tom. xxii., of which an abstract by Mr. George Busk is contained in the *Botanical and Physiological Memoirs*, published by the Ray Society, for 1853.

conversion takes place are not precisely known. In the 'still' form of the cell, with which we may commence the history of its life, the endoplasm consists of a colourless protoplasm, through which red or green coloured granules are more or less uniformly diffused; and the surface of the colourless protoplasm is condensed into an ectoplasm, which is surrounded by a tolerably firm cell-wall, consisting of cellulose or of some modification of it. Outside this (as shown at A), when the 'still' cell is formed by a change in the condition of a cell that has been previously 'motile,' we find another envelope, which seems to be of the same nature, but which is separated by the interposition of aqueous fluid; this, however, may be altogether wanting. The multiplication of the 'still' cells by subdivision takes place as in *Palmoglœa*, the endoplasm first undergoing separation into two halves (as seen at B), and each of these halves subsequently developing a cellulose envelope around itself, and undergoing the same division in its turn. Thus two, four, eight, sixteen new cells are successively produced; and these are sometimes set free by the complete dissolution of the envelope of the original cell; but they are more commonly held together by its transformation into a gelatinous investment in which they remain imbedded. Sometimes the endoplasm subdivides at once into four segments (as at D), of which every one forthwith acquires the character of an independent cell; but this, although an ordinary method of multiplication among the 'motile' cells, is comparatively rare in the 'still' condition. Sometimes, again, the endoplasm of the 'still' form subdivides at once into eight portions, which, being of small size, and endowed with motile power, may be considered as *zoöspores*. As far as the complete life-history of *Protococcus* is at present known, some of these zoöspores retain their motile powers, and develop themselves into the ordinary 'motile' cells; others produce a firm cellulose envelope and become 'still' cells; and others (perhaps the majority) perish without any further change.

When the ordinary division of the 'still' cells into two segments has been repeated four times, so as to produce sixteen cells—and sometimes at an earlier period—the new cells thus produced assume the 'motile' condition, being liberated before the development of the cellulose envelope, and becoming furnished with two long vibratile flagella, which seem to be extensions of the colourless protoplasm-layer that accumulates at their base so as to form a sort of transparent beak (H). In this condition it seems obvious that the colourless protoplasm is more developed relatively to the colouring matter than it is in the 'still' cells; and it usually contains 'vacuoles' occupied only by clear aqueous fluid, which are sometimes so numerous as to take in a large part of the cavity of the cell, so that the coloured contents seem only like a deposit on its walls. Before long this 'motile' cell acquires a peculiar saccular investment, which seems to correspond with the cellulose envelope of the 'still' cells, but is not so firm in its consistence (I, K, L); and between this and the surface of the ectoplasm a considerable space intervenes, traversed by thread-like extensions of the latter, which are rendered more distinct by iodine, and can be made to retract by means of

re-agents. The flagella pass through the cellulose envelope, which invests their base with a sort of sheath, and in the portion that is within this sheath no movement is seen. During the active life of the 'motile' cell the vibration of these flagella is so rapid that they can be recognised only by the currents they produce in the water through which the cells are quickly propelled; but when the motion becomes slacker, the flagella themselves are readily distinguishable, and they may be made more obvious by the addition of iodine, which, however, it should be noted, always kills the plant.

The multiplication of these 'motile' cells may take place in various modes, giving rise to a great variety of appearances. Sometimes they undergo a regular binary subdivision (B), whereby a pair of motile cells is produced (C), each resembling its single predecessor in possessing the cellulose investment, the transparent beak, and the vibratile flagella, before the dissolution of the original investment. Sometimes, again, the contents of the original cell undergo a segmentation in the first instance into four divisions (D); which may either become isolated by the dissolution of their envelope, and may separate from each other in the condition of 'free primordial cells' (H), developing their cellulose investments at a future time, or may acquire their cellulose investments (as in the preceding case) before the solution of that of the original cell; while sometimes, even after the disappearance of this, and the formation of their own independent investments, they remain attached to each other at their beaked extremities, the primordial cells being connected with each other by peduncular prolongations, and the whole compound body having the form of a +. This quaternary segmentation appears to be a more frequent mode of multiplication among the 'motile' cells than the subdivision into two, although, as we have seen, it is less common in the 'still' condition. So also a primary segmentation of the entire endochrome of the 'motile' cells into eight, sixteen, or even thirty-two parts, may take place (E, F), thus giving rise to as many minute gonidial cells. These, when set free, and possessing active powers of movement, are true zoöspores (G); they may either develop a loose cellulose investment or cyst, so as to attain the full dimensions of the ordinary motile cells (I, K), or they may become clothed with a dense envelope and lose their flagella, thus passing into the 'still' condition (A); and this last transformation may even take place before they are set free from the envelope within which they were produced, so that they constitute a mulberry-like mass, which fills the whole cavity of the original cell, and is kept in motion by its flagella.

To what extent *Protococcus* is an autonomous organism is still doubtful, but it appears to be more or less closely connected with many forms of life which have been described, not merely as distinct *species*, but as distinct *genera* of animalcules or of protophytes such as *Chlamydomonas*, *Euglena*, *Trachelomonas*, *Gyges*, *Gonium*, *Pandorina*, *Botryocystis*, *Uvella*, *Syncrypta*, *Monas*, *Astasia*, *Bodo*, and many others. Certain forms, such as the 'motile' cells I, K, L, appear in a given infusion, at first exclusively and then principally; they gradually diminish, become more and more rare, and finally

disappear altogether, being replaced by the 'still' form. After some time the number of the 'motile' cells again increases, and reaches, as before, an extraordinary amount; and this alternation may be repeated several times in the course of a few weeks. The process of segmentation is often accomplished with great rapidity. If a number of 'motile' cells be transferred from a larger glass into a smaller, it will be found, after the lapse of a few hours, that most of them have subsided to the bottom; in the course of the day they will all be observed to be upon the point of subdivision; on the following morning the divisional brood will have become quite free; and on the next the bottom of the vessel will be found covered with a new brood of dividing cells, which again proceed to the formation of a new brood, and so on. The activity of motion and the activity of multiplication seem to stand, in some degree, in a relation of reciprocity to each other; for the dividing process takes place with greater rapidity in the 'still' cells than it does in the 'motile.'

What are the precise *conditions which determine the transition between the 'still' and the 'motile' states* cannot yet be precisely defined, but the influences of certain agencies can be predicted with tolerable certainty. Thus it is only necessary to pour the water containing these organisms from a smaller and deeper into a larger and shallower vessel, in order at once to determine segmentation in numerous cells; a phenomenon which is observable also in many other protophytes. The 'motile' cells seem to be favourably affected by light, for they collect themselves at the surface of the water and at the edges of the vessel, but when they are about to undergo segmentation or to pass into the 'still' condition, they sink to the bottom of the vessel, or retreat to that part of it in which they are least subjected to light. When kept in the dark the 'motile' cells undergo a great diminution of their chlorophyll, which becomes very pale, and is diffused, instead of forming definite granules; they continue their movement, however, uninterruptedly without either sinking to the bottom, or passing into the 'still' form, or undergoing segmentation. A moderate warmth, particularly that of the vernal sun, is favourable to the development of the 'motile' cells; but a temperature of excessive elevation prevents it. Rapid evaporation of the water in which the 'motile' forms may be contained kills them at once; but a more gradual loss, such as takes place in deep glasses, causes them merely to pass into the 'still' form; and in this condition—especially when they have assumed a red hue—they may be completely dried up, and may remain in a state of dormant vitality for many years. It is in this state that they are wafted about in atmospheric currents, and that, being brought down by rain into pools, cisterns, &c., they may present themselves where none had been previously known to exist; and there, under favourable circumstances, they may undergo a very rapid multiplication, and may maintain themselves until the water is dried up, or some other change occurs which is incompatible with the continuance of their vital activity. They then very commonly become red throughout, the red colouring substance extending itself from the centre towards the circumference, and assuming an appearance like that of oil-

drops; and these red cells, acquiring thick cell walls and a mucous envelope, float in flocculent aggregations on the surface of the water. This state seems to correspond with the 'resting-spores' of other protophytes; and it may continue until warmth, air, and moisture cause the development of the red cells into the ordinary 'still' cells, green matter being gradually produced, until the red substance forms only the central part of the endochrome. After this the cycle of changes occurs which has been already described; and the plant may pass through a long series of these before it returns to the state of the red thick-walled cell, in which it may again remain dormant for an unlimited period. Even this cycle, however, cannot be regarded as completing the history of *Protococcus*, since it does not include the performance of any true generative act. There can be little doubt that, in some stage of its existence, a 'conjugation' of two cells occurs, as in *Palmoglœa*; and the attention of observers should be directed to its discovery, as well as to the detection of other varieties in the condition of this interesting little plant, which will probably be found to present themselves before and after the performance of that act.[1]

Included under the family of *Chroöcoccaceæ* are a number of minute microscopic organisms, exceedingly abundant in fresh-water, differing from the Protococcaceæ in not containing true chlorophyll grains, the cell-cap being, on the other hand, coloured by a soluble blue-green pigment known as 'phycocyanin.' They live either isolated, or a number congregated together, and enclosed in a more or less dense colourless jelly. They multiply by binary division, but do not, in any case, produce zoöspores. To this family belong the genera *Chroöcoccus*, *Glœocapsa*, *Aphanocapsa*, *Merismopedia*, and many others, the life-history of which is but very imperfectly known.

Resembling the Protococcaceæ in the independence of their individual cells are the two groups *Desmidiaceæ* and *Diatomaceæ*, which, in a systematic view, rank as subordinate divisions of the family **Conjugatæ**, their generative process being performed in the same simple manner as that of *Palmoglœa*. But these two tribes being of such special interest to the microscopist as to require separate treatment, only that higher group, the *Zygnemaceæ*, will be here noticed, in which the cells produced by binary subdivision remain attached to each other, end to end, so as to form long unbranched filaments (fig. 370), whose length is continually being increased by a repetition of the same process, which may take place in any part of the filaments, and not at their ends alone. The plants of this group are not found so much in running streams as in waters that are perfectly still, such as those of ponds, of reservoirs, ditches, bogs, or marshy grounds; and they are for the most part unattached, floating freely at or near the surface, especially when buoyed up by the bubbles of gas which are

[1] In the above sketch the Author has presented the facts described by Dr. Cohn under the relation which they seemed to him naturally to bear, but which differs from that in which they will be found in the original memoir; and he is glad to be able to state, from personal communication with its able author, that Dr. Cohn's later observations led him to adopt a view of the relationship of the 'still' and 'motile' forms which is in essential accordance with his own.

liberated from the midst of them under the influence of solar light and heat. In the early stage of their growth, whilst as yet the cells are undergoing multiplication by division, the endochrome is frequently diffused pretty uniformly through their cavities (fig. 370, A); but as they advance towards the stage of conjugation, it ordinarily arranges itself into regular spirals (B), a couple of star-like discs in each cell, or a single plate running through it in an axile direction. The act of conjugation usually occurs between the cells of two distinct filaments that happen to lie in proximity to each other, and all the cells of each filament generally take part in it at once. The adjacent cells put forth little protuberances, which come into contact with each other, and then coalesce by the breaking down of the intervening partitions, so as to establish a free passage between the cavities of the conjugating cells. In some genera of this family (such as *Mesocarpus*) the conjugating cells pour their endochromes into a dilatation of the passage that has been esta-



FIG. 370.—Various stages of the history of a *Spirogyra*: A, three cells, *a*, *b*, *c*, of a young filament, of which *b* is undergoing division; B, two filaments in the first stage of conjugation, showing the spiral disposition of their endochromes and the protuberances from the conjugating cells; C, completion of the act of conjugation, the endochromes of the cells of the filament *a* having entirely passed over to those of filament *b*, in which the zygospores are formed.

blished between them; and it is there that they commingle so as to form the 'zygospore.' But in the various species of *Spirogyra* (fig. 370, B), which are among the commonest and best known of Conjugatæ, the endochrome of one cell passes over entirely into the cavity of the other; and it is within the latter that the 'zygospore' is formed (C), the two endochromes coalescing into a simple mass, around which a firm envelope gradually makes its appearance. Further, it may be generally observed that *all* the cells of one filament thus empty themselves, whilst *all* the cells of the other filament become the recipients. Here, therefore, we seem to have a foreshadowing of the sexual distinction of the generative cells into 'sperm-cells' and 'germ-cells,' which we shall presently see in the filamentous *Confervaceæ*. Conjugation between two adjacent cells of the same individual also occurs in some species. Multiplication by 'zoöspores' does not take place among the Conjugatæ.

From the composite 'motile' forms of *Protococcus* the transition
s easy to the group of **Volvocineæ**, an assemblage of minute plants
f the greatest interest to the microscopist, on account both of the
nimalcule-like activity of their movements and of the great beauty
nd regularity of their forms. The most remarkable example of this
roup is the well-known *Volvox globator* (Plate VI.), which is not
ncommon in fresh-water pools, and which, attaining a diameter of
bout $\frac{1}{50}$ or even $\frac{1}{30}$ of an inch, may be seen with the naked eye
hen the drop containing it is held up to the light, swimming through
ıe water which it inhabits. Its onward motion is usually of a roll-
ıg kind; but it sometimes glides smoothly along, without turning
ı its axis; whilst sometimes, again, it rotates like a top, without
hanging its position. When examined with a sufficient magnifying
ower the *Volvox* is seen to consist of a hollow sphere, composed of
very pellucid material, which is studded at regular intervals with
ninute green spots, and which is often (but not constantly) traversed
y green threads connecting these spots. From each of the spots
roceed two long flagella, so that the entire surface is beset with
hese lashing filaments, to whose combined action its movements
re due. Within the external sphere may generally be seen from
wo to twenty other globes, of a darker colour, and of varying sizes;
he smaller of these are attached to the inner surface of the investing
phere, and project into its cavity; but the larger lie freely within
he cavity, and may often be observed to revolve by the agency of
heir own flagella. After a time the original sphere bursts, and the
ontained spherules swim forth and speedily develop themselves
nto the likeness of that within which they have been evolved,
heir coloured particles, which are at first closely aggregated together,
eing separated from each other by the interposition of the trans-
arent pellicle. It was long supposed that *Volvox* is a *single*
nimal; and it was first shown to be a *composite* fabric, made up of a
epetition of organisms in all respects similar to each other, by Pro-
essor Ehrenberg, who, however, considered these organisms as
monads, and described them as each possessing a mouth, several
tomachs, and an eye! Our present knowledge of their nature,
owever, leaves little doubt of their vegetable character;[1] and the
eculiarity of their history renders it desirable to describe it in some
etail.

Each of the so-called 'monads' (fig. 371, Nos. 9, 11) is a somewhat
lask-shaped plant-cell, about $\frac{1}{3000}$th of an inch in diameter, consist-
ng, as in the previous instances, of green chlorophyll granules diffused
hrough a colourless protoplasm, constituting an 'endochrome' (which
ommonly includes also a red spot of altered chlorophyll), and
ounded by an 'ectoplasm' formed of the condensed and colourless
urface-layer of the protoplasmic mass. It is prolonged outwardly
or towards the circumference of the sphere) into a sort of colourless

[1] Professor Stein, however, in his great work on the Infusoria (*Organismus der nfusionsthiere*, Abtheilung III, Leipzig, 1878), still ranks the *Volvocineæ* among ıe flagellate animalcules, to which they undoubtedly show a remarkable parallelism ı *structure*, the chief evidence of their vegetal le nature lying in their *physiological* onformity to undoubted thallophytes.

beak or proboscis, from which proceed two flagella (fig. 371, No. 11); and it is invested by a pellucid or hyaline envelope (No. 9, *d*) of considerable thickness, the borders of which are flattened against those of other similar envelopes (No. 5, *c*, *c*), but which does not appear to have the tenacity of a true membrane. It is impossible not to recognise the close similarity between the structure of this body



FIG. 371.—Structure of *Volvox globator*.

and that of the motile 'encysted' cell of *Protococcus pluvialis* (fig. 369, K). There is not, in fact, any perceptible difference between them, save that which arises from the regular aggregation, in *Volvox*, of the cells which normally detach themselves from one another in *Protococcus*. The presence of cellulose in the hyaline substance is not indicated, in the ordinary condition of *Volvox globator*, by the

iodine and sulphuric acid test, though the use of 'Schultz's solution' gives to it a faint blue tinge; there can be no doubt of its existence, however, in the hyaline envelope of *Volvox aureus*. The flagella and endoplasm, as in the motile forms of *Protococcus*, are tinged a deep brown by iodine, with the exception of one or two starch-particles in each cell, which are turned blue; and when the contents of the cell are liberated, bluish flocculi, apparently indicative of the presence of cellulose, are brought into view by the action of sulphuric acid and iodine. All these reactions are characteristically *vegetable* in their nature. When the cell is approaching maturity, its endoplasm always exhibits one or more 'vacuoles' (fig. 371, No. 9, *a*, *a*), of a spherical form, and usually about one-third of its own diameter; and these 'vacuoles' (which are the so-called 'stomachs' of Professor Ehrenberg) have been observed to undergo a very curious rhythmical contraction and dilatation at intervals of about forty seconds; the contraction (which seems to amount to complete obliteration of the cavity of the vacuole) taking place rapidly or suddenly, whilst the dilatation is slow and gradual. This curious action ceases, however, as the cell arrives at its full maturity[1]; a condition which seems to be marked by the greater consolidation of the 'ectoplasm,' by the removal or transformation of some of the chlorophyll, and by the formation of the red spot (*b*), which obviously consists, as in *Protococcus*, of a peculiar modification of chlorophyll.

Each cell normally communicates with the cells in nearest proximity with it by extensions of its own endochrome, which are sometimes single and sometimes double (fig. 371, No. 5, *b*, *b*); and these connecting processes necessarily cross the lines of division between their respective hyaline investments. The thickness of these processes varies very considerably; for sometimes they are broad bands, and in other cases mere threads; whilst they are occasionally wanting altogether. This difference seems partly to depend upon the age of the individual, and partly upon the abundance of nutriment which it obtains; for, as we shall presently see, the connection is most intimate at an early period, before the hyaline investments of the cells have increased so much as to separate the masses of endochrome to a distance from one another (fig. 371, Nos. 2, 3, 4); whilst in a mature individual, in which the separation has taken place to its full extent and the nutritive processes have become less active, the masses of endochrome very commonly assume an angular form, and the connecting processes are drawn out into threads (as seen in No. 5), or they retain their globular form, and the connecting processes altogether disappear. The influence of reagents, or the infiltration of water into the interior of the hyaline investment, will sometimes cause the connecting processes (as in *Protococcus*) to be drawn back into the central mass of endochrome; and they will also retreat on the mere rupture of the hyaline investment. From these circumstances it may be inferred that they are not enclosed in any definite

[1] The existence of rhythmically contracting vacuoles in *Volvox* (though confirmed by the observations of Prof. Stein) is denied by Mr. Saville Kent (*Manual of the Infusoria*, p. 47); but it may be fairly presumed that he has not looked for them at the stage of development at which their action was witnessed by Mr. Busk.

membrane. On the other hand, the connecting threads are sometimes seen as double lines, which seem like tubular prolongations of a consistent membrane, without any protoplasmic granules in their interior. It is obvious, then, that an examination of a considerable number of specimens, exhibiting various phases of conformation, is necessary to demonstrate the nature of these communications; but this may be best made out by attending to the history of their development, which we shall now describe.

The spherical body of the young *Volvox* (fig. 371, No. 1) is composed of an aggregation of somewhat angular masses of endochrome (*b*), separated by the interposition of hyaline substance and the whole seems to be enclosed in a distinctly membranous envelope, which is probably the distended hyaline investment of the original cell, within which, as will presently appear, the entire aggregation originated. In the midst of the polygonal masses of endochrome, one mass (*a*), rather larger than the rest, is seen to present a circular form; and this, as will presently appear, is the originating cell of what is hereafter to become a new sphere. The growing *Volvox* at first increases in size not only by the interposition of new hyaline substance between its component masses of endochrome, but also by an increase in these masses themselves (No. 2, *a*), which come into continuous connection with each other by the coalescence of processes (*b*) which they severally put forth; at the same time an increase is observed in the size of the globular cell (*c*), which is preliminary to its binary subdivision. A more advanced stage of the same developmental process is seen in No. 3, in which the connecting processes (*a*, *a*) are so much increased in size as to establish a most intimate union between the masses of endochrome, although the increase of the intervening hyaline substance carries these masses apart from one another; whilst the endochrome of the central globular cell has undergone segmentation into two halves. In the stage represented in No. 4 the masses of endochrome have been still more widely separated by the interposition of hyaline substance; each has become furnished with its pair of flagella; and the globular cell has undergone a second segmentation. Finally, in No. 5, which represents a portion of the spherical wall of a mature *Volvox*, the endochrome masses are observed to present a more scattered aspect, partly on account of their own reduction in size, and partly through the interposition of a greatly increased amount of hyaline substance, which is secreted from the surface of each mass; and that portion which belongs to each cell, standing to the endochrome-mass in the relation of the cellulose coat of an ordinary cell to its ectoplasm, is frequently seen to be marked out from the rest by delicate lines of hexagonal areolation (*c*, *c*), which indicate the boundaries of each. Of these it is often difficult to obtain a sight, a nice management of the light being usually requisite with fresh specimens; but the prolonged action of water (especially when it contains a trace of iodine) or of glycerin will often bring them into clear view. The prolonged action of glycerin, moreover, will often show that the boundary lines are double, being formed by the coalescence of two contiguous cell-walls; and they sometimes retreat



PLATE VI.





Volvox globator.

West, Newman ahrem

from each other so far that the hexagonal areolæ become rounded. As the primary sphere approaches maturity, the large secondary germ-mass, or *zoösporange*, whose origin has been traced from the beginning, also advances in development, its contents undergoing multiplication by successive segmentations, so that we find it to consist of eight, sixteen, thirty-two, sixty-four, and still more numerous divisions, as shown in fig. 371, Nos. 6, 7, 8. Up to this stage, at which the sphere first appears to become hollow, it is retained within the hyaline envelope of the cell within which it has been produced; a similar envelope can be easily distinguished, as shown in No. 10, just when the segmentation has been completed, and at that stage the flagella pass into it, but do not extend beyond it; and even in the mature *Volvox* it continues to form an investment around the hyaline envelopes of the separate cells, as shown in the same figure at No. 11. It seems to be by the adhesion of the hyaline investment of the new sphere to that of the old that the secondary sphere remains for a time attached to the interior wall of the primary; at what exact period, or in what precise manner, the separation between the two takes place, has not yet been determined. At the time of the separation the developmental process has generally advanced as far as the stage represented in No. 1, the foundation of one or more tertiary spheres being usually distinguishable in the enlargement of certain of its cells.

The development and setting free of these composite 'zoösporanges,' which is essentially a process of cell-subdivision or *gemmiparous extension*, is the ordinary mode of multiplication in *Volvox*, taking place at all times of the year, except when the *sexual generation* (now to be described) is in progress. The mode in which this process is here performed (for our knowledge of which we are indebted to the persevering investigations of Professor Cohn) shows a great advance upon the simple 'conjugation' of two similar cells, and closely resembles that which prevails not only among the higher algæ, but (under some form or other) through a large part of the cryptogamic series. As autumn advances, the *Volvox* spheres usually cease to multiply themselves by the formation of 'zoösporanges,' and certain of their ordinary cells begin to undergo changes by which they are converted, some into male or 'sperm-cells,' others into female or 'germ-cells,' the greater number, however, remaining 'sterile.' Each sphere of *Volvox globator* (Plate VI, fig. 1) contains both kinds of sexual cells, so that this species ranks as *monœcious*; but *V. aureus* is *diœcious*, the 'sperm-cells' and 'germ-cells' occurring in separate spheres. Both kinds of 'sexual' cells are at first distinguishable from the ordinary 'sterile' cells by their larger size (fig. 2, *a*), in this respect resembling 'zoösporanges' in an early stage; but their subsequent history is altogether different. The '*sperm*-cells' begin to undergo subdivision when they attain about three times the size of the 'sterile' cells; this, however, takes place not on the 'binary' plan, but in such a manner that the endochrome of the primary cell resolves itself into a cluster of very peculiar secondary cells (fig. 1, *a*, a^2, fig. 5), each consisting of an elongated 'body' containing an orange-coloured endochrome with a

red corpuscle, and of a long, colourless beak, from the base of which proceeds a pair of long flagella (figs. 6, 7), as in the 'antherozoids' of the higher cryptogams. As the sperm-cells approach maturity, the aggregate clusters may be seen to move within them, at first slowly, and afterwards more rapidly; the bundles then separate into their component *antherozoids*, which show an active, independent movement whilst still within the cavity of the primary cell (fig. 1, a^3); and finally escape by the giving way of its wall (a^4), diffusing themselves through the cavity of the *Volvox* sphere. The *germ*-cells (fig. 1, *b*, *b*), on the other hand, continue to increase in size without undergoing subdivision; at first showing large vacuoles in their protoplasm (b^2, b^2), but subsequently becoming filled with dark-green endochrome. The form of the 'germ-cell' gradually changes from its original flask-shape to the globular (b^3); and it projects into the cavity of the *Volvox* sphere, at the same time acquiring a gelatinous envelope. Over this the swarming antherozoids diffuse themselves (fig. 3), penetrating its substance, so as to find their way to the interior; and in this situation they seem to dissolve away, so as to become incorporated with the *oösphere*. The product of this fusion (which is only 'conjugation' under another form) is a reproductive cell or *oöspore*, which speedily becomes enveloped by an internal smooth membrane, and with a thicker external coat, which is usually beset with conical-pointed processes (fig. 4); and the contained chlorophyll gives place, as in *Palmogloea*, to starch and a red or orange-coloured oil. As many as forty of such 'oöspores' have been seen by Dr. Cohn in a single sphere of *Volvox*, which thus acquires the peculiar appearance that has been distinguished by Ehrenberg by a different specific name, *Volvox stellatus*. Soon after the 'oöspores' reach maturity, the parent-sphere breaks up, and the oöspores fall to the bottom, where they remain during the winter. Their further history has since been traced out by Kirchner, who found that their germination commenced in February with the liberation of the spherical 'endospore' from its envelope, and with its division into four cells by the formation of two partitions at right angles to each other. These partially separate, holding together only at one end, which becomes one pole of the globular cluster subsequently formed by cell-multiplication, the other pole only closing in when a large number of cells have been formed. The cells are then carried apart from one another by the hyaline investment formed by each, and the characteristic *Volvox* sphere is thus completed.[1]

Another phenomenon of a very remarkable nature, namely, the conversion of the contents of an ordinary vegetable cell into a free

[1] The doctrine of the vegetable nature of *Volvox*, which had been suggested by Siebold, Braun, and other German naturalists, was first distinctly enunciated by Prof. Williamson, on the basis of the history of its development, in the *Transactions of the Philosophical Society of Manchester*, vol. ix.

[The most recent and detailed accounts of the development of the various forms of *Volvox* are by Klein (*Pringsheim's Jahrbücher für wissenschaftliche Botanik*, vol. xx. 1889, p. 133) and Overton (*Botanisches Centralblatt*, vol. xxxix. 1889), which do not differ in any material point from the description given in the text. See also Bennett and Murray's *Handbook of Cryptogamic Botany*, p. 292.—Ed.]

form by protruding or retracting any portion of its mem-
wall, exactly like a true *Amœba*. By this self-moving
ach of these bodies (of which twenty may sometimes be
within a single *Volvox*) glides independently over the inner
of the sphere among its unchanged green cells, bending itself
ıy one of these with which it may come into contact, pre-
ter the manner of an *Amœba*. After the 'amœboid' has
travel, it is always noticed that for every such moving body
olvox there is the empty space of a missing cell; and this
the belief—founded on observation of the gradational tran-
ɔm the one condition to the other, and on the difficulty of
g that any such bodies could have entered the sphere para-
from without—that the 'amœboid' is really the product of
morphosis of a mass of vegetable protoplasm. This meta-
is may take place, according to Dr. Hicks, even after the
of binary subdivision has commenced. What is the sub-
destination of these amœboid bodies has not yet been
ed.[2]

her organisms allied to *Volvox* and included in the family
eæ we find a very interesting and instructive transition
the various modes of multiplication already described. In
a, a common organism in still water, a sexual process, similar
in *Volvox*, has been observed. In *Pandorina morum* the
re process is performed, according to the observations of
im, in a manner curiously intermediate between the lower
higher types referred to above. For within each cell of the
sixteen of which its mulberry-like mass is composed, a brood
n secondary cells is formed by ordinary binary subdivision;
e, when set free by the dissolution of their containing cell-
im forth as 'swarm-spores,' each being furnished with a
lagella. Among the crowd of these swarm-spores may be
some which approach in pairs, as if seeking one another;

We have here, therefore, a true process of 'conjugation' between motile protoplasm masses, each of which is in itself indistinguishable from a zoöspore. A similar process takes place also in *Conferva*, *Ulothrix*, *Hydrodictyon*, and a number of fresh-water algæ (fig. 372).

Included by many writers under the general term **Palmellaceæ** are a number of minute organisms of very simple structure, the relationship of which to the *Protococcaceæ* is not yet fully known. They all grow either on damp surfaces or in fresh water; and they may either form (1) a mere powdery layer, of which the component particles have little or no adhesion to each other; or they may present themselves (2) in the condition of an indefinite slimy film, or (3) in that of a tolerably firm and definitely bounded membranous 'frond.' The first of these states we have seen to be characteristic of *Palmoglæa* and *Protococcus*; the new cells which are originated by the process of binary subdivision usually separating from each other after a short time; and, even where they remain in cohesion, not forming a 'frond' or membranous expansion. The 'red snow,' which sometimes colours extensive tracts in Arctic or Alpine regions, penetrating even to the depth of several feet, and vegetating actively at a temperature which reduces most plants to a state of torpor, is generally considered to be a species of *Protococcus*; but as its cells are connected by a tolerably firm gelatinous investment, it would rather seem to be a *Palmella*. The second is the condition of *Palmella* proper, of which one species, *P. cruenta*, usually known under the name of 'gory dew,' is common on damp walls and in shady places, sometimes extending itself over a considerable area as a tough, gelatinous mass, of the colour and general appearance of coagulated blood. A characteristic illustration of it is also afforded by the *Hæmatococcus sanguineus* (fig. 373), which chiefly differs from *Palmella* in the partial persistence of the walls of the parent-cells, so that the whole mass is subdivided by partitions, which enclose a larger or smaller number of cells originating in the subdivision of their contents. Besides increasing in the ordinary mode of binary multiplication, the *Palmella* cells seem occasionally to rupture and diffuse their granular contents through the gelatinous stratum, and thus to give origin to a whole cluster at once, as seen at *e*, after the manner of other simple plants to be presently described, save that these minute segments of the endochrome, having no power of spontaneous motion, cannot be ranked as 'zoöspores.' The gelatinous masses of the *Palmella* are frequently found to contain parasitic growths formed by the extension of other plants through their substance; but numerous branched filaments sometimes present themselves, which, being traceable into absolute continuity with the cells, must be considered as properly appertaining



FIG. 372.—A, conjugating microzoöspores of *Ulothrix*; B, megazoöspore of *Ulothrix*, from Vines's 'Physiology of Plants.'

to them. Sometimes these filaments radiate in various directions from a single central cell, and must at first be considered as mere extensions of this; their extremities dilate, however, into new cells; and when these are fully formed, the tubular connections close up, and the cells become detached from each other.[1] Of the third condition we have an example in the curious *Palmodictyon* described by Kützing, the frond of which appears to the naked eye like a delicate network, consisting of anastomosing branches, each composed of a single or double row of large vesicles, within every one of which is produced a pair of elliptical cellules that ultimately escape as 'zoöspores.' The alternation between the 'motile' form and the 'still' or resting form, which has been described as occurring in *Protococcus*, has been observed in several other forms of this group; and it seems obviously intended, like the production of 'zoöspores,' to secure the dispersion



FIG. 373.—*Hæmatococcus sanguineus*, in various stages of development: *a*, single cells, inclosed in their mucous envelope; *b*, *c*, cluster formed by subdivision of parent-cell; *d*, more numerous cluster, its component cells in various stages of division; *e*, large mass of young cells, formed by the subdivision of the parent endochrome, and enclosed within a common mucous envelope.

of the plant and to prevent it from choking itself by overgrowth in any one locality. It is very commonly by plants of this group that the algal portions of lichens are formed.

Notwithstanding the very definite form and large size attained by the fronds or leafy expansions of the **Ulvaceæ**, to which group belong some of the most common grass-green seaweeds ('laver') found on every coast, yet their essential structure differs but very little from that of the preceding group: and the principal advance is shown in this, that the cells, when multiplied by binary subdivision, not only remain in firm connection with each other, but possess a very regular arrangement (in virtue of the determinate

[1] This fact, first made public by Mr. Thwaites (*Ann. of Nat. Hist.*, 2nd series, vol. ii. 1848, p. 313), is one of fundamental importance in the determination of the real character of this group.

plan on which the subdivision takes place), and form a definite membranous expansion. The mode in which this frond is produced may be best understood by studying the history of its development, some of the principal phases of which are seen in fig. 374. The isolated cells A, in which it originates, resembling in all points those of a *Protococcus*, give rise by their successive subdivisions in determinate directions to such regular clusters as those seen at B and C, or to such converfoid filaments as that shown at D. A continuation of the same regular mode of subdivision, taking place alternately in two directions, may at once extend the clusters B and C into leaf-like expansions; or, if the filamentous stage be passed through (different species presenting variations in the history of their development), the filament increases in breadth as well as in length (as seen at E), and finally becomes such a 'frond' as is shown at F, G. In the simple membranous expansion or *thallus* thus formed, there is but little approach to a differentiation of parts in the formation of root, stem, and leaf, such as the higher algæ present; every portion is the exact counterpart of every other, and every portion seems to take an equal share in the operations of growth and reproduction. Each cell is very commonly found to exhibit an imperfect partitioning into four parts preparatory to multiplication by double bipartition, and the entire frond usually shows the groups of cells arranged in clusters containing some multiple of four.



FIG. 374.—Successive stages of development of *Ulva*.

Besides this continuous increase of the individual frond, however, we find in most species of *Ulva* a provision for extending the plant by the dispersion of 'zoöspores.' The endochrome (fig. 375, *a*) subdivides into numerous segments (as at *b* and *c*), which at first are seen to lie in close contact within the cell that contains them, then begin to exhibit a kind of restless motion, and at last escape by the bursting of the cell-wall, and they swim freely through the water as zoöspores (*d*) by means of their flagella, either two or four belonging to each zoöspore, with which they have become endowed during the formation of the zoöspores within their mother-cells. At

last, however, they come to rest, attach themselves to some fixed point, and begin to grow into clusters or filaments (*e*) in the manner already described. The walls of the cells which have thus discharged their endochrome remain as colourless spots on the frond; sometimes these are intermingled with the portions still vegetating in the usual mode; but sometimes the whole endochrome of one portion of the frond may thus escape in the form of zoöspores, leaving behind it nothing but a white flaccid membrane. If the microscopist who meets with a frond of an *Ulva* in this condition examines the line of separation between its green and its coloured portions, he may not improbably meet with cells in the very act of discharging their zoöspores, which 'swarm' around their points of exit very much in the manner that animalcules are often seen to do around particular



FIG. 375.—Formation of zoöspores in *Ulva latissima*: *a*, portion of the ordinary frond; *b*, cells in which the endochrome is beginning to break up into segments; *c*, cells from the boundary between the coloured and colourless portions, some of them containing zoöspores, others being empty; *d*, flagellate zoöspores, as in active motion; *e*, subsequent development of the zoöspores.

spots of the field of view, and which might easily be taken for true Infusoria; but on carrying his observations further, he would see that similar bodies are moving *within* cells a little more remote from the dividing line, and that a little farther still they are obviously but masses of endochrome in the act of subdivision.[1]

More recent observation has brought out the interesting fact that in *Ulva* and its allies there are two kinds of swarm-spore, a larger kind, 'megazoöspores,' with four, and a smaller kind, 'microzoöspores,' with two cilia each (see fig. 372). Of these the megazoöspores germinate directly, as above described, while the microzoöspores have been

[1] Such an observation the Author had the good fortune to make in the year 1842, when the emission of zoöspores from the *Ulvaceæ*, although it had been described by the Swedish algologist Agardh, had not been seen (he believes) by any British naturalist.

observed to conjugate in pairs, producing zygospores, by the germination of which a new generation is produced. The two kinds of zoöspore may be produced on the same or on different individuals.

The **Oscillariaceæ** constitute another tribe of thallophytes of great interest to the microscopist, on account both of the extreme simplicity of their structure and of the peculiar animal-like movements which they exhibit. They consist of fine, usually microscopic threads, containing a blue-green endochrome, sometimes replaced by a red or violet, and occur singly or in thick strata in fresh running or more abundantly in stagnant water. The threads are unbranched and usually straight, and either each separate thread or a number together are, in most of the genera, enclosed in a gelatinous sheath. Some illustrations of these are seen on Plate VII. The contents of the sheaths are imperfectly divided into cells by transverse division; small pieces of the threads, consisting of a few cells, occasionally break off, round themselves off at both ends, move about with a slow undulating motion, and finally develop into new threads; these portions are known as *hormogones*. The most abundant genus *Oscillaria* has been so named from the peculiar oscillating or waving motion with which the threads are endowed. This consists of a creeping motion in the direction of the length of the thread, now backwards, now forwards, accompanied by a curvature of the thread and rotation round its own axis. The cause of this motion is still a matter of controversy. Professor Cohn [1] observed that the oscillating movements take place only when the thread is in contact with a solid substratum. Zukal [2] compares the motion of *Spirulina* to that of a growing tendril, and asserts that it is intimately connected with the growth of the filament. Hansgirg,[3] on the other hand, considers the twisting and nodding movements to be due, not to the growth of the thread, but to osmotic changes in the cell-contents. He regards them as being of the same nature as the movements of the sarcode in the pseudopodia of rhizopods and other protozoa. Schnetzler [4] describes the movements in *Oscillaria* as of six different kinds: (1) rotation of the thread or of its segments round its axis; (2) creeping or gliding over a solid substratum; (3) a free-swimming movement in the water: (4) rotation or flexion of the entire thread; (5) sharp tremblings or concussions; and (6) a radiating arrangement of the entangled threads. The movements are greatly influenced by temperature and light, being much more active in warmth and sunshine than in cold and shade. There are no zoöspores produced, nor is any sexual mode of generation known. The **Rivulariaceæ** and **Scytonemaceæ** (Pls. VII & VIII) are exceedingly common organisms in stagnant water, resembling the Oscillariaceæ in their blue-green colour, and in their reproduction by means of 'hormogones.'

Nearly allied to the preceding is the family of **Nostocaceæ**, consisting of distinctly beaded filaments, which, in the most familiar genus *Nostoc*, lie in firmly gelatinous envelopes of definite outline

[1] *Arch. Mikrosk. Anatomie*, 1867, p. 48.
[2] *Oesterreichische Bot. Zeitsch.* 1880, p. 11.
[3] See *Bot. Centralblatt*, vol. xii. 1882, p. 361.
[4] *Arch. Sci. Phys. et Nat.* 1885, p. 164.

PLATE VI



West, Newman

Oscillariaceæ and Scytonemaceæ.


PUBLIC LIBRARY

(fig. 376). The filaments are usually simple, though sometimes densely interwoven, and are almost always curved or twisted, often taking a spiral direction. The masses of jelly in which they are imbedded are sometimes globular or nearly so, and sometimes extend in more or less regular branches; they frequently attain a very considerable size; and as they occasionally present themselves quite suddenly (especially in the latter part of autumn on damp garden-walks), they have received the name of 'fallen stars.' They are not always so suddenly produced, however, as they appear to be; for they shrink up into mere films in dry weather and expand again with the first shower. Other species are not unfrequent among wet moss or on the surface of damp rocks. Species of *Anabæna* and *Aphanizomenon*, genera of Nostocaceæ, constitute a large portion of the bluish-green scum which floats on the surface of stagnant water. *Nostoc* multiplies, like the Oscillariaceæ, by the subdivision of its filaments, portions of which escape from the gelatinous mass wherein they were imbedded, and move slowly through the water in the direction of their length. These are 'hormogones,' similar to those of the Oscillariaceæ. After a time they cease to move, and a new gelatinous envelope is formed around each piece, which then begins to increase in length by the transverse subdivision of its segments. By the repetition of this process a mass of new filaments is produced, the parts of which are at first confused, but afterwards become more distinctly separated by the interposition of the gelatinous substance developed between them. Besides the ordinary cells of the beaded filaments, two other kinds are known, both larger than the ordinary cells, and called respectively *heterocysts* and *spores*. The function of the former is unknown; the latter develop directly into new individuals by division in the transverse direction only, without any sexual process.



FIG. 376.—Portion of gelatinous frond of *Nostoc*.

Although many of the plants belonging to the family **Siphonaceæ** attain a considerable size, and resemble the higher seaweeds in their general mode of growth, yet they retain a simplicity of structure so extreme as to require them to be ranked among the simpler thallophytes. They are inhabitants both of fresh water and of the sea, and consist of very large tubular cells, which often extend themselves into branches, so as to form an arborescent frond. These branches, however, are not separated from the stem by any intervening partition, except those parts where the generative organs are produced; but the whole frond is composed of a simple continuous tube, the entire contents of which may be readily pressed out through an orifice made by wounding any part of the wall. The genus *Vaucheria*, named after a Genevese botanist, may be selected

as a particularly good illustration of this family, its history having been pretty completely made out. Most of its species are inhabitants of fresh water, but some are marine; and they commonly present themselves in the form of cushion-like masses, composed of irregularly branching filaments, which, although they remain distinct, are densely tufted together and variously interwoven. Some species commonly form dense green mats on damp soil in flower-pots &c. The formation of motile *gonids* or 'zoöspores' may be readily observed in these plants, the whole process usually occupying but a very short time. The extremity of one of the filaments usually swells up in the form of a club, and the endochrome accumulates in it so as to give it a darker hue than the rest; a separation of this part from the remainder of the filament, by the interposition of a transparent space, is next seen; a new envelope is then formed around the mass thus cut off; and at last the membranous wall of the investing tube gives way, and the 'zoöspore' escapes, not, however, until it has undergone marked changes of form, and exhibited curious movements. Its motions continue for some time after its escape, and are then plainly seen to be due to the action of the cilia, which form a complete fringe round it. If it be placed in water in which some carmine or indigo has been rubbed, the coloured granules are seen to be driven in such a manner as to show that a powerful current is produced by their propulsive action, and a long track is left behind it. When it meets with an obstacle, the ciliary action not being arrested, the zoöspore is flattened against the object; and it may thus be compressed, even to the extent of causing its endochrome to be discharged. The cilia are best seen when their movements have been retarded or entirely arrested by means of opium, iodine, or other chemical reagents. The motion of the spore continues for about two hours; but after the lapse of that time it soon comes to an end, and the spore begins to develop itself into a new plant. It has been observed by Unger that the escape of the zoöspores generally takes place towards 8 A.M.; to watch this phenomenon, therefore, the plant should be gathered the day before, and its tufts examined early in the morning. The same filament may give off two or three zoöspores successively.

Recent discoveries have shown that there exists in this humble plant a true process of sexual generation, as was indeed long ago suspected by Vaucher, though upon no sufficient grounds. The branching filaments are often seen to bear at their sides peculiar globular or oval capsular protuberances, sometimes separated by the interposition of a stalk, which are filled with dark endochrome; and from these, after a time, new plants arise. In the neighbourhood of these bodies are found, in most species, certain other projections which, from being usually pointed and somewhat curved, have been named 'horns' (fig. 377, A, *a*); and these have been shown by Pringsheim to be 'antherids,' which produce 'antherozoids' in their interior; whilst the capsule-like bodies (A, *b*) are 'oögones' or 'archegones,' each containing a mass of endochrome which constitutes an 'oösphere' that is destined to become, when fertilised, the original cell of a new generation. The antherozoids (B, *c*, *d*)

PLATE VIII.



West, Newman ii chrom

Desmidiaceæ, Rivulariaceæ and Scytonemaceæ

hen set free from the antherid *a*, swarm over the exterior of ıe oögone *b*, and have been seen to penetrate its cavity through n aperture in its wall, and to come into contact with the surface of ıs endochrome-mass, over which ıey diffuse themselves; there they ɔem to undergo absorption, their ıbstance mingling itself with hat of the oösphere; and the ndoplasm of the 'oöspore' thus ɔrmed, which had previously no roper investment of its own, ɔon begins to form an envelope f cellulose (C, *b*), which increases ı thickness and strength, until : has acquired such a density as nables it to afford a firm pro-ɔction to its contents. While ı *Vaucheria* the separate fila-ıents are so slender as to be ɔarcely discernible to the naked ye, the frond of other genera of iphonaceæ, mostly natives of ıallow seas in the warmer parts f the globe, attains very large imensions. Thus in *Codium* it a spongy spherical or cylin-rical floating mass, as much as foot in length; in *Caulerpa* it ıs the appearance of a branched af springing from a stem, which ıts out roots from its under de: in *Acetabularia* it takes a ushroom-like form with a cap - 'pileus,' a quarter of an inch ı diameter, divided into regular ıambers, at the summit of a ylindrical stalk, 1½ to 3 inches . height. Munier-Charles[1] be-ɛves that many fossils generally ɛgarded as *Foraminifera* are in ɛality the calcareous skeleton of gæ belonging or nearly allied) the Siphonaceæ.



FIG. 377.—Successive phases of generative process in *Vaucheria sessilis*: at A are seen one of the 'horns' or antherids (*a*) and one of the oögones (*b*), as yet unopened; at B the antherid is seen in the act of emitting the antherozoids (*c*), of which many enter the opening at the apex of the oögone, whilst others (*d*) which do not enter it display their cilia until they become motionless; at C the orifice of the oögone is closed again by the formation of a cellulose coat around its endochrome, thus constituting an oöspore.

The microscopist who wishes) study the development of oöspores, as well as several ther phenomena of this low type of vegetation, may advantageously ave recourse to the little plant termed **Achlya prolifera**,[2] which

[1] *Comptes Rendus*, vol. lxxx. 1877, p. 814.

[2] This plant, though, as an inhabitant of water, formerly ranked among *Algæ*, is ow generally regarded as belonging to the group of *Fungi* on account of its

grows parasitically upon the bodies of dead flies lying in the water. Its tufts are distinguishable by the naked eye as clusters of minute colourless filaments; and these are found, when examined by the microscope, to be long tubes, devoid of all partitions, extending themselves in various directions. The tubes contain a colourless slightly granular protoplasm, the particles of which are seen to move slowly in streams along the walls, as in *Chara*, the currents occasionally anastomosing with each other (fig. 378, C). Within about thirty-six hours after the first appearance of the parasite on any body, the protoplasm begins to accumulate in the dilated ends of the filaments, each of which is then cut off from the remainder by the formation of a partition; and within this dilated cell the movement of the protoplasm continues for a time to be distinguishable. Very speedily, however, its endoplasm shows the appearance of being broken up into a large number of distinct masses, which are at first in close contact with each other, and with the walls of the cell (fig. 378, A), but which gradually become more isolated, each seeming to acquire a proper cell-wall; they then begin to move about within the parent-cell; and, when quite mature, they are set free by the rupture of its wall (B), to go forth, and, after swarming about for a time, to develop into tubiform cells resembling those from which they sprang. Each of these zoöspores is possessed of two flagella: their movements are not so powerful as those of the zoöspores of *Vaucheria*, and come to an end sooner. The generative process in this type is performed in a manner that may be regarded as an advance upon ordinary conjugation. The end of one of the long tubiform cells enlarges into a globular dilatation, the cavity of which becomes shut off by a transverse partition. Its contained endoplasm divides into two, three, or four segments, each of which takes a globular form, and is



FIG. 378.—Development of *Achlya prolifera*: A, dilated extremity of a filament *b*, separated from the rest by a partition *a*, and containing zoöspores in progress of formation; B, end of filament after the cell-wall has burst, and setting free zoöspores, *a*, *b*, *c*; C, portion of filament, showing the course of the circulation of granular protoplasm.

incapacity for the production of chlorophyll, and its parasitism on the bodies of animals, from whose juices its cells seem to draw their nourishment. It is very closely allied to *Saprolegnia*, a fungus parasitic on the bodies of living fish, and causing the very destructive disease to which salmon are liable.

n, a length of from four to six inches, and composed of a vast
ber of cylindrical tubular cells, which attain the length of four
or more, and adhere to each other by their rounded extremities,
points of junction corresponding to the knots or intersections
ie network. Each of these cells may form within itself an
nous multitude (from 7,000 to 20,000) of 'swarm-spores,' which
certain stage of their development are observed in active
on in its interior, but come to rest in the course of half an
, and then arrange themselves in such a way that by their
gation they again form a net of the original kind, which is set
by the dissolution of the wall of the mother-cell, and attains
e course of three or four weeks the size of the mother-colony.
les these bodies, however, certain cells produce from 30,000 to
)00 'microzoöspores' of longer shape, each furnished with four
flagella and a red 'eye-spot'; these escape from the cell in a
m, and move freely in the water for some time. Quite recently
igation between these smaller 'zoöspores' has been observed by
el-Port, taking place sometimes even with the mother-cell. The
ting body or 'zygospore' retains its green colour, but becomes
sted with a firm cell-wall of cellulose. In this condition these
es may remain dormant for a considerable time, and are de-
ed as 'hypnospores' or 'resting spores'; and in this state they
able to endure being completely dried up without the loss of
vitality, provided that they are secluded from the action of
, which causes them to wither and die. In this state they bear
ong resemblance to the cells of *Protococcus*. The first change
manifests itself in them, when they begin to germinate, is a
le enlargement; next the endochrome divides itself successively
distinct masses, usually two or four in number; and these,
n set free by the giving way of the enveloping membrane, pre-
the characters of ordinary 'zoöspores,' each of them possessing
flagella at its anterior semitransparent extremity. Their motile

cell-wall, on escaping from which it presents all the essential characters of a young *Hydrodictyon*. The rapidity of the growth of this curious organism is not one of the least remarkable parts of its history. The individual cells of which the net is composed, at the time of their emersion as 'zoöspores,' measure no more than $\frac{1}{3500}$th of an inch in length; but in the course of a few hours they grow to a length of from $\frac{1}{12}$th to $\frac{1}{3}$rd of an inch.

The members of the family **Pediastreæ** were formerly included in the *Desmidiaceæ*; but, though doubtless related to them in certain particulars, they present too many points of difference to be properly associated with them. Their chief point of resemblance consists in the firmness of the outer covering, and in the frequent interruption of its margin either by the protrusion of 'horns' (fig. 379, A), or by a notching more or less deep (fig. 380, B); but they differ in these two important particulars- that the cells are not made up of two sym-



Fig. 379.—Various phases of development of *Pediastrum granulatum*.

metrical halves, and that they are always found in aggregation, which is not, except in such genera as *Scenedesmus* which connect this group with the Desmids, in linear series, but in the form of discoidal fronds. In this tribe we meet with a form of multiplication by motile 'megazoöspores' which reminds us of the formation of the motile spheres of *Volvox*, and which takes place in such a manner that the resultant product may vary greatly in the number of its cells, and consequently both in size and in form. Thus in *Pediastrum granulatum* (fig. 379) the 'zoöspores' formed by the subdivision of the endochrome of one cell, which may be four, eight, sixteen, thirty-two, or sixty-four in number, escape from the parent-frond still enclosed in the inner layer of the cell-wall; and it is within this that they develop themselves into a cluster resembling that in which they originated, so that the frond may be composed of either of the just-mentioned multiples or submultiples of 16. At A is seen an old disc, of irregular shape, nearly emptied by the emission of its 'zoöspores,' which had been seen

e place within a few hours previously from the cells *a*, *b*, *c*, *d*, *e*; f the empty cells exhibit the cross slit through which their ts had been discharged; and where this does not present itself side next the observer, it is found on the other. Three of lls still possess their coloured contents, but in different condi-

One of them exhibits an early stage of the subdivision of the rome, namely, into two halves, one of which already appears again. Two others are filled by sixteen very closely crowded ores,' only half of which are visible, as they form a double layer. s these, one cell is in the very act of discharging its 'zoöspores,' f which have passed forth from its cavity, though still enve- n a vesicle formed by the extension of its innermost membrane; seven yet remain in its interior. The new-born family, as it s immediately on its complete emersion, is shown at B; the ores' are actively moving within the vesicle, and they do not as ow any indication either of symmetrical arrangement or of culiar form which they are subsequently to assume. Within a r of an hour, however, the 'zoöspores' are observed to settle down ne plane, and to assume some kind of regular arrangement, ommonly that seen at C, in which there is a single central urrounded by a circle of five, and this again by a circle of ten; o not, however, as yet adhere firmly together. The 'zoöspores' gin to develop themselves into new cells, increase in size, and nto closer approximation (D); and the edge of each, especially marginal row, presents a notch which foreshadows the produc- its characteristic 'horns.' Within about four or five hours he escape of the 'zoöspores' the cluster has come to assume much of the distinctive aspect of the species, the marginal cells grown out into horns (E); still, however, they are not very connected with each other, and between the cells of the ow considerable spaces yet intervene. It is in the course of ond day that the cells become closely applied to each other, at the growth of the horns is completed, so as to constitute a disc like that seen at F, in which, however, the arrangement interior cells does not follow the typical plan.[1] The formation crozoöspores' has also been observed, which may possibly con-

e varieties which present themselves, indeed, both as to the r of cells in each cluster and the plan on which they are d, are such as to baffle all attempts to base specific distinctions h grounds; and the more attentively the life-history of any these plants is studied, the more evident does it appear that reputed 'species' have no real existence. Some of these, , are nothing else than mere transitory forms; thus it can be y doubted that the specimen represented in fig. 380, D, under me of *Pediastrum pertusum*, is in reality nothing else than a frond of *P. granulatum* in the stage represented in fig. 379, E, nsisting of thirty-two cells. On the other hand, in fig. 380, E,

e Prof. Braun on *The Phenomenon of Rejuvenescence in Nature*, published Ray Society in 1853; and his subsequent memoir, *Algarum Unicellularum nova aut minus cognita*, 1855.

we see an emptied frond of *P. granulatum*, exhibiting the peculiar surface-marking from which the name of the species is derived, but composed of no more than eight cells. And instances every now and then occur in which the frond consists of only four cells, each of them presenting the two-horned shape. So, again, in fig. 380, B, and C, are shown two varieties of *Pediastrum Ehrenbergii*, whose frond is normally composed of sixteen cells; whilst at A is figured a form which is designated as *P. tetras*, but which may be strongly suspected to be merely a four-celled variety of B and C. Many similar cases might be cited; and the Author would strongly urge those microscopists who have the requisite time and opportunities, to apply themselves to the determination of the *real species* of these groups by studying the entire life-history of whatever forms may happen to lie within their reach, and noting all the varieties which present themselves among the offsets from any one stock. The characters of such



FIG. 380.—Various species (?) of *Pediastrum*: A, *P. tetras*; B, C, *P. Ehrenbergii*; D, *P. pertusum*; E, empty frond of *P. granulatum*.

varieties are diffused by the process of binary subdivision amongst vast multitudes of so-called individuals. Thus it happens that, as Mr. Ralfs has remarked, 'one pool may abound with individuals of *Staurastrum dejectum* or *Arthrodesmus incus* having the mucro curved outwards; in a neighbouring pool every specimen may have it curved inwards; and in another it may be straight. The cause of the similarity in each pool no doubt is that all its plants are offsets from a few primary fronds.' Hence the universality of any particular character in all the specimens of one gathering is by no means sufficient to entitle these to take rank as a distinct species: since they are, properly speaking, but repetitions of the same variety by a process of simple multiplication, really representing in their entire aggregate the one plant or tree that grows from a single seed.

Almost every pond and ditch contains some members of the family **Confervaceæ**; but they are especially abundant in moving water, and they constitute the greater part of those green threads

are to be seen attached to stones, with their free ends floating in the direction of the current, in every running stream, and on almost every part of the sea-shore, and which are commonly known under the name of 'silk-weeds,' or 'crow-silk.' Their form is usually very regular, each thread being a long cylinder made up by the union of a single filament of short cylindrical cells united to each other by their flattened extremities; sometimes these threads bear lateral branches, which have the same structure. The chlorophyll, though usually green, is occasionally of a brown or purple hue, and is usually distributed uniformly throughout the cell (as in fig. 381). The plants of this family are extremely favourable subjects for the study of the method of cell-multiplication by *binary subdivision*. The process usually, but not always, takes place only in the *terminal* cell; but may be almost always observed in some one of its stages. The first step is seen to be the subdivision of the endochrome, and the inflexion of the ectoplasm around it (fig. 381, A), and thus there is gradually formed a sort of hour-glass contraction in the cavity of the parent-cell, through which it is divided into two equal halves (fig. 381, B). The two surfaces of the original utricle produce a double layer of the mucose membrane between them. The cells, however, as in *Cladophora glomerata* (a common species), new cells originate as branches from any point on the surface by a process of budding, which, notwithstanding its apparent difference of mode, agrees with that previously described in its essential character, as the result of the subdivision of the terminal cell. A certain portion of the ectoplasm seems to undergo a kind of nutrition, for it is seen to be gradually carrying the cellulose envelope with it, so as to form a little protuberance; and this sometimes attains a considerable length before separation of its cavity from that of the cell which gave origin to it begins to take place. This separation is gradually effected, first by the infolding of the ectoplasm, just as in the preceding case, and thus the endochrome of the branch cell becomes completely separated from that of the stock. The branch then begins to elongate before the subdivision of its first-formed cell; and this process is often repeated for a time in all the cells of the filament, though it usually comes to be restricted at last to the terminal cell. The very young cells of some species of Confervaceæ are characterised by the possession of a large number of nuclei. They are multiplied by



FIG. 381.—Process of cell-multiplication in *Cladophora glomerata*.—A, portion of filament with incomplete separation at *a*, and complete partition at *b*; B, the separation completed, a new cellulose partition being formed at *a*; C, formation of additional layers of cellulose wall, *c*, beneath the mucous investment, *d*, and around the ectoplasm, *a*, which encloses the endochrome, *b*.

zoöspores, produced apparently indifferently from any cell of a fi ment, by free cell-formation. These zoöspores are of two kinds, lar or smaller; the larger kind have either two or four cilia, and ger nate directly; the smaller are biciliated, and conjugation betwe them has been observed in a few instances.



FIG. 382.—Development and reproduction of *Sphæroplea*.

Nearly allied to the Confervaceæ is a very interesting plant i which a true sexual mode of reproduction has been observed, Sphæro plea annulina, the development and generation of which have bee specially studied by Dr. F. Cohn.[1] The 'oöspore,' which is the pro duct of the sexual process to be presently described, is filled whe mature with a red oil, and is enveloped by two membranes, of whic

[1] *Ann. des Sci. Nat.* 4ème sér., Bot., tom. v. 1856, p. 187.

the outer one is furnished with stellate prolongations (fig. 382, No. 1). When it begins to vegetate its endochrome breaks up—first into two halves (No. 2), and then, by successive subdivisions, into numerous segments (Nos. 3, 4), at the same time becoming green towards its margin. These segments, set free by the rupture of their containing envelope, escape in the form of motile zoöspores, which are at first rounded or oval, each having a semi-transparent beak whence proceed two cilia; but they gradually elongate so as to become fusiform (No. 5), at the same time changing their colour from red to green. These move actively for a time, and then, losing their motile power, begin to develop themselves into filaments. The first stage in this development consists in the elongation of the cell, and the separation of the endochrome of its two halves by the interposition of a vacuole (No. 6), and in more advanced stages (Nos. 7, 8) a repetition of the like interposition gives to the endochrome that annular arrangement from which the plant derives its specific name. This is seen at No. 9, *a*, as it presents itself in the filaments of the adult plant; whilst at *b*, in the same figure, we see a sort of frothy appearance which the endochrome comes to possess through the multiplication of the vacuoles. The next stage in the development of the filaments that are to produce the oöspheres consists in the aggregation of the endochrome into definite masses (as seen at No. 10, *a*), which soon become star-shaped (as seen at *b*), each one being contained within a distinct compartment of the cell. In a somewhat more advanced stage (as seen at No. 11, *a*), the masses of endochrome begin to draw themselves together again; and they soon assume a globular or ovoidal shape (*b*), whilst at the same time definite openings (*c*) are formed in their containing cell-wall. Through these openings the 'antherozoids' developed within other cells gain admission, as shown at No. 12, *d*; and they become absorbed into the before-mentioned masses, which soon afterwards become invested with a firm membranous envelope, as shown in the lower part of No. 12. These undergo further changes whilst still contained within their tubular parent-cells, their colour passing from green to red; and a second investment is formed within the first, which extends itself into stellate prolongations, as seen in No. 13; so that, when set free, they precisely resemble the mature oöspores which we have taken as the starting-point in this curious history. Certain of the cells (as in No. 14), instead of giving origin to oöspores, have their annular collections of endochrome converted into 'antherozoids,' which, as soon as they have disengaged themselves from the mucilaginous sheath that envelopes them, move about rapidly in the cavity of their containing cell (*a*, *b*) around the large vacuoles which occupy its interior, and then make their escape through apertures (*c*, *d*) which form themselves in its wall, to find their way through similar apertures into the interior of the 'oögones,' as already described. These antherozoids are shown in No. 15, as they appear when swimming actively through the water by means of the two cilia which each possesses. The peculiar interest of this history consists in the entire absence of any special organs for the generative process, the ordinary filamentous cell developing oöspheres on the one hand and anthero-

zoids on the other, and in the simplicity of the means by which the fecundating process is accomplished.

The **Œdogoniaceæ** resemble *Confervaceæ* in general aspect and habit of life, but differ from them in some curious particulars. As the component cells of the filaments extend themselves longitudinally, new rings of cellulose are formed successively, and intercalated into the cell-wall at its upper end, giving it a ringed appearance. Only a single large zoöspore is set free from each cell; and its liberation is accomplished by the almost complete fission of the wall of the



FIG. 383.—A. Sexual generation of *Œdogonium ciliatum*: 1, filament with two oögones in process of formation, the lower one having two androspores attached to its exterior, the contents of the upper oögone in the act of being fertilised by the entrance of an antherozoid set free from the interior of its androspore; 2, free antherozoids; 3, mature oöspore, still invested with the cell-membrane of the parent-filament; 4, portions of a filament bearing special cells, from one of which an androspore is being set free; 5, liberated androspore.

B, Branches of *Chætophora elegans*, in the act of discharging ciliated zoöspores, which are seen, as in motion, on the right.

cell through one of these rings, a small part only remaining uncleft, which serves as a kind of hinge whereby the two parts of the filament are prevented from being altogether separated. Sometimes the zoöspore does not completely extricate itself from the parent-cell; and it may begin to grow in this situation, the root-like processes which it puts forth being extended into the cavity. The zoöspores are the largest known in any class of algæ; each has a nucleus, a red 'eye-spot' and an anterior hyaline spot to which is attached a tuft of cilia visible even before its escape from its mother-cell.

In their generative process, also, the *Œdogoniaceæ* show a curious departure from the ordinary type; for whilst the 'oöspheres' are

ormed within certain dilated cells of the ordinary filament (fig. 383, A, No. 1), which may be termed 'oögones,' and are fertilised by the enetration of 'antherozoids' (No. 2), these antherozoids are not, in all ne species, the immediate product of the sperm-cells of the same or f another filament, but are developed within a body termed an androspore' (No. 5), which is set free from within a special cell (No.), and which, being furnished with a terminal tuft of cilia, and having notile powers, very strongly resembles an ordinary zoöspore. This ndrospore, after its period of activity has come to an end, attaches self to the outer surface of an oögone, or of a cell in close proxiity to an oögone, as shown at No. 1, *b*; it then develops into a ery small male plant, known as a 'dwarf-male,' consisting of two or hree cells; the terminal of these cells is an antherid, from the apex f which a sort of lid drops, as seen in the upper part of No. 1, by hich its contained antherozoids (No. 2) are set free; and at the ame time an aperture is formed in the wall of the oögone by hich the antherozoid enters its cavity and fertilises its oösphere by ecoming absorbed into it. This mass then becomes an oöspore (No. 3), nvested with a thick wall of its own, but still retains more or less f the envelope derived from the cell within which it was developed. he offices of these different classes of reproductive bodies are only ow beginning to be understood, and the inquiry is one so fraught ith physiological interest, and, from the facility of growing these lants in aquaria, can be so easily pursued, that it may be hoped hat the zeal of microscopists will not long leave any part of it in bscurity.

The **Chætophoraceæ** constitute a beautiful and interesting little roup of confervoid plants, of which some species inhabit the sea, hilst others are found in fresh and pure water—rather in that of ently moving streams, however, than in strongly flowing currents. enerally speaking, their filaments put forth lateral branches, and xtend themselves into arborescent fronds; one of the distinctive characters of the group is afforded by the fact that the xtremities of these branches are usually prolonged into bristle-haped processes (fig. 383, B). As in many preceding cases, these lants multiply themselves by the conversion of the endochrome of ertain of their cells into 'zoöspores,' and these, when set free, are een to be furnished with either two or four cilia. 'Resting-pores' have also been seen in many species. One of the most eautiful objects under the microscope is *Draparnaldia glomerata*, ot uncommon in still water. It consists of an axis composed of a ingle row of large transparent cells containing but a small quantity f chlorophyll. From this proceed, at regular intervals, whorls of lender branches, the endochrome of which is deep green, and every ranch ends in a delicate hyaline hair of extraordinary length. The node of reproduction of the *Chætophoraceæ* closely resembles that of he *Confervaceæ*.

The **Batrachospermeæ**, whose name is indicative of the strong esemblance which their beaded filaments bear to frog-spawn, are ow ranked as humble fresh-water forms of a far higher, chiefly narine group of algæ, the *Rhodospermeæ*, or red sea-weeds. But

they deserve special notice here on account of the simplicity of their structure, and the extreme beauty of the objects they afford to the microscopist (fig. 384). They are chiefly found in water which is pure and gently flowing. 'They are so extremely flexible,' says Dr. Hassall, 'that they obey the slightest motion of the fluid which surrounds them; and nothing can surpass the ease and grace of their movements. When removed from the water they lose all form, and appear like pieces of jelly, without trace of organisation; on immersion, however, the branches quickly resume their former disposition.' Their colour is for the most part of a brownish green, but sometimes they are of a reddish or bluish purple. The central axis of each plant is at first composed of a single filament of large cylindrical cells laid end to end; but this is subsequently invested by other cells, in the manner to be presently described. It bears, at pretty regular intervals, whorls of short, radiating branches, each of which is composed of rounded cells, arranged in a bead-like row, and sometimes subdividing again into two, or themselves giving off lateral branches. Each of the primary branches originates in a little protuberance from the primitive cell of the central axis, precisely after the manner of the lateral cells of *Cladophora glomerata*; as this protuberance increases in size, its cavity is cut off by a septum, so as to render it an independent cell; and by the continual repetition of the process of binary subdivision this single cell becomes converted into a beaded filament. Certain of these branches, however, instead of radiating from the main axis, grow downwards upon it, so as to form a closely fitting investment that seems properly to belong to it. Some of the radiating branches grow out into long transparent bristles, like those of *Chætophoraceæ*; and within those are produced 'antherozoids,' which, though not endowed with the power of spontaneous movement, find their way to the oöspheres contained in other parts of the filaments; and by the fertilisation of the contents of these are produced the somewhat complicated fructifications known as 'cystocarps,' placed in the axils of the branches (fig. 384).



Fig. 384.
Batrachospermum moniliforme.

A very singular relationship, called by some writers an 'alternation of generations,' exists between *Batrachospermum* and *Chantransia*, a genus of fresh-water algæ previously placed in a totally different section. This relationship was first described by Sirodot,[1]

[1] Sirodot, *Les Batrachospermées*, fo. 1884; see also *Comptes Rendus*, vol. lxxvi 1873, pp. 1216, 1335; vol. xci. 1880, p. 862; vol. xcii. 1881, p. 993.

observations have since been confirmed by others. The
ting spores of *Batrachospermum* put out, under certain
ns, a kind of filament, known as a 'protoneme,' which
into a *Chantransia*, a non-sexual form of *Batrachospermum*,
ın reproduce itself from generation to generation by simple
, or by means of non-sexual spores, without producing
rgans. *Chantransia* is especially found in water where very
ht reaches it. When more exposed to light it undergoes
phosis, and then a branch springs up from the 'protoneme'
; in every respect a *Batrachospermum*, bearing true sexual
ıs above described. This may then go on reproducing itself,
t to the *Chantransia* form.

ng the highest of the Algæ in regard to the complexity of
ıerative apparatus, which contrasts strongly with the general
y of their structure, is the family of **Characeæ** (ranked by
tanists as a group of primary importance), some members
ı have received a large amount of attention from micro-
on account of the interesting phenomena they exhibit.
umble plants are for the most part inhabitants of fresh
and are found rather in such as are still than in those
re in motion; a few species, however, may be met with in
whose waters are rendered salt by communication with the
ey may be easily grown for the purposes of observation in
ss jars exposed to the light, all that is necessary being to
the water occasionally from the upper part of the vessel
rying away a film that is apt to form on its surface), and
ce this by fresh water. Each plant is composed of an
ge of long tubiform cells placed end to end, with a
central axis, around which the branches are disposed at
with great regularity (fig. 385, A). In *Nitella* the stem
ıches are composed of simple cells, which sometimes attain
th of several inches; whilst in most species of *Chara* each
ube is surrounded by an envelope of smaller ones, which is
ıs in *Batrachospermum*, save that the investing cells grow
as well as downwards from each node, and meet each other
stem half-way between the nodes, their ends dovetailing
another. These investing tubes constitute what is termed
ex' of *Chara*. They are of smaller diameter than the central
l are arranged spirally round it, giving the stem a twisted
ıce. Each 'node,' or zone from which the branches spring,
of a single plate or layer of small cells, which, in *Chara*, are
ıation of the cortical layer of the 'internode.' The branches
ether similar in structure to the primary axis, and termi-
, large elongated pointed cell, which is not covered by the
From the lower part of the stem 'rhizoids' or rooting
are put out, which attach the plant to the soil. Some
ıave the power of secreting carbonate of lime from the
. which they grow, if this be at all impregnated with
s matter; and by the deposition of it beneath their tegu-
ıey have gained their popular name of 'stoneworts.' The
form cells of *Nitella*, and the terminal uncorticated cells of

the branches of *Chara*, afford a very beautiful and instructive display of the phenomenon of *cyclosis*, or rotation of protoplasm in their interior. Each cell, in the healthy state, is lined by a layer of chlorophyll grains, which cover every part, except two longitudinal lines that remain nearly colourless (fig. 385, B); and a constant stream of semi-fluid protoplasm, containing starch grains and chlorophyll granules, is seen to flow over the green layer, the current passing up one side, changing its direction at the extremity, and flowing down the other side, the ascending and descending spaces being bounded by the transparent lines just mentioned. In



FIG. 385.—*Nitella flexilis*: A. Stem and branches of the natural size: *a*, *b*, *c*, *d*, four whorls of branches issuing from the stem; *e*, *f*, subdivision of the branches. B. Portion of the stem and branches enlarged: *a*, *b*, joints of stem; *c*, *d*, whorls; *e*, *f*, new cells sprouting from the sides of the branches; *g*, *h*, new cells sprouting at the extremities of the branches.

the young cells the rotation may be seen before this granular lining is formed. The rate of the movement is affected by anything that influences the vital activity of the plant; thus it is accelerated by moderate warmth, whilst it is retarded by cold; and it may be at once checked by a slight electric discharge through the plant. Carried along by the protoplasmic stream are a number of solid particles, which consist of starchy matter, and are of various sizes, being sometimes very small and of definite figure, whilst in other instances they are seen as large irregular masses, which appear to be formed by the aggregation of the smaller particles.[1] The produc-

[1] This interesting phenomenon may be readily observed by taking a small portion of the plant out of the water in which it is growing, and either placing it in

tion of new cells for the extension of the stem or branches, or for the origination of new whorls, is not here accomplished by the subdivision of the parent-cell, but takes place by the method of outgrowth (fig. 385, B, *e*, *f*, *g*, *h*), which, as already shown, is nothing but a modification of the usual process of cell-multiplication; in this manner the extension of the individual plant is effected with considerable rapidity. When these plants are well supplied with nutriment, and are actively vegetating under the influence of light, warmth, &c. they not unfrequently develop 'bulbils,' which are little cluster of cells, filled with starch, that sprout from the sides of the central axis, and then, falling off, evolve the long tubiform cells characteristic of the plant from which they were produced. There are also several other non-sexual ways in which these plants are reproduced, but they are peculiar among cryptogams in not producing true 'spores,' either stationary or motile. The *Characeæ* may be multiplied by artificial subdivision, the separated parts continuing to grow under favourable circumstances, and gradually developing themselves into the typical form.

The generative apparatus of *Characeæ* consists of two sets of bodies, both of which grow at the bases of the branches (fig. 386, A, B), either on the same or on different individuals; one set, formerly known as 'globules,' are really *antherids*; whilst the other, known as 'nucules,' contain the *oöspheres*, and are true oögones or *archegones*. The 'globules,' which are nearly spherical, and often of a bright red colour, have an envelope made up of eight triangular plates or 'shields' (B, C), often curiously marked, which encloses a central portion of a light reddish colour; this central portion is principally composed of a mass of filaments rolled up compactly together. From the centre of the inner face of each shield a cylindrical cell termed a 'manubrium' projects inwards nearly to the centre of the sphere. The antherid is supported on a short flask-shaped pedicel which also projects into the interior. At the apex of each of the eight manubria is a roundish hyaline cell, called a 'capitulum,' and at the apex of each capitulum six smaller cells or 'secondary capitula.' From the centre of each of these secondary capitula grow four long whip-shaped filaments (C), constituting the mass already referred to. The number of these filaments in each antherid is about 200, and each of these filaments divides by transverse septa into from 100 to 200 small disc-shaped cells, which number therefore from 20,000 to 40,000 in each antherid. In every one of these cells there is formed, by a gradual change in its contents (the successive stages of which are seen at D, E, F), an *antherozoid*, a spiral thread of protoplasm consisting of two or three coils, which, at first motionless, after a time begins to move and revolve within the cell, and at last the cell-wall gives way, and the spiral thread makes its escape (G), partially straightens itself, and moves actively through the water for some time (H) in a tolerably determinate

a large aquatic box or in the zoöphyte-trough (p. 297), or laying it on the glass stage-plate and covering it with thin glass. A portion of *Chara* or *Nitella* placed in the growing slide (pp. 288, 289) may be kept under observation for many days together.

direction, by the lashing action of two long and very delicate cilia with which it is furnished. The exterior of the 'nucule' (A, B) is formed by five or ten spirally twisted tubes that give it a very peculiar aspect; and these enclose a central sac containing protoplasm, oil, and starch-globules. Each of these tubes consists, in its lower part, of a very long unsegmented cell; while at its upper part two small cells are segmented off; and these small cells



FIG. 386.—Generative organs of *Chara fragilis*: A, antherid or 'globule' developed at the base of archegone or 'nucule'; B, nucule enlarged, and globule laid open by the separation of its valves; C, one of the valves, with its group of antheridial filaments each composed of a linear series of cells, within every one of which an antherozoid is formed; in D, E, and F the successive stages of this formation are seen; and at G is shown the escape of the mature antherozoids, H.

of all the tubes form together the 'crown' of the nucule. When ready for fertilisation the branches of the crown part slightly, forming an open passage or 'neck' down to the central germ-cell or *oösphere*; and through this canal the antherozoids make their way down to perform the act of fertilisation by becoming absorbed into the substance of the oösphere. Ultimately the nucule, which has now become a hard black body, falls off, and the fertilised germ-

cell, or 'oöspore,' gives origin to a new plant after the nucule has remained dormant through the winter.[1]

Desmidiaceæ and Diatomaceæ.

Among those simple Algæ whose generative process consists in the 'conjugation' of two similar cells, there are two groups of such peculiar interest to the microscopist as to need a special notice: these are the *Desmidiaceæ* and the *Diatomaceæ*.[2] Both of them were ranked by Ehrenberg and many other naturalists as animalcules; but the fuller knowledge of their life-history and the more extended acquaintance with the parallel histories of other simple forms of vegetation which have been gained during the last twenty years are now generally accepted as decisive of their vegetable nature.

The *Desmidiaceæ*[3] are minute plants of a bright green colour growing in fresh water; generally speaking, the cells are independent of each other (figs. 387–390); but sometimes those which have been produced by binary subdivision from a single parent-cell remain adherent one to another in linear series, so as to form a filament (fig. 391; Plate IX, fig. 3). They are distinguished by two peculiar features, one of these being the semblance of a division of each cell into two symmetrical halves by a 'sutural line,' which is sometimes so decided as to have led to the belief that the cell is really double (Plate VIII, figs. 2, 6), though in other cases it is merely indicated by a slight notch; the other feature is the frequency of projections from the surface, which are sometimes short and inconspicuous, but are often elongated into spines (Plate VIII, fig. 6), presenting a very symmetrical arrangement. These projections are generally formed by the cellulose envelope alone, which possesses an almost horny consistence, so as to retain its form after the discharge of its contents (fig. 387, B, D); while, in other instances, they are formed by a notching of the margin of the cell (Plate IX, fig. 1) which may affect only the outer casing, or may extend into the cell-cavity. The outer coat is surrounded by a very transparent sheet of gelatinous substance, which is sometimes very distinct (as shown in fig. 391; Plate IX, fig. 6); but in

[1] A full account of the *Characeæ* will be found in Prof. Sachs' *Text-book of Botany*, 2nd English edition, p. 292. Various observers have asserted that particles of the protoplasmic contents of the cells of the *Characeæ*, when set free by the rupture of their cells, may continue to live, move, and grow as independent rhizopods. But the writer is disposed to think that the phenomena thus represented are rather to be regarded as cases of parasitism, the decaying cells of *Nitella* having been found by Cienkowski (*Beiträge zur Kenntniss der Monaden*, in *Arch. f. Mikr. Anat.* bd. i 1865, p. 203) to be inhabited by minute, spindle-shaped, ciliated bodies, which seem to correspond with the 'spores' of the *Myxomycetes*, going through an amœboid stage, and then producing a *plasmode* which, after undergoing a sort of encysting process, finally 'breaks up' into spindle-shaped particles resembling those found in the *Nitella* cells.

[2] [Whether the process which takes place in diatoms is a true sexual conjugation is a point which cannot at present be regarded as fully determined.—Ed.]

[3] Our first accurate knowledge of this group dates from the publication of Mr. Ralfs' admirable monograph of the British Desmids in 1848. Later information in regard to it will be found in the section contributed by Mr. W. Archer to the fourth edition of Pritchard's *Infusoria*, and in Cooke's *British Desmids*, 1887.

other cases its existence is only indicated by its preventing the contact of the cells. Klebs states[1] that in Desmids, as in the other *Conjugatæ*, this mucilaginous sheath is composed of two portions—a homogeneous substance which is but slightly refringent, and a portion which consists of minute rods at right angles to the cell-wall. He regards the sheath as entirely independent of the substance of the cell-wall, and as derived from the protoplasmic contents of the cell by diffusion through the cell-wall. The true cell-wall encloses a primordial utricle, which is not always closely adherent to it; and this immediately surrounds the endochrome, which occupies nearly the whole interior of the cell, and in certain stages of its growth is found to contain starch-granules. The endochrome and starch-grains are arranged symmetrically in the two halves of the cell, often in very beautiful patterns, bands, or stars.

Many species of desmids have a power of slow movement in the water, the cause of which is not obvious, these organisms being entirely destitute of vibratile cilia. Klebs[2] describes this movement as being of four kinds, viz. (1) a forward movement on the surface, one end of the cell touching the bottom, while the other end is more or less elevated, and oscillates backwards and forwards; (2) an elevation in a direction vertical to the substratum, the free end making wide circular movements; (3) a circular motion, followed by an alternate sinking of the free end and elevation of the other end; and (4) an oblique elevation so that both ends touch the bottom, lateral movements in this position, then an elevation and circular motion of one end, and a sinking again to an oblique or horizontal position. Klebs regards all these movements as due to an exudation of mucilage, and the first two to the formation during the motions of a filament of mucilage by which the desmid is temporarily attached to the bottom, and which gradually lengthens. The movements of desmids are especially active when they are in the process of dividing. Stahl found that, like the movements of zoöspores, they are affected by light, and always move towards the light.

A 'cyclosis' may be readily observed in many *Desmidiaceæ*, and is particularly obvious along the convex and concave edges of the cell of any vigorous specimen of *Closterium*, with a magnifying power of 250 or 300 diameters (fig. 387, A, B). By careful focussing the flow may be seen in broad streams over the whole surface of the endrochrome; and these streams detach and carry with them, from time to time, little oval or globular bodies (A, *b*) which are put forth from it, and are carried by the course of the flow to the transparent spaces at the extremities, where they join a crowd of similar bodies. In each of these spaces (B) a protoplasmic flow proceeds from the somewhat abrupt termination of the endochrome towards the obtuse end of the cell (as indicated by the interior arrows), and the globules it contains are kept in a sort of twisting movement on the *inner* side (*a*) of the primordial utricle. Other currents are seen apparently external to it, which form three or four distinct

[1] *Untersuchungen aus dem Bot. Inst. Tübingen*, 1886, p. 333.
[2] *Biologisches Centralblatt*, 1885, p. 353.

PLATE IX.



Desmidiaceæ.

West, Newman chromo.



courses of particles, passing towards and away from *c* (as indicated by the outer arrows). Another curious movement is often to be witnessed in the interior of the cells of members of this family, which has been described as 'the swarming of the granules,' from the extraordinary resemblance which the mass of particles in active vibratory motion bears to a swarm of bees. It is especially observable in the hyaline terminal portions of the cells of species of *Closterium*, as shown in fig. 387, B. This motion continues for some time after the particles have been expelled by pressure from the interior of the cell; and it appears to be an active form of the molecular movement common to other minute particles freely suspended in fluid. This movement of minute particles affords an instance of the phenomenon known as 'Brownian movement,' and is probably of a purely mechanical nature.

When the single cell has come to its full maturity it commonly multiplies itself by *binary subdivision*; but the plan on which this



FIG. 387.—Cyclosis in *Closterium lunula*: A, cell showing central separation at *a*, in which the large particles, *b*, are not seen; B, one extremity enlarged, showing the movement of particles in the colourless space; D, cell in a state of division.

takes place is often peculiarly modified, so as to maintain the symmetry characteristic of the tribe. In a cell of the simple cylindrical form of those of *Desmidium* (fig. 391), little more is necessary than the separation of the two halves at the sutural line, and the formation of a partition between them by the infolding of the primordial utricle; in this manner, out of the lowest cell of the filament A, a double cell, B, is produced. But it will be observed that each of the simple cells has a bifid wart-like projection of the cellulose wall on either side, and that the half of this projection, which has been appropriated by each of the two new cells, is itself becoming bifid, though not symmetrically; in process of time, however, the increased development of the sides of the cells which remain in contiguity with each other brings up the smaller projections to the dimensions of the larger, and the symmetry of the cells is restored. In *Closterium* (fig. 387; Plate IX, fig. 2) the two halves of the endochrome first retreat from one another at the sutural line, and a constriction takes place round the cellulose wall: this constriction

deepens until it becomes an hour-glass contraction, which proceeds until the cellulose wall entirely closes round the primordial utricle of the two segments; in this state one half commonly remains passive, whilst the other has a motion from side to side, which gradually becomes more active; and at last one segment quits the other with a sort of jerk. At this time a constriction is seen across the middle of the primordial utricle of each segment, indicating the formation of the sutural band; but there is no division of the cell-cavity, which is that belonging to one of the halves of the original entire cell. The cyclosis, for some hours previously to subdivision, and for a few hours afterwards, runs quite round the obtuse end, *a*, of the endochrome; but gradually a transparent space is formed, like that at the opposite extremity, by the retreat of the coloured layer; whilst, at the same time, its obtuse form becomes changed to a more elongated and contracted shape. Thus, in five or six hours after the separation, the aspect of each extremity becomes the same, and each half resembles the cell by the division of which it originated.

The process is seen to be performed after nearly the same method in *Staurastrum*, the division taking place across the central constriction, and each half gradually acquiring the symmetry of the original. In such forms as *Cosmarium*, however, in which the cell consists of two lobes united together by a narrow isthmus, the division takes place after a different method; for when the two halves of the outer wall separate at the sutural line, a semi-globular protrusion of the endochrome is put forth from each half; these protrusions are separated from each other and from the two halves of the original cell (which their interposition carries apart) by a narrow neck; and they progressively increase until they assume the appearance of the half-segments of the original cell. In this state, therefore, the plant consists of a row of four segments, lying end to end, the two old ones forming the extremes, and the two new ones (which do not usually acquire the full size or the characteristic markings of the original before the division occurs) occupying the intermediate place. At last the central fission becomes complete, and two bipartite fronds are formed, each having one old and one young segment; the young segment, however, soon acquires the full size and characteristic aspect of the old one; and the same process, the whole of which may take place within twenty-four hours, is repeated ere long. The same general plan is followed in *Micrasterias denticulata*; but as the small hyaline hemisphere, put forth in the first instance from each half-cell (fig. 388, A), enlarges with the flowing in of the endochrome, it undergoes progressive subdivision at its edges, first into three lobes (B), then into five (C), then into seven (D), then into thirteen (E), and finally at the time of its separation (F) acquires the characteristic notched outline of its type, being only distinguishable from the older half by its smaller size. The whole of this process may take place within three hours and a half. In *Sphærozosma* the cells thus produced remain connected in rows within a gelatinous sheath, like those of *Desmidium* (fig. 391): and different stages of the process may commonly be observed in the different parts of any one of the filaments thus formed. In any

such filament it is obvious that the two oldest segments are found at its opposite extremities, and that each subdivision of the intermediate cells must carry them farther and farther from each other. This is a very different mode of increase from that of the *Confervaceæ*, in which commonly the terminal cell alone undergoes subdivision, and is consequently the one last formed.

The sexual generative process in the *Desmidiaceæ*, which occurs but rarely compared to that of binary division, always consists of an act of 'conjugation.' It commences with the dehiscence of the



FIG. 388.—Successive stages of binary subdivision of *Micrasterias denticulata*.

firm external envelope of each of the conjugating cells, so as to separate it into two valves (fig. 389, C, D; fig. 390, C). The contents of each cell thus set free without any distinct investment blend with those of the other; and a 'zygospore' is formed by their union, which soon acquires a truly cellulose envelope.[1] This envelope is at first very delicate, and is filled with green and granular contents; by degrees the envelope acquires increased thickness, and its contents become brown or red. Ultimately the envelope becomes differentiated into three layers, of which the innermost and outermost are colourless, while the middle one is firmer and brown.

[1] In certain species of *Closterium*, as in many of the *Diatomaceæ*, the act of conjugation gives origin to *two* zygospores.

The outer surface is sometimes smooth, as in *Closterium* and its allies (fig. 390; Plate IX, fig. 8); but in *Cosmarium* it becomes granular, tuberculated, or spinous (fig. 389, D; Plate VIII, figs. 1, 4), the spines being sometimes simple and sometimes forked at their extremities. The mode in which conjugation takes place in the filamentous species constituting the *Desmidieæ* proper, is, however, in many respects different. The filaments first separate into their component joints, and when two cells approach in conjugation, the outer cell-wall of each splits or gapes at that part which adjoins the other cell, and a new growth takes place, which forms a sort of connecting tube that unites the cavities of the two cells (fig. 391, D, E). Through this tube the entire endochrome of one cell passes over into the cavity of the other (D); and the two are commingled so as to form a single mass (E), as is the case in many of the *Conjugatæ*. The joint which contains the zygospore can scarcely be distinguished at first (after the separation of the empty cell), save by the greater density of its contents; but the proper coats of the zygospore gradually become more distinct, and the enveloping cell-wall disappears.



FIG. 389.—Conjugation of *Cosmarium botrytis*: A, mature cell; B, empty cell-envelope; C, transverse view; D, zygospore with empty cell-envelopes.

The subsequent history of the zygospore has been followed out in the case of *Cosmarium botrytis*. After remaining at rest for a considerable time, it germinates by the bursting of the two outer coats, the protoplasmic contents escaping while still enclosed in the innermost coat. In this body the protoplasm and endochrome are already divided into two halves, which contract somewhat, and the whole becomes enveloped in a new cell-wall. A constriction has, in the meantime, made its appearance between the two halves, which are of somewhat unequal size, and thus the new desmid is formed.



FIG. 390.—Conjugation of *Closterium striolatum*: A, ordinary cell; B, empty cell; C, two cells in conjugation, with zygospore.

›division of this family into genera, according to the Mr. Ralfs ('British Desmidieæ'), as modified by Mr. tchard's 'Infusoria'), is based in the first instance upon ion or disconnection of the individual cells, two groups formed, of which one includes all the genera whose cells, plied by binary division, remain united into an elongated hilst the other, and much larger one, comprehends all ich the cells be- ted by the com- he fission. The ision of the fila- oup, in which ores are always smooth (Pl. IX, sed on the fact set of genera the any times longer are broad, and re neither con- furnished with or projections; e other set (fig. fig. 3) the length of each joint are l, and the joints less constricted, ateral teeth or angles, or some ; and it is for part upon the in these last that the generic are based. The oup presents a is for primary the marked dif- the proportions such elongated *Closterium* (figs. l. IX, fig. 2), in



FIG. 391.—Binary subdivision and conjugation of *Desmidium cylindricum*: A, portion of filament, surrounded by gelatinous envelope; B, dividing cell; C, single cell viewed transversely; D, two cells in conjugation; E, formation of zygospore.

length is many times the breadth, being thus separated n which, as in *Micrasterias* (fig. 388; Pl. IX, fig. 1), *Cos-* .389; Pl. VIII, fig. 2), and *Staurastrum* (Pl. VIII; figs. 5, breadth more nearly equals the length. In the former the are smooth, whilst in the latter they are very commonly VIII, figs. 1, 4) and are sometimes quadrate. In this group econdary characters are derived from the degree of con- ween the two halves of the cell, the division of its margin its by incisions more or less deep, and its extension into nes.

midiaceæ are not found in running streams, unless the

motion of the water be very slow, but are to l
ing though not stagnant waters. Small shal
dry up in summer, especially in open, expo
boggy moors, are most productive. The larg
commonly lie at the bottom of the pools, e
thin, gelatinous stratum, or collected into finge
passing the fingers beneath these they may be
the surface of the water, and may then be lift
scoop. Other species form a slimy stratum flo
bog-pools, or a greenish or dirty cloud upon tl
other aquatic plants; and these also are bes
the hand beneath them, and 'stripping' t
fingers, so as to carry off upon them what adl
other hand, the bodies of which we are in s
diffused through the water, there is no other
up in large quantities by the box or scoop an
straining through a piece of linen. At first, i
linen but a mere stain or a little dirt; bu
repeated quantities a considerable accumulat
made. This should then be scraped off with a
into bottles with fresh water. If what has be
be richly charged with these forms, it should l
a bottle; this at first seems only to contai
allowing it to remain undisturbed for a little
sink to the bottom, and most of the water m
to be replaced by a fresh supply. If the bottl
solar light, these little plants will flourish, a
their native pools; and their various phases
reproduction may be observed during succe
years. If the pools be too deep for the use
scoop, a collecting-bottle attached to a stick
its stead. The ring-net may also be adva
especially if it be so constructed as to allow
tion of one piece of muslin for another.
pieces of previously wetted muslin in succe
of these minute organisms may be separa
the pieces of muslin may be brought hom
mouthed bottles, either separately or severa
the organisms are obtained from one or fron
they are then to be opened out in jars of fil
exposed to the light, when the desmids will de

The **Diatomaceæ**, like the Desmidiaceæ, a
a firm, external coating, within which is inclu
whose superficial layer constitutes a 'primor
external coat is consolidated by *silex*, the pre
of the most distinctive characters of the grou
peculiar surface-markings of its members.
by some that the solidifying mineral forms a
from the exterior of the cellulose wall; but th
for regarding that wall as itself interpenetrat
a membrane bearing the characteristic surface-

oval by hydrofluoric acid. The 'endochrome' is in other plants, of a viscid protoplasm, in les of colouring matter. In the ordinary con- granules are diffused through it with tolerable n the central spot, which is occupied by a nucleus they commonly form a ring, from which anules may be seen to diverge into the cell- being bright green, however, the endochrome is The principal colouring substance appears to f ordinary chlorophyll; it takes a green or th sulphuric acid, and often assumes this hue in is combined in greater or less proportion a tter termed *diatomin*, which is very unstable s in drying. At certain times, oil-globules are otoplasm; these seem to represent the starch- *diaceæ* and the oil-globules of other protophytes. of the granular particles of the endochrome, cyclosis of the *Desmidiaceæ*, has been noticed h in some of the larger species of *Diatomaceæ*, *eriata*, *Nitzschia scalaris*, and *Campylodiscus* ssor Max Schultze in *Coscinodiscus*, *Biddulphia*, it this movement has not the regularity so ceding group.

l these organisms *Bacillariaceæ* from the genus have called them *Diatomaceæ* from *Diatoma*. ferable, as indicating the ease with which their each other. This is well seen in the genus rectangular individual *frustules*, where the g from the principle of lateral union causes ilaments or zigzag chains, the frustules remain- and united only by a small isthmus or cushion ilar cohesion at the angles is seen in the allied *a* (fig. 403), in *Isthmia* (fig. 408), and in many *iddulphia* (fig. 396) there even seems to be a achment at these points. In some diatoms, s produced by successive acts of binary subdi- ain coherent one to another, and thus are pro- sters of various shapes. Thus it is obvious that short cylinder, an aggregation of such cylinders, a rounded filament, as in *Melosira* (fig. 398); the form of the sides of the frustules, if they other, a *straight* filament will be produced, as in

But if, instead of being parallel, the sides be wards each other, a *curved* band will be the continue entire, but may so divide itself as to unsions, as those of *Licmophora flabellata* (fig. may be sufficient to occasion the band to wind nd a central axis, and thus to form, not merely spiral of several turns, as in *Meridion circulare* atoms, again, possess a *stipe*, or stalk-like ap- ggregations of frustules are attached to other

plants, or to stones, pieces of wood, &c.; and this may be a simple foot-like appendage, as in *Achnanthes longipes* (fig. 412), or it may be a composite plant-like structure, as in *Licmophora* (fig. 401), *Gomphonema* (fig. 413), and *Mastogloia* (fig. 416). Little is known respecting the nature of this stipe: it is, however, quite flexible, and may be conceived to be an extension of the cellulose coat, uncon-solidated by silex, analogous to the prolongations which have been seen in the *Desmidiaceæ*, and to the filaments which sometimes connect the cells of the *Palmellaceæ*. Some diatoms, again, have a mucous or gelatinous investment, which may even be so substantial that their frustules lie—as it were—in a bed of it, as in *Mastogloia* (figs. 416 B, 417), or may form a sort of tubular sheath to them, as in *Schizonema* (fig. 415). In a large proportion of the group, however, the frustules are always met with entirely *free*, neither remaining in the least degree coherent one to another after the process of binary subdivision has once been completed, nor being in any way connected either by a stipe, or by a gelatinous investment. This is the case, for example, with *Triceratium* (fig. 393), *Pleurosigma* (Plate I, figs. 1, 2), *Actinocyclus*, *Actinoptychus* (fig. 407), *Arachnoidiscus* (Plate XII), *Campylodiscus* (fig. 405), *Surirella* (fig. 404), *Coscino-discus* (Plate I, figs. 3, 4), *Heliopelta*, and many others. The solitary discoidal forms, however, when obtained in their living state, are commonly found cohering to the surface of aquatic plants.

We have now to examine more minutely into the curious struc-ture of the silicified casing which encloses every diatom-cell or 'frustule,' and the presence of which imparts a peculiar interest to the group; not merely on account of the elaborately marked pattern which it often exhibits, but also through the perpetuation of the minutest details of that pattern in the specimens obtained from fossilised deposits. This silicified casing is usually formed of two perfectly symmetrical valves united to one another by means of two embracing rings which constitute the connecting zone or *girdle*, and thus exactly represent a minute box which serves for the reproduc-tion of the species. This process is known as the encystment, and is not uncommon, especially amongst the *Naviculaceæ*, frustules being frequently found amongst them open from the separation of the two valves, showing the two rings covering each other, as the lid of a box may cover a portion of the box itself.

It is thus not correct to designate the line shown in the front view of the outer ring as the line of 'suture,' since the *suture* is the line of meeting bounding two surfaces placed on the same plane. The form resulting, however, varies widely in different diatoms: for sometimes each valve is hemispherical, so that the cavity is globular; sometimes it is a smaller segment of a sphere resembling a watch-glass, so that the cavity is lenticular; sometimes the central portion is completely flattened and the sides abruptly turned up, so that the valve resembles the cover of a pill-box, in which case the cavity will be cylindrical; and these and other varieties may co-exist with any modifications of the contour of the valves, which may be square, triangular (fig. 393), heart-shaped (fig. 405, A), boat-shaped (fig. 404, A), or very much elongated (fig. 400), and may be furnished (though this

ong diatoms) with projecting outgrowths (figs. 409, 410).
ı shape presented by the frustule differs completely with
; under which it is seen. In all instances, the frustule is
l to present its 'front' view when its line of meeting is
wards the eye, as in fig. 404, B, C; whilst its 'side' view
ıen the centre of either valve is directly beneath the eye
hough the two valves meet along the line of junction in
rly formed frustules which have been just produced by
bdivision (as shown in fig. 396, A, *e*), yet as soon as they
ndergo any increase the valves separate from one another;
ıe silicification of the cell-membrane thus left exposed a
ps is formed, each of which is attached by one edge to the
alve, while the other edge is free.[1] As will be presently
one of the valves is always older than the other; and the
ıe older valve partly encloses that of the younger, just as
of a pill-box surrounds the upper part of the box itself.[2]
wly formed cell increases in length, separating the valves
ınother, both hoops increase in breadth by additions to their
, and the outer hoop slides off the inner one, until there
ıt a very small 'overlap.' As growth and binary division
ually going on when the frustules are in a healthy vigorous
it is rare to find a specimen in which the valves are not in
ee separated by the interposition of the hoops.

ıpermeability of the silicified casing seems to render neces-
xistence of special apertures through which the surrounding
y come into communication with the contents of the cell.
e believed that they have seen such apertures along the
line of suture' of the disc-shaped diatoms, and at the extre-
y of the elongated forms. Ehrenberg, followed by Kützing,
ɔreted as apertures or ostioles the central and terminal
: the *Naviculaceæ*, *Cymbelleæ*, and similar forms; but this
ore generally regarded as incorrect. We have, in fact, no
emonstration of the existence of special apertures communi-
ween the outside and the inside of the cell; and we are com-
ıave recourse, on this point, to hypothesis. It is, however,
ıt the diatom-cell is always composed of at least two valves,
which the possibility of such a communication must
y be admitted, or at least the existence of endosmotic and
currents in the liquids. In the encysted forms we have
d also the existence of an interval between the two rings,

efers to those diatoms in which the process of binary subdivision is pos-
ıis, as will be seen presently, is not the case in many genera.—ED.]
ıs long since pointed out by Dr. Wallich in his important memoir on the
ıt and Structure of the Diatom-valve' (*Transact. of Microsc. Soc.* n.s.
0, p. 129); but his observation seems not to have attracted the notice of
ıntil in 1877 he called attention to it in a more explicit manner (*Monthly
ırn.* vol. xvii. p. 61). The correctness of his statement has been con-
e distinguished American diatomist, Prof. W. Hamilton Smith; but as it
lled in question by Mr. J. D. Cox (*American Journal of Microscopy*,
, p. 100), who asserts that in *Isthmia* there are *three* hoops—two attached
alves, and the third overlapping them both at their line of junction—the
ıimself made a very careful examination of a large series of specimens of
l *Biddulphia*, the result of which has fully satisfied him of the correct-
Vallich's original description.

although it may be very minute; while *Navicula* has been sometimes seen with the valves actually separated.



FIG. 392.—Magnification of 'ultimate structure' of *Coscinodiscus asteromphalus*, from a drawing by Messrs. Nelson and Karop. ('Quekett Journal,' vol. ii. ser. ii. p. 269.)

The nature of the delicate markings with which almost every diatom frustule is beset, has been one of the most interesting inquiries of the students of these forms, since the introduction of the homogeneous, and especially the apochromatic objectives; and it cannot be doubted that certain peculiarities of structure have been demonstrated which were never before seen. In the present state of the theory and practice of microscopy, it would be extremely unwise to give absolute adhesion to any present interpretation of what is now held by some students of diatom structure of no mean repute and of unrivalled manipulative skill to be the absolute structure of some of the larger forms.

Thus concerning the group *Coscinodisceæ*, representing the most beautiful of the discoid forms of the whole group of *Diatomaceæ*, we re-



FIG. 393.—*Triceratium favus*: A, side view; B, front view.

present in fig. 3, Plate I, a micro-photographic image of *C. asteromphalus* magnified 110 diameters. But in fig. 392 the *areolæ* of this diatom are seen under great magnification with recent powers. It is contended that the diatom, although consisting of a single siliceous membrane, has a double structure, viz. coarse and fine areolations, the latter within the former; and there appears little reason to doubt this. The coarse areolations are for the most part circular in outline, and the intervening silex is thick. Inside these areolations is an extremely delicate perforated membrane, the outer row of whose perforations are larger than the rest. From the very delicacy of this membrane, and its consequent easy fracture, it is often wanting. In Plate I, fig. 4, we present a photo-micrograph of the same object magnified 2,000 diameters.

thmia nervosa, a side and front view of which are seen in a similar construction is discoverable. In this diatom the areolations are very large and the silex correspondingly ut the inner membrane is excessively thin and delicate. The ons are large and irregular in shape the margin, but small and circular in re. In fig. 394 the form of areola shown, and a broken membrane th the fracture passing through the ons.[1]



FIG. 394.—Areolations in *Isthmia nervosa*.

less interesting is the beautiful form *scus Kittonii*; a photo-micrograph of nified 270 diameters is seen in Pl. I, while a small portion of the centre of ed form, *A. Sturtii*, magnified 2,000 shown in fig. 6 in the same plate. 'beaded' appearance of diatom-valves iversal in all those which have been examined, that it must led as common to all diatoms, although this is not yet abso- roved. But, while it is admitted that the beading of the nay be common to all diatoms, it cannot be regarded as hat the siliceous envelope is composed of globular particles arranged in regular rows; while the variety in the size and nent of these particles shows that they are correlated with processes of the organisms, and afford characters for the nation of the species. The nature of these granules, their the mode in which they are arranged, have from the earlier nicroscopy rendered diatoms of special value as 'test-objects.' pearance has led to the use, in speaking of diatoms, of the terms 'transverse,' 'longitudinal' or 'oblique striæ,' these truth simply the intervals which separate the boundaries of ds,' apertures, or their equivalents, whatever they may ulti- rove to be; and this is clearly seen when they are observed ectives of sufficient numerical aperture and proportional *Pleurosigma angulatum* is one of the most commonly em- st-objects, and at the same time one of the most reliable, its ble constancy rendering it especially valuable for this purpose; the contrary, *Amphipleura pellucida* is extremely variable, it were, the torment of microscope-makers and rival diatom , who do not take into account the variability of this type, g, in fact, that one *A. pellucida* may be extremely fine, and being in truth a varietal form, may be nearly as coarse as *rhomboides*. The new apochromatic objectives, and the ating eye-pieces both for the eye and for projection, con- by Zeiss, of Jena, have brought about such progress in phy that the image of *P. angulatum* appears to some minds no doubt as to the details of its structure. If we closely the photographic image of a portion of *P. angulatum*, pro- der a magnification of 4,300 diameters, and shown in Plate from a photograph by Dr. Zeiss, it will, in the majority of

[1] on the finer structure of certain diatoms, E. M. Nelson and G. C. Karop, *ckett Club*, vol. ii. ser. ii. p. 296.

cases, leave perhaps little doubt that the valves are covered by the beads or apertures in a decussate arrangement. We have, in the judgment of Count Castracane, to do here with 'beads' and not with 'cavities.' But, from the recent advances of our knowledge, this by no means follows; they may with high probability be considered perforations in the silex of the frustule. This is indeed placed almost in the form of a demonstration by the interesting fact that Mr. C. Haughton Gill has succeeded in *filling up* the 'dots' or 'pearls' of the *Naviculæ* and the secondary markings of the discoid and other forms, so as to give evidence that the filling must be deposited in cavities. It was done by soaking clean diatoms in a solution of subnitrate of mercury until their markings are filled with it; then they are immersed in sulphide of ammonium; a double decomposition takes place, by which black insoluble sulphide of mercury is produced, and left in the minute cavities in which it certainly appears to be formed. By observing the lines of fracture, which always follow the interval between two rows of 'beads,' there will be much suggestion given to the observer on this subject. Count Castracane, referring to Plate X, asks, 'Would it have been possible to have seen these pearl-like objects isolated, if, instead of beads, we had had apertures or depressions?' We can only reply that misinterpretation on such a subject is so possible that it is only by employing all the aids to interpretation which ingenuity can place within our reach, we can ever be certain as to our visual interpretation of these minute phenomena. On the other hand, the areolated valves of *Triceratium favus* (fig. 393) present a line of fracture which traverses indifferently the hexagonal areæ and the lines in relief which connect them.

Dr. Van Heurck has been able to employ the new lens made by Abbe, having a numerical aperture of 1·63, upon his special subject, the *Diatomaceæ*. He concludes that diatom valves consist of two membranes or thin films and of an intermediate layer, the *latter being pierced with openings*. The outer membrane is delicate, and may be easily destroyed by acids, friction, and the several processes of 'cleaning.' When the openings or apertures of this interior portion are arranged in alternate rows they assume the hexagonal form; when in straight rows then the openings are square or oblong.

It is, however, due to Mr. T. F. Smith, who has worked at the subject for years, to say that he has long maintained this view, and has presented skilful photo-micrographs in support of his contention. In Pl. I, fig. 1, we have a photograph of his, showing the *inside* of a valve of *P. angulatum* magnified 1,750 diameters, and exhibiting the 'postage stamp' fracture; while in fig. 2, in the same plate, we have the *outside* of *P. angulatum*, showing a different structure; and Mr. Smith has abundant evidence of the existence of what he has so long maintained.

By using the new lens of the great aperture of 1·63, Dr. Van Heurck has produced some remarkable photo-micrographs, which rather confirm these general inferences than present any new data of knowledge concerning the diatoms. By his great courtesy we have been favoured with a phototype plate prepared by Dr. Van Heurck from his own photo-micrographs, and the reader will be enabled to study these in Plate XI, of which a full description is given

Plate X.

Pleurosigma angulatum.

Magnified 4900 diams.

Photo-Micrograph by Dr. R. Zeiss taken
2 m/m. Apochromatic Objective N. A. 1.30
and projection eye-piece 4.

Reprint by Kühl & Co., Frankfort

in the earlier part of this treatise, giving descriptions of the plates. He has further enhanced the plate by giving in fig. 7 a photo-micrograph of Nobert's nineteenth band.

Diatoms, like other organisms already described, are reproduced by conjugation, and multiply by autofission or division. Reproduction is necessary to every organism, while multiplication by fission belongs only to certain organic types. In the early days of the study of diatoms, it would appear that even that distinguished observer William Smith had at least not a clear idea of the encysting of the *frustule* or individual diatom, which implies the existence of the two valves and of the double girdle or zone or connecting ring projecting from each valve in a direction at right angles to its plane. Hence, instead of finding, as a result of fission, a progressive diminution of the diameter of the frustules, Mr. Smith speaks of their increase, of which he is unable to offer any explanation. The fact that in *Melosira subflexilis* (fig. 395, A) and *M. varians* (fig. 395, B) large and small frustules are seen united in rows, ought to be sufficient to show that they are dependent not only on binary subdivision, but also on the special conditions of evolution of the new frustule, by which it is able to increase materially in size. This power of diatoms to expand their siliceous coatings has therefore been denied by some, who are induced to maintain this necessary consequence of the division of encysted frustules, viz. the progressive decrease in size of the young frustules, which would thus reach the smallest possible dimensions. This has led Pfitzer[1] to imagine that when diatoms have reached their smallest possible dimensions by repeated binary division, the process of conjugation takes place between them, resulting in the formation of an *auxospore*, capable of reproducing two sporangial frustules of considerably larger size, which would again give rise, by fission, to a new series of diminishing frustules, until these again reach their minimum size. This theory has, in the judgment of Count Castracane, deceived many botanists, from the idea that it was founded on actual observation, and has at the same time been in harmony with the natural tendency to generalisation, in attributing to the whole family of diatoms that faculty of division which has been regarded as the universal property of the vegetable cell. The unconfirmed auxospore theory rests on the



A *Melosira subflexilis.* FIG. 395. B *Melosira varians.*

[1] *Untersuchungen über. Bau u. Entwickelung der Bacillarien*, 8vo, Bonn, 1871.

supposed inability of the siliceous walls of diatoms to expand; and implies, secondly, the idea that all diatoms are capable of binary subdivision: and thirdly, that there is no mode of reproduction except by auxospores. That the silicious walls of diatoms are capable of distension seems to result from the examples already given of *Melosira subflexilis* and *M. varians*, as also from some other species in which there may often be observed a sudden variation in diameter in frustules united together in a row. But the power of increase in size of the siliceous diatom-cell is evidently proved by the sporangial frustules of *Orthosira Dickiei*,[1] where, in the chain of cylindrical frustules of the same diameter, the sporangial frustule is dilated in its equatorial axis, but much more so in its polar axis, pushing back the base of the next cell and forcing it to fold itself up so as to occupy the whole cell-cavity, and sometimes even that of the next frustule. The exactness and fidelity of the figure given in Smith's 'Synopsis,' besides being guaranteed by the authority of the distinguished author and by the signature of the celebrated artist Tuffen West, Count Castracane has been able to confirm by a magnificent preparation of these diatoms in which are a number of sporangial frustules. The auxospore theory supposes the fact that all diatoms are capable of binary subdivision, since the auxospore is understood, according to Pfitzer, to provide for the progressive decrease in size of the frustules, with the production of larger sporangial frustules, destined to commence a new descending series. But binary subdivision cannot take place in genera with unequal valves, as it is universally acknowledged that the two new valves which are formed in the process of binary subdivision must stereotype themselves on the old valves; and for this reason this process cannot take place in those genera in which the axes cross one another, like *Campylodiscus*, or in those in which the two valves, although equal, yet constantly unite in such a way that the similar parts alternate with one another, as may be seen in *Asterolampra*. That it is impossible for binary subdivision to take place in these three classes of forms, is confirmed by the fact that, notwithstanding that there are recorded not less than seventy-five observations of the process of division in them, not one affords an exception to the rule given above.

Where multiplication by binary subdivision occurs among the *Diatomaceæ*, it takes place on the same general plan as in the *Desmidiaceæ*, but with some modifications incident to peculiarities of the structure of the former group. The first stage consists in the elongation of the cell, and the formation of a 'hoop' adherent to each end-valve, so that the two valves are separated by a band, which progressively increases in breadth by addition to the free edges of the hoops, as is well seen in fig. 396, A. In the newly formed cell *e*, the two valves are in immediate apposition; in *d* a band intervenes; in *a* this band has become much wider; and in *b* the increase has gone on until the original form of the cell is completely changed. At the same time the endochrome separates into two halves: the nucleus also subdivides in the manner formerly shown

[1] See Castracane, 'The Theory of the Reproduction of Diatoms,' *Atti dell' Accad. Pontif. dei Nuovi Lincei*, May 31, 1874; and 'New Arguments to prove that Diatoms are reproduced by means of germs,' *ibid.* March 19, 1876.

PLATE XI.



Fig. 1. Fig. 2. Fig. 3.

Fig. 4. Fig. 5. Fig. 6.

Fig. 7. Fig. 8. Fig. 9.

Tuerck phot. J. Mayes, phototyp.

TEST OBJECTS FOR THE MICROSCOPE.

ve by C. Zeiss. N.A. 1.60. Eye-piece 12. Monochromatic illumination by sunlight.



g. 368, G, H, I) ; and the primordial utricle folds in, first forming mere constriction, then an hour-glass contraction, and finally a mplete double partition, as in other instances. From each of its jacent surfaces a new silicious valve is formed, as shown at fig. 6, A, C, just as a new cellulose wall is generated in the subdivision other cells ; and this valve is usually the exact counterpart of the e to which it is opposed, and forms with it a complete cell, so that e original frustule is replaced by two frustules, each of which has .e old and one new valve, just as in *Desmidiaceæ*. Generally eaking, the new valves are a little smaller than their predecessors ; that, after repeated subdivisions (as in chains of *Isthmia*), a minution of diameter becomes obvious.[1] But sometimes the new lves are a little larger than their predecessors ; so that, in the amentous species, there may be an increase sufficient to occasion a adual widening of the filament, although not perceptible except hen two contiguous frustules are compared ; whilst, in the free forms, ustules of different sizes ay be met with, of which ie larger are more numer- is than the smaller, the ıcrease in number having ıken place in geometrical ogression, whilst that of ze was uniform. It is not lways clear what becomes the 'hoop.' In *Melosira* fig. 395, A and B), and erhaps in the filamentous ecies generally, the 'hoops' ppear to keep the new ustules united together for me time. This is at first e case also in *Biddulphia* ıd *Isthmia* (fig. 408), in hich the continued connec- on of the two frustules by means gives rise to an ppearance of two complete ustules having been de- loped within the original ig. 396, A, C) ; subse- ıently, however, the two ew frustules slip out of the oop, which then becomes mpletely detached. The me thing happens with many other diatoms, so that the 'hoops' re to be found in large numbers in the settlings of water in which ese plants have long been growing.



FIG. 396.—*Biddulphia pulchella*: A, chain of cells in different states: *a*, full size; *b*, elongation preparatory to subdivision; *c*, formation of two new cells; *d*, *e*, young cells; B, end view; C, side view of a cell more highly magnified.

But in some other cases all trace of the hoop is lost, so that it ay be questioned whether it has ever been properly silicified, and

[1] This could not be explained on the hypothesis of the rigidity of the walls within hich fission takes place.

true generative act, and that when that progeny is c
currents into different localities, each will continue
its own special type so long as the process of binary divis

We have seen that division is of the nature of mu
and not of reproduction ; and that, where it does take pl
be regarded as the exception, and not as the rule.
reproduction, Count Castracane, who has been an obse
thirty years devoted to the study of diatoms, has had
tunity of noting in what way the process differs in parti
He contends that he has been able to see in a *Podo*
emission of gonids or sporules or embryonal forms, in th
in which Rabenhorst saw it in *Melosira varians*, and
Pleurosigma Spencerii ; and in another case there
number of oval cysts of a species of *Navicula* easily r
The greater number of these were in a quiescent state
few were seen in motion by means of two flagelliform ci
these larger or smaller cysts represented zygospores, a
them were shown to be zoözygospores. Castracane ha
fortune to meet with a number of large and small
imbedded in a gelatinous mass, all of them having in the
similar corpuscles. From the condition of two gree
indistinct forms, these went on, by an easy transition,
themselves as naviculoid types, and at length develope
grown frustules of *Mastogloia*. All this proves in his jud
reproduction in diatoms may present itself in different
with different peculiarities ; for which reason one ough
arguing from special cases to general laws. The only
can be asserted of all cases of reproduction, is that
preceded by conjugation, which results in the fertilised
sporules or gonids, which, after a period of repose or of
inclosed within a cyst, or within a membranous frond,
frustule, attain a condition for living an independen



ARACHNOIDISCUS JAPONICUS.

marine deposit of the Miocene period, he met with a perfect
ule of *Coscinodiscus punctatus*, which, between the two planes
ıe valves, and therefore within the cell, exhibited some round
:s which admitted of no other interpretation except that of
essions or traces of the embryonal forms surprised by death
ə still attached to the mother-cell. More recently he has met
other cases identical in character, so that he has no longer any
t as to the presence of silex in the cell-walls of diatoms
h have not yet emerged to the light.

No one appears at present to have given attention to a circum-
:e described by the Abbé[1] in relation to a specimen of *Striatella
unctata*, which has passed thousands of times under the eyes of
vithout its significance being recognised. The diatoms which
have most frequently under our observation do not always
bit the same arrangement of their endochrome. The attempt
indeed been made to found the classification of diatoms on the
ngement of the endochrome, according as it is present in the
ı of plates or of granules; thus distinguishing the *placochromatic*
the *coccochromatic* forms; but a difficulty is presented in the
' of this classification by certain types which sometimes belong
:he one, sometimes to the other class. And this cannot be the
ılt of accident. Such variations might occur in some diatoms
the result of special biological conditions of the individual.
:re may frequently be seen, for example, a specimen of *Melosira
ians* with its cell-cavity filled with endochrome, not in a condition
unequal amorphous masses, but of uniform rounded corpuscles;
this demands particular attention, or at least gives good ground
special research. A diligent examination instituted in these
:s has demonstrated the existence in them of a special organi-
on; and the determination of a narrow and well-defined limit of
ine seems to prove that these were perfectly distinct and
'pendent of one another. From the perfect resemblance of
e with the gonids and embryonal forms seen to escape from the
her-cell by Rabenhorst, O'Meara, and Castracane, he concludes
this special arrangement of the endochrome must be interpreted
' prelude to the process of reproduction. These observations
possibly attract the attention of some who are applying them-
es to the study of diatoms to so important an argument, on
:h may depend the possibility of establishing a really good
sification of diatoms which will at length satisfy diatomists. At
ent preference is generally accorded to the classification proposed
I. L. Smith, which establishes the class of *Raphideæ* from the
ence of a raphe in the plane of the valves. If there is, on the
es, in place of the raphe, a simple line of division, the forms thus
acterised are termed *Pseudoraphideæ*; while those in which
valves have neither raphe nor its equivalent are called *Crypto-
ideæ*, or, better, *Anaraphideæ*. While, therefore, in the present
e of our knowledge of diatoms, any classification can only be
rded as provisional, we do not propose any innovation on this

[1] See 'The Diatoms of the Coasts of Istria and Dalmatia,' *Atti dell' Accad. Pontif. Nuovi Lincei*, April 27 and May 25, 1873.

point, although we are disposed to accord our preference to that suggested by H. L. Smith.

The most curious phenomenon presented by diatoms is undoubtedly their power of movement, which induced Ehrenberg and the other early observers of these organisms to place them erroneously in the animal kingdom, although it affords no evidence of consciousness. This power of movement, if not common to all diatoms, is very evident in those species which are normally or accidentally free, and most conspicuously in oblong forms. In those also which are stalked it has been noticed that if, from any cause, a frustule becomes detached, it is endowed with a motion similar to that of the species which are normally free. This circumstance has caused the abandonment of Mr. W. Smith's proposal to assign a generic value to the condition in which the frustule is presented without regard to its form. Hence those genera are not now generally recognised which differ only in being enclosed in a membranous frond, or in being stalked, especially since frustules contained, for example, in *Schizonema*,[1] have been seen to escape from it, and to be prevented from returning again to it in company with the sister *Navicula*. Hence the genera *Schizonema*, *Berkeleya*, and *Dickiea* must be reunited to *Navicula*; *Cocconema*, *Endonema*, and *Colletonema* to *Cymbella*; and *Homeocladia* to *Nitzschia*. The singular phenomenon of movement which may be observed in many genera of diatoms among which the most singular is that presented by *Bacillaria paradoxa* (fig. 400), in which the rod-like frustules are seen to be continually gliding one along another, in a retrograde direction, before they become detached- is found to be in general a movement backwards and forwards in a straight line so far as they meet with no impediment, while the intervention of obstacles determines a passive change of direction. The cause of this movement is uncertain; but the most probable interpretation attributes it to the action of the changes resulting from the nutrition of the cell, which must necessarily absorb food in a liquid condition. Taking account therefore of the relatively considerable quantity of silex necessary to the organisation of the diatom cell in proportion to its minute dimensions, and bearing in mind, at the same time, the incalculably small traces of silex in solution in the water, it may be understood how active must be the exchange from the exterior to the interior of the cell, and *vice versa*, and hence how such an exchange must determine a continual change of position backwards and forwards, through the reaction exercised on the delicate floating frustules.

Conjugation, so far as is at present known, takes place among the ordinary *Diatomaceæ* almost exactly as among the *Desmidiaceæ*, except that it sometimes results in the production of two 'zygospores' instead of a single one. Thus in *Surirella* (fig. 404), the valves of two free and adjacent frustules separate from each other, and the two endochromes (probably included in their primordial utricles) are discharged; these coalesce to form a single mass, which becomes enclosed in a gelatinous envelope; and in due time

[1] See Castracane, 'Observations on the Genera *Homeocladia* and *Schizonema*,' in *Atti dell' Accad. Pontif. dei Nuovi Lincei*, May 23, 1880

this 'zygospore' shapes itself into a frustule resembling that of its parent, but of larger size. But in *Epithemia* (fig. 397, A, B), the first diatom in which the conjugating process was observed by Mr. Thwaites[1]—the endochrome of each of the conjugating frustules (C, D) appears to divide at the time of its discharge into two halves; each half coalesces with half of the other endochrome; and thus *two* 'zygospores' (E, F) are formed, which, as in the preceding case, become invested with a gelatinous envelope, and gradually assume the form and markings of the parent frustules, but grow to a very much larger size, the sporangial masses having obviously a power of self-increase up to the time when their envelopes are consolidated. It seems to be in this way that the normal size is recovered, after the progressive diminution which is incident to repeated binary multiplication. Of the subsequent history of the 'zygospores' much remains to be learnt; and it may not be the same in all cases. Appearances have been seen which make it almost certain that the contents of each zygospore break up into a brood of *gonids*, and that it is from these that the new generation originates. These gonids, if each be surrounded (as in many other cases) by a distinct cyst, may remain undeveloped for a considerable period; and they must augment considerably in size before they obtain the dimensions of the parent frustule. It is in this stage of the process that the modifying influence of external agencies is most likely to exert its effects; and it may be easily conceived that (as in higher plants and animals) this influence may give rise to various diversities among the respective individuals of the same brood; which diversities, as we have seen, will be transmitted to all the repetitions of each that are produced by the process of binary division. Hence a very considerable latitude is to be allowed to the limits of species, when the different forms of *Diatomaceæ* are compared; and here, as in many other cases, a most important question arises as to what *are* those limits—a question which can only be answered by such a careful



FIG. 397.—Conjugation of *Epithemia turgida*: A, front view of single frustule; B, side view of the same; C, two frustules with their concave surfaces in close apposition; D, front view of one of the frustules, showing the separation of its valves; E, F, side and front views after the formation of the zygospores.

[1] See *Annals of Natural History*, vol. xx. ser. i. 1847, pp. 9, 343; and vol. i. ser. ii. 1848, p. 161.

study of the entire life-history of every single type as may advantageously occupy the attention of many a microscopist who is at present devoting himself to the resolution of the markings on diatom-valves, and to the multiplication of reputed species by the detection of minute differences.[1]

This formation of what are termed 'auxospores'—as serving to augment the size of the cells which are to give origin to a new generation—takes place on a very different plan in some of those filamentous types, such as *Melosira* (fig. 395, A, B), in which a strange inequality presents itself in the diameters of the different cells of the same filament, the larger ones being usually in various stages of binary subdivision, by which they multiply themselves longitudinally. According to the observations of Mr. Thwaites (*loc. cit.*), these also are the products of a kind of conjugation between the adjacent cells of the ordinary diameter, taking place before the completion of their separation. He describes the endochrome of particular frus-



FIG. 398.—Self-conjugation (?) of *Melosira italica* (*Aulacosira crenulata*, Thwaites): 1, simple filament; 2, filament developing auxospores; *a*, *b*, *c*, successive stages in the formation of auxospores; auxospore-frustules in successive stages, *a*, *b*, *c*, of multiplication.

tules, after separating as if for the formation of a pair of new cells, as moving back from the extremities towards the centre, rapidly increasing in quantity and aggregating into a zygospore (fig. 398, No. 2, *a*, *b*, *c*): around this a new envelope is developed, which may or may not resemble that of the ordinary frustules, but which remains in continuity with them; and this zygospore soon undergoes binary subdivision (No. 3, *a*, *b*, *c*), the cells of the new series thus developed presenting the character of those of the original filament (1), but greatly exceeding them in size. From what has been already stated, it seems probable that a gradual reversion to the smaller form takes place in subsequent subdivisions, a further reduction being checked

[1] See on this subject a valuable paper by Prof. W. Smith 'On the Determination of Species in the *Diatomaceæ*,' in the *Quart. Journ. of Microsc. Science*, vol. iii. 1855, p. 130; a memoir by Prof. W. Gregory 'On Shape of Outline as a Specific Character of *Diatomaceæ*,' in *Trans. of Microsc. Soc.* 2nd series, vol. iii. 1854, p. 10; and the Author's Presidential Address, in the same volume, pp. 44–50; 'On *Navicula crassinervis*, *Frustulia saxonica* and *N. rhomboides*, as Test-objects,' by W.H. Dallinger, *Monthly Micro. Journ.* 1876, vol. xvii. p. 1; also an *Additional note* on the identity of these, by the same Author, *ibid.* p. 173.

by a new formation of zygospores. Whether this formation partakes of the character of 'conjugation' (as supposed by Mr. Thwaites), is still doubtful, some later observers regarding 'auxospores' as simply enlarged forms of single cells.

Most of the diatoms which are not fixed by a stipe possess some power of spontaneous movement; and this is especially seen in those whose frustules are of a long narrow form, such as that of the *Naviculæ* generally. The motion is of a peculiar kind, being usually a series of jerks, which carry forward the frustule in the direction of its length, and then carry it back through nearly the same path. Sometimes, however, the motion is smooth and equable, and this is especially the case with the curious *Bacillaria paradoxa* (fig. 400), whose frustules slide over each other in one direction until they are all but detached, and then slide as far in the opposite direction, repeating this alternate movement at very regular intervals.[1] In either case the motion is obviously quite of a different nature from that of beings possessed of a power of self-direction. 'An obstacle in the path,' says Mr. W. Smith, 'is not avoided, but pushed aside; or, if it be sufficient to avert the onward course of the frustule, the latter is detained for a time equal to that which it would have occupied in its forward progression, and then retires from the impediment as if it had accomplished its full course.' The character of the movement is obviously similar to that of those motile forms of protophytes which have been already described; but it has not yet been definitely traced to any organ of impulsion, and the cause of it is still obscure. By Mr. W. Smith it is referred to forces operating within the frustule, and originating in the vital operations of growth &c. which may cause the surrounding fluid to be drawn in through one set of apertures and expelled through the other.[2] 'If,' as he remarks, 'the motion be produced by the exosmose taking place alternately at one and the other extremity, while endosmose is proceeding at the other, an alternating movement would be the result in frustules of a linear form; whilst in others of an elliptical or orbicular outline, in which foramina exist along the entire line of suture, the movements, if any, must be irregular or slowly lateral. Such is precisely the case. The backward and forward movements of the *Naviculæ* have been already described; in *Surirella* (fig. 404) and *Campylodiscus* (fig. 405) the motion never proceeds further than a languid roll from one side to the other; and in *Gomphonema* (fig. 414), in which a foramen fulfilling the nutritive office is found at the larger extremity only, the movement (which is only seen when the frustule is separated from its stipe) is a hardly perceptible advance in intermitted jerks in the direction of the narrow end.'

[1] This curious phenomenon the Author has himself repeatedly had the opportunity of witnessing.

[2] It has been objected to this view, by the authors of the *Micrographic Dictionary*, that, if such were the case, the like movements would be frequently met with in other minute unicellular organisms. But there are no other such organisms in which the cell is almost entirely enclosed in an impermeable envelope, so that the imbibition and expulsion of fluid are limited to a small number of definite points, instead of being allowed to take place equally (as in other unicellular organisms) over the entire surface. See Mereschkowski in *Journ. Roy. Microsc. Soc.* vol. i. ser. ii. 1881, p. 102.

The principles upon which this interesting group should be classified cannot be properly determined until the history of the generative process—of which nothing whatever is yet known in a large proportion of diatoms, and but little in any of them—shall have been thoroughly followed out. The observations of Focke[1] render it highly probable that many of the forms at present considered as distinct from each other would prove to be but different states of the same, if their *whole* history were ascertained. On the other hand, it is by no means impossible that some which appear to be nearly related in the structure of their frustules and in their mode of growth, may prove to have quite different modes of reproduction. At present, therefore, *any* classification must be merely provisional; and in the notice now to be taken of some of the most interesting forms of the *Diatomaceæ*, the method of Professor Kützing, which



Fig. 399.



Fig. 400.

Fig. 399.—*Meridion circulare.* Fig. 400.—*Bacillaria paradoxa.*

is based upon the characters of the individual frustules, is followed in preference to that of Mr. W. Smith, which was founded on the degree of connection remaining between the several frustules after binary division.[2] In each family the frustules may exist under four conditions: (*a*) free, the binary division being entire, so that the frustules separate as soon as the process has been completed; (*b*) stipitate, the frustules being implanted upon a common stem (fig. 401), which keeps them in mutual connection after they have themselves undergone a complete binary division; (*c*) united in a filament,

[1] According to this observer (*Ann. of Nat. Hist.* 2nd series, vol. xv. 1855, p. 36) *Navicula bifrons* forms, by the spontaneous fission of its internal substance, spherical bodies, which, like gemmules, give rise to *Surirella microcora*. These by conjugation produce *N. splendida*, which gives rise to *N. bifrons* by the same process. He is only able to speak positively, however, as to the production of *N. bifrons* from *N. splendida*; that of *Surirella microcora* from *N. bifrons*, and that of *N. splendida* from *Surirella microcora*, being matters of inference from the phenomena witnessed by him.

[2] The method of Kützing was the one followed, with some modification, by Mr. Ralfs in his revision of the group for the fourth edition of Pritchard's *Infusoria*; and to his systematic arrangement the Author would refer such as desire more detailed information.

which will be continuous (fig. 396 A, B,) if the cohesion extend to the entire surfaces of the sides of the frustules, but may be a mere zigzag chain (fig. 402) if the cohesion be limited to their angles; (*d*) aggregated into a frond (fig. 415), which consists of numerous frustules more or less regularly enclosed in a gelatinous investment.

Commencing with the last-named division (A), the first family is that of *Eunotieæ*, of which we have already seen a characteristic example in *Epithemia turgida* (fig. 397). The essential characters of this family consist in the more or less lunate form of the frustules in the lateral view (fig. 397, B), and in the striæ being continuous across the valves without any interruption by a longitudinal line. In the genus *Eunotia* the frustules are free; in *Epithemia* they are very commonly adherent by the flat or concave surface of the connecting zone; and in *Himantidium* they are usually united into ribbon-like filaments. In the family *Meridieæ* we find a similar union of the transversely striated individual frustules; but these are narrower at one end than at the other, so as to have a cuneate or wedge-like form, and are regularly disposed with their corresponding extremities always pointing in the same direction, so that the filament is curved instead of straight, as in the beautiful *Meridion circulare* (fig. 399). Although this plant, when gathered and placed under the microscope, presents the appearance of circles overlying one another, it really grows in a helicoid (screw-like) form, making several continuous turns. This diatom abounds in many localities in this country; but there is none in which it presents itself in such rich luxuriance as in the mountain-brooks about West Point in the United States, the bottoms of which, according to Professor Bailey, 'are literally covered in the first warm days of spring with a ferruginous-coloured mucous matter, about a quarter of an inch thick, which, on examination by the microscope, proves to be filled with millions and millions of these exquisitely beautiful siliceous bodies. Every submerged stone, twig, and spear of grass is enveloped by them, and the waving plume-like appearance of a filamentous body covered in this way is often very elegant.' The frustules of *Meridion* are attached when young to a gelatinous cushion; but this disappears with the advance of age. In the family *Licmophoreæ* also the frustules



Fig. 401.—*Licmophora flabellata.*

are wedge-shaped; in some genera they have transverse markings, whilst in others these are deficient; but in most instances there are to be observed two longitudinal suture-like lines on each valve (which have received the special designation of *vittæ*) connecting their two extremities. The newly formed part of the stipe in the genus *Licmophora*, instead of itself becoming double with each act of binary division of the frustule, increases in breadth, while the frustules themselves remain coherent, so that a beautiful fan-like arrangement is produced (fig. 401). A splitting away of a few frustules seems occasionally to take place, from one side or the other, before the elongation of the stipe; so that the entire plant presents us with a more or less complete *flabella* or fan upon the summit of the branches, with imperfect flabellæ or single frustules irregularly scattered throughout the entire length of the footstalk. This beautiful plant is marine, and is attached to seaweeds and zoöphytes.



Fig. 402. Fig. 403.

Fig. 402.—*Diatoma vulgare*: *a*, side view of frustule; *b*, frustule undergoing division.

Fig. 403.—*Grammatophora serpentina*: *a*, front and side views of single frustule; *b*, *b*, front and end views of divided frustule; *c*, frustule about to undergo division; *d*, frustule completely divided.

In the next family, that of *Fragilariæ*, the frustules are of the same breadth at each end, so that if they unite into a filament they form a straight band. In some genera they are smooth, in others transversely striated, with a central nodule: when striæ are present, they run across the valves without interruption. To this family belongs the genus *Diatoma*, which gives its name to the entire group, that name (which means cutting through) being suggested by the curious habit of the genus, in which the frustules, after division, separate from each other along their lines of junction, but remain connected at their angles, so as to form zigzag chains (fig. 402). The valves of *Diatoma*, when turned sideways (*a*), are seen to be strongly marked by transverse striæ, which extend into the front view. The proportion between the length and the breadth of each valve is found to vary so considerably that, if the extreme forms only were compared, there would seem adequate ground for regarding them as belonging to different species. The genus inhabits fresh water, preferring gently running streams, in which it is sometimes very abundant. The genus *Fragilaria* is nearly allied to *Diatoma*, the difference

between them consisting chiefly in the mode of adhesion of the frustules, which in *Fragilaria* form long, straight filaments with parallel sides; the filaments, however, as the name of the genus implies, very readily break up into their component frustules, often separating at the slightest touch. Its various species are very common in pools and ditches. This family is connected with the next by the genus *Nitzschia*, which is a somewhat aberrant form, distinguished by the presence of a prominent keel on each valve, dividing it into two portions which are usually unequal, while the entire valve is sometimes curved, as in *N. sigmoidea*, which has been used as a test object, but is not suitable for that purpose on account of the extreme variability of its striation. Nearly allied to this is the genus *Bacillaria*, so named from the elongated staff-like form of its frustules; its valves have a longitudinal punctated keel, and their transverse striæ are interrupted in the median line. The principal species of this genus is the *B. paradoxa*, whose remarkable movement has been already described. Owing to this displacement of the frustules, its filaments seldom present themselves with straight parallel sides, but nearly always in forms more or less oblique, such as those represented in fig. 400. This curious object is an inhabitant of salt or of brackish water. Many of the species formerly ranked under this genus are now referred to the genus *Diatoma*. The genera *Nitzschia* and *Bacillaria* have been associated by Mr. Ralfs[1] with some other genera which agree with them in the bacillar or staff-like form of the frustules and in the presence of a longitudinal keel, in the sub-family *Nitzschieæ*, which ranks as a section of the *Surirelleæ*. Another sub-family, *Synedreæ*, consists of the genus *Synedra* and its allies, in which the bacillar form is retained, but the keel is wanting, and the valves are but little broader than the front of the frustule.



FIG. 404.—*Surirella constricta*: A, side view; B, front view; C, binary subdivision.

In the *Surirelleæ* proper the frustules are no longer bacillar, and the breadth of the valves is usually (though not always) greater than the front view. The distinctive character of the genus *Surirella*, in addition to the presence of the supposed 'canaliculi,' is derived from the longitudinal line down the centre of each valve (fig. 404, A) and the prolongation of the margins into 'alæ.' Numerous species are known, which are mostly of a somewhat ovate form,

[1] See Pritchard's *Infusoria*, 4th ed. p. 940. The genus *Nitzschia* was in the first instance placed by Mr. Ralfs in the family *Fragilarieæ*, and the genus *Bacillaria* in the family *Surirelleæ*.

some being broader and others narrower than *S. constricta*; the greater part of them are inhabitants of fresh or brackish water, though some few are marine; and several occur in those infusorial earths which seem to have been deposited at the bottoms of lakes, such as that of the Mourne Mountains in Ireland (fig. 419, *b*, *c*, *k*). In the genus *Campylodiscus* (fig. 405) the valves are so greatly increased in breadth as to present almost the form of discs (A), and at the same time have more or less of a peculiar twist or saddle-shaped curvature (B). It is in this genus that the supposed 'canaliculi' are most developed, and it is consequently here that they may be best studied; and of there being here really *costæ*, or internally projecting ribs, no reasonable doubt can remain after examination of them under the binocular microscope, especially with the 'black-ground' illumination. The form of the valves in most of the species is circular or nearly so; some are nearly flat, whilst in others the twist is greater than in the species here represented. Some of the species are marine, whilst others occur in fresh water; a very beautiful form, the *C. clypeus*, exists in such abundance in the



FIG. 405.—*Campylodiscus costatus*: A, front view; B, side view.

infusorial stratum discovered by Professor Ehrenberg at Soos, near Ezer, in Bohemia, that the earth seems almost entirely composed of it.

The next family, *Striatellæ*, forms a very distinct group, differentiated from every other by having longitudinal costæ on the connecting portions of the frustules, these costæ being formed by the inward projection of annular siliceous plates (which do not, however, reach to the centre), so as to form septa dividing the cavity of the cell into imperfectly separated chambers. In some instances these annular septa are only formed during the production of the valves in the act of division, and on each repetition of such production, being thus always *definite* in number; whilst in other cases the formation of the septa is continued after the production of the valves, and is repeated an uncertain number of times before the recurrence of a new valve-production, so that the annuli are *indefinite* in number. In the curious *Grammatophora serpentina* (fig. 403) the septa have several undulations and incurved ends, so as to form serpentine curves, the number of which seems to vary with the length of the frustule. The lateral surfaces of the valves in

natophora are very finely striated, and some species, as *G.*
ssima and *G. marina*, are used as test-objects. The frustules
st of the genera of this family separate into zigzag chains, as
toma; but in a few instances they cohere into a filament, and
ore rarely they are furnished with a stipe. The small family
noëæ was separated by Mr. Ralfs from the *Striatellæ*, with
it is nearly allied in general characters, because its septa
in the latter are longitudinal and divide the central portions
hambers) are transverse, and are confined to the lateral portions
frustules, which appear in the front view as in *Biddulphieæ*.
pical form of this family is the *Terpsinoë musica*, so named
the resemblance which the markings of its costæ bear to
l notes.

e next come to two families in which the lateral surfaces of
ustules are *circular*; so that, according to the flatness or
city of the valves and the breadth of the intervening hooped
the frustules may have the form either of thin discs, short
ers, bi-convex lenses, oblate spheroids, or even of spheres.
ng at the structure of the individual frustules, the line of
cation between these two families, *Melosireæ* and *Coscino-*
, is by no means distinct, the principal difference between
being that the valves of the latter are commonly areolated,
those of the former are smooth. Another important differ-
owever, lies in this, that the frustules of the *Coscinodisceæ*
vays free, whilst those of the *Melosireæ* remain coherent into
its, which often so strongly resemble those of the simple
vaceæ as to be readily distinguishable only by the effect of
Of these last the most important genus is *Melosira* (fig. 395).
of its species are marine, others fresh-water; one of the latter,
racea, seems to grow best in boggy pools containing a fer-
us impregnation; and it is stated by Professor Ehrenberg that
s up from the water, and incorporates with its own substance,
iderable quantity of iron. The filaments of *Melosira* very
nly fall apart at the slightest touch, and in the infusorial
in which some species abound the frustules are always
detached (fig. 419, *a*, *a*, *d*, *d*). The meaning of the remarkable
ice in the sizes and forms of the frustules of the same
its (fig. 395) has not yet been fully ascertained. The sides of
lves are often marked with radiating striæ (fig. 419, *d*, *d*);
some species they have toothed or serrated margins, by which
stules lock together. To this family belongs the genus *Hyalo-*
of which *H. subtilis* was first brought into notice by the
ofessor Bailey as a test-object, its disc being marked, like the
-turned back of a watch, with lines of exceeding delicacy,
sible by good objectives and careful illumination.

family *Coscinodisceæ* includes a large proportion of the most
ul of those discoidal diatoms of which the valves do not
any considerable convexity, and are connected by a narrow
The genus *Coscinodiscus*, which is easily distinguished from
the genera of this family by not having its disc divided into
tments, is of great interest from the vast abundance of its

valves in certain fossil deposits (fig. 418, *a*, *a*, *a*), especially the infusorial earth of Richmond in Virginia, of Bermuda, and of Oran, as also in guano. Each frustule is of discoidal shape, being composed of two delicately undulating valves united by a hoop; so that if the frustules remain in adhesion, they would form a filament resembling that of *Melosira* (fig. 395, B). The regularity of the hexagonal areolation shown by its valves renders them beautiful microscopic objects: in some species the areolæ are smallest near the centre, and gradually increase in size towards the margin; in others a few of the central areolæ are the largest, and the rest are of nearly uniform size; while in others, again, there are radiating lines formed by areolæ of a size different from the rest. Most of the species are either marine or are inhabitants of brackish water; when living they are most commonly found adherent to sea-weeds or zoöphytes; but when dead the valves fall as a sediment to the bottom of the water. In both these conditions they were found by



FIG. 406.—Structure of siliceous valve of *Coscinodiscus oculus iridis*: 1, hexagonal areola of inner or 'eye-spot' layer; 2, areola of outer layer.

Professor J. Quekett in connection with zoöphytes which had been brought home from Melville Island by Sir E. Parry; and the species seem to be identical with those of the Richmond earth. The investigations of Mr. J. W. Stephenson[1] on *Coscinodiscus oculus iridis* show that the peculiar 'eye-like' appearance in the centre of each of its hexagonal areolæ arises from the intermingling of the markings of two distinct layers, differing considerably in structure, the markings of the lower layer being partially seen through those of the upper. By fracturing these diatoms Mr. Stephenson succeeded in separating portions of the two layers, so that each could be examined singly. He also mounted them in bisulphide of carbon, the refractive index of which is high; and also in a solution of phosphorus in bisulphide of carbon, which has a still higher refractive index. If we suppose a diatom to be marked with *convex depressions*, they would act as concave lenses in air, which is less refractive than their own silex; but when such lenses are immersed in bisulphide of carbon, or in the phosphorus solution, they would be converted into *convex lenses* of the more refractive substance, and have their action in air reversed. Analogous but

[1] *Monthly Microscopical Journal*, vol. x. 1873, p. 1.

opposite changes must take place when convex diatom-lenses are viewed first in air, and then in the more refractive media. Applying these and others tests to *Coscinodiscus oculus iridis*, Mr. Stephenson considered both layers to be composed of hexagons, represented in fig. 406, from drawings by Mr. Stewart. The upper layer is much stronger and thicker than the lower one, and the framework of its hexagons more readily exhibits its beaded appearance. The lower layer is nearly transparent, and little conspicuous when seen in bisulphide of carbon, except as shown in the figure, when the framework of the hexagons and the rings in the midst of them appear thickened and more refractive. In both layers the balance of observations tends to the belief that the hexagons have no floors, and are in fact perforated by foramina like those of minute polycystina. The cells formed by the hexagons of the upper layer are of considerable depth; those of the lower layer are shallower. It is very desirable that living forms of *Coscinodisci* should be carefully examined; since, if they really have foramina, some minute organs may be protruded through them.

The genus *Actinocyclus*[1] closely resembles the preceding in form, but differs in the markings of its valvular discs, which are minutely and densely punctated or areolated, and are divided radially by single or double dotted lines, which, however, are not continuous but interrupted. The discs are generally iridescent; and, when mounted in balsam, they present various shades of brown, green, blue, purple, and red; blue or purple, however, being the most frequent. An immense number of species have been erected by Professor Ehrenberg on minute differences presented by the rays as to number and distribution; but since scarcely two specimens can be found in which there is a perfect identity as to these particulars, it is evident that such minute differences between organisms otherwise similar are not of sufficient account to serve for the separation of species. This form is very common in guano from Ichaboe. Allied to the preceding are the two genera *Asterolampra* and *Asteromphalus*, both of which have circular discs of which the marginal portion is minutely areolated, whilst the central area is smooth and perfectly hyaline in appearance, but is divided by lines into radial compartments which extend from the central umbilicus towards the periphery. The difference between them simply consists in this, that in *Asterolampra* all the compartments are similar and equidistant and the rays equal, whilst in *Asteromphalus* (Pl. I, fig. 3) two of the compartments are closer together than the rest, and the enclosed hyaline ray (which is distinguished as the median or basal ray) differs in form from the others, and is sometimes specially continuous with the umbilicus. The eccentricity thus produced in the other rays has been made the basis of another generic designation, *Spatangidium*; but it may be doubted whether this is founded on a valid distinction.[2] These

[1] The Author concurs with Mr. Ralfs in thinking it preferable to limit the genus *Actinocyclus* to the forms originally included in it by Ehrenberg, and to restore the genus *Actinoptychus* of Ehrenberg, which had been improperly united with *Actinocyclus* by Professors Kützing and W. Smith.

[2] See Greville in *Quart. Journ. Microsc. Science*, vol. vii. 1859, p. 158; and in *Trans. Microsc. Soc.* vol. viii. n.s. 1860, p. 102, and vol. x. 1862, p. 41; also Wallich in the same *Transactions*, vol. viii. 1860, p. 44.

beautiful discs are for the most part obtainable from guano, and from soundings in tropical and antarctic seas. From these we pass on to the genus *Actinoptychus* (fig. 407), of which also the frustules are discoidal in form, but in which each valve, instead of being flat, has an undulating surface, as is seen in front view (B), giving to the side view (A) the appearance of being marked by radiating bands. Owing to this peculiarity of shape, the whole surface cannot be brought into focus at once except with a low power; and the difference of aspect which the different radial divisions present in fig. 407 is simply due to the fact that one set is out of focus whilst the other is in it, since the appearances are reversed by merely altering the focal adjustment. The *number* of radial divisions has been considered a character of sufficient importance to serve for the distinction of species; but this is probably subject to variation; since we not unfrequently meet with discs, of which one has (say) eight, and another ten such divisions, but which are precisely alike in every other particular. The valves of this genus also are very abundant in the infusorial earth of Richmond, Bermuda, and Oran (fig. 418, *b*, *b*, *b*), and many of the same species have been found in guano and in the seas of various parts of the world. The frustules in their living state appear to be generally attached to sea-weeds or zoöphytes.



FIG. 407.—*Actinoptychus undulatus*: A, side view; B, front view.

The Bermuda earth also contains the very beautiful form which, though scarcely separable from *Actinoptychus* except by its marginal spines, has received from Professor Ehrenberg the distinctive appellation of *Heliopelta* (sun-shield). The object is represented as seen on its *internal* aspect by the parabolic illuminator, which brings into view certain features that can scarcely be seen by ordinary transmitted light. Five of the radial divisions are seen to be marked out into circular areolæ; but in the five which alternate with them a minute beaded structure is observable. This may be shown, by careful adjustment of the focus, to exist over the whole interior of the valve, even on the divisions in which the circular areolation is here displayed; and it hence appears probable that this marking belongs to the *internal* layer,[1] and that the circular areolation exists in the *outer* layer of the silicified valves. In the alternating divisions whose surface is here displayed, the areolation of the outer layer, when brought into view by focussing down to it, is seen to be formed by equilateral triangles; it is not, however, nearly so well marked as the circular areolation of the first-mentioned divisions. The dark spots seen at the end of the rays, like the

[1] It is stated by Mr. Stodder (*Quart. Journ. Microsc. Science*, vol. iii. n.s. 1863, p. 215) that not only has he seen, in broken specimens, the inner granulated plate projecting beyond the outer, but that he has found the inner plate altogether separated from the outer. The Author is indebted to this gentleman for pointing out that his figure represents the *inner* surface of the valve.

dark centre, appear to be solid areolations of silex not traversed by markings, as in many other diatoms; they are apparently *not* orifices, as supposed by Professor Ehrenberg. Of this type, again, specimens are found presenting six, eight, ten, or twelve radial divisions, but in other respects exactly similar; on the other hand, two specimens agreeing in their number of divisions may exhibit minute differences of other kinds; in fact, it is rare to find two that are *precisely* alike. It seems probable, then, that we must allow a considerable latitude of variation in these forms before attempting to separate any of them as distinct species. Another very beautiful discoidal diatom, which occurs in guano, and is also found attached to sea-weeds from different parts of the world (especially to a species employed by the Japanese in making soup), is the *Arachnoidiscus* (Plate XII), so named from the resemblance which the beautiful markings on its disc cause it to bear to a spider's web. According to Mr. Shadbolt,[1] who first carefully examined its structure, each valve consists of two layers: the outer one, a thin flexible horny membrane, indestructible by boiling in nitric acid; the inner one siliceous. It is the former which has upon it the peculiar spider's web-like markings; whilst it is the latter that forms the supporting framework which bears a very strong resemblance to that of a circular Gothic window. The two can occasionally be separated entire by first boiling the discs for a considerable time in nitric acid and then carefully washing them in distilled water. Even without such separation, however, the distinctness of the two layers can be made out by focussing for each separately under a $\frac{1}{4}$- or $\frac{1}{5}$-inch objective; or by looking at a valve as an opaque object (either by the parabolic illuminator, or by the Lieberkühn, or by a side light) with a $\frac{1}{10}$-inch objective, first from one side and then from the other. But it can be seen to very best advantage by the use of apochromatic objectives of suitable power and a suitable diaphragm for *dark-ground* illumination.[2]

This family is connected with the succeeding by the small group *Eupodisceæ*, the members of which agree with the *Coscinodisceæ* in the general character of their discoid frustules, and with the *Biddulphieæ* in having areolar processes on their lateral surfaces. In the beautiful *Aulacodiscus* these areolations are situated near the margin, and are connected with bands radiating from the centre; the surface also is frequently inflated in a manner that reminds us of *Actinoptychus*. These forms are for the most part obtained from guano.

The members of the next family, *Biddulphieæ*, differ greatly in their general form from the preceding, being remarkable for the great development of the lateral valves, which, instead of being nearly flat or discoidal, so as only to present a thin edge in front view, are so convex or inflated as always to enter largely into the front view, causing the central zone to appear like a band between

[1] *Trans. Microsc. Society*, 1st series, vol. iii. p. 49.

[2] These valves afford admirable objects for showing the 'conversion of relief' in Nachet's stereo-pseudoscopic microscope (p. 97).

them. This band is very narrow when the new frustules are first produced by binary division, but it increases gradually in breadth, until the new frustule is fully formed and is itself undergoing the same duplicative change. In *Biddulphia* (fig. 396) the frustules have a quadrilateral form, and remain coherent by their alternate angles (which are elongated into tooth-like projections), so as to form a zigzag chain. They are marked externally by ribbings which seem to be indicative of internal *costæ* partially subdividing the cavity. Nearly allied to this is the beautiful genus *Isthmia* (fig. 408), in which the frustules have a trapezoidal form owing to the oblique prolongation of the valves; the lower angle of each frustule is coherent to the middle of the next one beneath, and from the basal frustule proceeds a stipe by which the filament is attached. Like the preceding, this genus is marine, and is found attached to the sea-weeds of our own shores. The areolated structure of its surface is very conspicuous both in the valves and in the connecting 'hoop'; and this hoop, being silicified, not only connects the two new frustules (as at *b*, fig. 408), until they have separated from each other, but, after such separation, remains for a time round one of the frustules, so as to give it a truncated appearance (*a*, *c*).



Fig. 408.—*Isthmia nervosa.*

The family *Angulifera*, distinguished by the angular form of its valves in their lateral aspect, is in many respects closely allied to the preceding; but in the comparative flattening of their valves its members more resemble the *Coscinodisceæ* and *Eupodisceæ*. Of this family we have a characteristic example in the genus *Triceratium*, of which striking form a considerable number of species are met with in the Bermuda and other infusorial earths, while others are inhabitants of the existing ocean and of tidal rivers. The *T. favus* (fig. 393), which is one of the largest and most regularly marked of any of these, occurs in the mud of the Thames and in various other estuaries on our own coast; it has been found, also, on the surface of large sea-shells from various parts of the world, such as those of *Hippopus* and *Haliotis*, before they have been cleaned; and it presents itself likewise in the infusorial earth of Petersburg (U.S.A.). The projections at the angles which are shown in that species are prolonged in some other species into 'horns'; whilst in others, again, they are mere tubercular elevations. Although the *triangular* form of the frustule, when looked at sideways, is that which is characteristic of the genus, yet in some of the species there seems a tendency to produce *quadrangular* and even *pentagonal* forms, these being marked as *varieties* by their exact correspondence in sculpture, colour, &c. with the normal triangular

forms.[1] This departure is extremely remarkable, since it breaks down what seems at first to be the most distinctive character of the genus; and its occurrence is an indication of the degree of latitude which we ought to allow in other cases. It is difficult, in fact, to distinguish the square forms of *Triceratium* from those included in the genus *Amphitetras*, which is chiefly characterised by the cubiform shape of its frustules. In the latter the frustules cohere at their angles, so as to form zigzag filaments, whilst in the former the frustules are usually free, though they have occasionally been found in chains.

Another group that seems allied to the *Biddulphieæ* is the curious assemblage of forms brought together in the family *Chætocereæ*, some of the filamentous types of which seem also allied to the *Melosireæ*. The peculiar distinction of this group consists in the presence of tubular 'awns,' frequently proceeding from the connecting hoop, sometimes spinous and serrated, and often of great length (fig. 409);



FIG. 409.—*Chætoceros Wighamii*: *a*, front view, and *b*, side view of frustule; *c*, side view of connecting hoop and awns; *d*, entire filament.



FIG. 410.—*Bacteriastrum furcatum*.

by the interlacing of which the frustules are united into filaments whose continuity, however, is easily broken. In the genus *Bacteriastrum* (fig. 410) there are sometimes as many as twelve of these awns, radiating from each frustule like the spokes of a wheel, and in some instances regularly bifurcating. With this group is associated the genus *Rhizosolenia*, of which several species are distinguished by the extraordinary length of the frustule (which may be from six to twenty times its breadth), giving it the aspect of a filament (fig. 411), by a transverse annulation that imparts to this filament a jointed appearance, and by the termination of the frustule at each end in a

[1] See Mr. Brightwell's excellent memoirs 'On the Genus *Triceratium*' in *Quart. Journ. Microsc. Science*, vol. i. 1853, p. 245; vol. iv. 1856, p. 272; vol. vi. 1858, p. 153; also Wallich in the same *Journal*, vol. iv. 1858, p. 242; and Greville in *Trans. Microsc. Soc.* n.s. vol. ix. 1861, pp. 48, 69.

cone, from the apex of which a straight awn proceeds. It is not a little remarkable that the greater number of the examples of this curious family are obtained from the stomachs of Ascidians, Salpæ, Holothuriæ, and other marine animals.[1]

The second principal division (B) of the *Diatomaceæ* consists, it will be remembered, of those in which the frustules have a median longitudinal line and a central nodule. In the first of the families which it includes, that of *Cocconeideæ*, the central nodule is obscure

FIG. 411.—*Rhizosolenia imbricata.*



FIG. 412.—*Achnanthes longipes*: *a*, *b*, *c*, *d*, *e*, frustules in different stages of binary division.

FIG. 413. — *Gomphonema geminatum*: its frustules connected by a dichotomous stipe.

or altogether wanting on one of the valves, which is distinguished as the inferior. This family consists but of a single genus, *Cocconeis*, which includes, however, a great number of species, some or other of them occurring in every part of the globe. Their form is usually that of ellipsoidal discs, with surfaces more or less exactly parallel, plane, or slightly curved; and they are very commonly found adherent to each other. The frustules in this genus are frequently invested by a membranous envelope which forms a border to them; but this

[1] See Brightwell in *Quart. Journ. Microsc. Science*, vol. iv. 1856, p. 105; vol. vi. 1858, p. 93; Wallich in *Trans. Microsc. Soc.* n.s. vol. viii. 1860, p. 48; and West, in the same, p. 151.

to belong to the immature state, subsequently disappearing
r less completely.

other family in which there is a dissimilarity in the two surfaces is that of the *Achnantheæ*, the frustules of which markable for the bend they show in the direction of their , often more conspicuously than in the example here repre-. This family contains free, adherent, and stipitate forms, the most common of the latter being *Achnanthes longipes* 12), which is often found growing on marine algæ. The nce between the markings of the upper and lower valves is istinctly seen; for while both are traversed by striæ, which olvable under a sufficient power into rows of dots, as well as ongitudinal line which sometimes has a nodule at each end *Navicula*), the lower valve (*a*) has also a transverse line, form-*tauros*, or cross, which is wanting in the upper valve (*e*). A ence of the connecting membrane, so as to form an additional tion between the may sometimes be ed in this genus; in fig. 412 it not olds together the ew frustules resul- from the subdivi- the lowest cell, *a*, are not yet com- separated the one he other, but it may erved to invest the stules *b* and *c*, which ot merely separated, e themselves begin- undergo binary sub- n; and it may also



FIG. 414.—*Gomphonema geminatum*, more highly magnified: A, side view of frustule; B, front view; C, frustule in the act of division.

ceived to invest the frustule *d*, from which the frustule *e*, being minal one, has more completely freed itself.

the family *Cymbelleæ*, on the other hand, both valves possess ngitudinal line with a nodule in the middle of its length; but lves have the general form of those of the *Eunotieæ*, and the ; so much nearer one margin than the other that the nodule etimes rather marginal than central, as we see in *Cocconema* 19, *f*).

e *Gomphonemeæ*, like the *Meridieæ* and *Licmophoreæ*, have les which are cuneate or wedge-shaped in their front view (figs. 14), but are distinguished from those forms by the presence of ngitudinal line and central nodule. Although there are some orms in this family, the greater part of them, included in the *Gomphonema*, have their frustules either affixed at their bases ached to a stipe. This stipe seems to be formed by an exu- from the frustule, which is secreted only during the process ary division; hence, when this process has been completed, the ion of the single filament below the frustules ceases; but when

it recommences a sort of joint or articulation is formed, from which a new filament begins to sprout for each of the half-frustules; and when these separate, they carry apart the peduncles which support them as far as their divergence can take place. It is in this manner that the dichotomous character is given to the entire stipe (fig. 413). The species of *Gomphonema* are, with few exceptions, inhabitants of fresh water, and are among the commonest forms of *Diatomaceæ*.

Lastly, we come to the large family *Naviculeæ*, the members of which are distinguished by the symmetry of their frustules, as well in the lateral as in the front view, and by the presence of a median longitudinal line and central nodule in both valves. In the genus *Navicula* and its allies the frustules are free or simply adherent to each other; while in another large section they are included within a gelatinous envelope, or are enclosed in a definite tubular or gelatinous frond. Of the genus *Navicula* an immense number of species have been described, the grounds of separation being often extremely trivial. Those which have a lateral sigmoid curvature have been separated by Mr. W. Smith under the designation *Pleurosigma*, which is now generally adopted: but his separation of another set of species under the name *Pinnularia* (which had been previously applied by Ehrenberg to designate the striated species), on the ground that its striæ (costæ) are not resolvable into dots, was not considered valid by Mr. Ralfs, because in many of the more minute species it is impossible to distinguish with certainty between striæ and costæ. Mr. Slack has since given an account of the resolution of the so-called costæ of twelve species of *Pinnulariæ* into 'beaded' structures.[1] The beautiful genus *Stauroneis*, which belongs to the same group, differs from all the preceding forms in having the central nodule of each valve dilated laterally into a band free from striæ, which forms a cross with the longitudinal band. The multitudinous species of the genus *Navicula* are for the most part inhabitants of fresh water; and they constitute a large part of most of the so-called 'infusorial earths' which were deposited at the bottoms of lakes. Among the most remarkable of such deposits are the substances largely used in the arts for the polishing of metals, under the names of Tripoli and rotten-stone; these consist in great part of the frustules of *Naviculæ* and *Pinnulariæ*. The Polierschiefer, or 'polishing slate,' of Bilin in Bohemia, the powder of which is largely used in Germany for the same purpose, and which also furnishes the fine sand used for the most delicate castings in iron, occurs in a series of beds averaging fourteen feet in thickness, and these present appearances which indicate that they have been at some time exposed to a high temperature. The well-known 'Turkey-stone,' so generally employed for the sharpening of edge-tools, seems to be essentially composed of a similar aggregation of frustules of *Naviculæ* &c. which have been consolidated by heat. The species of *Pleurosigma*, on the other hand, are for the most part either marine or are inhabitants of brackish water, and they comparatively seldom present themselves in a fossilised state. Of *Stauroneis* some species inhabit fresh water, while others are marine; and the former present themselves frequently in certain 'infusorial earths.'

[1] *Monthly Microscopical Journal*, vol. vi. 1871, p. 71.

Of the members of the sub-family *Schizonemeæ*, consisting of those *Naviculeæ* in which the frustules are united by a gelatinous envelope, some are remarkable for the great external resemblance they bear to acknowledged algæ. This is especially the case with the genus *Schizonema*, in which the gelatinous envelope forms a regular tubular frond, more or less branched, and of nearly equal diameter throughout, within which the frustules lie either in single file or without any definite arrangement (fig. 415), all these frustules having arisen from the binary division of one individual. In the genus *Mastogloia*, which is specially distinguished by having the annulus furnished with internal costæ projecting into the cavity of the frustule, each frustule is separately supported on a gelatinous cushion (fig. 416, B), which may itself be either borne on a branching stipe



FIG. 415.—*Schizonema Grevillii*: A, natural size; B, portion magnified five diameters; C, filament magnified 100 diameters; D, single frustule.

(A), or may be aggregated with others into an indefinite mass (fig. 417). The careful study of these composite forms is a matter of great importance, since it enables us to bring into comparison with each other great numbers of frustules which have unquestionably a common descent, and which must therefore be accounted as of the same species, and thus to obtain an idea of the *range of variation* prevailing in this group, without a knowledge of which specific definition is altogether unsafe. Of the very strongly marked varieties which may occur within the limits of a single species, we have an example in the valves C, D, E, F (fig. 416), which would scarcely have been supposed to belong to the same specific type did they not occur upon the same stipe. The careful study of these varieties in every instance in which any disposition to variation shows itself, so

as to *reduce* the enormous number of species with which our systematic treatises are loaded, is a pursuit of far greater real value than the *multiplication* of species by the detection of such minute differences as may be presented by forms discovered in newly explored localities; such differences as have already been pointed out being, probably, in a large proportion of cases, the result of the multiplication of some one form, which, under modifying influences that we do not yet understand, has departed from the ordinary type. The more faithfully and comprehensively this study is carried out in *any* department of natural history, the more does it prove that the range

Fig. 416.



Fig. 417.



FIG. 416.—*Mastogloia Smithii*: A, entire stipe; B, frustule in its gelatinous envelope; C–F, different forms of frustule as seen in side view; G, front view; H, frustule undergoing subdivision.
FIG. 417.—*Mastogloia lanceolata*.

of variation is far greater than had been previously imagined; and this is especially likely to be the case with such humble organisms as those we have been considering, since they are obviously more influenced than those of higher types by the conditions under which they are developed; whilst, from the very wide geographical range through which the same forms are diffused, they are subject to very great diversities of such conditions.

The general habits of this most interesting group cannot be better stated than in the words of Mr. W. Smith:—'The *Diatomaceæ* inhabit the sea or fresh water; but the species peculiar to the one are never found in a living state in the other locality;

though there are some which prefer a medium of a mixed nature, and are only to be met with in water more or less brackish. The latter are often found in great abundance and variety in districts occasionally subject to marine influences, such as marshes in the neighbourhood of the sea, or the deltas of rivers, where, on the occurrence of high tides, the freshness of the water is affected by percolation from the adjoining stream, or more directly by the occasional overflow of its banks. Other favourite habitats of the *Diatomaceæ* are stones of mountain streams or waterfalls, and the shallow pools left by the retiring tide at the mouths of our larger rivers. They are not, however, confined to the localities I have mentioned—they are, in fact, most ubiquitous, and there is hardly a roadside ditch, water-trough, or cistern, which will not reward a search and furnish specimens of the tribe.' Such is their abundance in some rivers and estuaries, that their multiplication is affirmed by Professor Ehrenberg to have exercised an important influence in blocking up harbours and diminishing the depth of channels! Of their extraordinary abundance in certain parts of the ocean the best evidence is afforded by the observations of Sir J. D. Hooker upon the *Diatomaceæ* of the southern seas; for within the Antarctic Circle they are rendered peculiarly conspicuous by becoming enclosed in the newly formed ice, and by being washed up in myriads by the sea on to the 'pack' and 'bergs,' everywhere staining the white ice and snow a pale ochreous brown. A deposit of mud, chiefly consisting of the siliceous valves of *Diatomaceæ*, not less than 400 miles long and 120 miles broad, was found at a depth of between 200 and 400 feet on the flanks of Victoria Land in 70° south latitude. Of the thickness of this deposit no conjecture could be formed; but that it must be continually increasing is evident, the silex of which it is in a great measure composed being indestructible. A fact of peculiar interest in connection with this deposit is its extension over the submarine flanks of Mount Erebus, an active volcano of 12,400 feet elevation, since a communication between the ocean waters and the bowels of a volcano, such as there are other reasons for believing to be occasionally formed, would account for the presence of *Diatomaceæ* in volcanic ashes and pumice which was discovered by Professor Ehrenberg. It is remarked by Sir. J. D. Hooker that the universal presence of this microscopic vegetation throughout the South Polar Ocean is a most important feature, since there is a marked deficiency in this region of higher forms of vegetation; and were it not for them, there would neither be food for aquatic animals, nor (if it were possible for these to maintain themselves by preying on one another) could the ocean waters be purified of the carbonic acid which animal respiration and decomposition would be continually imparting to them. It is interesting to observe that some species of marine diatoms are found through every degree of latitude between Spitzbergen and Victoria Land, whilst others seem limited to particular regions. One of the most singular instances of the preservation of diatomaceous forms is their existence in guano, into which they must have passed from the intestinal canals of the birds of whose accumulated excrement that substance is composed, those birds having received them, it

is probable, from shell-fish, to which these minute organisms serve as ordinary food.

The indestructible nature of the silicified casings of *Diatomaceæ* has also served to perpetuate their presence in numerous localities from which their living forms have long since disappeared; for the accumulation of sediment formed by their successive production and death, even on the bed of the ocean or on the bottoms of fresh-water lakes, gives rise to deposits which may attain considerable thickness, and which, by subsequent changes of level, may come to form part of the dry land. Thus very extensive siliceous strata, consisting almost entirely of marine *Diatomaceæ*, are found to alter-

FIG. 418.—Fossil Diatomaceæ &c. from Oran: *a*, *a*, *a*, *Coscinodiscus*; *b*, *b*, *b*, *Actinocyclus*; *c*, *Dictyochya fibula*; *d*, *Lithasteriscus radiatus*; *e*, *Spongolithis acicularis*; *f*, *f*, *Grammatophora parallela* (side view); *g*, *g*, *Grammatophora angulosa* (front view).

nate, in the neighbourhood of the Mediterranean, with calcareous strata chiefly formed of *Foraminifera*, the whole series being the representative of the chalk formation of Northern Europe, in which the silex that was probably deposited at first in this form has undergone conversion into flint, by agencies hereafter to be considered. Of the diatomaceous composition of these strata we have a characteristic example in fig. 418, which represents the fossil *Diatomaceæ* of Oran in Algeria. The so-called 'infusorial earth' of Richmond in Virginia, as well as that of Bermuda, both marine deposits, are very celebrated among microscopists for the number and beauty of the forms they have yielded; the former constitutes a stratum of eighteen feet in thickness, underlying the whole city, and extending over an area whose limits are not known. Several deposits of more limited

ent, and apparently of fresh-water origin, have been found in our
ı islands; as, for instance, at Dolgelly in North Wales, at South
urne in Ireland (fig. 419), and in the island of Mull in Scotland.
ilar deposits in Sweden and Norway are known under the name
ergmehl, or mountain-flour; and in times of scarcity the inha-
nts of those countries are accustomed to mix these substances
h their dough in making bread. This has been supposed merely
have the effect of giving increased bulk to their loaves, so as to
der the really nutritive portion more satisfying; but as the *berg-*
il has been found to lose from a quarter to a third of its weight
exposure to a red heat, there seems a strong probability that it

. 419.—Fossil Diatomaceæ &c. from Mourne Mountains, Ireland: *a*, *a*, *a*, *aillonella* (*Melosira*) *procera* and *G. granulata*; *d*, *d*, *d*, *G. biseriata* (side view); *b*, *Surirella plicata*; *c*, *S. craticula*; *k*, *S. caledonica*; *e*, *Gomphonema gracile*; *Cocconema fusidium*; *g*, *Tabellaria vulgaris*; *h*, *Pinnularia dactylus*; *i*, *P. obilis*; *l*, *Synedra ulna*.

ıtains organic matter enough to render it nutritious in itself.
ıen thus occurring in strata of a fossil or sub-fossil character,
diatomaceous deposits are generally distinguishable as white or
am-coloured powders of extreme fineness.

For collecting fresh *Diatomaceæ* those general methods are to be
l recourse to which have been already described. 'Their living
sses,' says Mr. W. Smith, 'present themselves as coloured fringes
ached to larger plants, or forming a covering to stones or rocks
cushion-like tufts—or spread over their surface as delicate velvet—
depositing themselves as a filmy stratum on the mud, or inter-
ked with the scum of living or decayed vegetation floating on the
face of the water. Their colour is usually a yellowish-brown of a

greater or less intensity, varying from a light chestnut in individual specimens to a shade almost approaching black in the aggregated masses. Their presence may often be detected, without the aid of a microscope, by the absence, in many species, of the fibrous tenacity which distinguishes other plants; when removed from their natural position they become distributed through the water, and are held in suspension by it, only subsiding after some little time has elapsed.' Notwithstanding every care, the collected specimens are liable to be mixed with much foreign matter; this may be partly got rid of by repeated washings in pure water, and by taking advantage, at the same time, of the different specific gravities of the diatoms and of the intermixed substances, to secure their separation. Sand, being the heaviest, will subside first; fine particles of mud, on the other hand, will float after the diatoms have subsided. The tendency of living diatoms to make their way towards the light will afford much assistance in procuring the free forms in a tolerably clean state: for if the gathering which contains them be left undisturbed for a sufficient length of time in a shallow vessel exposed to the sunlight, they may be skimmed from the surface. Marine forms must be looked for upon sea-weeds, and in the fine mud or sand of soundings or dredgings; they are frequently found also, in considerable numbers, in the stomachs of Holothuriæ, Ascidians, and Salpæ, in those of the oyster, scallop, whelk, and other testaceous mollusca, in those of the crab and lobster, and other Crustacea, and even in those of the sole, turbot, and other flat-fish. In fact, the diatom collector will do well to examine the digestive cavity of *any* small aquatic animals that may fall in his way, rare and beautiful forms having been obtained from the interior of *Noctiluca*. The separation of the diatoms from the other contents of these stomachs must be accomplished by the same process as that by which they are obtained from guano or the calcareous 'infusorial earths.' Of this the following are the most essential particulars: The guano or earth is first to be washed several times in pure water, which should be well stirred, and the sediment then allowed to subside for some hours before the water is poured off, since, if it be decanted too soon, it may carry the lighter forms away with it. Some kinds of earth have so little impurity that one washing suffices; but in any case it is to be continued so long as the water remains coloured. The deposit is then to be treated, in a flask or test-tube, with hydrochloric (muriatic) acid, and, after the first effervescence is over, a gentle heat may be applied. As soon as the action has ceased, and time has been given for the sediment to subside, the acid should be poured off and another portion added; and this should be repeated as often as any effect is produced. When hydrochloric acid ceases to act, strong nitric acid should be substituted; and after the first effervescence is over, a continued heat of about 200° F. should be applied for some hours. When sufficient time has been given for subsidence, the acid may be poured off and the sediment treated with another portion; and this is to be repeated until no further action takes place. The sediment is then to be washed until all trace of the acid is removed; and, if there have been no admixture of siliceous

n the earth or guano, this sediment will consist almost entirely *tomaceæ*, with the addition, perhaps, of sponge-spicules. The ıtion of siliceous sand and the subdivision of the entire aggre- ›f diatoms into the larger and the finer kinds, may be accom- d by stirring the sediment in a tall jar of water, and then, it is still in motion, pouring off the supernatant fluid as soon › coarser particles have subsided; this fluid should be set aside, ıs soon as a finer sediment has subsided, it should again be d off; and this process may be repeated three or four times at sing intervals, until no further sediment subsides after the of half an hour. The first sediment will probably contain all ındy particles, with, perhaps, some of the largest diatoms, may be picked out from among them; and the subsequent ents will consist almost exclusively of diatoms, the sizes of will be so graduated that the earliest sediments may be ined with the lower powers, the next with medium powers, the latest will require the higher powers—a separation which ended with great convenience.[1] It sometimes happens that sed diatoms are so strongly united to each other by siliceous ıt as not to be separable by ordinary methods; in this case, lumps of the deposit should be boiled for a short time in a weak ne solution, which will act upon this cement more readily than siliceous frustules; and as soon as the lump is softened, so as to ›le to mud, this must be immediately washed in a large quantity ıter, and then treated in the usual way. If a very weak ne solution does not answer the purpose, a stronger one may e tried. This method, devised by Professor Bailey, has been sed by him with much success in various cases.[2]

e mode of mounting specimens of *Diatomaceæ* will depend the purpose which they are intended to serve. If they can be ed quite fresh, and if it be desired that they should exhibit, as as possible, the appearance presented by the living plants, they l be put up in aqueous media within cement-cells; but if they ›t thus mounted within a short time after they have been ed, about a tenth part of alcohol should be added to the water. e desired to exhibit the stipitate forms in their natural position ent to other aquatic plants, the entire mass may be mounted ıne's medium or in glycerin jelly, in a deeper cell; and such a ation is a very beautiful object for the back-ground illumina- If, on the other hand, the minute structure of the siliceous pes is the feature to be brought into view, the fresh diatoms ›e boiled in nitric or hydrochloric acid, which must then be l off (sufficient time being allowed for the deposit of the

somewhat more complicated method of applying the same principle is described Okeden in the *Quart. Journal Microsc. Science*, vol. iii. 1855, p. 158. thor believes, however, that the method above described will answer every

r other methods of cleaning and preparing diatoms, see *Quart. Journ. of . Science*, vol. vii. 1859, p. 167, and vol. i. n.s. 1861, p. 143; and *Trans. of . Soc.* vol. xi. n.s. 1863, p. 4. A little book entitled *Practical Directions ecting, Preserving, Transporting, Preparing, and Mounting Diatoms* (New 77), containing papers by Professors A. Mead Edwards, Christopher Johnson, nilton L. Smith, will be found to contain much useful information.

residue); and the sediment, after being washed, should be boiled in water with a small piece of soap, whereby the diatoms will be cleansed from the flocculent matter which they often obstinately retain.[1] After a further washing in pure water, they are to be either mounted in balsam in the ordinary manner, or be set up 'dry' on a very thin slide. In order to obtain a satisfactory view of their markings, objectives of very large aperture are required, and all the improvements which have recently been introduced in the construction and mode of using the sub-stage condenser require to be put into practice. But to those who have the time, the will, and the appliances, there is a fine field now open for working, to a far higher point than we have touched at present, the true structure of such diatoms as can be made amenable to the powers possessed by our best recent optical appliances; and for the leisure of a professional or commercial man we know of no more suitable and attractive employment for the microscope. It will often be convenient to mount certain particular forms of *Diatomaceæ* separately from the general aggregate; but, on account of their minuteness, they cannot be selected and removed by the usual means. The larger forms which may be readily distinguished under a simple microscope may be taken up by a camel's-hair pencil which has been so trimmed as to leave two or three hairs projecting beyond the rest. But the smaller can only be dealt with by a single fine bristle or stout sable-hair, which may be inserted into the cleft end of a slender wooden handle: and if the bristle or hair should be split at its extremity in a brush-like manner it will be particularly useful. (Such split hairs may always be found in a shaving brush which has been for some time in use; those should be selected which have their split portions so closely in contact that they appear single until touched at their ends.) When the split extremity of such a hair touches the glass slide, its parts separate from each other to an amount proportionate to the pressure; and, on being brought up to the object, first pushed to the edge of the fluid on the slide, may generally be made to seize it. A very experienced American diatomist, Professor Hamilton Smith, strongly recommends a thread of glass drawn out to capillary fineness and flexibility, by which (he says) the most delicate diatom may be safely taken up and deposited upon a slide damped by the breath. For the selection and transference of diatoms under the compound microscope, recourse may be had to some of the forms of 'mechanical finger' which have been devised by American diatomists.[2]

Phæosporeæ.—The greater number of the sea-weeds exhibit a higher type of organisation than any that has hitherto been described. The old classification of sea-weeds into *Melanosporeæ*, *Rhodosporeæ*, and *Chlorosporeæ*, according as their colouring matter is olive-brown, red, or green, cannot altogether be retained. Under the head of *Phæosporeæ* is now included a very large number of the brown and

[1] See Prof. H. L. Smith in *Amer. Journ. of Microscopy*, vol. v. 1880, p. 257. It is important that the soap should be free from kaolin, silex, or any other insoluble matter.

[2] For a description of those of Prof. Hamilton Smith and Dr. Rezner, see *Journ. of Roy. Microsc. Soc.* vol. ii. 1879, p. 951; and that of Mr. Veeder, vol. iii. 1880, p. 700, of the same Journal.

olive-brown sea-weeds. In ascending this series we shall have to notice a *gradual differentiation* of organs, those set apart for reproduction being in the first place separated from those appropriated to nutrition; while the principal parts of the nutritive apparatus, which are at first so blended into a uniform expansion or *thallus* that no real distinction exists between root, stem, and leaf, are progressively evolved on types more and more peculiar to each respectively, and have their functions more and more limited to themselves alone. Hence we find a 'differentiation,' not merely in the external form of organs, but also in their internal structure, its degree bearing a close correspondence to the degree in which their functions are respectively *specialised* or limited to particular actions. But this takes place by very slow gradations, a change of external form often showing itself before there is any decided differentiation either in structure or function. Thus in the simple *Ulvaceæ*, whatever may be the extent of the thallus, every part has exactly the same structure, and performs the same actions, as every other part, living *for* and *by* itself alone. And though, when we pass to the higher sea-weeds, such as the common *Fucus* and *Laminaria*, we observe a certain foreshadowing of the distinction between root, stem, and leaf, this distinction is very imperfectly carried out, the root-like and stem-like portions serving for little else than the mechanical attachment of the leaf-like part of the plant. There is not yet any departure from the simple *cellular* type of structure, the only modification being that the several layers of cells, where many exist, are of different sizes and shapes, the texture being usually closer on the exterior and looser within, and that the texture of the stem and roots is denser than that of the leaf-like expansions or *fronds*. The cells of the *Phæosporeæ* contain a substance closely resembling starch, and an olive-brown pigment, which they share with the *Fucaceæ*, known as *phycophæin*. The group of olive-green sea-weeds presents us with the lowest type in the family *Ectocarpaceæ*, which, notwithstanding, contains some of the most elegant structures that are anywhere to be found in the group, the full beauty of which can only be discerned by the microscope. Such is the case, for example, with *Sphacelaria*, a small and delicate sea-weed, which is very commonly found growing upon larger algæ, either near low-water mark or altogether submerged, its general form being remarkably characterised by a symmetry that extends also to the individual branches, the ends of which, however, have a decayed look that seems to have suggested the name of the genus (from the Greek σφάκελος, gangrene). This apparent decay possibly consists in the resolution of the endochrome of the terminal cells into motile biciliated antherozoids, which, when mature, escape by an opening with a long tubular neck, which forms itself in the wall of the *sphacele*. The same happens with the terminal cells of the peculiar lateral branchlets, which are known as propagative buds. Janczewski, however, believes that these so-called antherozoids are really the zoöspores of parasitic fungi, belonging to the family *Chytridiaceæ*, with which the sphaceles of the *Sphacelariaceæ* are liable to be infested. It is doubtful whether there is any true process of sexual reproduction in

the *Sphacelariaceæ*. The ordinary mode of propagation of the *Phæosporeæ* is by non-sexual zoöspores; and these are of two kinds, produced respectively in unilocular and multilocular zoösporanges. The former are comparatively large, nearly spherical, ovoid or pear-shaped cells, the contents of which break up into a large number of zoöspores. The multilocular zoösporanges have the appearance of jointed hairs, and are divided internally into a number of chambers, each of which gives birth to a single zoöspore. The zoöspores from the unilocular sporanges appear in all cases to germinate directly, while those from the multilocular sporanges sometimes coalesce in pairs before germinating. The different families of *Phæosporeæ* present a most interesting gradual transition from the conjugation of swarm-cells to the impregnation of a female 'oösphere' by male antherozoids. In *Ectocarpus*, *Giraudia*, and *Scytosiphon*, conjugation takes place between swarm-cells from the multilocular sporanges which appear to be exactly alike, but a slight differentiation is exhibited in one of them coming to rest and partially losing its cilia before conjugation takes place (fig. 420, II). In *Cutleria* and *Zanardinia* the differentiation is more complete. The male and female swarm-cells are produced either on the same or on different individuals; the latter are much larger than the former, and come perfectly to rest, entirely losing their cilia before being impregnated by the former. In *Dictyota* the differentiation is carried still further, and the female reproductive bodies are true 'oöspheres,' being from the first motionless masses of protoplasm not provided with cilia. In the family *Laminariaceæ*, belonging to the *Phæosporeæ*, are included many of the largest of the sea-weeds, chiefly natives of southern seas, the frond often attaining enormous dimensions, and exhibiting rudimentary differentiation into rhizoids or organs of attachment, stem, and leaves. Such are *Lessonia*, which grows to a great height and resembles a branching tree with pendent leaves two or three feet long; *Macrocystis*, where the stalk-like base of each branch of the leaf is hollowed out into a large pear-shaped air-bladder; *Nereocystis*, *Laminaria*, and others.



FIG. 420.—Process of conjugation in *Ectocarpus siliculosus*. (From Vines's 'Physiology.')

In the **Fucaceæ** the generative apparatus is contained in the globular 'conceptacles,' which are usually sunk in the tissue near the extremities of the fronds. In some species, as *Fucus platycarpus*, the same conceptacles contain both 'antherids' and 'oögones'; in others these two sexual elements are disposed in different conceptacles on the same plant; whilst in the commonest of all, *F. vesiculosus* (bladder-wrack), they are limited to different individuals. When a section

nade through one of the flattened conceptacles of *F. platycarpus*, interior is seen to be a nearly globular cavity (fig. 421), lined h hairs, some of which are greatly elongated, so as to project ough the pore by which the cavity opens on the surface. Among se are to be distinguished, towards the period of their maturity, tain filaments (fig. 422, A), the *antherids*, whose granular contents uire an orange hue, and gradually shape themselves into oval ies (B), each with an orange-coloured spot and two long ratile cilia, which, when discharged by the rupture of the con- ining cell, have for a time a rapid, undulatory motion whereby



421.—Vertical section of conceptacle of *Fucus platycarpus* lined with filaments, among which lie the antheridial cells and the oögones containing oöspheres.

se 'antherozoids' are diffused through the surrounding liquid. ing amidst the mass of hairs, near the walls of the cavity, are n (fig. 421) numerous dark pear-shaped bodies, which are the *ones*, or parent-cells of the 'oöspheres.' Each of these oögones es origin, by binary subdivision, to a cluster of eight 'germ-cells' öspheres; and these are liberated from their envelopes before the of fertilisation takes place. This act consists in the swarming the antherozoids over the surface of the oöspheres, to which they mmunicate a rotatory motion by the vibration of their own cilia. the hermaphrodite *Fuci* this takes place within the conceptacles,

and *Ptilota*, are extremely beautiful objects for low powers when mounted in glycerin jelly. In many of them the phenomenon to which we have previously referred under the name of 'continuity of protoplasm' is very beautifully exhibited. The colour of the red sea-weeds is due to the presence of a pigment known as *rhodospermin* or *phyco-erythrin*, soluble in water, which may be separated in the form of beautiful regular crystals.

The only mode of propagation which was until recently known to exist in this group of sea-weeds is the production and liberation of 'tetraspores' (fig. 423, B), formed by two successive binary subdivisions of the contents of special cells, which sometimes form part of the general substance of the frond, but sometimes congregate in particular parts or are restricted to special branches.



FIG. 424.—*Nemalion multifidum*: I, a branch with a carpogone, *c*, and pollinoids *sp*; II, III, commencement of the formation of the fructification; IV, V, development of the spore-cluster; *t*, denotes the trichogyne, *c* the carpogone and fructification. (From Goebel's 'Outline of Classification.' The Clarendon Press.

If the second binary division takes place in the same direction as the first, the tetraspores are arranged in linear series; but if its direction is transverse to that of the first, the four spores cluster together. These, when separated by the rupture of their envelope, do not comport themselves as 'zoöspores'; but, being destitute of propulsive organs, are passively dispersed by the motion of the sea itself. Their production, however, taking place by simple cell-division, and not being the result of any form of sexual conjunction, the 'tetraspores' of the *Florideæ* must be regarded, like the 'zoöspores' of the *Ulvaceæ*, as *gonids* analogous rather to the *buds* than to the *seeds* of higher plants. It is now known that a true generative process takes place in this group; but the sexual organs

re not usually found on the plants which produce tetraspores; so hat there would appear to be an alternation between the two modes f propagation. Antheridial cells are found, sometimes on the eneral surface of the frond, more commonly at the ends of branches, nd occasionally in special conceptacles. Their contents, however, re not motile 'antherozoids,' but minute rounded particles, known s *pollinoids*, having no power of spontaneous movement. Some- imes on the same individuals as the antherids, and sometimes on ifferent ones, are produced the female organs, which curiously refigure the pistil in flowering plants. This organ is known as he *procarp*, and consists, in its simplest form, e.g. in *Porphyra*, the 'purple laver,' of a single cell with a lateral hair-like appendage, the *trichogyne*. In the higher forms it is composed of one or more fertile cells constituting the *carpogone*, and one or more sterile cells which make up the *trichophore*, and convey the fertilising substance from the trichogyne to the carpogone. Fertilisation is effected by the attachment of one of the pollinoids to the trichogyne, the walls of which are absorbed at that spot, so that the fertilising material passes down its tube to the trichophore, and thence to the carpogone; one of the cells of the carpogone contains the oösphere, which, after fertilisation, breaks up into a number of *carpospores*; round these is frequently formed a hard investment, and this structure is then known as a *cystocarp*; from it the carpospores ultimately escape, and then germinate. In the true *Corallines*, which are *Florideæ* whose tissue is consolidated by calcareous deposit, not only the tetraspores, but also both kinds of sexual organ, are produced in cavities or *conceptacles*, imbedded in the thallus or forming wart-like swellings; the female conceptacle opens by a terminal orifice or 'ostiole'; the pollinoids are furnished with wing-like appendages. In a considerable number of the red sea-weeds, as, for example, in *Dudresnaya*, the process of fertilisation is more complex than this, and consists of two distinct stages. First, the trichogyne is impregnated by the pollinoids; and secondly, the fertilising principle is then conveyed from the trichophore-cells at the base of the trichogyne to the cells which ultimately produce the carpospores, and which may be at a considerable distance from the trichogyne, even on a different branch. This transference is effected by means of long simple or branched tubes which are known as 'fertilising tubes.' The sexual mode of reproduction has, however, at present been observed in comparatively few species of sea-weed; and, considering the number of species of *Florideæ* found on our coasts, there is no branch of microscopical observation which is more likely to reward the young investigator with new discoveries.

CHAPTER IX

FUNGI

FUNGI, as already mentioned, differ essentially from algæ in the absence of chlorophyll, and therefore in the absence of any power of directly forming starch or other similar substance by the mutual decomposition of carbonic acid and water, accompanied by evolution of oxygen. They must therefore, in all cases, be either *saprophytes* or *parasites*, deriving their nourishment from already organised food-materials, either, in the former case, from decaying animal or vegetable substances, or, in the latter case, from the living tissues of other plants or of animals. Fungus-parasites are the cause of most of the diseases to which plants, and of a large number of those to which animals, are subject.

The individual fungus always consists of one or more *hyphæ*, slender filaments containing protoplasm and a nucleus (except possibly in some of the most simple forms), but no chlorophyll and rarely any pigment. The cell-wall is composed of a substance differing somewhat in its properties from ordinary cellulose, since it is not coloured blue by iodine after treatment with sulphuric acid; it is known as *fungus-cellulose* or fungin. These hyphæ may be quite distinct or very loosely attached to one another; those which penetrate the soil, or the tissue of the 'host' on which the fungus is parasitic, constitute the *mycele*. In the larger fungi, such as the mushroom, the portion above the soil is composed of a dense mass of these hyphæ, lying side by side, constituting a so-called *pseudo-parenchyme*, but never a true tissue. In some families the hyphæ have a tendency to become agglomerated into balls of great hardness called *sclerotes*, which have the power of maintaining their vitality for very long periods. The modes of reproduction of fungi, both sexual and non-sexual, are very various. Among the latter the most common are by non-motile *spores* or *gonids*, and by *zoöspores*. The former are very minute bodies, each composed of a single cell, or rarely of several cells, which are either formed within a spore-case or *sporange*, or are detached from the extremity of hyphæ by a process of pinching off or *abstriction*. From their extreme lightness they are wafted through the air in enormous numbers, and thus bring about the extraordinarily rapid spread of many fungi, such as moulds. The zoospores are, like those of the lower algæ, minute naked masses of protoplasm provided with one or more vibratile cilia, by means of

:h they move very rapidly through water, and finally force their into the tissue of the host, where the zoöspore loses its cilia, sts itself with a cell-wall, and proceeds to germinate, which is ted, as is also the case with the ordinary spores, by putting out *rminating filament*, which ultimately develops into the new ;us plant. In a large number of fungi no process of sexual re- luction is known. The various modes which do occur will be ribed under the separate families.

Some families of fungi are characterised by the remarkable pheno- on known as *alternation of generations*. Each species occurs in (or sometimes three) perfectly distinct forms, which bear no mblance to one another, and were long supposed to belong to ıly separate families. Each phase or 'generation' has its own e of reproduction, but does not reproduce its own special form, :he other, or one of the other forms, and two or three generations :hus required to complete the cycle. Each member of the cycle enerally speaking, parasitic on a totally different plant from the t' of the other forms.

The classification of fungi is attended with very great difficulties, ıg to our still imperfect acquaintance with the mode of reproduc- in several of the groups. The following are the more distinct remarkable types:[1]—

The **Myxomycetes**, Myxogastres, or Mycetozoa, are a group of singular organisms, on the very confines of the animal and table kingdoms, doubtfully included among the fungi, and be- d by many to have a closer affinity to the rhizopods. They appear ed at one period of their life-history to have an animal, at another d a vegetable existence. Several species are not uncommon on yed wood, bark, heaps of decaying leaves, &c. The 'plasmode' *Ethalium septicum*, known as 'flowers of tan,' forms yellow ulent masses in tan-pits. The development of other species epresented in fig. 425. Commencing with the germination of spores, each *spore* is a spherical cell (C) enclosed in a delicate ıbranous wall; and when it falls into water this wall undergoes ure (D), and an amœba-like body (E) escapes from it, consisting little mass of protoplasm, with a round central nucleus enclosing cleolus and a contractile vesicle, and having amœba-like move- ts connected with the protrusion and withdrawal of peculiar esses or pseudopodes. This soon elongates (F), and becomes ted at one end, whence a long *flagellum* is put forth, the lashing ın of which gives motion to the body, which may now be termed *warm-spore*. After a time the flagellum disappears and the active ements of the spore cease; but it now begins again to put forth to withdraw finger-like pseudopodes, by means of which it creeps ıt like an *Amœba*, and feeds like that rhizopod upon solid par- s which it engulfs within its soft protoplasm. These swarm-cells

[The classification of fungi here adopted is essentially that of De Bary in his *parative Morphology and Biology of the Fungi, Mycetozoa, and Bacteria*. g to the very large recent additions to our knowledge of the structure of fungi, ıs been found necessary entirely to rearrange this portion of Dr. Carpenter's .—Ed.]

may multiply by bipartition to an indefinite extent; but after a time a 'conjugation' takes place between two of these *myxamœbæ* (H), their substance undergoing a complete fusion into one body (I), from which extensions are put forth (K); and by the union of a number of these bodies are produced the motile protoplasmic bodies known as *plasmodes*, the ordinary form in which these singular bodies are known. These continue to grow by the ingestion and assimila-



FIG. 425.—Development of *Myxomycetes*: A, plasmode of *Didymium serpula*; B, successive stages, *a*, *a'*, *b*, of sporanges of *Arcyria flava*; C, ripe spore of *Physarum album*; D, its contents escaping; E, F, G, the swarm-spore first becoming flagellated, and then amœboid; H, conjugation of two amœboids, which at I, have fused together, and, at J, are beginning to put out extensions and ingest nutriment, of which two pellets are seen in its interior.

tion of the solid nutriment which they take into their substance: and, by the ramification and inosculation of these extensions, a complete network is formed.

The filaments of this network exhibit active undulatory movements, which in the larger ones are visible under an ordinary lens, or even to the naked eye, but which it requires microscopic power to discern in the smaller. With sufficiently high amplification, a constant movement of granules may be seen flowing along the threads,

and streaming from branch to branch. Here and there offshoots of the protoplasm are projected, and again withdrawn, in the manner of the pseudopodes of an *Amœba*; while the whole organism may be occasionally seen to abandon the support over which it had grown, and to creep over neighbouring surfaces, thus far resembling in all respects a colossal ramified *Amœba*. The plasmodes are often found to have taken up into them and enclosed a great variety of foreign bodies, such as the spores of fungi, parts of plants, &c. They are curiously sensitive to light, and may sometimes be found to have retreated during the day to the dark side of the leaves, or into the recesses of the tan over which they had been growing, and again to creep out on the approach of night. Under certain conditions the swarm-spores may lose their power of motion and become encysted; they are then known as *microcysts*, and may remain in this resting condition for a considerable time, especially if desiccated. If again placed in water, they return to their motile swarming state. The plasmodes may also enter a resting state, in which they assume a wax-like consistence, and dry up into a brittle horny mass. They are then known as *sclerotes*. In a few genera the spores are not contained in sporanges, but are borne on external supports or *sporophores*. But in the great majority of genera the plasmode becomes ultimately transformed into *sporanges* (B, *a*, *a'*, *b*); either each plasmode becomes a single sporange, or it divides into a larger or smaller number of pieces, each of which undergoes this transformation. When mature, the cavity of the sporange is either entirely filled with the very numerous *spores*, or in most genera tubes or threads of different forms occur among the spores, and constitute the *capillitium*. These capillitium-tubes have often a spiral appearance, owing to irregular thickenings of the cell-wall, and are very beautiful objects under the microscope. The growth of many species of *Myxomycetes* is exceedingly rapid, going through their whole cycle of development, with its various phases, in the course of a few days.

The **Chytridiaceæ** are a group of minute microscopic fungi showing an affinity in some respects to the Myxomycetes, and even to the infusorial animalcules. Their ordinary mode of propagation is by zoöspores bearing one or two cilia, which either germinate directly or conjugate to produce a resting-spore. They are parasitic on fresh-water organisms, both animal and vegetable; and their chief interest to the microscopist is that their zoöspores have apparently frequently been mistaken for antherids of the 'host.'

The **Ustilagineæ** are fungi parasitic on flowering plants, attacking the stem, leaves, and other parts, where they form brown or yellow spots. They are often exceedingly destructive to vegetation, causing the diseases of cereal crops known as bunt, smut, &c. The course of development of these fungi is not yet in all cases accurately known. The mycele, consisting of slender segmented hyphæ, spreads extensively within the tissues of the host, and bears spores which either reproduce the mycele again directly, or with the intervention of so-called 'sporids.'

The **Uredineæ** afford the most remarkable illustration among fungi of the phenomenon already mentioned, that of *alternation of*

generations, forms previously considered to belong to widely separated groups being now known to be stages in the cycle of development of the same species. A striking instance of this is furnished by the well-known and very destructive disease of wheat and other grasses known as 'mildew,' produced by the attacks on the leaves of the parasitic fungus *Puccinia graminis*. It was long ago observed that wheat was especially liable to this disease in the vicinity of barberry bushes; and it is now known that a fungus parasitic on barberry leaves, formerly known as *Æcidium berberidis*, is the 'æcidiospore' generation of the same species of which *Puccinia graminis* is the



FIG. 426.—*Puccinia graminis*. From De Bary's 'Comparative Morphology and Biology of the Fungi.' (The Clarendon Press.)

'teleutospore' generation. The complete cycle of development of the best known *Uredineæ*, such as the mildew, is this. The form known as *Puccinia graminis* produces *teleutospores*, thick-walled spores, borne usually in pairs, at the extremity of elongated cells known as *basids* or *sterigmata*. Each of these teleutospores gives rise, on germinating within the tissue of the grass, to a hypha or *promycele*, the terminal cells of which develop, on slender basids, each a single spore or *sporid*. These sporids will germinate only on the leaves of the

barberry, where they produce, first of all, a mass of interwoven hyphæ within the tissue, and then the peculiar reproductive bodies known as *æcidia* (fig. 427). The 'æcidium' is a cup-shaped receptacle of a bright red or yellow colour, which breaks through the epiderm of the leaf, and discharges a large number of *æcidiospores*, which are produced in rows or chains springing from basids at the base of the receptacle. These are accompanied, often on the other surface of the leaf, by *spermogones*, smaller spherical or flask-shaped receptacles, which also eventually break through the epiderm, and are filled with barren hyphæ known as *paraphyses*. Among these are other shorter hyphæ or 'sterigmata,' from the extremities of which are abstricted narrow ellipsoidal cells, the *spermatia*. The purpose of these is unknown; but they may be male elements which have lost their function. The æcidiospores will germinate only on the leaves and stems of grasses, either producing the teleutospore-form directly, or giving rise to a third 'uredo-form.' This consists of filiform basids, each of which bears a round oval spore, the *uredospore*, which germinates very rapidly,



FIG. 427.—*Æcidium tussilaginis*: A, portion of the plant, magnified; B, section of one of the 'æcidia' with its spores.

constantly reproducing the same form. The same mycele which produces the uredo-form also gives rise subsequently to the teleutospore-form. The fungus usually hibernates and remains in a state of rest in the teleutospore-form.

Of the **Peronosporeæ** (fig. 428) some species grow on the dead bodies of animals and on dead plants, others are parasitic in the living tissues of flowering plants, causing widespread diseases, such as the potato-blight. On the mycele, consisting of a number of distinct septated hyphæ, are produced the sexual organs, *oögones* and *antherids*. Fertilisation is not effected by means of motile antherozoids, as in other classes of fungi and of algæ, but the antherid puts out a cylindrical or conical tube-like process, the *fertilisation-tube*. The antherids and oögones are each single enlarged cells produced in close proximity to one another; the fertilisation-tube is produced from the part of the antherid which is in immediate contact with the oögone, and discharges into the latter the contents of the antherid, thus causing its protoplasmic contents or 'oösphere' to develop into the

impregnated 'oöspore.' The further history of the oöspore is singularly different, even in different species of the same genus. In some it germinates directly into a new mycele; in others it breaks up into a number of swarm-spores or zoöspores; each of these comes to rest, and after a time germinates into a new mycele. In addition to the sexual organs of reproduction, many species of Peronosporeæ also produce non-sexual *spores* or *gonids*, which are borne on special branches springing erect from the mycele, the *sporophores*, or *gonidiophores*. A similar difference is exhibited in the further development of these spores. Either they germinate directly in water into a new mycele, or the protoplasmic contents break up into a number of zoöspores which germinate in the same way. In those species which are parasitic on living plants, such as *Phytophthora infestans* which produces the potato-disease, and *Cystopus candidus*,



FIG. 428.—A-G, *Cystopus candidus*; H, *Phytophthora infestans*. A, branch of mycele growing at the apex, *t*, with *haustoria*, *h*, between the cells of the pith of *Lepidium sativum*; B, branch of mycele bearing gonids; C, D, E, formation of swarm-spores from gonids; F, swarm-spores germinating; G, swarm-spores germinating on a stomate and piercing the epiderm of the stem of a potato at E. After De Bary; magnified about 400 times. From 'Outlines of Classification and Special Morphology of Plants,' by Dr. K. Goebel.

very common on cress and other cruciferous plants, the rapid spread of the disease is caused by the great facility with which the spores are disseminated by the wind; falling on leaves in moist weather, they there germinate; the germinating tube passes through a stomate, and the mycele is developed with great rapidity within the tissue of the host. The condition in the case of the potato-disease is said by Professor De Bary to consist in an undue thinness of the cuticle, accompanied by excessive humidity, whereby the spores of the fungus will germinate on the surface of the plant, sending out processes which penetrate to its interior, though otherwise germinating only on cut surfaces.

The **Saprolegnieæ** are saprophytic or parasitic fungi, nearly allied to the *Peronosporeæ*, and differing from them chiefly in two points: although organs are known in many species closely resembling the antherids of the *Peronosporeæ*, the act of impregnation has not actually been observed, the oöspore being, at least in many cases, apparently produced *parthenogenetically*, i.e. without impregnation. In some species a single oöspore is produced within each oögone, but more often the contents of the latter break up into a number of oöspores, each of which gives rise to a mycele, or breaks up into zoöspores. In some genera, e.g. *Achlya* (fig. 429), zoöspores are also produced in very large numbers by the breaking up of the contents of *zoösporanges*, special enlarged cells of the mycele. The well-known salmon-disease is caused by the attacks of the parasitic *Saprolegnia ferox* on the living flesh of the animal.



FIG. 429.—Two sporanges of *Achlya*. From Goebel's 'Outlines of Classification and Special Morphology.'

The **Mucorini** are filamentous fungi, resembling the two last orders in their vegetative development, but differing in their mode of reproduction. To this family belong some of the most common moulds which make their appearance on damp or decaying organic substances. The ordinary mode of non-sexual reproduction is by *endogenous spores* or gonids, produced within a sporange (fig. 430, A). These are borne at the ends of sporangiophores, long erect unseptated hyphæ, springing directly from the mycele or from the original germinating filament. Several other kinds of non-sexual spores occur in the family, including *chlamydospores*, reproductive cells formed within the ordinary cells of the hyphæ. Sexual reproduction takes place by means of *zygospores* (C), but is at present known only in a few species. Either from ordinary hyphæ or from sporangiophores spring a pair of short branches, the extremities of which

become firmly attached to one another. These swell out greatly i an obconical form, on account of the passage into them of a l amount of nutrient material. A larger or smaller piece is then off from each of them by a transverse wall; the median cell-w which separates them disappears, and the two terminal portions t



FIG. 430.—B, mycele (three days old) of *Phycomyces nitens*, grown in a dro mucilage with a decoction of plums; the finest ramifications are omitted; *g*, conidiophore of *Mucor mucedo* in optical longitudinal section; C, a germinat zygospore of *Mucor mucedo*; the germ-tube, *k*, puts out a lateral conidiophor In D are conjugating branches, *b b*, the extremities of which, *a a*, though they h not yet coalesced, are already cut off by transverse walls; the zygospore is for from the coalescence of the cells *a a*. A, C, D, after Brefeld, greatly magnifi B, from nature, slightly magnified. From Goebel's 'Outlines of Classificat and Special Morphology.'

cut off coalesce to form the zygospore, which often swells to a consid able size, and its outer coat becomes frequently beautifully cover with warts or other protuberances. After a period of rest the zy spore germinates, its inner coat of cellulose bursting through the ou warty and cuticularised *epispore*, and developing into the first germ nating filament.

r nearly allied to the Mucorini are the **Entomophthoreæ**, : fungi, the mycele of which develops within the bodies of nsects, especially caterpillars and flies, and after death outside the body as a flocculent felt. An example of this of fungi is frequently presented in the destruction of the house-fly by *Empusa muscæ*. In its fully developed condi- spore-bearing filaments of this plant stand out from the body y like the 'pile' of velvet, and the spores thrown off from all directions form a white circle round it, as it rests motion- a window-pane. The filaments which show themselves ex- are the fructification of the fungus which occupies the inte- ie fly's body, and this orginates in the spores which find their) the circulating fluid from without. A healthy fly shut up iseased one takes the disease from it by the deposit of a spore part of its surface; for this, beginning to germinate, sends ocess which finds its way into the interior, either through ithing-pores or between the rings of the body; and having the interior cavities, it gives off the germinating filaments nstitute the earliest stage of the *Empusa*. Again, it is not common in the West Indies to see individuals of a species *tes* (the representative of the wasp of our own country) out with plants of their own length projecting from some their surface, the germs of which have probably been intro- is in the preceding case) through the breathing-pores at es, and have taken root in their substance, so as to produce ant vegetation. In time, however, this fungous growth through the body and destroys the life of the insect; it ms to grow more rapidly, the decomposing tissue of the dead ng still more adapted than the living structure to afford it it.

Ascomycetes include an enormous number of species, most of e parasitic on living, or saprophytic on decaying leaves, many microscopic. The mycele always consists of branched and hyphæ. In only a comparatively few species is a sexual reproduction known; the special character of the group is the ial reproduction of *ascospores* within elongated sacs or tubes s *asci*. These are commonly collected together in masses; ction of hyphæ which give birth to the asci is known as the the mass of tissue enclosing or bearing the hymenes as the e or *fructification*. Its form and structure vary greatly in rent sections of the family. The ascospores are always pro- ithin the ascus by free-cell formation, and their number is our or a 'power' of four, most commonly eight. The asci lly surrounded by enlarged club-shaped or sterile hyphæ, the es. In many Ascomycetes, in addition to the ascospores, exogenous *spores* or conids are produced at the extremity of res or conidiophores (fig. 431, A). This is the case with a nber of moulds or mildews, of which the common blue mould, *um glaucum*, may be taken as a type. The familiar form of ulds is that in which they produce these spores in enormous s; but, under certain conditions, the sexual mode of repro-

duction sets up (fig. 431, B–H). One of the branches of the mycele elongates, and coils spirally upon itself into a corkscrew-like body, the carpogone or *ascogone*, which constitutes the female organ; whilst another branch acts as the male organ or antherid, extending itself over the spire and impregnating the ascogone by the passage of its protoplasm into the latter organ. The structure thus formed becomes enclosed in a mass of sterile tissue, and within this are developed the



FIG. 431.—Development of *Eurotium repens*: A, small part of a mycele with the conidiophore, *c*, and young ascogones, *a s*; B, the spiral ascogone, *a s*, with the antheridial branch, *p*; C, the same with the filaments beginning to grow round it to form the wall of the sporocarp; D, a sporocarp seen from without; E, F, young sporocarp in optical longitudinal section; *w*, parietal cells; *f*, the filling tissue (pseudo-parenchymatous); *a s*, the ascogone; G, an ascus; H, an ascospore. After De Bary. A, magnified 190, the rest 600 times.

asci, each containing numerous spores, which germinate directly into a new mycele. The enveloping tissue, together with the asci, is known as the *sporocarp*.

In some Ascomycetes a tendency is exhibited for the formation of sclerotes, dense hardened masses of interwoven hyphæ. An example of this is furnished by the structure known as 'ergot,' the sclerote of a fungus of this kind, *Claviceps purpurea*, which attacks the ovary of rye and other grasses. Many species of *Peziza* have a peculiar form known as the *botrytis* form, reproduced by conids only, and

long believed to be altogether distinct from the Ascomycetes. Of this nature is the so-called *Botrytis bassiana* (fig. 432), a kind of mould, the growth of which is the real source of the disease termed *muscardine*, which formerly carried off silkworms in large numbers, just when they were about to enter the chrysalis state, to the great injury of their breeders. The plant presents itself under a considerable variety of forms (A–F), all of which, however, are of extremely simple structure, consisting of elongated or rounded cells, connected



FIG. 432.—*Botrytis bassiana*: A, the fungus as it first appears at the orifices of the stigmas; B, tubular filaments bearing short branches, as seen two days afterwards; E, magnified view of the same; C, D, appearance of filaments on the fourth and sixth days; F, masses of mature spores falling off the branches, with filaments proceeding from them.

in necklace-like filaments, very nearly as in the ordinary 'bead-moulds.' The spores of this fungus, floating in the air, enter the breathing-pores which open into the tracheal system of the silk-worm; they first develop themselves within the air-tubes, which are soon blocked up by their growth; and they then extend themselves through the fatty mass beneath the skin, occasioning the destruction of this tissue, which is very important as a reservoir of

nutriment to the animal when it is about to pass into its chrysalis condition. The disease invariably occasions the death of the grub which it attacks; but it seldom shows itself externally until afterwards, when it rapidly shoots forth from beneath the skin, especially at the junction of the rings of the body. Although it spontaneously attacks only the larva, yet it may be communicated by inoculation to the chrysalis and the moth, as well as to the grub; and it has also been observed to attack other lepidopterous insects. A careful investigation of the circumstances which favour the development of this disease was made by Audouin, who first discovered its real nature; and he showed that its spread was favoured by the overcrowding of the worms in the breeding establishments, and particularly by the practice of throwing the bodies of such as died into a heap in the immediate neighbourhood of a living silkworm: for this heap speedily became covered with this kind of mould, which found upon it a most congenial soil; and it kept up a continual supply of spores, which, being diffused through the atmosphere of the neighbourhood, were drawn into the breathing-pores of individuals previously healthy. The precautions obviously suggested by the knowledge of the nature of the disease, thus afforded by the microscope, having been duly put in force, its extension was successfully kept down. A similar growth of different species of the genus *Sphæria* takes place in the bodies of certain caterpillars, in New Zealand, Australia, and China; and being thus completely pervaded by a dense substance, which, when dried, has almost the solidity of wood, these caterpillars come to present the appearance of twigs, with long slender stalks that are formed by the growth of the fungus itself. The Chinese species is valued as a medicinal drug.

The **Saccharomycetes** are now generally regarded as a degraded form of the Ascomycetes. They resemble the Schizomycetes in the simplicity of their character and in their 'zymotic' action. The most familiar form of this family is the *Saccharomyces* (*Torula*) *cerevisiæ*, the presence of which in yeast gives to it the power of exciting the alcoholic fermentation in saccharine liquids. When a small drop of yeast is placed under a magnifying power of 400 or 500 diameters, it is seen to contain a large number of globular or ovoid cells, averaging about $\frac{1}{3000}$th of an inch in diameter, for the most part isolated, but sometimes connected in short series; and each cell is filled with a nearly colourless 'endoplasm,' usually exhibiting one or more vacuoles. When placed in a fermentable fluid containing some form of nitrogenous matter in addition to sugar,[1] they vegetate in the manner represented in fig. 433. Each cell puts forth one or two projections, which seem to be young cells developed as buds or offsets from their predecessors; these, in the course of a short time, become complete cells, and again per-

[1] It appears from the researches of Pasteur that, although the presence of albuminous matter (such as is contained in a saccharine wort, or in the juices of fruits) favours the growth and reproduction of yeast, yet that it can live and multiply in a solution of pure sugar, containing ammonium tartrate with small quantities of mineral salts, the decomposition of the ammonia salt affording it the nitrogen it requires for the production of protoplasm, while the sugar and water supply the carbon, oxygen, and hydrogen.

m the same process; and in this manner the single cells of yeast velop themselves, in the course of a few hours, into rows of four, e, or six, which remain in connection with each other whilst the ınt is still growing, but which separate if the fermenting pro- s be checked, and return to the isolated condition of those which ginally constituted the yeast. Thus it is that the quantity of ast first introduced into the fermentable fluid is multiplied six nes or more during the changes in which it takes part. Under tain conditions not yet determined, the yeast-cells multiply in other mode, namely, by the breaking up of the endoplasm into gments, usually four in number, around each of which a new 'cell- ll' forms itself; and these endogenous spores are ultimately set e by the dissolution of the wall of the parent-cell, and soon enlarge d comport themselves as ordinary yeast-cells. The process of the mation of these spores resembles in all essential points the forma- n of ascospores; and hence *Torula* is regarded as a low or degraded e of that order. Many other fungi of like simplicity have the wer to act as 'ferments'; thus in wine-making the fermentation the juices of the grapes or other fruit employed is set going by

a *b* *c* *d*

433.—*Saccharomyces cerevisiæ*, or yeast-plant, as developed during the process of fermentation: *a*, *b*, *c*, *d*, successive stages of cell-multiplication.

development of minute fungi whose germs have settled on their ıs, these germs not being injured by desiccation, and being lily transported by the atmosphere in the dried-up state. There eason to believe, moreover, that a similar 'zymotic' action may excited by fungi of a higher grade in the earlier stages of their wth, the alcoholic fermentation being set up in a suitable liquid h as an aqueous solution of cane-sugar, with a little fruit-juice) sowing in it the spores of any one of the ordinary moulds, such as *ıicillium glaucum*, *Mucor*, or *Aspergillus*, provided the temperature kept up to blood-heat; and this even though the solution has n previously heated to 284° Fahr., a temperature which must kill germs it may itself contain.

The Basidiomycetes are distinguished by the entire absence, as as is at present known, of sexual organs, and by the formation their conids or spores at the apex of special enlarged cells, the *ids*. They include the largest and most familiar of our fungi, h as the genera *Agaricus*, *Boletus*, *Polyporus*, *Lycoperdon*, *allus*, &c. They are saprophytes, obtaining their nourishment m the decaying vegetable matter in the soil, stumps of trees , &c., among which the mycele penetrates, consisting often of a ıse weft of septated hyphæ, the 'spawn' of the mushroom. The ial portion, known as the *receptacle* or fructification, bears either

externally, as in the case of the mushroom (fig. 434), or internally, as in the case of the *Lycoperdon*, or 'puff-ball,' the fertile portion or *hymene*. On this hymene project the extremities of special hyphæ, which are swollen into *basids*; the non-sexual conids or *basidiospores* are formed at the extremity of the basids, usually in fours, from which they are easily detached, and, from their small size and great lightness, are readily carried through the air in great quantities. In the *Hymenomycetes*, of which the common mushroom (*Agaricus campestris*) may be taken as a type, the receptacle has the form of a capshaped *pileus* (fig. 435), raised on a stalk or *stipe*, the whole composed of a pseudo-parenchyme consisting of a dense agglomeration of parallel hyphæ, the cortical portion of which is slightly differentiated into an epiderm. In the family to which the mushroom belongs, the hymene is borne at the edge of narrow gill-like projections or *lamellæ* radiating from the apex of the stipe on the under side of the pileus. Among the basids are seen other cells of similar shape and usually larger size, also the extremities of special hyphæ, called *cystids*, the function of which is obscure. The basidiospores vary greatly in colour in different genera. They are always unicellular, and the membrane consists of two coats, the *endospore* and *exospore*, the former of which consists of pure cellulose, while the latter is more or less cuticularised. On germinating the endospore bursts through the exospore, and grows into a germinating filament, from which is developed the mycele, and on this ultimately the receptacles.



FIG. 434.—*Agaricus campestris*, formation of the hymene: A and B slightly magnified; C, a part of B, magnified 550 times. The portion marked with fine dots is protoplasm.

Lichens.—The microscopic study of this group has latterly acquired a new interest for the botanist, from the remarkable

discovery announced in its complete form by Schwendener in 1869[1] (and now accepted by the highest authorities), that instead of constituting a special type of Thallophytes, parallel to *Algæ* (with which they correspond in their *vegetative* characters) and *Fungi* (to which they are more allied in *fructification*), they are really to be regarded as *composite* structures, having an algal base, on which fungi have sown themselves and live parasitically. As, however, they do not furnish objects of interest to the ordinary microscopist (the peculiar density of their structure rendering a minute examination of it more than ordinarily difficult), nothing more than a general account of their curious organisation will here be attempted. The algal portion of a lichen belongs to one or other of the lower groups, and consists of cells termed *gonids*—usually green, but sometimes red or bluish-green—interspersed among long cellular filaments. The proportion between these two components of the thallus varies in different examples of the type. Thus, in the simplest wall-lichens the palmella-like parent-cell gives origin, by the ordinary process of cell-division, to a single layer of cells, which spreads itself over the stony surface in a more or less circular form; and the 'thallus,' which increases in thickness by the formation of new layers upon its free surface, has no very defined limit, and, in consequence of the slight adhesion of its components, is said to be 'pulverulent.' But in the more complex forms of lichens the thallus is mainly composed of long hyphæ, which dip down into the superficial layers of the bark of the trees on which they grow, and form by their interweaving a hard crustaceous 'thallus' in which the *gonids* are imbedded, sometimes irregularly, sometimes in definite layers, known as the *gonidial layer*, covered by an envelope of interlacing filaments. It is from this algal portion of the structure that the *soredes* of lichens



FIG. 435.—*Agaricus campestris*, natural size. (From Goebel's 'Classification and Morphology of Plants.')

[1] See his memorable work *Ueber die Algentypen der Flechtengonidien* (Basel, 1869).

are formed, which are little projections of the surface, composed of single or aggregate *gonids*, invested by hyphæ, and falling, when dry, into a powder, of which every particle is capable of reproducing the plant from which it proceeded.

The *fructification* of lichens, on the other hand, is the production of their fungal overgrowths, which are nourished by the algal vegetation. The lichen-forming fungi, in fact, live upon their algal hosts, like the entophytic fungi (such as the 'blights' of corn), which infest the higher forms of vegetation, each of the former choosing its own alga, just as the latter mostly attach themselves to particular victims. The peculiarity in the parasitism of the lichen-fungi lies in the fact that they are not attached to their host externally at any one particular spot, and do not penetrate into its cells, but weave themselves round them, and enclose them in their hyphal tissue. But not only this; the algal constituent of the lichen appears also to derive benefit from, and to be nourished by, the



FIG. 436.—*Leptogium scotinum*: Vertical section of the gelatinous thallus, magnified 550 times. An epidermal layer clothes the inner tissue, which consists for the most part of formless and colourless jelly, in which the coiled strings of gonids lie: single larger cells of the strings (the limiting cells) are of a higher colour; between them run the slender hyphæ. (From Goebel's 'Classification.')

fungus-hyphæ, affording an example of the singular kind of mutual dependence known as *commensalism* or *symbiosis*. The formation of sexually produced 'spores' usually takes place in *asci* arranged vertically in the midst of straight elongated sterile cells termed *paraphyses*, so as to form a layer that lies either on the surface of cup-shaped receptacles termed *apotheces*, or is completely enclosed within *peritheces*. Each of the asci contains a definite number of ascospores (usually eight, but always a 'power' of two), which are projected from the receptacles with some force; and their emission, which seems to be due to the different effects of moisture upon the several layers of the receptacle, is often kept up continuously for some time. The formation of these asci, as in the case of the ordinary *Ascomycetes*, is probably the result of a sexual union which takes place between the male *pollinoids* or 'spermatia' and the female *trichogyne*. These pollinoids are produced within antherids which are often specially designated 'spermogones,' formed

ıin these cavities, and, when mature, escaping in great numbers ı their orifices. Having no power of spontaneous movement, r must probably be conveyed by the infiltration of rain-water to *ichogyne* which lies imbedded in the tissue beneath; and when r have imparted their fertilising influence to the contents of the *gone* at its base, these develop themselves into a spore-bearing *hece*, the whole mass of spores which this contains being the luct of the cell-division of the originally fertilised 'oöspore.'



187.—Examples of various algæ which are employed as the gonids of lichens: ndicates always the hypha of the fungus; *g'* the gonid: A, germinating re, *s*, of *Physcia parietina*, the germ-tube of which adheres closely to *Protocus viridis*; B, a filament of *Scytonema* with hyphæ of *Stereocaulon ramulosus* ned round it; C, from the thallus of the lichen *Physma chalaganum*—a hyphal nch is entering a cell of the *Nostoc* filament (gonid); D, from the thallus of lichen *Synalissa symphorea*—the gonids are the alga *Glœocapsa*; E, from thallus of the lichen *Cladonia furcata*; the gonids, which are being surnded by the hyphæ, are the cells of *Protococcus*. After Bornet. A, C, D, E gnified 950; B, 650 times. (From Goebel's 'Classification and Special Morlogy of Plants.')

The fungus-constituent of lichens belongs, in the great majority ases, to the Ascomycetes, in a very few to the Basidiomycetes. gonids have been referred to a very large number of genera of e, among which may be mentioned *Protococcus*, *Chroöcoccus*, *ocapsa*, *Palmella*, *Scytonema*, *Nostoc*, and *Chroölepus*.

The Bacteria or Schizomycetes.—At the close of this chapter we e the *Bacteria* or *Schizomycetes*; that it is their place in the ıral system may be doubted and easily traversed. Cohn does hesitate to say that to account them offshoots of the Fungi

is to 'contradict all trustworthy observations'; [1] and it may be fairly admitted that what we know of their development does not suggest close kinship with the Fungi. But, great as is the labour which has been bestowed upon this group, and vast as the literature is to which it has given rise, it is impossible to assign an exact and clearly definable position to what is at the same time a remarkable and important group; and we therefore, as a matter of convenient arrangement, place them as PROTOPHYTES, at the base of the lowest Fungi, for no other, and therefore for the quite insufficient reason in the main, that they contain, as a rule, no chlorophyll.

There can be no doubt that some forms of the Bacteria manifest affinity with the chlorophyllaceous Algæ; but the affinity is in the present state of our knowledge none the less indefinable, even if our knowledge of the Bacteria as an entire group were complete enough to admit of a generalisation of their relations. That the affinities of the Bacteria as a complete group are closer with the Flagellata than is generally admitted, the present Editor is convinced; and whenever the saprophytic Flagellata—which are the indispensable agents, *not* in the putrefactive fermentation by which *infusions and gelatine masses* are broken up, but by which *great masses of organic tissue* are reduced—and at the same time the Bacteria, as a whole, have been broadly and comprehensively worked out, it will be found that both their morphological and physiological affinities are of the closest order.

It is impossible to take what we know of such a form as *B. lineola*, which has an easily demonstrated flagellate character, and reproduces in every fission a flagellum, common to both dividing forms, which snaps at the moment of complete division, leaving each form with a flagellum at either end—perfect as the primal form whence the fission arose—without observing how completely this coincides with the mode of fission in half a dozen saprophytic monads. But as an instance *Cercomonas typica* (named by Kent) may be given,[2] where the process is identical. True the Cercomonas has a conjugating and subsequent resting stage, after which swarms emerge from spores thus formed. But a fuller knowledge of *B. lineola* is certainly wanting before we can deny the further analogy. And this incidence is the more suggestive, since it is characteristic of the whole group of saprophytic monads, and their function is identical with that of the saprophytic Bacteria.

No doubt if such affinity were established, it would lead to much rearrangement at the base of the organic series.

Since there is an apparent and highly suggestive leaning of the Bacteria to those forms of Algæ which form the group of *Nostocaceæ*, these also would be brought nearer the Flagellata; while the *Myxotozoa* will have singular points of contact with these, one of which has reference to the mode of *sporing* of one at least of the flagellate saprophytes,[3] while it is suggestive that the same grouping, should the affinity be established, would involve a connection with the Algæ and the Fungi.

[1] Cohn, *Beiträge*, ii. 188. [2] *Manual of the Infusoria*, i. 259.
[3] *J.R.M.S.* vol. v. ser. ii. pp. 189–90, fig. 16, Plate V.

y definite results leading to a comprehensive view of the of the Bacteria as a whole that can render generalisation er safe.

word *Bacteria* will be understood *rod-shaped organic* is is the characteristic of the group. They are often less breadth, and may be sphere-like or cylindrical cells. forms, whether longer or shorter, are possessed, as a rule, lla. The mode of multiplication commonly observed is by partition. The products of successive fissions may remain a single filiform row loosely attached, or attached by the lament of the flagella, or they may at once separate imal cell.

nature of this simplest cell we have hitherto learnt ly little; the protoplasm is generally homogeneous, and cies it forms chlorophyll, although the absence of it and ring matters is a distinct characteristic of the group. emarkable of the coloured forms uniformly tinged red nd named by Professor E. Ray Lankester;[1] other forms ound by Van Tieghem, Engelmann, and Zopf.

the protoplasm of the Bacteria, however, no nuclei have n discovered, but a delicate investing envelope, probably kening of the outmost area of the protoplasm, which is elatinous in its outer portions.

rms of Bacteria have the power of entirely free move- quently this movement is coincident with a revolution on axis of the rod, curved or straight, and in the vast cases this is directly correlated with a vortical action of ellum—an action which may be seen with the utmost proper means be employed, in the case of *Spirillum* id less easily, but with almost equal certainty, in the other forms, not excluding *B. termo*.

lest forms in which Bacteria are found are as *isolated cells ovate shape*: these are known as *Micrococci*; but many laced under this head are in reality immature and de- *nads* of the saprophytic group.

-like forms are found isolated and free, or in chains. ods are known as *Bacteria*; the long rods as *Bacilli*. are fusiform in appearance are known as *Clostridia*.

d rods or spiral forms are either (1) closely coiled, when own as *Spirillum* and *Spirochæte* (more threadlike); or re openly coiled are known as *Vibriones*.

e also very *elongated* filiform varieties known as *Lepto-* imes though rarely branched; and *Beggiatoa*, the filaments ed at one extremity stretch the other free in the sur- id.

these may be united by some interfusing gelatinous which all action ceases, or is of the most limited kind; ring films, which appear on the surface or suspended in of putrescent fluids, are known as *Zoöglœæ*. They may

[1] *Quart. Journ. Micros. Sci.* new series, xiii. 408.

also be found on the surfaces of solid bodies, where the putrefactive ferment is in action.

The only rational attempt which has been made to *classify* the *Bacteria* is into I. *Endosporous* Bacteria; and II. *Arthrosporous* Bacteria. That this classification can be permanent is highly improbable; it at best roughly covers the present state of our knowledge.

I. The *endosporous* forms are those whose multiplication is brought about by the formation within a cell of a minute globular or oval body, which, while the surrounding protoplasm of the mother-cell disappears (is assimilated?), gradually reaches its mature condition. The formation of spores occurs most abundantly when the substratum is almost exhausted, or the vital processes are in some way interrupted.



FIG. 438. — *Bacillus megaterium*. (From De Bary's 'Comparative Morphology of Fungi.')

II. *Arthrosporous* forms are reproduced by the separation of single members from their connection with a group, which then give origin to new generations. They are separate individuals in which micrococci or spores appear, from which arise forms ultimately similar to those from which the forms bearing the cocci originated.

A chosen illustration of the *endosporous Bacteria* is *Bacillus megaterium*. It was first observed on boiled cabbage leaves, and is considered by De Bary as an 'exceedingly instructive form.' It is 2·5μ in short diameter and about four times as long as this. It is illustrated in fig. 438: *a* represents a motile chain of the Bacilli in active vegetation. This is magnified 250 diameters. *b* is two active rods magnified 600 diameters. *p* shows the result of treating a form in the condition *b* with an alcoholic solution of iodine. *c* is a rod with five cells preparing to form spores. *d* to *f* represent successive stages of a pair of rods in the act of forming spores, *e* an hour later than *d*, and *f* an hour later than *e*. The cells which did not contain spores disappeared or perished. *r* is a quadri-cellular rod with ripe spores. g^1 is a five-celled rod with three ripe spores placed in a nutrient solution after several days' desiccation. g^2 is the same an hour after; g^3 is the same after another two hours and a half. h^1 is two spores with the walls of the mother-cells dried and placed in a nutrient solution; h_2 is the same forty-five minutes later; *i*, *k*, *l* three stages of germination of the spore.

Bacillus anthracis and *B. subtilis* are forms that range under the same division. *B. anthracis* is the form which has been proved to be the virus of splenic fever or charbon. It is found in great profusion in the blood and tissues of animals attacked by this disease. The filaments or rods approach 1μ in thickness in strong specimens grown in the blood of smitten animals, and they occasionally attain three or four, sometimes five times this length. They are connected

together in the blood in straight rods varying in length. Fig. 439 shows two filaments grown on a microscopic slide (De Bary) in a solution of meat extract, partly in an advanced state of spore-formation. At the upper part of the figure two ripe spores have escaped. These spores on germination elongate and give rise to new groups of rods and filaments.

B. subtilis, which is the Bacillus common to decomposing hay infusion, has a life-history extremely similar to *B. anthracis*. It spores in precisely the same manner. The outer wall of the spore is comparatively thick, and the protoplasm elongates in the direction of the longer axis of the spore and of the mother-cell with which this coincided. B, fig. 439, represents the development of *B. subtilis*: 1 shows fragments of filaments with ripe spores; at 2 the spore is beginning to germinate; 3, the young rod is projecting from the wall of the spore. 4 represents germ-rods curved in a horseshoe shape and with the extremities connected, one of them having one extremity subsequently released; 5, germ-tubes with the two extremities remaining connected and already greatly increased in size. The whole represents a magnification of 600 diameters.



FIG. 439.—A, *Bacillus anthracis*; B, *B. subtilis*. (From De Bary's 'Fungi.')

A sufficiently detailed *illustration of the development of the arthrosporous Bacteria* may be seen in *Beggiatoa alba*. In the refuse waters discharged from factories, especially the sulphuretted effluents of sewage works, is found this form—the 'sewage fungus' of engineers. It may have a thickness of 5μ, and it may be as attenuated as to measure only 1μ. It is attached in an erect manner to objects in the impure water it affects (fig. 440); and the filaments consist of rows of cells, and in the protoplasm of these granules of sulphur are enclosed. The filaments readily break up into cells about as long as they are broad, and become at length active, but eventually attach themselves to some object and come to rest, when they multiply by fission and accumulate in masses of *zoöglœa*. 'They may develop into rods, and these again into the filaments after the rods have passed through the swarming state.'

Spirally twisted forms also arise in this species. These break into coiled parts, possessed of flagella, and exhibit extremely active movement. The flagella in these are as strong and easily seen as in the *Spirillum volutans*, and these forms were known at an earlier period as Ophidomonas.

Fig. 440 shows at 1 a group of the attached filaments of *Beggiatoa alba*: 2 to 5 show portions of filaments of differing diameters; 5 shows a filament in the act of multipartition. The small dark circles throughout represent the granules of sulphur; 6 to 8 show fragments rich

in sulphur with transverse septation developed by treatment wi methyl-violet solution. In 8 the formation of cocci and spores seen ; 9 shows the result of filaments having broken up into spore



FIG. 440.—*Beggiatoa alba*. (From De Bary's 'Comparative Morphology of Fungi.'

10 shows spores in movement. 1 is magnified 540 diameters, th remainder 900 diameters.

Figure 441 shows the growth of the curved and spiral forms of the same : A is a group of attached filaments ; B to H show por-

tions of spiral filaments; C, D, F, to H represent the act of division into smaller fragments but without motion; in H the separate cells are distinctly shown; E shows the separation of a complete spirillum form possessed of flagella and capable of great activity.

The Bacteria behave very variously under the same conditions of supply or exclusion of oxygen. Some require free oxygen in quantity, as e.g. *B. subtilis*; while in others the vital activities are promoted by its exclusion. But there can be no doubt that gradual modification of either condition will bring about adaptations. Nägeli has shown that there are forms which usually depend on oxygen which continue to vegetate when free oxygen ceases.

Their nutrition is carried on like that of other vegetative forms devoid of chlorophyll. The actual typical group are without doubt the saprophytic Bacteria. The relation of the *parasitic* or *pathogenic* forms to these is one of the most interesting problems in microscopic biology. That they are physiological modifications of the saprophytic forms appears *per se* a possibility; but in the light thrown upon biological change and survival by the hypothesis of the origin of species, the suggestion incites to practical inquiry and research. If the parasitic Bacteria are physiological modifications of the saprophytic forms, to know the path by which they biologically became such may be to put more into the hands of medicine than could be accomplished by any other means.



FIG. 441.—*Beggiatoa alba*, curved and spiral forms. (From De Bary's 'Comparative Morphology of Fungi.')

Bacterium termo is the most universally present and abundant of the saprophytic forms. It is 1μ to 1·5μ long, and 0·5 to 0·7μ broad, usually of dumb-bell form. These Bacteria are usually seen in 'vacillating' movement in their free state; each cell bears a flagellum at each end, as B, D (fig. 442), whilst the double cells bear a flagellum at each extremity. The formation of the second flagellum takes place

by the drawing out of a filament of protoplasm between two cells that are separating from each other (as in fig. 443, *a*, *b*), the rupture of which gives a new flagellum to each. Their flagella are so minute as to be among the most 'difficult' of all microscopic objects, their diameter being calculated from 200 measurements by Dr. Dallinger at no more than $\frac{1}{200000}$th of an inch.[1] Although this species does not ordinarily multiply in any other way than by transverse subdivision, yet, under 'cultivation' at a temperature of 86° Fahr., its cells have been seen to elongate themselves into motionless rods, resembling those of *Bacilli*, whose endoplasm breaks up into separate particles that are set free as small bright almost spherical spores, which sometimes congregate so as to form a *zoöglœa*-film. These



FIG. 442.—A, *Bacterium termo*, each cell furnished with a single flagellum. Magnified 4,000 diameters B, C, D, *Bacterium lineola*, each cell when separated having a flagellum at either end. Magnified 3,000 diameters. (Dallinger.)

germinate into short slender rods, which are at first motionless, but soon undergo transverse fission, and then acquire flagella.[2]

The *Vibriones* may be represented by *V. rugula*, seen in fig. 443,



FIG. 443.—Four individuals of *Vibrio rugula*, each showing flagellum at one or both ends; two other individuals, *a* and *b*, separating from each other, and drawing out a protoplasmic filament to form their second flagella. Magnified 2,000 diameters. (Dallinger.)

They are slightly curved rods and threads from 6μ to 16μ long, and varying in thickness from 0·5μ to 2μ. They have well-marked flagella, one at each end. They appear in vegetable infusions, causing fermentation of cellulose.

The *Spirilla* are the largest forms in the group, characterised by their spirally formed cells and their graceful spiral motion. They are fairly represented in fig. 444 by *Spirillum undula* (A), and *Spirillum volutans* (B). The threads of the former are from 1·1μ to 1·4μ in thickness, and from 9μ to 12μ in length. They are intensely active, and possess a flagellum at either end. They are found in varying decomposing infusions.

Spirillum volutans was known to and named by Ehrenberg. It is from 1·5μ to 2·3μ in thickness, and varies from 25μ to 30μ or more in length. They have distinctly granular contents. They have a

[1] *Journ. of Roy. Micros. Soc.* vol. i. (1878), p. 175 [2] Ewart, *loc. cit.*

very easily demonstrable flagellum at each end of the spiral; a flagellum was distinctly suggested by Ehrenberg on account of the vortical action visible in the fluid before this spirillum as it advanced.

On the whole it is surprising to find at this time what difficulty there appears on the part of some botanists to distinguish these motile filaments in the Bacteria. With the superb 6mm. power of Zeiss (apochromatic dry N.A. 0·95), all but the most difficult of these can be seen with relative ease *on a dark ground* with a 12 or 18 eyepiece, provided they be examined *alive with the flagella in motion.* For the more difficult ones (*B. termo* and *B. lineola*) more careful arrangements are required.

The germinating power of the spores of Bacteria may be brought into operation at once on their reaching ripeness, or they may be desiccated for an indefinite time, and again, on reaching suitable surroundings, will germinate as before. This power is held in various degrees by different forms, but the whole subject needs more



FIG. 444.—A, *Spirillum undula*, showing flagellum at each end. Magnified 3,000 diameters. B, *Spirillum volutans.* Magnified 2,000 diameters. (Dallinger.)

uniform and exhaustive inquiry. The spores of *B. subtilis* retain their vitality for years if kept in a dry air, while those of *B. anthracis* are stated by Pasteur to remain alive in absolute alcohol[1]; and Brefeld found their power to germinate uninjured after the lapse of three years in a dry atmosphere. He also found them proof against the boiling point of water, and even a higher temperature; but he found that fewer and fewer survived in boiling nutrient fluid until the end of the third hour, when all were destroyed. So Buchner found that the same spores were wholly killed only after three or four hours' boiling;[2] while Pasteur states that groups of uncertain spores can withstand a temperature of 130° C. There is, however, uncertainty, because a want of uniformity, in the results from various sources. 20° to 25° C. may be taken as the average degree of temperature at which these organisms will freely germinate; but *B. termo*, for example, has been known to germinate from 5·5° C. to 40° C.

[1] 'Charbon et Septicémie,' *Compt. Rend.* lxxxv. p. 99.
[2] Naegeli, *Unters. über niedere Pilze*, 1882, p. 220.

Nothing like 'conjugation,' or any other form of sexual generation, has yet been witnessed in any Bacteria ; and until such shall have been discovered, no confidence can be felt that we know the entire life-history of any one type.[1] When these facts are allowed their due weight, no difficulty can be felt in admitting the action of Bacteria &c. in producing decomposition under conditions which might at first view be fairly supposed to preclude the possibility of their presence. This action is altogether analogous to that of the yeast-plant in producing saccharine fermentation ; and the careful and exact experiments of Pasteur, repeated and verified in a great variety of modes by Professors Lister, Tyndall, and others, seem to leave no reasonable doubt on these two points—(1) that putrefactive fermentation does not take place, even in liquids which are peculiarly disposed to pass into it, except in the presence of Bacteria-germs ; and (2) that neither these germs nor any others arise in such liquids *de novo*, but that they are all conveyed into them by the air when not otherwise introduced. It is thus also with the parasitic or pathogenic forms of Bacteria in setting up disease. Thus 'splenic fever' is producible by the inoculation of *Bacillus anthracis*, and the typhoid fever of the pig by inoculation with another species of *Bacillus*, the plants having been in both cases 'cultivated,' so as to be free from other contaminating matter. Again, it has been ascertained by careful microscopical examination of the fluid of the vaccine vesicle, that it is charged with a multitude of minute granules not above $\frac{1}{50000}$th of an inch in diameter ; and it has been further determined that these, rather than the fluid in which they are suspended, are the active agents in the production of a similar vesicle in the skin into which they are inserted. This vesicle must contain hundreds or thousands for every one originally introduced ; and it is obvious that their multiplication has so strong an analogy to that of Bacteria, as to suggest the idea that it must take place by a like process of cell-development. Similar observations have been made upon glanders, sheep-pox, and cattle-plague ; so that an animal suffering under either of these terrible diseases is a focus of infection to others, for precisely the same reason that a tub of fermenting beer is capable of propagating its fermentation to fresh wort. A most notable instance of such propagation is afforded by the spread of the disease termed 'pébrine' among the silkworms of the south of France, which, according to Pasteur, is caused by a minute organism named *Nosema Bombycis*, the mortality caused by it being estimated to produce a money loss of from three to four millions sterling annually for several years following 1853, when it first broke out with violence. It has been shown by microscopic investigation that in silkworms strongly affected with this disease, every tissue and organ in the body is swarming with these minute cylindrical corpuscles about 4·2μ long, and that these even pass into

[1] As it seems unquestionable that among the higher Fungi 'conjugation' often takes place at a very early stage of growth, it seems a not very improbable surmise that the 'granular spheres' observed by Mr. Ewart in *Bacillus* and *Spirillum*, which seem to correspond with the 'microplasts' observed by Prof. E. Ray Lankester in his *Bacterium rubescens*, may be a product of conjugation in the micrococcus stage of these organisms.

the undeveloped eggs of the female moth, so that the disease is hereditarily transmitted. And it has been further ascertained by the researches of Pasteur that these corpuscles are the active agents in the production of the disease, which is engendered in healthy silkworms by their reception into their bodies; whilst, if due precautions be taken against their transmission, the malady may be completely exterminated.

Bacteriology is now so distinctly a branch of biological science that it would be out of place here to even present a summary of its voluminous details and methods of research. The microscope in its most perfect form is an indispensable adjunct to the rapidly progressive work of this department of biological research, and the most delicate and refined employment of the microscope and all its adjuncts is in the last degree important. Only a skilled microscopist can be a successful bacteriologist. But for the methods of the bacteriological laboratory we must refer the reader to treatises on this branch of science,[1] it being enough here to remark that the employment of nutrient gelatines, nutrient agar-agar, and other similar media poured over glass plates, and into test tubes, so as by inoculation to obtain plate and tube cultures of specific and isolated forms with their characteristic appearances, is one of the essential methods. Cleanliness and care, as well as practice in manipulation, are the essentials in effecting these; but as they solidify, the inoculated bacteria, instead of moving freely as they would in a liquid medium, are fixed to one spot, where they develop in a characteristic manner showing their own morphological features.

The pathological value of these researches is great beyond our present ability to estimate, and must have an apparently increasing value. But it is a branch of microscopy with which a work of this sort may not deal, further than to show the right use of the microscope and its appliances, by which the work of pathological bacteriology can alone be successfully done.

[1] The English student will find an admirable aid in the *Manual of Bacteriology*, by Professor E. Crookshank.

CHAPTER X

MICROSCOPIC STRUCTURE OF THE HIGHER CRYPTOGAMS

Hepaticæ.—Quitting now the algal and fungoid types, and entering the series of terrestrial cryptogams, we have first to notice the little group of *Hepaticæ*, or liverworts, which is intermediate between lichens and ordinary mosses, agreeing rather with the algal thallus of the former in its general mode of growth, whilst closely resembling the latter in its fructification. This group presents numerous objects of great interest to the microscopist; and no species is richer in these than the very common *Marchantia polymorpha*, which may often be found growing between the paving-stones of damp courtyards, but which particularly luxuriates in the neighbourhood of springs or waterfalls, where its lobed fronds are found covering extensive surfaces of moist rock or soil, adhering by the radical filaments (rhizoids) which arise from their lower surface. At the period of fructification these fronds send up stalks, which carry at their summits either round shield-like discs, or radiating bodies that bear some resemblance to a wheel without its tire (fig. 445). The former carry the male organs, or *antherids*; while the latter in the first instance bear the female organs, or *archegones*, which afterwards give place to the *sporanges* or spore-cases.[1]

FIG. 445.—Frond of *Marchantia polymorpha*, with gemmiparous conceptacles, and lobed receptacles bearing archegones.

The green surface of the frond of *Marchantia* is seen, under a low magnifying power, to be divided into minute diamond-shaped spaces (fig. 446, A, *a*, *a*,) bounded by raised bands (*c*, *c*); every one of these spaces has in its centre a curious brownish-coloured body (*b*, *b*), with an opening in its middle, which allows a few small green cells to be seen through it. When a thin vertical section is made of the frond

[1] In some species the same shields bear both sets of organs; and in *Marchantia androgyna* we find the upper surface of one-half of the shield developing antherids, whilst the under surface of the other half bears archegones.

it is seen that each of the lozenge-shaped divisions of its surface esponds with an air-chamber in its interior, which is bounded w by a floor (*a*, *a*) of closely set cells, from whose under surface rhizoids arise; at the sides by walls (*c*, *c*) of similar solid enchyme, the projection of whose summits forms the raised ds on the surface; and above by an epiderm (*b*, *b*) formed of a le layer of cells; whilst its interior is occupied by a loosely nged parenchyme composed of branching rows of cells (*f*, *f*) that n to spring from the floor, these cells being what are seen from re when the observer looks down through the central aperture mentioned. If the vertical ion should happen to traverse of the peculiar bodies which upy the centres of the divi-s, it will bring into view a cture of remarkable com-city. Each of these *stomates* they are termed, from the ek στόμα, mouth) forms a sort haft (*g*), composed of four or rings (like the 'courses' of ks in a chimney) placed one n the other (*h*), every ring g made up of four or five ; and the lowest of these s (*i*) appears to regulate the ture by the contraction or ansion of the cells which pose it, and is hence termed 'obturator-ring.' In this ner each of the air-chambers he frond is brought into com-nication with the external osphere, the degree of that munication being regulated he limitation of the aperture. shall hereafter find that the es of the higher plants con- intercellular spaces, which communicate with the ex-or by stomates, but that the structure of these organs is far less plex in them than in this humble liverwort.



FIG. 446.—Structure of frond of *Marchantia polymorpha*: A, portion seen from above; *a*, *a*, lozenge-shaped divisions; *b*, *b*, stomates in the centre of the lozenges; *c*, *c*, greenish bands separating the lozenges. B, vertical section of the frond, showing *a*, *a*, the dense layer of cellular tissue forming the floor of the air-chamber, *d*, *d*, the epidermal layer, *b*, *b*, forming its roof; *c*, *c*, its walls; *f*, *f*, loose cells in its interior; *g*, stomate divided perpendicularly; *h*, rings of cells forming its wall; *i* cells, forming the obturator-ring.

The frond of *Marchantia* usually bears upon its surface, as shown ig. 445, a number of little open basket-shaped *gemmiparous conacles* (fig. 447), which may often be found in all stages of develop-nt, and are structures of singular beauty. They contain when ure a number of little green round or oblong discoidal *gemmæ*, composed of two or more layers of cells; and their wall is sur-nted by a glistening fringe of 'teeth,' whose edges are themselves ularly fringed with minute outgrowths. This fringe is at first ned by the splitting up of the epiderm, as seen at B, at the

time when the 'conceptacle' and its contents are first making their way above the surface. The little gemmæ are at first evolved as single globular cells, supported upon other cells which form their footstalks; these single cells, undergoing binary subdivision, evolve themselves into the gemmæ; and these gemmæ, when mature, spontaneously detach themselves from their footstalks, and lie free within the cavity of the conceptacle. Most commonly they are at last washed out by rain, and are thus carried to different parts of the neighbouring soil, on which they grow very rapidly when well supplied with moisture; sometimes, however, they may be found growing whilst still contained within the conceptacles, forming natural grafts (so to speak) upon the stock from which they have been developed or detached; and many of the irregular lobes which the frond of *Marchantia* puts forth seem to have this origin. The very curious observation was long ago made by Mirbel, who carefully watched the development of these *gemmæ*, that stomates are formed on the side which happens to be exposed to the light, and that rhizoids are put forth from the lower side, it being apparently a matter of indifference *which* side of the little gemma is at first turned upwards, since each has the power of developing either stomates or rhizoids according to the influence it receives. After the tendency to the formation of these organs has once been given, however, by the sufficiently prolonged influence of light upon one side and of darkness and moisture on the other, any attempt to alter it is found to be vain; for if the surfaces of the young fronds be then inverted, a twisting growth soon restores them to their original aspect.



FIG. 447.—Gemmiparous conceptacles of *Marchantia polymorpha*: A, conceptacle fully expanded, rising from the surface of the frond, *a*, *a*, and containing gonidial gemmæ already detached. B, first appearance of conceptacle on the surface of the frond, showing the formation of its fringe by the splitting of the epiderm.

When *Marchantia* vegetates in damp shady situations which are favourable to the nutritive processes, it does not readily produce the true fructification, which is to be looked for rather in plants growing in more exposed places. Each of the stalked peltate (shield-like) discs contains a number of flask-shaped cavities opening upon its upper surface, which are brought into view by a vertical section; and in each of these cavities is lodged an *antherid* which is composed of a mass of 'sperm-cells,' within which are developed

'antherozoids' like those of *Chara*, and surmounted by a long neck that projects through the mouth of the flask-shaped cavity. The wheel-like receptacles (fig. 445), on the other hand, bear on their under surface, at an early stage, concealed between membranes that connect the origins of the lobes with one another, a set of *archegones*, shaped like flasks with elongated necks (fig. 448) : each of these has in its interior an 'oösphere' or 'germ-cell,' to which a canal leads down from the extremity of the neck, and which is fertilised by the penetration of the antherozoids through this canal until they reach it. Instead, however, of at once evolving itself into a new plant resembling its parent, the fertilised oösphere or 'embryo-cell' develops itself into a mass of cells enclosed within a capsule, which is termed a *sporange*; and thus the mature receptacle, in place of archegones, bears capsules or sporanges, each of them filled with an aggregation of cells that constitute the immediate progeny of the original germ-cell. These cells, discharged by the bursting of the sporange, are of two kinds : namely, *spores*, each enclosed in a double spore-membrane; and *elaters*, which are very elongated cells, each containing a double spiral fibre coiled up in its interior. This fibre is so elastic that when the surrounding pressure is withdrawn by the bursting of the sporange the spores extend themselves (fig. 449), tearing apart the cell-membrane; and they do this so suddenly as to jerk forth the spores which may be adherent to their coils, and thus assist in their dispersion. The spores, when subjected to moisture, with a moderate amount of light and warmth, develop themselves into little collections of cells, which gradually assume the form of flattened fronds; and thus the species is very extensively multiplied, every one of the aggregate of spores which is the product of a single germ-cell being capable of giving origin to an independent individual.



FIG. 448.—Archegones of *Marchantia polymorpha*, in successive stages of development.

FIG. 449.—Elater and spores of *Marchantia*.

Marchantia is the type of the section known as the *thalloid* Hepaticæ. Another section, the *foliose* Hepaticæ, is represented by the genus *Jungermannia*, exceedingly common plants, of a moss-like habit, growing on moist banks and similar situations. While the structure of the sexual organs, and of the sporanges, resembles in its main features that of *Marchantia*, the vegetative organs are very different, consisting of a slender creeping stem

with small semi-transparent leaves. This distinct differentiation of stem and leaves indicates a decided advance in organisation, and marks the passage from the *thallophytic* to the *cormophytic* type of structure.

Musci.—There is not one of the tribe of *Mosses* whose external organs do not serve as beautiful objects when viewed with low powers of the microscope; while their more concealed wonders are admirably fitted for the detailed scrutiny of the practised observer. Mosses always possess a distinct axis of growth, commonly more or less erect, on which the minute and delicately formed leaves are



FIG. 450.—Structure of mosses: A, plant of *Funaria hygrometrica*, showing, *f* the leaves, *u* the sporanges supported upon the setæ or footstalks *s*, closed by the opercule *o*, and covered by the calypter *c*. B, sporanges of *Encalyptra vulgaris*, one of them closed and covered with the calypter, the other open; *u*, *u*, the sporanges; *o*, *o*, the opercules; *c*, calypter; *p*, peristome; *s*, *s*, setæ. C, longitudinal section of very young sporange of *Splachnum*; *a*, solid tissue forming the lower part of the capsule; *c*, columel; *l*, space around it for the development of the spores; *e*, epidermal layer of cells, thickened at the top to form the opercule *o*; *p*, two intermediate layers, from which the peristome will be formed; *s*, inner layer of cells forming the wall of the cavity.

arranged with great regularity. The stem shows some indication of the separation of a *cortical* or external portion from the *medullary* or central, by the intervention of a circle of bundles of elongated cells, which seem to prefigure the woody portion of the stem of higher plants, and from which prolongations pass into the leaves, so as to afford them a sort of midrib. The leaf usually consists of either a single or a double layer of cells, having flattened sides by which they adhere one to another; they rarely present any distinct epidermal layer: but such a layer, perforated by stomates of simple structure, is commonly found on the *seta* or bristle-like footstalk bearing the fructification, and sometimes on the midribs of the leaves. The rhizoids of mosses, like those of *Marchantia*, consist of long

ılar cells of extreme transparency, within which the protoplasm frequently be seen to circulate, as in the elongated cells of *ra*.

What has commonly been regarded as the 'fructification' of ses—namely, the 'urn' or 'capsule' filled with spores, which is



451.—Antherids and antherozoids of *Polytrichum commune*: A, group of herids, mingled with hairs and sterile filaments (paraphyses). Of the three herids, the central one is in the act of discharging its contents; that on the is not yet mature; while that on the right has already emptied itself, so that cellular structure of its walls becomes apparent. B, cellular contents of an herid, previously to the development of the antherozoids; C, the same, wing the first appearance of the antherozoids; D, the same, mature and charging the antherozoids.

e at the top of a long footstalk that springs from the centre of ster of leaves (fig. 450, A)—is not the real fructification, but roduct; for mosses, like liverworts, possess both *antherids* and *egones*. These organs are sometimes found in the same envelope *erigone*), sometimes on different parts of the same plant, some- s only on different individuals; but in either case they are

usually situated close to the axis, among the bases of the leaves. The 'antherids' are globular, oval, or elongated bodies (fig. 451, A), composed of aggregations of cells, of which the interior are 'sperm-cells,' each of which, as it comes to maturity, develops within itself an 'antherozoid' (B, C, D); and the antherozoids, set free by the rupture of the cells within which they are formed, make their escape by a passage that opens for them at the summit of the antherid. The antherids are generally surrounded by a cluster of hair-like filaments, composed of cells joined together (fig. 451, A), which are called *paraphyses*; these seem to be 'sterile' or undeveloped antherids. In the 'hair-moss,' *Polytrichum commune*, one of the largest of our mosses, common on dry heaths, these antherids are collected into conspicuous star-like clusters at the extremities of the branches of the 'male' plants. These are to be seen about April, and at the same time the archegones may be detected concealed among the leaves on the 'female' plants; while the capsules, or sporanges, in this and most other mosses, make their appearance late in the summer, and remain through the winter. The 'archegones' bear a general resemblance to those of *Marchantia* (fig. 448), and the fertilisation of their contained 'oöspheres,' or 'germ-cells,' is accomplished in the manner already described. The fertilised 'embryo-cell' becomes gradually developed by cell-division into a conical body elevated upon a stalk; and this at length tears across the walls of the flask-shaped archegone by a circular fissure, carrying the higher part upwards on its summit as a *calypter* or 'hood' (fig. 450, B, *c*), while the lower part remains to form a kind of collar round the base of the stalk, known as the *vagine*.

The urn, theca, or *sporange*, which is the immediate product of the generative act, is closed at its summit by an *opercule*, or lid (fig. 450, B, *o*, *o*), which falls off when the contents of the sporange



FIG. 452.—Mouth of sporange of *Funaria*, showing the peristome *in situ*.

FIG. 453.—Double peristome of *Fontinalis antipyretica*

are mature, so as to give them free exit: and the mouth thus laid open is surrounded, in many mosses, by a beautiful toothed fringe, which is termed the *peristome*. This fringe, as seen in its original undisturbed position (fig. 452), is a beautiful object for the binocular microscope; it is very 'hygrometric,' executing, when breathed on,

a curious movement which is probably concerned in the dispersion of the spores. In figs. 453–455 are shown three different forms of peristome, spread out and detached, illustrating the varieties which it exhibits in different genera of mosses ; varieties whose existence and readiness of recognition render them characters of extreme value to the systematic botanist, whilst they furnish objects of great interest and beauty for the microscopist. The peristome seems always to be originally double, one layer springing from the outer, and the other from the inner, of two layers of cells which may be always distinguished in the immature sporange; but one or other of these is frequently wanting at the time of maturity, and sometimes both are obliterated, so that there is no peristome at all. The number of the 'teeth' is always a 'power' of four, varying from four to sixty-four ; sometimes they are prolonged into straight or twisted hairs. The *spores*, or gonidial cells, are contained in the



FIG. 454.—Double peristome of *Bryum intermedium.*



FIG. 455.—Double peristome of *Cinclidium arcticum.*

upper part of the sporange, where they are clustered round a central pillar, which is termed the *columel.* In the young sporange the whole mass is nearly solid (fig. 450, C), the space (*l*) in which the spores are developed being very small ; but this gradually augments, the walls becoming more condensed ; and at the time of maturity the interior of the sporange is almost entirely occupied by the spores. These are formed in groups of four by the binary subdivision of the 'mother-cells' which first differentiate themselves from those forming the capsule itself. The capsule and seta of mosses together constitute the organ known as the *sporogone.* Thus, the 'spore-capsule' in liverworts and mosses, being the immediate product of the act of fertilisation (which constitutes the point of departure of each 'new generation'), is to be considered as the *progeny* of the plant that bears it ; which, supplying the nutriment at whose expense it develops itself, acts as its 'nurse.'

The development of the spore into a new plant commences with the rupture of its firm yellowish-brown outer coat or *exospore*, and the protrusion of its cell-wall proper or *endospore*, from the

projecting extremity of which new cells are put forth by a process of outgrowth, forming a sort of confervoid filament (as in fig. 462, C). At certain points of this filament its component cells multiply by subdivision, so as to form rounded clusters or buds, from every one of which an independent plant may arise ; so that several individuals may be evolved from a single spore. And as a numerous aggregate of spores is developed, as we have seen, from a single germ-cell, the rapid extension of mosses is thus secured, although no separate individual ever attains more than a very limited size.

The tribe of *Sphagnaceæ*, or 'bog-mosses,' is now separated by muscologists from true mosses on account of the marked differences by which they are distinguished, the three groups, *Hepaticæ*, *Bryaceæ* (or ordinary mosses), and *Sphagnaceæ* being ranked as together forming the group of *Muscineæ*. The stem of *Sphagnaceæ* is more distinctly differentiated than that of *Bryaceæ* into the central or medullary, the outer or cortical, and the intermediate or woody portions ; and a very rapid passage of fluid takes place through its elongated cells, especially in the medullary and cortical layers, so that if one of the plants be placed dry in a flask of water, with its rosette of leaves bent downwards, the water will speedily drop from this until the flask is emptied. The leaf-cells of the *Sphagnaceæ* exhibit a very curious departure from the ordinary type : for instead of being small and polygonal, they are large and elongated (fig. 456) : they contain no chlorophyll, but have spiral fibres loosely coiled in their interior ; and their membranous walls have large rounded apertures, by which their cavities freely communicate with one another, as is sometimes curiously evidenced by the passage of wheel-animalcules that make their habitation in these chambers. Between these coarsely spiral cells are some thick-walled narrow elongated cells containing chlorophyll ; these, which give to the leaf its firmness, do not, in the very young leaf, differ much in appearance from the others, the peculiarities of both being evolved by a gradual process of differentiation. The antherids, or male organs, of *Sphagnaceæ* resemble those of liverworts, rather than those of mosses, in their form and arrangement ; they are grouped in 'catkins' at the tips of lateral branches, each of the imbricated perigonal leaves enclosing a single globose antherid on a slender footstalk, and they are surrounded by very long branched paraphyses of cobweb-like tenuity. The female organs, or archegones, which do not differ in structure from those of mosses, are grouped together in a sheath of deep green



FIG. 456.—Portion of the leaf of *Sphagnum*, showing the large empty cells, *a*, *a*, *a*, with spiral fibres and communicating apertures; and the intervening bands, *b*, *b*, *b*, composed of small elongated chlorophyllous cells.

aves at the end of one of the short lateral branchlets at the side of he rosette or terminal crown of leaves. The two sets of organs re always distributed on different branches, and in some instances n different plants. The 'sporange' which is formed as the product f the impregnation of the germ-cell is very uniform in all the pecies, being almost spherical, with a slightly convex lid, without eak or point, and showing no trace of a peristome; and the spores t contains are produced in groups of four (as in mosses) around a hemispherical 'columel.' Besides the ordinary spores, however, he *Sphagnaceæ* sometimes develop a smaller kind, the 'microspores,' ormed by a further division of the mother-cells; the significance of hese is unknown. The ordinary spores when germinating do not produce the branched confervoid filament of true mosses, but if growing on wet peat evolve themselves into a lobed foliaceous 'prothallium,' resembling the frond of liverworts; whilst if they levelop in water a single long filament is formed, of which the ower end gives off rhizoids, while the upper enlarges into a bud rom which the young plant is evolved. In either case the prothallium and its temporary roots wither away as soon as the young plant begins to branch. From their extraordinary power of imbibing nd holding water, the *Sphagnaceæ* are of great importance in the conomy of Nature, clothing with vegetation many areas which would otherwise be sterile, and serving as reservoirs for storing up noisture for the use of higher forms of vegetation.

Filices.—In the general structure of *Ferns* we find a much nearer pproximation to flowering plants; but this does not extend to heir reproductive apparatus, which is formed upon a type essentially he same as that of mosses, though evolved at a very different period f life. As the tissues of which their fabrics are composed are ssentially the same as those to be described in the next chapter, it will not e requisite here to dwell upon them. The stem (where it exists) is for the nost part made up of cellular parenchyme, which is separated into a ortical and a medullary portion by the nterposition of a circular series of ibro-vascular bundles containing true oody tissue and ducts. These bundles orm a kind of irregular network, from vhich prolongations are given off that ass into the leaf-stalks, and thence nto the midrib and its lateral branches; nd it is their peculiar arrangement in he leaf-stalk of the common brake which ives to the transverse section the marking commonly known as 'King Charles n the oak.' A thin section, especially if somewhat oblique (fig. 457), isplays extremely well the peculiar character of the ducts of the ern, which are termed 'scalariform' from the resemblance of the egular markings on their walls to the rungs of a ladder. These



FIG. 457.—Oblique section of footstalk of fern leaf, showing bundle of scalariform ducts.

bundles of scalariform ducts or 'tracheïdes' are usually surrounded by sheaths of *sclerenchyme*, tissue composed of cells the walls of which have become very hard and of a deep brown colour. These sclerenchymatous sheaths are a very conspicuous feature in a transverse section of the stem or rhizome of most ferns, and are the principal agent in giving it strength and solidity.

What is usually considered the *fructification* of the fern affords a most beautiful and readily prepared class of opaque objects for the lower powers of the microscope; nothing more being necessary than to lay a fragment of the frond that bears it upon the glass stage-plate or to hold it in the stage-forceps, and to throw an adequate light upon it by the side-condenser. It usually presents itself in the form of isolated spots on the under surface of the frond termed *sori*,

FIG. 458.—Leaflet of *Polypodium*, with sori.



FIG. 459.—Portion of frond of *Hæmionitis*, with sori.

as in the common *Polypodium* (fig. 458), and in *Aspidium* (fig. 460); but sometimes these 'sori' are elongated into bands, as in the common *Scolopendrium* (hart's-tongue); and these may coalesce with each other, so as almost to cover the surface of the frond with a network, as in *Hæmionitis* (fig. 459); or they may form merely a single band along its borders, as in the common *Pteris* (brake-fern). The sori are sometimes 'naked' on the under surface of the fronds; but they are frequently covered with a delicate membrane termed the *indusium*, which may either form a sort of cap upon the summit of each sorus, as in *Aspidium* (fig. 460), or a long fold, as in *Scolopendrium* and *Pteris*; or a sort of cup, as in *Deparia* (fig. 461). Each of these sori, when sufficiently magnified, is found to be made up of a multitude of *sporanges*, or spore-capsules (figs. 460, 461),

which are sometimes closely attached to the surface of the frond, but more commonly spring from it by a pedicel or footstalk. The wall of the sporange is composed of flattened cells, applied to each other by their edges; but there is generally one row of these thicker and larger than the rest which springs from the pedicel, and is continued over the summit of the sporange, so as to form a projecting ring, which is known as the *annulus* (fig. 461). This ring has an elasticity superior to that of all the rest of the capsular wall, causing it to split across when mature, so that the contained spores may escape; and in many instances the two halves of the sporange are carried widely apart from each other, the fissure extending to such a depth as to separate them completely. In *Osmunda* (the so-called 'flowering fern') and *Ophioglossum* (adder's tongue) the sporanges have no annulus. It will frequently happen that specimens of fern-fructification gathered for the microscope will be found to have all the sporanges burst and the spores dispersed, whilst in others less advanced the sporanges may all be closed; others, however, may often be met with in which some of the sporanges are closed and others are

FIG. 460.—Sorus and indusium of *Aspidium*.

FIG. 461.—Sorus and cup-shaped indusium of *Deparia prolifera*.

open; and if these be watched with sufficient attention the rupture of some of the sporanges and the dispersion of the spores may be observed to take place whilst the specimen is under observation in the field of the microscope. In sori whose sporanges have all burst, the annuli connecting their two halves are the most conspicuous objects, looking, when a strong light is throw upon them, like strongly banded worms of a bright brown hue. This is particularly the case in *Scolopendrium*, whose elongated sori are remarkably beautiful objects for the microscope in all their stages; until quite mature, however, they need to be brought into view by turning back the two indusial folds that cover them. The commonest ferns, indeed, which are found in almost every hedge, furnish objects of no less beauty than those yielded by the rarest exotics; and it is in every respect a most valuable training to the young to teach them how much may be found to interest, when looked for with intelligent eyes, even in the most familiar, and therefore disregarded, specimens of Nature's handiwork.

The 'spores' (fig. 462, A) set free by the bursting of the spor-

anges usually have a somewhat angular form, and are invested by a yellowish or brownish outer coat, the *exospore*, which is marked very much in the manner of pollen-grains (fig. 507) with points, streaks, ridges, or reticulations. When placed upon a damp surface, and exposed to a sufficiency of light and warmth, the spore begins to germinate, the first indication of its vegetative activity being a slight enlargement, which is manifested in the rounding off of its angles. This is followed by the putting forth of a tubular prolongation (fig. 462, B, *a*) of the internal cell-wall or *endospore* through an aperture in the outer spore-coat; and moisture being absorbed through this, the cell becomes so distended as to burst the external unyielding integument, and soon begins to elongate itself in a direction opposite to that of the first rhizoid. A production of new cells by subdivi-



FIG. 462.—Development of prothallium of *Pteris serrulata*: A, spore set free from the sporange; B, spore beginning to germinate, putting forth the tubular prolongation *a*, from the principal cell *b*; C, first-formed linear series of cells; D, prothallium taking the form of a leaf-like expansion; *a*, first, and *b*, second rhizoid: *c*, *d*, the two lobes, and *e*, the indentation between them; *f*, *f*, first-formed part of the prothallium; *g*, external coat of the original spore; *h*, *h*, antherids.

sion then takes place from its growing extremity; this at first proceeds in a single series, so as to form a kind of confervoid filament (C); but the multiplication of cells by subdivision soon takes place transversely as well as longitudinally, so that a flattened leaf-like expansion (D) is produced, so closely resembling that of a young *Marchantia* as to be readily mistaken for it. This expansion, which is termed the *prothallium*, varies in its configuration in different species, but its essential structure always remains the same. From its under surface are developed not merely the rhizoids (*a*, *b*), which serve at the same time to fix it in the soil and to supply it with moisture, but also the *antherids* and *archegones*, which constitute the true representatives of the essential parts of the flower of higher plants. Some of the former may be distinguished at an early period of the development of the prothallium (*h*, *h*); and at the time of its

omplete evolution these bodies are seen in considerable numbers, specially in the neighbourhood of the rhizoids. Each has its origin n a peculiar protrusion that takes place from one of the cells of the rothallium (fig. 463, A, *a*); this is at first entirely filled with hlorophyll-granules, but soon cell-division sets up in it. A central ell *b* becomes distinguished from all the rest by its much larger size, nd is surrounded by one r two layers of much maller cells known as he *tapetal* or *mantle-ells*. These take no art in the formation of he antherozoids; but he protoplasmic con-ents of the large central ell divide by free-cell ormation into a large umber of cells known as he *antherozoid-mother-ells* (*c*); each of these gain breaks up into our cells, not at first rovided with cell-walls, he *sperm-cells*. Each f the sperm-cells (B, *e*) s seen, as it approaches naturity, to contain a pirally-coiled filament; nd when set free by he bursting of the ntherid the sperm-cells themselves burst, and give exit to their antherozoids (C), which execute rapid move-ments of rotation on their axes, partly de-pendent on the long ilia with which they are furnished.



FIG. 463.—Development of the antherids and antherozoids of *Pteris serrulata*: A, projection of one of the cells of the prothallium, showing the antheridial cell *b*, with its sperm-cells *e*, within the cavity of the original cell *a*. B, antherid completely developed; *a*, wall of antheridial cell; *e*, sperm-cells, each enclosing an antherozoid. C, antherozoid more highly magnified, showing its large extremity *a*, its small extremity *b*, and its cilia *d*, *d*.



FIG. 464.—Archegone of *Pteris serrulata*: A, as seen from above; *a*, *a*, *a*, cells surrounding the base of the cavity; *b*, *c*, *d*, successive layers of cells, the highest enclosing a quadrangular orifice. B, side view, showing A, A, cavity containing the germ-cell, *a*; B, B, walls of the archegone, made up of the four layers of cells, *b*, *c*, *d*, *e*, and having an opening, *f*, on the summit; *c*, *c*, antherozoids within the cavity; *g*, large extremity; *h*, vibratile cilia; *i*, small extremity in contact with the germ-cell, and dilated.

The *archegones* are fewer in number, and are found upon a different part of the prothallium. Each of them originates in a single cell of its superficial layer, which undergoes subdivision by a horizontal partition. Of the two cells thus produced the upper gives origin, by successive subdivisions, to the 'neck' of the archegone, which, when fully developed (fig. 464), is composed of twelve or more cells, built up in layers of four cells each, one upon another, so as to form a kind of chimney or shaft. The lower of the

two first-formed cells becomes the *central cell* of the archegone; and this again undergoing horizontal subdivision, the lower half becomes the *oösphere* or *germ-cell*, whilst the upper extends itself into the *neck*. By the conversion into mucilage of a central row, an open passage or *canal* is formed, through which the antherozoids make their way to the oösphere lying at its bottom (fig. 464, B, *a*). The oösphere, when fertilised by the penetration of the antherozoids, becomes the 'embryo-cell' of a new plant, the development of which speedily commences.[1] In the aberrant group of *Ophioglossaceæ* (adder's-tongue ferns), the development of the prothallium takes place underground, in the form of a small roundish tuber, composed of parenchymatous tissue containing no chlorophyll, and producing antherids and archegones on its upper surface.

The early development of the embryo-cell takes place according to the usual method of repeated subdivision, producing a homogeneous globular mass of cells. Soon, however, rudiments of special organs begin to make their appearance; the embryo grows at the expense of the nutriment prepared for it by the prothallium: and it bursts forth from the cavity of the archegone, which organ in the meantime is becoming atrophied. In the very beginning of its development the tendency is seen in the cells of one extremity to grow upward so as to evolve the stem and leaves, and in those of the other extremity to grow downward to form the root; and when these organs have been sufficiently developed to absorb and prepare the nutriment which the young fern requires, the prothallium decays away. Thus, then, the 'spore' of the fern must be considered as a generative 'gonid' or detached flower-bud, capable of developing itself into a prothallium that may be likened to a receptacle bearing the sexual apparatus. But this prothallium serves the further purpose of 'nursing' the embryos originated by the generative act; which embryos finally develop themselves, not, as in mosses, into

[1] The study of the development of the spores of ferns, and of the act of fertilisation and of its products, may be conveniently prosecuted as follows:—Let a frond of a fern whose fructification is mature be laid upon a piece of fine paper, with its spore-bearing surface downwards; in the course of a day or two this paper will be found to be covered with a very fine brownish dust, which consists of the discharged spores. This must be carefully collected, and should be spread upon the surface of a smoothed fragment of porous sandstone, the stone being placed in a saucer, the bottom of which is covered with water; and a glass tumbler being inverted over it, the requisite supply of moisture is ensured, and the spores will germinate luxuriantly. Some of the prothallia soon advance beyond the rest; and at the time when the advanced ones have long ceased to produce antherids, and bear abundance of archegones, those which have remained behind in their growth are beginning to be covered with antherids. If the crop be now kept with little moisture for several weeks, and then suddenly watered, a large number of antherids and archegones simultaneously open; and in a few hours afterwards the surface of the larger prothallia will be found almost covered with moving antherozoids. Such prothallia as exhibit freshly opened archegones are now to be held by one lobe between the forefinger and thumb of the left hand, so that the upper surface of the prothallium lies upon the thumb; and the thinnest possible sections are then to be made with a thin narrow-bladed knife, perpendicularly to its surface. Of these sections, which, after much practice, may be made no more than one-fifteenth of a line in thickness, some will probably lay open the canals of the archegones; and within these, when examined with a power of 200 or 300 diameters, antherozoids may be occasionally distinguished. The prothallium of the common *Osmunda regalis* will be found to afford peculiar facilities for observation of the development of the antherids, which are produced at its margin.

mere sporogones, but, as in Phanerogams, into entire plants, complete in everything but the true generative organs, which evolve themselves from the detached spores.

The singular discovery has recently been made by the researches of De Bary, Farlow, and others, that the ordinary *alternation of generations* in ferns may be interrupted by the suppression either of the *sporophyte*, the asexual or spore-bearing generation, or of the *oöphyte* or sexual generation which bears the true reproductive organs. These phenomena are called respectively *apospory* and *apogamy*. The former has been observed especially in varieties of *Athyrium Filix-fœmina* and *Polystichum angulare*, and is shown by the production of prothalloid structures bearing antherids and archegones on the fronds in the place of ordinary sori. The latter occurs not unfrequently in *Pteris serrulata*, the sporophytic generation springing directly from the prothallium without the intervention of archegones and antherids.

The little group of **Equisetaceæ** (Horse-tails) which seem nearly allied to the Ferns in the type of their generative apparatus, though that of their vegetative portion is very different, affords certain objects of considerable interest to the microscopist. The whole of their structure is penetrated to such an extraordinary degree by *silex*, that even when its organic portion has been destroyed by prolonged maceration in dilute nitric acid, a consistent skeleton still remains. This mineral, in fact, constitutes in some species not less than 13 per cent. of the whole solid matter, and 50 per cent. of the inorganic ash ; and it especially abounds in the epiderm, which is used by cabinet makers for smoothing the surface of wood. Some of the silicious particles are distributed in two lines, parallel to the axis ; others, however, are grouped into oval forms, connected with each other, like the jewels of a necklace, by a chain of particles forming a sort of curvilinear quadrangle ; and these (which are, in fact, the particles occupying the guard-cells of the stomates) are arranged in pairs. Their form and arrangement are peculiarly well seen under polarised light, for which the prepared epiderm is an extremely beautiful object ; and it is asserted by Sir D. Brewster (whose authority upon this point has been generally followed) that each silicious particle has a regular axis of double refraction. What is usually designated as the fructification of the Equisetaceæ forms a cone or spike at the extremity of certain of the stem-like branches (the real stem being a horizontal rhizome), and consists of a cluster of shield-like discs, each of which carries a circle of *sporanges* or spore-capsules, that open by longitudinal slits to set free the spores. Each of these spores has attached to it two pairs of elastic filaments (fig. 465) called *elaters* ; these are at first coiled up around the spore, in the manner represented at A, though more closely applied to the surface ; but, on the liberation of the spore, they extend themselves in the manner shown at B, the slightest application of moisture, however, serving to make them close together (the assistance which they afford in the dispersion of the spores being no longer required) when the spores have alighted on a damp surface. If a number of these spores be spread out on a slip of glass under the

field of view, and, whilst the observer watches them, a bystander breathes gently upon the glass, all the filaments will be instantaneously put in motion, thus presenting an extremely curious spectacle, and will almost as suddenly return to their previous condition when the effect of the moisture has passed off. If one of the sporanges which has opened, but has not discharged its spores, be mounted in a cell with a movable cover, this curious action may be exhibited over and over again. These spores, like those of ferns, develop into a prothallium; and this bears antherids and archegones, the former at the extremities of the lobes, and the latter in the angles between them.

Nearly allied to Ferns, also, is a curious little group of small aquatic plants, the **Rhizocarpeæ** (or Pepper-worts), which either float on the surface or creep along shallow bottoms. These all agree in having two kinds of spore, produced in separate sporanges; the larger, or 'megaspores,' giving origin to prothallia which produce archegones only; and the smaller, or 'microspores,' undergoing progressive subdivision, usually without the formation of a distinct prothallium, each of the cells thus formed giving origin to an antherozoid. In this, as we shall presently see, there is a distinct fore-



FIG. 465.—Spores of *Equisetum*, with their elatera.

shadowing of the mode in which the generative process is performed in flowering plants, the 'microspore' obviously corresponding to the pollen-grain, while the 'megaspore' may be considered to represent the primitive cell of the ovule.

Another alliance of Ferns is to the **Lycopodiaceæ** (Club-mosses), a group which at the present time attains a great development in warm climates, and which, it would seem, constituted a large part of the arborescent vegetation of the Carboniferous epoch. In the *Lycopodieæ* proper the sporanges are all of one kind, and all the spores are of the same size, each, as in *Ophioglossum*, giving origin to a subterraneous prothallium that develops both antherids and archegones. The plant which originates from the fertilised 'germ-cell' of the archegone attains in colder climates only a moss-like growth, with a creeping stem usually branching dichotomously, and imbricated leaves; but is distinguished from the true mosses, not only by its higher general organisation (which is on a level with that of ferns), but by the character of its fructification, which is a club-shaped 'spike,' bearing small imbricated leaves, in the axils of which lie the sporanges. The spores developed within these are remarkable for the large quantity of oily matter they contain, giving them an

inflammability that causes their being used in theatres to produce 'artificial lightning.' But in the allied groups of *Selaginelleæ* and *Isoeteæ* there are (as in the *Rhizocarpeæ*) two kinds of spore produced in separate sporanges; one set producing 'megaspores,' from which archegone-bearing prothallia are developed, and the other producing 'microspores,' which, by repeated subdivision, give origin to antherozoids without the formation of prothallia. It is a very interesting indication of a tendency towards the phanerogamic type of sexual generation, that the prothallium in this group is chiefly developed *within* the sporange, forming a kind of 'endosperm,' only the small part which projects from the ruptured apex of the spore producing one or more archegones. The arborescent *Lepidodendra* and *Sigillariæ* of the Coal-measures seem to have formed connecting links between the *Vascular Cryptogams* and the *Phanerogams*, alike in the structure of their stems and in their fructification. For the *Lepidostrobi* or cone-like 'fruit' of these trees represent the club-shaped spikes of the *Lycopodiaceæ*; and seem to have borne 'megaspores' in the sporanges of its basal portion, and 'microspores' in those of its upper part. Some of the best seams of coal appear to have been chiefly formed by the accumulation of these 'megaspores.'

Thus, in our ascent from the lower to the higher Cryptogams, we have seen a gradual change in the general plan of structure, bringing their superior types into a close approximation to the flowering plant, which is undoubtedly the highest form of vegetation. But we have everywhere encountered a mode of generation which, whilst essentially the same throughout the series, is no less essentially distinct from that of the Phanerogam, the fertilising material of the 'sperm-cells' being embodied, as it were, in self-moving filaments, the antherozoids, which find their way to the 'germ-cells' by their own independent movements, and the 'embryo-cell' being destitute of that store of prepared nutriment which surrounds it in the true seed, and supplies the material for its early development. In the lower Cryptogams we have seen that the fertilised oöspore is thrown at once upon the world (so to speak) to get its own living; but in ferns and their allies the 'embryo-cell' is nurtured for a while by the prothallium of the parent plant. While the true *reproduction of the species* is effected by the proper generative act, the *multiplication of the individual* is accomplished by the production and dispersion of 'gonidial' spores; and this production, as we have seen, takes place at very different periods of existence in the several groups, dividing the life of each into two separate epochs, in which it presents itself under two very distinct phases that contrast remarkably with each other. Thus, the frond of *Marchantia*, evolved from the spore and bearing the antherids and archegones, is that which seems naturally to constitute *the* plant; but that which represents this phase in the ferns is the minute *Marchantia*-like prothallium. In ferns, on the other hand, the product into which

the fertilised 'embryo-cell' evolves itself is that which is commonly regarded as *the* plant; and this is represented in the liverworts and mosses by the sporogone alone.[1] We shall encounter a similar diversity (which has received the inappropriate designation of 'alternation of generations') in some of the lower forms of the animal kingdom.

[1] For more detailed information on the structure and classification of the Cryptogams generally the reader is referred to Goebel's *Outlines of Classification and Special Morphology*, and De Bary's *Comparative Anatomy of the Phanerogams and Ferns*, translations of both of which have been published by the Clarendon Press; and especially to Bennett and Murray's *Handbook of Cryptogamic Botany*, published by Longmans (London, 1889).

CHAPTER XI

OF THE MICROSCOPIC STRUCTURE OF PHANEROGAMIC PLANTS

BETWEEN the two great divisions of the Vegetable Kingdom which are known as *Cryptogamia* and *Phanerogamia* the separation is by no means so abrupt as it formerly seemed to be. For, as has been already shown, though the Cryptogamia were formerly regarded as altogether non-sexual, a true generative process, requiring the concurrence of male and female elements, is traceable almost throughout the series. And in the higher types of that series we have seen a foreshadowing of those provisions for the nurture of the fertilised embryo which constitute the distinctive characters of the Phanerogamia. On the other hand, although we are accustomed to speak of *Phanerogamia* as 'flowering plants,' yet not only are the conspicuous parts of the flower often wanting, but in the important group of *Gymnosperms* (including the *Coniferæ* and *Cycadeæ*) the essential parts of the generative apparatus are reduced to a condition closely approximating to that of the higher Cryptogams. There are, however, certain fundamental differences between the modes in which the act of fertilisation is performed in the two groups. For (1) whilst in all the higher Cryptogams it is in the condition of free-moving 'antherozoids' that the contents of the sperm-cell find their way to the germ-cell; these are conveyed to it, throughout the phanerogamic series, by an extension of the lining membrane of the sperm-cell or pollen-grain into a tube, which penetrates to the germ-cell, contained in the interior of the body called the 'ovule.' Again (2), while the 'germ-cell' or oösphere in the higher Cryptogams is contained in a structure that originated in a spore detached from the parent plant, it is not only formed and fertilised in all Phanerogams whilst still borne on the parent fabric, but continues for some time to draw from it the nutriment it requires for its development into the 'embryo.' And at the time of its detachment from the parent the matured 'seed' contains, not merely an 'embryo' already advanced a considerable stage, but a store of nutriment to serve for its further development during germination. As there is nothing parallel to this among Cryptogams, it may be said that reproduction by *seeds*, not the possession of flowers, is the distinctive character of Phanerogams. The *ovules*, which when fertilised and matured become seeds, are developed from specially modified leaves, which remain open in Gymnosperms, but which in all other Phanerogams fold together so as to enclose the ovules within an 'ovary.' Each ovule consists of a

'nucellus' surrounded by 'integuments' which remain unclosed at the apex, leaving open a short canal termed the 'micropyle' or 'foramen.' One cell of the nucleus undergoes great enlargement, and becomes the *embryo-sac*, whose cavity is filled, in the first instance, with a mucilaginous fluid containing protoplasm. At the end of the embryo-sac which lies nearest the micropyle a germ-cell or 'oösphere' is developed; in Phanerogams by free cell-formation, but in Gymnosperms indirectly after the formation of a 'corpuscle,' which represents the archegone of *Selaginella*. By a further process of free cell-formation the remainder of the embryo-sac comes to be filled with cells, constituting what is termed the 'endosperm'; and this serves, like the prothallium of ferns, to imbibe and prepare nutriment which is afterwards appropriated by the embryo. In many seeds (as those of the *Leguminosæ*) the whole nutritive material of the endosperm has been absorbed into the 'cotyledons' (or seed-leaves) of the embryo by the time that the seed is fully matured and independent of the parent; but in other cases it remains as a 'separate endosperm.' In either case it is taken into the substance of the embryo during its germination.

Elementary Tissues.—No marked change shows itself in general organisation as we pass from the cryptogamic to the phanerogamic series of plants. For a large proportion of the fabric of even the most elaborately formed tree (including the parts most actively concerned in living action) is made up of components of the very same kind as those which constitute the entire organisms of the simplest cryptogams. For, although the stems, branches, and roots of trees and shrubs are principally composed of *woody* tissue, such as we do not meet with in any but the highest Cryptogams, yet the special office of this is to afford mechanical support; when it is once formed, it takes no further share in the vital economy than to serve for the conveyance of fluid from the roots upwards through the stem and branches to the leaves; and even in these organs, not only the pith and the cortex, with the 'medullary rays,' which serve to connect them, but the 'cambium layer' intervening between the bark and the wood in which the periodical formation of the new layers both of bark and wood takes place, are composed of *cellular* substance. This tissue is found, in fact, wherever *growth* is taking place: as, for example, in the growing points of the root-fibres, in the leaf-buds and leaves, and in the flower-buds and sexual parts of the flower: it is only when these organs attain an advanced stage of development that *woody* structure is found in them, its function (as in the stem) being merely to give support to their softer textures; and the small proportion of their substance which it forms is at once seen in those beautiful 'skeletons' which, by a little skill and perseverance, may be made of leaves, flowers, and certain fruits. All the softer and more pulpy tissue of these organs is composed of cells more or less compactly aggregated together, and having forms that approximate more or less closely to the globular or ovoidal, which may be considered as their original type.

As a general rule, the rounded shape is preserved only when the cells are but loosely aggregated, as in the parenchymatous (or pulpy)

stance of leaves, which often forms a distinct layer known as the ngy parenchyme' immediately beneath the epiderm of the upper ace (fig. 466), and it is then only that the distinctness of their ls become evident. When the tissue becomes more solid, the s of the vesicles are ssed against each er, so as to flatten n and to bring them close apposition, then the cavities adjacent cells are arated by a single par- n wall. Frequently appens that the pres- e is exerted more in direction than in ther, so that the form sented by the outline he cell varies accord- to the direction in ch the section is le. This is well wn in the pith of the ng shoots of elder, c, or other rapidly wing trees, the cells of which, when cut transversely, generally ibit circular outlines; whilst, when the section is made verti- y, their borders are straight, so as to make them appear like



FIG. 466.—Section of leaf of *Agave*, treated with dilute nitric acid, showing the protoplasmic contents contracted in the interior of the cells: *a*, epidermal cells; *b*, guard-cells of the stomate; *c*, cells of parenchyme; *d*, their protoplasmic contents.



FIG. 467.—Sections of cellular parenchyme of *Aralia*, or rice-paper plant: A, transversely to the axis of the stem; B, in the direction of the axis.

es or elongated prisms, as in fig. 466. A very good example of h a cellular parenchyme is to be found in the substance known as *-paper*, which is made by cutting the herbaceous stem of a nese plant termed *Aralia papyrifera* vertically round and round

with a long sharp knife, so that its tissues may be (as it were) unrolled in a sheet. The shape of its cells when thus prepared is irregularly prismatic, as shown in fig. 467, B; but if the stem be cut transversely, their outlines are seen to be circular or nearly so (A). When, as often happens, the cells have a very elongated form, this elongation is in the direction of their growth, which is that, of course, wherein there is least resistance. Hence their greatest length is nearly always in the direction of the axis; but there is one remarkable exception, that, namely, which is afforded by the 'medullary rays' of exogenous stems whose cells are greatly elongated in the horizontal direction (fig. 489, *a*), *their* growth being from the centre of the stem towards its circumference. It is obvious that fluids will be more readily transmitted in the direction of greatest elongation, being that in which they will have to pass through the least number of partitions: and whilst their ordinary course is in the direction of the *length* of the roots, stems, or branches, they will be enabled by means of the medullary rays to find their way in the *transverse* direction.



FIG. 468.—Section of stellate parenchyme of *rush*.

One of the most curious varieties of form which vegetable cells present is the *stellate* cell, represented in fig. 468, forming the spongy parenchymatous substance in the stems of many aquatic plants, of the *rush* for example, which are furnished with air-spaces. In other instances these air-spaces are large cavities which are altogether left void of tissue: such is the case in the *Nuphar lutea* (yellow water-lily), the footstalks of whose leaves contain large air-chambers, the walls of which are built up of very regular cubical cells, whilst some curiously formed large stellate cells project into the cavity which they bound (fig. 469). The dimensions of the component vesicles of cellular tissue are extremely variable; for although their diameter is very commonly between $\frac{1}{300}$th and $\frac{1}{500}$th of an inch, they occasionally measure as much as $\frac{1}{30}$th of an inch across, whilst in other instances they are not more than $\frac{1}{300}$th.



FIG. 469.—Cubical parenchyme, with stellate cells, from petiole of *Nuphar lutea*.

The cells of a growing tissue are always formed, as we have seen, by cell-division, that is, by the formation of cellulose walls across

cells previously in existence. The original cell-wall must therefore always be single. It is only in older thick-walled cells that a line of demarcation becomes obvious in the form of an intermediate lamella, at one time called 'intercellular substance,' and supposed to be a distinct structure, but now shown to be the result merely of a difference in density or molecular structure of the cell-walls during their thickening. This layer very frequently ultimately assumes a mucilaginous character. Where cells have a rounded outline, it is obvious that 'intercellular spaces' must exist between them; and as the tissue develops, these spaces often increase greatly in size. They are called 'schizogenous' if formed simply by the parting of cells from one another; 'lysigenous' if resulting from the disappearance or absorption of cells. Recent observations have shown that the wall of intercellular spaces is frequently clothed with a lining of protoplasm. There are many forms of fully developed cellular parenchyme, in which, in consequence of the loose aggregation of their component cells, these may be readily isolated, so as to be prepared for separate examination without the use of reagents which alter their condition; this is the case with the pulp of ripe fruits, such as the strawberry or currant (the snowberry is a particularly favourable subject for this kind of examination), and with the parenchyme of many fleshy leaves, such as those of the carnation (*Dianthus caryophyllus*) or the London pride (*Saxifraga umbrosa*). Such cells usually contain evident *nuclei* which are turned brownish-yellow by iodine, whilst their membrane is only turned pale yellow, and in this way the nucleus may be brought into view, when, as often happens, it is not previously distinguishable. If a drop of the iodised solution of chloride of zinc be subsequently added, the cell-membrane becomes of a beautiful blue colour, whilst the nucleus and the granular protoplasm that surrounds it retain their brownish-yellow tint. The use of dilute nitric or sulphuric acid, of alcohol, of syrup, or of several other reagents, serves to bring into view the *primordial* or *parietal utricle*, its contents being made to coagulate and shrink, so that it detaches itself from the cellulose wall with which it is ordinarily in contact, and shrivels up within its cavity, as shown in fig. 466. It would be a mistake, however, to regard this as a distinct membrane; for it is nothing else than the peripheral layer of protoplasm, naturally somewhat more dense than that which it includes, but passing into it by insensible gradations.

It is probable that all cells, at some stage or other of their growth, exhibit, in a greater or less degree of intensity, that curious movement of *cyclosis* which has been already described as occurring in the *Characeæ*, and which consists in the steady flow of one or of several currents of protoplasm over the inner wall of the cell, this being rendered apparent by the movement of the particles which the current carries along with it. The best examples of it are found among submerged plants, in the cells of which it continues for a much longer period than it usually does elsewhere; and among these are two, *Vallisneria spiralis* and *Anacharis alsinastrum* (or *Elodea canadensis*), which are peculiarly fitted for the exhibition of this interesting phenomenon. *Vallisneria* is an aquatic plant

that grows abundantly in the rivers of the south of Europe, but is not a native of this country; it may, however, be readily grown in a tall glass jar having at the bottom a couple of inches of mould, which, after the roots have been inserted into it, should be closely pressed down, the jar being then filled with water, of which a portion should be occasionally changed.[1] The jar should be freely exposed to light, and should be kept in as warm but equable a temperature as possible. The long grass-like leaves of this plant are too thick to allow the transmission of sufficient light through them for the purpose of this observation, and it is requisite to make a thin slice or shaving with a sharp knife. If this be taken from the surface, so that the section chiefly consists of the superficial layer of cells, these will be found to be small, and the particles of chlorophyll, though in great abundance, will rarely be seen in motion. This layer should therefore be sliced off (or, perhaps still better, scraped away) so as to bring into view the deeper layer, which consists of larger cells, some of them greatly elongated, with particles of chlorophyll in smaller number, but carried along in active rotation by the current of protoplasm; and it will often be noticed that the directions of the rotation in contiguous cells are opposite. If the movement (as is generally the case) be checked by the shock of the operation, it will be revived again by gentle warmth; and it may continue under favourable circumstances, in the separated fragment, for a period of weeks, or even of months. Hence, when it is desired to exhibit the phenomenon, the preferable method is to prepare the sections a little time before they are likely to be wanted, and to carry them in a small vial of water in the waistcoat pocket, so that they may receive the gentle and continuous warmth of the body. In summer, when the plant is in its most vigorous state of growth, the section may be taken from any one of the leaves; but in winter it is preferable to select those which are a little yellow. An objective of $\frac{1}{4}$-inch focus will serve for the observation of this interesting phenomenon, and very little more can be seen with a $\frac{1}{8}$-inch; but the $\frac{1}{25}$-inch constructed by Messrs. Powell and Leland enables the borders of the protoplasmic current, which carries along the particles of chlorophyll, to be distinctly defined; and this beautiful phenomenon may be most luxuriously watched under their patent binocular.

Anacharis alsinastrum is a water-weed which, having been accidentally introduced into this country many years ago, has since spread itself with such rapidity through our canals and rivers as in many instances seriously to impede their navigation. It does not require to root itself in the bottom, but floats in any part of the water it inhabits; and it is so tenacious of life that even small fragments are sufficient for the origination of new plants. The leaves have no distinct epiderm, but are for the most part composed of two layers of cells, and these are elongated and colourless in the centre, forming a

[1] Mr. Quekett found it the most convenient method of changing the water in the jars in which *Chara*, *Vallisneria*, &c. are growing, to place them occasionally under a water-tap, and allow a very gentle stream to fall into them for some hours; for by the prolonged overflow thus occasioned all the impure water, with the *Conferva* that is apt to grow on the sides of the vessel, may be readily got rid of.

kind of midrib; towards the margins of the leaves, however, there is but a single layer. Hence no preparation whatever is required for the exhibition of this interesting phenomenon, all that is necessary being to take a leaf from the stem (one of the older yellowish leaves being preferable), and to place it with a drop of water, either in the aquatic-box or on a slip of glass beneath a thin glass cover. A higher magnifying power is required, however, than that which suffices for the examination of the cyclosis in *Chara* or in *Vallisneria*, the $\frac{1}{8}$-inch object glass being here preferable to the $\frac{1}{4}$-in., and the assistance of the achromatic condenser being desirable. With this amplification the phenomenon may be best studied in the single layer of marginal cells, although when a lower power is used it is most evident in the elongated cells forming the central portion of the leaf. The number of chlorophyll-granules in each cell varies from three or four to upwards of fifty; they are somewhat irregular in shape, some being nearly circular flattened discs, whilst others are oval; and they are usually from $\frac{1}{300}$th to $\frac{1}{500}$th of an inch in diameter. When the rotation is active the greater number of these granules travel round the margin of the cells, a few, however, remaining fixed in the centre; their rate of movement, though only $\frac{1}{10}$th of an inch per minute, being sufficient to carry them several times round the cell within that period. As in the case of *Vallisneria*, the motion may frequently be observed to take place in opposite directions in contiguous cells. The thickness of the layer of protoplasm in which the granules are carried round is estimated by Mr. Wenham at no more than $\frac{1}{3000}$th of an inch. When high powers and careful illumination are employed, delicate ripples may be seen in the protoplasmic currents.[1]

Cyclosis, however, is by no means restricted to submerged plants; for it has been witnessed by numerous observers in so great a variety of other species that it may fairly be presumed to be universal. It is especially observable in the *hairs* of the epidermal surface. Such hairs are furnished by various parts of plants; and what is chiefly necessary is, that the part from which the hair is gathered should be in a state of vigorous growth. The hairs should be detached by tearing off with a pair of fine pointed forceps the portion of the epiderm from which they spring, care being taken not to grasp the hair itself, whereby such an injury would be done to it as to check the movement within it. The apochromatic hair should then be placed with a drop of water under thin glass; and it will generally be found advantageous to use a $\frac{1}{8}$-inch with the 12 or the 18 eye-piece objective with an achromatic condenser. The nature of the movement in the hairs of different species is far from being uniform. In some instances, the currents pass in single lines along the entire length of the cells, as in the hairs from the filaments of *Tradescantia virginica*, or Virginian spiderwort (fig. 470, A); in others there are several such currents which retain their distinctness, as in the jointed hairs of the calyx of the same plant (B); in others, again, the streams coalesce into a network, the reticulations of which

[1] *Quart. Journ. of Microsc. Science*, vol. iii. (1855), p. 277.

change their position at short intervals, as in the hairs of *Glaucium luteum*; whilst there are cases in which the current flows in a sluggish uniformly moving sheet or layer. Where several distinct currents exist in one cell, they are all found to have one common point of departure and return, namely, the *nucleus* (B, *a*), from which it seems fairly to be inferred that this body is the centre of the vital activity of the cell. In all cases in which the cyclosis is seen in the hairs of a plant, the cells of the epiderm also display it, provided that their walls are not so opaque or so strongly marked as to prevent the movement from being distinguished. The epiderm may be most readily torn off from the stalk or the midrib of the leaf, and must then be examined as speedily as possible, since it loses its vitality when thus detached much sooner than do the hairs. Even when no obvious movement of particles is to be seen, the existence of a cyclosis may be concluded from the peculiar arrangement of the molecules of the protoplasm, which are remarkable for their high refractive power, and which, when arranged in a 'moving train,' appear as bright lines across the cell; and these lines, on being carefully watched, are seen to alter their relative positions. The leaf of the common *Plantago* (plantain) furnishes an excellent example of cyclosis, the movement being distinguishable at the same time both in the cells and in the hairs of the epiderm torn from its stalk or midrib. It is a curious circumstance that when a plant which exhibits the cyclosis is kept in a cold dark place for one or two days, not only is the movement suspended, but the moving particles collect together in little heaps, which are broken up again by the separate motion of their particles, when the stimulus of light and warmth occasions a renewal of the activity. It is well to collect the specimens about midday, that being the time when the rotation is most active, and the movement is usually quickened by artificial warmth, which, indeed, is a necessary condition in some instances to its being seen at all. The most convenient method of applying this warmth, while



FIG. 470.—Rotation of fluid in hairs of *Tradescantia virginica*: A, portion of epiderm with hair attached; *a*, *b*, *c*, successive cells of the hair; *d*, cells of the epiderm; *e*, stomate. B, joints of a beaded hair showing several currents; *a*, nucleus.

the object is on the stage of the microscope, is to blow a stream of air upon the thin glass cover through a glass or metal tube previously heated in a spirit-lamp.

The walls of the cells of plants are frequently thickened by deposits, which are first formed on the inner surface, and which may present very different appearances according to the manner in which they are arranged. In its simplest condition such a deposit forms a thin uniform layer over the whole internal surface of the cellulose wall, scarcely detracting at all from its transparency, and chiefly distinguishable by the 'dotted' appearance which the membrane then presents (fig. 467, A). These dots, however, are not pores, as their aspect might naturally suggest, but are merely points at which the deposit is wanting, so that the original cell-wall there remains unthickened. A more complete consolidation of cellular tissue is effected by deposits of *sclerogen* (a substance which, when separated from the resinous and other matters that are commonly associated with it, is found to be allied in chemical composition to cellulose) in succes-



FIG. 471.—Tissue of the testa or seed-coat of *star-anise*: A, as seen in section; B, as seen on the surface.

FIG. 472.—Section of *cherry-stone*, cutting the cells transversely.



FIG. 473.—Section of *coquilla nut*, in the direction of the long diameter of the cells.

sive layers, one within another (fig. 471, A), which present themselves as concentric rings when the cells containing them are cut through; and these layers are sometimes so thick and numerous as almost to obliterate the original cavity of the cell. Such a tissue is known as *sclerenchyme* or sclerenchymatous tissue. By a con-

tinuance of the same arrangement as that which shows itself in the single layer of the dotted cell—each deposit being deficient at certain points, and these points corresponding with each other in the successive layers—a series of passages is left, by which the cavity of the cell is extended at some points to its membranous wall; and it commonly happens that the points at which the deposit is wanting on the walls of the contiguous cells are coincident, so that the membranous partition is the only obstacle to the communication between their cavities (figs. 471-473). It is of such tissue that the 'stones' of stone-fruit, the gritty substance which surrounds the seeds and forms little hard points in the fleshy substance of the pear, the shell of the cocoa-nut, and the endosperm of the seed of *Phytelephas* (known as 'vegetable ivory') are made up; and we see the use of this very curious arrangement in permitting the cells, even after they have attained a considerable degree of consolidation, still to remain permeable to the fluid required for the nutrition of the parts which such tissue encloses and protects.

Fig. 474.—Spiral cells of leaf of *Oncidium*.

The deposit sometimes assumes, however, the form of definite *fibres*, which lie coiled up on the inner surface of the cells, so as to form a single, a double, or even a triple or quadruple spire (fig. 474). Such *spiral cells* are found abundantly in the leaves of certain orchidaceous plants, immediately beneath the epiderm, where they are brought into view by vertical sections; and they may be obtained in an isolated state by macerating the leaf and peeling off the epiderm so as to expose the layer beneath, which is then easily separated into its components. In an orchidaceous plant named *Sacculabium guttatum* the spiral cells are unusually long, and have spires winding in opposite directions, so that by their mutual intersection a series of diamond-shaped markings is produced. Spiral cells are often found upon the surface of the testa or outer coat of seeds; and in *Collomia grandiflora*, *Salvia verbenaca* (wild clary), and some other plants, the membrane of these cells is so weak, and the elasticity of their fibres so great, that when the membrane is softened by the action of water the fibres suddenly uncoil and elongate themselves (fig. 475), springing out, as it were, from the surface of the seed, to which they give a peculiar flocculent appearance. This very curious phenomenon may

Fig. 475.—Spiral fibres of seed-coat of *Collomia*.

be best observed in the following manner:—A very thin transverse slice of the seed should first be cut, and laid upon the lower glass of the aquatic box; the cover should then be pressed down, and the box placed upon the stage, so that the microscope may be exactly focussed to the object, the power employed being the 1-inch, $\frac{2}{3}$-inch, or $\frac{1}{2}$-inch. The cover of the aquatic box being then removed, a small drop of water should be placed on that part of its internal surface with which the slice of the seed had been in contact; and the cover being replaced, the object should be immediately looked at. It is important that the slice of the seed should be very thin, for two reasons; first, that the view of the spirals may not be confused by their aggregation in too great numbers; and second, that the drop of water should be held in its place by capillary attraction, instead of running down and leaving the object, as it will do if the glasses be too widely separated.

In some part or other of most plants we meet with cells containing granules of *starch*, which specially abound in the tubers of the potato and in the seeds of cereals. Starch-grains are originally formed in the interior of chlorophyll-corpuscles, and therefore within

FIG. 476.—Cells of *peony* filled with starch.

FIG. 477.—Granules of *starch* as seen under polarised light.

the protoplasm-layer of the cell; but as they increase in size, the protoplasm-layer thins itself out as a mere covering film, and at last almost entirely disappears. So long as the starch-grains remain imbedded in the protoplasm-layer they continue to grow; but when they accumulate so as to occupy the cell-cavity their growth stops. They are sometimes minute and very numerous, and so closely packed as to fill the cell-cavity (fig. 476); in other instances they are of much larger dimensions, so that only a comparatively small number of them can be included in any one cell; while in other cases, again, they are both few and minute, so that they form but a small proportion of the cell-contents. Their nature is at once detected by the addition of a solution of iodine, which gives them a beautiful blue colour. Each granule when highly magnified exhibits a peculiar spot, termed the *hilum*, round which are seen a set of circular lines that are for the most part concentric (or nearly so) with it. When viewed by polarised light each grain exhibits a dark cross, the point of intersection being at the hilum (fig. 477); and when a selenite plate is interposed the cross becomes beautifully coloured. Opinions have been very much divided regarding the internal structure of the starch-grain, but the doctrine of Nägeli

that it is composed of successive layers which increase by 'intussusception,' that is, by the intercalation of fresh molecules of starch between those already in existence, is the one now generally adopted, though the alternative theory of formation by the 'apposition' of successive layers has many advocates. These layers differ in their proportion of water, the outermost layer, which is the most solid, having within it a watery layer, this, again, being succeeded by a firm layer, which is followed by a watery layer, and so on, the proportion of water increasing towards the centre in both kinds of layer, and attaining its maximum in the innermost part of the grain, where the formation of new layers takes place, causing the distension of the older ones. Although the dimensions of the starch-grains produced by any one species of plant are by no means constant, yet there is a certain average for each, from which none of them depart very widely; and by reference to this average the starch-grains of different plants that yield this product in abundance may be microscopically distinguished from one another—a circumstance of considerable importance in commerce. The largest starch-grains in common use are those of the plant (a species of *Canna*) known as *tous-les-mois*. The average diameter of those of the *potato* is about the same as the diameter of the smallest of the tous-les-mois, and the size of the ordinary starch-grains of *wheat* and of *sago* is about the same as that of the smallest grains of potato-starch; whilst the granules of *rice*-starch are so very minute as to be at once distinguishable from any of the preceding.

In certain plants, especially those belonging to particular natural orders, the stem, leaves, and other parts are permeated by long branched tubes, constituting the *laticiferous tissue*. The elements of this tissue may be either greatly enlarged prosenchymatous cells or true vessels. In either case they contain a copious milky-white or coloured juice, the *latex*, which exudes freely when the part containing it is wounded, and dries rapidly on exposure. The chemical composition of the latex varies; it may contain in solution powerful alkaloids, as in the case of the opium-poppy, or gum-resins. Caoutchouc and gutta-percha are the dried latex of tropical trees and shrubs belonging to several natural orders. Good examples of laticiferous tissue are furnished by the Papaveraceæ, of which our common field-poppy is an example, many Compositæ such as the dandelion and lettuce, Convolvulaceæ, Euphorbiaceæ or spurges, Apocynaceæ, Moraceæ including the mulberry &c.

Deposits of mineral matter in a crystalline condition, known as *raphides*, are not unfrequently found in vegetable cells, where they are at once brought into view by the use of polarised light. Their designation (derived from ῥαφίς, a needle) is very appropriate to one of the most common states in which these bodies present themselves, that, namely, of bundles of needle-like crystals, lying side by side in the cavity of the cells; such bundles are well seen in the cells lying immediately beneath the epiderm of the bulb of the medicinal squill. It does not apply, however, to other forms which are scarcely less abundant; thus, instead of bundles of minute needles, single large crystals, octohedral or prismatic, are frequently met

ith, and the prismatic crystals are often aggregated in beautiful ellate groups. The most common material of these crystals is alate of lime, which is generally found in the stellate form ; and no lant yields these stellate raphides so abundantly as the common *hubarb*, the best specimens of the dry medicinal root containing as uch as 35 per cent. of them. In the epiderm of the bulb of the *sion* the same material occurs in the octohedral or the prismatic rm. In other instances, the calcareous base is combined with rtaric, citric, or malic acid ; the acicular raphides consist almost ivariably of oxalate of lime. Some raphides are as long as $\frac{1}{40}$th of a inch, while others measure no more than $\frac{1}{100}$th. They occur in all arts of plants—the wood, pith, bark, root, leaves, stipules, sepals, etals, fruit, and even in the pollen. They are always situated in lls, and not in the intercellular passages ; the cell-membrane, how-ver, is often so much thinned away as to be scarcely distinguish-ble. Certain plants of the *Cactus* tribe, when aged, have their issues so loaded with raphides as to become quite brittle, so that hen some large specimens of *C. senilis*, said to be a thousand years ld, were sent to Kew Gardens from South America, some years nce, it was found necessary for their preservation during transport pack them in cotton like jewellery. Raphides are probably to be nsidered as non-essential results of the vegetative processes, being or the most part produced by the union of organic acids generated the plant with mineral bases imbibed by it from the soil. The te Mr. E. Quekett succeeded in artificially producing raphides ithin the cells of rice-paper, by first filling these with lime-water y means of the air-pump, and then placing the paper in weak olutions of phosphoric and oxalic acids. The artificial raphides of hosphate of lime were rhombohedral ; while those of oxalate of ime were stellate, exactly resembling the natural raphides of the hubarb. Besides the structures already mentioned as affording good llustrations of different kinds of raphides, may be mentioned the arenchyme of the leaf of *Agave*, *Aloë*, *Cycas*, *Encephalartos*, &c. ; he epiderm of the bulb of the hyacinth, tulip, and garlic ; the bark of the apple, *Cascarilla*, *Cinchona*, lime, locust, and many other trees ; the pith of *Elæagnus*, and the testa of the seeds of *Anagallis* and the elm.

A large proportion of the denser parts of the fabric of the higher plants is made up of the substance which is known as *woody fibre* or *prosenchymatous tissue*. This, however, can only be regarded as a variety of cellular tissue ; for it is composed of peculiarly elongated cells (fig. 493), usually pointed at their two extremities so as to become spindle-shaped, whose walls have a special tendency to undergo consolidation by the internal deposit of sclerogen. It is obvious that a tissue consisting of elongated cells, adherent together by their entire length, and strengthened by internal deposit, must possess much greater tenacity than any tissue in which the cells depart but little from the primitive spherical form ; and we accordingly find woody fibre present wherever it is requisite that the fabric should possess not merely density, but the power of resistance to tension. In the higher classes of the vegetable kingdom it constitutes the chief part of the stem and branches, where these have a

firm and durable character; and even in more temporary structures, such as the herbaceous stems of annual plants, and the leaves and flowers of almost every tribe, this tissue forms a more or less important constituent, being especially found in the neighbourhood of the spiral vessels and ducts, to which it affords protection and support. Hence the bundles of fasciculi composed of these elements, which form the 'veins' of leaves, and which give 'stringiness' to various esculent vegetable substances, are commonly known under the name of *fibro-vascular* tissue. In their young and unconsolidated state the woody cells seem to conduct fluids with great facility in the direction of their length; and in the *Coniferæ*, whose stems and branches are destitute of ducts, they afford the sole channel for the ascent of the sap. The *fibro-vascular bundles*, which are the chief strengthening elements of such organs as the stem, branches, leaf-stalks, flower-stalks &c., are, in the higher plants, structures of considerable complexity; in Exogens they consist of three distinct portions, the *xylem*-portion composed chiefly of the different kinds of vessels hereafter to be described, a *phloem*-portion composed of prosenchymatous tissue and 'sieve-tubes,' and a formative *cambium*-portion.



FIG. 478.—Section of *coniferous wood* in the direction of the tracheïdes, showing their 'bordered pits': *a*, *a*, *a*, medullary rays crossing the fibres.

A peculiar set of markings seen on the woody fibres of the *Coniferæ*, and of some other tribes, is represented in fig. 478; in each of these spots the inner circle appears to mark a deficiency of the lining deposit, as in the pitted cells of other plants; whilst the *outer* circle indicates the boundary of a lenticular cavity which intervenes between the adjacent cells at this point. There are varieties in this arrangement so characteristic of different tribes, that it is sometimes possible to determine, by the microscopic inspection of a minute fragment, even of a fossil wood, the tribe to which it belonged. Markings of this kind, very characteristic of the wood of *Coniferæ*, though not peculiar to that order, are known as 'bordered pits,' and the elongated cells in which they occur as 'tracheïdes.'

All the more perfect forms of Phanerogams contain, in some part of their fabric, the peculiar structures which are known as *spiral vessels*.[1] These have the elongated shape of fibre-cells; but the internal deposit, as in the spiral cells, takes the form of a spiral fibre winding from end to end, and retaining its elasticity; this fibre may be single, double, or even quadruple, this last character pre-

[1] So long, however, as they retain their original cellular character, and do not coalesce with each other, these fusiform spiral cells cannot be regarded as having any more claim to the designation of *vessels*, than have the elongated cells of the woody tissue.

senting itself in the very large elongated fibre-cells of *Nepenthes* (Chinese pitcher-plant). Such vessels are especially found in the delicate membrane (medullary sheath) surrounding the pith of Exogens, and in the 'xylem-portion' of the woody bundles of Exogens and Endogens; thence they proceed to the leaf-stalks, through which they are distributed to the leaves. By careful dissection under the microscope these *fibro-vascular bundles* may be separated entire; but their structure may be more easily displayed by cutting *round*, but not *through*, the leaf-stalk of the strawberry, geranium, &c. and then drawing the parts asunder. The membrane composing the tubes of the vessels will thus be broken across; but the fibres within, being elastic, will be drawn out and unrolled. Spiral vessels are sometimes found to convey *fluid*, whilst in other cases they contain *air* only; the conditions of this difference are not yet certainly known.

Although fluid generally finds its way with tolerable facility through the various forms of cellular tissue, especially in the direction of the greatest length of the cells, a more direct means of connection between distant parts is required for its active transmission. This is afforded by the peculiar kind of vessel known as *ducts*, which consist of cells laid end to end, the partitions between them being more or less obliterated. The origin of these ducts is occasionally very evident, both in the contraction of their diameter at regular intervals, and in the persistence of remains of their partitions (fig. 493, *b*, *b*); but in most cases it can only be ascertained by studying the history of their development, neither of these indications being traceable. Some of these ducts (fig. 479, 2) are indistinguishable from the *spiral* vessels already described, save in the want of elasticity in their spiral fibre, which causes it to break when the attempt is made to draw it out. This rupture would seem to have taken place, in some instances, from the natural elongation of the cells by growth, the fibre being broken up into rings, which lie sometimes close together, but more commonly at considerable intervals; such a duct is said to be *annular* (fig. 479, 1). Intermediate forms between the spiral and annular ducts, which show the derivation of the latter from the former, are very frequently to be met with. The spirals are sometimes broken up still more completely, and the fragments of the fibre extend in various directions, so as to meet and form an irregular network lining the duct, which is then said to be *reticulated*. The continuance of the deposit, however, gradually contracts the meshes, leaving the walls of the duct marked only by pores like those of porous cells; and such canals, designated as *pitted* ducts, are especially met with in parts of most solid structure and least rapid growth (fig. 479, 3). The *scalariform* ducts of ferns may be regarded as a modification of the spiral; but spiral ducts are frequently to be met with also in the rapidly growing leaf-stalks of flowering plants, such as the rhubarb. Not unfrequently, however, we find all forms of ducts in the same bundle, as seen in fig. 479. The size of these ducts is occasionally so great as to enable their openings to be distinguished by the unaided eye; they are usually largest in stems whose size is small in proportion to the surface of leaves which they support, such as the common cane or the vine;

and, generally speaking, they are larger in woods of dense texture, such as oak and mahogany, than in those of which the fibres, remaining unconsolidated, can serve for the conveyance of fluid. They are entirely absent in the *Coniferæ*.

The vegetable tissues whose principal forms have been now described, but among which an immense variety of detail is found, may be either studied as they present themselves in thin *sections* of the various parts of the plant under examination, or in the isolated conditions in which they are obtained by *dissection*. The former process is the most easy, and yields a large amount of information; but still it cannot be considered that the characters of any tissue have been properly determined until it has been dissected out. Sections of some of the hardest vegetable substances, such as 'vegetable ivory,' the 'stones' of fruit, the 'shell' of the cocoa-nut, &c. can scarcely be obtained except by slicing and grinding; and these may be mounted either in Canada balsam or in glycerin-jelly. In cases, however, in which the tissues are of only moderate firmness, the section may be most readily and effectually made with the 'microtome'; and there are few parts of the vegetable fabric which may not be advantageously examined by this means, any very soft or thin portions being placed in it between two pieces of cork, elder-pith, or carrot. In certain cases, however, in which even this compression would be injurious, the sections must be made with a sharp knife, the substance being laid on the nail or a slip of glass. In dissecting the vegetable tissues scarcely any other instrument will be found really necessary than a pair of needles (in handles), one of them ground to a cutting edge. The adhesion between the component cells, fibres, &c. is often sufficiently weakened by a few hours' maceration to allow of their readily coming apart, when they are torn asunder by the needle-points beneath the simple lens of a dissecting microscope. But if this should not prove to be the case, it is desirable to employ some other method for the sake of facilitating their isolation. None is so effectual as the boiling of a thin slice of the substance under exami-



FIG. 479.—Longitudinal section of stem of *Italian reed*: *a*, cells of the pith; *b*, fibro-vascular bundle, containing 1, annular ducts; 2, spiral ducts; 3, pitted ducts with woody fibre; *c*, cells of the epiderm.

ı either in dilute nitric acid or in a mixture of nitric acid and ıte of potassa. This last method (which was devised by tz) is the most rapid and effectual, requiring only a few tes for its performance; but as oxygen is liberated with such ɔm as to give an almost explosive character to the mixture, it d be put in practice with extreme caution. After being thus ɔd the tissue should be boiled in alcohol, and then in water; t will then be found very easy to tear apart the individual cells, , &c. of which it may be composed. These may be preserved ounting in weak spirit.

tem and Root.—It is in the stems and roots that we find the est variety of tissues in combination, and the most regular of structure; and sections of these viewed under a low mag- ng power are objects of peculiar beauty, independently of the tific information which they afford. The axis (under which is included the stem with its branches, and the root with its fications) always has for the basis of its structure a dense cellular ıchyme; though, in an advanced stage of development, this constitute but a small portion of it. In the midst of the ıchyme we generally find fibro-vascular bundles, consisting of y fibre, with ducts of various kinds, and (very commonly) spiral ls. It is in the mode of arrangement of these bundles that the amental difference exists between the stems which are commonly nated as *endogenous* (growing from within), and those which more correctly termed *exogenous* (growing on the outside); for he former the bundles are dispersed throughout the whole ıeter of the axis without any peculiar plan, the intervals between ı being filled up by cellular parenchyme; whilst in the latter are arranged side by side in such a manner as to form a cylinder *ɔod*, which includes within it the portion of the cellular substance rn as *pith*, whilst it is itself enclosed in an envelope of the same tance that forms the *bark*. These two plans of axis-formation ɔctively characteristic of those two great groups into which ıerogams are subdivided—namely, the *Monocotyledons* and the *tyledons*—will now be more particularly described.

When a transverse section (fig. 480) of a *monocotyledonous* stem amined microscopically, it is found to exhibit a number of fibro- ılar bundles, disposed without any regularity in the midst of nass of cellular tissue, which forms (as it were) the matrix or of the fabric. Each bundle contains two, three, or more large s, which are at once distinguished by the size of their openings; these are surrounded by woody fibre and spiral vessels, the ıverse diameter of which is so extremely small that the portion e bundles which they form is at once distinguished in transverse on by the closeness of its texture (fig. 481). The bundles are numerous in the centre of the stem, and become gradually more ded towards its circumference; but it frequently happens that ortion of the area in which they are most compactly arranged is ıbsolutely at its exterior, this portion being itself surrounded n investment composed of cellular tissue only; and sometimes nd the central portion, also, completely destitute of fibro-vascular

bundles; so that a sort of indication of the distinction between pith, wood, and bark is here presented. This distinction, however, is very imperfect; for we do not find either the central or the peripheral portions ever separable, like pith and bark, from the intermediate



FIG. 480.—Transverse section of stem of young palm.

woody layer. In its young state the centre of the stem is always filled up with cells; but these not unfrequently disappear after a time, except at the *nodes*, leaving the stem hollow, as we see in the whole tribe of grasses. When a vertical section is made of a woody stem (as that of a palm) of sufficient length to trace the whole extent of the fibro-vascular bundles, it is found that, whilst they pass at their upper extremity into the leaves, they pass at the lower end towards the surface of the stem, and assist, by their interlacement with the outer bundles, in forming that extremely tough investment which the lower ends of these stems present. New fibro-vascular bundles are being continually formed in the upper part of the stem, in continuity with the leaves which are successively put forth at its summit; but while these take part in the elongation of the stem, they contribute but little to the increase of its diameter. For those which are most recently formed only pass into the centre of the stem during the higher part of their course, and usually make their way again to its exterior at no great distance below; and, when once formed, they receive no further additions



FIG. 481.—Portion of transverse section of stem of *Wanghie cane*.

It was from the idea formerly entertained that these successively formed bundles descend in the interior of the stem through its entire length until they reach the roots, and that the stem is thus continually receiving additions to its interior, that the term *endogenous* was given to this type of stem-structure; but, from the fact just stated regarding the course of the fibro-vascular bundles, it is obvious that such a doctrine cannot be any longer admitted.

In the stems of dicotyledonous phanerogams, on the other hand, we find a method of arrangement of the several parts which must be regarded as the highest form of the development of the axis, being that in which the greatest differentiation exists. A distinct division is always seen in a transverse section (fig. 482) between three concentric areas—the *pith*, the *wood*, and the *bark*—the first (*a*) being central, the last (*b*) peripheral, and these having the wood interposed between them, its circle being made up of wedge-shaped bundles (*d*, *d*), kept apart by the *medullary rays* composed of unchanged cellular tissue (*c*, *c*) that pass between the pith and the bark. The pith (fig. 483, *a*) is almost invariably composed of cellular tissue only, which usually presents (in transverse section) a hexagonal areolation. When newly formed it has a greenish hue, and its cells are filled with fluid; but it gradually dries up and loses its colour; and not unfrequently its component cells are torn apart by the rapid growth of their envelope, so that irregular cavities are found in it; or if



FIG. 482.—Diagram of the first formation of an exogenous stem: *a*, pith; *b b*, bark; *c c*, plates of cellular tissue (medullary rays) left between the woody bundles *d d*.



FIG. 483.—Transverse section of stem of *Clematis*: *a*, pith; *b*, *b*, *b*, woody bundles; *c*, *c*, *c*, medullary rays.

the stem should increase with extreme rapidity it becomes hollow, the pith being reduced to fragments, which are found adhering to its interior wall. The pith is immediately surrounded by a delicate membrane, consisting almost entirely of spiral vessels, which is termed the *medullary sheath*.

The *woody* portion of the stem (fig. 483, *b*, *b*) is made up of woody

fibres, usually with the addition of ducts of various kinds; these, however, are absent in one large group, the *Coniferæ* or fir-tribe with its allies (figs. 487–490), in which the prosenchymatous cells or *tracheïdes* are of unusually large diameter, and are marked by the bordered pits already described. In any stem or branch of more than one year's growth the woody structure presents a more or less distinct appearance of division into concentric rings, the number of which varies with the age of the tree (fig. 484). The composition of the several rings, which are the sections of so many cylindrical layers, is uniformly the same, however different their thickness: but the arrangement of the two principal elements—namely, the cellular and the vascular tissue—varies in different species, the vessels being sometimes almost uniformly diffused through the whole layer, but in other instances being confined to its inner part; while in other cases, again, they are dispersed with a certain regular irregularity (if such an expression may be allowed), so as to give a curiously

Fig. 484.—Transverse section of stem of *Rhamnus* (buckthorn), showing concentric layers of wood.

Fig. 485.—Portion of the same more highly magnified.

figured appearance to the transverse section (figs. 484, 485). The general fact, however, is that the vessels predominate towards the inner side of the ring (which is the part of it first formed), and that the outer portion of each layer is almost exclusively composed of cellular tissue. Such an arrangement is shown in fig. 483. This alternation of vascular and cellular tissue frequently serves to mark the succession of layers, when, as is not uncommon, there is no very distinct line of separation between them.

The number of layers is usually considered to correspond with that of the *years* during which the stem or branch has been growing; and this is, no doubt, generally true in regard to the trees of temperate climates, which thus ordinarily increase by 'annual layers.' There can be no doubt, however, that such is not the universal rule: and that we should be more correct in stating that each layer indicates an *epoch of vegetation*, which, in temperate climates, is usually (but not invariably) a year, but which is commonly much less in the

case of trees flourishing in tropical regions. Thus among the latter it is very common to find the leaves regularly shed and replaced *twice* or even *thrice* in a year, or *five* times in two years; and for every crop of leaves there will be a corresponding layer of wood. It sometimes happens, even in temperate climates, that trees shed their leaves prematurely in consequence of continued drought, and that, if rain then follow, a fresh crop of leaves appears in the same season; and it cannot be doubted that in such a year there would be *two* rings of wood produced, which would probably not together exceed the ordinary *single* layer in thickness. That such a division may even occur as a consequence of an interruption to the processes of vegetation produced by seasonal changes—as by heat and drought in a tree that flourishes best in a cold damp atmosphere, or by a fall of temperature in a tree that requires heat—would appear from the frequency with which a *double* or even a *multiple* succession of rings is found in transverse sections of wood to occupy the place of a *single* one. Thus in a section of hazel stem (in the Author's possession), of which a portion is represented in fig. 486, between two layers of the ordinary thickness there intervenes a band whose breadth is altogether less than that of either of them, and which is

a *b* *c*

FIG. 486.—Portion of transverse section of stem of *hazel*, showing, in the portion *a*, *b*, *c*, six narrow layers of wood.

yet composed of no fewer than six layers, four of them (*c*) being very narrow, and each of the other two (*a*, *b*) being about as wide as these four together. The inner rings of wood, being not only the oldest, but the most solidified by matters deposited within their component cells and vessels, are spoken of collectively under the designation *duramen* or 'heart-wood.' On the other hand, it is through the cells and ducts of the outer and newer layers that the sap rises from the roots towards the leaves; and these are consequently designated as *alburnum* or 'sap-wood.' The line of demarcation between the two is sometimes very distinct, as in lignum vitæ and cocos-wood; and as a new ring is added every year to the exterior of the alburnum an additional ring of the innermost part of the alburnum is every year consolidated by internal deposit, and is thus added to the exterior of the duramen. More generally, however, this consolidation is gradually effected, and the alburnum and duramen are not separated by any abrupt line of division.

The *medullary rays* which cross the successive rings of wood connecting the cellular substance of the pith with that of the bark, and dividing each ring of wood into wedge-shaped segments, are thin plates of cellular tissue (fig. 483, *c*, *c*), not usually extending to any

great depth in the vertical direction. It is not often, however, that their character can be so clearly seen in a transverse section as in the diagram just referred to; for they are usually compressed so closely as to appear darker than the wedges of woody tissue between which they intervene (figs. 485, 487), and their real nature is best understood by a comparison of *longitudinal* sections made in two



FIG. 487.—Portion of transverse section of the stem of *cedar*: *a*, pith; *b*, *b*, *b*, woody layers; *c*, bark.

different directions—namely *radial* and *tangential*—with the transverse. Three such sections of a fossil coniferous wood in the Author's possession are shown in figs. 488–490. The stem was of such large size that, in so small a part of the area of its transverse section as is represented in fig. 488, the medullary rays seem to run parallel to each other, instead of radiating from a common centre. They are very narrow; but are so closely set together that only two or three rows of tracheïdes (no ducts being here present) intervene between any pair of them. In the longitudinal section taken in a radial direction (fig. 489) and consequently passing in the same course with the medullary rays, these are seen as thin plates (*a*, *a*, *a*) made up of superposed cells very much elongated, and crossing in a horizontal direction the tracheïdes which lie parallel to one another vertically. And in the tangential section (fig. 490), which is taken in a direction at right angles to that of the medullary rays, and therefore cuts them across, we see that each of the plates thus formed has a very limited depth from above downwards, and is composed of no more than one thickness of cells in the horizontal direction. A section of the stem of mahogany taken in the same direction as the last (fig. 491) gives a very good view of the cut ends of the medullary rays as they pass between the prosenchy-



FIG. 488.—Portion of transverse section of large stem of coniferous wood (fossil), showing part of two annual rings, divided at *a*, *a*, and traversed by very thin but numerous medullary rays.

matous cells; and they are seen to be here of somewhat greater thickness, being composed of two or three rows of cells, arranged side by side.

FIG. 489.—Portion of vertical section of the same wood, taken in a radial direction, showing the tracheïdes with 'bordered pits,' without ducts, crossed by the medullary rays, *a*, *a*.



FIG. 490.—Portion of vertical section of the same wood, taken in a tangential direction, so as to cut across the medullary rays.

In another fossil wood, whose transverse section is shown in fig. 492, and its tangential section in fig. 493, the medullary rays are seen to occupy a much larger part of the substance of the stem, being shown in the transverse section as broad bands (*a a*, *a a*) intervening between the closely set prosenchymatous cells, among which some large ducts are scattered; whilst in the tangential section they are observed to be not only deeper than the preceding from above downwards, but also to have a much greater thickness. This section also gives an excellent view of the ducts, *b b*, *b b*, which are here plainly seen to be formed by the coalescence of large cylindrical cells lying end to end. In another fossil wood in the Author's possession the medullary rays constitute a still larger proportion of the stem; for in the transverse section (fig. 492), they are seen as very broad bands (*b*, *b*), alternating with plates of woody structure (*a a*), whose thickness is often less than their own; whilst in the tangential section (fig. 495) the cut extremities of the medullary rays occupy a very large part of the area, having apparently determined the sinuous course of the



FIG. 491.—Vertical section of mahogany.

prosenchymatous cells, instead of looking (as in fig. 490) as if th had forced their way between these cells, which there hold a near

FIG. 492.—Transverse section of a fossil wood, showing the medullary rays, *a*, *a*, *a*, *a*, *a*, *a*, running nearly parallel to each other, and the openings of large ducts in the midst of the prosenchymatous tissue.



FIG. 493.—Vertical (tangential) section of the same wood, showing the prosenchymatous cells separated by the medullary rays, and by the large ducts, *b b*, *b b*.

straight and parallel course on either side of them. The medulla rays maintain a connection between the external and the inter

FIGS. 494 and 495.—Transverse and vertical sections of a fossil wood, showing the separation of the woody plates, *a a*, *a a*, by the very large medullary rays, *b b*, *b b*.

parts of the cellular tissue or *fundamental parenchyme* of the stem which have been separated by the interposition of the wood.

The *bark* is usually found to consist of three principal layers : e external or *epiphlœum*, which includes the *suberous* (or corky) yer ; the middle, or *mesophlœum*, also termed the *cellular envelope* ; d the internal, or *endophlœum*, which is more commonly known the *liber*. The two outer layers are entirely cellular, and are iefly distinguished by the form, size, and direction of their cells. ıe *epiphlœum* is generally composed of one or more layers of colour- ss or brownish cells, which usually present a cubical or tabular rm, and are arranged with their long diameters in the horizontal rection ; it is this which, when developed to an unusual thickness, rms *cork*, a substance which is by no means the product of one nd of tree exclusively, but exists in greater or less abundance in e bark of every exogenous stem. The *mesophlœum* consists of lls, usually containing more or less chlorophyll, prismatic in their rm, and disposed with their long diameters parallel to the axis ; it more loosely arranged than the preceding, and contains inter- llular passages, which often form a network of canals which have e character of laticiferous vessels ; and, although usually less veloped than the suberous layers, it sometimes constitutes the ief thickness of the bark. The *liber* or 'inner bark,' on the other nd, usually contains woody fibre in addition to the cellular tissue d laticiferous canals of the preceding ; and thus approaches more arly in its character to the woody layers, with which it is in close oximity on its inner surface. The liber may generally be found to made up of a succession of thin layers, equalling in number those the wood, the innermost being the last formed ; but no such ccession can be distinctly traced either in the cellular envelope or the suberous layer, although it is certain that they, too, augment thickness by additions to their interior, whilst their external por- ıns are frequently thrown off in the form of thickish plates, or tach themselves in smaller and thinner laminæ. The bark is ways separated from the wood by the *cambium layer*, which is the rt wherein all new growth takes place. This layer seems to con- t of mucilaginous semi-fluid matter ; but it is really made up of lls of a very delicate texture, which gradually undergo transfor- ıation, whereby they are for the most part converted into tracheïdes, cts, spiral vessels, &c. These materials are so arranged as to gment the fibro-vascular bundles of the wood on their external rface, thus forming a new layer of 'alburnum,' which encloses all ose that preceded it ; whilst they also form a new layer of 'liber' the interior of all those which preceded it. They also extend the edullary rays, which still maintain a continuous connection between e pith and the bark ; and a portion remains unconverted, so as ways to keep apart the liber and the alburnum. This type of m-structure is termed *exogenous* ; a designation which applies ry correctly to the mode of increase of the woody layers, although just shown) the liber is formed upon a truly endogenous plan.

Numerous departures from the normal type are found in particu- tribes of dicotyledons. Thus in some the wood is not marked by ıcentric circles, their growth not being interrupted by any seasonal ange. In other cases, again, each woody zone is separated from

the next by the interposition of a thick layer of cellular substance. Sometimes wood is formed in the bark (as in *Calycanthus*), so that several woody columns are produced, which are quite independent of the principal woody axis, and cluster around it. Occasionally the woody stem is divided into distinct segments by the peculiar thickness of certain of the medullary rays, and in the stem, of which fig. 496 represents a transverse section, these cellular plates form four large segments, disposed in the manner of a Maltese cross, and alternating with the four woody segments, which they equal in size.

The exogenous stem, like the (so-called) endogenous, consists, in its first-developed state, of cellular tissue only: but after the leaves have been actively performing their functions for a short time, we find a circle of fibro-vascular bundles, as represented in fig. 482, interposed between the central (or *medullary*) and the peripheral (or *cortical*) portions of the fundamental tissue, these fibro-vascular

FIG. 496.—Transverse section of the stem of a climbing plant (*Aristolochia ?*) from New Zealand.



FIG. 497.—Portion of transverse section of *Arctium* (burdock) showing one of the fibro-vascular bundles that lie beneath the cellular epiderm.

bundles being themselves separated from each other by plates of cellular tissue, which still remain to connect the central and the peripheral portions of that tissue. This first stage in the formation of the exogenous axis, in which its principal parts—the pith, wood, bark, and medullary rays—are marked out, is seen even in the stems of herbaceous plants, which are destined to die down at the end of the season (fig. 497); and sections of these, which are very easily prepared, are most interesting microscopic objects. In such stems the difference between the endogenous and the exogenous types is manifested in little else than the disposition of the fibro-vascular layers which are scattered through nearly the whole of the fundamental tissue (although more abundant towards its exterior) in the former case, but are limited to a circle within the peripheral portion of the cellular tissue in the latter. It is in the further development which takes place during succeeding years in

the woody stems of perennial exogens that those characters are displayed which separate them most completely from the ferns and their allies, whose stems contain a cylindrical layer of fibro-vascular bundles, as well as from (so-called) endogens. For whilst the fibro-vascular layers of the latter, when once formed, undergo no further increase, those of exogenous stems are progressively augmented on their outer side by the metamorphosis of the cambium layer; so that each of the bundles which once lay as a mere series of parallel cords beneath the cellular epiderm of a first-year's stem, may become in time the small end of a wedge-shaped mass of wood extending continuously from the centre to the exterior of a trunk of several feet in diameter, and becoming progressively thicker as it passes upwards. The fibro-vascular bundles of exogens are therefore spoken of as 'indefinite' or 'open,' whilst those of endogens and vascular cryptogams (ferns &c.) are said to be 'definite' or 'closed.' The 'open' fibro-vascular bundles of exogens and of gymnosperms may be stated to consist of three distinct parts: the *xylem* portion, which consists chiefly of ducts, of the nature of spiral, annular, or pitted vessels, and which is the portion of the bundle nearest to the centre of the organ; the *phloëm* or 'bast' portion, which consists largely of prosenchymatous cells, among which are almost always 'sieve-tubes' with their 'sieve-plates,' and which is the peripheral portion of the bundle; while between them is the formative *cambium*, from which fresh xylem is constantly being formed on one side, fresh phloëm on the other side. The 'closed' bundles of endogens and of vascular cryptogams consist of xylem and phloëm only. When the xylem and phloëm portions of fibro-vascular bundle lie side by side, as is usually the case, the bundle is said to be *collateral*; when either portion encloses the other like a cylinder, it is *concentric*.

The structure of the *roots* of endogens and exogens is essentially the same in plan as that of their respective stems. Generally speaking, however, the roots of exogens have no pith, although they have medullary rays; and the succession of distinct rings is less apparent in them than it is in the stems from which they diverge. In the delicate branches which proceed from the larger root-fibres a central bundle of vessels will be seen enveloped in a sheath of cellular substance; and this investment also covers in the end of the branch, which is usually somewhat dilated, and is furnished at its extremity with one or more layers of cells, which are constantly being thrown off, known as the *pileorhiza* or *root-cap*. The structure of the branches of the root may be well studied in the common duckweed, every floating leaf of which has a single root hanging down from its lower surface. The central fibro-vascular cylinder which is characteristic of the finer roots of exogens, as well as of endogens, is surrounded by a single layer of cells very clearly differentiated from the surrounding fundamental tissue, known as the *bundle-sheath*. We have already seen the peculiar form assumed by the bundle-sheath in the stem of ferns and other vascular cryptogams.

The structure of stems and roots cannot be thoroughly examined in any other way than by making sections in different directions

with the microtome. The general instructions already given leave little to be added respecting this special class of objects, the chief points to be attended to being the preparation of the stems, &c. for slicing, the sharpness of the knife, and the dexterity with which it is handled, and the method of mounting the sections when made. The wood, if green, should first be soaked in strong alcohol for a few days, to get rid of the resinous matter; and it should then be macerated in water for some days longer, for the removal of its gum, before being submitted to the cutting process. If the wood be dry, it should first be softened by soaking for a sufficient length of time in water, and then treated with spirit, and afterwards with water, like green wood. Some woods are so little affected even by prolonged maceration, that boiling in water is necessary to bring them to the degree of softness requisite for making sections. No wood that has once been dry, however, yields such good sections as that which is cut fresh. When a piece, of the appropriate length, has been placed in the grasp of the section instrument (wedges of deal or other soft wood being forced in with it, if necessary for its firm fixation), a few thick slices should first be taken, to reduce its surface to an exact level; the surface should then be wetted with spirit, the micrometer-screw moved through a small part of a revolution, and the slice taken off with the razor, the motion given to which should partake both of *drawing* and *pushing*. A little practice will soon enable the operator to discover in each case how thin he may venture to cut his sections without a breach of continuity, and the micrometer-screw should be turned so as to give the required elevation. If the surface of the wood has been sufficiently wetted, the section will not curl up in cutting, but will adhere to the surface of the razor, from which it is best detached by dipping the razor in water so as to float away the slice of wood, a camel-hair pencil being used to push it off if necessary. All the sections that may be found sufficiently thin and perfect should be put aside in a bottle of weak spirit until they be mounted. For the minute examination of their structure, they may be mounted either in weak spirit or in glycerin-jelly. Where a mere general view only is needed, dry mounting answers the purpose sufficiently well: and there are many stems, such as that of *Clematis*, of which transverse sections rather thicker than ordinary make very beautiful *opaque* objects when mounted dry on a black ground. Canada balsam should not be had recourse to, except in the case of very opaque sections, as it usually makes the structure too transparent. Transverse sections, however, when slightly charred by heating between two plates of glass until they turn brown, may be mounted with advantage in Canada balsam, and are then very showy specimens for the gas-microscope. The number of beautiful and interesting objects which may be thus obtained from even the commonest trees, shrubs, and herbaceous plants, at the cost of a very small amount of trouble, can scarcely be conceived save by those who have specially attended to these wonderful structures; and a careful study of sections made in different parts of the stem, especially in the neighbourhood of the 'growing point,' will reveal to the eye of the physiologist

some of the most important phenomena of vegetation. The judicious use of the *staining process* not only improves the appearance of such sections, but adds greatly to their scientific value. *Fossil woods*, when well preserved, are generally *silicified*, and can only be cut and polished by a lapidary's wheel. Should the microscopist be fortunate enough to meet with a portion of a *calcified* stem in which the organic structure is preserved, he should proceed with it after the manner of other hard substances which need to be reduced by grinding.

Epiderm of Leaves.—On all the softer parts of the higher plants, save such as grow under water, we find a surface layer differing in its texture from the parenchyme beneath, and constituting a distinct membrane, known as the *epiderm*. This membrane is composed of cells, the walls of which are flattened above and below, whilst they adhere closely to each other laterally, so as to form a continuous

FIG. 498.—Epiderm of leaf of *Yucca*, showing stomates.



FIG. 499.—Epiderm of leaf of Indian corn (*Zea Mais*), showing stomates.

stratum (figs 502, 504, *a*, *a*). The shape of these cells is different in almost every tribe of plants; thus in the epiderm of the *Yucca* (fig. 498), Indian corn (fig. 499), *Iris* (fig. 503), and most other monocotyledons, they are elongated, and present an approach to a rectangular contour, their margins being straight in the *Yucca* and *Iris*, but minutely sinuous or crenated in the Indian corn. In most dicotyledons, on the other hand, the cells of the epiderm depart less from the rounded form, but their margins usually exhibit large irregular sinuosities, so that they seem to fit together like the pieces of a dissected map, as is seen in the epiderm of the apple (fig. 500, *b*, *b*). Even here, however, the cells of that portion of the epiderm (*a*, *a*) which overlies the 'veins' of the leaf have an elongated form, approaching that of the wood-cells of which these veins are chiefly composed; and it seems likely, therefore, that the elongation of the ordinary epiderm cells of monocotyledons has reference to that parallel arrangement of the veins which their leaves almost constantly exhibit.

The cells of the epiderm are colourless, or nearly so, having no or but little chlorophyll in their interior ; and their walls are generally thickened by secondary deposit, especially on the side nearest the atmosphere. This outermost hardened continuous wall of the epidermal layer of cells is known as the *cuticle*. The deposit (cutin)



FIG. 500.—Portion of epiderm of lower surface of leaf of *apple*, with layer of parenchyme in immediate contact with it: *a*, *a*, elongated cells overlying the veins of the leaf; *b*, *b*, ordinary epiderm-cells, overlying the parenchyme; *c*, *c*, stomates; *d*, *d*, green cells of the 'spongy' parenchyme, forming a very open network near the lower surface of the leaf.

is of a nature to render the membrane very impermeable to fluids, so as to protect the soft tissue of the leaf from drying up. In most European plants the epiderm contains but a single row of cells, which, moreover, are usually thin-walled ; whilst in the generality



FIG. 501.—Portion of epiderm of upper surface of leaf of *Rochea falcata* as seen at A from its inner side, and at B from its outer side: *a*, *a*, small cells forming inner layer; *b*, *b*, large prominent cells of outer layer; *c*, *c*, stomates disposed between the latter

of tropical species there exist two, three, or even four layers of thick-walled cells, this last number being seen in the *Oleander*, the epiderm of which, when separated, has an almost leathery firmness. This difference in conformation is obviously adapted to the conditions of growth under which these plants respectively exist ; since the

epiderm of a plant indigenous to temperate climates would not afford a sufficient protection to the interior structure against the rays of a tropical sun; whilst the less powerful heat of this country would scarcely overcome the resistance presented by the dense and non-conducting integument of a species formed to exist in tropical climates.

A very curious modification of the epiderm is presented by *Rochea falcata*, which has the surface of its ordinary epiderm (figs. 501, 502, *a*, *a*) nearly covered with a layer of large prominent isolated cells, *b*, *b*. A somewhat similar structure is found in *Mesembryanthemum crystallinum*, commonly known as the 'ice-plant'; a designation it owes to the peculiar appearance of its surface, which looks as if it were covered with frozen dew-drops. In other instances, the epiderm is partially invested by a layer of *scales*, which are nothing else than flattened hairs, often having a very peculiar form; the 'peltate scales' of *Elæagnus* and other shrubs and herbs are very beautiful objects under the microscope. In numerous other cases, again, we find the surface beset with true *hairs*, which occasionally consist of single elongated cells, but are more commonly made up of a linear series, attached end to end. Sometimes these hairs bear little glandular bodies at their extremities, by the secretion of which a peculiar viscidity is given to the surface of the leaf, stem, or flower-stalk, as in many kinds of rose, geranium, &c.; in other instances, the hair has a glandular body at its base, containing a peculiar secretion: when this secretion is of an irritating quality, as in the nettle, it constitutes a 'sting.' A great variety of such organs may be found by a microscopic examination of the surface of the leaves of plants having any kind of superficial investment to the epiderm. Many connecting links present themselves between hairs and scales, such as the stellate hairs of *Deutzia scabra*, which a good deal resemble those within the air-chambers of the yellow water-lily (fig. 469). The so-called 'glands' or 'tentacles' of the sundew (*Drosera*) are not really hairs, but outgrowths of the internal tissue of the leaf, each being penetrated by a fibro-vascular bundle.



FIG. 502.—Portion of vertical section of leaf of *Rochea*, showing the small cells, *a*, *a*, of the inner layer of epiderm; the large cells, *b*, *b*, of the outer layer; *c*, one of the stomates; *d*, *d*, cells of the parenchyme; L, cavity between the parenchymatous cells into which the stomate opens.

The epiderm in many plants, especially those belonging to the grass tribe, has its cell-walls impregnated with *silex*, like that of *Equisetum*; so that, when the organic matter seems to have been got rid of by heat or by acids, the forms of the epidermal cells, hairs, stomates, &c. are still marked out in silex, and (unless the dissipation of the organic matter has been most perfectly accomplished) are most beautifully displayed by polarised light. Such silicified

epiderms are found in the husks of the grains yielded by these plants; and there is none in which a larger proportion of mineral matter exists than that of *rice*, which contains some curious elongated cells with toothed margins. The hairs with which the *palea* (chaff-scales) of most grasses are furnished are strengthened by the like silicious deposit; and in *Festuca pratensis*, one of the common meadow-grasses, the paleæ are also beset with longitudinal rows of little cup-like bodies formed of silex. The epiderm and scaly hairs of *Deutzia scabra* also contain a large quantity of silex, and are remarkably beautiful objects for the polariscope.

In nearly all plants which possess a distinct epiderm, this is perforated by the minute openings termed *stomates* (figs. 500, 502, *c*, *c*), which are bordered by cells of a peculiar form, the 'guard-cells,' differing from those of the epiderm, and more resembling in character those of the tissue beneath. They are further distinguished by containing a larger number of chlorophyll-grains than the ordinary cells of the epiderm. These guard-cells are usually somewhat kidney-shaped, and lie in pairs (fig. 503, *b*, *b*), with an oval opening between them: but by an alteration in their form, the opening may be contracted or nearly closed. In the epiderm of *Yucca*, however, the opening is bounded by two pairs of cells, and is somewhat quadrangular (fig. 498); and a like doubling of the guard-cells, with a narrower slit between them, is seen in the epiderm of the Indian corn (fig. 499). In the stomates of no phanerogam, however, do we meet with any conformation at all to be compared in complexity with that which has been described in the humble *Marchantia*. Stomates are usually found most abundantly (and sometimes exclusively) in the epiderm of the *lower* surface of leaves, where they open into the air-chambers that are left in the parenchyme which lies next the inferior epiderm; in leaves which float on the surface of water, however, they are found in the epiderm of the upper surface only; whilst in leaves that habitually live entirely submerged, as there is no distinct epiderm, so there are no stomates. In the erect leaves of grasses, the *Iris* tribe, &c. they are found equally (or nearly so) on both surfaces. As a general fact, they are least numerous in *succulent* plants, whose moisture, obtained in a scanty supply, is destined to be retained in the system; whilst they abound most in those which exhale fluid most readily, and therefore absorb it most quickly. It has been estimated that no fewer than 160,000 are con-



FIG. 503.—Portion of epiderm of leaf of *Iris germanica* torn from its surface, and carrying away with it a portion of the parenchymatous layer in immediate contact with it: *a*, *a*, elongated cells of the epiderm; *b*, *b*, cells of the stomates; *c*, *c*, cells of the parenchyme; *d*, *d*, impressions on the epidermal cells formed by their contact; *e*, cavity in the parenchyme, corresponding to the stomate.

n every square inch of the under surface of the leaves of *rea* and of several other plants, the greatest number seem-ys to be present where the upper surface of the leaves is destitute of these organs. In *Iris germanica* each surface ly 12,000 stomates in every square inch; and in *Yucca* each as 40,000. In *Oleander*, *Banksia*, and some other plants ates do not open directly upon the lower surface of the but lie in the deepest part of little pits or depressions, e excavated in it and lined with hairs; the mouths of these h the hairs that line them, are well brought into view by thin slice from the surface of the epiderm with a sharp ut the form of the cavities and the position of the stomates be well made out in vertical sections of the leaves.

internal structure of *leaves* is best brought into view by vertical sections, traversing the two layers of epiderm and mediate cellular parenchyme; portions of such sections are figs. 502, 504, and 505. In close apposition with the cells upper epiderm (fig.), which may or may perforated with the (*c*, *c*, *d*, *d*), we find a oft thin-walled cells, ir longest diameter angles to the surface eaf, and containing quantity of chloro-hese generally press ly one against an-at their sides be-tually flattened, and are left, save where definite air-chamber h the stomate opens , *e*); and the com-



FIG. 504.—Vertical section of epiderm and of portion of subjacent parenchyme of leaf of *Iris germanica* taken in a transverse direction: *a*, *a*, cells of epiderm; *b*, *b*, cells at the sides of the stomates; *c*, *c*, guard-cells; *d*, *d*, openings of the stomates; *e*, *e*, cavities in the parenchyme into which the stomates open; *f*, *f*, cells of the parenchyme.

of this superficial layer is well seen when, as often happens, it o closely to the epiderm as to be carried away with this when off (fig. 503, *c*, *c*). This layer, usually peculiar to the upper f leaves, is known as the 'palisade-parenchyme.' Beneath layer of leaf-cells there are usually several others rather pactly arranged; and the tissue gradually becomes more lax, its cells not being in close apposition, and large inter-assages being left amongst them, until we reach the lower which the parenchyme only touches at certain points, its yer forming a sort of network, the so-called 'spongy paren-fig. 500, *d*, *d*) with large interspaces, into which the stomates t is to this arrangement that the darker shade of green invariably presented by the upper surface of leaves is prin-ue, the colour of the component cells of the parenchyme deeper in one part of the leaf than in another. In those owever, whose leaves are erect instead of being horizontal, heir two surfaces are equally exposed to light, the paren-

chyme is arranged on both sides in the same manner, and their epiderms are furnished with an equal number of stomates. This is the case, for example, with the leaves of the common garden *Iris* (fig. 505), in which, moreover, we find a central portion (*d*, *d*) formed by thick-walled colourless tissue, very different either from ordinary leaf-cells or from woody fibre. The explanation of its presence is to be found in the peculiar conformation of the leaves; for if we pull one of them from its origin we shall find that what appears to be the flat expanded blade really exposes but half its surface, the blade being doubled together longitudinally, so that what may be considered its under surface is entirely concealed. The two halves are adherent together at their upper part; but at their lower they are commonly separated by a new leaf which comes up between them; and it is from this arrangement, which resembles the position of the legs of a man on horseback, that the leaves of the Iris tribe are said to be *equitant*. Now by tracing the middle layer of colourless cells, *d*, *d*, down to that lower portion of the leaf where its two halves diverge from one another, we find that it there



FIG. 505.—Portion of vertical longitudinal section of leaf of *Iris*, extending from one of its flattened sides to the other: *a*, *a*, elongated cells of epiderm; *b*, *b*, stomata cut through longitudinally; *c*, *c*, green cells of parenchyme; *d*, *d*, colourless tissue, occupying interior of leaf.

becomes continuous with the epiderm, to the cells of which (fig. 505, *a*) these bear a strong resemblance in every respect save the greater proportion of their breadth to their length. Another interesting variety in leaf-structure is presented by the water-lily and other plants whose leaves float on the surface; for here the usual arrangement is entirely reversed, the closely set layers of green leaf-cells being found in contact with the lower surface, whilst all the upper part of the leaf is occupied by a loose spongy parenchyme, containing a very large number of air-spaces that give buoyancy to the leaf: and these spaces communicate with the external air through the numerous stomates, which, contrary to the general rule, are here found in the upper epiderm alone.

The examination of the foregoing structures is attended with very little difficulty. Many epiderms may be torn off, by the exercise of a little dexterity, from the surfaces of the leaves they invest without any preparation; this is especially the case with monocotyledons generally, the veins of whose leaves run parallel, and with such dicotyledons as have very little woody structure in

their leaves; in those, on the other hand, whose leaves are furnished with reticulated veins to which the epiderm adheres (as is the case in by far the larger proportion), this can only be detached by first macerating the leaf for a few days in water; and if their texture should be particularly firm, the addition of a few drops of nitric acid to the water will render their epiderms more easily separable. Epiderms may be advantageously mounted either in weak spirit or in glycerin-jelly. Very good sections of most leaves may be made by a sharp knife, handled by a careful manipulator; but it is generally preferable to use the microtome, placing the leaf between two pieces either of very soft cork or of elder-pith or carrot, or imbedding it in paraffin. In order to study the structure of leaves with the fulness that is needed for scientific research, numerous sections should be made in different directions, and slices taken parallel to the surfaces at different distances from them should also be examined. There is no known medium in which such sections can be preserved altogether without change; but some one of the methods formerly described will generally be found to answer sufficiently well.

Flowers.—Many small flowers, when looked at entire with a low magnifying power, are very striking microscopic objects; and the interest of the young in such observations can scarcely be better excited than by directing their attention to the new view they thus acquire of the 'composite' nature of the humble down-trodden daisy, or to the beauty of the minute blossoms of many of those umbelliferous plants which are commonly regarded only as rank weeds. The scientific microscopist, however, looks more to the organisation of the separate parts of the flower; and among these he finds abundant sources of gratification, not merely to his love of knowledge, but also to his taste for the beautiful. The general structure of the *sepals* and *petals*, which constitute the 'perianth' or floral envelope, closely corresponds to that of leaves, the chief difference lying in the peculiar change of hue which the chlorophyll almost invariably undergoes in the latter class of organs, and very frequently in the former also. There are some petals, however, whose cells exhibit very interesting peculiarities, either of form or marking, in addition to their distinctive coloration; such are those of the *Pelargonium*, of which a small portion is represented in fig. 506. The different portions of this petal—when it has been dried after stripping it of its epiderm, immersed for an hour or two in oil of turpentine, and then mounted in Canada balsam—exhibit a most beautiful variety of vivid coloration, which is seen to exist chiefly in the thickened partitions of the cells; whilst the surface of each cell presents a very curious opaque spot with numerous diverging prolongations.

FIG. 506.—Cells from petal of *Pelargonium*.

This method of preparation, however, does not give a true idea of the structure of the cells; for each of them has a peculiar mammillary protuberance, the base of which is surrounded by hairs; and this it is which gives the velvety appearance to the surface of the petal, and which, when altered by drying and compression, occasions the peculiar spots represented in fig. 506. Their real character may be brought into view by Dr. Inman's method, which consists in drying the petal (when stripped of its epiderm) on a slip of glass, to which it adheres, and then placing on it a little Canada balsam diluted with turpentine, which is to be boiled for an instant over the spirit lamp, after which it is to be covered with a thin glass. The boiling 'blisters' it, but does not remove the colour; and on examination many of the cells will be found showing the mammilla very distinctly, with a score of hairs surrounding its base, each of these slightly curved, and pointing towards the apex of the mammilla. The petal of the common scarlet pimpernel (*Anagallis arvensis*), that of the common chickweed (*Stellaria media*), together with many others of a small and delicate character, are also very beautiful microscopic objects; and the two just named are peculiarly favourable subjects for the examination of the spiral vessels in their natural position. For the 'veins' which traverse these petals are entirely made up of spiral vessels, none of which individually attain any great length, but one follows or takes the place of another, the conical commencement of each somewhat overlapping the like termination of its predecessor; and where the 'veins' seem to branch, this does not happen by the bifurcation of a spiral vessel, but by the 'splicing on' (so to speak) of one to the side of another, or of two new vessels diverging from each other to the end of that which formed the principal vein.

The *anthers* and *pollen-grains*, also, present numerous objects of great interest, both to the scientific botanist and to the amateur microscopist. In the first place, they afford a good opportunity of studying that form of 'free cell-formation' which seems peculiar to the parts concerned in the reproductive process, and which consists in the development of new cell-walls round a number of isolated masses of protoplasm forming parts of the contents of a 'parent-cell,' so that the new cells lie free within its cavity, instead of being formed by its subdivision, as in the ordinary method of multiplication. If the anther be examined by thin sections at an early stage of its development within the young flower-bud, it will be found to be made up of ordinary cellular parenchyme in which no peculiarity anywhere shows itself; but a gradual 'differentiation' speedily takes place, consisting in the development of a set of very large cells in two vertical rows, which occupy the place of the *loculi* or 'pollen-chambers' that afterwards present themselves; and these cells give origin to the pollen-grains, whilst the ordinary parenchyme remains to form the walls of the pollen-chambers. The pollen-grains are formed within 'mother-cells,' the endoplasm of each breaking up into four segments. These become invested by a double envelope, a firm *extine*, and a thin *intine*, and they are set free, when mature, by the bursting of the pollen-chambers. It is not a little curious

the layer of cells which lines the pollen-chambers should exhibit, considerable proportion of plants, a strong resemblance in struc- through not in form, to the elaters of *Marchantia* (fig. 449). they have in their interior a fibrous deposit, which sometimes s a continuous spiral (like that in fig. 474), as in *Narcissus* and *cyamus*; but it is often broken up, as it were, into rings, as in *Iris* and hyacinth; in many instances it forms an irregular ork, as in the violet and saxifrage; in other cases, again, a f interrupted arches, the fibres being deficient on one side, as in yellow water-lily, bryony, primrose, &c.; whilst a very peculiar ate aspect is often given to these cells by the convergence of the rupted fibres towards one point of the cell-wall, as in the cactus, nium, madder, and many other well-known plants. Various rmediate modifications exist; and the particular form presented a varies in different parts of the wall of one and the same anther. ems probable that, as in Hepaticæ, the elasticity of these spiral may have some share in the opening of the pollen-chambers and ne dispersion of the pollen-grains.

The form of the pollen-grains seems to depend in part upon the e of division of the cavity of the parent-cell into quarters; rally speaking, it approaches the spheroidal, but it is very often tical, and sometimes tetrahedral. It varies more, however, n the pollen is dry than when it is moist; for the effect of the bition of fluid, which usually takes place when the pollen is ed in contact with it, is to soften down angularities, and to g the cell nearer to the typical sphere. The extine or outer of the pollen-grain often exhibits very curious markings, which a due to an increased thickening at some points and a thinning y at others. Sometimes these markings give to the surface layer ose a resemblance to a stratum of cells (fig. 507, B, C, D) that a very careful examination can detect the difference. The hening of the surface by spines or knobby protuberances, as rn at A, is a very common feature; and this seems to enable pollen-grains more readily to hold to the surface whereon they be cast. Besides these and other inequalities of the surface, t pollen-grains have what appear to be pores or slits in their ne (varying in number in different species), through which the ne protrudes itself as a tube, when the bulk of its contents has a increased by imbibition; it seems probable, however, that the ne is not absolutely deficient at these points, but is only thinned y. Sometimes the pores are covered by little disc-like pieces or which fall off when the pollen-tube is protruded. This action s place naturally when the pollen-grains fall upon the surface of stigma, which is moistened with a viscid secretion; and the en-tubes, at first mere protrusions of the inner coat of their cell, nuating themselves between the loosely packed cells of the stigma, r downwards through the style, sometimes even to the length of ral inches, until they reach the ovary. The first change, namely protrusion of the inner membrane through the pores of the exterior, be made to take place artificially by moistening the pollen a water, thin syrup, or dilute acids (different kinds of pollen-

grains requiring different modes of treatment); but the subsequent extension by growth will only take place under the natural conditions. By treating some pollen-grains, as those of *Lilium japonicum*, *L. rubrum*, or *L. auratum*, with the viscid liquid abundantly secreted by the stigma, not only may the extrusion and lengthening of the pollen-tubes be watched, but the grains with their extruded tubes may be preserved almost unchanged by mounting in this liquid.

The darker kinds of pollen may be generally rendered transparent by mounting in Canada balsam; or, if it be desired to avoid the use of heat, in the benzol solution of Canada balsam, setting aside the slide for a time in a warm place. For the less opaque pollens the dammar solution is preferable. The more delicate pollens, however, become too transparent in either of these media; and it is consequently preferable to mount them either dry, or (if they will bear it without rupturing) in fluid. The most interesting forms are found, for the most part, in plants of the orders *Amarantaceæ*, *Cichoriaceæ*, *Cucurbitaceæ*, *Malvaceæ*, and *Passifloreæ*; others are furnished also by *Convolvulus*, *Campanula*, *Œnothera*, *Pelargonium* (geranium), *Polygonum*, *Sedum*, and many other plants. It is frequently preferable to lay down the entire anther, with its adherent pollen-grains (where these are of a kind that hold to it), as an opaque object: this may be done with great advantage in the case of the common mallow (*Malva sylvestris*) or of the hollyhock (*Althæa rosea*), the anthers being picked soon after they have opened, whilst a large proportion of their pollen is yet undischarged, and being laid down as flat as possible, before they have begun to wither, between two pieces of smooth blotting-paper, then subjected to moderate pressure, and finally mounted upon a black surface. They are then, when properly illuminated, most beautiful objects for objectives of $\frac{2}{3}$-, 1-, $1\frac{1}{2}$-, or 2-in. focus, especially with the binocular microscope.[1]



FIG. 507.—Pollen-grains of—A, *Althæa rosea* (hollyhock); B, *Cobæa scandens*; C, *Passiflora cærulea*; D, *Ipomœa purpurea*.

[1] It sometimes happens that when the pollen of pines or firs is set free, large quantities of it are carried by the wind to a great distance from the woods and plantations in which it has been produced, and are deposited as a fine yellow dust, so strongly resembling sulphur as to be easily mistaken for it. This (supposed) general diffusion of sulphur (such as occurred in the neighbourhood of Windsor in 1879) has frightened ignorant rustics into the belief that the 'end of the world' was at hand. Its true nature is at once revealed by placing a few grains of it under the microscope.

› are, in fact, few more interesting objects for the young ɔist than pollen-grains, both from the ease with which they ys be procured, and the almost infinite variety and beauty orms. Some of the commonest weeds, such as the dandelion ndsel, are distinguished by the beauty of their pollen-grains. ns are sometimes nearly or quite spherical, as in the hazel, poplar; or of very irregular outline, as in many grasses. most common form is elliptical, with three or five longi- furrows, as in the wallflower, hyacinth and crocus, the ɔeing sometimes covered with warts, as in the snowdrop. uchsia they are triangular. In addition to the mallow and ɛ, spiny pollen-grains occur in the groundsel, dandelion, a, and many other plants. Sometimes the grains are united by delicate threads, as in the *Rhododendron* and *Fuchsia*; union is much more complete in the *Orchideæ* and *Ascle-* vhere the whole of the pollen in each anther-lobe is glued by a viscid substance into a club-shaped *pollinium*, or pollen- n what are called *anemophilous* flowers, in which the pollen l through the air by the agency of the wind, the grains are ght, dry, and usually spherical; while in *entomophilous* the pollen of which is carried from flower to flower by a search of honey, the various forms above described, and ers, are adapted to cause the grains to adhere to the hairy le of the body of the insect, and thus promote their dis-

The various species of *Epilobium* (willow-herb) and ɪ (evening primrose) are very favourable objects for ob- the emission of pollen-tubes and their entrance into the

tructure and development of the *ovules* that are produced ıe ovary at the base of the pistil, and the operation in which *tilisation* essentially consists, are subjects of investigation ve a peculiar interest for scientific botanists, but which, in nce of the special difficulties that attend the inquiry, are nonly regarded as within the province of ordinary micro-

Some general instructions, however, may prove useful to vould like to inform themselves as to the mode in which the e function is performed in phanerogams. In tracing the d early history of the ovule, very thin sections should be made the flower-bud, both vertically and transversely; but when › is large and distinct enough to be separately examined, it › placed on the thumb-nail of the left hand, and very thin nade with a sharp razor; the ovule should not be allowed ›, and the section should be removed from the blade of the a wetted camel-hair pencil. The tracing downwards of the bes through the tissue of the style may be accomplished by (which, however, will seldom follow one tube continuously reat part of its length), or, in some instances, by careful ı with needles. Plants of the *Orchis* tribe are the most le subjects for this kind of investigation, which is best ı by artificially applying the pollen to the stigma of several nd then examining one or more of the styles daily. 'If

the style of a flower of *Epipactis*,' says Schacht, 'to which the pollen has been applied about eight days previously, be examined in the manner above mentioned, the observer will be surprised at the extraordinary number of pollen-tubes, and he will easily be able to trace them in large strings, even as far as the ovules. *Viola tricolor* (heartsease) and *Ribes nigrum* and *rubrum* (black and red currant) are also good plants for the purpose; in the case of the former plant withered flowers may be taken and branched pollen-tubes will not unfrequently be met with.' The entrance of the pollen-tube into the micropyle may be most easily observed in *orchidaceous* plants and in *Euphrasia*, it being only necessary to tear open with a needle the ovary of a flower which is just withering, and to detach from the placenta the ovules, almost every one of which will be found to have a pollen-tube sticking in its micropyle. These ovules, however, are too small to allow of sections being made, whereby the origin of the embryo may be discerned; and for this purpose, *Œnothera* (evening primrose) has been had recourse to by Hofmeister, whilst Schacht recommends *Lathræa squamaria*, *Pedicularis palustris*, and particularly *Pedicularis sylvatica*.



FIG. 508.—Seeds as seen under a low magnifying power: A, poppy; B, *Amaranthus* (prince's feather); C, *Antirrhinum majus* (snapdragon); D, *Dianthus* (clove-pink); E, *Bignonia*.

We have now, in the last place, to notice the chief points of interest to the microscopist which are furnished by mature *seeds*. Many of the smaller kinds of these bodies are very curious, and some are very beautiful objects when looked at in their natural state under a low magnifying power. Thus the seed of the poppy (fig. 508, A) presents a regular reticulation upon its surface, pits, for the most part hexagonal, being left between projecting walls; that of the pink (D) is regularly covered with curiously jagged divisions, every one of which has a small bright black hemispherical knob in its middle; that of *Amaranthus hypochondriacus* has its surface traced with extremely delicate markings (B); that of *Antirrhinum* is strangely irregular in shape (C), and looks almost like a piece of furnace-slag; and those of many *Bignoniaceæ* are remarkable for the beautiful radiated structure of the translucent membrane which surrounds them (E). This structure is extremely well seen in the seed of the *Eccremocarpus scaber*, a half-hardy climbing plant common in our gardens; and when its membranous 'wing' is examined under a sufficient magnifying power, it is found to be

ed by an extraordinary elongation of the cells of the seed-coat he margin of the seed, the side-walls of which cells (those, ely, which lie in contact with one another) are thickened so as rm radiating ribs for the support of the wing, whilst the front back walls (which constitute its membranous surface) retain their nal transparence, being marked only with an indication of l deposit in their interior. In the seed of *Dictyoloma peruviana*, les the principal 'wing' prolonged from the edge of the seed-, there is a series of successively smaller wings, whose margins concentric rings over either surface of the seed; and all these s are formed of radiating fibres only, composed, as in the pre-g case, of the thickened walls of adjacent cells, the intervening brane, originally formed by the front and back walls of these , having disappeared, apparently in consequence of being un-orted by any secondary deposit. Several other seeds, as those *henogyne speciosa* and *Lophospermum erubescens*, possess wing-appendages; but the most remarkable development of these ns is said by Mr. Quekett to exist in a seed of *Calosanthes* *ca*, an East Indian plant, in which the wing extends more than ch on either side of the seed. Some seeds are distinguished by culiarity of form which, although readily discernible by the d eye, becomes much more striking when they are viewed under ry low magnifying power. This is the case, for example, with eeds of the carrot, whose long radiating processes make it bear, r the microscope, no trifling resemblance to some kinds of star-; and with those of *Cyanthus minor*, which bear about the same ee of resemblance to shaving-brushes. In addition to the pre-g, the following may be mentioned as seeds easily to be ined, and as worth mounting for opaque objects:—*Anagallis*, *hum graveolens*, *Begonia*, *Carum carui*, *Coreopsis tinctoria*, *ra*, *Delphinium*, *Digitalis*, *Elatine*, *Erica*, *Gentiana*, *Gesneria*, *cyamus*, *Hypericum*, *Lepidium*, *Limnocharis*, *Linaria*, *Lychnis*, *mbryanthemum*, *Nicotiana*, *Origanum onites*, *Orobanche*, *Petunia*, *da*, *Saxifraga*, *Scrophularia*, *Sedum*, *Sempervivum*, *Silene*, *aria*, *Symphytum asperrimum*, and *Verbena*. The following be mounted as transparent objects in Canada balsam: *era*, *Hydrangea*, *Monotropa*, *Orchis*, *Parnassia*, *Pyrola*, *Saxi-a*.[1] The seeds of umbelliferous plants generally are remarkable the peculiar *vittæ*, or receptacles for essential oil, which are d in the closely applied pericarp or seed-vessel which encloses . Various points of interest respecting the structure of the or envelope of seeds, such as the fibre-cells of *Cobœa* and *mia*, the stellate cells of the star-anise, and the densely con-ated tissue of the 'shells' of the coquilla-nut, cocoa-nut, &c. ng been already noticed, we cannot here stop to do more than rt to the peculiarity of the constitution of the husk of corn-s. In these, as in other grasses, the ovary itself continues to lop the seed, giving a covering to it that surrounds the testa, closely adheres to it. The 'bran' detached in grinding consists

[1] A part of these lists have been derived from the *Micrographic Dictionary*.

not only of these two coats, but also (as the microscope reveals) of an outer layer of the grain itself, formed of hexagonal cells disposed with great regularity. As these are filled with *gluten*, the removal of this layer takes away one of the most nutritious parts of the grain; and it is most desirable, therefore, that only the two outer indigestible coats should be detached by the 'decorticating' process devised for the purpose. The hexagonal cell-layer is so little altered by a high temperature as still to be readily distinguishable when the grain has been ground after roasting, thus enabling the microscopist to detect even a small admixture of roasted corn with coffee or chicory without the least difficulty.[1]

[1] In a case in which the Author was called upon to make such an investigation, he found as many as *thirty* distinctly recognisable fragments of this cellular envelope in *a single grain* of a mixture consisting of chicory with only 5 per cent. of roasted corn.

CHAPTER XII

ICROSCOPIC FORMS OF ANIMAL LIFE—PROTOZOA

on; now, to the Animal Kingdom, we begin by directing ıtion to those minute and simple forms which correspond in al series with the *Protophyta* in the vegetable (Chap. VIII); ı is the more desirable since the formation of a distinct ı which the name of PROTOZOA (first proposed by Siebold) appropriately given is one of the most interesting results scopic inquiry. This group, which must be placed at the ıe of the animal scale, beneath the great sub-kingdoms— ıta, Mollusca, Articulata, and Radiata—marked out by s characterised by the extreme simplicity that prevails in ıture of the beings that compose it, the lowest of them ngle protoplasmic particles or 'jelly-specks,' whilst even ıe highest, however numerous their units may be, these are ıg *protophytes*) mere repetitions of one another, each f maintaining an independent existence. In this there is a ious and significant parallelism to the earliest embryonic higher animals; for the fertilised germ of any one of t shapes itself as a single cell, and then, by repeated binary ons, develops itself into a *morula* or 'mulberry-mass' of ıresponding to the 'multicellular' organisms met with he higher Protozoa. There is, so far, in neither case any ıat 'differentiation' of organs which is characteristic of the ıimals; but whilst, in the Protozoön, each cell is not merely o its fellows, but is independent of them, the *morula*, in go on to a higher stage, becomes the subject of a series of ıental changes tending to the production of a single whole, rts are mutually dependent. The first of these changes is ırsion into a *gastrula* or primitive stomach, whose wall is of a double membrane, the outer lamella, or *ectoderm*,[1] rived directly from the external cell-layer of the morula, ıe inner, or *endoderm*, is formed by the 'invagination' of r into the space left void by the dissolution of the central ıe 'morula.' This *gastrula-stage*,[2] as we shall see hereafter,

[1] ırms *epiblast* and *hypoblast* are generally used by English embryologists the 'ectoderm' and 'endoderm' used here.

[2] *ıstrula-stage* is in a number of cases brought about by a concentric split- walls of the morula into two layers, and by the appearance at one point which leads into the central cavity: this cavity is the original segmenta- of the morula, and not a fresh cavity, as in 'invaginate gastrulæ.'

remains permanent in the great group of *Cœlenterata*, though the endoderm and ectoderm are separated from each other in its higher forms by the development of generative and other organs between them. But in all classes above the cœlenterates the primitive stomach forms a part, and often only an insignificant part, of the whole digestive tract. Thus the whole animal kingdom may be divided, in the first place, into the PROTOZOA, which are either single cells or aggregates of similar cells corresponding to the *morula*-stage of higher types; and the METAZOA, in which the morula takes on the condition of an individualised organism, the life of every part of which contributes to the general life of the whole. Putting this important truth into other words, we may say of the Protozoa that they are either unicellular or unicellular aggregates, while the Metazoa are multicellular, and their constituent cells have different functions.

The lowest of the *Protozoa*, however, like the simplest protophytes, do not even attain the rank of a true *cell*, understanding by that designation a definite protoplasmic unit (*plastid*), which is limited by a cell-wall, and contains a 'nucleus.' For they consist of particles of protoplasm, termed 'cytodes,' of indefinite extent, which have neither cell-wall nor nucleus, but which yet take in and digest food, convert it into the material of their own bodies, cast out the indigestible portions, and reproduce their kind, with the regularity and completeness that we have been accustomed to regard as characteristic of higher animals. With regard, however, to this apparent absence of a nucleus we have to bear in mind that the progress of research is continually diminishing the number of forms devoid of a nucleus, or, at any rate, of a nuclear material scattered throughout the substance of the plastid; in retaining, therefore, the group of non-nucleated Protozoa we are acting on the principle of not going beyond our evidence, and by no means reflecting on the later systematists who have merged the various types (whether nucleated or non-nucleated) among other divisions of the Protozoa. Between some of these *Monerozoa* (as they have been designated by Professor Haeckel, who first drew attention to them) and the *Myxomycetes* or the *Chlamydomyxa* already described, no definite line of division can be drawn, the only justification for the separation here adopted being that the affinities of the former seem to be rather with the lowest forms of vegetation, whilst the whole life-history of the types now to be described, and the connected gradation by which they pass into undoubted rhizopods, leave no doubt of *their* claim to a place in the animal kingdom.

MONEROZOA.

A characteristic example of this lowest protozoic type is presented by the *Protomyxa aurantiaca* (fig. 509), a marine 'moner' of an orange-red colour, found by Professor Haeckel upon dead shells of *Spirula* near the Canary Islands. In its active state it has the stellar form shown at F, its arborescent extensions dividing and inosculating so as to form a constantly changing network of proto-

plasmic threads, along which stream in all directions orange-red granules, obviously belonging to the body itself, together with foreign organisms (*b*, *c*)—such as marine diatoms, radiolarians, and infusoria—which, having been entrapped in the pseudopodial network, are carried by the protoplasmic stream into the central mass, where the nutrient matter of their bodies is extracted, the hard skeletons being cast out. Neither nucleus nor contractile vesicle is to be discerned, but numerous floating and inconstant vacuoles (*a*) are dispersed



FIG. 509.—*Protomyxa aurantiaca*: A, encysted statospore; B, incipient formation of swarm-spores, shown at C escaping from the cyst, at D swimming freely by their flagellate appendages, and at E creeping in the amœboid condition; F, fully developed reticulate organism, showing numerous vacuoles, *a*, and captured prey, *b*, *c*.

through the substance of the body. After a time the currents become slower; the ramified extensions are gradually drawn inwards; and, after ejecting any indigestible particles it may still include, the body takes the form of an orange-red sphere round which a cyst soon forms itself, as shown in A. After a period of quiescence the protoplasmic substance retreats from the interior of the cyst, and breaks up into a number of small spheres (B), which, at first inactive, soon begin to move within the cyst, and change their shape to that of a pear with the small end drawn out to a point.

The cyst then bursts, and the red pear-shaped bodies issue forth into the water (C), moving freely about by the vibrations of *flagella* formed by the drawing out of their small ends, just as do the flagellated zoöspores of protophytes. These bodies, being without trace of either nucleus, contractile vesicle, or cell-wall, are to be regarded as particles of simple homogeneous protoplasm, to which the designation *plastidules* has been appropriately given. After about a day the motions cease; the flagella are drawn in, and the plastidules take the form and lead the life of *Amœbæ*, putting forth inconstant pseudopodial processes, and engulfing nutrient particles in their substance (D). Two or more of these amœbiform bodies



FIG. 510.—*Vampyrella spirogyræ* as seen at A sucking out contents of *Spirogyra*-cell; at B in encysted condition, the cyst *a* enclosing granular protoplasm *b*; at C, division of contents of cyst into tetraspores, of which one is escaping in the amœboid condition to develop itself into the adult form shown at D.

unite to form a 'plasmodium,' as in the *Myxomycetes*; its pseudopodial extensions send out branches which inosculate to form a network; and the body grows, by the ingestion of nutriment, to the size of the original. In this cycle of change there seems no intervention of a generative act, the coalescence of the amœbiform plastidules having none of the characters of a true 'conjugation.' But it is by no means improbable that after a long course of multiplication by successive subdivisions some kind of conjugation may intervene.

Another very interesting 'moneric' type is the *Vampyrella*, of which one form (fig. 510) has long been known in its encysted condition as a minute brick-red sphere attached to the filaments of

the conjugate *Spirogyra*; whilst another (fig. 511, *a*, *a*) similarly attaches itself to the branches of *Gomphonema*. The walls of the cysts are composed of two membranes, of which the interior gives the characteristic reaction of cellulose, whilst the softer external layer is nitrogenous. After remaining some time in the quiescent condition the encysted protoplasm breaks up into two or four 'tetraspores' (fig. 511, *b*, *d*); these escape by openings in the cyst (fig. 510, C), and soon take the spherical form, emitting very slender pseudopodial filaments (figs. 510, D, 511, B) like those of an *Actinophrys*, but possessing neither nucleus nor contractile vesicle. In this condition they show great activity, moving about in search of the special nutriment they require, drawing themselves out in strings and fine filaments which tear asunder and again unite to send off branches and form fine fan-like expansions, and these occasionally contracting again into minute spheres. When the *V. spirogyræ* is watched in water containing some filaments of *Spirogyra*, it may be seen to wander until it meets one of these filaments, to which, if it be healthy and loaded with chlorophyll, it attaches itself. It soon begins to perforate the wall of the filament; and when the interior of this has been reached, its endoplasm, carrying with it the chlorophyll-granules it includes, passes slowly into the body of the *Vampyrella*. In this manner cell after cell is emptied of its contents; and the plunderer, satiated with food, resumes its quiescent spherical form to digest it. The chlorophyll-granules which it has ingested become diffused through the body, but gradually cease to be distinguishable, the protoplasmic mass assuming a brick-red colour. The first layer it exudes to form its cyst is the outer or nitrogenous investment, within which the cellulose layer is afterwards formed. The *V. gomphonematis* in like manner creeps over the stems and branches of the *Gomphonema* (fig. 511, *e*), adapting itself to the form of its support; and as soon as it has reached one of the terminal silicious cells of the diatom, it extends itself over it so as completely to envelop the cell in a thin layer of protoplasm. From the surface of this a number of fine pseudopodia radiate into the surrounding water (*f*); whilst another portion of the protoplasm finds its way between the two silicious valves into the interior, and appropriates its contents. The valves, when emptied, break off from their support, and are cast out of the body of the *Vampyrella*, which soon proceeds to another *Gomphonema*-cell and plunders it in the same manner. After thus ingesting the nutriment furnished by several cells, and acquiring its full size, it passes, like *V. spyrogyræ*, into the encysted condition, to recommence—after a period of quiescence—the same cycle of change. Mr. Bolton discovered near Birmingham, and Professor Ray Lankester described, a form allied to *Vampyrella*—*Archerina Boltoni*—which is remarkable for being chlorophyllogenous; this species presents another interesting peculiarity. 'Groups of ghost-like outlines corresponding to chlorophyll-corpuscles and their radiant filamentous pseudopodia, entirely devoid of any substance,' were observed, and were compared to the numerous cellulose chambers which are secreted and abandoned by the protoplasm of *Chlamydomyxa*.

Intermediate between the foregoing and the 'reticularian' pods, to be presently described, is another simple protozoön covered in ponds in Germany by MM. Claparède and Lachn and named by them *Lieberkuehnia Wageneri*.[1] The whole stance of the body of this animal and its pseudopodial exten (fig. 512), is composed of a homogeneous, semi-fluid, granular p plasm, the particles of which, when the animal is in a sta

FIG. 511.—*Vampyrella gomphonematis*: A, colony of *Gomphonema* attacked by *Vampyrellæ*; *a*, encysted state; *b*, *b*, cysts with contents breaking up into tetraspores, *d*, *d*, seen escaping at *e*; at *f* is shown a *Vampyrella* sucking out contents of *Gomphonema*-cells, the emptied frustules of which, *g*, *h*, are cast forth. B, isolated *Vampyrella* creeping about by its extended pseudopodia.

activity, are continually performing a circulatory movement, w may be likened to the rotation of the particles in the protopla network within the cell of a *Tradescantia*. It is a marked peculi

[1] *Etudes sur les Infusoires et les Rhizopodes*, Geneva, 1858–1861. The bes figure of *Lieberkühnia*, given by M. Claparède, has been reproduced by the A in Plate I. of his *Introduction to the Study of the Foraminifera*.

eudopodial extension of this type that it does not take place
ion from all parts of the body indifferently, but that it
entirely from a sort of trunk that soon divides into branches,
gain speedily multiply by further subdivision, until at last
ide of finer and yet finer threads are spun out by whose
l inosculations a complicated network is produced, which
likened to an animated spider's web. The protoplasm is
in a very delicate and closely applied envelope. Any small
ry particles that may come into contact with the glutinous
of the pseudopodia are retained in adhesion by it, and
partake of the general movement going on in their sub-
This movement takes place in two principal directions—
body towards the extremities of the pseudopodia, and from
tremities back to the
ain. In the larger
a double current may
two streams passing
ame time in opposite
s; but in the finest
the current is single,
anule may be seen to
one of them to its very
y, and then to return,
meeting and carrying
h it a granule that
n advancing in the
direction. Even in
ler processes granules
times observed to come
nd, to oscillate for a
l then to take a retro-
urse, as if they had
ngled in the opposing
just as is often to be
hara. When a granule
t a point where a fila-
rcates, it is often arrested for a time, until drawn into one
ther current; and when carried across one of the bridge-
ections into a different band, it not unfrequently meets a
roceeding in the opposite direction, and is thus carried back
ody without having proceeded very far from it. The
dial network along which this 'cyclosis' takes place is con-
ndergoing changes in its own arrangement, new filaments
forth in different directions, sometimes from its margin,
s from the midst of its ramifications, whilst others are
. Not unfrequently it happens that to a spot where two or
nents have met, there is an afflux of the protoplasmic sub-
t causes it to accumulate there as a sort of secondary centre,
ch a new radiation of filamentous processes takes place.
lly the pseudopodia are entirely retracted, and all activity
o that the body presents the appearance of an inert lump.

FIG. 512.—*Lieberkuehnia Wageneri.*

But if watched sufficiently long its activity is resumed, so that it may be presumed to have been previously satiated with food, which is undergoing digestion during its stationary period. No encysting process has been noticed in *Lieberkuehnia*; but Cienkowsky has discovered that in *L. paludosa* reproduction is effected by a process of fission, which commences with the formation of a new pseudopodial stalk at the base of the animal, the envelope being perforated at this point. As the marine type of it occurs on our own coasts, the fresh-water type may very likely be found in our ponds, and either may be recommended as a most worthy object of careful study.

Rhizopoda.

We now arrive at the group of *rhizopods*, or 'root-footed' animals, first established by Dujardin for the reception of the *Amœba* and its allies, which had been included by Professor Ehrenberg among his infusory animalcules, but which Dujardin separated from them as being mere particles of *sarcode* (protoplasm), having neither the definite body-wall nor the special mouth of the true *Infusoria*, but putting forth extensions of their sarcodic substance, which he termed *pseudopodia* (or false feet), serving alike as instruments of locomotion and as prehensile organs for obtaining food. According to Dujardin's definition of this group, the *Monerozoa*, already described, would be included in it; but it seems on various grounds desirable to limit the term *Rhizopoda* to those Protozoa in which the presence of a *nucleus*, the differentiation of an *ectosarc* (or firmer superficial layer of protoplasm) from the semi-fluid *endosarc*, together with the more definite form and restricted size, indicate a distinct approach to the condition of true cells. Many different schemes for the classification of the rhizopods have been proposed, but none of them can be regarded as entirely satisfactory, our knowledge of the reproductive processes, and of other important parts of the life-history of these creatures, being still extremely imperfect; and as some parts of the scheme proposed by the Author twenty years ago,[1] based on the characters of the pseudopodial extensions, have been accepted by more recent systematists, he thinks it best still to adhere to it, as seeming to him to be, on the whole, most natural.

I. In the first division, *Reticularia*, the pseudopodia freely ramify and inosculate, so as to form a network, exactly as in *Lieberkuehnia*, from which they are distinguished by the possession of a nucleus and by the investment of their sarcodic bodies in a firm envelope. This is most commonly either a *calcareous* shell of very definite shape, or a *test* built up of sand-grains or other minute particles more or less firmly united by a calcareous cement exuded from the sarcodic body. These testaceous forms, which are exclusively marine, constitute the group of *Foraminifera*, whose special interest to the microscopist entitles it to separate consideration; and it is only for convenience that two *Reticularia* which inhabit fresh water also, and the envelopes of whose bodies are

[1] *Natural History Review*, 1861, p. 456; and *Introduction to the Study of the Foraminifera*, 1862, chap. ii.

usually membranous, are here separated from the Foraminifera (to which they properly belong) for description as types of the group. The *Reticularia* have little locomotive power, and only seem to exercise it to find a suitable situation for their attachment, the capture of their food being effected by their pseudopodial network.

II. The second division, *Heliozoa*, consists of the rhizopods whose pseudopodia extend themselves as straight radiating rods, having little or no tendency to subdivide or ramify, though they are still sufficiently soft and homogeneous (at least in the lower types), to coalesce when they come into contact with each other. These have usually (probably always) a contractile vesicle as well as a nucleus; and the higher forms of them are characterised by the enclosure of symbiotic yellow corpuscles (*zoöchlorellæ*) in the substance of their endosarc. By far the larger number of this group also have skeletons of mineral matter, which are always *silicious*; and these are sometimes perforated casings of great regularity of form, as in the marine *Polycystina*, sometimes internal frameworks of marvellous symmetry, as in the marine *Radiolaria*. These two groups, also, will be reserved for special notice, the simple *Heliozoa*, which are among the commonest inhabitants of fresh water, furnishing the best illustrations of the essential characters of the type. They seem, for the most part, to have but little locomotive power, capturing their prey by their extended pseudopodia. The tendency of modern writers is to separate the *Heliozoa*, as here understood, into the two groups of *Heliozoa* (sens. strict.) and *Radiolaria*, the latter being distinguished by the presence of a central capsule or mass of protoplasm surrounded by a special envelope, the better development of the skeleton, the greater tendency of the pseudopodia to coalesce with one another, and the not infrequent presence of 'yellow bodies.'

III. The third group, *Lobosa*, contains the rhizopods which most nearly approach the condition of true cells, in the differentiation of their almost membranous ectosarc and their almost liquid endosarc, and in the non-coalescence of their pseudopodial extensions, which, instead of being either thread-like or rod-like, are *lobate*, that is, irregular projections of the body, including both ectosarc and endosarc, which are continually undergoing change both in form and number. The *Lobosa* are comparatively active in their habits, moving freely about in search of food, which is still received into the substance of their bodies through any part of their surface—unless this is enclosed in envelopes, such as are formed by many of them, either by exudation from the surface of their bodies of some material (probably chitinous) which hardens into a membrane, or by aggregating and uniting grains of sand or other small solid particles, which they build up into 'tests.' A large proportion of them are inhabitants of fresh water, and some are even found in damp earth.

Reticularia.—This type is very characteristically represented by the genus *Gromia* (fig. 513), some of whose species are marine, and are found, like ordinary *Foraminifera*, among tufts of corallines, algæ, &c.; whilst others inhabit fresh water, adhering to Confervæ and other plants of running streams. It was in this type that the presence of a nucleus, formerly supposed to be wanting in Reticularia

generally, was first established by Dr. Wallich. The sarcode-body of this animal is encased in an egg-shaped, brownish-yellow, chitinous envelope, which may attain a diameter of from $\frac{1}{72}$th to $\frac{1}{78}$th of an inch, looking to the naked eye so like the egg of a zoöphyte or the seed of an aquatic plant, that its real nature would not be suspected so long as it remained quiescent. The 'test' has a single round orifice, from which, when the animal is in a state of activity, the sarcodic substance streams forth, speedily giving off ramifying extensions, which, by further ramification and inosculation, form a network like that of Lieberkühnia. But the sarcode also extends itself so as to form a continuous layer over the whole exterior of the 'test,' and from any part of this layer fresh pseudopodia may be given off. By the alternate extension and contraction of these, minute protophytes and protozoa are entrapped and drawn into the interior of the test, where their nutritive material is extracted and assimilated; and if the 'test' (as happens in some species) be sufficiently transparent, the indigestible hard parts (such as the silicious valves of diatoms, shown in fig. 513) may be distinguished in the midst of the sarcodic substance. By the same agency the *Gromia* sometimes creeps up the sides of a glass vessel. In the intervals of quiescence, on the other hand, the whole sarcodic body, except a film that serves for the attachment of the test, is withdrawn into its interior.



FIG. 513.—*Gromia oviformis*, with its pseudopodia extended.

Another example of the reticularian group is afforded by the curious little *Microgromia socialis* (fig. 514), first discovered by Mr. Archer, and further investigated with great care by Hertwig,[1] which

[1] 'Ueber *Microgromia*,' in *Archiv für Mikr. Anat.* bd. x. Supplement.

has the curious habit of uniting with neighbouring individuals, by the fusion of the pseudopodia, into a common 'colony,' the individuals sometimes remaining at a distance from one another as at A, but sometimes aggregating themselves into compact masses as at B. The nearly globular thin calcareous shell is prolonged into a short neck having a circular orifice, from which the sarcode-body extends itself,



FIG. 514.—*Microgromia socialis*: A, colony of individuals in extended state, some of them undergoing transverse fission; B, colony of individuals (some of them separated from the principal mass) in compact state; C, D, formation and escape of swarm-spore, seen free at E.

giving off very slender pseudopodia which radiate in all directions. A distinct nucleus can be seen in the deepest part of the cavity; while a contractile vesicle lies embedded in the sarcodic substance nearer the mouth. Multiplication by duplicative subdivision has been distinctly observed in this type; but with a peculiar departure

from the usual method. A transverse constriction divides the body into two halves—as shown in two individuals of colony A—each half possessing its own nucleus and contractile vesicle; the posterior segment, which at first lies free at the bottom of the cell, then presses forwards towards its orifice, as shown at C, and finally, by amœboid movements, escapes from it, sometimes stretching itself out like a worm (as seen at D), sometimes contracting itself into a globe, and sometimes spreading itself out irregularly over the pseudopodia of the colony. But it finally gathers itself together and takes an oval form; and either develops a pair of flagella, and forsakes the colony as a free-swimming *monad*, or assumes the form of an *Actinophrys*, moving about by three or four pointed pseudopodia—probably in each case coming after a time to rest, excreting a shell, and laying the foundation of a new colony. There is reason to think that a multiplication by longitudinal fission also takes place, in which the escaping segment and the one left behind in the old shell remain attached by their pseudopodia, and the former develops a new shell without undergoing any change of condition.

Heliozoa.—The *Actinophrys sol*, sometimes termed the 'sun-animalcule' (fig. 515), is one of the commonest examples of this group, being often met with in lakes, ponds, and streams, amongst Confervæ and other aquatic plants, as a whitish-grey spherical particle distinguishable by the naked eye, from which (when it is brought under sufficient magnifying power) a number of very pellucid, slender, pointed rods are seen to radiate. The central portion of the body is composed of homogeneous sarcode, enclosing a distinct nucleus; but the peripheral part has a 'vesicular' aspect, as in the type next to be described (fig. 516). This appearance is due to the number of 'vacuoles' filled with a watery fluid, which are included in the sarcodic substance, and which may be artificially made either to coalesce into larger ones or to subdivide into smaller. A 'contractile vesicle,' pulsating rhythmically with considerable regularity, is always to be distinguished, either in the midst of the sarcode-body, or (more commonly) at or near its surface; and it sometimes projects considerably from this, in the form of a sacculus with a delicate membranous wall, as shown at fig. 515, A, *cv*. The cavity of this sacculus is not closed externally, but communicates with the surrounding medium—not, however, by any distinct and permanent orifice, the membraniform wall giving way when the vesicle contracts, and then closing over again. This alternating action seems to serve a respiratory purpose, the water thus taken in and expelled being distributed through a system of channels and vacuoles excavated in the substance of the body, some of the vacuoles which are nearest the surface being observed to undergo distension when the vesicle contracts, and to empty themselves gradually as it refills. The body of this animal is nearly motionless, but it is supplied with nourishment by the instrumentality of its pseudopodia, its food being derived not merely from vegetable particles, but from various small animals, some of which (as the young of Entomostraca) possess great activity as well as a comparatively high organisation. When one of these happens to come into contact with

one of the pseudopodia (which have firm axis-filaments (*ax*) clothed with a granular sarcode), this usually retains it by adhesion ; but the mode in which the particle thus taken captive is introduced into the body differs according to circumstances. If the prey is large and vigorous enough to struggle to escape from its entanglement, it may usually be observed that the neighbouring pseudopodia bend over and apply themselves to it, so as to assist in holding it captive, and that it is slowly drawn by their joint retraction towards the body of its captor. Any small particle not capable of offering active resistance, on the other hand, may be seen after a little time to glide towards the central body along the edge of the pseudopodium, without any



FIG. 515.—*Actinophrys sol*: A, figure showing the wide vacuolated cortical layer or ectosarc (*R*) and the fine granulated endosarc (*M*); *n*, central nucleus, *ax*, axial filaments of pseudopodia; *cv*, contractile vacuole; *N* food-mass inclosed in a large food-vacuole. B, a colony of four individuals, after treatment with acetic acid; *R*, *M*, and *N*, as before; *r*, *r*, vacuoles. C, a cyst; *z*, *c*, outer and inner envelopes. D, a burst cyst from which the young is escaping, though still inclosed by the inner envelope. (From Bütschli, after Grenacher, Stein, and Cienkowsky.)

visible movement of the latter, much in the same manner as in Gromia. When in either of these modes the food has been brought to the surface of the body, this sends over it on either side a prolongation of its own sarcode-substance ; and thus a marked prominence is formed (fig. 515, A, *N*), which gradually subsides as the food is drawn more completely into the interior. The struggles of the larger animals, and the ciliary action of *Infusoria* and *Rotifera*, may sometimes be observed to continue even after they have been thus received into

the body; but these movements at last cease, and the process of digestion begins. The alimentary substance is received into one of the vacuoles, where it lies in the first instance surrounded by liquid; and its nutritive portion is gradually converted into an indistinguishable gelatinous mass, which becomes incorporated with the material of the sarcode-body, as may be seen by the general diffusion of any colouring particles it may contain. Several vacuoles may be thus occupied at one time by alimentary particles; frequently four to eight are thus distinguishable, and occasionally ten or twelve; Ehrenberg, in one instance, counted as many as sixteen, which he described as multiple stomachs. Whilst the digestive process, which usually occupies some hours, is going on, a kind of slow circulation takes place in the entire mass of the endo-



FIG. 516.—*Actinosphærium Eichornii*: *m*, endosarc; *r*, ectosarc; *c*, *c*, contractile vacuoles.

sarc with its included vacuoles. If, as often happens, the body taken in as food possesses some hard indigestible portion (as the shell of an entomostracan or rotifer), this, after the digestion of the soft parts, is gradually pushed towards the surface, and is thence extruded by a process exactly the converse of that by which it was drawn in. If the particle be large, it usually escapes at once by an opening which extemporises itself for the occasion; but if small it sometimes glides along a pseudopodium from its base to its point, and escapes from its extremity.

The ordinary mode of reproduction in *Actinophrys* seems to be by binary subdivision, its spherical body showing an annular con-

striction, which gradually deepens so as to separate its two halves by a sort of hour-glass constriction, and the connecting band becoming more and more slender, until the two halves are completely separated. The segments thus divided are not always equal, and sometimes their difference in size is very considerable. A junction of two individuals, on the other hand, has been seen to take place in *Actinophrys*, and has been supposed to correspond to the 'conjugation' of protophytes; it is very doubtful, however, whether this junction really involves a complete fusion of the substance of the bodies which take part in it, and there is not sufficient evidence that it has any true generative character. Certain it is that such a junction or 'zygosis' may take place, not between two only, but even several individuals at once, their number being recognised by that of their contractile vesicles; and that, after remaining thus united for several hours as a colony,



FIG. 517.—Marginal portion of *Actinosphærium Eichornii* as seen in optical section under a higher magnifying power: *m*, endosarc; *r*, ectosarc; *a*, *a*, *a*, pseudopodia; *n*, *n*, nuclei with nucleoli; *f*, ingested food-mass.

they may separate again without having undergone any discoverable change.

Under the generic name *Actinophrys* was formerly ranked the larger but less common Heliozoön, now distinguished as *Actinosphærium Eichornii* (fig. 516); the pseudopodia are longer and more numerous; there are generally a number instead of one contractile vacuole, and there is more than one nucleus. The axis of the pseudopodia may be seen to be clothed with a layer of soft sarcode derived from the superficial or cortical zone of the body. Several nuclei (*n*, *n*) are usually to be seen imbedded in the protoplasmic mass. The general life-history of this type corresponds with that of the pre-

ceding, but its mode of reproduction presents some marked peculiarities. In many, if not in all cases it commences, as first observed by Kölliker, with the conjugation of two separate individuals. The binary segmentation is preceded by a withdrawal of the pseudopodia, even their clearly defined axis becoming indistinct and finally disappearing; the body becomes enveloped by a clear gelatinous exudation, which forms a kind of cyst; and within this the process of binary subdivision is repeatedly performed, until the original single mass is replaced by a sort of *morula*, each spherule of which shows the distinction between the central and cortical regions, the former including a single nucleus, whilst the latter is strengthened by silicious deposit into a firm investment. After remaining in this state during the winter the young *Actinosphæria* come forth in the spring without this silicious investment, and gradually grow into the likeness of their parent.[1]



FIG. 518. — *Clathrulina elegans*: A, complete organism; B, swarm-spore showing nucleus, *n*, and two contractile vesicles near its opposite end.

A large number of new and curious freshwater forms of this type are being frequently brought under notice, of which the *Clathrulina elegans* (fig. 518) may be specially mentioned as presenting an obvious transition to the *Polycystine* type. This has been found in various parts of the Continent, and also (by Mr. Archer[2]) in Wales and Ireland, occurring chiefly in dark ponds shaded by trees and containing decaying leaves. Its soft sarcode-body, which is not differentiated into ectosarc and endosarc, is encased by a silicious capsule of spherical form, regularly perforated with oval

[1] On the results of the artificial division of *Actinosphærium* see K. Brandt, *Ueber Actinosphærium Eichornii*, Halle a/S., 1877; Gruber, *Berichte d. Naturf. Ges. zu Freiburg i B.*, 1886; Nussbaum, *Arch. f. Mikr. Anat.* xxvi.

[2] See his memoir on Fresh-water Radiolaria in *Quart. Journ. of Microsc. Sc.* n.s. vol. ix. 1869, p. 250.

apertures, and supported on a long silicified peduncle. The body itself and the pseudopodia which it puts forth through the apertures of the capsule seem closely to correspond with those of *Actinophrys*. Reproduction here takes place not only by binary fission, but by the formation of 'swarm-spores.' In the first mode, one of the two segments remains in possession of the silicious capsule, whilst the other finds its way out through one of the apertures, lives for some hours in a free condition as an Actinophrys, and ultimately produces the capsule and stem characteristic of its type. In the second mode numerous small rounded sarcode-masses, each possessing a nucleus, are produced within the capsule, in what manner cannot be clearly made out; and every one of these is enveloped in a firm envelope, set round with short spines, probably silicious. These cysts remain for months within the common capsule; and when the time arrives for their further development the sarcode-corpuscles slip out of their cysts, and escape through the orifices of the capsule as flagellated monads of oval form (fig. 518, B), each having a nucleus, *n*, near the base of the flagella, and two contractile vesicles near its opposite end. After swarming for some hours in this condition, they change to the free *Actinophrys* form, and finally acquire the silicious capsule and stem of the Clathrulina.



FIG. 519.—Diagrammatic representation of *Amœba proteus*: E C, ectosarc; E N, endosarc; C V, contractile vesicle; N, nucleus; P, pseudopodia; V I L, villous tuft.

Lobosa.—No example of the rhizopod type is more common in streams and ponds, vegetable infusions, &c. than the *Amœba* (fig. 519); a creature which cannot be described by its form, for this is as changeable as that of the fabled Proteus, but may yet be definitely characterised by peculiarities that separate it from the two groups already described. The distinction between 'ectosarc' and 'endosarc' is here clearly marked, so that the body approaches much more closely in its characters to an ordinary 'cell' composed of cell-wall and cell-contents. It is through the 'endosarc' alone, E N, that those coloured and granular particles are diffused, on which the hue and opacity of the body depend; its central portion seems to have an almost watery consistence, the granular particles being seen to move quite freely upon one another with every change in the shape of the body; but its superficial portion is more viscid, and graduates insensibly into the firmer substance of the 'ectosarc.' The ectosarc, E C, which is perfectly pellucid, forms an almost membranous investment to the endosarc; still it is not possessed of such tenacity as to oppose a solution of its continuity at any point, for

the introduction of alimentary particles, or for the extrusion of effete matter ;[1] and thus there is no evidence, in *Amœba* and its immediate allies, of the existence of any more definite orifice, either oral or anal, than exists in other rhizopods. The more advanced differentiation of the ectosarc from the endosarc of *Amœba* is made evident by the effects of reagents. If an *Amœba radiosa* be treated with a dilute alkaline solution, the granular and molecular endosarc shrinks together and retreats towards the centre, leaving the radiating extensions of the ectosarc in the condition of cæcal tubes, of which the walls are not soluble at the ordinary temperature either in acetic or mineral acids, or in dilute alkaline solutions, thus agreeing with the envelope noticed by Cohn as possessed by *Paramecium* and other ciliated *Infusoria*, and with the containing membrane of ordinary animal cells. A 'nucleus,' N, is always distinctly visible in *Amœba*, adherent to the inner portion of the ectosarc, and projecting from this into the cavity occupied by the endosarc ; when most perfectly seen it presents the aspect of a clear flattened vesicle surrounding a solid and usually spherical nucleolus ; it is readily soluble in alkalies, and first expands and then dissolves when treated with acetic or sulphuric acid of moderate strength ; but when treated with dilute acid it is rendered darker and more distinct, in consequence of the precipitation of a finely granular substance in the clear vesicular space that surrounds the nucleolus. A 'contractile vesicle,' C V, seems also to be uniformly present, though it does not usually make itself so conspicuous by its external prominence as it does in *Actinophrys* ; and the neighbouring part of the body is often prolonged into a set of villous processes, V I L, the presence of which has been thought by some to mark a specific distinction, but which seems too variable and transitory to be so regarded.

The pseudopodia, which are not appendages, but lobate extensions of the body itself, are few in number, short, broad, and rounded : and their outlines present a sharpness which indicates that the substance of which their exterior is composed possesses considerable tenacity. No movement of granules can be seen to take place along the surface of the pseudopodia ; and when two of these organs come into contact, they scarcely show any disposition even to mutual cohesion, still less to fusion of their substance. Sometimes the protrusion seems to be formed by the ectosarc alone, but more commonly endosarc also extends into it, and an active current of granules may be seen to pass from what was previously the centre of the body into the protruded portion, when the latter is undergoing rapid elongation ; whilst a like current may set towards the centre of the body from some other protrusion which is being withdrawn into it. It is in this manner that an *Amœba* moves from place to place, a protrusion like the finger of a glove being first formed, into

[1] This remarkable character has been stated by Professor Huxley in the following admirable sentence: 'Physically the ectosarc might be compared to the wall of a soap-bubble, which, though fluid, has a certain viscosity, which not only enables its particles to hold together and form a continuous sheet, but permits a rod to be passed into or through the, bubble without bursting it, the walls closing together, and recovering their continuity as soon as the rod is drawn away.'

which the substance of the body itself is gradually transferred, and another protrusion being put forth, either in the same or in some different direction, so soon as this transference has been accomplished, or even before it is complete. The kind of progression thus executed by an *Amœba* is described by most observers as a 'rolling' movement, this being certainly the aspect which it commonly seems to present; but it is maintained by MM. Claparède and Lachmann that the appearance of rolling is an optical illusion, since the nucleus and contractile vesicle always maintain the same position relatively to the rest of the body, and that 'creeping' would be a truer description of the mode of progression. It is in the course of this movement from place to place that the *Amœba* encounters particles which are fitted to afford it nourishment; and it appears to receive such particles into its interior through any part of the ectosarc, whether of the body itself or of any of its lobose expansions, insoluble particles which resist the digestive process being got rid of in the like primitive fashion.

If may often be seen that portions of the sarcode-body of an *Amœba*, detached from the rest, can maintain an independent existence; and it is probable that such separation of fragments is an ordinary mode of increase in this group. When a pseudopodial lobe has been put forth to a considerable length, and has become enlarged and fixed at its extremity, the subsequent contraction of the connecting portion, instead of either drawing the body towards the fixed point, or retracting the lobe into the body, causes the connecting band to thin away until it separates; and the detached portion speedily shoots out pseudopodial processes of its own, and comports itself in all respects as an independent *Amœba*. Multiplication also takes place by regular binary subdivision. Various observers have seen phenomena which they have supposed to be evidence of the formation of 'swarm-spores'[1] or of the development of cysts, but it must be borne in mind that a large number of protozoa pass during the course of their life through amœbiform stages, some of which may have been taken as true species of *Amœba*. No sexual act has been certainly recognised as part of the life-history of *Amœba*, the union of two or more individuals, which may be occasionally witnessed, having more the character of the 'zygosis' of Actinophrys.

A sarcodic organism discovered by Greef, and named by him *Pelomyxa palustris* (fig. 520), which spreads over the bottom of stagnant ponds in the condition of slimy masses of indefinite form, exhibits a further advance upon the Amœban type. The substance of its body, which may be of the size of two millimetres, exhibits a very clear differentiation between the homogeneous hyaline ectosarc (B, *a*, *d*), and the contained endosarc, which contains such a multitude of spherical vacuoles, *b*, as to have a 'vesicular' or frothy aspect. When it feeds upon the decomposing vegetable matter at the bottom of the pool it inhabits, its body acquires a blackish hue, but in other situations it may be colourless. Besides the vacuoles there are seen in the endosarc a great number of nucleus-like bodies,

[1] Prof. A. M. Edwards (U.S.A.) in *Monthly Microsc. Journ.* vol. viii. 1872, p. 29.

e, *e*, and also many hyaline globular brilliant bodies, *f*, *f*, which are regarded by Greef as germs or swarm-spores developed from nucleoli set free within the general cavity of the body by the bursting of the nuclei. This creature during the active period of its life moves like an amœba, either by general undulations of its surface, or by special pseudopodial extensions, *d*. After a time, however, its movements cease, and it looks as if dead; but by the giving way of its ectosarc, a multitude of minute amœbiform bodies break forth, each having its nucleus and contractile vesicle. These at first live as



FIG. 520.—*Pelomyxa palustris*: A, as it appears when in amœboid motion; B, portion more highly magnified, showing *a*, *a*, the hyaline ectosarc; *b*, one of the vacuoles of the endosarc; *c*, rod-like bodies (probably *Bacteria*) scattered through the endosarc; *d*, protruded extension of ectosarc with endosarc passing into it; *e*, *e*, nuclei; *f*, *f*, globular hyaline bodies.

Amœbæ, but afterwards pass into a resting state, assuming a spherical or oval shape, and then put forth flagella, by which they swim actively for a time; later on, they probably settle down to develop themselves into the parental form.

The Amœban like the Actinophryan type shows itself in the testaceous as well as in the naked form, the commonest example of this being known under the names *Arcella* and *Difflugia*. The body of the former is enclosed in a 'test' composed of a horny membrane, apparently resembling in constitution the *chitin* which gives solidity to the integuments of insects; it is usually discoidal

(fig. 521, C, D) with one face flat and the other arched, the aperture being in the centre of the flat side ; and its surface is often marked with a minute and regular pattern. The test of *Difflugia*, on the other hand, is more or less pitcher-shaped (A, B), and is chiefly made up of minute particles of gravel, shell, &c. cemented together. In each of these genera the sarcode-body resembles that of *Amœba* in every essential particular, the contrast being very marked between its large, distinct, lobose extensions, and the ramifying and inosculating pseudopodia of *Gromia* (fig. 513). In each case a detached portion of the sarcodic body will put forth pseudopodia of its own type ; and the separation of a bud or gemmule put forth from the mouth of the test seems to be an ordinary mode of propagation among the amœbans thus enclosed. In *Arcella* it has been observed that the pseudopodia of two or more individuals unite by bridges of protoplasm, and afterwards separate ; and it seems to be almost certain that this is a true 'conjugation,' and not a mere 'zygosis.' A remarkable method of reproduction has been observed by Gruber in *Euglypha alveolata* ; in an active form highly refractive



Fig. 521.—Testaceous forms of *Amœban* rhizopods: A, *Difflugia proteiformis*; B, *Difflugia oblonga*; C, *Arcella acuminata*; D, *Arcella dentata*.

bodies, which, seen from the surface, look like discs, are to be found beside the nucleus. Reproduction commences with the protrusion of protoplasm from the orifice of the test, and, later on, the just-mentioned bodies pass out also, and form a covering for the extruded protoplasm ; in about an hour the process is complete, but the new or daughter-cell is still without a nucleus. This is derived from that of the mother, which increases in size, elongates greatly, and then becomes constricted ; the anterior portion passes into the daughter-cell. Here we have the remarkable phenomena of the formation of the test by the parent-cell and the rare case of division of the protoplasmic body preceding that of its nucleus.

Many testaceous *amœbans* have been recently discovered, which form tests of remarkable regularity and sometimes of singular beauty ; and it is difficult to determine, in many cases, whether the minute plates of which they are composed have been formed by exudation from their own bodies or have been picked up from the surface over which the animals crawl. There can be no doubt of this kind, however, in regard to the *Quadrula symmetrica* represented in fig. 522 ; the sarcode-body is here encased in a pear-shaped test, of glassy transparence, made up of a great number of square

plates which touch each other by their edges. The sarcode-body does not usually fill the test, the intervening space being occupied by a clear liquid, and traversed by bands of protoplasm. In the posterior part of the body is seen a large clear spherical nucleus, with a distinct dark nucleolus; and in front of this are contractile vesicles, usually two in number.[1]

Coccoliths and Coccospheres.—This would seem the most appropriate place for the description of certain peculiar little bodies found very extensively diffused over the deep-sea bottom, especially abounding in the Globigerina-mud, which may be considered as chalk in process of formation. It was in the specimens of this mud brought up by the 'Cyclops' soundings in 1857 that Professor Huxley first found the *Coccoliths* (fig. 523, 1, 2) which Dr. Wallich in 1860 found aggregated in the spherical masses which he designated as 'coccospheres' (3). Regarding the gelatinous matrix in which they were imbedded as a new type of the *Monerozoa* described by Haeckel, having the condition of an indefinitely extended *plasmodium*, Professor Huxley proposed to designate it by the name *Bathybius*, indicative of its habitat in the depths of the sea; and this idea was accepted by Haeckel, whose representation of a living specimen of *Bathybius*, with imbedded coccoliths, is given in fig. 523, 3. The observations made in the 'Challenger' Expedition, however, have not confirmed this view; the supposed *Bathybius* being a gelatinous precipitate, consisting of sulphate of lime, slowly deposited in water to which strong spirit has been added. Whatever be their nature, coccoliths and coccospheres are bodies of great interest; since their occurrence in chalk and in very early limestones is an additional link in the evidence of the similarity of the conditions under which they were formed to those at present prevailing on the sea-bed of the Atlantic and other oceans. Two distinct types are recognisable among the coccoliths, which Professor Huxley has designated respectively *discoliths* and *cyatholiths*. The former are round or oval discs, having



FIG. 522.—*Quadrula symmetrica*, with extended pseudopodia.

[1] See especially the recent admirable work of Professor Leidy on the fresh-water rhizopods of the United States, 1880. It is to be regretted that its able author's time and opportunities did not permit him to follow out the life-histories of the many interesting forms which he has described and figured.

a thick strongly refracting rim and a thinner internal portion, the greater part of which is occupied by a slightly opaque, cloud-like patch lying round a central corpuscle (fig. 523, *5*). In general, the 'discoliths' are slightly convex on one side, slightly concave on the other, and the rim is raised into a prominent ridge on the more convex side; so that when viewed edgewise they present the appearances shown in figs. *8*, *9*. Their length is ordinarily between $\frac{1}{4000}$th and $\frac{1}{5000}$th of an inch; but it ranges from $\frac{1}{2700}$th to $\frac{1}{11000}$th. The largest are commonly free, but the smallest are generally found imbedded among heaps of granular particles, of which some are probably discoliths in an early stage of development. The 'cyatholiths,' also, which have the general appearance of a cup and saucer, have, when full grown, an oval contour, though they are often circular when immature. They are convex on one face and flat or concave on the



FIG. 523.—*Coccoliths* and *Coccospheres*: *1*, *2*, *7*, cyatholiths seen obliquely; *3*, coccosphere with imbedded cyatholiths; *4*, coccoliths imbedded in supposed protoplasmic expansion; *5*, discolith seen in front view; *6*, cyatholith seen in front view, showing (1) central corpuscle, (2) granular zone, (3) transparent outer zone; *8*, *9*, discoliths seen edgewise.

other; and when left to themselves they lie on one or other of these two faces. In either of these aspects they seem to be composed of two concentric zones (fig. *6*, *2*, *3*) surrounding an oval thick-walled central corpuscle (*1*), in the centre of which is a clear space sometimes divided into two. The zone (*2*) immediately surrounding the central corpuscle is usually more or less distinctly granular, and sometimes has an almost bead-like margin. The narrower outer zone (*3*) is generally clear, transparent, and structureless, but sometimes shows radiating striæ. When viewed sidewise or obliquely, however, the 'cyatholiths' are found to have a form somewhat resembling that of a shirt-stud (figs. *1*, *2*, *7*). Each consists of a lower plate, shaped like a deep saucer or watch-glass; of a smaller upper plate, which is sometimes flat, sometimes more or less concavo-convex; of the oval, thick-walled, flattened corpuscle, which connects these two plates together at their centres; and of

an intermediate granular substance which more or less completely fills up the interval between the two plates. The length of these cyatholiths ranges from about $\frac{1}{1800}$th to $\frac{1}{8000}$th of an inch, those of $\frac{1}{8000}$th of an inch and under being always circular. It appears from the action of dilute acids upon the coccoliths that they must mainly consist of calcareous matter, as they readily dissolve, leaving scarcely a trace behind. When the cyatholiths are treated with very weak acetic acid, the central corpuscle rapidly loses its strongly refracting character; and there remains an extremely delicate, finely granular membranous framework. When treated with iodine they are stained, but not very strongly, the intermediate substance being the most affected. Both discoliths and cyatholiths are completely destroyed by strong hot solutions of caustic potass or soda. The coccospheres (fig. *3*) are made up by the aggregation of bodies resembling 'cyatholiths' of the largest size in all but the absence of the granular zone; they sometimes attain a diameter of $\frac{1}{700}$th of an inch. What is their relation to the coccoliths, and under what conditions these bodies are formed, are questions whereon no positive judgment can be at present given.

Sporozoa.

The term Sporozoa has been applied by Leuckart to a group of protozoic animals of which the well-known Gregarinida are certainly members, and to which the Myxosporidia and Sarcosporidia[1] may also belong. They are especially characterised by the peculiarities of their mode of reproduction, in which a period of encystation (which may or may not be preceded by conjugation) is succeeded by the breaking up of the contained protoplasm into a large number of small 'spores.'

The Gregarinida lead a parasitic life, and may often be met with in the intestinal canal or other cavities of earthworms, insects, &c. and sometimes in that of higher animals. An individual *Gregarina* essentially consists of a large single cell, usually more or less ovate in form, and sometimes attaining the extraordinary length of *two-thirds of an inch*.[2] A sort of beak or proboscis frequently projects from one extremity; and in some instances this is furnished with a circular row of hooklets, closely resembling that which is seen on the head of Tænia. There is here a much more complete differentiation between the cell-membrane and its contents than exists either in *Actinophrys* or in *Amœba*; and in this respect we must look upon *Gregarina* as representing a decided advance in organisation. Being nourished upon the juices already prepared for it by the digestive operations of the animal which it infests, it has no need of any such apparatus for the introduction of solid particles into the interior of its body, as is provided in the 'pseudopodia' of the rhizopods and in the oral cilia of the Infusoria. Within the cavity of the cell,

[1] Consult the memoir by Dr. R. Blanchard in *Bull. Soc. Zool. France*, x. p. 244.

[2] See Prof. Ed. Van Beneden on *Gregarina gigantea* (found in the intestinal canal of the lobster) in *Quart. Journ. Microsc. Sci.* n.s. vol. x. 1870, p. 51, and vol. xi. p. 242.

whose contents are usually milk-white and minutely granular, there is generally seen a pellucid nucleus; and when, as often happens, the cell undergoes duplicative subdivision, the process commences in a constriction and cleavage of this nucleus. The membrane and its contents, except the nucleus, are soluble in acetic acid. The movements of the body are of very various kinds; there is a forward movement which may be due, as suggested by Lankester, to the undulations of the body. The cell itself may undergo contraction, and consequent change in form, which may or may not be accompanied by locomotion; circular constrictions may extend along the body; or the cell may bend on itself and again straighten out. By Van Beneden the contractility of the cell is localised in a layer of the



FIG. 524.—Cyst of *Monocystis agilis*, the Gregarinid of the earthworm (750 diams.), showing ripe chlamydospores and complete absence of any residual protoplasm in the cyst. (After Professor Ray Lankester.)

ectoplasm, which he has found to consist of a layer of contractile fibrils. When the process of encystation commences we find that, whatever the original form of the body may be, it becomes globular, ceases to move, and becomes invested by a structureless 'cyst,' within which the substance of the body undergoes a singular change. The nucleus disappears, and the sarcodic mass breaks up into a series of globular particles, which gradually resolve themselves (as shown at *b*, *c*, *d*, *e*, fig. 525) into forms very like those of *Naviculæ*, and a cyst more advanced, and greatly magnified, is shown in fig. 524. These 'pseudo-navicellæ' or 'spores,' as it is better to call them, are set free in time by the bursting of the capsule that incloses them; and

they develop themselves into a new generation of Gregarinæ, passing through an amœba-like stage. A sort of 'conjugation' been seen to take place between two individuals, whose bo coming into contact with each other by corresponding points, become more globular in shape, and are then encysted by the fo



FIG. 525.—*Gregarina Sænuridis*, from testis of *Tubifex rivulorum* two adults uniting: *a*, succeeding stage; *b*, encystation stage: in *c* and *d* the contents are seen breaking up; in *e* the characteristic pseudo-navicellar form has been acquired by the spores. (After Kölliker.)



FIG. 526.—*Coccidium oviforme* (Leuckart) from the liver of the rabbit: *a*, cyst just formed; *b*, condensed contents, the outer envelope has disappeared; *c*, contents divided into four sporoblasts; *d*, the sporoblasts have become rounded and clearer internally; *e* and *f*, formation of the falciform germ; *g* and *h*, spores more highly magnified—*g* from the side, *h* from in front.

tion of a capsule around them both; the partition-walls between their cavities disappear; and the substance of the two bodies becomes completely fused together. But as the products of this 'zygosis' is the same as that of the ordinary encysting process, there seeems no sufficient reason for regarding it, like the 'conjugation' of protophytes, as a true generative act.

The *Coccodia* (fig. 526) are Sporozoa which look like minute ova, and which are found resting *within* the cells of their hosts; the young, developed from spores, are falciform in shape, and, moving about actively, are able to penetrate fresh cells. They have been found in the epithelium of the intestine of various forms, and in the liver of vertebrates. Some parasites found in the blood, such as *Drepanidium ranarum*, Lankester, may be migrating young.

Of the imperfectly known *Myxosporidia* it may be said that their spores are the bodies which are known as 'psorosperms'; while the bodies observed by Rainey and others, and wrongly regarded as the cause of the cattle plague, are sarcocystids which live in the muscular fibre of mammals.

Professor Haeckel's memoirs on *Monera* and the *Gastræa Theory* will be found in successive numbers of the *Jenaische Zeitschrift* beginning with 1868, and in a collected form in the two parts of his *Biologische Studien*. The first of his memoirs on *Monera* is translated in *Quart. Journ. Microsc. Sci.* n.s. vol. ix. 1869; and the first of his papers on the *Gastræa Theory* in vol. xiv. 1874, of the same journal. See also the valuable series of papers on the *Freshwater Rhizopods*, by Mr. Wm. Archer, in the current series of the *Quart. Journ. Microsc. Sci.*; the important memoirs of Hertwig and Lesser in the *Archiv für mikr. Anat.* (especially the suppl. Heft to Bd. X. 1874), and the Presidential Addresses of Professor Allman to the Linnean Society for 1876 and 1877 (in Nos. 69 and 71 of its Journal) on 'Recent Researches on some of the more simple Sarcode-Organisms,' of which the Author has freely availed himself; as also the chapters dealing with the Rhizopoda and Sporozoa in Professor Bütschli's edition of Bronn's *Klassen und Ordnungen des Thierreichs*, 1880, and Professor Ray Lankester's article, 'Protozoa,' in the ninth edition of the *Encyclopædia Britannica*, 1885.

CHAPTER XIII

ANIMALCULES—INFUSORIA AND ROTIFERA

NOTHING can be more vague or scientifically inappropriate than the title Animalcules; since it only expresses the small dimensions of the beings to which it is applied, and does not indicate any of their characteristic peculiarities. In the infancy of microscopic knowledge, it was natural to associate together all those creatures which could only be discerned at all under a high magnifying power, and whose internal structure could not be clearly made out with the instruments then in use; and thus the most heterogeneous assemblage of plants, zoöphytes, minute crustaceans, larvæ of worms, molluscs, &c. came to be aggregated with the true animalcules under this head. The class was being gradually limited by the removal of all such forms as could be referred to others; but still very little was known of the real nature of those that remained in it until the study was taken up by Professor Ehrenberg, with the advantage of instruments which had derived new and vastly improved capabilities from the application of the principle of achromatism. One of the first and most important results of his study, and that which has most firmly maintained its ground, notwithstanding the overthrow of Professor Ehrenberg's doctrines on other points, was the separation of the entire assemblage into two distinct groups, having scarcely any feature in common except their minute size, one being of very *low*, and the other of comparatively *high* organisation. On the lower group he conferred the designation of *Polygastrica* (many-stomached), in consequence of having been led to form an idea of their organisation which the united voice of the most trustworthy observers now pronounces to be erroneous; and as the retention of this term must tend to perpetuate the error, it is well to fall back on the name *Infusoria*, or infusory animalcules, which simply expresses their almost universal prevalence in infusions of organic matter. To the higher group Professor Ehrenberg's name *Rotifera* or *Rotatoria* is, on the whole, very appropriate, as significant of that peculiar arrangement of their cilia upon the anterior parts of their bodies, which, in some of their most common forms, gives the appearance (when the cilia are in action) of wheels in revolution; the group, however, includes many members in which the ciliated lobes are so formed as not to bear the least resemblance to wheels. In their general organisation these 'wheel-animalcules' stand at a much higher level than the unicellular Infusoria, but it

is difficult to decide what is their relationship to other groups of 'Vermes.' Notwithstanding the wide zoölogical separation between these two kinds of animalcules, it seems most suitable to the plan of the present work to treat of them in connection with one another; since the microscopist continually finds them associated together, and studies them under similar conditions.

Section I.—Infusoria.

This term, as now limited by the separation of the *Rhizopoda* on the one hand, and of the *Rotifera* on the other, is applied to a far smaller range of forms than was included by Professor Ehrenberg under the name of 'polygastric' animalcules. For a large section of these, including the *Desmidiaceæ*, *Diatomaceæ*, *Volvocineæ*, and many other protophytes, have been transferred by general (though not universal) consent to the vegetable kingdom. And it is not impossible that many of the reputed *Infusoria* may be but larval forms of higher organisms, instead of being themselves complete animals. Still an extensive group remains, of which no other account can at present be given than that the beings of which it is composed go through the whole of their lives, so far as we are acquainted with them, in a grade of existence which is essentially protozoic, each individual apparently consisting of but *a single cell*, though its parts are often so highly differentiated as to represent (only, however, by way of *analogy*) the 'organs' of the higher animals after which they are usually named.

Among the *ciliate* Infusoria, which form not only by far the largest, but also the most characteristic division of the group, there is probably none save such as are degraded by parasitic habits which has not a *mouth*, or permanent orifice for the introduction of food, which is driven towards it by ciliary currents; while a distinct *anal* orifice, for the ejection of the indigestible residue, is not infrequently present. The mouth is often furnished with a *dental* armature, and leads to an *œsophageal canal*, down which the food passes into the digestive cavity. This cavity is still occupied, however, as in rhizopods, by the *endosarc* of the cell; but instead of lying in mere vacuoles formed in the midst of this, the food-particles are usually aggregated, during their passage down the œsophagus, into minute pellets, each of which receives a special investment of firm protoplasm, constituting it a *digestive vesicle* (fig. 531); and these go through a sort of circulation within the cell-cavity.

The 'contractile vesicles,' again, attain a much higher development in this group, and are sometimes in connection with a network of canals channelled out in the 'ectosarc'; while their rhythmical action resembles that of the *circulatory* and *respiratory* apparatus of higher animals. There is ample evidence, also, of the presence of a specially contractile modification of the protoplasmic substance, having the action (though not the structure) of *muscular* fibre; and the manner in which the movements of the active free-swimming Infusoria are directed, so as to avoid obstacles and find out passages,

seems to indicate that another portion of their protoplasmic substance must have to a certain degree the special endowments which characterise the *nervous* systems of higher animals. Altogether, it may be said that in the ciliate Infusoria *the life of the single cell finds its highest expression.*[1]

Before proceeding to the description of the *ciliate* Infusoria, however, it will be of advantage to notice two smaller groups—the *flagellate* and the *suctorial*—which, on account of the peculiarities of their structure and actions, are now ranked as distinct, and of whose 'unicellular' character there can be no reasonable doubt, since they are, for the most part, 'closed' cells, scarcely distinguishable morphologically from those of protophytes.

Flagellata.—Our knowledge of this tribe has been greatly augmented in recent years, not only by the discovery of a great variety of new forms, but still more by the careful study of the life-history of several among them. The *monads*, properly so called,[2] which are amongst the smallest living things at present known, are its simplest representatives; but it also includes organisms of much greater complexity; and some of its composite forms seem to have a very remarkable relation to sponges. The *Monas lens*, long familiar to microscopists as occurring in stagnant waters and infusions of decomposing organic matter, is a spheroidal particle of protoplasm, from $\frac{1}{2000}$th to $\frac{1}{3200}$th of an inch in diameter, enclosed in a delicate hyaline investment or 'ectosarc,' and moving freely through the water by the lashing action of its slender *flagellum*, whose length is from three to five times the diameter of the body. Within the body may be seen a variable number of vacuoles; and these are occasionally occupied by particles distinguishable by their colour, which have been introduced as food. These seem to enter the body, not by any definite mouth (or permanent opening in the ectosarc), but through an aperture that forms itself in some part of the oral region near the base of the flagellum. In some true *Monadinæ* neither nucleus nor contractile vesicle is distinguishable, but in the majority a nucleus can be clearly seen. The life-history of several simple *Monadinæ* presenting themselves in infusions of decaying animal matter (a cod's head being found the most productive material) has been studied with admirable perseverance

[1] The doctrine of the unicellular nature of the *Infusoria* has been a subject of keen controversy among zoölogists from the time when it was first definitely put forward by Von Siebold (*Lehrbuch der vergleich. Anat.* Berlin, 1845) in opposition to the then paramount doctrine of Ehrenberg as to the complexity of their organisation, which had as yet been called in question only by Dujardin (*Hist. Nat. des Infusoires*, Paris, 1841). Of late, however, there has been a decided convergence of opinion in the direction above indicated; which has been brought about in great degree by the contrast between the *protozoic* simplicity of the reproductive and developmental processes in Infusoria, as, for example, shown by Dallinger and Drysdale, and by the former alone in the life-histories of the Saprophytes, and the complexity of the like processes as seen in even the lowest of the *Metazoa*, which has been specially and forcibly insisted on by Haeckel ('Zur Morphologie der Infusorien,' *Jenaische Zeitschr.* Bd. vii. 1873). An excellent summary of the whole discussion was given by Professor Allman in his Presidential Address to the Linnean Society in 1875.

[2] The family *Monadina* of Ehrenberg and Dujardin consists of an aggregate of forms now known to be of very dissimilar nature, many of them belonging to the vegetable kingdom.

and thoroughness by Messrs. Dallinger and Drysdale, of whose important observations a general summary will now be given.[1]

The present Editor, while adopting the lead of Dr. Carpenter, greatly doubts the suitability or correctness of the *saprophytic* monad forms appearing at this place in the organic series. They possess features that ally them, as has been already suggested, much more nearly to the vegetable series, and indicate affinities with certain Nostocaceæ and the Bacteria; while a leaning to the Mycetozoa and the chlorophyllaceous Algæ, and even some forms of Fungi, is quite apparent to the careful student.

There are some reasons for looking at the saprophytic monad forms as a possibly degraded but still specialised group. In common with saprophytic Bacteria, they are specifically related to the setting up and carrying on of decomposition in dead organic tissues. In organic infusions and films of gelatine, or tubes of agar-agar, the bacterial forms are, as a rule, enough to set up and carry on the destructive ferment. But where great masses of tissue are decomposing, the presence of the larger monad forms is certain and inevitable; and by them, accompanied by the Bacteria, the processes of fermentative rotting are carried to the end.

It is their morphology which points to the Flagellata, and we should incline to consider them a degenerate, and by degeneration specialised form of the Flagellata if they—about eight or nine distinct forms in this latitude—belong properly to the Flagellata at all.

The simplest of these organisms is represented in fig. 1, Plate XIII, A. It has been named by Saville Kent *Monas Dallingeri*, and has by comparison a simple life-history. As it is with the entire group, all is subservient to rapidity of multiplication; and there are two methods in which this is effected. The first and commonest is by fission; fig. 1, A, represents the normal form of the organism. It has a long diameter of about the $\frac{1}{6000}$th of an inch, and has great ease and grace, and relative power of movement. In a certain stage of its history as it swims freely there suddenly appears a constriction across its body, as in fig. 2. This is at once accompanied by an apparent effort of the opposite flagella to pull against each other; the consequence is a very rapid stretching of a neck of sarcode between two halves of the body, as at fig. 3. This becomes longer, as at 4, and attains the length of two flagella as at 5, when the two dividing halves approach and mutually dart from each other, snapping the connecting fibre of sarcode in the middle, so that two perfect forms are set free, as in 6 and 7.

This, in the course of from two to three minutes, is once more begun and carried on in each half successively, so that there is an increase of the form by this means in rapid geometric ratio.

But this is an exhaustive process vitally, for after a period varying from eight to ten days there always appears in the unaltered and unchanged field of observation normal forms, with a remarkable

[1] See their successive papers in the *Monthly Microsc. Journ.* vol. x. 1873, pp. 53, 245; vol. xi. 1874, pp. 7, 69, 97; vol. xii. 1874, p. 261; and vol. xiii. 1875, p. 185; and *Proceed. Roy. Soc.* vol. xxvii. 1878, p. 332. But especially for the latest results with recent objectives, *Journ. Roy. Micro. Soc.* vol. v. 1885, p. 177; vol. vi. p. 193; vol. vii. p. 185; vol. viii. p. 177.

diffluent or amœba-like envelope, as seen in figs. 8 and 9, A. These sometimes swim and sometimes creep, amœba-like, by pseudopodia; but directly the diffluent sarcode of one touches that of another they at once melt together, as in fig. 10, A. This leads to the rapid approach of the oval bodies of the two organisms, as in fig. 11, B, resulting in their fusion, as in figs. 12, 13, 14, and a still condition of the sac (fig. 14) for a period of not less than six hours; when it bursts, as seen in fig. 15, pouring out an immense host of exquisitely minute *spores*, as shown in fig. 15. These are opaque or semi-opaque, but by observation upon them at a temperature of 65° to 70° Fahr., they in the course of thirty minutes become transparent, elongate, as in figs. 16 and 17, and, continuing to grow, assume the conditions and sizes represented in figs. 18 and 19; and we were able to trace them through all their changes of growth from the spore into the adult condition, as at fig. 20, until they entered upon and passed through the self-division into two described and figured in A.

The next form, though even more simple in appearance, has a much more complex morphological history. It is seen in its normal form in fig. 1, C. It has but one flagellum, and, as we believe, on that account has a much more restricted power of movement. It is from the $\frac{1}{5000}$th to the $\frac{1}{7000}$th of an inch in long diameter. In its motion at one stage of its life its oval body becomes uncertain in form, as seen in 2, 3, 4, C; but when this has continued for not more than a minute, the flagellum falls in upon the body, as in 4, and the organism becomes perfectly still. In this condition, after a space ranging from ten to twenty minutes, two white bars at right angles suddenly appear, as in fig. 5; this is almost immediately followed by another and a similar one at right angles to the first, as in fig. 6. Then the circumference of the flattened sphere twists, leaving the centre unaffected, so that the body assumes a turbined appearance, as seen in fig. 7. After this the interior substance breaks up, and becomes a knot of slightly moving but compact forms, as in fig. 8; which remains in this state for from fifteen to twenty minutes, and then becomes dissociated, as in fig. 9; so that we have here a complex form of multiple partition, giving rise to enormous numbers, because, although much smaller than the form in which they arose, they consume and assimilate food all over, and are simply swimming in their pabulum, and so rapidly reach the normal size, when they each enter upon and pass through a similar process.

But here also at certain periods there appeared forms that inaugurate distinctly genetic processes. A form like fig. 10, C, appears, larger than the normal form, and always mottled in the part nearest the flagellum. These forms rapidly attached themselves to the normal forms, as seen in fig. 11, which resulted in a blending of the two as they swam together, until 'either was melted into other'; and a still sac, shown in fig. 12, resulted.

This remained from thirty to thirty-six hours absolutely inert: but at the expiration of that time it burst, as seen in fig. 13, D, and poured out an enormously diffusive fluid, which as it flowed into the surrounding water appeared like a denser fluid, diffusing itself through one of less density; but no spores were at this stage at all apparent. It

Plate XIII.



Dallinger del ad nat

F Huth, Lith^r Edin^r

LIFE HISTORIES OF SAPROPHYTES.

was only after much effort that we at last, by keeping the finest of our senses near the mouth of the empty sac, were able to discover, where before nothing was visible, the appearance of minute specks, which became larger and larger, growing as seen in 14, 15, 16, 17, until the adult size was reached, as at 18, and by the act of multipartition on the part of one of these, watched from its first disclosure by the microscope, we were able to re-enter the cycle of its life-history.

The third form, which we may here consider fully, so as to present a good group of histories typical in their presentation of the morphology of the whole of the monad-saprophytes as we at present know them, is given in E and F, Plate XIII.

The monad has been named by S. Kent *Dallingeria Drysdali*. The form more recently and completely studied by Mr. Dallinger—with all the advantages derived from trained experience, and under objectives of the highest quality and greatest magnifying power—is seen in its normal shape in fig. 1, is a long oval, slightly constricted in the middle, and having a kind of pointed neck (*a*), from which proceeds a flagellum about half as long again as the body. From the shoulder-like projections behind this (*b*, *c*,) arise two other long and fine flagella, which are directed backwards. The sarcode-body is clear, and apparently structureless, with minute vacuoles distributed through it; and in its hinder part a nucleus (*d*) is distinguishable. The extreme length of the body is seldom more than the $\frac{1}{4000}$th of an inch, and is often the $\frac{1}{5000}$th. This monad swims with great rapidity, its movements, which are graceful and varied, being produced by the action of the flagella, which can not only impel it in any direction, but can suddenly reverse its course or check it altogether. But besides this free-swimming movement, a very curious 'springing' action is performed by this monad when the decomposing organic matter of the infusion is breaking up, the process of disintegration being apparently assisted by it. The two posterior flagella anchor themselves and coil into a spiral, and the body then darts forwards and upwards, until the anchored flagella straighten out again, when the body falls forward to its horizontal position, to be again drawn back by the spiral coiling of the anchored flagella. This monad multiplies by longitudinal fission, the first stage of which is the splitting of the anterior flagellum into two (fig. 2, *a*, *b*), and a movement of the nucleus (*c*) towards the centre. In the course of *from thirty to sixty seconds* the fission extends down the neck (fig. 3 *a*); a line of division is also seen at the posterior end (*c*), and the nucleus (*b*) shows an incipient cleavage. In a few seconds the cleavage-line runs through the whole length of the body, the separation being widest posteriorly (fig. 4, *a*); and in from one to four minutes the cleavage becomes almost complete (fig. 5), the posterior part of the body, with the two halves (*a* and *b*) of the original nucleus, being now quite disconnected, though the anterior parts are still held together by a transverse band of sarcode, as seen in fig. 6, which continues to rapidly elongate, as in fig. 7, and becomes the length of two side flagella, as in fig. 8. The forms then approach and rapidly recede from each other, snapping the cord, as in figs. 9 and 10. In this way *two* forms exist instead of one; and each of these almost

immediately enters upon and passes through the same process of fission, which from first to last is completed in from four to seven minutes; and being repeated at intervals of a few minutes, this mode of multiplication produces a rapid increase in the number of the monads.

Such fission does not, however, continue indefinitely, for after a successive series of fissions, followed in one of the divided bodies for eight or nine hours, certain individuals do not again enter upon the process of fission, but undergo a peculiar change, which shows itself first in the absorption of the two lateral flagella and the great development of the nucleus, and afterwards in the formation of a transverse granular band across the middle of the body (fig. 11, E). One of these altered forms, swimming into a group in the 'springing' state, within a few seconds firmly attaches itself to one of them, which at once unanchors itself, and the two swim freely and vigorously about, shown in fig. 12, generally for from thirty-five to forty-five minutes. Gradually, however, a 'fusion' of the two bodies and of their respective nuclei takes place, the two trailing flagella of the 'springing' form being drawn in (fig. 13, F); and in a short time longer the two anterior flagella also disappear, and all trace of the separate bodies is lost, the nuclei vanish, and the resultant is an irregular amœboid mass (fig. 14), which gradually acquires the smooth, distended, and 'still' condition represented in fig. 14, *a*. This is a cyst filled with reproductive particles of such extraordinary minuteness that, when emitted from the ends of the cyst (fig. 15, *a*) after the lapse of four or five hours, they can only be distinguished under an amplification of 5000 diameters, with perfect central illumination, i.e. the full cone of a large-angled condenser. Yet these particles, when continuously watched, are soon observed to enlarge and to undergo elongation (figs. 16, 17, 18, 19, 20), and within two hours after their emission from the sac the anterior flagellum, and afterwards the two lateral flagella (fig. 19), can be distinguished. Slight movements then commence, the neck-like protrusion shows itself and in about half an hour more the regular swimming action begins. About four hours after the escape of its germ from the sac, the monad acquires its characteristic form (fig. 21), though still only one-half the length of its parent; but this it attains in another hour, and the process of multiplication by fission, as already described, commences very soon afterwards. There can be no reasonable doubt that the 'conjugation' of two individuals, followed by the transformation of their fused bodies into a sac filled with reproductive germs, is to be regarded (as in protophytes) in the light of a true *generative* process; and it is interesting to observe the indication of sexual distinction here marked by the different states of the two conjugating individuals. There is every reason to believe that *the entire life-cycle* of this monad has thus been elucidated; and it will now be sufficient to notice the principal diversities observed by Messrs. Dallinger and Drysdale in the life-cycles of the other monadine forms which they have studied.

The *bi-flagellate* or 'acorn' monad of the same observers (identified by Kent with the *Polytoma uvella* of Ehrenberg) presents some remarkable peculiarities in its mode of reproduction. Its binary fission extends only to the protoplasmic substance of its body, leaving

its envelope entire ; and by a repetition of the process, as many as sixteen segments, each attaining the likeness of the parent, are seen thus enclosed, their flagella protruding through the general investment. This compound state being supposed by Ehrenberg to be the normal one, he named it accordingly. But the parent-cyst soon bursts, and sets free the contained 'macro-spores,' which swim about freely, and soon attain the size of the parent. Again, the posterior part of the body of certain individuals shows an accumulation of granular protoplasm, giving to that region a roughened acorn-cup-like aspect ; the bursting of the projection, while the creature is actively swimming through the water, sets free a multitude of indefinitely shaped granular fragments, within each of which a minute bacterium-like corpuscle is developed ; and this, on its release, acquires in a few hours the size and form of the original monad. This process seems analogous to the development of 'micro-spores' among protophytes by the direct breaking up of the protoplasm. It is, like the previous process, non-sexual or *gonidial*, the true generative process consisting here, as in the preceding cases, in the 'conjugation' of two individuals, with the usual results.

The *hooked monad* (*Heteromita uncinata*, Kent) is another biflagellate form, usually ovate with one end pointed, and from $\frac{1}{3000}$th to $\frac{1}{2000}$th of an inch in length, being distinguished from the preceding by the peculiar character of its flagella, of which the one that projects forward is not more than half the length of the body, and is permanently hooked, while the other, whose length is about twice that of the body, is directed backwards, flowing in graceful curves. Its motion consists of a succession of springs or jerks rapidly following each other, which seems produced by the action of the hooked flagellum. Multiplication takes place by *transverse* fission, and continues uninterruptedly for several days. A difference then becomes perceptible between larger and smaller individuals, the former being further distinguished by the presence of what seems to be a contractile vesicle in the anterior part of the body. Conjugation occurs between one of the larger and one of the smaller forms, the latter being, as it were, absorbed into the body of the larger ; and the resulting product is a spherical cyst, which soon begins to exhibit a cleavage-process in its interior. This continues until the whole of its sarcodic substance is subdivided into minute oval particles, which are set free by the rupture of the cyst, and of which each is usually furnished with a single flagellum, by whose lashing movement it swims freely. These germs speedily attain the size and form of the parent, and then begin to multiply by transverse fission, thus completing the 'genetic' cycle.

The *calycine monad* of the same observers (*Tetramitus rostratus*, Perty) has a length of from $\frac{1}{900}$th to $\frac{1}{1000}$th of an inch, and a compressed body tapering backwards to a point. Its four flagella (which constitute its generic distinction) arise nearly together from the flattened front of the body, and its swimming movement is a graceful gliding. Near the base of the flagella are a pair of contractile vesicles, and further behind is a large nucleus. Multiplication takes place by longitudinal fission, which is preceded by a change to a semi-

amœboid state. This gives place to a more regular pear-like form, the four flagella issuing from the large end; and the fission commences at their base, two pairs being separated by the cleavage-plane. The nucleus also undergoes cleavage, and its two halves are carried apart by the backward extension of the cleavage. The two half-bodies at last remain connected only by their hinder prolongations, which speedily give way, and set them free. Each, however, has, as yet, only two flagella; but these speedily fix themselves by their free extremities, undergo a rapid vibratory movement, and in the course of about two minutes split themselves from end to end. A still more complete change into the amœboid condition, in which the creature not only moves, but also feeds, like an *Amœba* (devouring all the living and dead Bacteria in its neighbourhood), occurs previously to 'conjugation'; and this takes place between two of the amœboid forms, which begin to blend into each other almost immediately upon coming into contact. The conjugated bodies, however, swim freely about for a time, the two sets of flagella apparently acting in concert. But by the end of about eighteen hours the fusion of the bodies and nuclei is complete, the flagella are lost, and a spherical distended sac is then formed, which, in a few hours more without any violent splitting or breaking up, sets free innumerable masses of reproductive particles. These under a magnifying power of 2500 diameters can be just recognised as oval granules, which rapidly develop themselves into the likeness of their parents, and in their turn multiply by duplicative fission, thus completing the 'genetic' cycle.

One of the most important researches thus ably prosecuted by Messrs. Dallinger and Drysdale has reference to the temperatures respectively endurable by the adult or developed forms of these monads, and by their reproductive germs. A large number of experiments upon the several forms now described indubitably led to the conclusion that all the *adult* forms, as well as all those which had reached a stage of development in which they can be distinguished from the reproductive granules, are utterly destroyed by a temperature of 150° Fahr. But, on the other hand, the reproductive granules emitted from the cysts that originate in 'conjugation' were found capable of sustaining a *fluid* heat of 220°, and a dry heat of about 30° more, those of the Cercomonad surviving exposure to a *dry* heat of 300° Fahr. This is a fact of the highest interest in its bearing on the question of 'spontaneous generation,' or abiogenesis; since it shows that germs capable of surviving desiccation may be everywhere diffused through the air, and may, on account of their extreme minuteness (as they certainly do not exceed $\frac{1}{250000}$th of an inch in diameter), altogether escape the most careful scrutiny and the most thorough cleansing processes; while (2) their extraordinary power of resisting heat will prevent these germs from being killed, either by boiling, or by dry-heating up to even 300° Fahr.[1]

Beyond these facts others of some importance, as well as a new

[1] Descriptions of the special apparatus used by Messrs. Dallinger and Drysdale in their researches will be found in *Monthly Micros. Journ.* vol. xi. 1874, p. 97; *ibid.* vol. xv. 1876, p. 165; and *Proceed. Roy. Soc.* vol. xxvii. 1878, p. 343.

saprophytic organism [1] of special character, have been discovered during a recent period. But it will be of more moment here to note to what an extent in this series of observations *the new homogeneous objectives, especially in their apochromatic form*, have been successfully employed in enlarging the area of knowledge.

The present Editor has gone carefully over the great part of the work, revising all the critical points with the best apochromatic objectives, and the homogeneous forms of achromatics with an aperture of 1·50 and with a clear demonstration of the immensely greater ease with which the work could have been done had these lenses been used in the original investigation.

But the easily accessible proof of this is given in the work done by Dr. Dallinger upon the *nucleus* of the nucleated forms of these monads.

Briefly to present the facts, we may recall the part taken in the *act of fission* in the form last described (*Dallingeria Drysdali*). It will be seen by reference that it appeared to us that the *nucleus followed the processes inaugurated by the somatic sarcode*. That in fact it was a passive participator in the act of fission. This is all that can be made out *to-day* by the very lenses originally employed.

But by the employment of a $\frac{1}{12}$th inch and $\frac{1}{20}$th inch homogeneous of N.A. 1·50 by Powell and Lealand, and an apochromatic of $\frac{1}{12}$th inch N.A. 1·40 by the same Firm ; and also by the use of the beautiful 3 mm. and 2 mm. N.A. 1·40 of Zeiss (apochromatic), it can be seen with comparative ease *that it is in the nucleus that all* the activities of the body *are originated.*

This may be followed from a study of Plate XIV. Fig. 1, A, represents the nucleus of the form drawn at fig. 1, E, Plate XIII. In long diameter it is of an average length of $\frac{1}{2000}$th of an inch ; but instead of being a darkly refractive object, as seen with the objectives used twelve years ago, it is with the present lenses, freed from chromatic and spherical aberration, a body in the monad undergoing no process of change, an oval globule with a complicated plexus-like involution throughout its substances, as seen in fig. 6, A, Plate XIV. But directly the process of fission is to be inaugurated, we need not wait to see its first action in the splitting of the flagellum, as in fig. 2, E, Plate XIII, ; for by observing the nucleus we discover, before any change has begun in the body-substance, that the *plexus* in the nucleus has condensed itself on *either side of the nucleus*, as in fig. 1, *b*, A, Plate XIV. A clear space is left at *c*, and no change has taken place in the body-sarcode, *a*, *a*, *a*. But shortly an incision takes place in the nucleus, as at *d*, fig. 2, and this is immediately *followed* by the incision *f* in the body-sarcode, and the process goes on simultaneously in nucleus and body, as in fig. 3, until the division of the nucleus is completely effected, and the total severance of the body follows.

But as soon as the nucleus is *divided*, the plexus, which has been during division, as in fig. 3, condensed over *part* of each dividing half, at once distributes itself evenly again, as in fig. 6, A, and remains so until another change is inaugurated in the form to which the nucleus belongs.

[1] *Journ. of Royal Micros. Soc.* vol. v.

Not less remarkable is this in the *conjugation* of the same form. With the old lenses we could only discover that the end of a series of fissions had been reached by the change which came over the entire body of the terminal form seen in fig. 11, E, Plate XIII. But now, before the amœboid state preceding the assumption of the condition shown in fig. 11 takes place, it can be seen that the nucleus undergoes remarkable change, for it passes from a highly refractive plexus-like condition into a large milky structureless state, and in this condition blends with one of the ordinary forms whose nucleus is of the ordinary type. The first result of fusion is seen in fig. 4, A, Plate XIV, showing only the greatly magnified blended nuclei, and where the blending between them is seen to be nearly complete at *a*, and a nucleus or nucleolus is manifest; while when the blending is more perfect there is a diffusion of this central or nucleolar body through the substance of the whole, as in fig. 5, A.

In B, Plate XIV, the nucleus only, separate from the body of the organism known as *Tetramitus rostratus*, is shown as we can reveal it with recent German and English apochromatic objectives. This entire organism is relatively large, and its nucleus will average in long diameter the $\frac{1}{1000}$th of an inch.

Hence it affords a still better means of study. Now this organism divides by fission for a very considerable time, but at length many forms become amœboid—acting precisely as an amœba, but retaining traces of their primal form. In this state two of them blend, and as a result a sac of spore is formed from which a new generation arises.

We could with the old objectives determine nothing more than the fact that the amœboid form had supervened; but now it is easy to show that the nucleus in the body of a form not yet amœboid is undergoing change upon which the amœboid state is certain to supervene.

This is even more striking in the growth of the germ. It attains a certain size in growth, and then there is an arrest of all enlargement. This we had long observed in the earlier observations. But now with apochromatic object-glasses it has been demonstrated that this arrest of outward growth is only the signal for an internal development. Fig. 1, B, Plate XIV, shows the condition of the nucleus when there is an apparent pause in its growth. Fig. 2 shows the same nucleus after about forty minutes of external inaction, a plexus-like formation having filled its substance.

The nucleus remains thus in the mature body of the monad *until fission is to be inaugurated*, when the change seen in fig. 3 followed by the changes and deeper division seen in figs. 4, 5, 6, 7, and 8, which, *after* the state of the nucleus seen in fig. 4 has been reached, is shared in by initiation of division in the substance of the entire body.

It thus appears that a form of *karyokinesis* takes place in the nucleus of even such lowly forms as these, and that it is the nucleus that is the seat of their intensest vitality.

A large series of more complex forms of flagellate Infusoria has been brought to our knowledge by the researches of the late

Plate XIV.





STUDIES OF THE NUCLEUS IN SAPROPHYTIC ORGANISMS.



Professor James-Clark (U.S.A.),[1] followed by those of Stein, Saville Kent,[2] and Bergh. In some of these a sort of collar-like extension of what appears to be the protoplasmic ectosarc proceeds from the anterior extremity of the body (fig. 527, *cl*), forming a kind of funnel, from the bottom of which the flagellum arises; and by its vibrations a current is produced within the funnel, which brings down food-particles to the 'oral disc' that surrounds its origin where the ectosarc seems softer than that which envelops the rest of the body. Towards the base of the collar a nucleus (*n*) is seen; while near the posterior termination of the body is a single or double contractile vesicle (*cv*). The body is attached by a pedicle proceeding from its posterior extremity, which also seems to be a prolongation of the ectosarc. These animalcules multiply by longitudinal fission; and this, in some cases (as in the genus *Monosiga*), proceeds to the extent of a complete separation of the two bodies, which henceforth, as in the ordinary *Monadina*, live quite independently of each other. But in other forms, as *Codosiga*, the fission does not extend through the pedicel, and the twin bodies being thus held together at their bases, and themselves undergoing duplicative fission, clusters are produced which spring from common pedicels (fig. 528); and by the extension of the division down the pedicels themselves, composite arborescent fabrics, like those of zoöphytes, are produced.



FIG. 527.—Single zoöid of *Codosiga umbellata*: *cl*, collar; *n*, nucleus; *cv*, double contractile vesicle.

In another group a structureless and very transparent horny calyx, closely resembling in miniature the polype-cell of a *Campanularia* forms itself round the body of the monad, which can retract itself into the bottom of it; and in the genus *Salpingœca* both calyx and collar are present. In some forms of this group multiplication seems to take place, not by fission, but by gemmation; and, as among hydroid polypes, the *gemmæ* may either detach themselves and live independently, or may remain in connection with their parent-stocks, forming composite fabrics, in some of which the calyces follow one another in linear series, whilst in others they

[1] See his memoirs in *Ann. Nat. Hist.* ser. 3, vol. xviii. 1866; *ibid.* ser. 4, vol. i. 1868; vol. vii. 1871; and vol. ix. 1872.

[2] See his *Manual of the Infusoria*, 1880–82, 2 vols. and 1 vol. of plates.

take on a ramifying arrangement. While some of these composite organisms are sedentary, others, as *Dinobryon*, are free-swimming.

Two solitary flagellate forms, *Anthophysa* and *Anisonema*, may be specially noticed as presenting several interesting points of resemblance to the peculiar type next to be described, the most noticeable being the presence of a distinct mouth and the possession of two different motor organs—one a comparatively stout and stiff bristle, of uniform diameter throughout, which moves by occasional jerks, and the other a very delicate tapering flagellum, which is in constant vibratory motion. If, as appears from the recent observations of Bütschli, the well-known *Astasia*—of which one species has a blood-red colour, and sometimes multiplies to such an extent as to tinge the water of the ponds it inhabits—has a true mouth for the

FIG. 528.—*Codosiga umbellata*: Colony-stock, springing from single pedicel tripartitely branched.

reception of its food, it must be regarded as an animal, and separated from the *Euglena* (with which it has been generally associated), the latter being pretty certainly a plant belonging to the same group as *Volvox*.[1]

There can be no longer any doubt that the well-known *Noctiluca miliaris*—to which is attributable the *diffused* luminosity that frequently presents itself in British seas—is to be regarded as a gigantic type of the 'unicellular' *Flagellata*. This animal, which is of spheroidal form, and has an average diameter of about $\frac{1}{60}$th of an inch, is just large enough to be discerned by the naked eye when the water in which it may be swimming is contained in a glass jar held up t

[1] See the memoir by Prof. Bütschli in *Zeitschrift f. Wissensch. Zool.* Bd. XXX. of which an abridgment (with plate) is given in *Quart. Journ. Micros. Sci.* vol. XX. 1879, p. 63.

the light ; and its tail-like appendage, whose length about equals its own diameter, and which serves as an instrument of locomotion, may be discerned with a hand-magnifier. The form of *Noctiluca* is nearly that of a sphere, so compressed that while on one aspect (fig. 529, A) its outline, when projected on a plane, is nearly circular, it is irregularly oval in the aspect (B) at right angles to this. Along one side of this body is a meridional groove, resembling that of a peach ; and this leads at one end into a deep depression of the surface, *a*, termed the *atrium*, from the shallower commencement of which the *tentacle*, *d*,[1] originates ; whilst it deepens down at the base of the tentacle to the mouth, *e*. Along the opposite meridian there extends a slightly elevated ridge, *c*, which commences with the appearance of a bifurcation at the end of the atrium farthest from



FIG. 529.—*Noctiluca miliaris* as seen at A on the aboral side, and at B on a plane at right angles to it : *a*, entrance to atrium ; *b*, atrium ; *c*, superficial ridge ; *d*, tentacle ; *e*, mouth leading to œsophagus, within which are seen the flagellum springing from its base, and the tooth-like process projecting into it from above ; *f*, broad process from the central protoplasmic mass proceeding to superficial ridge ; *g*, duplicature of wall ; *h*, nucleus. (Magnified about ninety diameters.)

the tentacle : this is of firmer consistence than the rest of the body, and has somewhat the appearance of a rod imbedded in its walls. The mouth opens into a short œsophagus, which leads directly down to the great central protoplasmic mass ; on the side of this canal, farthest from the tentacle, is a firm ridge that forms a tooth-like projection into its cavity ; whilst from its floor there arises a long

[1] The organ here termed 'tentacle' is commonly designated *flagellum* ; while what is here termed the *flagellum* is spoken of by most of those who have recognised it as a *cilium*. The Author agrees with M. Robin in considering the former organ, which has a remarkable resemblance to a single fibrilla of striated muscle as one peculiar to *Noctiluca*, and the latter as the true homologue of the flagellum of the ordinary Flagellata. It is curious that several observers have been unable to discover the so-called cilium, which was first noticed by Krohn. Professor Huxley sought for it in at least fifty individuals without success ; and out of the great number which he afterwards examined he did not get a clear view of it in more than half a dozen.

flagellum, which vibrates freely in its interior. The central protoplasmic mass sends off in all directions branching prolongations of its substance, whose ramifications inosculate ; these become thinner and thinner as they approach the periphery, and their ultimate filaments, coming into contact with the delicate membranous body-wall, extend themselves over its interior, forming a protoplasmic network of extreme tenuity (fig. 530). Besides these branching prolongations, there is sent off from the central protoplasmic mass a broad, thin, irregularly quadrangular extension (fig. 529, B, *f*), which extends to the superficial rod-like ridge, and seems to coalesce with it ; its lower free edge has a thickened border ; whilst its upper edge becomes continuous with a plate-like striated structure, *g*, which seems to be formed by a peculiar duplicature of the body-wall. At one side of the protoplasmic mass is seen a spherical vesicle, *h*, of



FIG. 530.—Portion of superficial protoplasmic reticulation formed by ramification of an extension *a* of central mass. (Magnified 1000 diameters.)

about $\frac{3}{2000}$ths of an inch in diameter, having clear colourless contents, among which transparent oval corpuscles may usually be detected. This, from the changes it undergoes in connection with the reproductive process, must be regarded as a *nucleus*.

The particles of food drawn into the mouth (probably by the vibrations of the flagellum) seem to be received into the protoplasmic mass at the bottom of the œsophagus by extensions of its substance, which enclose them in filmy envelopes that maintain themselves as distinct from the surrounding protoplasm, and thus constitute extemporised digestive vesicles. These vesicles soon find their way into the radiating extensions of the central mass (as shown in fig. 529, B), and are ensheathed by the protoplasmic substance which goes on to form the peripheral network (fig. 531). Their number and position are alike variable ; sometimes only one or two are to be distinguished ; more commonly from four to eight can be seen :

l even twelve or more are occasionally discernible. The place of h in the body is constantly being changed by the contractions of protoplasmic substance, these in the first place carrying it from centre towards the periphery of the body, and then carrying it k to the central mass, into whose substance it seems to be ed as soon as it has discharged any indigestible material it may e contained, which is got rid of through the mouth. Every part the protoplasmic reticulation is in a state of incessant change, ich serves to distribute the nutrient material that finds its way o it through the walls of the digestive vesicles; but no regular *losis* (like that of plants) can be observed in it. Besides the gestive vesicles,' vacuoles filled with clear fluid may be distinshed, alike in the central protoplasmic mass, and in its extensions, is shown in the centre of fig. 529. There is no contractile vesicle. The peculiar 'tentacle' of *Noctiluca* is a flattened whip-like fila-nt, gradually tapering from its base to its extremity, the two tened faces being directed respectively towards and away from oral aperture. When either of its flattened faces is examined, it



FIG. 531.—Pair of digestive vesicles of *Noctiluca* lying in course of extension of central protoplasmic mass, *a*, to form peripheral reticulation, *b*, and containing remains of Algæ. (Magnified 480 diameters.)

ws an alternation of light and dark spaces, in every respect embling those of striated muscular fibre, except that the clear ces are not subdivided. But when looked at in profile, it is seen t between the striated band and the aboral surface is a layer of nular protoplasm. The tentacle slowly bends over towards the ıth about five times in a minute, and straightens itself still more vly, the middle portion rising first, while the point approaches base, so as to form a sort of loop, which presently straightens. eems probable that the contraction of the substance forming the k bands produces the bending of the filament; whilst, when relaxes, the filament is straightened again by the elasticity of the nular layer.

The extreme transparence of *Noctiluca* renders it a particularly ɔurable subject for the study of the phenomena of phosphorescence. ıen the surface of the sea is rendered luminous by the general ısion of *Noctilucæ*, they may be obtained by the tow-net in un-ited quantities; and when transferred into a jar of sea-water, y soon rise to the surface, where they form a thick stratum. The htest agitation of the jar in the dark causes an instant emission of

their light, which is of a beautiful greenish tint, and is vivid enough to be perceptible by ordinary lamp-light. This luminosity is but of an instant's duration, and a short rest is required for its renewal. A brilliant, but short-lived display of luminosity, to be followed by its total cessation, may be produced by electric or chemical stimulation. Professor Allman found the addition of a drop of alcohol to the water containing specimens of *Noctiluca*, on the stage of the microscope, produce a luminosity strong enough to be visible under a half-inch objective, lasting with full intensity for several seconds, and then gradually disappearing. He was thus able to satisfy himself that the special seat of the phosphorescence is the peripheral protoplasmic reticulation which lines the external structureless membrane.

The reproduction in this interesting type is effected in various ways. According to Cienkowsky, even a small portion of the protoplasm of a mutilated *Noctiluca* will (as among rhizopods) reproduce the entire animal. Multiplication by fission or binary subdivision, beginning in the enlargment, constriction, and separation of the two halves of the nucleus, has been frequently observed. Another form of non-sexual reproduction, which seems parallel to the 'swarming' of many protophytes, commences by a kind of encysting process. The tentacle and flagellum disappear, and the mouth gradually narrows, and at last closes up; the meridional groove also disappears, so that the animal becomes a closed hollow sphere. The nucleus elongates, and becomes transversely constricted, and its two halves separate, each remaining connected with a portion of the protoplasmic network. This duplicative subdivision is repeated over and over again, until as many as 512 'gemmules' are formed, each consisting of a nuclear particle enveloped by a protoplasmic layer, and each having its flagellum. The entire aggregate forms a disc-like mass projecting from the surface of the sphere; and this mass sometimes detaches itself as a whole, subsequently breaking up into individuals; whilst, more commonly, the gemmules detach themselves one by one, the separation beginning at the margin of the disc, and proceeding towards its centre. The gemmules are at first closed monadiform spheres, each having a nucleus, contractile vesicle, and flagellum; the mouth is subsequently formed, and the tentacle and permanent flagellum afterwards make their appearance. A process of 'conjugation' has also been observed, alike in ordinary *Noctilucæ* and in their closed or encysted forms, which seems to be sexual in its nature. Two individuals, applying their oral surfaces to each other, adhere closely together, and their nuclei become connected by a bridge of protoplasmic substance. The tentacles are thrown off, the two bodies gradually coalesce, and the two nuclei fuse into one. The whole process occupies about five or six hours, but its results have not been followed out.[1]

[1] *Noctiluca* has been the subject of numerous memoirs, of which the following are the most recent: Cienkowski, *Arch. f. Micros. Anat.* Bd. vii. 1871, p. 181, and Bd. ix. 1873, p. 47; Allman, *Quart. Journ. Micros. Sci.* n.s. vol. xii. 1872, p. 89; Robin, *Journ. de l'Anat. et de Physiol.* tom. xiv. 1878, p. 586; Vignal, *Arch. de Physiol.* sér. ii. tom. v. 1878, p. 415; Stein, *Der Organismus der Infusionsthiere*, iii. 2, 1883; and Bütschli, *Morphol. Jahrbuch*, x. 1885, p. 529. For the group of which it and *Leptodiscus* (Hertwig) are the representatives, Ray Lankester has suggested the name *Rhynchoflagellata*.

The name *Cilio-flagellata* and the definition of the group must ›th be altered, now that Klebs and Bütschli have shown that what ere regarded as cilia in the transverse grooves of their bodies is ally a flagellum; the name to be used is *Dinoflagellata*.[1] Al- ›ough this group does not contain any great diversity of forms, yet it specially worthy of notice, not only on account of the occasiona' ›pearance of some of them in extraordinary multitudes, but also for eir power of forming cellulose—a property which is often thought be particularly characteristic of plants. The *Peridinium* observed Professor Allman in 1854 was present in such quantities that imparted a brown colour to the water of some of the large ponds Phœnix Park, Dublin, this colour being sometimes uniformly ffused, and sometimes showing itself more deeply in dense clouds, rying in extent from a few square yards to upwards of a hundred. ıe animal (fig. 532, A, B) has a form approaching the spherical, th a diameter of from $\frac{1}{1300}$th to $\frac{1}{500}$th of an inch, and is rtially divided into two hemispheres by a deep equatorial furrow, whilst the flagellum-bearing hemisphere, A, has a deep meridional ›ove on one side, *b*, extending from the equatorial groove to the le, the flagellum taking its origin from the bottom of this vertical



FIG. 532.—*Peridinium uberrimum*: A, B, front and back views; C, encysted stage; D, duplicative subdivision.

›ove, near its junction with the equatorial. The members of this ›up vary considerably in their mode of taking food; from the eaches of Bergh it would appear that those which are provided ›h chromatophores have a plant-like mode of obtaining food, while ›se which are without chromatophores are truly animal in their thod of alimentation. A 'contractile vesicle' has been rarely ›erved; but a large nucleus, sometimes oval and sometimes horse- ›e-shaped, seems always present. The *Peridinia* multiply by nsverse fission (fig. 532, D), which commences in the subdivision the nucleus, and then shows itself externally in a constriction of ungrooved hemisphere, parallel to the equatorial furrow. They ›s into a quiescent condition, subsiding towards the bottom of the ter, and the loricated forms appear to throw off their envelopes. ere is reason to believe that conjugation obtains in certain cases: *›odinium cinctum* has been observed by Professor Askenasy to ›ulate, but the development of the zygote, as the product of copu- ion may be called, has not yet been worked out. Some of the *ridinia* are found in sea-water, but the most remarkable marine ms of the cilio-flagellate group belong to the genus *Ceratium* (fig. 3), in which the cuirass extends itself into long horny appendages.

[1] Or, more correctly, *Dinomastigophora*.

In the *Ceratium tripos* (1) there are three of these appendages: two of them curved, proceeding from the anterior portion of the cuirass, and the third, which is straight or nearly so, from its posterior portion. They are all more or less jagged or spinous. In *Ceratium furca* (2) the two anterior horns are prolonged straight forwards, one of them being always longer than the other; whilst the posterior is prolonged straight backwards. The anterior and posterior halves of the cuirass are separated by a ciliated furrow, from one point of which the flagellum arises; and at the origin of this is a deep depression into which the flagellum may be completely and suddenly withdrawn. The Author has found the *Ceratium tripos* extremely

FIG. 533.—1, *Ceratium tripos*; 2, *Ceratium furca*.

abundant in Lamlash Bay, Arran, where it constitutes a principal article of the food of the *Antedons* that inhabit its bottom.[1]

Suctoria.—The *suctorial* Infusoria constitute a well-marked group, all belonging to one family, *Acinetina*, the nature of which has been until recently much misunderstood, chiefly on account of the parasitism of their habit. Like the typical *Monadina*, they are closed cells, each having its nucleus and contractile vesicle; but instead of freely swimming through the water, they attach themselves by flexible peduncles, sometimes to the stems of *Vorticellinæ*, but also to filamentous Algæ, stems of zoöphytes, or to the bodies of larger animals. Their nutriment is obtained through delicate

[1] See Allman in *Quart. Micros. Journ.* vol. iii. 1855, p. 24; H. James-Clark in *Ann. Nat. Hist.* ser. iii. vol. xviii. 1866, p. 429; and Bergh, *Morphol. Jahrbuch*, vii. 1881, p. 177.

tubular extensions of the ectosarc, which act as suctorial tentacles (fig. 534), the free extremity of each being dilated into a little knob, which flattens out into a button-like disc when it is applied to a food-particle. Free-swimming Infusoria are captured by these organs, of which several quickly bend over towards the one which was at first touched, so as firmly to secure the prey; and when several have thus attached themselves, the movements of the imprisoned animal become feebler, and at last cease altogether, its body being drawn nearer to that of its captor. Instead, however, of being received into its interior like the prey of *Actinophrys*, the captured animalcule remains on the outside, but yields up its soft substance to the suctorial power of its victor. As soon as the suck-

FIG. 534.—*Suctorial Infusoria*: 1, Conjugation of *Podophrya quadripartita*; 2, formation of embryos by enlargement and subdivision of the nucleus; 3, ordinary form of the same; 4, *Podophrya elongata*.

ing disc has worked its way through the envelope of the body to which it has attached itself, a very rapid stream, indicated by the granules it carries, sets along the tube, and pours itself into the interior of the Acineta-body. Solid particles are not received through these suctorial tentacles, so that the *Acinetina* cannot be fed with indigo or carmine; but, so far as can be ascertained by observation of what goes on within their bodies, there is a general protoplasmic *cyclosis* without the formation of any special 'digestive vesicles.' The ordinary forms of this group are ranked under the two genera *Acineta* and *Podophrya*, which are chiefly distinguished by the presence of a firm envelope or *lorica* in the former, while the body of the latter is naked. In one curious form, the *Ophryodendron*, the suckers are borne in a brush-like expansion on a long retractile

proboscis-like organ ; and the rare *Dendrosoma*, whose size is comparatively gigantic, forms by continuous gemmation an arborescent 'colony,' of which the individual members remain in intimate connection with one another.

Multiplication in this group seems occasionally to take place by longitudinal fission, but this is rare in the adult state. Sometimes external *gemmæ* are developed by a sort of pinching off of a part of the free end of the body, which includes a portion of the nucleus ; the tentacula of this bud disappear, but its surface becomes clothed with cilia ; and, after a short time, it detaches itself and swims away—comporting itself subsequently like the internal embryos, whose production seems the more ordinary method of propagation in this type. These originate in the breaking up of the nucleus into several segments, each of which incloses itself in a protoplasmic envelope ; and this becomes clothed with cilia, by the vibrations of which the embryos are put in motion within the



FIG. 535.—Immature forms of *Podophrya quadripartita* : 1, Amœboid state (*Trichophrya* of Claparède and Lachmann); 2, the same more advanced; 3, incipient division into lobes.

body of the parent (fig. 534, 2), from which they afterwards escape by its rupture. In this condition (*a*) they swim about freely, and seem identical with what has been described by Ehrenberg as a distinct generic form, *Megatricha*. And, according to the observations of Mr. Badcock,[1] these *Megatricha*-forms multiply freely by self-division. After a short time, however, they settle down upon filamentous Algæ or other supports, lose their cilia, put forth suctorial tentacles (which seem to shoot out suddenly in the first instance, but are afterwards slowly retracted and protruded with a kind of spiral movement), and assume a variety of amœbiform shapes (fig. 535, 1, 2, 3), some of them corresponding to that of the genus *Trichophrya*. In this stage they become quiescent at the approach of winter, the suctorial tentacles and the contractile vesicles disappearing ; they do not, however, seem to acquire any special envelope, remaining as clear, motionless, protoplasmic particles. But with the return of warmth their development recommences, a

[1] *Journ. of Roy. Micros. Soc.* vol. iii. 1880, p. 563.

footstalk is formed, and they gradually assume the characteristic form of *Podophrya quadripartita*. A regular 'conjugation' has been observed in this type, the body of one individual bending down so as to apply its free surface to the corresponding part of another, with which it becomes fused (fig. 534, 1); but whether this always precedes the production of internal embryos, or is any way preparatory to propagation, has not yet been ascertained.[1]

Ciliata.—As it is in this tribe of animalcules that the action of the organs termed *cilia* has the most important connection with the vital functions, it seems desirable here to introduce a more particular notice of them. They are always found in connection with *cells*, of whose protoplasmic substance they may be considered as extensions, endowed in a special degree with its characteristic contractility. The form of the filaments is usually a little flattened, tapering gradually from the base to the point. Their size is extremely variable, the largest that have been observed being about $\frac{1}{500}$th of an inch in length, and the smallest about $\frac{1}{13000}$th. When in motion each filament appears to bend from its root to its point, returning again to its original state, like the stalks of corn when depressed by the wind; and when a number are affected in succession with this motion, the appearance of progressive waves following one another is produced, as when a cornfield is agitated by successive gusts. When the ciliary action is in full activity, however, little can be distinguished save the whirl of particles in the surrounding fluid; but the *back* stroke may often be perceived, when the *forward* stroke is made too quickly to be seen, and the real direction of the movement is then opposite to the apparent. In this back stroke, when made slowly enough, a sort of 'feathering' action may be observed, the thin edge being made to cleave the liquid, which has been struck by the broad surface in the opposite direction. It is only when the rate of movement has considerably slackened that the shape and size of the cilia, and the manner in which their stroke is made, can be clearly seen. Their action has been observed to continue for many hours, or even days, after the death of the body at large. As *cilia* are not confined to animalcules and zoöphytes, but give motion to the zoöspores of many protophytes, and also clothe the free internal surfaces of the respiratory and other passages in all the higher animals, including man (our own experience thus assuring us that their action takes place, not only without any exercise of *will*, but even without *consciousness*), it is clear that to regard animalcules as possessing a 'voluntary' control over the action of their cilia is altogether unscientific.

In the ciliated Infusoria, the differentiation of the sarcodic substance into 'ectosarc' or cell-wall, and 'endosarc' or cell-contents,

[1] The *Acinetina* were described both by Ehrenberg and Dujardin; but the first full account of their peculiar organisation was given by Stein in his *Organismus der Infusionsthierchen*. Misled, however, by their parasitic habits, Stein originally supposed them not to be independent types, but to be merely transitional stages in the development of *Vorticellinæ* and other ciliate Infusoria; this doctrine he long since abandoned. Much information as to this group will also be found in the beautiful *Etudes sur les Infusoires et les Rhizopodes* of MM. Claparède and Lachmann, Geneva, 1858–61.

becomes very complete, the ectosarc possessing a membranous firmness which prevents it from readily yielding to pressure, and having a definite internal limit, instead of graduating insensibly (as in rhizopods) into the protoplasmic layer which lines it. A 'nucleus' seems always present, being sometimes 'parietal' (or adherent to the interior of the ectosarc), in other cases lying in the midst of the endosarc. In many *Ciliata* a distinct 'cuticle' or exudation-layer may be recognised on the surface of the ectosarc: and this cuticle, which is studded with regularly arranged markings like those of Diatomaceæ, seems to be the representative of the carapace of *Arcella* &c. as of the cellulose coat of protophytes. It is sometimes hardened, so as to form a 'shield' that protects



FIG. 536.—A, *Kerona silurus*: *a*, contractile vesicle; *b*, mouth; *c*, *c*, animalcules swallowed by the Kerona, after having themselves ingested particles of indigo. B, *Paramecium caudatum*: *a*, *a*, contractile vesicles; *b*, mouth. The dotted lines indicate currents.

the body on one side only, or a 'lorica' that completely invests it; and there are other cases in which it is so prolonged and doubled upon itself as to form a sheath resembling the 'cell' of a zoöphyte, within which the body of the animalcule lies loosely, being attached only by a stalk at the bottom of the case, and being able either to project itself from the outlet or to retract itself into the interior. In the marine forms known as *Dictocysta* and *Codonella*, described by Haeckel, the body is enclosed in a silicious lattice-work shell, usually bell-shaped or helmet-shaped, which bears so strong a resemblance to the shells of many Radiolaria as to be easily mistaken for them. The form of the body is usually much more definite than that of the naked rhizopods, each species having its characteristic shape, which is only departed from, for the most part, when the animalcule is subjected to pressure from without, or when its cavity has been distended by the ingestion of any substance above the ordinary size. The *cilia* and other mobile appendages of

the body are extensions of the outer layer of the 'ectosarc' proper; and this layer, which retains a high degree of vital activity, is sometimes designated the 'cilia-layer.' Beneath this is a layer in which (or in certain bands of which) regular, parallel, fine striæ may be distinguished, and as this striation is also distinguishable in the eminently contractile foot-stalk of *Vorticella*[1] (fig. 537, B) there seems good reason to regard it as indicating a special modification of protoplasmic substance, which resembles muscle in its endowments. Hence this is termed the 'myophan-layer.' Beneath this, in certain species of Infusoria, there is found a thin stratum of condensed protoplasm, including minute 'trichocysts,' which resemble in miniature the 'thread-cells' of zoophytes; and this, where it exists, is known as the 'trichocyst-layer.' The hair-like processes of protoplasm may be caused to protrude from the cell by such irritation as is effected by the addition of a little iodine to the water in which the animalcule is living.



FIG. 537.—Group of *Vorticella nebulifera* showing, A, the ordinary form; B, the same with the stalk contracted; C, the same with the bell closed; D, E, F, successive stages of fissiparous multiplication.

The vibration of ciliary filaments, which are either disposed along the entire margin of the body, as well as around the oral aperture (fig. 537, A, B), or are limited to some one part of it, which is always in the immediate vicinity of the mouth, supplies the means in this group of *Infusoria* both for progression through the water and for drawing alimentary particles into the interior of their bodies. In some their vibration is constant, whilst in others it is only occasional. The modes of movement which infusory animalcules execute by means of these instruments are extremely varied and remarkable. Some propel themselves directly forwards, with a velocity which appears, when highly magnified, like that of an arrow, so that the eye can scarcely follow them; whilst others drag their bodies slowly along like a leech. Some attach themselves by one of their long filaments to a fixed point, and revolve around it with great rapidity, whilst others move by undulations, leaps, or successive gyrations: in short, there is scarcely any kind of animal movement which they do not exhibit. But there are cases in which the locomotive filaments have a bristle-like firmness, and, instead of keeping themselves in rapid vibration, are moved

[1] On the morphology of the Vorticellinæ see Bütschli, *Morphol. Jahrb.* xi. p. 553.

(like the spines of Echini) by the contraction of the integu
which they arise, in such a manner that the animalcule
their means over a solid surface, as we see especially in
lynceus (fig. 541, P, Q). In *Chilodon* and *Nassula*, again,
is provided with a circlet of plications or folds, looking lik
which, when imperfectly seen, received the designation of
their function, however, is rather that of laying hold of
ary particles by their expansion and subsequent drawing
(somewhat after the fashion of the tentacula of zoöphyte
reducing them by any kind of masticatory process. S
Opalina, are entoparasitic, and have no mouth ; a form
Opalina (*Anoplophrya circulans*) lives in the blood o
aquaticus ; other entoparasites, such as *Trichonympha* in t
ant,' still possess their mouth. The curious contraction of
stalk of the *Vorticella* (fig. 537), again, is a movement of
nature, being due to the contractility of the tissue tha
the interior of the tubular pedicle. This stalk serves to
bell-shaped body of the animalcule to some fixed object,
leaf or stem of duck-weed ; and when the animal is in
food, with its cilia in active vibration, the stalk is fully
If, however, the animalcule should have drawn to its m
particles too large to be received within it, or should be t
any other that happens to be swimming near it, or
'jarred' by a smart tap on the stage of the microscope,
suddenly contracts into a spiral, from which it shortly
extends itself again into its previous condition. The ce
to whose contractility this action is due, has been de
muscular, though not possessing the characteristic structur
kind of muscular fibre ; it possesses, however, the special i
of muscle, being instantly called into contraction (accord
observations of Kühne) by electrical excitation. The o
'impressionable' organs [1] for the direction of their action
possession of which Infusoria can be credited are th
bristle-like bodies which project in some of them from the
hood of the mouth, and in *Stentor* from various parts of th
The red spots seen in many *Infusoria*, which have been
as eyes by Professor Ehrenberg, from their supposed corre
with the eye-spots of *Rotifera*, really bear a much g
semblance to the red spots which are so frequently se
protophytes. R. Hertwig, who seems to have successfully
himself against the strictures of Professor Vogt, has de
vorticellid—*Erythropsis agilis*—as having a pigment-sp
cannot but be regarded as a rudimentary eye ; Metschni
thinks that *Erythropsis* is an acinetan, found a similar for
similar eye near Madeira ; and Harker has observed that i
allowed to fall on a part only of a colony of *Ophridium ve*
the members soon congregate to the illuminated portion.

The interior of the body does not always seem to co

[1] The term 'organs of sense' implies a *consciousness* of impressions, it is difficult to conceive that unicellular Infusoria can be endowed. The cells of the human body do their work without themselves knowing it.

ided cavity occupied by soft protoplasm ; for the tegu-
er appears in many instances to send prolongations
different directions, so as to divide it into chambers of
ape, freely communicating with each other, which may
ither by protoplasm, or by particles introduced from with-
limentary particles which can be distinguished in the
he transparent bodies of Infusoria are usually proto-
arious kinds, either entire or in a fragmentary state.
aceæ seem to be the ordinary food of many ; and the in-
their *loricæ* enables the observer to recognise them
y. Sometimes entire Infusoria are observed within the
ers not much exceeding them in size (fig. 541, B) ; but
when they have been recently swallowed, since the prey
lergoes digestion. It would seem as if these creatures
by any means indiscriminately, since particular kinds of
attracted by particular kinds of aliment ; the crushed
eggs of Entomostraca, for example, are so voraciously
y the *Coleps* that its body is sometimes quite altered in
e distension. This circumstance, however, by no means
such creatures possess a sense of taste and a power of
selection ; for many instances might be cited in which
he like apparently conscious nature are performed with-
h guidance. The ordinary process of feeding, as well as
nd direction of the ciliary currents, may be best studied
through the water containing the animalcules a few
indigo or carmine. These may be seen to be carried by
vortex into the mouth, and their passage may be traced
distance down a short (usually ciliated) œsophagus.
commonly become aggregated together, so as to form a
of nearly globular form ; and this, when it has attained
the hollow within which it is moulded, seems to receive
ent of firm sarcodic substance, resembling the 'digestive
Noctiluca, and to be then projected into the softer
the interior of the cell, its place in the œsophagus being
other particles subsequently ingested. (This 'moulding,'
s by no means universal, the aggregations of coloured
n the bodies of Infusoria being often destitute of any
of form.) A succession of such pellets being thus intro-
the cell-cavity, a kind of circulation is seen to take place
ior, those that first entered making their way out after
st yielding up their nutritive materials), generally by a
nal orifice, but sometimes by the mouth. When the
thus moving round the body of the animalcule, two of
etimes appear to become fused together, so that they
annot have been separated by any firm membranous in-
When the animalcule has not taken food for some time,
or clear spaces, extremely variable both in size and
led only with a very transparent fluid, are often seen in
asm ; and their fluid sometimes shows a tinge of colour,
ns to be due to the solution of some of the vegetable
l upon which the animalcule may have fed last.

Contractile vesicles (fig. 536, *a*, *a*), usually about the size of the 'vacuoles,' are found, either singly or to the number of from two to sixteen, in the bodies of most ciliated animalcules; and may be seen to execute rhythmical movements of contraction and dilatation at tolerably regular intervals, being so completely obliterated, when emptied of their contents, as to be quite undistinguishable, and coming into view again as they are refilled. These vesicles do not change their position in the individual, and they are pretty constant, both as to size and place, in different individuals of the same species; hence they are obviously quite different in character from the 'vacuoles.' In *Paramecium* there are always to be observed two globular vesicles (fig. 536, B, *a*, *a*), each of them surrounded by several elongated cavities, arranged in a radiating manner, so as to give to the whole somewhat of a star-like aspect, as seen in fig. 538, 1, *v*, *v*; and the liquid contents are seen to be propelled from the former into the latter, and *vice versa*. Further, in *Stentor*, a complicated network of canals, apparently in connection with the contractile vesicles, has been detected in the substance of the 'ectosarc,' and traces of this may be observed in other Infusoria. In some of the larger animalcules it may be distinctly seen that the contractile vesicles have *permanent* valvular orifices opening outwards, and that an expulsion of fluid from the body into the water around it is effected by their contraction; in some vorticellids the contractile vesicle is connected by a canal with the 'vestibule' which lies beneath the mouth opening, and when the vesicle contracts the water is driven into the mouth, and so to the exterior. Hence it appears likely that their function is of a respiratory and depuratory nature; and that they serve, like the gill-openings of fishes, for the expulsion of water which has been taken in by the mouth, and which has traversed the interior of the body.

Of the reproduction of the ciliated Infusoria our knowledge is still very imperfect; for, although various modes of multiplication have been observed among them, it still remains doubtful whether any process takes place that can be regarded, like the conjugation of the *Monadina*, as analogous to the sexual generation of higher organisms. The best evidence is that of Gruber, which will be mentioned directly. Binary subdivision would seem to be universal among them, and has in many instances been observed (as elsewhere) to commence in the nucleus. The division takes place in some species longitudinally, that is, in the direction of the greatest length of the body (fig. 537, D, E, F), in other species transversely (fig. 541, C, D); whilst in some, as in *Chilodon cucullulus* (fig. 539), it has been supposed to occur in either direction indifferently. But it may fairly be questioned whether, in this last case, one set of the apparent 'fissions' is not really 'conjugation' of two individuals. This duplication is performed with such rapidity, under favourable circumstances, that, according to the calculation of Professor Ehrenberg, no fewer than 268 *millions* might be produced in a month by the repeated subdivisions of a single *Paramecium*. When this fission occurs in *Vorticella* (fig. 537), it extends down the stalk, which thus becomes double for a greater or less part of its length; and thus a

whole bunch of these animalcules may spring (by a repetition of the same process) from one base. In some members of the same family arborescent structures are produced resembling that of *Codosiga* (fig. 528) by the like process of continuous subdivision. Another curious result of this mode of multiplication presents itself in the family *Ophrydina*, masses of individuals which separately resemble



FIG. 538.—Sexual (?) reproduction of *Infusoria*.

certain *Vorticellina* being found imbedded in a gelatinous substance of a greenish colour, sometimes adherent and sometimes free. These masses, which may attain the diameter of four or five inches, present such a strong general resemblance to a mass of *Nostoc*, or even of frog's spawn, as to have been mistaken for such; but they simply result from the fact that the multitude of individuals produced by a repetition of the process of self-division remain connected with

each other for a time by a gelatinous exudation from the surface of their bodies, instead of at once becoming completely isolated. From a comparison of the dimensions of the individual *Ophryda*, each of



FIG. 539.—Fissiparous multiplication of *Chilodon cucullulus*: A, B, C, successive stages of longitudinal fission(?); D, E, F, successive stages of transverse fission.

which is about $\frac{1}{120}$th of an inch in length, with those of the composite masses, some estimate may be formed of the number included in the latter; for a cubic inch would contain nearly *eight millions* of them if closely packed; and many times that number must exist in the larger masses, even making allowance for the fact that the bodies of the animalcules are separated from each other by their gelatinous cushion, and that the masses have their central portions occupied by water only. Hence we have, in such clusters, a distinct proof of the extraordinary extent to which multiplication by duplicative subdivision may proceed without the interposition of any other operation. These animalcules, however, free themselves at times from their gelatinous bed, and have been observed to undergo an 'encysting process' corresponding with that of the *Vorticellina*. The chemical composition of this jelly or zoöcytium has been investigated by Halliburton, who finds that it resembles vegetable cellulose in its general properties, but differs from it and agrees with the form of cellulose manufactured by the Tunicata in being less easily converted into sugar.



FIG. 540.—Encysting process in *Vorticella microstoma*: A, full-grown individual in its encysted state; *a*, retracted oval circlet of cilia; *b*, nucleus; *c*, contractile vesicle; B, a cyst separated from its stalk; C, the same more advanced, the nucleus broken up into spore-like globules; D, the same more developed, the original body of the Vorticella, *d*, having become sacculated, and containing many clear spaces; at E, one of the sacculations having burst through the enveloping cyst, a gelatinous mass, *e*, containing the gemmules is discharged.

Many, perhaps all, ciliated Infusoria at certain times undergo an

encysting process, resembling the passage of protophytes into the 'still' condition, and apparently serving like it as a provision for their preservation under circumstances which do not permit the continuance of their ordinary vital activity. Previously to the formation of the cyst, the movements of the animalcule diminish in vigour, and gradually cease altogether; its form becomes more rounded; its oral aperture closes; and its cilia or other filamentous prolongations are either lost or retracted, as is well seen in *Vorticella* (fig. 540, A). A new wreath of cilia, however, is developed near the base, and in this condition the animal detaches itself from its stem, and swims freely for a short time, soon passing, however, into the 'still' condition. The surface of the body then exudes a gelatinous excretion that hardens around it so as to form a complete coffin-like case, within which little of the original structure of the animal can be distinguished. Even after the completion of the cyst, however, the contained animalcule may often be observed to move freely within it, and may sometimes be caused to come forth from its prison by the mere application of warmth and moisture. In the simplest form of the 'encysting process,' indeed, the animalcule seems to remain altogether quiescent through the whole period of its torpidity; so that, however long may be the duration of its imprisonment, it emerges without any essential change in its form or condition. But in other cases this process seems to be subservient either to multiplication or to metamorphosis. For in *Vorticella* the substance of the encysted body (B) appears to break up (C, D) into eight or nine segments, which, when set free by the bursting of the cyst, come forth as spontaneously moving spherules. Each of these soon increases in size, develops a ciliary wreath within which a mouth makes it appearance, and gradually assumes the form of the *Trichodina grandinella* of Ehrenberg. It then develops a posterior wreath of cilia and multiplies by tranverse fission; each half fixes itself by the end on which the mouth is situated, a short stem becomes developed, and the cilia-wreath disappears. A new mouth and cilia-wreath then form at the free extremity, and the growth of the stem completes the development into the true vorticellan form.[1] In *Trichoda lynceus*, again, the 'encysting process' appears subservient to a like kind of metamorphosis, the form which emerges from the cyst differing in many respects from that of the animalcule which became encysted. According to M. Jules Haime, by whom this history was very carefully studied,[2] the form to be considered as the larval one is that shown in fig. 541, A, E, which has been described by Professor Ehrenberg under the name of *Oxytricha*. This possesses a long, narrow, flattened body, furnished with cilia along the greater part of both margins, and having also at its two extremities a set of larger and stronger hair-like filaments; and its mouth, which is an oblique slit on the right-hand side of its fore-part, has a fringe of minute cilia on each lip. Through this mouth large particles are not unfrequently swallowed, which are seen lying in the midst of the

[1] Everts, *Untersuchungen an Vorticella nebulifera*, quoted by Professor Allman, *loc. cit.*

[2] *Annales des Sci. Nat.* ser. iii. tome xix. 1853, p. 109.

endosarc without any surrounding vesicle ; and sometimes even an animalcule of the same species, but in a different stage of its life, is seen in the interior of one of these voracious little devourers (B). In this phase of its existence the *Trichoda* undergoes multiplication by transverse fission, after the ordinary mode (C, D) ; and it is usually one of the short-bodied 'doubles' (E) thus produced that passes into the next phase. This phase consists in the assumption of the globular form and the almost entire loss of the locomotive appendages (F) ; in the escape of successive portions of the granular protoplasm, so that 'vacuoles' make their appearance (G) ; and in the



FIG. 541.—Metamorphoses of *Trichoda lynceus*: A, larva (*Oxytricha*); B, a similar larva after swallowing the animalcule represented at M; C, a very large individual on the point of undergoing fission; D, another in which the process has advanced further; E, one of the products of such fission; F, the same body become spherical and motionless; G, aspect of this sphere fifteen days afterwards; H, later condition of the same, showing the formation of the cyst; I, incipient separation between living substance and exuvial matter; K, partial discharge of the latter, with flattening of the sphere; L, more distinct formation of the confined animal; M, its escape from the cyst; N, its appearance some days afterwards; O, more advanced stage of the same; P, Q, perfect *Aspidiscæ*, one as seen sideways, moving on its bristles, the other as seen from below (magnified twice as much as the preceding figures).

formation of a gelatinous envelope or cyst, which, at first soft, afterwards acquires increased firmness (H). After remaining for some time in this condition, the contents of the cyst become clearly separated from their envelope ; and a space appears on one side, in which ciliary movement can be distinguished (I). This space gradually extends all round, and a further discharge of granular matter takes place from the cyst, by which its form becomes altered (K) ; and the distinction between the newly formed body to which the cilia belong and the effete residue of the old becomes more and more apparent (L). The former increases in size, whilst the latter diminishes ; and at last the former makes its escape through an aperture in the wall of the cyst, a part of the latter still remaining

within its cavity (M). The body thus discharged (N) does not differ much in appearance from that of the Oxytricha before its encystment (F), though of only about two-thirds its diameter; but it soon develops itself (O, P, Q) into an animalcule very different from that in which it originated. First it becomes still smaller by the discharge of a portion of its substance; numerous very stiff bristle-like organs are developed, on which the animalcule creeps, as by legs, over solid surfaces; the external integument becomes more consolidated on its upper surface, so as to become a kind of carapace; and a mouth is formed by the opening of a slit on one side, in front of which is a single hair-like flagellum, which turns round and round with great rapidity, so as to describe a sort of an inverted cone whereby a current is brought towards the mouth. This latter form had been described by Professor Ehrenberg under the name of *Aspidisca*. It is very much smaller than the larva, the difference being, in fact, twice as great as that which exists between A and P, Q (fig. 541), since the last two figures are drawn under a magnifying power double that employed for the preceding. How the *Aspidisca*-form in its turn gives origin to the *Oxytricha*-form has not yet been made out. A similar 'encysting process' has been observed to take place among several other forms of ciliated Infusoria; so that, considering the strong general resemblance in kind and degree of organisation which prevails throughout the group, it does not seem unlikely that it may occur at some stage of the life of nearly all these animalcules. And it is not improbably in the 'encysted' condition that their dispersion chiefly takes place, since they have been found to endure desiccation in this state, although in their ordinary condition of activity they cannot be dried up without loss of life. When this circumstance is taken into account, in conjunction with the extraordinary rapidity of multiplication of these animalcules, there seems no difficulty in accounting for the universality of their diffusion. It may be stated as a general fact that wherever decaying organic matter exists in a liquid state, and is exposed to air and warmth, it speedily becomes peopled with some or other of these minute inhabitants; and it may be fairly presumed that, as in the case of the Fungi, the dried cysts or germs of Infusoria are everywhere floating about in the air, ready to develop themselves wherever the appropriate conditions are presented; while all our knowledge of their history seems further to justify the belief that (in some instances, at least) the same germs may develop themselves into a succession of forms so different as to have been regarded as distinct specific or even generic types.

A very important advance was supposed to have been made in this direction by the asserted discovery of M. Balbiani[1] that a true process of *sexual generation* occurs among Infusoria, his observations having led him to the conclusion that male and female organs are combined in each individual of the numerous genera he has examined, but that the congress of two individuals is necessary for

[1] See his 'Recherches sur les Phénomènes sexuels des Infusoires' in Dr. Brown-Séquard's *Journal de la Physiologie* for 1861. An abstract of these researches is contained in the *Quart. Journ. of Micros. Sci.* for July and October 1862.

the impregnation of the ova, those of each being fertilised by the spermatozoa of the other. He regards the 'nucleus' as an *ovarium* or aggregation of germs, whilst the 'nucleolus' is really a *testis* or aggregation of spermatozoids. The particular form and position which these organs present, and the nature of the changes which they undergo, vary in the several types of Infusoria; but as we have in the common *Paramecium aurelia* an example which, although exceptional in some particulars, affords peculiar facilities for the observation of the process, and has been most completely studied by M. Balbiani, it is here selected for illustration. This animalcule, as is well known, multiplies itself with great rapidity (under favourable circumstances) by duplicative subdivision, which always takes place in the *transverse* direction, and the condition represented in fig. 538, 1, 2, is not, as has been usually supposed, another form of the same process, but is really the sexual congress of two individuals previously distinct. When the period arrives at which the *Paramecia* are to propagate in this manner, they are seen assembling upon certain parts of the vessel, either towards the bottom or on the walls; and they are soon found coupled in pairs, closely adherent to each other, with their similar extremities turned in the same direction, and their two mouths closely applied to each other, but still continuing to move freely in the liquid, turning constantly round upon their axes. This conjugation lasts for five or six days, during which period very important changes take place in the condition of the reproductive organs. In order to distinguish these the animalcules should be slightly flattened by compression, and treated with acetic acid, which brings the reproductive apparatus into more distinct view, as shown in fig. 538, 1–5. In 1 each individual contains an ovarium, *a*, which is shown to present in the first instance a smooth surface; and from this there proceeds an excretory canal or oviduct, *c*, that opens externally at about the middle of the length of the body into the buccal fissure, *e*. Each individual also contains a seminal capsule, *b*, in which is seen lying a bundle of spermatozoids curved upon itself, and which communicates by an elongated neck with the orifice of the excretory canal. The successive stages by which the seminal capsule arrives at this condition from that of a simple cell, whose granular contents resolve themselves (as it were) into a bundle of filaments, are shown in 6–10. In 2 the surface of the ovary, *a*, is seen to present a lobulated appearance, which is occasioned by the commencement of its resolution into separate ova; while the seminal capsule is found to have undergone division into two or four secondary capsules, *b*, *b*, each of which contains a bundle of spermatozoa now straightened out. This division takes place by the elongation of the capsule into the form represented in 11, and by the narrowing of the central portion whilst the extremities enlarge, the further multiplication being effected by the repetition of the same process of elongation and fission. In 3, which represents one of the individuals still in conjugation, the four seminal capsules, *b*, *b*, are represented as thus elongated in preparation for another subdivision; whilst the ovary *a*, *a*, has begun, as it were, to unroll itself, and to break up into

fragments which are connected by the tube *m*. It is in this condition that the object of the conjugation appears to be effected, by the passage of the seminal capsules of each individual, previously to their complete maturation, into the body of the other. In 4 is shown the condition of a *Paramecium* ten hours after the conclusion of the conjugation; the ovary has here completely broken up into separate granular masses, of which some, *a*, *a*, remain unchanged, whilst others, *o*, *o*, *o*, *o*, either two, four, or eight in number, are converted into ovules that appear to be fertilised by the escape of the spermatozoa from the seminal capsules, these being now seen in process of withering. Finally, in 5, which represents a *Paramecium* three days after the completion of the conjugation, are seen four complete ova, *o*, *o*, *o*, *o*, within the connecting tube, *m*, *m*; whilst the seminal capsules have now altogether disappeared. In fig. 538, 13–18, are seen the successive stages of the development of the ovule, which seems at first (13) to consist of a germ-cell having within it a secondary cell containing minute granules, which is to become the 'vitelline vesicle.' This secondary cell augments in size, and becomes more and more opaque from the increase of its granular contents (14, 15, 16), forming the 'vitellus' or yolk, in the midst of which is seen the clear 'germinal vesicle,' which shows on its wall, as the ovule approaches maturity, the 'germinal spot' (17). The germinal vesicle is subsequently concealed (18) by the increase in the quantity and opacity of the vitelline granules. The fertilised ova seem to be expelled by the gradual shortening of the tube that contains them; and this shortening also brings together the scattered fragments of the granular substance of the original ovarium, so as to form a mass resembling that shown in 1, *a*, by the evolution of which, after the same fashion, another brood of ova may be produced. Gruber has recently reinvestigated the process of conjugation in the Infusoria: he finds that the nucleolus of each becomes a striated spindle, and approaches the nucleolus of the other cell; the two touch and finally fuse, thereby effecting an intermixture of the different germ-plasmas. If this be the correct manner of interpreting the phenomenon, it is clearly comparable to the sexual reproduction of multicellular animals.

There can be no doubt as to the occurrence of 'conjugation' among ciliated Infusoria; and this not only in the free-swimming, but also in the attached forms, as *Stentor* (fig. 538, 21). In *Vorticella*, according to several recent observers, what has been regarded as *gemmiparous* multiplication—the putting forth of a bud from the base of the body—is really the conjugation of a small individual in the free-swimming stage with a fully developed fixed individual, with whose body its own becomes fused. But it is doubtful whether such conjugation has any reference to the encysting process. According to Bütschli and Engelmann, the conjugating process results in the breaking up of the nucleus and (so called) nucleolus of the conjugating individuals; these individuals separate again, and after the expulsion of the broken-up nuclear structures the characteristic nucleus and nucleolus are re-formed. The same excellent observers adduce strong grounds for distrusting Balbiani's

assignment of sexual characters to the nucleus and nucleolus. For although a striation may be observed on the surface of the latter, no one has witnessed its subdivision into spermatozoidal filaments. And if embryos are really produced at the expense of the nucleus, what Balbiani described as sexual *ova* are really non-sexual *gemmules*, each consisting (like the zoöspore of protophytes) of a segment of the nucleus surrounded by an envelope of protoplasm. There is still much uncertainty in regard to the embryonic forms of ciliate Infusoria, some eminent observers asserting that the 'gemmule' in the first instance, besides forming a cilia-wreath, puts forth suctorial appendages (fig. 538, 19, A, B, C), by means of which it imbibes nourishment until the formation of its mouth permits it to obtain its supplies in the ordinary way; whilst others maintain these acinetiform bodies to be parasites, which even imbed themselves in the substance of the Infusoria they infest.[1]

It is obvious that no classification of Infusoria can be of any permanent value until it shall have been ascertained by the study of their entire life-history what are to be accounted really distinct forms. And the differences between them, consisting chiefly in the shape of their bodies, the disposition of their cilia, the possession of other locomotive appendages, the position of the mouth, the presence of a distinct anal orifice, and the like, are matters of such trivial importance as compared with those leading features of their structure and physiology on which we have been dwelling that it does not seem desirable to attempt in this place to give any detailed account of them. The life-history of the *ciliate Infusoria* is a subject pre-eminently worthy of the attention of microscopists, who can scarcely be better employed than in tracing out the sequence of its phenomena with similar care and assiduity to that displayed by Messrs. Dallinger and Drysdale in the study of the *Monadina*. 'In pursuing our researches,' say these excellent observers, 'we have become practically convinced of what we have theoretically assumed —the absolute necessity for prolonged and patient observation of the same forms. Two observers, independently of each other, examining the same monad, if their inquiries were not sufficiently prolonged, might, with the utmost truthfulness of interpretation, assert opposite modes of development. Competent optical means, careful interpretation, close observation, and *time* are alone capable of solving the problem.

Section II.—Rotifera, or Wheel-animalcules.

We now come to that higher group of animalcules which, in point of complexity of organisation, is as far removed from the preceding as mosses are from the simplest protophytes, the only point of real resemblance between the two groups, in fact, being the

[1] There can be no doubt that Stein was wrong in his original doctrine that the fully developed *Acinetina* are only transition stages in the development of *Vorticellina* and other ciliated Infusoria. But the balance of evidence seems to the writer to be in favour of his later statement, that the bodies figured in fig. 538, 19, are really infusorian embryos, and not parasitic Acinetæ.

minuteness of size which is common to both. A few species of the wheel-animalcules are marine, or the inhabitants of brackish pools near the sea-shore ; but the great majority known to us belong to fresh water, and are to be found in ditches, ponds, reservoirs, lakes, and slowly running streams—sometimes attached to the leaves and stems of water-plants, sometimes creeping on the Algæ, sometimes swimming freely through the water. They are met with also in gutters on the house-top, in water-butts, on wet moss, grass, and liverworts, in the interior of *Volvox globator* and *Vaucheria*, in vegetable infusions, on the backs of *Entomostraca*, in the viscera of slugs, earth-



FIG. 542.—*Rotifer vulgaris*, as seen at B, with the wheels drawn in, and at A with the wheels expanded : *b*, eye-spots ; *c*, wheels ; *d*, antenna ; *e*, jaws and teeth ; *f*, alimentary canal ; *g*, cellular mass inclosing it ; *h*, longitudinal muscles ; *i*, *i*, tubes of water-vascular system ; *k*, young animal ; *l*, cloaca.

worms and *Naiades*, and in the body-cavities of *Synaptæ*—in fact, in almost every place where there are moisture and food. The wheel-like organs from which the class derives its designation are most characteristically seen in the common *Rotifer* (fig. 542), where they consist of two disc-like lobes or projections of the body whose margins are fringed with long cilia ; and it is the uninterrupted succession of strokes given by these cilia, each row of which nearly returns (as it were) into itself, that gives rise by an optical illusion to the notion of 'wheels.' The disposition of the cilia varies much in the different genera, but it may be said broadly that they are arranged

so as to fulfil three different purposes, viz. to bring food to the mouth, to conduct it through the alimentary canal, and to enable the animal to swim.

The great transparence of the Rotifera permits their general structure to be easily recognised. They have usually an elongated



FIG. 543.—*Brachionus rubens*: *sp*, styligerous prominences; *cw*, coronal wreath; *ts*, tactile styles; *a*, dorsal antenna; *a'*, *a'*, lateral antennæ; *lm*, longitudinal muscles; *œ*, œsophagus; *oy*, ovary; *om*, ovum; *g*, germ; *vt*, vibratile tags; *i*, intestine; *f*, foot; *t*, toes; *gn*, brain; *e*, eye; *mx*, mastax; *ti*, trophi; *gg*, gastric glands; *s*, stomach; *lc*, longitudinal canals; *cv*, contractile vesicle; *cl*, cloaca; *fg*, foot-gland. (After Dr. Hudson.)

form, similar on the two sides; but this rarely exhibits any traces of segmental division. The body is covered with an envelope of two layers. The inner of these is a soft lining to the outer, which may be soft and flexible, or membranous, and of very varying degrees of stiffness, or even of an inflexible substance capable of resisting the

action of caustic potash. In this latter condition it is called a *lorica*. The greater number of the Rotifera have an organ of attachment at the posterior extremity of the body, which is usually prolonged into a tail or false foot, by which they can affix themselves to any solid object; and this is their ordinary position when keeping their 'wheels' in action for a supply of food or of water; they have no difficulty, however, in letting go their hold and moving through the water in search of a new attachment, and may therefore be considered as perfectly free. The sessile species, in their adult stage, on the other hand, remain attached by the posterior extremity to the spot on which they have at first fixed themselves, and their cilia are consequently employed for no other purpose than that of creating currents in the surrounding water.

In considering the internal structure of Rotifera we shall take as its type the arrangement which it presents in *Brachionus rubens* (fig. 543), a common large and handsome animal, and one that bears the temporary captivity of a compressorium remarkably well.



FIG. 544.—Malleate.

ms, malleus { *us*, uncus. *mm*, manubrium.
is, incus { *rs*, ramus. *fm*, fulcrum.

Its vase-shaped *lorica* is hard and transparent; open in front to allow the protrusion of the head, and closed behind, except where a small aperture permits the passage of the foot. The anterior dorsal edge bears six sharp spines, and the ventral edge has a wavy outline. The *head* is shaped like a truncated cone, with the larger end forward, is rounded at each side, and carries on its front surface three protuberances (*sp*), covered with stout vibrating hairs called *styles*. All round the rim of the head runs a row of cilia which on the ventral surface dips down into either side of a ciliated *buccal funnel*. At the bottom of the buccal funnel is the *mastax* (*mx*), a muscular bulb containing the jaws or *trophi* (*ti*). These latter are hard, glassy bodies consisting of two hammer-like pieces called *mallei* (fig. 544) and a third anvil-piece called an *incus*. Each *malleus* (*ms*) is in two parts—the *manubrium* (*mm*), or handle, and the *uncus* (*us*), of five finger-like processes, which unite to form the hammer's head. The *incus* (*is*), or anvil, is formed of two prism-shaped bodies, or *rami* (*rs*), pointed at their free ends, and attached at their broad ends to a thin plate called the *fulcrum* (*fm*), which, seen ventrally or dorsally, looks like a rod. These various parts are connected by muscular fibres, and so acted on by muscles attached to themselves, and to the interior of the mastax, that the unci rise and fall at the same time that the rami open and shut. The food is torn by the unci, crushed by the rami, and then passes between the latter down a short œsophagus (*œ*) into the *stomach* (*s*). This has thick cellular walls, and is lined with cilia, especially at its lower third, which is often divided by a constriction from the upper part, and is often so different in its shape and contents as to merit

the name of an *intestine* (*i*). The lower end of the intestine generally expands into a *cloaca* (*cl*), into which open the ducts of the *ovary* (*oy*), and *contractile vesicle* (*cv*). Just above the mastax, and sometimes just below it, on the œsophagus, are what are supposed to be *salivary glands*; while attached to the upper end of the stomach are two *gastric glands* (*gg*), often possessing visible ducts. There are two further glands (*fg*) in the foot, which is itself a prolongation of the ventral portion of the trunk below the aperture of the cloaca. These foot-glands secrete a viscid substance which is discharged by ducts passing to the tips of the two toes (*t*), and which serves to attach the animal to one spot when it is using its frontal cilia to procure food.

Longitudinal muscles (*lm*) for withdrawing the head and foot within the lorica can be readily seen, and these parts are driven out again by the pressure of transverse muscular fibres acting on the fluids of the body.



FIG. 545.



FIG. 546.—Male: *e*, eye; *lc*, longitudinal canals; *vt*, vibratile tag; *cv*, contractile vesicle; *ss*, sperm-sac; *p*, penis; *f*, foot; *fg*, foot-gland.

On either side of the body is a tortuous tube commencing in a plexus in the head and running down to open on the *contractile vesicle* (*cv*). These tubes bear little *tags* (*vt*), each of which appears to contain a vibrating cilium. The real structure of these bodies is uncertain, and the use of the whole apparatus is much disputed; but the tags are possibly very minutely ciliated funnels, their free ends open to the body-cavity; and it seems probable that the fluids of the body-cavity are conducted through them, along the tortuous tubes, into the contractile vesicle, and are by it discharged into the cloaca. The apparatus would therefore be mainly an excretory one.[1]

The ovary is large and its germs are conspicuous. The animal is oviparous and the huge egg is easily discharged through the oviduct and cloaca owing to the very fluid condition of its contents. It is retained by a thread till hatched at the bottom of the lorica. There

[1] But see Dr. Hudson's Presidential Address, *Journ. of the Royal Micros. Soc.* Feb. 1891, p. 13, in which reasons are given for suspecting that the contractile vesicle may also have a respiratory function, and the vibratile tags and longitudinal canals an excretory one.

are three kinds of eggs: the common soft-shelled eggs, which are large, oval, and produce females; similar soft eggs, which are smaller, more spherical, and produce males; and *ephippial* eggs (fig. 545), with thick cellular coverings, often ornamented with spines. These latter can be dried completely without losing their vitality, and so, lying buried in the mud of dried-up ponds, preserve the species for next year. There is a bilobed *nervous ganglion* (*gn*) between the buccal funnel and the dorsal surface. Above it is the *eye* (*e*)—a refracting sphere on a mass of crimson pigment. From the ganglion pass nerve-threads to a *dorsal antenna* (*a*) and to two *lateral antennæ* (*a'*) on either side of the dorsal surface. These latter organs are rocket-headed terminations of the nervous threads, and have each a bundle of fine hairs passing through a hole in the lorica. The dorsal antenna has a similar bundle and lies sheathed in a tube (fig. 547) which has its base just above the nervous ganglion, and passes thence between the two central anterior spines of the lorica. It is furnished with a muscle, by means of which the bunch of setæ at the free extremity can, by invagination, be drawn within the tube.

FIG. 547.

The *male* (fig. 546) is but a third of the length of the female, and is unlike it in shape. It has a cylindrical trunk, small foot, and flat, round head, surrounded by a simple ring of long cilia. It has no *lorica* nor any *alimentary tract* of any kind, but it has a *nervous system* similar to that of the female, a red eye, and antennæ. Its *excretory* and *muscular* systems are also of the female pattern. The only other internal organ is a large *sperm-sac* (*ss*) ending at its lower extremity in a protrusile, ciliated, hollow *penis* (*p*), whose outlet holds the position of the anus in the female; that is, on the dorsal surface, at the base of the foot.

The Rotifera have been divided by Dr. Hudson and Mr. P. H. Gosse[1] into four orders, according to their powers of locomotion. These are:

1. RHIZOTA (*the rooted*). Fixed when adult.
2. BDELLOIDA (*the leech-like*). That swim with their ciliary wreath, and creep like a leech.
3. PLOÏMA (*the sea-worthy*). That only swim with their ciliary wreath.
4. SCIRTOPODA (*the skippers*). That swim with their ciliary wreath and skip with arthropodous limbs.

The order *Rhizota* contains two families, chiefly differing from each other in the position of the mouth, which in the *Floscullariadæ* (figs. 1 and 2, Plate XV) is central, lying in the body's longer axis, but in the *Melicertadæ* (fig. 3, Plate XV) is lateral. Almost all the species of both families live in gelatinous tubes secreted by themselves, and often fortified in various ways: by *débris* gathered from the water by the action of their ciliary wreaths and showered down at random; by pellets formed in a ciliated cup near the anterior end of the body, and deposited in regular order on the gelatinous tube; or by large fæcal pellets also regularly deposited.

[1] *The Rotifera, or Wheel-animalcules.* Longmans, 1889.

The second order, *Bdelloida* (fig. 7, Plate XV), while having many points in common with the *Melicertadæ*, have a foot peculiarly their own. It has several false joints that can be drawn one within the other like those of a telescope. The corona consists of two nearly circular discs, each surrounded with a double row of cilia, and both of these can be withdrawn into an infolding of the ventral surface at the anterior end of the body, leaving the animal with a long pointed conical head. When the discs are so furled the animal fixes the toes of its foot, elongates the foot and body, catches hold with the furthest point of the conical head, releases the foot, and then, contracting the body and foot while the head remains fixed, draws forward the toes and refixes them, and so *da capo*. It can swim, however, in the usual fashion, with its ciliary wreath. All the species of this order can, under proper circumstances, be dried up into balls, which will retain their vitality for even years, though in a state of utter dustiness. This is due to their secreting round their bodies (after having drawn in both head and foot) a gelatinous covering which retains the body-fluids safe from evaporation.[1] This process takes some time, so that if an attempt is made to dry them on an ordinary glass-slip they simply disintegrate. In a house gutter or in wet moss or sand, where the drying up of the water, in which the Rotifera are, is slowly accomplished, the animals have time to complete their gelatinous coverings before the water fails them. In this order the males have not as yet been discovered.

The third order, *Ploïma*, is divided into a loricate and an illoricate group, which are not, however, very sharply separated ; as in some cases the outer layer of the skin is, though horny, yet thin and flexible. *Brachionus rubens* (fig. 543), which has already been fully described, is a good type of the *loricata*, and *Copeus cerberus* (fig. 6, Plate XV) of the *illoricata*. Most of the species of this order have a forked jointed foot, the fork being formed of two toes varying greatly in size and shape, but all secreting the viscous fluid already mentioned. The great majority of the Rotifera belong to the *Ploïma*.

The fourth order, *Scirtopoda*, contains but one family, *Pedalionidæ*, and has only two genera, *Pedalion* and *Hexarthra*, and each of these has but one known species. *Pedalion* (figs. 4, 5, 8, Plate XV) is an extraordinary creature. Its internal organs are on the usual rotiferous plan, but its body bears no fewer than six hollow limbs, ending in plumes like those of the *Arthropoda*, and worked by pairs of opposing muscles which traverse their entire length. These limbs are arranged round the body, some on the dorsal, some on the ventral surface, and all running parallel to the body's longer axis. In *Hexarthra*, on the contrary, all the limbs are on the ventral surface, and are arranged radiatingly. There is no foot in either Rotiferon : but in *Pedalion* there are two ciliated club-like processes at the posterior extremity, rising above the dorsal surface and secreting a similar viscous fluid to that secreted in the toes of other *Rotifera*.

[1] See Davis in *Monthly Micros. Journ.* vol. ix. 1863, p. 207 ; Slack, at p. 241 of same volume ; and the report of a discussion on the subject at the Royal Microscopical Society, *Journ. of Royal Micros. Soc.* 1887, p. 179.

PLATE XV



West, Newman chromo

Typical Rotifers.

This strange creature was discovered by Dr. C. T. Hudson in a pond near Clifton in 1871; Hexarthra was discovered by Dr. Schmarda in a brackish ditch near the Nile in 1853; their arthropodous limbs give them a strong resemblance to a Nauplius larva, and make it probable that the *Rotifera* will have to be placed between the VERMES and ARTHROPODA.[1]

[1] The following treatises and memoirs) in addition to those already referred to) contain valuable information in regard to the life-history of animalcules and their principal forms:—Ehrenberg, *Die Infusionsthierchen*, Berlin, 1838; Dujardin, *Histoire naturelle des Zoophytes infusoires*, Paris, 1841; Pritchard, *History of Infusoria*, 4th ed. London, 1861 (a comprehensive repertory of information); Stein, *Der Organismus der Infusionsthiere*, Leipzig: Erste Abtheilung, 1859; Zweite Abtheilung, 1867; Dritte Abtheilung, Hälfte I. 1878. Saville Kent's *Manual of the Infusoria*, 1880–1; and Professor Bütschli's *Protozoa* (1880–1) in the new edition of Bronn's Thier-reichs. For the Rhizopoda and Infusoria specially see Claparède and Lachmann, *Études sur les Infusoires et les Rhizopodes*, Geneva, 1858–61; Cohn, in *Siebold und Kölliker's Zeitschrift*, 1851–4 and 1857; Lieberkühn, in *Müller's Archiv*, 1856, and *Ann. of Nat. Hist.* 2nd ser. vol. xviii. 1856; Engelmann, *Zur Naturgeschichte der Infusionsthiere*, 1862; and Professor Bütschli's *Studien über die Conjugation der Infusorien &c.*, 1876. For the Rotifera specially see Leydig, in *Siebold und Kölliker's Zeitschrift*, Bd. vi. 1854; Gosse on Melicerta ringens, in *Quart. Journ. of Micros. Sci.* vol. i. 1853, p. 1; on the Manducatory Organs of Rotifera, *Phil. Trans.* 1856; Huxley on Lacinularia socialis in *Trans. Micros. Soc.* ser. ii. vol. i. 1853, p. 1; Cohn, in *Siebold und Kölliker's Zeitschrift*, Bde. vii. ix. 1856, 1858; Dr. Moxon, *Trans. Linn. Soc.* 1864; Karl Eckstein, *Siebold und Kölliker's Zeitschrift*, 1883; Bourne, *Rotifera*, in the 9th edition of the *Encyclopædia Britannica*; Joliet, 'Monographie des Mélicertes,' *Archiv. zool. expér.* sér. ii. tom. i. p. 131; and Plate, *Jenaische Zeitschr.* xix. p. 1. *The Rotifera, or Wheel-animalcules*, by Hudson and Gosse: Longmans, 1889. Mr. Slack's *Marvels of Pond Life*, 2nd edit. (London, 1871), contains many interesting observations on the habits of Infusoria and Rotifera.

CHAPTER XIV

FORAMINIFERA AND RADIOLARIA

RETURNING now to the lowest or *rhizopod* type of animal life (Chapter XII), we have to direct our attention to two very remarkable series of forms, almost exclusively marine, under which that type manifests itself, all of them distinguished by *skeletons* so consolidated by mineral deposit as to retain their form and intimate structure long after the animals to which they belonged have ceased to live, even for those undefined periods in which they have been imbedded as fossils in strata of various geological ages. In the first of these groups, the *Foraminifera*, the skeleton usually consists of a *calcareous* many-chambered shell, which closely invests the sarcode-body, and which, in a large proportion of the group, is perforated with numerous minute apertures; this shell, however, is sometimes replaced by a 'test,' formed of minute grains of sand cemented together; and there are a few cases in which the animal has no other protection than a membranous envelope. In the second group, the *Radiolaria*, the skeleton is always *silicious* and may be either composed of disconnected spicules, or may consist of a symmetrical open framework, or may have the form of a shell perforated by numerous apertures, which more or less completely incloses the body. The *Foraminifera* probably take, and always have taken, the largest share of any animal group in the maintenance of the solid calcareous portion of the earth's crust by separating from its solution in ocean-water the carbonate of lime continually brought down by rivers from the land. The *Radiolaria* do the same, though in far less measure, for the silex. And both extract from sea-water the organic matter universally diffused through it, converting it into a form that serves for the nutrition of higher marine animals.

SECTION I.—FORAMINIFERA.

The animals of this group belong to that *reticularian* form of the rhizopod type in which—with a differentiation between the containing and the contained sarcodic substance which is involved in the formation of a definite investment—a distinct *nucleus* (sometimes single, in other cases multiple) is probably always present.[1] The shells of Foraminifera are, for the most part, *poly-*

[1] The *absence* of a nucleus was long supposed to be a characteristic of the animals of the *Foraminifera*; and its presence in *Gromia* (first detected by Dr Wallich

halamous, or many-chambered (Plates XVI and XVII), often so strongly resembling those of *Nautilus*, *Spirula*, and other cephalopod molluscs, that it is not surprising that the older naturalists, to whom the structure of these animals was entirely unknown, ranked them under that class. But independently of the entire difference in the character of the animal bodies by which the two kinds of shells are formed, there is a most important distinction between them in regard to the relation of the animal to the shell. For whilst in the chambered shells of the *Nautilus* and other cephalopods the animal is a single individual tenanting only the last formed chamber, and withdrawing itself from each chamber in succession, as it adds to this another and larger one, the animal of a nautiloid foraminifer has a *composite* body, consisting of a number (sometimes very large) of segments,' each repeating the rest, which continues to increase by *gemmation* or budding from the last formed segment. And thus each of the chambers, however numerous they may be, is not only formed, but continues to be occupied by its own segment, which is connected with the segments of earlier and later formation by a continuous stolon' (or creeping stem), that passes through apertures in the *septa* or partitions dividing the chambers. From what we know of the semi-fluid condition of the sarcode-body in the reticularian type, there can be little doubt that there is an incessant circulatory change in the actual substance of each segment; so that the material taken in as food by the segments nearest the surface or margin is speedily diffused through the entire mass. The relation between these 'polythalamous' forms, therefore, and the *monothalamous* or single-chambered, of which we have already had an example in *Gromia*, and of which others will be presently described, is simply that, whereas any buds produced by the latter detach themselves to form separate individuals, those put forth by the former remain in continuity with the parent stock and with each other, so as to form a 'composite' animal and a 'polythalamous' shell.

According to the plan on which the gemmation takes place will be the configuration of the shelly structure produced by the segmented body. Thus, if the bud should be put forth from the aperture of a *Lagena* (Plate XVII, fig. 12) in the direction of the axis of its body, and a second shell should be formed around this bud in continuity with the first; and this process should be successionally repeated, a straight rod-like shell would be produced, whose multiple chambers communicate with each other by the openings that originally constituted their mouths, the mouth of the last-formed chamber being the only aperture through which the protoplasmic body, thus composed of a number of segments connected by a peduncle or 'stolon' of the same material, could now project itself or draw in its food. The successive segments may be all of the same size, or nearly so, in which case the entire rod will approach the cylindrical form, or will resemble a line of beads; but it often

was regarded as differentiating that type from the Foraminifera proper. But the researches of Hertwig and Lesser, F. E. Schulze, Bütschli, and others, having established its presence in several true Foraminifera, and the Author's own observations having confirmed these, its general presence may be fairly assumed.

happens that each segment is somewhat larger than the preceding (fig. 16), so that the composite shell has a conical form, the apex of the cone being the original segment, and its base the one last formed. The method of growth now described is common to a large number of Foraminifera, chiefly belonging to the sub-family *Vodosarina*, but even in that group we have every gradation between the *rectilineal* (fig. 16) and the *spiral* mode of growth (fig. 22); whilst in the genus *Peneroplis* it is not at all uncommon for shells which commence in a spiral to exchange this in a more advanced stage for the rectilineal habit. When the successive segments are added in a spiral direction, the character of the spire will depend in great degree upon the enlargement or non-enlargement of the successively formed chambers; for sometimes it opens out very rapidly, every whorl being considerably broader than that which it surrounds, in consequence of the great excess of the size of each segment over that of its predecessor, as in *Peneroplis*, fig. 548; but more commonly there is so little difference between the successive segments, after the spire has made two or three turns, that the breadth of each whorl scarcely exceeds that of its predecessor, as is well seen in the section of the

FIG. 548.—Foraminifera:—*Peneroplis* and *Orbiculina*.

Rotalia represented in fig. 566. An intermediate condition is presented by *Rotalia*, which may be taken as a characteristic type of a very large and important group of Foraminifera, whose general features will be presently described. Again, a spiral may be either 'nautiloid' or 'turbinoid,' the former designation being applied to that form in which the successive convolutions all lie in one plane (as they do in the Nautilus), so that the shell is 'equilateral' or similar on its two sides; whilst the latter is used to mark that form in which the spire passes obliquely round an axis, so that the shell becomes 'inequilateral,' having a more or less conical form, like that of a snail or a periwinkle, the first formed chamber being at the apex. Of the former we have characteristic examples in *Polystomella* (Plate XVII, fig. 23) and *Nonionina*; whilst of the latter we find a typical representation in *Rotalia Beccarii* (fig. 22). Further, we find among the shells whose increase takes place upon the spiral plan a very marked difference as to the degree in which the earlier convolutions are invested and concealed by the latter. In the great *rotaline* group, whose characteristic form is a turbinoid spiral, all the convolutions are usually visible, at least on one side (fig 17); but among the *nautiloid* tribes it more

Plate XVI.



A TYPICAL GROUP OF FORAMINIFERA

frequently happens that the last-formed whorl encloses the preceding to such an extent that they are scarcely, or not at all, visible externally, as is the case in *Cristellaria* (fig. 17), *Polystomella* (fig. 23), and *Nonionina*. The turbinoid spire may coil so rapidly round an elongated axis that the number of chambers in each turn is very small; thus in *Globigerina* (figs. 20, 21, Plate XVII) there are usually only four; and in *Valvulina* the regular number is only three. Thus we are led to the *biserial* arrangement of the chambers, which is characteristic of the *textularian* group (fig. 8, *a*, *b*, and 9, Plate XVI), in which we find the chambers arranged in two rows, each chamber communicating with that above and that below it on the opposite side, without any direct communication with the



FIG. 549.—*Discorbina globularis* (*Rosalina varians*, Schultze), with its pseudopodia extended.

chamber of its own side, as will be understood by reference to fig. 564, A, which shows a 'cast' of the sarcode-body of the animal. On the other hand, we find in the nautiloid spire a tendency to pass (by a curious transitional form to be presently described) into the *cyclical* mode of growth; in which the original segment, instead of budding forth on one side only, develops *gemmæ* all round, so that a ring of small chambers (or chamberlets) is formed around the primordial chamber, and this in its turn surrounds itself after the like fashion with another ring; and by successive repetitions of the same process the shell comes to have the form of a disc made up of a great number of concentric rings, as we see in *Orbitolites* (fig. 551) and in *Cycloclypeus* (fig. 569).

These and other differences in the *plan of growth* were made by M. D'Orbigny the foundation of his classification of this group, which, though at one time generally accepted, has now been abandoned by most of those who have occupied themselves in the study of the Foraminifera. For it has come to be generally admitted that 'plan of growth' is a character of very subordinate importance among the Foraminifera, so that any classification which is primarily based upon it must necessarily be altogether unnatural, those characters being of primary importance which have an immediate and direct relation to the physiological condition of the animal, and are thus indicative of the real affinities of the several groups which they serve to distinguish. The most important of these characters will now be noticed.[1]

Two very distinct types of shell structure prevail among ordinary Foraminifera—namely, the *porcellanous* and the *hyaline* or *vitreous*. The shell of the former, when viewed by reflected light, presents an opaque-white aspect which bears a strong resemblance to porcelain: but when thin natural or artificial laminæ of it are viewed by transmitted light the opacity gives place to a rich brown or amber colour, which in a few instances is tinged with crimson. No structure of any description can be detected in this kind of shell-substance, which is apparently homogeneous throughout. Although the shells of this 'porcellanous' type often present the appearance of being perforated with foramina, yet this appearance is illusory, being due to a mere 'pitting' of the external surface, which, though often very deep, never extends through the whole thickness of the shell. Some kind of inequality of that surface, indeed, is extremely common in the shells of the 'porcellanous' Foraminifera, one of the most frequent forms of it being a regular alternation of ridges and furrows, such as is occasionally seen in *Miliola*, but which is an almost constant characteristic of *Peneroplis* (fig. 548). But no difference of texture accompanies either this or any other kind of inequality of surface, the raised and depressed portions being alike homogeneous. In the shells of the *vitreous* or *hyaline* type, on the other hand, the proper shell substance has an almost glassy transparence, which is shown by it alike in thin natural lamellæ and in artificially prepared specimens of such as are thicker and older. It is usually colourless, even when (as in the case with many *Rotalinæ*) the substance of the animal is deeply coloured: but in some few species, such as *Globigerina rubra*, *Truncatulina rosea*, and *Polytrema miniaceum*, the shell is commonly, like the animal body, of a more or less deep crimson hue. All the shells of the hyaline type are beset more or less closely with *tubular perforations*, which pass directly, and (in general) without any subdivision, from one surface to the other. These tubuli are in some instances sufficiently coarse for their orifices to be distinguished with a low magnifying power as 'punctations' on the surface of the shell, as is shown in fig. 549: whilst in other cases they are so minute as only to be discernible in

[1] This subject will be found amply discussed in the Author's *Introduction to the Study of the Foraminifera*, published by the Ray Society, to which work he would refer such of his readers as may desire more detailed information in regard to it.

Plate XVII



A TYPICAL GROUP OF FORAMINIFERA



thin sections seen by transmitted light under a higher magnifying power, as is shown in figs. 574, 575. When they are very numerous and closely set, the shell derives from their presence that kind of opacity which is characteristic of all minutely tubular textures, whose tubuli are occupied either by air or by any substance having a refractive power different from that of the intertubular substance, however perfect may be the transparence of the latter. The straightness, parallelism, and isolation of these tubuli are well seen in vertical sections of the thick shells of the largest examples of the group, such as *Nummulites* (fig. 573). It often happens, however, that certain parts of the shell are left unchannelled by these tubuli; and such are readily distinguished, even under a low magnifying power, by the readiness with which they allow transmitted light to pass through them, and by the peculiar vitreous lustre they exhibit when light is thrown obliquely on their surface. In shells formed upon this type we frequently find that the surface presents either bands or spots which are so distinguished, the non-tubular *bands* usually marking the position of the septa, and being sometimes raised into ridges, though in other instances they are either level or somewhat depressed; whilst the non-tubular *spots* may occur on any part of the surface, and are most commonly raised into tubercles, which sometimes attain a size and number that give a very distinctive aspect to the shells that bear them.

Between the comparatively *coarse* perforations which are common in the *rotaline* type, and the *minute* tubuli which are characteristic of the *nummuline*, there is such a continuous gradation as indicates that their mode of formation, and probably their uses, are essentially the same. In the former, it has been demonstrated by actual observation that they allow the passage of pseudopodial extensions of the sarcode-body through every part of the external wall of the chambers occupied by it (fig. 549); and there is nothing to oppose the idea that they answer the same purpose in the latter, since, minute as they are, their diameter is not too small to enable them to be traversed by the finest of the threads into which the branching pseudopodia of Foraminifera are known to subdivide themselves. Moreover, the close approximation of the tubuli in the most finely perforated nummulines makes their collective area fully equal to that of the larger but more scattered pores of the most coarsely perforated rotalines. Hence it is obvious that the *tubulation* or *non-tubulation* of foraminiferal shells is the key to a very important physiological difference between the animal inhabitants of the two kinds respectively; for whilst every segment of the sarcode-body in the former case gives off pseudopodia, which pass at once into the surrounding medium, and contribute by their action to the nutrition of the segment from which they proceed, these pseudopodia are limited in the latter case to the *final* segment, issuing forth only through the aperture of the last chamber, so that all the nutrient material which they draw in must be first received into the last segment, and be transmitted thence from one segment to another until it reaches the earliest. With this difference in the physiological condition of the animal of these two types is usually associated a further

very important difference in the conform
that whilst the aperture of communicatio
and between the last chamber and the exte
in the 'vitreous' shells, serving merely to g
stolon or thread of sarcode from which the
be budded off, it is much wider in the 'porc
give passage to a 'stolon' that may not onl
but may serve as the medium for transm
from the outer to the inner chambers.

Between the highest types of the *porce*
series respectively, which frequently bear
each other in *form*, there are certain other
in *structure*, which clearly indicate their
Thus, for example, if we compare *Orbitoli*
clypeus we recognise the same plan of grow
lets being arranged in concentric rings
chamber; and to a superficial observer th
difference between them. But a minuter
not only is the texture of the shell 'porcell
in *Orbitolites*, whilst it is 'vitreous' and mi
clypeus, but that the partitions between th
in the former, whilst they are *double* in the
the sarcode-body having its own proper sh
over, between these double partitions an a
careous substance is very commonly found
be termed the *intermediate skeleton*; and
peculiar system of inosculating *canals*,
chamberlets in interspaces left between the
titions, and which seem to convey through
of the sarcode-body whose segments occup
occasionally find this 'intermediate skelet
peculiar *outgrowths*, which have no direct r
shell. Of this we have a very curious exam
is in these that we find the 'canal systen
development. Its most regular distribut
Polystomella and in *Operculina*; and an ac
in the description of those types.

Porcellanea.—Commencing, now, with
we shall briefly notice some of its most imp
so related to each other as to constitute but
Its simplest type is presented by the *Corni*
found attached to seaweeds and zoöphytes
shell, of which the interior forms a continu
chambers; the latter portion of the spire is
out, as in *Peneroplis*, so that the form of th
a circle to a long narrow slit. Among the
minifera, and abounding near the shores
some forms of the *miliolinæ* type, so named
some of their minute fossilised forms (of
limestone in the neighbourhood of Paris
posed) to millet-seeds. The peculiar mode o

are characterised will be best understood by examining, in the first instance, the form which has been designated as *Spiroloculina*. This shell is a spiral, elongated in the direction of one of its diameters, and having at each turn a contraction at either end of that diameter which partially divides each convolution into two chambers; the separation between the consecutive chambers is often made more complete by a peculiar projection from the inner side of the cavity, known as the 'tongue' or 'valve,' which may be considered as an imperfect septum. Now it is a very common habit in the milioline type for the chambers of the later convolutions to extend themselves over those of the earlier, so as to conceal them more or less completely; and this they very commonly do somewhat unequally, so that more of the earlier chambers are visible on one side than on the other. *Miliolæ* thus modified (fig. 1, Pl. XVI) have received the names of *Quinqueloculina* and *Triloculina* according to the number of chambers visible externally; but the extreme inconstancy which is found to mark such distinctions, when the comparison of specimens has been sufficiently extended, entirely destroys their value as differential characters, and the term *Miliolina* is now more frequently applied to them collectively. Sometimes, on the other hand, the earlier convolutions are so completely concealed by the later that only the two chambers of the last turn are visible externally; and in this type, which has been designated *Biloculina*, there is often such an increase in the breadth of the chambers as altogether changes the usual proportions of the shell, which has almost the shape of an egg when so placed that either the last or the penultimate chamber faces the observer. It is very common in milioline shells for the external surface to present a 'pitting,' more or less deep, a ridge-and-furrow arrangement (fig. 3), or a honeycomb division; and these diversities have been used for the characterisation of species. Not only, however, may every intermediate gradation be met with between the most strongly marked forms, but it is not at all uncommon to find the surface smooth on some parts, whilst other parts of the surface in the same shell are deeply pitted or strongly ribbed or honeycombed; so that here, again, the inconstancy of these differences deprives them of much of their value as distinctive characters.

An interesting illustration of the tendency to dimorphism amongst the Foraminifera has been observed by MM. Munier Chalmas and Schlumberger[1] in the structure of the shells of this group. They find that while two forms, which they distinguish as form A and form B, are similar externally they differ in internal structure, form B having its initial chamber much smaller than that of form A, and this 'microsphere' is followed by a larger number of chambers than is the 'megasphere' of form A. What this difference signifies it is at present impossible to say, but it has been suggested that it may be one of sexual character. The observations of the French naturalists referred to open out a new field of inquiry, and one which is enjoying the attention of several works in this department of research.

Reverting again to the primitive type presented in the simple

[1] *Bulletin Soc. Geol.* ser. iii. vol. xiii. p. 273.

spiral of *Cornuspira*, we find the most co
it in *Peneroplis* (fig. 548), a very beautiful
not to be found on our own coasts, is one c
Foraminifera in the shore-sands and shall
warmer regions. This is normally a nauti
spire flattens itself out as it advances in
externally by a series of transverse bands,
tion of the internal septa that divide the cav
these chambers communicate with each oth
pores traversing each of the septa, and giv
of sarcode that connect the segments of the
the 'septal plane' closing in the last-formed
row of pores through which the pseudopodia
selves into the surrounding medium. Th
which has a peculiarly 'porcellanous' aspec
set *striæ* that cross the spaces between the
these markings, however, do not indicate in
due to a surface-furrowing of the shelly walls
type passes into two very curious modificat
which, instead of flattening itself out, remai
Nautilus, having only a single aperture,
extensions that subdivide like the branches
name of *Dendritina*, the other having its s
tilineal direction, so that the shell takes th
being distinguished by the name of *Spiroli*
tion of intermediate forms, however, has m
modifications, though ranked as of generic
are merely *varietal*, a continuous gradatio
from the elongated septal plane of the typ
single row of isolated pores, to the arrow
Dendritina, with all its pores fused togeth
dendritic aperture, and a like gradation b
the ordinary forms and the 'spiroline' var
circular septal plane, into which both *Pe*
tend to elongate themselves.

From the ordinary nautiloid multilocul
a more complex and highly developed form
tropical and subtropical regions, but is the
namely, which has received the designatio
The relation of this to the preceding type
by an examination of its earlier stage o
see that the shell resembles that of *Penero*
but that its principal chambers are divide
passing at right angles to the primary into
by sub-segments of the sarcode-body. E
septa is perforated by an aperture, so that
formed, through which (as in fig. 551) th
unites together all the sub-segments of eac
of successive rows alternate with one anot
pores of the principal septa are so disposed
any row normally communicates with two c

adjacent rows. The later turns of the spire very commonly grow completely over the earlier, and thus the central portion or 'umbilicus' comes to be protuberant, whilst the growing edge is thin. The spire also opens out at its growing margin, which tends to encircle the first formed portion, and thus gives rise to the peculiar shape represented in fig. 548, in the illustration on the extreme right, which is the common *aduncal* type of this organism. But sometimes even at an early age the growing margin extends so far round on each side that its two extremities meet on the opposite side of the original spire, which is thus completely enclosed by it; and its subsequent growth is no longer *spiral* but *cyclical*, a succession of *concentric rings* being added, one around the other, as shown in the middle illustration in the same figure. This change is extremely curious, as demonstrating the intimate relationship between the *spiral* and the *cyclical* plans of growth, which at first sight appear essentially distinct. In all but the youngest examples of *Orbiculina* the septal plane presents more than a single row of pores, the number of rows increasing in the thickest specimens to six or eight. This increase is associated with a change in the form of the sub-segments of sarcode from little blocks to columns, and with a greater complexity in the general arrangement, such as will be more fully described hereafter in *Orbitolites*. The largest existing examples of this type are far surpassed in size by those which make up a considerable part of a Tertiary limestone on the Malabar coast of India, whose diameter reaches seven or eight lines.

A very curious modification of the same general plan is shown in *Alveolina*, a genus of which the largest existing forms (fig. 550) are commonly about one-third of an inch long, while far larger specimens are found in the Tertiary limestones of Scinde. Here the spire turns round a very elongate axis, so that the shell has almost the form of a cylinder drawn to a point at each extremity. Its surface shows a series of longitudinal lines which mark the principal septa; and the bands that intervene between these are marked transversely by lines which show the subdivision of the principal chambers into 'chamberlets.' The chamberlets of each row are connected with each other, as in the preceding type, by a continuous gallery; and they communicate with those of the next row by a series of multiple pores in the principal septa, such as constitute the external orifices of the last-formed series, seen on its septal plane at *a*, *a*.

The highest development of that cyclical plan of growth which we have seen to be sometimes taken on by Orbiculina is found in *Orbitolites*; a type which, long known as a very abundant fossil in the earlier Tertiaries of the Paris basin, has lately proved to be scarcely less abundant in certain parts of the existing ocean. The largest recent specimens of it, sometimes attaining the size of a shilling, have hitherto been obtained only from the coast of New Holland, the Fijian reefs, and various other parts of the Polynesian Archipelago; but discs of comparatively minute size and simpler organisation are to be found in almost all foraminiferal sands and dredgings from the shores of the warmer regions of the globe, being especially abundant in those of some of the Philippine Islands, of the

Red Sea, of the Mediterranean, and especially of the Ægean. When such discs are subjected to microscopic examination, they are found (if uninjured by abrasion) to present the structure represented in fig. 551, where we see on the surface (by incident light) a number of rounded elevations, arranged in concentric zones around a sort of



FIG. 550.—*Alveolina Boscii*: *a*, lateral aspect; *b*, terminal aspect; *c*, transverse section of shell.

nucleus (which has been laid open in the figure to show its internal structure); whilst at the margin we observe a row of rounded projections, with a single aperture or pore in each of the intervening depressions. In very thin discs the structure may often be brought into view by mounting them in Canada balsam and transmitting

light through them; but in those which are too opaque to be thus seen through, it is sufficient to rub down one of the surfaces upon a stone, and then to mount the specimen in balsam. Each of the superficial elevations will then be found to be the roof or cover of an ovate cavity or 'chamberlet,' which communicates by means of a lateral passage with the chamberlet on either side of it in the same ring; so that each circular zone of chamberlets might be described as a continuous annular passage dilated into cavities at intervals. On the other hand, each zone communicates with the zones that are internal and external to it by means of passages in a radiating direction; these passages run, however, not from the chamberlets of the inner zone to those of the outer, but from the connecting passages of the former to the chamberlets of the latter; so that the chamberlets of each zone *alternate* in position with those of the zones



FIG. 551.—*Orbitolites.* Ideal representation of a disc of complex type.

internal and external to it. The radial passages from the outermost annulus make their way at once to the margin, where they terminate, forming the 'pores' which (as already mentioned) are to be seen on its exterior. The central nucleus, when rendered sufficiently transparent by the means just adverted to, is found to consist of a 'primordial chamber' (*a*), usually somewhat pear-shaped, that communicates by a narrow passage with a much larger 'circumambient chamber' (*b*), which nearly surrounds it, and which sends off a variable number of radiating passages towards the chamberlets of the first zone, which forms a complete ring round the circumambient chamber.[1]

[1] Although the above may be considered the *typical* form of the Orbitolite, yet, in a very large proportion of specimens, the first few zones are not complete circles, the early growth having taken place from one side only; and there is a very beautiful variety in which this one-sidedness of increase imparts a distinctly *spiral* character to the early growth, which soon, however, gives place to the *cyclical*. In the *Orbitolites italica* (fig. 553), brought up from depths of 1500 fathoms or more, the 'nucleus'

The idea of the nature of the living occupant of these cavities which might be suggested by the foregoing account of their arrangement, is fully borne out by the results of the examination of the sarcode-body, which may be obtained by the maceration in dilute acid (so as to remove the shelly investment) of specimens of *Orbitolites* that have been gathered fresh and preserved in spirit. For this body is found to be composed (fig. 552) of a multitude of segments of sarcode, presenting not the least trace of higher organisation in any part, and connected together by 'stolons' of the like substance. The 'primordial' pear-shaped segment, *a*, is seen to have budded off its 'circumambient' segment, *b*, by a narrow footstalk or stolon; and this circumambient segment, after passing almost entirely round the primordial, has budded off three stolons, which swell into new sub-segments from which the first ring is formed. Scarcely any two specimens are precisely alike as to the mode in which the first ring originates from the 'circumambient segment'; for sometimes a score or more of radial passages extend themselves from every part of the margin of the latter (and this, as corresponding with the plan of growth afterwards followed, is probably the *typical* arrangement); whilst in other cases (as in the example before us) the number of these primary offsets is extremely small. Each zone is seen to consist of an assemblage of ovate sub-segments, whose height (which could not be shown in the figure) corresponds with the thickness of the disc; these sub-segments, which are all exactly similar and equal to one another, are connected by annular stolons; and each zone is connected with that on its exterior by radial extensions of those stolons passing off between the sub-segments.



FIG. 552.—Composite animal of simple type of *Orbitolites complanata*:—*a*, central mass of sarcode; *b*, circumambient segment, giving off peduncles, in which originate the concentric zones of sub-segments connected by annular bands.

The radial extensions of the outermost zone issue forth as pseudopodia from the marginal pores, searching for and drawing in alimentary materials in the manner formerly described; the whole of the soft body, which has no communication whatever with

is formed by three or four turns of a spiral closely resembling that of a *Cornuspira* with an interruption at every half-turn, as in *Spiroloculina*, the growth afterwards becoming purely concentric.

the exterior, save through these marginal pores, being nourished by the transmission of the products of digestion from zone to zone through similar bands of protoplasmic substance. In all cases in which the growth of the disc takes place with normal regularity it is probable that a complete circular zone is added at once. Thus we find this simple type of organisation giving origin to fabrics of by no means microscopic dimensions, in which, however, there is no other differentiation of parts than that concerned in the formation of the shell, every segment and every stolon (with the exception of the two forming the 'nucleus') being, so far as can be ascertained, a precise repetition of every other, and the segments of the nucleus differing from the rest in nothing else than their form. The equality of the endowments of the segments is shown by the fact—of which accident has repeatedly furnished proof—that a small portion of a disc, entirely separated from the remainder, will not only continue



FIG. 553.—Disc of *Orbitolites italica*, Costa, sp. (*O. tenuissima*, Carp.), formed round fragment of previous disc.

to live, but will so increase as to form a new disc (fig. 553), the want of the 'nucleus' not appearing to be of the slightest consequence, from the time that active life is established in the outer zones.

One of the most curious features in the history of this type is its capacity for developing itself into a form which, whilst fundamentally the same as that previously described, is very much more complex. In all the larger specimens of *Orbitolites* we observe that the marginal pores, instead of constituting but a single row, form many rows one above another; and, besides this, the chamberlets of the two surfaces, instead of being rounded or ovate in form, are usually oblong and straight-sided, their long diameters lying in a radial direction, like those of the cyclical type of *Orbiculina*. When a vertical section is made through such a disc, it is found that these oblong chambers constitute two *superficial* layers, between which

are interposed *columnar* chambers of a ro
last are connected together by a complex
arrangement of which will be best understo
of a part of the sarcode-body that occupies t
oblong superficial chambers are occupied by
c c, *d d*, lying side by side, so as to form
each of them disconnected from its neighbo
only by a double footstalk with the two ann
which obviously correspond with the single
(fig. 552). These indirectly connect toget
superficial chamberlets of each zone, but
segments of the intermediate layer ; for th
terminate above and below in the annular st
directly from one to the other, but somet
direct c
another
of the s
of whi
figure)
other b
such a
simple
thus bu
with tw
next in
nates
threads,
outermo
multipl
pores,
pseudop



FIG. 554.—Portion of animal of complex type of *Orbitolites complanata*: *a a'*, *b b'*, the upper and lower rings of two concentric zones; *c c*, the upper layer of superficial sub-segments, and *d d*, the lower layer, connected with the annular bands of both zones; *c c* and *c' c'*, vertical sub-segments of the two zones.

Nov
so differ
describe
first se
separati
complex
But the
examin
of specimens, which ought never to be passed
be appealed to, furnishes these very singula
two forms must be considered as specifically
not only a gradational passage from one to
often combined in the same individual, the
portion of a large disc frequently presentin
the *outer* and later-formed part has developed
2nd, that although the last-mentioned circu
suggest that the change from the one plan t
a feature of advancing age, yet this can
although the complex sometimes evolves i
first (the 'nucleus,' though resembling that

ing out two or more tiers of radiating threads), more frequently the simple prevails for an indefinite number of zones, and then changes itself in the course of a few zones into the complex. No department of natural history could furnish more striking instances than are afforded by the different forms presented by the foraminiferal types now described, of the wide *range of variation* that may occur within the limits of one and the same species ; and the microscopist needs to be specially put on his guard as to this point in respect to the lower types of animal as to those of vegetable life, since the determination of form seems to be far less precise among such than it is in the higher types.[1]

In what manner the reproduction of *Orbitolites* is accomplished, we can as yet do little more than guess ; but from appearances sometimes presented by the sarcode-body, it seems reasonable to infer that *gemmules*, corresponding with the zoöspores of protophytes, are occasionally formed by the breaking up of the sarcode into globular masses, and that these, escaping through the marginal pores, are sent forth to develop themselves into new fabrics.

Arenacea.—In certain forms of the preceding family, and especially in the genus *Miliola*, we not unfrequently find the shells encrusted with particles of sand, which are imbedded in the proper shell-substance. This incrustation, however, must be looked on as (so to speak) accidental, since we find shells that are in every other respect of the same type altogether free from it. A similar accidental incrustation presents itself among certain 'vitreous' and perforate shells ; but there, too, it is usually on a basis of true shell, and the sandy incrustation is often entirely absent. There is, however, a group of Foraminifera in which the true shell is constantly and entirely *replaced* by a sandy envelope, which is distinguished as a 'test,' the arenaceous particles being held together only by a cement exuded by the animal. It is not a little curious that the forms of these arenaceous 'tests' should represent those of many different types among both the 'porcellanous' and the 'vitreous' series ; whilst yet they graduate into one another in such a manner as to indicate that all the members of this 'arenaceous' group are closely related to each other, so as to form a series of their own. And it is further remarkable that while the deep-sea dredgings recently carried down to depths of from 1,000 to 2,500 fathoms have brought up few forms of either 'porcellanous' or 'vitreous' Foraminifera that were not previously known, they have added greatly to our knowledge of the 'arenaceous' types, the number and variety of which far exceed all previous conception. These have been systematically described by Mr. H. B. Brady, F.R.S.[2] whose researches have led him to believe that the long-established division of the Foraminifera into the arenaceous and calcareous groups does

[1] For further information on the subject of *Orbitolites* see the Author's account of the genus in the reports of H.M.S. *Challenger*. Mr. H. B. Brady in his '*Challenger*' *Report* (p. 224) describes a remarkable allied type from the Southern Ocean—*Keramosphæra Murrayi*—in which the test is spherical, and the chambers are arranged in concentric layers.

[2] See his important report on the Foraminifera dredged by H.M.S. *Challenger* (1884), illustrated by 116 plates.



not correspond to any natural arrang
is tolerably constant in many grou
certain sub-families of *Textulariidæ*,
uniform.

In the midst of the sandy mud wh
the warm area of the 'Globigerina mu
a glacial stream flowed, there were fo
varying in size from a large pin's hea
of an aggregation of sand-grains, r
together by a tenacious protoplasmic
open the whole interior was found t
and no trace of any structural arrang
their mass. Hence they might be su
agglomerations were it not for their
type previously described; for, just as
tiation of its homogeneous sarcode,
one of these uniform blendings of sa
of its two components—the sand fo
the sarcode occupying its interior—
rhiza. This type, which abounds on
presents remarkable variations of fo
sometimes stellate, sometimes cervi
arrangement prevails throughout, th
dark-green sarcode, while the 'test' is
sand-grains not held together by any
no definite orifice, so that the pseud
stices between the sand-grains, which
during life with living protoplasm th
the sand-grains after death. These
forms, the 'stellate' varieties rangi
diameter, and the 'cervicorn' to near
larger form was found by Mr. Bra
made it the Faroë Channel (see his '
Syringammina appears, when comple
an inch and a half in diameter; owing
plete absence of cement becomes very
can scarcely support its own weight

More recently another large and
the same group has been obtained
Indian Museum, from the Bay of B
generic name *Masonella*. The test
nearly half an inch in diameter, eit
a central chamber and simple or b
at the periphery.

The purely *arenaceous* Foramini
Brady[3] (by whom they have been

[1] See the description and figures of this
Journ. Micros. Sci. vol. xvi. 1876, p. 221.
[2] *Ann. and Mag. Nat. Hist.* 1889, ser. vi.
[3] See his 'Notes' in *Quart. Journ. of Mi*
vol. xxi. 1881, p. 31.

ilies, the first of which, *Astrorhizida*, includes with the preceding amber of coarse sandy forms, usually of considerable size, and ntially monothalamous, though sometimes imperfectly chambered onstrictions at intervals. Some of the more interesting examples his family will now be noticed, beginning with the *Saccammina* s), which is a remarkably regular type, composed of coarse sand- ns firmly cemented together in a globular form, so as to constitute ll nearly smooth on the outer, though rough on the inner surface, a projecting neck surrounding a circular mouth (fig. 555, *a*, *b*,

This type, which occurs in extraordinary abundance in certain lities (as the entrance of the Christiania fjord, and still further



FIG. 555.—Arenaceous Foraminifera: *a*, *Saccammina spherica*; *b*, the same laid open; *c*, portion of the test, enlarged to show its component sand-grains; *d*, *Pilulina Jeffreysii*; *e*, portion of the test enlarged, showing the arrangement of the sponge-spicules.

rth on the shores of Franz Josef Land), is of peculiar interest m the fact that a closely allied species (*Saccammina Carteri*) is, Mr. H. B. Brady has shown, one of the chief constituents of tain beds of the Lower Carboniferous limestone of the north of gland and elsewhere. In striking contrast to the preceding is other single-chambered type, distinguished by the whiteness of 'test,' to which the Author has given the name of *Pilulina*, from resemblance to a homœopathic 'globule' (fig. 555, *d*, *e*). The m of this is a very regular sphere; and its orifice, instead of ng circular and surrounded by a neck, is a slit or fissure with ghtly raised lips, and having a somewhat S-shaped curvature. It by the structure of its 'test,' however, that it is especially dis- guished; for this is composed of the finest ends of sponge-spicules, y regularly 'laid' so as to form a kind of felt, through the sub- nce of which very fine sand-grains are dispersed. This 'felt' is

somewhat flexible, and its components do r
any kind of cement, as it is not affected b
nitric acid; its tenacity, therefore, see
wonderful manner in which the separate
It is not a little curious that these two for
selves in the same dredging, and that there
difference in the character of their sarcod
preceding case, have a dark-green hue.
(fig. 556, *d*), on the other hand, is somewha
has its two extremities elongated into tub
at the end of each. The materials of the
according to the nature of the bottom wh



Fig. 556.—Arenaceous Foraminifera: *a*, *b*, upper
phragmium globigeriniforme; *c*, *Hormosina*
elongata; *e*, terminal portion, and *f*, middle po
g, *Thurammina papillata*; *h*, portion of its ir

they come up with 'Globigerina mud,' i
abound, whilst sand-grains are scarce, t
made up of the former, which are 'laid' i
the interspaces of which are filled up by fi
they are brought up from a bottom on w
the larger part of the 'test' is made up of
Foraminifera, with here and there a spon
In each case, however, the tubular extens
times forms a sort of proboscis, *e*, nearly
in length) are entirely made up of sponge
with extraordinary regularity. The gen
resembles Saccammina in the structure of
posed of sand-grains very firmly cemented

are of smaller size, and they are so disposed as to present a smooth surface internally, though the exterior is rough. What is most remarkable about this is the geometrical regularity of its form, which is typically triradiate (fig. 557, *c*), the rays diverging at equal angles from the central cavity, and each being a tube (*d*) with an orifice at its extremity. Not unfrequently, however, it is quadriradiate, the rays diverging at right angles; and occasionally a fifth ray presents itself, its radiation, however, being generally in a different plane. The three rays are normally of equal length; but one of them is sometimes shorter than the other two; and when this is the case the angle between the long rays increases at the expense of the other two, so that the long rays lie more nearly in a straight line. Sometimes the place of the third ray is indicated only by a little knob; and then the two long rays have very nearly the same direction. We are thus led to forms in which there is no vestige of a third ray, but merely a single straight tube, with an orifice at each end; and the length of this, which often exceeds half an inch, taken in connection with the abundance in which it presents itself in dredgings in which the triradiate forms are rare, seems to preclude the idea that these long single rods are broken rays of the latter. It is undoubtedly in this group that we are to place the genus *Haliphysema*, which, from constructing its 'test' entirely of sponge-spicules, and even including these in its pseudopodial expansions, has been ranked as a sponge, although observation of it in its living state leaves no doubt whatever of its rhizopodal character.[1]

Lituolida.—The type of this family, which is named after it, is a large, sandy, many-chambered fossil form occurring in the chalk, to which the name *Lituola* was given by Lamarck, from its resemblance in shape to a crosier. A great variety of recent forms, mostly obtained by deep-sea dredging, are now included in it, as bearing a more or less close resemblance to it and to each other in their chambered structure, and in the arrangement of the sand-grains of which their tests are formed. These grains are, for the most part, finer than those of which the tests of the preceding family are constructed, and are set (so to speak) more artistically, and a considerable quantity of a cement exuded by the animal is employed in uniting them. This is often mixed up with sandy particles of extreme fineness to form a sort of 'plaster' with which the exterior of the test is smoothed off, so as to present quite a polished surface. It is remarkable that the cement contains a considerable quantity of oxide of iron, which imparts a ferruginous hue to the 'tests' in which it is largely employed. The forms of the *Lituoline* 'tests' often simulate in a very curious way those of the simpler types of the *vitreous* series. Thus, the long spirally coiled undivided sandy tube of *Ammodiscus* is the isomorph of *Spirillina*. In the genus *Haplophragmium* (fig. 556, *a*, *b*, and Plate XV, fig. 6) we have singular imitations of the Globigerine, Rotaline, and Nonionine types; and in

[1] See Saville Kent in *Ann. of Nat. Hist.* ser. v. vol. ii. 1878; Professor Ray Lankester in *Quart. Journ. Micros. Sci.* vol. xix. 1878, p. 476; and Professor Möbius' *Foraminifera von Mauritius*, 1880.

Thurammina papillata (fig. 556, *g*) a not less remarkable imitation of the Orbuline. This last is specially noteworthy for the admirable manner in which its component sand-grains are set together, these being small and very uniform in size, and being disposed in such a manner as to present a smooth surface both inside and out (fig. 556, *k*), whilst there are at intervals nipple-shaped protuberances, in every one of which there is a rounded orifice. A like perfection of finish is seen in the test of *Hormosina globulifera* (fig. 556, *c*), which is composed of a succession of globular chambers rapidly increasing in size, each having a narrow tubular neck with a rounded orifice, which is received into the next segment. In other species of the same genus there is a nearer approach to the ordinary Nodosarine type, their tests being sometimes constructed with the regularity characteristic of the shells of the true *Nodosaria*, Plate XVII, 16, whilst in other



FIG. 557.—Arenaceous Foraminifera: *a*, *b*, exterior and sectional views of *Rhecophax sabulosa*; *c*, *Rhabdammina abyssorum*; *d*, cross-section of one of its arms; *e*, *Rhecphax scorpiurus*; *f*, *Hormosina Carpenteri*.

cases the chambers are less regularly disposed (fig. 557, *f*), having rather the character of bead-like enlargements of a tube, whilst their walls show a less exact selection of material, sponge-spicules being worked in with the sand-grains, so as to give them a hirsute aspect. A greater rudeness of structure shows itself in the Nodosarine forms of the genus *Rheophax*, in which not only are the sand-grains of the test very coarse, but small Foraminifera are often worked up with them (fig. 557, *e*). A straight, many-chambered form of the same genus (fig. 557, *a*, *b*) is remarkable for the peculiar finish of the neck of each segment; for whilst the test generally is composed of sand-grains, as loosely aggregated as those of which the test of *Astrorhiza* is made up, the grains that form the neck are firmly united by ferruginous cement, forming a very smooth wall to the tubular orifice.

The highest development of the 'arenaceous' type at the present time is found in the forms that imitate the very regular *nautiloid*

shells, both of the 'porcellanous' and the 'vitreous' series; and the most remarkable of these is the *Cyclammina cancellata* (fig. 558), which has been brought up in considerable abundance from depths ranging downwards to 1900 fathoms, the largest examples being found within 700 fathoms. The test (fig. 558, *a*) is composed of aggregated sand-grains firmly cemented together and smoothed over externally with 'plaster,' in which large glistening sand-grains are sometimes set at regular intervals, as if for ornament. On laying open the spire it is found to be very regularly divided into chambers by partitions formed of cemented sand-grains (*b*), a communication between these chambers being left by a fissure at the inner margin of the spire, as in *Operculina* (fig. 570). One of the most curious features in the structure of this type is the extension of the cavity of each chamber into passages excavated in its thick external wall

FIG. 558.—*Cyclammina cancellata*, showing at *a*, its external aspect; *b*, its internal structure; *c*, a portion of its outer wall in section, more highly magnified, showing the sand-grains of which it is built up and the passages excavated in its substance.

each passage being surrounded by a very regular arrangement of sand-grains, as shown at *c*. It not unfrequently happens that the outer layer of the test is worn away, and the ends of the passages then show themselves as pores upon its surface; this appearance, however, is abnormal, the passages simply running from the chamber-cavity into the thickness of its wall, and having (so long as this is complete) no external opening. This 'labyrinthic' structure is of great interest, from its relation not only to the similar structure of the large fossil examples of the same type, but also to that which is presented in other gigantic fossil arenaceous forms to be presently described.

Although some of the nautiloid *Lituolæ* are among the largest of existing Foraminifera, having a diameter of 0·3 inch, they are mere dwarfs in comparison with two gigantic fossil forms, whose

structure has been elucidated by Mr. H. B.
Geologists who have worked over the Gree
have long been familiar with solid sphe
present themselves not unfrequently, varyi
pistol-bullet to that of a small cricket-ball;
them as mineral concretions, others were le
presented by their surfaces to suppose them
A specimen having been fortunately disco
the original structure had remained uncon



FIG. 559.—General view of the internal structure
zontal section, l^1, l^2, l^3, l^4 mark the four thic
sections A marks the internal surface of a laye
fracture; B, the appearance presented by a simil
the radiating processes; C, the result of a t
through the cancellated substance of a lamell
sented by the external surface of a lamella
fracture which has passed through the radial pr
section taken in a radial direction, so as to cross
intervening spaces; c^1, c^2, c^3, c^4, successive char

filtration, it was submitted by Professor M
was at once led by his examination of it to
of the arenaceous group of Foraminifera, t
signation *Parkeria*, in compliment to his val
Mr. W. K. Parker. A section of the s
centre (fig. 559) presents an aspect very mu
Orbitolite, a series of chamberlets being
round a 'nucleus'; and as the same appea
ever be the direction of the section, it bec

[1] See their 'Description of *Parkeria* and *Loftusi*
tions, 1869, p. 721. Though it appears convenient
Parkeria to remain, it must be noted that some of t
are of opinion that *Parkeria* is one of the Stromatopo
group of fossil *Hydroida* (see the memoir by Professo
in 1886 by the Palæontographical Society).

chamberlets, instead of being arranged in successive *rings* on a single plane, so as to form a disc, are grouped in concentric *spheres*, each completely investing that which preceded it in date of formation. The outer wall of each chamberlet is itself penetrated by extensions of the cavity into its substance, as in the *Cyclammina* last described; and these passages are separated by partitions very regularly built up of sand-grains, which also close in their extremities, as is shown in fig. 560. The concentric spheres are occasionally separated by walls of more than ordinary thickness, and such a wall is seen in fig. 559 to close in the last-formed series of chamberlets. But these walls have the same 'labyrinthic' structure as the thinner ones, and an examination of numerous specimens shows that they are not formed at any regular intervals. The 'nucleus' is always composed of a single series of chambers arranged end to end, sometimes in a straight line, as in fig. 559, c^1, c^2, c^3, c^4, sometimes forming a spiral, and in one instance returning upon itself. But the outermost chamber enlarges, and extends itself over the whole 'nucleus,' very much as the 'circumambient' chamber of the Orbitolite extends itself round the primordial chamber; and radial prolongations given off from this in every direction form the first investing sphere, round which the entire series of concentric spheres are successively formed. Of the sand of which this remarkable fabric is constructed about 60 per cent. consists of phosphate of lime, and nearly the whole remainder of carbonate of lime. Another large fossil arenaceous type, constructed upon the same general plan, but growing spirally round an elongated axis, after the manner of *Alveolina* (fig. 550), and attaining a length of three inches, has been described by Mr. H. B. Brady (*loc. cit.*) under the name *Loftusia*, after its discoverer, the late Mr. W. K. Loftus, who brought it from the Turko-Persian frontier, where specimens were found in considerable numbers imbedded in 'a blue marly limestone,' probably of early Tertiary age.



FIG. 560.—Portion of one of the lamellæ of *Parkeria*, showing the sand-grains of which it is built up, and the passages extending into its substance.

There is nothing, it seems to the Author, more wonderful in Nature than the building up of these elaborate and symmetrical structures by mere 'jelly-specks,' presenting no trace whatever of that definite 'organisation' which we are accustomed to regard as necessary to the manifestations of conscious life. Suppose a human mason to be put down by the side of a pile of stones of various shapes and sizes, and to be told to build a dome of these, smooth on both surfaces, without using more than the least possible quantity of a very tenacious but very costly cement in holding the stones together. If he accomplished this well, he would receive credit for great intelligence and skill. Yet this is exactly what these little 'jelly-specks'

do on a most minute scale, the 'tests' they construct, when highly magnified, bearing comparison with the most skilful masonry of man. From *the same sandy bottom* one species picks up the *coarser* quartz-grains, unites them together with a ferruginous cement secreted from its own substance, and thus constructs a flask-shaped 'test,' having a short neck and a single large orifice. Another picks up the *finer* grains and puts them together with the same cement into perfectly spherical 'tests' of the most extraordinary finish, perforated with numerous small pores disposed at pretty regular intervals. Another selects the *minutest* sand-grains and the terminal portions of sponge-spicules and works these up together—apparently with no cement at all, but by the mere 'laying' of the spicules—into perfect white spheres, like homœopathic globules, each having a single fissured orifice. And another, which makes a straight many-chambered 'test,' the conical mouth of each chamber projecting into the cavity of the next, while forming the walls of its chambers of ordinary sand-grains rather loosely held together, shapes the conical mouths of the successive chambers by firmly cementing to each other the quartz-grains which border it. To give these actions the vague designation 'instinctive' does not in the least help us to account for them; since what we want is to discover the *mechanism* by which they are worked out; and it is most difficult to conceive how so artificial a selection can be made by creatures so simple.

Vitrea.—Returning now to the Foraminifera which form true *shells* by the calcification of the superficial layer of their sarcode-bodies, we shall take a similar general survey of the *vitreous* series, whose shells are perforated by multitudes of minute foramina (fig. 549). Thus, *Spirillina* has a minute, spirally convoluted, undivided tube, resembling that of Cornuspira, but having its wall somewhat coarsely perforated by numerous apertures for the emission of pseudopodia. The 'monothalamous' forms of this growth mostly belong to the family *Lagenida*, which also contains a series of transition forms leading up gradationally to the 'polythalamous' nautiloid type. In *Lagena* (Plate XVII, figs. 12, 13, 14, 15) the mouth is narrowed and prolonged into a tubular neck, giving to the shell the form of a microscopic flask: this neck terminates in an everted lip, which is marked with radiating furrows. A mouth of this kind is a distinctive character of a large group of many-chambered shells, of which each single chamber bears a more or less close resemblance to the simple Lagena, and of which, like it, the external surface generally presents some kind of ornamentation, which may have the form either of longitudinal ribs or of pointed tubercles. Thus the shell of *Nodosaria* (Plate XVII, fig. 16) is obviously made up of a succession of lageniform chambers, the neck of each being received into the cavity of that which succeeds it; whilst in *Cristellaria* (fig. 17) we have a similar succession of chambers, presenting the characteristic radiate aperture, and often longitudinally ribbed, disposed in a nautiloid spiral. Between *Nodosaria* and *Cristellaria*, moreover, there is such a gradational series of connecting forms as shows that no essential difference exists between these two types, and it is a fact of no little interest that some of the simpler of these varietal forms,

of which many are to be met with on our own shores, but which are more abundant on those of the Mediterranean and especially of the Adriatic, can be traced backwards in geological time at least as far as the Permian epoch. In another genus, *Polymorphina*, we find the shell to be made up of lageniform chambers arranged in a double series, alternating with each other on the two or more sides of a rectilinear axis; here, again, the forms of the individual chambers, and the mode in which they are set one upon another, vary in such a manner as to give rise to very marked differences in the general configuration of the shell, which are indicated by the name it bears.

Globigerinida.—Returning once again to the simple 'monothalamous' condition, we have in *Orbulina*—a minute spherical shell that presents itself in greater or less abundance in deep-sea dredgings from almost every region of the world—a globular chamber with porous walls, but destitute of any general aperture, the office of which is served by a series of larger pores scattered throughout the wall of the sphere. It has been maintained by some that *Orbulina* is really a detached generative segment of *Globigerina*, with which it is generally found associated. The shell of *Globigerina* consists of an assemblage of nearly spherical chambers (fig. 561), having coarsely



FIG. 561.—*Globigerina bulloides* as seen in three positions.

porous walls, and cohering externally into a more or less regular turbinoid spire, each turn of which consists of four chambers progressively increasing in size. These chambers, whose total number seldom exceeds sixteen, may not communicate directly with each other, but open separately into a common 'vestibule' which occupies the centre of the under side of the spire. This type has recently attracted great attention, from the extraordinary abundance in which it occurs at great depths over large areas of the ocean bottom. Thus its minute shells have been found to constitute no less than 97 per cent. of the 'ooze' brought up from depths of from 1,260 to 2,000 fathoms in the middle of the northern parts of the Atlantic Ocean. The younger shells, consisting of from eight to twelve chambers, are thin and smooth, but the older shells are thicker, their surface is raised into ridges that form a hexagonal areolation round the pores (fig. 562); and this thickening is shown by examination of thin sections of the shell to be produced by an exogenous deposit around the original chamber-wall (corresponding with the 'intermediate skeleton' of the more complex types), which sometimes contains little flask-shaped cavities filled with sarcode—as was first pointed out by Dr. Wallich. But the sweeping of the upper waters

of the ocean by the 'tow-net,' which was systematically carried during the voyage of the 'Challenger,' brought into prominence fact that these waters in all but the coldest seas are inhabited *floating Globigerinæ*, whose shells are beset with multitudes of licate calcareous spines, which extend themselves radially from angles at which the ridges meet to a length equal to four or times the diameter of the shell (fig. 563). Among the bases of t spines the sarcodic substance of the body exudes through the p of the shell, forming a flocculent fringe around it ; and this ext



FIG. 562.—*Globigerina conglobata* (Brady): *a*, *b*, *c*, bottom specimens; *d*, section of shell.

itself on each of the spines, creeping up one side to its extrem and passing down the other with the peculiar flowing movem already described. The whole of this sarcodic extension is at o retracted if the cell which holds the Globigerina receives a sud shock, or a drop of any irritating fluid is added to the water it c tains. It is maintained by Sir Wyville Thomson that the botto deposit is formed by the continual 'raining down' of the Globigeri of the upper waters, which (he affirms) only *live* at or near the s face, and which, when they die, lose their spines and subside. T

Author, however, from his own examination of the Globigerina ooze, is of opinion that the shell forming its surface-layer must *live on the bottom*, being incapable of floating in consequence of their weight; and that if they have passed the earlier part of their lives in the upper waters they drop down as soon as the calcareous deposit continually exuding from the body of each animal, instead of being employed in the formation of new chambers, is applied to the thickening of those previously formed. That many types of Foraminifera *pass their whole lives* at depths of at least 2,000 fathoms is proved, in regard to those forming calcareous shells, by their attachment to stones, corals, &c.; and in the case of the arenaceous types by the fact that they can only procure *on the bottom* the sand of which their 'tests' are made up.



FIG. 563.—*Globigerina*, as captured by tow-net, floating at or near surface.

A very remarkable type has recently been discovered, adherent to shells and corals brought from tropical seas, to which the name *Carpenteria* has been given. This may be regarded as a highly developed form of Globigerina, its first-formed portion having all the essential characters of that genus. It grows attached by the apex of its spire, and its later chambers increase rapidly in size, and are piled on the earlier in such a manner as to form a depressed cone with an irregular spreading base. The essential character of Globigerina—the separate orifice of each of its chambers—is here retained with a curious modification; for the central vestibule into which they all open forms a sort of vent whose orifice is at the apex of the cone, and is sometimes prolonged into a tube that proceeds from it; and the external wall of this cone is so marked out by septal bands that it comes to bear a strong resemblance to a minute *Balanus* (acorn-shell), for which this type was at first mistaken. The principal chambers are partly divided into chamberlets by incomplete partitions, as we shall find them to be in *Eozoön*. The presence of sponge-spicules in large quantity in the chambers of many of the best preserved examples of this type was for some time a source of perplexity; but this was explained by the late Professor Max Schultze,[1] who showed how the pseudopodia of this rhizopod have the habit like those of *Haliphysema* of taking into themselves sponge-spicules, which they draw into the chambers, so that they become incorporated with the sarcode-body. It should be added that Pro-

[1] *Archiv f. Naturgesch.* xxix. 1863, p. 81.

fessor Schultze, with whom Mr. H. J. Carter,[1] Mr. H. B. Brady,[2] a Dr. Goes[3] are in agreement, regard *Carpenteria* as allied to *Polytre* Some interesting observations have been made by Professor Mobi on a large branching and spreading form of *Carpenteria* which recently met with on a reef near Mauritius, and to which he has gi the name of *C. rhaphidodendron*.

A less aberrant modification of the Globigerine type, howeve presented in the two great series which may be designated (after leading forms of each) as the *Textularian* and the *Rotalian*. notwithstanding the marked difference in their respective plan growth, the characters of the individual chambers are the sa their walls being coarsely porous, and their apertures being o semi-oval, or crescent-shaped, sometimes merely fissured. In *Te laria* (Plate XVI, fig. 9) the chambers are arranged biseri along a straight axis, the position of those on the two sides of it b alternate, and each chamber opening into those above and belo on the opposite side by a narrow fissure, as is well shown in s



FIG. 564.—Internal silicious casts representing the forms of the segments o the animals of, A, *Textularia*; B, *Rotalia*.

'internal casts' (fig. 564, A) as exhibit the forms and connectio the segments of sarcode by which the chambers were occupied du life. In the genus *Bulimina* the chambers are so arranged as to f a spire like that of a Bulimus, and the aperture is a curved fis whose direction is nearly transverse to that of the fissure of Te laria: but in this, as in the preceding type, there is an extraordi variety in the disposition of the chambers. In both, moreover, shell is often covered by a sandy incrustation, so that its perforat are completely hidden, and can only be made visible by the remov the adherent crust. And so many cases are now known in w the shell of *Textularinia* is entirely replaced by a sandy test, some systematists prefer to range this group among the *Arenace*

In the *Rotalian* series the chambers are disposed in a turbi spire, opening one into another by an aperture situated on the lo

[1] *Annals and Mag. Nat. Hist.* ser. iv. vols. xvii. xix. xx.
[2] '*Challenger*' *Report*.
[3] *K. Svenska Vet. Handlingar*, xix. No. 4, p. 94.
[4] See his *Foraminifera von Mauritius*, 1880, plates v. vi.

and inner side of the spire, as shown in Plate XVII, fig. 22, the forms and connections of the segments of their sarcode-bodies being shown in such 'internal casts' as are represented in fig. 564, B. One of the lowest and simplest forms of this type is that very common one now distinguished as *Discorbina*. The early form of *Planorbulina* is a Rotaline spire, very much resembling that of *Discorbina*; but this afterwards gives place to a cyclical plan of growth, and in those most developed forms of this type which occur in warmer seas the earlier chambers are completely overgrown by the latter, which are often piled up in an irregular 'acervuline' manner, spreading over the surfaces of shells or clustering round the stems of zoöphytes. In the genus *Tinoporus* there is a more regular growth of this kind, the chambers being piled successively on the two sides of the original median plane, and those of adjacent piles communicating with each other obliquely (like those of *Textularia*) by large apertures, whilst they communicate with those directly above and below by the ordinary pores of the shell. The simple or smooth varieties of this genus forming the sub-genus *Gypsina* present great diversities of shape, with great constancy in their internal structure, being sometimes spherical, sometimes resembling a minute sugar-loaf, and sometimes being irregularly flattened out. The typical form (fig. 565), in which the walls of the piles are thickened at their meeting angles into solid columns that appear on the surface as tubercles, and are sometimes prolonged into spinous outgrowths that radiate from the central mass, is of very common occurrence in shore-sands and shallow-water dredgings on some parts of the Australian coast and among the Polynesian islands. To the simple form of this genus we are probably to refer many of the fossils of the Cretaceous and early Tertiary period that have been described under the name *Orbitolina*, some of which attain a very large size. Globular *Orbitolinæ*, which appear to have been artificially perforated and strung as beads, are not unfrequently found associated with the 'flint-implements' of gravel-beds. Another very curious modification of the Rotaline type is presented by *Polytrema*, which so much resembles a zoöphyte as to have been taken for a minute millepore, but which is made up of an aggregation of 'Globigerine' chambers communicating with each other like those of *Tinoporus*, and differs from that genus primarily in its erect and usually branching manner of growth and the freer communication between its chambers. This, again, is of special interest in relation to *Eozoön*, showing that an indefinite zoöphytic mode of growth is perfectly compatible with truly foraminiferal structure.



Fig. 565.—*Tinoporus baculatus.*

In *Rotalia*, properly so called, we find a marked advance towards the highest type of foraminiferal structure, the partitions that

divide the chambers being in the best developed examples compo
of two laminæ, and spaces being left between them which
passage to a system of canals whose general distribution is sh
in fig. 566. The proper walls of the chambers, moreover,
thickened by an extraneous deposit or 'intermediate skeleton,' wh
sometimes forms radiating outgrowths. This peculiarity of confor
tion, however, is carried much further in the genus *Calcarina*, wh
has been so design
from its resemblance
spur-rowel (fig. 571).
solid club-shaped app
ages with which this
is provided entirely
long to the 'interme
skeleton' *b*, which is q
independent of the ch
bered structure *a*; and
is nourished by a se
canals containing prolo
tions of the sarcode-b
which not only furrow
surface of these appenda
but are seen to trav
their interior when thi
laid open by section,
shown at *c*. In no o
recent foraminifer does
'canal system' attain a
development; and its
tribution in this mir



FIG. 566.—Section of *Rotalia Schrœteriana* near its base and parallel to it, showing, *a*, *a*, the radiating interseptal canals; *b*, their internal bifurcations; *c*, a transverse branch; *d*, tubulated wall of the chambers.

shell, which has been made out by careful microscopic study, affo
a valuable clue to its meaning in the gigantic fossil organ
Eozoön canadense. The resemblance which *Calcarina* bears to
radiate forms of *Tinoporus* (fig. 565), which are often found w
them in the same dredgings, is frequently extremely striking;
in their early growth the two can scarcely be distinguished, si
both commence in a 'Rotaline' spire with radiating appenda
but whilst the successive chambers of *Calcarina* continue to
added on the same plane, those of *Tinoporus* are heaped up in
regular piles.

Certain beds of Carboniferous limestone in Russia are enti
made up, like the more modern Nummulitic limestone, of an agg
gation of the remains of a peculiar type of Foraminifera, to wh
the name *Fusulina* (indicative of its fusiform or spindle-like sha
has been given (fig. 567). In general aspect and plan of growth
so much resembles *Alveolina* that its relationship to that type wo
scarcely be questioned by the superficial observer. But when
mouth is examined it is found to consist of a single slit in
middle of the lip; and the interior, instead of being minut
divided into chamberlets, is found to consist of a regular series
simple chambers; while from each of these proceeds a pair

elongated extensions, which correspond to the 'alar prolongations' of other spirally growing Foraminifera, but which, instead of wrapping round the preceding whorls, are prolonged in the direction of the axis of the spire, those of each whorl projecting beyond those of the preceding, so that the shell is elongated with every increase in its diameter. Thus it appears that in its general plan of growth *Fusulina* bears much the same relation to a symmetrical Rotaline or Nummuline shell that *Alveolina* bears to *Orbiculina*; and this view of its affinities is fully confirmed by the Author's microscopic examination of the structure of its shell. For although the Fusulina limestone of Russia has undergone a degree of metamorphism, which so far obscures the tubulation of its component shells as to prevent him from confidently affirming it, yet the appearances he could distinguish were decidedly in its favour. And having since received from Dr. C. A. White specimens from the Upper Coal Measures of Iowa, U.S.A., which are in a much more perfect state of



FIG. 567.—Section of *Fusulina* limestone.

preservation, he is able to state with certainty, not only that *Fusulina* is tubular, but that its tubulation is of the large coarse nature that marks its affinity rather to the *Rotaline* than to the *Nummuline* series. This type is of peculiar interest as having long been regarded as the oldest form of Foraminifera which was known to have occurred in sufficient abundance to form rocks by the aggregation of its individuals. It will be presently shown, however, that in point both of antiquity and of importance it is far surpassed by another.

Nummulinidæ.—All the most elaborately constructed, and the greater part of the largest, of the 'vitreous' Foraminifera belong to the group of which the well-known Nummulite may be taken as the representative. Various plans of growth prevail in the family; but its distinguishing characters consist in the completeness of the wall that surrounds each segment of the body (the septa being generally double instead of single), the density and fine porosity of the shell-substance, and the presence of an 'intermediate skeleton,'

with a 'canal system' for its nutrition. It is true that ... racters are also exhibited in the highest of the Rotaline ... they are deficient in the genus *Amphistegina*, which co... Nummuline series with the Rotaline; but the occurren... modifications in their border forms is common to other tr... groups. With the exception of *Amphistegina*, all the gen... family are symmetrical in form, the spire being nautiloi... as follow that plan of growth, whilst in those which ... cyclical plan there is a constant equality on the two sid... median plane; but in *Amphistegina* there is a reversio... Rotalian type in the turbinoid form of its spire, as in the ... already specified, although its general conformity to the Nu... type is such as to leave no reasonable doubt as to its ti... placed in this family. Notwithstanding the want of symm... its spire, it accords with *Operculina* and *Nummulites* in h... chambers extended by 'alar prolongations' over each su... the previous whorl; but on the under side these prolongati... almost entirely cut off from the principal chambers, and ar... placed as apparently to alternate with them in position, so ... D'Orbigny, supposing them to constitute a distinct series of ... described its plan of growth as a biserial spire, and made ... character of a separate order.[1]

The existing *Nummulinidæ* are almost entirely restr... tropical climates; but a beautiful little form, *Polystomella* ... the representative of a genus that presents the most regu... complete development of the 'canal system' anywhere ... met with, is common on our own coasts. The peculiar ... marking shown in the figure consists in a strongly ... ridge-and-furrow plication of the shelly wall of each segment ... its posterior margin, the furrows being sometimes so deep ... resemble fissures opening into the cavity of the chamber be... No such openings, however, exist, the only communication ... the sarcode-body of any segment has with the exterior ... either through the fine tubuli of its shelly walls or through ... row of pores that are seen in front view along the inner m... of the septal plane, collectively representing a fissured ape... divided by minute bridges of shell. The meaning of the plicat... the shelly wall comes to be understood when we examine the ... formation of the segments of the sarcode-body, which may be ... in the common *Polystomella crispa* by dissolving away the sh... fresh specimens by the action of dilute acid, but which may be ... studied in such internal casts (fig. 568) of the sarcode-body ... canal system of the large *P. craticulata* of the Australian coa... may sometimes be obtained by the same means from dead ... which have undergone infiltration with ferruginous silicates.[2]

[1] For an account of this curious modification of the Nummuline plan of ... the real nature of which was first elucidated by Messrs. Parker and Rupert ... see the Author's *Introduction to the Study of the Foraminifera* (published ... Ray Society).

[2] It was by Professor Ehrenberg that the existence of such 'casts' in the ... sands of various geological periods (from the Silurian to the Tertiary) w... pointed out, in his memoir 'Ueber den Grünsand und seine Erläuteru...

e segments of the sarcode-body are smooth along their *b*, b^1, but that along their posterior edge, *a*, they are kwards into a set of 'retral processes'; and these pro- ler the ridges of the shell, whilst the shelly wall dips spaces between them, so as to form the furrows seen . The connections of the segments by stolons, *c*, c^1, gh the pores at the inner margin of each septum, are r displayed in such 'casts.' But what they serve most demonstrate is the canal system, of which the distri- most remarkably complete and symmetrical. At *d*, n three turns of a spiral canal which passes along one segments of the like number of convolutions, whilst a canal is found on the side which in the figure is under- wo spires are connected by a set of meridional canals, ı pass down between the two layers of the septa that



nternal cast of *Polystomella craticulata*: *a*, retral processes from the posterior margin of one of the segments; *b*, b^1, smooth argin of the same segment; *c*, c^1, stolons connecting successive nd uniting themselves with the diverging branches of the meri- ıls; *d*, d^1, d^2, three turns of one of the spiral canals; *e*, e^1, e^2, e meridional canals; *f*, f^1, f^2, their diverging branches.

gments; whilst from each of these there passes off rface a set of pairs of diverging branches, *f*, f^1, f^2, which surface along the two sides of each septal band, the ings of those on its anterior margin being in the fur- the retral processes of the next segment. These canals occupied in the living state by prolongations of the and the diverging branches of those of each convolu- mselves, when this is enclosed by another convolution,

ns,' in *Abhandlungen der königl. Akad. der Wissenschaften*, as soon afterwards shown by the late Professor Bailey (*Quart. Journ.* v. 1857, p. 83) that the like infiltration occasionally takes place in ra, enabling similar 'casts' to be obtained from them by the solu- s in dilute acid; the Author, as well as Messrs. Parker and Rupert wards obtained most beautiful and complete internal casts from ra brought from various localities. A number of Greensands yield- rere collected on the 'Challenger' Expedition, the most notable from ralia.

with the stolon processes connecting the successive segments of the latter, as seen at c^1. There can be little doubt that this remarkable development of the canal system has reference to the unusual amount of shell-substance which is deposited as an 'intermediate skeleton' upon the layer that forms the proper walls of the chambers, and



FIG. 569.—*Cycloclypeus*—external surface and vertical and horizontal sections.

which fills up with a solid 'boss' what would otherwise be the depression at the umbilicus of the spire. The substance of this 'boss' is traversed by a set of straight canals, which pass directly from the spiral canal beneath, towards the external surface, where they open in little pits, as is shown in Plate XVII, 23, the umbilical boss in *P. crispa*, however, being much smaller in proportion than it



FIG. 570.—*Operculina* laid open to show its internal structure: *a*, marginal cord seen in cross-section at *a'*; *b*, *b*, external walls of the chambers; *c*, *c*, cavities of the chambers; *c' c'*, their alar prolongations; *d*, *d*, septa divided at *d' d'* and at *d''* so as to lay open the interseptal canals, the general distribution of which is seen in the septa *e*, *e*; the lines radiating from *e*, *e* point to the secondary pores; *g*, *g*, non-tubular columns.

is in *P. craticulata*. There is a group of Foraminifera to which the term *Nonionina* is properly applicable, that is probably to be considered as a sub-genus of *Polystomella*, agreeing with it in its general conformation, and especially in the distribution of its canal system, but differing in its aperture, which is here a single fissure at the inner edge of the septal plane, and in the absence of the 'retral pro-

esses' of the segments of the sarcode-body, the external walls of ıe chambers being smooth. This form constitutes a transition to ıe ordinary Nummuline type, of which *Polystomella* is a more aber- ınt modification.

The Nummuline type is most characteristically represented at the resent time by the genus *Operculina*, which is so intimately united ɔ the true *Nummulite* by intermediate forms that it is not easy to ɐparate the two, notwithstanding that their typical examples are ·idely dissimilar. The former genus (fig. 570) is represented on our wn coast and in northern seas by very small and feeble forms, but ; attains a much higher development in the tropics, where its iameter sometimes reaches one-fourth of an inch. The shell is a attened nautiloid spire, the breadth of whose earlier convolutions ıcreases in a regular progression, but of which the last convolution n full-grown specimens) usually flattens itself out like that of *'eneroplis*, so as to be very much broader than the preceding. The ĸternal walls of the chambers, arching over the spaces between the ɐpta, are seen at *b*, *b* ; and these are bounded at the outer edge of



FIG. 571.—*Calcarina* laid open to show its internal structure : *a*, chambered portion; *b*, intermediate skeleton; *c*, one of the radiating prolongations proceeding from it, with extensions of the canal-system.

ach convolution by a peculiar band, *a*, termed the 'marginal cord.' his cord, instead of being perforated by minute tubuli like those vhich pass from the inner to the outer surface of the chamber-walls vithout division or inosculation (fig. 574), is traversed by a system ɔf comparatively large inosculating passages seen in cross-section at *c'*, and these form part of the canal system to be presently de- ıcribed. The principal cavities of the chambers are seen at *c*, *c* ; vhile the 'alar prolongations' of those cavities over the surface of he preceding whorl are shown at *c'*, *c'*. The chambers are separated ɔy the septa, *d*, *d*, *d*, formed of two laminæ of shell, one belonging ɔo each chamber, and having spaces between them in which lie the 'interseptal canals,' whose general distribution is seen in the septa marked *e*, *e*, and whose smaller branches are seen irregularly divided in the septa *d'*, *d'*, whilst in the septum *d''* one of the principal trunks is laid open through its whole length. At the approach of each septum to the marginal cord of the preceding is seen the narrow fissure which constitutes the principal aperture of communi-

cation between the chambers ; in most of the septa, however, there are also some isolated pores (to which the lines point that radiate from *e*, *e*) varying both in number and position. The interseptal canals of each septum take their departure at its inner extremity from a pair of spiral canals, of which one passes along each side of the marginal cord ; and they communicate at their outer extremity with the canal system of the 'marginal cord,' as shown in fig. 576. The external walls of the chambers are composed of the same finely tubular shell-substance that forms them in the Nummulite ; but, as in that genus, not only are the septa themselves composed of vitreous non-tubular substance, but that which lies over them, continuing them to the surface of the shell, has the same character, showing itself externally in the form sometimes of continuous ridges, sometimes of rows of tubercles, which mark the position of the septa beneath. These non-tubular plates or columns are often traversed by branches of the canal system, as seen at *g*, *g*. Similar columns of non-tubular substance, of which the summits show themselves as tubercles on the surface, are not unfrequently seen between the septal bands, giving a variation to the surface-marking which, taken in conjunction with variations in general conformation, might be fairly held sufficient to characterise distinct species, were it not that on *a comparison of a great number of specimens* these variations are found to be so gradational that no distinct line of demarcation can be drawn between the individuals which present them.

The genus *Nummulites*, though represented at the present time by small and comparatively infrequent examples, was formerly developed to a vast extent, the Nummulitic limestone, chiefly made up by the aggregation of its remains (the material of which the Pyramids are built), forming a band, often 1,800 miles in breadth and frequently of enormous thickness, that may be traced from the Atlantic shores of Europe and Africa, through Western Asia to Northern India and China, and likewise over vast areas of North America (fig. 572). The diameter of a large proportion of fossil Nummulites ranges between half an inch and an inch ; but there are some whose diameter does not exceed $\frac{1}{16}$th of an inch, whilst others attain the gigantic diameter of $4\frac{1}{2}$ inches. Their typical form is that of a double-convex lens ; but sometimes it much more nearly approaches the globular shape, whilst in other cases it is very much flattened ; and great differences exist in this respect among individuals of what must be accounted one and the same species. Although there are some Nummulites which closely approximate *Operculina* in their mode of growth, yet the typical forms of this genus present certain well-marked distinctive peculiarities. Each convolution is so completely invested by that which succeeds it, and the external wall or spiral lamina of the new convolution is so completely separated from that of the convolution it encloses by the 'alar prolongations' of its own chambers (the peculiar arrangement of which will be presently described), that the spire is scarcely if at all visible on the external surface. It is brought into view, however, by splitting the Nummulite through the median plane, which may often be accomplished simply by striking it on one edge, with a hammer, the opposite

edge being placed on a firm support ; or, if this method should not succeed, by heating it in the flame of a spirit-lamp, and then throwing it into cold water or striking it edgeways. Nummulites usually show many more turns, and a more gradual rate of increase in the breadth of the spire, than Foraminifera generally : this will be apparent from an examination of the vertical section shown in fig. 573, which is taken from one of the commonest and most characteristic



Fig. 572.—A, piece of *Nummulitic limestone* from Pyrenees, showing Nummulites laid open by fracture through median plane ; B, *Orbitoides*.

fossil examples of the genus, and which shows no fewer than ten convolutions in a fragment that does not nearly extend to the centre of the spire. This section also shows the complete inclosure of the older convolutions by the newer, and the interposition of the alar prolongations of the chambers between the successive layers of the spiral lamina. These prolongations are variously arranged in different



Fig. 573.—Vertical section of portion of *Nummulites lævigata* : *a*, margin of external whorl ; *b*, one of the outer row of chambers ; *c*, *c*, whorl invested by *a* ; *d*, one of the chambers of the fourth whorl from the margin ; *e*, *e'*, marginal portions of the inclosed whorls ; *f*, investing portions of outer whorl ; *g*, *g*, spaces left between the investing portion of successive whorls ; *h*, *h*, sections of the partitions dividing these.

examples of the genus : thus in some, as *N. distans*, they keep their own separate course, all tending radially towards the centre ; in others, as *N. lævigata*, their partitions inosculate with each other, so as to divide the space intervening between each layer and the next into an irregular network, presenting in vertical section the appearance shown in fig. 573 ; whilst in *N. garansensis* they are broken

up into a number of chamberlets having little or no direct com
cation with each other.

Notwithstanding that the inner chambers are thus so d
buried in the mass of investing whorls, yet there is evidence



FIG. 574.—Portion of a thin section of *Nummulites lævigata* taken in t
direction of the preceding, highly magnified to show the minute struct
of the shell: *a, a*, portions of the ordinary shell-substance traversed
parallel tubuli; *b, b*, portions forming the marginal cord, traversed
diverging and larger tubuli; *c*, one of the chambers laid open; *d, d*,
pillars of solid substance not perforated by tubuli.

the segments of sarcode which they contained were not cut off
communication with the exterior, but that they may have re
their vitality to the last. The shell itself is almost
where minutely porous, being penetrated by parallel tubuli,
pass directly from one surfaco to the other. These tubes are s
as divided lengthwise by a vertical section, in fig. 574, *a, a*;
the appearance they present when cut across in a horizontal s
is shown in fig. 57
transparent shell-sub
a, a, a being closely
with minute punct
which mark their o
In that portion of the
however, which form
margin of each whor
574, *b, b*), the tubes are
and diverge from each
at greater intervals;
is shown by horizontal se
that they communicate
with each other latera
as to form a network s
is seen at *b, b*, fig. 576
certain other points, *d*,
fig. 574, the shell-sub
is not perforated by tub



FIG. 575.—Portion of horizontal section of *Nummulites* showing the structure of the walls and of the septa of the chambers: *a, a, a*, portion of the wall covering three chambers, the punctations of which are the orifices of tubuli; *b, b*, septa between these chambers containing canals which send out lateral branches, *c, c*, entering the chambers by larger orifices, one of which is seen at *d*.

is peculiarly dense in its texture, forming solid pillars which
to strengthen the other parts; and in Nummulites whose su
have been much exposed to attrition, it commonly happens th
pillars of the superficial layer, being harder than the ordinary
substance, and being consequently less worn down, are le

prominences, the presence of which has often been accounted (but erroneously) as a specific character. The successive chambers of the same whorl communicate with each other by a passage left between the inner edge of the partition that separates them and the 'marginal cord' of the preceding whorl: this passage is sometimes a single large broad aperture, but is more commonly formed by the more or less complete coalescence of several separate perforations, as is seen in fig. 573, *b*. There is also, as in *Operculina*, a variable number of isolated pores in most of the septa, forming a secondary means of communication between the chambers. The canal system of *Nummulites* seems to be arranged upon essentially the same plan as that of *Operculina*; its passages, however, are usually more or less obscured by fossilising material. A careful examination will generally disclose traces of them in the middle of the partitions that divide the chambers (fig. 575, *b*, *b*), while from these may be seen to proceed the lateral branches (*c*, *c*), which, after burrowing (so to speak) in the walls of the chambers, enter them by large orifices (*d*). These 'interseptal' canals, and their communication with the inosculating system of passages excavated in the marginal cord, are extremely well seen in the 'internal cast' represented in fig. 576.



FIG. 576.—Internal cast of two of the chambers of *Nummulites striata*, with the network of canals, *b*, in the marginal cord communicating with canals passing between the chambers.

A very interesting modification of the Nummuline type is presented in the genus *Heterostegina* (fig. 577), which bears a very strong resemblance to *Orbiculina* in its plan of growth, whilst in every other respect it is essentially different. If the principal chambers of an *Operculina* were divided into chamberlets by secondary partitions in a direction transverse to that of the principal septa, it would be converted into a *Heterostegina*, just as a *Peneroplis* would be converted by the like subdivision into an *Orbiculina*. Moreover, we see in *Heterostegina*, as in *Orbiculina*, a great tendency to the opening out of the spire with the advance of



FIG. 577.—*Heterostegina*.

age; so that the apertural margin extends round a large part
shell, which thus tends to become discoidal. And it is not a
curious that we have in this series another form, *Cycloclypeus*,
bears exactly the same relation to *Heterosteyina* that *Orbitolite*
to *Orbiculina*, in being constructed upon the *cyclical* plan fro
commencement, its chamberlets being arranged in rings aro
central chamber. This remarkable genus, at present only kno
the recent condition by specimens dredged at considerable
from the coast of Borneo and at one or two points in the W
Pacific, is perhaps the largest of existing Foraminifera, some
mens of its discs in the British Museum having a diameter
and a quarter inches. Notwithstanding the difference of it
of growth, it so precisely accord
the Nummuline type in every
racter which essentially disting
the genus that there cannot
doubt of the intimacy of their
tionship. It will be seen fro
examination of that portion
figure which shows *Cycloclype*
vertical section that the solid
of shell by which the chambere
tion is inclosed are so much th
and consist of so many more la
in the central portion of the
than they do nearer its edge
new lamellæ must be progres
added to the surfaces of th
concurrently with the addition
rings of chamberlets to its m
These lamellæ, however, are
applied one to the other witho
intervening spaces; and they
traversed by columns of non-t
substance, which spring fro
septal bands, and gradually in
in diameter with their approa
the surface, from which they project in the central portion
disc as glistening tubercles.



FIG. 578.—Section of *Orbitoides Fortisii*, parallel to the surface, traversing, at *a*, *a*, the superficial layer, and at *b*, *b*, the median layer.

The Nummulitic limestone of certain localities (as the south
of France, Southern Germany, North-eastern India, &c.) conta
vast abundance of discoidal bodies termed *Orbitoides* (fig. 57
which are so similar to Nummulites as to have been taken for
but which bear a much closer resemblance to *Cycloclypeus*.
are only known in the fossil state; and their structure can o
ascertained by the examination of sections thin enough to be t
lucent. When one of these discs (which vary in size, in diff
species, from that of a fourpenny-piece to that of half a crow
even larger) is rubbed down so as to display its internal organis
two different kinds of structure are usually seen in it, one
composed of chamberlets of very definite form, quadrangular in

species, circular in others, arranged with a general but not constant regularity in concentric circles (figs. 578, 579, *b*, *b*); the other, less transparent, being formed of minuter chamberlets which have no such constancy of form, but which might almost be taken for the



FIG. 579.—Portions of the section of *Orbitoides Fortisii*, shown in fig. 578, more highly magnified: *a*, superficial layer; *b*, median layer.

pieces of a dissected map (*a*, *a*). In the upper and lower walls of these last, minute punctations may be observed, which seem to be the orifices of connecting tubes whereby they are perforated. The relations of these two kinds of structure to each other are made

FIG. 580.—Vertical section of *Orbitoides Fortisii*, showing the large central chamber at *a*, and the median layer surrounding it, covered above and below by the superficial layers.

evident by the examination of a vertical section (fig. 580), which shows that the portion *b*, figs. 578, 579, forms the median plane, its concentric circles of chamberlets being arranged round a large central chamber, as in *Cycloclypeus*; whilst the chamberlets of the portion *a* are irregularly superposed one upon the other, so as to form several layers which are most numerous towards the centre of the disc, and thin away gradually towards its margin. The disposition and connections of the chamberlets of the median layer in *Orbitoides* seem to correspond very closely with those which have been already described as prevailing in *Cycloclypeus*, the most satisfactory indications to this effect being furnished by the silicious 'internal casts' to be met with in certain Greensands, which afford a model of the sarcode-body of the animal. In such a fragment (fig. 581) we recognise the chamberlets of three successive zones, *a*, *a'*, *a''*, each of which seems normally to communicate by one or two passages with the chamberlets of the zone internal and external to its own; whilst between the chamberlets of the same zone there seems to be no direct



FIG. 581.—Internal cast of portion of median plane of *Orbitoides Fortisii*, showing, at *a a*, *a' a'*, *a'' a''*, six chambers of each of three zones, with their mutual communications; and at *b b*, *b' b'*, *b'' b''*, portions of three annular canals.

connection. They are brought into relation, however, by m
of annular canals, which seem to represent the spiral canals o
Nummulite, and of which the 'internal casts' are seen at *b b*,
b'' b''.

A most remarkable fossil, referable to the foraminiferal
has been recently discovered in strata much older than the
earliest that were previously known to contain organic rem
and the determination of its real character may be regarded a
of the most interesting results of microscopic research. This f
which has received the name *Eozoön canadense* (fig. 582), is f
in beds of Serpentine limestone that occur near the base of



FIG. 582.—Vertical section of *Eozoön canadense*, showing alternation of calcareous (light) and serpentinous (dark) lamellæ.

Laurentian formation of Canada, which has its parallel in Europ
the 'fundamental gneiss' of Bohemia and Bavaria, and in the
earliest stratified rocks of Scandinavia and Scotland. These
are found in many parts to contain masses of considerable size,
usually of indeterminate form, disposed after the manner of
ancient coral reef, and consisting of alternating layers—freque
numbering from 50 to 100—of carbonate of lime and serpen
(silicate of magnesia). The regularity of this alternation and
fact that it presents itself also between other calcareous and silic
minerals having led to a suspicion that it had its origin in org
structure, thin sections of well-preserved specimens were submi
to microscopic examination by Dr. (now Sir W.) Dawson, of M

treal, who at once recognised its foraminiferal nature,[1] the *calcareous* layers presenting the characteristic appearances of true *shell*, so disposed as to form an irregularly chambered structure, and frequently traversed by systems of ramifying canals corresponding to those of *Calcarina* ; whilst the *serpentinous* or other silicious layers were regarded by him as having been formed by the infiltration of silicates in solution into the cavities originally occupied by the sarcode-body of the animal—a process of whose occurrence at various geological periods, and also at the present time, abundant evidence has already been adduced. Having himself taken up the investigation (at the instance of Sir William Logan), the Author was not only able to confirm Dr. Dawson's conclusions, but to adduce new and important evidence in support of them.[2] Although this determination has been called in question, on the ground that some resemblance to the supposed organic structure of Eozoön is presented by bodies of purely mineral origin,[3] yet, as it has been accepted not only by most of those whose knowledge of foraminiferal structure gives weight to their judgment (among whom the late Professor Max Schultze may be specially named), but also by geologists who have specially studied the micro-mineralogical structure of the older Metamorphic rocks,[4] the Author feels justified in here describing *Eozoön* as he believes it to have existed when it originally extended itself as an animal growth over vast areas of the sea-bottom in the Laurentian epoch.

Whilst essentially belonging to the Nummuline group, in virtue of the fine tubulation of the shelly layers forming the 'proper wall' of its chambers, *Eozoön* is related to various types of recent Foraminifera in its other characters. For in its indeterminate zoöphytic mode of growth it agrees with *Polytrema* in the incomplete separation of its chambers ; it has its parallel in *Carpenteria* ; whilst in the high development of its 'intermediate skeleton' and of the 'canal system' by which this is formed and nourished, it finds its nearest representative in *Calcarina*. Its calcareous layers were so superposed one upon another as to include between them a succession

[1] This recognition was due, as Dr. Dawson has explicitly stated in his original memoir (*Quart. Journ. of Geol. Soc.* vol. xxi. p. 54), to his acquaintance, not merely with the Author's previous researches on the minute structure of the Foraminifera, but with the special characters presented by thin sections of *Calcarina* which had been transmitted to him by the Author. Dr. Dawson has given an account of the geological and mineralogical relations of *Eozoön*, as well as of its organic structure, in a small book entitled *The Dawn of Life*.

[2] For a fuller account of the results of the Author's own study of *Eozoön*, and of the basis on which the above reconstruction is founded, see his papers in *Quart. Journ. of Geol. Soc.* vol. xxi. p. 59, and vol. xxii. p. 219, and in the *Intellectual Observer*, vol. vii. 1865, p. 278 ; and his 'Further Researches' in *Ann. of Nat. Hist.* June 1874.

[3] See the memoirs of Professors King and Rowney in *Quart. Journ. of Geol. Soc.* vol. xxii. p. 185, and *Ann. of Nat. Hist.* May 1874.

[4] Among these the Author is permitted to mention Professor Geikie, of Edinburgh, who has thus studied the older rocks of Scotland, and Professor Bonney, of London, who has made a like study of the Cornish and other Serpentines. By both these eminent authorities he is assured that they have met with no purely mineral structure in the least resembling *Eozoön*, either in its regular alternation of calcareous and serpentinous lamellæ, or in the dendritic extensions of the latter into the former ; and while they accept as entirely satisfactory the doctrine of its organic origin maintained by the Author, they find themselves unable to conceive of any inorganic agency by which such a structure could have been produced.

of 'storeys' of *chambers* (fig. 583, A^1, A^1, A^2, A^2), the chaml of each 'storey' usually opening one into another, as at *a*, *a*, apartments *en suite*, but being occasionally divided by complete s as at *b*, *b*. These septa are traversed by passages of communica between the chambers which they separate, resembling those wh in existing types, are occupied by *stolons* connecting together segments of the sarcode-body. Each layer of shell consists of finely tubulated or 'Nummuline' lamellæ, B, B, which form boundaries of the chambers beneath and above, serving (so to sp as the *ceiling* of the former, and as the *floor* of the latter; an an intervening deposit of homogeneous shell-substance C, C, wh constitutes the 'in mediate skeleton.' tubuli of this 'N muline' layer (fig. 5 are usually filled up in the Nummul of the 'Nummu limestone') by min infiltration, so as transparent section present a fibrous pearance; but it tunately happens t through their hav in some cases esca infiltration the tu lation is as disti as it is even in rec Nummuline shells (585), bearing a sin lar resemblance in occasional waviness that of the crab's cl The thickness of t interposed layer va considerably in dif



FIG. 583.—Portion of the calcareous shell of *Eozoön canadense* as it would appear if the serpentine that fills its chambers were dissolved away: A^1, A^1, chambers of lower storey opening into each other at *a*, *a*, but occasionally separated by a septum, *b*, *b*; A^2, A^2, chambers of upper storey; B, B, proper walls of the chambers, formed of a finely tubular or Nummuline substance; C, C, intermediate skeleton, occasionally traversed by large stolon-passages, D, connecting the chambers of different storeys, and penetrated by the arborescent systems of canals, E, E, E.

ent parts of the same mass, being in general greatest near base and progressively diminishing towards its upper surfa The 'intermediate skeleton' is occasionally traversed by la passages (D), which seem to establish a connection between successive layers of chambers; and it is penetrated by arboresc systems of canals (E, E), which are often distributed both extensively and so minutely through its substance as to le very little of it without a branch. These canals take their orig not directly from the chambers, but from irregular *lacunæ* interspaces between the outside of the proper chamber-walls a the 'intermediate skeleton,' exactly as in *Calcarina*, the ext sions of the sarcode-body which occupied them having apparen been formed by the coalescence of the pseudopodial filaments th passed through the tubulated lamellæ.

In the fossilised condition in which *Eozoön* is most commonly found, not only the cavities of the chambers, but the canal systems to their smallest ramifications are filled up by the silicious infiltration which has taken the place of the original sarcode-body, as in the cases already cited, and thus when a piece of this fossil is subjected to the action of dilute acid, by which its calcareous portion is dissolved away, we obtain an *internal cast* of its chambers and canal system (fig. 584), which, though altogether dissimilar in *arrangement*, is essentially analogous in *character* to the 'internal casts' represented in figs. 564, 568. This cast presents us, therefore, with a *model* in hard serpentine of the soft sarcode-body which originally occupied the chambers, and extended itself into the ramifying canals, of the calcareous shell; and, like that of *Polystomella*, it affords an even more satisfactory elucidation of the relations of these parts than we could have gained from the study of the living organism.



FIG. 584.—Decalcified portion of *Eozoön canadense* shell, showing the serpentinous *internal cast* of the chambers, canals, and tubuli of the original, presenting an exact model of the animal substance which originally filled them.

We see that each of the layers of serpentine, forming the lower part of such a specimen, is made up of a number of coherent segments, which have only undergone a partial separation; these appear to have extended themselves horizontally without any definite limit; but have here and there developed new segments in a vertical direction, so as to give origin to new layers. In the spaces between these successive layers, which were originally occupied by the calcareous shell, we see the 'internal casts' of the branching canal system, which give us the exact models of the extensions of the sarcode-body that originally passed into them. But this is not all. In specimens in which the Nummuline layer constituting the 'proper wall' of the chambers was originally well preserved, and in which the decalcifying process has been carefully managed (so as not, by too rapid an evolution of carbonic acid gas, to disturb the arrangement of the serpentinous residuum), that layer is represented by a thin white film covering the exposed surfaces of the segments; the superficial aspect

of which, as well as its sectional view, are shown in fig. 584. when this layer is examined with a sufficient magnifying power found to consist of extremely minute needle-like fibres of serpen which sometimes stand upright, parallel, and almost in contact each other, like the fibres of asbestos (so that the film which form has been termed the 'asbestiform layer'), but which are quently grouped in converging brush-like bundles, so as to be close to each other in certain spots at the surface of the film, w widely separated in others. Now these fibres, which are less $\frac{1}{1000}$th of an inch in diameter, are the 'internal casts' of the t of the Nummuline layer (a precise parallel to them being present the 'internal cast' of a *recent Amphistegina* which was in the Aut possession); and their arrangement presents all the varieties w have been mentioned as existing in the shells of *Operculina*.



FIG. 585.—Vertical section of a portion of one of the calcareous lamellæ *Eozoön canadense*: *a a*, Nummuline layer perforated by parallel tubul which show a flexure along the line *a' a'*; beneath this is seen the inter mediate skeleton, *c*, *c*, traversed by the large canals, *b*, *b*, and by obliqu cleavage planes, which extend also into the Nummuline layer.

these delicate and beautiful silicious fibres represent those *pseu podial* threads of sarcode which originally traversed the minu tubular walls of the chambers; and *a precise model* of the ancient animal of which we have any knowledge, notwithstan the extreme softness and tenuity of its substance, is thus prese to us with a completeness that is scarcely even approached in later fossil.

In the upper part of the 'decalcified' specimen shown in fig. it is to be observed that the segments are confusedly heaped toge instead of being regularly arranged in layers, the *lamellated* n of growth having given place to the *acervuline*. This change i no means uncommon among Foraminifera, an irregular pi together of the chambers being frequently met with in the l growth of types whose earlier increase takes place upon some m

more definite plan. After what fashion the *earliest* development of *Eozoön* took place, we have at present no knowledge whatever ; but in a *young* specimen which has been recently discovered it is obvious that each successive 'storey' of chambers was limited by the closing in of the shelly layer at its edges, so as to give to the entire fabric a definite form closely resembling that of a straightened *Peneroplis*. Thus it is obvious that the chief peculiarity of *Eozoön* lay in its capacity for *indefinite extension*, so that the product of a single germ might attain a size comparable to that of a massive coral. Now this, it will be observed, is simply due to the fact that its increase by gemmation takes place *continuously*, the new segments successively budded off remaining in connection with the original stock, instead of detaching themselves from it, as in Foraminifera generally. Thus the little *Globigerina* forms a shell of which the number of chambers does not usually seem to increase beyond *sixteen*, any additional segments detaching themselves so as to form separate shells ; but by the repetition of this multiplication the sea-bottom of large areas of the Atlantic Ocean at the present time has come to be covered with accumulations of *Globigerinæ*, which, if fossilised, would form beds of limestone not less massive than those which have had their origin in the growth of *Eozoön*. The difference between the two modes of increase may be compared to the difference between a herb and a tree. For in the herb the individual organism never attains any considerable size, its extension by gemmation being limited ; though the aggregation of individuals produced by the detachment of its buds (as in a potato-field) may give rise to a mass of vegetation as great as that formed in the largest tree by the continuous putting forth of new buds.

It has been hitherto only in the Laurentian serpentine limestone of Canada that *Eozoön* has presented itself in such a state of preservation as fully to justify the assumption of its organic nature. But from the greater or less resemblance which is presented to this by serpentine-limestones occurring in various localities among strata that seem the geological equivalents of the Canadian Laurentians, it seems a justifiable conclusion that this type was very generally diffused in the earlier ages of the earth's history, and that it had a large (and probably the chief) share in the production of the most ancient calcareous strata, separating carbonate of lime from its solution in ocean water, in the same manner as do the polypes by whose growth coral reefs and islands are being upraised at the present time.

An elaborate work, 'Der Bau des Eozoön Canadense' (1878) has been recently published by Professor Möbius, of Kiel, in which the structure of *Eozoön* is compared with that of various types of Foraminifera, and, as it differs from that of every one of them, is affirmed not to be organic at all, but purely mineral. Upon this the Author would remark, that if the validity of this mode of reasoning be admitted, *any* fossil whose structure does not correspond with that of some existing type is to be similarly rejected. Thus the *Stromatopora* of Silurian and Devonian rocks, which some palæontologists regard as a coral, others as polyzoary, others as a calcareous sponge, and others as foraminifer, would not be a fossil at all, because it differs

from every known living form. Yet the suggestion that it mineral origin would be scouted as absurd by every palæontol Again, it is urged by Professor Möbius that as the supposed system of *Eozoön* has not the constancy and regularity of dist tion which it presents in existing Foraminifera, it must be accou a mineral infiltration. To this the Author would reply—(1) a prolonged and careful study of this 'canal system,' in a variety of modes, with an amount of material at his disposal times greater than Professor Möbius could command, has sati him that in well-preserved specimens the canal system, so far being vague and indefinite, has a very regular plan of distribut (2) that this plan does not differ more from the arrangen characteristic of the several types of existing Foraminifera these differ from each other, its *general* conformity to them such as to satisfy Professor Max Schultze (one of the ablest stu of the group) of its foraminiferal character; and (3) that not does the distribution of the canal system of *Eozoön* differ in ce essential features from every form of mineral infiltration hitl brought to light, but that *canal systems in no respect differing each other in distribution are occupied by different minerals*; a which seems conclusively to point to their *pre-existence* in the careous layers, and the *subsequent* penetration of these minerals the passages previously occupied by sarcode—precisely as happened in those 'internal casts' of existing Foraminifera Professor Möbius altogether ignores.

The argument for the foraminiferal nature of *Eozoön* is essent a *cumulative* one, resting on a number of *independent probabil* no one of which, taken separately, has the cogency of a *proof* the accordance of them all with that hypothesis has an al demonstrative value, no other hypothesis accounting at once fo whole assemblage of facts. As it is the Author's intention t forth this in the best and completest form he can devise, at earliest possible period, he would beg for a *suspension of judgme* the part of those who have credited Professor Möbius with ha completely settled the question, the small amount of evidence tained in his memoir bearing no comparison to that of an opp bearing of which the Author is in possession.[1]

[1] The work, which the death of the Author unfortunately prevented his pul ing himself, will, it is hoped, be before long made accessible to the student unde editorship of Professor Rupert Jones. It is, however, to be noted that Mr. J. W. Gre who has had an opportunity of examining the so-called Tudor specimen of *Eo* communicated to the Geological Society, on March 11, 1891, a paper, of whic following is an abstract:—

After careful examination of all the slides and figures, and after considerati Sir W. Dawson's interpretation, the author is absolutely unable to recognise in specimen any trace of the 'proper wall,' 'canals,' or 'stolon passages' which claimed to occur in *Eozoön*, or any reasons for regarding the calcite bands as 'intermediate skeleton' of a foraminifer. There are points in Sir W. Daw figure which might pass as 'stolon passages,' but they appear very different photograph, and the specimen agrees with the latter. The author, however, reasons for concluding that the case against the organic origin of the Tudor speci does not rest on negative evidence alone; for, though the rock is much contorted, twin lamellæ and cleavage-planes of the calcite are not bent; and the fact that crystalline bands cut across the bedding-planes further shows their secondary ori The rock in which the specimen was found is not 'Lower Laurentian,' and is inclu by Messrs. Selwyn and Vennor in the Huronian.

Collection and Selection of Foraminifera.—Many of the Foraminifera attach themselves in the living state to sea-weeds, zoöphytes, &c.; and they should therefore be carefully looked for on such bodies, especially when it is desired to observe their internal organisation and their habits of life. They are often to be collected in much larger numbers, however, from the sand or mud dredged up from the sea-bottom, or even from that taken from between the tide-marks. In a paper containing some valuable hints on this subject [1] Mr. Legg mentions that, in walking over the Small-mouth Sand, which is situated on the north side of Portland Bay, he observed the sand to be distinctly marked with white ridges, many yards in length, running parallel with the edge of the water; and upon examining portions of these, he found Foraminifera in considerable abundance. One of the most fertile sources of supply that our own coasts afford is the *ooze* of the oyster-beds, in which large numbers of living specimens will be found; the variety of specific forms, however, is usually not very great. In separating these bodies from the particles of sand, mud, &c. with which they are mixed, various methods may be adopted in order to shorten the tedious labour of picking them out one by one under the simple microscope; and the choice to be made among these will mainly depend upon the condition of the Foraminifera, the importance (or otherwise) of obtaining them alive, and the nature of the substances with which they are mingled. Thus, if it be desired to obtain *living* specimens from the oyster-ooze for the examination of their soft parts, or for preservation in an aquarium, much time will be saved by stirring the mud (which should be taken from the surface only of the deposit) in a jar with water, and then allowing it to stand for a few moments; for the finer particles will remain diffused through the liquid, while the coarser will subside; and, as the Foraminifera (in the present case) will be among the *heavier*, they will be found at the bottom of the vessel with comparatively little extraneous matter, after this operation has been repeated two or three times. It would always be well to examine the first deposit let fall by the water that has been poured away, as this may contain the smaller and lighter forms of Foraminifera. But supposing that it be only desired to obtain the *dead* shells from a mass of sand brought up by the dredge, a very different method should be adopted. The whole mass should be exposed for some hours to the heat of an oven, and be turned over several times, until it is found to have been thoroughly dried throughout; and then, after being allowed to cool, it should be stirred in a large vessel of water. The chambers of their shells being now occupied by air alone (for the bodies of such as were alive will have shrunk up almost to nothing), the Foraminifera will be the *lightest* portion of the mass; and they will be found floating in the water, while the particles of sand &c. subside. Another method, devised by Mr. Legg, consists in taking advantage of the relative sizes of different kinds of Foraminifera and of the substances that accompany them. This, which is especially applicable to the mud and rubbish obtainable from sponges (which may be got in

[1] *Trans. of Micros. Soc.* ser. ii. vol. ii. 1854, p. 19.

large quantity from the sponge-merchants), consists in sifting whole aggregate through successive sieves of wire-gauze, commen with one of ten wires to the inch, which will separate large extran particles, and proceeding to those of twenty, forty, seventy, and wires to the inch, each (especially that of seventy) retaining a n larger proportion of foraminiferal shells than of the accompan particles; so that a large portion of the extraneous matter being got rid of, the final selection becomes comparatively easy. Ce forms of Foraminifera are found attached to shells, especially biv (such as the *Chamida*) with foliated surfaces; and a careful ex nation of those of tropical seas, when brought home 'in the r is almost sure to yield most valuable results. The final selecti specimens for mounting should always be made under some approp form of single microscope, a fine camel-hair pencil, with the wetted between the lips, being the instrument which may be most veniently and safely employed, even for the most delicate speci In mounting Foraminifera as microscopic objects the method adopted must entirely depend upon whether they are to be vi by *transmitted* or by *reflected* light. In the former case they sl be mounted in Canada balsam, the various precautions to pr the retention of air-bubbles, which have been already described, carefully observed. In the latter no plan is so simple, easy, effectual as attaching them with a little gum to wooden s They should be fixed in various positions, so as to presen the different aspects of the shell, particular care being that its mouth is clearly displayed; and this may often be readily managed by attaching the specimen *sideways* to the w the circular depression of the slide. Or the specimens ma attached to discs fitted for being held in a disc-holder; whils the examination of specimens in every variety of position. M Beck's disc-holder will be found extremely convenient. Whe will often happen, the several individuals differ considerably one another, special care should be taken to arrange them in illustrative of their range of variation and of the mutual connec of even the most diverse forms. For the display of the int structure of Foraminifera it will often be necessary to make extre thin sections, in the manner already described; and much time be saved by attaching a number of specimens to the glass sli once and by grinding them down together. For the preparati sections, however, of the extreme thinness that is often req those which have been thus reduced should be transferre separate slides and finished off each one by itself.

Section II.—Radiolaria.

It has been shown that one series of forms belonging to *rhizopod* type is characterised by the *radiating* arrangement of t rod-like *pseudopodia*, suggesting the designation *Heliozoa* or ' animalcules'; and that even among those fresh-water forms tha not depart widely from the common *Actinophrys* there are s whose bodies are enclosed in a complete silicious skeleton. just as the reticularian type of rhizopod life culminates in the ma

eous-shelled *Foraminifera*, so does the heliozoic type seem to nate in the marine *Radiolaria*; which, living for the most ear the surface of the ocean, form *silicious* skeletons (often of llous symmetry and beauty) that fall to the bottom on the of the animals that produced them, and may remain unchanged, hose of the diatoms, through unlimited periods of time. Some se skeletons, mingled with those of diatoms, had been detected ofessor Ehrenberg in the midst of various deposits of foramini- origin, such as the calcareous Tertiaries of Sicily and Greece, f Oran in Africa; and he established for them the group of



o. 586.—Fossil *Radiolaria* from Barbadoes: *a, Podocyrtis mitra*; *b, Rhabdolithus sceptrum*; *c, Lychnocanium falciferum*; *d, Eucyrtidium tubulus*; *e, Flustrella concentrica*; *f, Lychnocanium lucerna*; *g, Eucyrtidium elegans*; *h, Dictyospyris clathrus*; *i, Eucyrtidium Mongolfieri*; *k, Stephanolithis spinescens*; *l, S. nodosa*; *m, Lithocyclia ocellus*; *n, Cephalolithis sylvina*; *o, Podocyrtis cothurnata*; *p, Rhabdolithus pipa*.

ystina, to which he was able also to refer a beautiful series of making up nearly the whole of a silicious sandstone prevail- rough an extensive district in the island of Barbadoes (fig. 586). ing, however, was known of the nature of the animals that d them until they were discovered and studied in the living state rofessor J. Müller,[1] who established the group of *Radiolaria*,

Ueber die *Thalassicollen, Polycystinen*, und *Acanthometren* des Mittel-,' in *Abhandlungen der königl. Akad. der Wissensch. zu Berlin*, 1858, and ely published; also 'Ueber die im Hafen von Messina beobachteten *Poly-n*,' in the *Monatsberichte* of the Berlin Academy for 1855, pp. 671–676.

including therein, with the *Polycystina* of Ehrenberg, the *Acanthometrina* first recognised by himself, and the *Thalassicolla* which been discovered by Professor Huxley. Not long afterwards appeared the magnificent and 'epoch-making' work of Professor Haeckel[1], and since that time much has been added by various observers to our knowledge of this group, which still remains, however, very imperfect.

Each individual radiolarian consists of two portions of colourless or colourless sarcode—one portion nucleated and central, the other portion peripheral, and almost always containing certain yellow corpuscles. These two portions are separated by a membrane called the *capsule*; but this is so porous as to allow of their free communication with each other. The inner central capsule is also the s



FIG. 587.—Polycystina: A, *Haliomma hystrix*; B, *Pterocanium*, with ani

organ of reproduction, for it is the intracapsular protoplasm, with the nuclei imbedded in it, which serves for the formation of flagellate spores; the outer capsule has the special office of protecting and providing nourishment for the cell. The *pseudopodia* radiate in all directions (fig. 587) from the deeper portion of the extracapsular sarcode; they have generally much persistency of direction and little flexibility; in some species (but not ordinarily) they branch and anastomose, while in others they are inclosed in hollow rods that form part of the silicious skeleton, and issue forth from the extremities of these. A flow of granules takes place along them; and the mode in which they obtain food-particles (consi

[1] *Die Radiolarien* (Rhizopoda Radiaria), Berlin, 1862. This great work lately been followed by a gigantic monograph published in the '*Challenger*' *Re* which extends over 1800 pages, and is illustrated by 140 plates. In it are desc 4318 species, of which 3508 are new to science.

of diatoms and other minute algæ, marine infusoria, &c.), and draw them into the sarcode-bodies of the radiolarians, appears to correspond entirely with their action in *Actinophrys* and other Heliozoa. The yellow cells, or *Zoöxanthellæ*, as K. Brandt has proposed to call them, so often seen in these cells, are not confined to Radiolaria, for they are found also in Actiniæ and various other invertebrates; nor are they always present in examples studied; they are now completely recognised[1] as algæ which form a 'symbiotic' relation with their host, the animal profiting by the removal of its waste products by its messmate, by the oxygen which its guest evolves in sunlight, and by the food-material it provides after death, while the plant feeds on the waste of the animal.

In most *Radiolaria* skeletal structures are developed in the sarcode-body, either inside or outside the capsule, or in both positions; sometimes in the form of investing networks having more or less of a *spheroidal* form (fig. 589, 1, 2), or of *radiating* spines, 3, or of combinations of these, 4, 5. But in many cases the skeleton consists only of a few scattered spicules; and this is especially the case in certain large composite forms or 'colonies' (fig. 594) which may consist of as many as a thousand zoöids, aggregated together in various forms, discoidal, cylindrical, spheroidal, chain-like, or even necklace-like. The 'colonies' seem to be produced, like the multiple segments of the bodies of Foraminifera, by the non-sexual multiplication of a primordial zoöid; but whether this multiplication takes place by fission, or by the budding off of portions of the sarcode-body, has not yet been clearly made out. The emission of flagellated zoöspores, provided with a very large nucleus, and in some cases with a rod-like crystal, has been observed in many radiolarians; but of the mode in which they are produced, and of their subsequent history, very little is at present known. Until the structure and life-history of the animals of this very interesting type shall have been more fully elucidated, no satisfactory classification of them can be framed; and nothing more will be here attempted than to indicate some of the principal forms under which the radiolarian type presents itself.[2]



FIG. 588.—Polycystina: A, *Podocyrtis Schomburgkii*; B, *Rhopalocanium ornatum*.

[1] See especially K. Brandt, *Verhandl. Physiol. Gesellsch.* Berlin, 1881–82, p. 22; *Mitth. Zool. Stat. Neapel*, iv. p. 191; P. Geddes, *Nature*, xxv. p. 303.

[2] Considerable attention has been given to the question of the classification of the Radiolaria by Haeckel and by R. Hertwig, *Jenaische Denkschr.* ii. 1879, p. 129.

Discida.—Among the beautiful silicious structures whicl met with in the radiolarian sandstone of Barbadoes (fig. 586) is none more interesting than the skeleton of *Astromma* (fig.



Fig. 589.—Various forms of Radiolaria (after Haeckel): 1, *Ethmosphæ siphonophora*; 2, *Actinomma inerme*; 3, *Acanthometra xiphacantha* 4, *Arachnosphæra obligacantha*; 5, *Cladococcus viminalis*.

in which we have a remarkable example of the *range of varia* that is compatible with conformity to a general plan of struc As in other forms of Haeckel's group of *Discida*, there is in skeleton a combination of radial and of circumferential parts,

former consisting of solid spoke-like rods, whilst the latter is composed of a silicious network more or less completely filling up the spaces between the rays. The radial part of the skeleton predominates in the beautiful four-rayed example represented at D, having



FIG. 590.—Varietal modifications of *Astromma*.

the form of a cross with equal arms; whilst in F and G it still shows itself very conspicuously, though the spaces between the rays are in great part filled up by the circumferential network. In the five-rayed specimens A and B, on the other hand, the radial portion is much



FIG. 591.—*Perichlamydium prætextum*.



FIG. 592.—*Stylodyctya gracilis*.

less developed, whilst the circumferential becomes more discoidal. And in C and E, while the circumferential network forms a pentagonal disc, the radial portion is represented only by solid projections at its angles. The transition between the extreme forms is found

to be so gradual when a number of specimens are compared th lines of specific distinction can be drawn between them ; an difference in the *number* of rays is probably of no more accou these low forms of animal life than it is in the discoidal dia Other discoidal forms, showing a like combination of radial circumferential parts, are represented in figs. 591 and 592, and in fig. 586, *e*, *m*.

Entosphærida.—In this group the silicious shell is spher and is formed *within* the capsule ; and it is not traversed by although prolongations of the shell often extend themselves rad outwards, as in *Cladococcus* (fig. 589, 5). Sometimes the ce sphere is inclosed in two, three, or even more concentric sp connected by radii, as in the beautiful *Actinomma* (fig. 589, 2 minding us of the wonderful concentric spheres carved in ivo the Chinese. One of the most common examples of this gro the *Haliomma Humboldtii* (fig. 593) in which the shell is doubl

Polycystina.—This name, which originally included the prece group, is now restricted to those which have the shell formed *o* the capsule. This shell may, as i preceding, be a simple sphere posed of an open silicious networ in *Ethmosphæra* (fig. 589, 1) ; or it consist of two or three conce spheres connected by radii ; or, a it may put forth radial outgro which sometimes extend thems to several times the diameter of shell, and ramify more or minutely, as in *Arachnosphæra* 589, 4). But more frequently the opens out at one pole into a more or less bell-like, as in *Podo* (fig. 588, A, and fig. 586, *a*, *o*), *Rhopalocanium* (fig. 588, B), *Pterocanium* (fig. 587, B); or it may be elongated into a some cylindrical form, one pole remaining closed, while the other is or less contracted, as in *Eucyrtidium* (fig. 586, *d*, *g*, *i*). The tr tion between these forms, again, proves to be as gradational, w many specimens are compared,[1] as it is among Foraminifera.



Fig. 593.—*Haliomma Humboldtii.*

Acanthometrina.—In this group the animal is not inclosed wi a shell, but is furnished with a very regular skeleton, comp of elongated spines, which radiate in all directions from a com centre (fig. 587, A). The soft sarcode-body is spherical in form, occupies the spaces left between the bases of these spines, w are sometimes partly inclosed (as in the species represented transverse projections. The 'capsule' is pierced by the pse podia, whose convergence may be traced from without inwa afterwards passing through it ; and it is itself enveloped i layer of less tenacious protoplasm, resembling that of which

[1] The general plan of structure of the *Polycystina* and the signification of immense variety of forms, were ably discussed by Dr. Wallich in the *Trans. of Micros. Soc.* n.s. vol. xiii. 1865, p. 75.

pseudopodia are composed. One species, the *Acanthometra echinoides*, which presents itself to the naked eye as a crimson-red point, the diameter of the central part of its body being about $\frac{6}{1000}$ths of an inch, is very common on some parts of the coast of Norway, especially during the prevalence of westerly winds; and the Author has himself met with it abundantly near Shetland, in the floating brown masses termed *madre* by the fishermen (who believe them to furnish food to the herring), which consists mainly of this Acanthometra mingled with Entomostraca.

Phæodaria.—Among the most important of the *Radiolaria* collected by the 'Challenger' are the comparatively large (as much as 1 mm. in diameter) single-celled forms which are remarkable for the constant presence of large, dark brown granules, which are scattered irregularly round the central capsule and cover the greater part of its outer surface. The nucleus is large, the capsular membrane is always double, and is pierced by one or more large openings; the whole cell is inclosed in a thick gelatinous covering, and there is nearly always a well-developed extracapsular silicious skeleton, according to the structure of which the group is subdivided.



FIG. 594.—*Sphærozoum ovodimare.*

Collozoa.—To this group belong those remarkable composite forms, which, exhibiting the characteristic radiolarian type in their individual zoöids, are aggregated into masses in which the skeleton is represented only by scattered spicules, as in *Sphærozoum* (fig. 594) and *Thalassicolla*. These 'sea-jellies,' which so abound in the seas of warm latitudes as to be among the commonest objects collected by the tow-net, are small gelatinous rounded bodies, of very variable size and shape, but usually either globular or discoidal. Externally they are invested by a layer of condensed sarcode, which sends forth pseudopodial extensions that commonly stand out like rays, but sometimes inosculate with each other so as to form a network. Towards the inner surface of this coat are scattered a great number of oval bodies resembling cells having a tolerably distinct membraniform wall and a conspicuous round central nucleus. Each of these bodies appears to be without any direct connection with the rest, but it serves as a centre round which a number of minute yellowish-green vesicles are disposed. Each of these groups is protected by a

silicious skeleton, which sometimes consists of separate
in fig. 594), but which may be a thin perforated sphere,
certain Polycystina, sometimes extending itself into
longations. The internal portion of each mass is com
aggregation of large vesicle-like bodies imbedded in a sof
substance.[1]

From the researches made during the 'Challenger'
it appears that the *Radiolaria* are very widely diffused
waters of the ocean, some forms being more abundant
and others in temperate seas: and that they live not onl
the surface, but also at considerable depths. Their silicio
accumulate in some localities (in which the calcareous
Foraminifera are wanting) to such an extent as to fo
larian ooze'; and it is obvious that the elevation of su
into dry land would form a bed of silicious sandstone re
well-known Barbadoes rock, which is said to attain a
1,100 feet, or a similar rock of yet greater thickness in
Islands. Few microscopic objects are more beautif
assemblage of the most remarkable forms of the Barb
cystina (fig. 586), especially when seen brightly illumi
a black ground; since (for the reason formerly expl
solid forms then become much more apparent than th
these objects are examined by light transmitted through
when they are mounted in Canada balsam the black-
mination is much to be preferred for the purpose
although minute details of structure can be better ma
they are viewed as transparent objects with higher pow
of the more solid forms when exposed to a high temp
slip of platinum foil undergo a change in aspect which
peculiarly beautiful as opaque objects, their glassy
giving place to an enamel-like opacity. They may then
on a black ground and illuminated either with a side
with the parabolic speculum. No class of object is m
than these to the binocular microscope, its stereoscop
causing them to be presented to the mind's eye in con
so as to bring out with the most marvellous and beaut
their delicate sculpture.[2]

[1] See Professor Huxley (to whom we owe our first knowledge of thes
Nat. Hist. ser. ii. vol. viii. 1851, p. 433; also Professor Müller, of Berlin,
Micros. Sci. vol. iv. 1856, p. 72, and in his treatise *Ueber die Thala
cystinen, und Acanthometren des Mittelmeeres*, the magnificent wo
Haeckel, *Die Radiolarien*, and the monograph by K. Brandt, publish
und Flora des Golfes von Neapel, 1885, 'Die koloniebildend
(Sphærozoëen) des Golfes von Neapel.'

[2] For a fuller description of the fossil forms of this group see Profes
memoirs in the *Monatsberichte* of the Berlin Academy for 1846, 1847,
his *Microgeologie*, 1854; and *Ann. of Nat. Hist.* vol. xx. 1847. The
separating the *Polycystina* from the Barbadoes sandstone is describ
long in the *Quart. Journ. of Micros. Sci.* n.s. vol. i. 1861, p. 64.

CHAPTER XV

SPONGES AND ZOÖPHYTES

I. Sponges.

ıe Protozoa and commence the study of the Metazoa, which the egg-cell undergoes subdivision, the result- f which do not separate or lead an independent combine to form an organic whole, various parts ·ious functions. Of these Metazoa the simplest ex- e found among Sponges. The determination of the the animals of this class has been entirely effected by examination of their minute structure; for until this ɔerly understood, not only was the general nature of ; entirely misapprehended, but they were regarded lists as having no certain claim to a place in the ı. What that place is, is, to some extent, still an but it may now be unhesitatingly affirmed that a ;regate of protozoic units, only in the sense in which composed of cells; some of these cells have a striking the collared *Flagellata* (fig. 527), whilst others re- (fig. 519). These units are held together by a con- ;ive-tissue-like substance which clothes the skeletal ; represents our usual idea of a sponge, and is itself stinct cellular elements. In the simpler forms of ɔr, this framework is altogether absent; in others it ɔnly by calcareous or silicious 'spicules,' which are gh the sarcodic substance (fig. 596, B); in others, ɛton is a keratose (horny) network, which may be ɛ (as in our ordinary sponge) of any mineral support, ten strengthened by calcareous or silicious spicules st in what may be regarded as the highest types of ilicious component of the skeleton increases, and the ɜhes until the skeleton consists of a beautiful silicious ɔling spun glass. But whatever may be the condi- *eleton*, that of the body that clothes it remains ɜame; and the peculiarity that chiefly distinguishes ɔny from the plant-like colonies of the flagellate ıt whilst the latter extend themselves *outwards* by ication, sending their zoöid-bearing branches to

meet the water they inhabit, the surface of the former exte itself *inwards*, forming a system of passages and cavities lined these and the amœboid cells, through which a current of wate drawn in to meet them by the action of the flagella. The min pores (fig. 595, *b*, *b*) with which the surface *a*, *a* of the living spo is beset lead to incurrent passages that open into chambers ly beneath it (*c*, *c*), and open into the 'ampullaceous sacs,' or, as t are now more often called, 'flagellate chambers,' from the pres round their walls of the flagellate or collared cells. The wa drawn in by their agency is driven outwards through a system excurrent canals, which, uniting into larger trunks, proceed to *oscula* or projecting vents, *d*, from each of which, during active life of the sponge, a stream of water, carrying out excrem titious matter, is continually issuing. The in-current brings i the chambers both food-material and oxygen ; and from the man in which coloured particles experimentally diffused through water wherein a sponge is living are received into its sarcodic s stance, it seems clear that the nutrition of the entire fabric is resultant of the feed action of the flagel units, each of wh takes in, after its k the food-parti brought by the cur of water, and imp the product of digestion of them the general sarc mass.[1]



FIG. 595.—Diagrammatic section of a sponge: *a*, *a*, superficial layer; *b*, inhalant apertures or pores; *c*, *c*, flagellated chambers; *d*, exhalant oscule; *e*, deeper substance of the sponge.

The continuous code-substance or 'soderm' that clo the skeleton of sponge and constitutes the chief part of its living body incl great numbers of stellate granular cells. Their long slender pseu podia, radiating towards those of their neighbours, often u together to form a complex network ; on the chief parts of course of the water-way they become fusiform in shape and c tractile in function, and it is by their agency that the contin contractions and expansions of the oscula are produced, which very characteristic of the living sponge. As has been shown Professor C. Stewart and Dr. von Lendenfeld, sensory organs, for of groups of cells with long projecting filaments, are to be seen the surface of many sponges. Any one of these amœboids, ag detached from the mass, may lay the foundation of a new 'colo In the aggregate mass produced by its continuous segmentat

[1] The view that sponges are essentially protozoic colonies has found its c supporters in Prof. H. James Clark, Mr. H. J. Carter, and Mr. Saville Kent; the now known facts as to the history of their development are decisive as to metazoic nature of the group. For an excellent summary of this aspect of the qu tion see Prof. F. E. Schulze, *Sitzungsber. Berlin Akad.* 1885, p. 179.

certain globular clusters are distinguishable, each having a cavity in its interior; and the amœboids that form the wall of this cavity become metamorphosed into collared flagellate cells whose flagella project into it. Thus is formed one of the characteristic 'ampullaceous sacs,' which, at first closed, afterwards communicates with the exterior, on the one hand, by an incurrent passage, and on the other with the excurrent canal-system leading to the oscula. Besides this reproduction by 'microspores,' there is another form of non-sexual reproduction by macrospores, which are clusters of amœboids encysted in firm capsules, frequently strengthened on their exterior by a layer of spicules of very peculiar form. These 'seed-like bodies,' which answer to the encysted states of many protophytes, are met with in the substance of the sponge, chiefly in winter; and after being set free through the oscula they give exit to their contained amœboids, each of which may found a new colony. A true process of sexual generation, moreover, is known to take place in sponges, certain of the amœboids, like certain cells of *Volvox*, becoming 'sperm-cells,' and developing spermatozoa by the metamorphosis of their nuclei; while others become 'germ-cells,' developing themselves by segmentation (when fertilised) into the bodies known as 'ciliated gemmules,' which are set free from the walls of the canals, swim forth from the vents, and for a time move actively through the water. According to Professor Haeckel, the fertilised germ-cells are to be regarded as true *ova*, and the products of their segmentation as *morulæ*, which, by invagination, become *gastrulæ*; and he argues that the whole system of canals and ampullaceous sacs is really, like the system of canals in the sponge-like *Alcyonium*, an extension of the primitive gastric cavity, the *oscula* of sponges being the undeveloped representatives of the *polypes* of the zoöphyte.[1]

The arrangement of the keratose reticulation in the sponges with which we are most familiar may be best made out by cutting thin slices of a piece of sponge submitted to firm compression, and viewing these slices, mounted upon a dark ground, with a low magnifying power under incident light. Such sections, thus illuminated, are not merely striking objects, but serve to show, very characteristically, the general disposition of the larger canals and of the smaller pores with which they communicate. In the ordinary sponge the fibrous skeleton is almost entirely destitute of spicules, the absence of which, in fact, is one important condition of that flexibility and compressibility on which its uses depend. When spicules exist in connection with such a skeleton, they are usually either altogether imbedded in the fibres, or are implanted into them at their bases; but smaller and simpler sponges, such as *Grantia*, have no horny skeleton, and their calcareous spicules are imbedded in the general substance of the body. Sponge-spicules are much more frequently silicious than calcareous; and the variety of forms presented by the silicious spicules is much greater than that which

[1] See Chapter V. of Mr. Saville Kent's *Manual of the Infusoria*, and Chapter V. of vol. i. of Mr. Balfour's *Comparative Embryology*, as well as Professor Haeckel's important work on the Calcareous Sponges.

we find in the comparatively small division in which they
composed of carbonate of lime. The long needle-like spicules, w
are extremely abundant in several sponges, lying close toge
in bundles, are sometimes straight, sometimes slightly cur



FIG. 596.—A, section through *Phakellia ventilabrum*, var. *convexa*, taken at r
angles to the surface, to show the arrangement of the parts of a sponge: *p*, p
on the surface leading to *ic*, the inhalent canals, then to the flagellated chambe
fc, and thence to the exhalent canals, *ec*, to *o*, the oscula in the dermal membra
dm. B, more highly magnified view of the internal portion (choanosome
Axinella parasitica × 290: *mc*, mesodermal cells. Other letters as in A. (Af
Ridley and Dendy.)

they are sometimes pointed at both ends, sometimes at one only; one or both ends may be furnished with a head like that of a pin, or may carry three or more diverging points which sometimes curve back so as to form hooks. When the spicules project from the horny framework they are usually somewhat conical in form, and their surface is often beset with little spines arranged at regular intervals, giving them a jointed appearance.[1] The more recent authorities on Sponges, such as Professor Sollas and Messrs. Ridley and Dendy, have recognised that in the present state of our knowledge the spicules which are ordinarily found in silicious Sponges belong to one of two groups, which, as they differ considerably in size, may be called megascleres (or, more correctly, megaloscleres) and microscleres. It is to the definite arrangement of the former that, with or without the addition of spongin, the sponge owes its definite skeleton; the microscleres give consistency to the tissue of the sponge, and are irregularly scattered throughout its substance. If we desire to give them physiological names we may call the megaloscleres skeletal spicules, and the microscleres flesh-spicules. If we bear in mind that in the opinion of the most competent spongologists the polyaxial spicules are the most primitive, there is no practical objection to our noticing them in the reverse order; a method which will be found to conduce to simplicity of description. In the examination of spicules, it is necessary, first of all, to distinguish between *axes* and *rays*; thus in the Monaxonida the megaloscleres have but a single axis, but the growth from the point of origin may be on either side, when we have two-rayed or diactinal megaloscleres, or it may extend in one direction only, when the scleres are said to be monactinal. In the Calcispongiæ there are three axes and three rays; but in some sponges, such as Venus'



FIG. 597.—Structure of the chelæ of Monaxonid Sponges: 1, tridentate anisochela from in front; 1*a*, from the side; 2, 2*a*, front and side views of a palmate isochela; *t*, *t'*, tubercle; *at*, *at'*, anterior tooth or palm; *lt*, *lt'*, lateral tooth or palm; *s*, shaft; *f*, fimbria. (After Ridley and Dendy.)

[1] A minute account of the various forms of spicules contained in Sponges is given by Mr. Bowerbank in his first memoir 'On the Anatomy and Physiology of the Spongiadæ' in *Phil. Trans.* 1858, pp. 279-332; and in his *Monograph of the British Spongiadæ*, published by the Ray Society. The Calcareous Sponges have been made by Professor Haeckel the subject of an elaborate monograph, *Die Kalkschwämme*, Berlin, 1872. For compendious enumerations and classifications of the various kinds of spicules, see Professor Sollas, art. 'Sponges,' in *Encycl. Britannica*, and Messrs. Ridley and Dendy, *Report on the 'Challenger' Monaxonida*, pp. xv–xxi.

flower-basket, the growth is along both directions of the axe that while there are three axes there are six rays, or the spi are hexactinellid. In others, such as *Geodia* and the Lith Sponges there are four axes, whence such forms are called tetrax Lastly there are the least regular megaloscleres which may be m radiate or spherical.

As is well known, the flesh-spicules are of the most varied fo and it is a matter of some difficulty so to group them as to re them more easy of comprehension by the student. Messrs. Ridley Dendy suggest that, provisionally at any rate, we should regard t as (1) simple linear, (2) hooked, (3) stellate. The first may be poi at either end, and these are often spinous, or they may be long hair-like, and be or not be arranged in bundles (*dragmata*); a com form is that of a bow, and these, again, are sometimes arrange bundles, which have been formed within one and the same The hooked forms may be simple sigmiform microscleres, or shape may be complicated by the inner margin of the shaft or l thinning out to a fine knife-edge. The most complex forms of group are the microscleres which the just-quoted authors denomi *chelæ*. They describe these scleres (fig. 597) as having a mor less curved shaft (*s*), which bears at each end a variable numbe sharply recurved processes (*at*, *at'*, *lt*, which they call the 'teeth,' or if b and expanded the 'palms'; these are nected with the shaft by a buttress projection, which is generally so t parent as to be with difficulty made The shaft itself is frequently drawn at the side into wing-like processe fimbriæ (*f*). If the two ends of spicule are equal, we have *isochelæ*; i equal, *anisochelæ*. The stellate m scleres may be spiral, have a shaft spinose whorls, or a cylindrical shaft a toothed whorl at either end.



FIG. 598.—Anisochelæ of *Cladorhiza inversa* showing *n*, the nucleus of the mother-cell of the spicule, from in front, *a*, and from the side, *b*. × 300. (After Ridley and Dendy.)

spicules of sponges cannot be considered, like the *raphides* of pl as mere deposits of mineral matter in a crystalline state; for, all other parts of the organism, they are of cellular origin (fig. and the special cells which produce them are distinguished as coblasts; in this there is first developed a central organic th around which concentric layers of silica or chalk are laid down.

There is an extremely interesting group of Sponges in which horny skeleton is entirely replaced by a *silicious* framework of g firmness and of singular beauty of construction. This framew may be regarded as fundamentally consisting of an arrangemen *six-rayed* spicules, the extensions of which come to be, as it w soldered to one another; and hence the group is distinguished *sexradiate*. Of this type the beautiful *Euplectella* of the Ma seas which was for a long time one of the greatest of zoolog rarities, but which now, under the name of 'Venus' flower-bask is a common ornament of our drawing-rooms—is one of the m

characteristic examples.[1] Another example is presented by the *Holtenia Carpenteri*, of which four specimens, dredged up from a depth of 530 fathoms between the Faroë Islands and the north of Scotland, were among the most valuable of the 'treasures of the deep' obtained during the first deep-sea exploration (1868) carried on by Sir Wyville Thomson and the Author. This is a turnip-shaped body, with a cavity in its interior, the circular mouth of which is surrounded with a fringe of elongated silicious spicules; whilst from its base there hangs a sort of beard of silicious threads that extend themselves, sometimes to a length of several feet, into the Atlantic mud on which these bodies are found. The framework is much more massive than that of *Euplectella*, but it is not so exclusively mineral; for if it be boiled in nitric acid it is resolved into separate spicules, these being not soldered together by silicious continuity, but held together by animal matter. Besides the regular sex-radiate spicules, there is a remarkable variety of other forms, which have been fully described and figured by Sir Wyville Thomson.[2] One of the greatest features of interest in this *Holtenia* is its singular resemblance to the *Ventriculites* of the Cretaceous formation. Subsequent investigations have showed that it is very widely diffused, and that it is only one of several deep-sea forms, including some of singularly beautiful structure, which are the existing representatives of the old ventriculite type. One of these was previously known from being occasionally cast up on the shore of Barbadoes after a storm. This *Dictyocalyx pumiceus* has the shape of a mushroom, the diameter of its disc sometimes ranging to a foot. A small portion of its reticulated skeleton is a singularly beautiful object when viewed with incident light under a low magnifying power.

With the exception of the genus *Spongilla* and its allies, all known sponges are marine, but they differ very much in habit of growth. For whilst some can only be obtained by dredging at considerable depths, others live near the surface, whilst others attach themselves to the surfaces of rocks, shells, &c. between the tide-marks. The various species of *Grantia* in which, of all the marine sponges, the flagellate cells can most readily be observed, belong to this last category. They have a peculiarly simple structure, each being a sort of bag whose wall is so thin that no system of canals is required, the water absorbed by the outer surface passing directly towards the inner, and being expelled by the mouth of the bag. The flagella may be plainly distinguished with a $\frac{1}{4}$-inch objective on some of the cells of the gelatinous substance scraped from the interior of the bag; or they may be seen *in situ* by making very thin transverse sections of the substance of the sponge. It is by such sections alone that the internal structure of sponges, and the relation of their spicular and horny skeletons to their fleshy substance, can be demonstrated. They are best made by the imbedding process. In

[1] The structure and arrangement of the soft parts of *Euplectella aspergillum* have been investigated by Prof. F. E. Schulze, *Trans. Royal Soc. of Edinburgh*, xxix. p. 661.

[2] See his elaborate memoir in *Phil. Trans.* 1870, and his *Depths of the Sea*, 1872, p. 71.

order to obtain the *spicules* in an isolated condition, the ar matter must be got rid of either by incineration or by che reagents. The latter method is preferable, as it is difficult to the mineral residue from carbonaceous particles by heat alone (as is commonly the case) the spicules are *silicious*, the sponge be treated with strong nitric or nitro-muriatic acid, until its ar substance is dissolved away; if, on the other hand, they be *carcous*, a strong solution of potass may be employed instead of acid. The operation is more rapidly accomplished by the ai heat; but if the saving of time be not of importance, it is prefe on several accounts to dispense with it. The spicules, when obta in a separate state, should be mounted in Canada balsam. Spo tissue may often be distinctly recognised in sections of a chalcedony, and other silicious concretions, as will be more stated hereafter.[1]

II. Zoöphytes (Cœlenterata).

Under the general designation *Zoöphytes* it will be still venient to group those animals which form composite skeleton 'polyparies' of a more or plant-like character, associa with them the *Acalephæ*, w are now known to be the 'so zoöids' of polypes, but exclu the *Polyzoa* on account of very different structure, withstanding their zoöp forms and habits of life. animals belonging to this g may be considered as fo upon the primitive *gas* type, their gastric ca (though sometimes exten itself almost indefinitely) l lined by the original *endo* and their surface being cov by the original *ectoderm*, these two lamellæ not b separated by the interpos of any body-cavity or *ca* It is a fact of great inte that although the produc the development of a *mora* here a distinctly individual polype, in which several m ally dependent parts make a single organic whole, yet these parts still retain much of t independent protozoic life; which is manifested in two very



Fig. 599.—Longitudinal section of the body of a hydra killed in full digestion: *cc*, ectoderm; *en*, endoderm; *mp*, muscular processes; *d*, a diatom; *f*, food. (After T. J. Parker.)

[1] A complete and valuable handbook to the Sponges has been lately publishe Dr. G. C. Vosmaer as vol. ii. of Bronn's *Klassen und Ordnungen des Thierre* Leipzig, 1887. Compare also the article by Professor Sollas in the ninth edition of

markable modes. In the first place, the digestive sac is observed to be lined by a layer of amœboid cells, which send out pseudopodial prolongations into its cavity (fig. 599) by whose agency (it may be pretty certainly affirmed) the nutrient material is first introduced into the body-substance. This process of 'intracellular digestion' was first noticed by Professor Allman in the beautiful hydroid polype *Myriothela*;[1] the like has been since shown by Mr. Jeffery Parker to be true of the ordinary *Hydra*;[2] and Professor E. Ray Lankester has made the same observation upon the curious little Medusa (*Limnocodium*), lately found in a *fresh-water* tank in this country, whither it has undoubtedly been introduced; while the observations of Krukenberg have shown that a similar process obtains among the sea-anemones.[3] (It may be mentioned in this connection, that Metschnikoff has seen the cells which line the alimentary canal of the lower planarian worms gorging themselves with coloured food-particles, exactly in the manner of *Amœbæ* and the liver-fluke, and that a number of larvæ are known to obtain their nourishment in the same way.[4]) The second 'survival' of protozoic independence is shown in the extraordinary power possessed by *Hydra*, *Actinia*, &c. of reproducing the entire organism from a mere fragment. This great division includes the two principal groups the HYDROZOA and the ACTINOZOA, the former comprehending the *Polypes*, and the latter the *Anemones*. In the Hydrozoa the mouth is placed on a projecting oral cone, while in the Anthozoa it is sunk below the level of the oral circlet of tentacles, and the cavity developed from and connected with the digestive cavity separates its wall from the body-wall and is traversed by a series of vertical partitions or septa. As most of the hydroid polypes are essentially microscopic animals, they need to be described with some minuteness; whilst in regard to the Actinozoa those points only will be dwelt on which are of special interest to the microscopist.

Hydrozoa.—The type of this group is the *Hydra* or fresh-water polype, a very common inhabitant of pools and ditches, where it is most commonly to be found attached to the leaves or stems of aquatic plants, floating pieces of stick, &c. Two species are common in this country, the *H. viridis* or green polype, and the *H. vulgaris*, which is usually orange-brown, but sometimes yellowish or red (its colour being liable to some variation according to the nature of the food on which it has been subsisting); a third less common species, the *H. fusca*, is distinguished from both the preceding by the length of its tentacles, which in the former are scarcely as long as the body, whilst in the latter they are, when fully extended, many times longer

Encyclopædia Britannica; the '*Challenger*' *Reports* by Professor Schulze, Messrs. Ridley and Dendy, Polejaeff, and Sollas; and the numerous memoirs of Professors O. Schmidt and Schulze, and of Dr. von Lendenfeld.

[1] *Phil. Trans.* 1875, p. 552. It should be noted that Professor Claus called attention to the ingestion of foreign bodies by amœboid cells of *Monophytes* in 1874. See his *Schriften Zool. Inhalts.* (Wien, 1874), p. 30

[2] *Proc. of Roy. Soc.* vol. xxx. 1880, p. 61.

[3] *Quart. Journ. Micros. Sci.* n.s. vol. xx. 1880, p. 371.

[4] Consult an interesting article on 'Intercellular Digestion,' by Metschnikoff, in *Revue Scientifique*, ser. iii. vol. xi. p. 688.

(fig. 600 [1]). The body of the Hydra consists of a simple bag or sac, which may be regarded as a stomach, and is capable of varying its shape and dimensions in a very remarkable degree, sometimes extending itself in a straight line so as to form a long narrow cylinder, at other times being seen (when empty) as a minute contracted globe, whilst, if distended with food, it may present the form of an inverted flask or bottle, or even of a button. At the upper end of this sac is a central opening, the mouth; and this is surrounded by a circle of tentacles or 'arms,' usually from six to ten in number, which are arranged with great regularity around the orifice. The body is prolonged at its lower end into a narrow base, which is furnished with a suctorial disc, and the Hydra usually attaches itself by this, while it allows its tendril-like tentacles to float freely in the water. The wall of the body is composed of two layers of cells; and between these, which are the ectoderm and endoderm, there is a delicate intermediate layer, which forms the supporting lamella.[2] The arms are made up of the same materials as the body; but their surface is beset with little wart-like prominences, which, when carefully examined, are found to be composed of clusters of 'thread-cells,' having a single large cell with a long spiculum in the centre of each. The structure of these thread-cells or 'urticating organs' will be described hereafter; at present it will be enough to point out that this apparatus, repeated many times on each tentacle, is doubtless intended to give to the organ a great prehensile power, the minute filaments forming a rough surface adapted to prevent the object from readily slipping out of the grasp of the arm, whilst the central spicule or 'dart' is projected into its substance, probably conveying into it a poisonous fluid secreted by a vesicle at its base.



Fig. 600.—*Hydra fusca*, with a young bud at *b*, and a more advanced bud at *c*.

[1] On the specific characters of *Hydra* consult Haacke, *Jenaische Zeitschr.* xiv. p. 133; and Jickeli, *Zool. Anzeig.* v. p. 491.

[2] To this intermediate layer, Mr. G. C. Bourne applies the term *mesoglœa*. For an account of its variations and structure among the Cœlenterata, and a discussion of its homology with the mesoderm of higher Metazoa, see his essay on *Fungia* in vol. xxvii. of the *Quart. Journ. Micros. Sci.* n.s.

The latter inference is founded upon the oft-repeated observation, that if the living prey seized by the tentacles have a body destitute of hard integument, as is the case with the minute aquatic worms which constitute a large part of its aliment, this speedily dies, even though, instead of being swallowed, it escapes from their grasp; whilst, on the other hand, minute Entomostraca, insects, and other animals or ova, with hard envelopes, may escape without injury, even after having been detained for some time in the polype's embrace. The contractility of the tentacles (the interior of which is traversed by a canal that communicates with the cavity of the stomach) is very remarkable, especially in the *Hydra fusca*, whose arms, when extended in search of prey, are not less than seven or eight inches in length; whilst they are sometimes so contracted, when the stomach is filled with food, as to appear only like little tubercles around its entrance. By means of these instruments the Hydra is enabled to draw its support from animals whose activity, as compared with its own slight powers of locomotion, might have been supposed to remove them altogether from its reach; for when, in its movements through the water, a minute worm or a water-flea happens to touch one of the tentacles of the polype, spread out as these are in readiness for prey, it is immediately seized by this; other arms are soon coiled around it, and the unfortunate victim is speedily conveyed to the stomach, within which it may frequently be seen to continue moving for some little time. Soon, however, its struggles cease, and its outline is obscured by a turbid film, which gradually thickens, so that at last its form is wholly lost. The soft parts are soon completely dissolved, and the harder indigestible portions are rejected through the mouth. A second orifice has been observed at the lower extremity



FIG. 601.—*Campanularia gelatinosa.*

of the stomach; but this would not seem to be properly regard anal, since it is not used for the discharge of such exuviæ; probably rather to be considered as representing, in the Hydra entrance to that ramifying cavity which, in the *compound Hydr* brings into mutual connection the lower extremities of the stom of all the individual polypes.

The ordinary mode of reproduction in this animal is by a 'gen tion' resembling that of plants. Little bud-like processes (fig. *b*, *c*) developed from its external surface gradually come to rese the parent in character, and to possess a digestive sac, mouth, tentacles; for a long time, however, their cavity is connected that of the parent, but at last the communication is cut off by closure of the canal of the stalk, and the young polype its attachment and goes in of its own maintenance. second generation of buc sometimes observed on the y polype before quitting its pa and as many as *nineteen* y *Hydræ* in different stage development have been seen connected with a single ori stock (fig. 602). This pr takes place most rapidly u the influence of warmth abundant food; it is usually pended in winter, but ma made to continue by keepin polypes in a warm situation well supplied with food. An very curious endowment see depend on the same conditi the extraordinary power w one portion possesses of re ducing the rest. Into what number of parts a *Hydra* be divided, each may retai vitality, and give origin new and entire fabric: so that *thirty* or *forty* individuals be formed by the section of one. The *Hydra* also propagates it however, by a truly sexual process, the fecundating apparatus vesicle producing 'sperm-cells,' and the ovum (containing the 'g cell,' imbedded in a store of nutriment adapted for its early deve ment) being both evolved in the substance of the walls of stomach—the male apparatus forming a conical projection beneath the arms, while the female ovary, or portion of the bo substance in which the ovum is generated, has the form o knob protruding from the middle of its length. It would app that sometimes one individual Hydra develops only the male cy or sperm-cells, while another develops only the female cysts or

FIG. 602.—*Hydra fusca* in gemmation: *a*, mouth; *b*, base; *c*, origin of one of the buds.

sacs; but the general rule seems to be that the same individual forms both organs. The fertilisation of the ova, however, cannot take place until after the rupture of the spermatic cyst and of the ovisac, by which the contents of both are set free. The autumn is the chief time for the development of the sexual organs, but they also present themselves in the earlier part of the year, chiefly betweeen April and July. According to Ecker, the eggs of *H. viridis* produced early in the season run their course in the summer of the same year; while those produced in the autumn pass the winter without change. When the ovum is nearly ripe for fecundation the ovary bursts its ectodermal covering, and remains attached by a kind of pedicle. It seems to be at this stage that the act of fecundation occurs; a very strong elastic shell or capsule then forms round the ovum, the surface of which is in some cases studded with spine-like points, in others tuberculated, the divisions between the tubercles being polygonal. The ovum finally drops from its pedicle, and attaches itself by means of a mucous secretion, till the hatching of the young Hydra, which comes forth provided with four rudimentary tentacles like buds. The Hydra possesses the power of free locomotion, being able to remove from the spot to which it has attached itself to any other that may be more suitable to its wants; its changes of place, however, seem rather to be performed under the influence of *light*, towards which the Hydra seeks to move itself, than with reference to the search after food.[1]

The *compound Hydroids* may be likened to a *Hydra* whose gemmæ, instead of becoming detached, remain permanently connected with the parent; and as these in their turn may develop gemmæ from their own bodies, a structure of more or less arborescent character, termed a *polypary*, may be produced. The form which this will present, and the relation of the component polypes to each other, will depend upon the mode in which the gemmation takes place; in all instances, however, the entire cluster is produced by continous growth from a single individual; and the stomachs of the several polypes are united by tubes, which proceed from the base of each, along the stalk and branches, to communicate with the cavity of the central stem. Whatever may be the form taken by the stem and branches constituting the polypary of a hydroid colony, they will be found to be, or to contain, fleshy tubes having two distinct layers, the inner (endoderm) having nutritive functions; the outer (ectoderm) usually secreting a hard cortical layer, and thus giving rise to fabrics of various forms. Between these a muscular coat is sometimes noticed. The fleshy tube, whether single or compound, is called a *cænosarc*, and through it the nutrient matter circulates. The 'zoöids,' or individual members of the colony, are of two kinds: one the *polypite*, or *alimentary* zoöid, resembling the Hydra in essential

[1] A very full account of the structure and development of *Hydra* has been published by Kleinenberg, of whose admirable monograph a summary is given by Professor Allman, with valuable remarks of his own, in *Quart. Journ. Micros. Sci.* n.s. vol. xiv. 1874, p. 1. See also the important paper by Mr. Jeffery Parker already cited. On the chlorophyll corpuscles of *H. viridis* consult Brandt, *Mitth. Zool. Stat. Neapel*, iv. p. 191; Hamann, *Zool. Anzeig.* vi. p. 367; and Lankester *Quart. Journ. Micros. Sci.* n.s. xxii. p. 229.

structure, and more or less in aspect; the other, the *gonozoöi* *sexual* zoöid, developed at certain seasons only, in buds of parti shape.[1]

The simplest division of the Hydroida is that adopted by Hincks,[2] who groups them under the sub-order *Athecata* and *The* the latter being again divided into the *Thecaphora* and the *Gy* *chroa*. In the first, neither the 'polypites' nor the sexual z bear true protective cases; in the second the polypites are lodg cells, or, as Mr. Hincks prefers to call them, *calycles*, many of v resemble exquisitely formed crystal cups, variously ornamented sometimes furnished with lids or opercula; in the third, which tains the Hydras, there is no polypary, and the reproductive z (gonozoöids) are always fixed and developed in the body-walls. cording to Mr. Hincks, the two sexes are sometimes borne o same colony, but more commonly the zoöphyte is dioecious. cases, however, are much less rare than has been supposed in v both male and female are mingled on the same shoots. The s zoöids either remain attached, and discharge their conten maturity, or become free and enter upon an independent exist The free forms nearly always take the shape of *Medusæ* (jelly- swimming by rhythmical contractions of their bell or umbrella. digestive cavity is in the handle (manubrium) of the bell; an generative elements (sperm-cells or ova) are developed either be the membranes of the manubrium or in special sacs in the c radiating from it. The ova, when fertilised by the sperma undergo 'segmentation' according to the ordinary type, the yolk-mass subdividing successively into two, four, eight, si thirty-two or more parts, until a 'mulberry mass' is formed then begins to elongate itself, its surface being at first smooth showing a transparent margin, but afterwards becoming clothed cilia, by whose agency these little *planulæ*, closely resembling ci Infusoria, first move about within the capsule, and then swim freely when liberated by the opening of its mouth. At this p the embryo can be made out to consist of an outer and an layer of cells, with a hollow interior; after some little time th disappear, and one extremity becomes expanded into a kind of by which it attaches itself to some fixed object: a mouth is fo and tentacles sprout forth around it; and the body increases in l and thickness, so as gradually to acquire the likeness of one o parent polypes, after which the 'polypary' characteristic of the g is gradually evolved by the successive development of polype- from the first-formed polype and its subsequent offsets. The Me of these polypes (fig. 605) belong to the division called 'naked-e on account of the eye-spots usually seen surrounding the marg the bell at the base of the tentacles.

A characteristic example of this production of medusa 'gonozoöids' is presented by the form termed *Syncoryne Sarsii*

[1] A useful list of the principal terms used in describing hydroids, with defini will be found on pp. 16 and 17 of Professor Allman's *Report on the Hydroida* (*mulariidæ*) of the *Challenger*.

[2] *History of British Hydroid Zoöphytes*, 1868.

603) belonging to the sub-order *Athecata*. At A is shown the alimentary zoöid, or polypite, with its tentacles, and at B the successive stages *a*, *b*, *c*, of the sexual zoöids, or medusa-buds. When sufficiently developed the Medusa swims away, and as it grows to maturity enlarges its manubrium, so that it hangs below the bell. The Medusæ of the genus *Syncoryne* (as now restricted) have the form named *Sarsia* in honour of the Swedish naturalist Sars. Their normal character is that of free swimmers ; but Agassiz ascertained that in some cases towards the end of the breeding season the sexual zoöids remain fixed, and mature their products while attached to the zoöphyte.[1] This latter condition of the sexual zoöids is very common amongst the Hydroida ; and various intermediate stages may be traced in different genera between the mode in which the gonozoöids are produced in the common Hydra, as already described, and that of Syncoryne. In *Tubularia* the gonozoöids, though permanently attached, are furnished with swimming bells, having four tubercles representing marginal tentacles. A common and interesting species, *Tubularia indivisa*, receives its specific name from the infrequency with which branches are given off from the stems, these for the most part standing erect and parallel, like the stalks of corn, upon the base to which they are attached. This beautiful zoöphyte, which sometimes grows between the tide-marks, but is more abundantly obtained by dredging in deep water, often attains a size which renders it scarcely a microscopic object, its stems being sometimes no less than a foot in height and a line in diameter. Several curious phenomena, however, are brought into view by microscopic examination. The polype-stomach is connected with the cavity of the stem by a circular opening, which is surrounded by a sphincter ; and an alternate movement of dilatation and contraction takes place in it, fluid being apparently forced up from below, and then expelled again, after which the sphincter closes in preparation for



FIG. 603.—Development of Medusa buds in *Syncoryne Sarsii*: A, an ordinary polype, with its club-shaped body covered with tentacles; B, a polype putting forth medusoid gemmæ; *a*, a very young bud; *b*, a bud more advanced, the quadrangular form of which, with the four nuclei whence the cirrhi afterwards spring, is shown at *d*; *c*, a bud still more advanced.

[1] Hincks, *op. cit.* p. 49.

a recurrence of the operation, this, as observed by Mr. List being repeated at intervals of eighty seconds. Besides the foregoi movement, a regular flow of fluid, carrying with it solid particles various sizes, may be observed along the whole length of the ste passing in a somewhat spiral direction. It is worthy of menti here that when a Tubularia is kept in confinement the polype-hea almost always drop off after a few days, but are soon renewed ag by a new growth from the stem beneath ; and this exuviation a regeneration may take place many times in the same individual.[1]

It is in the families *Campanulariida* and *Sertulariida* (wh polyparies are commonly known as 'corallines'), that the hor branching fabric attains its completest development, not only affo ing an investment to the stem, but forming cups or cells for t protection of the polypites, as well as capsules for the reproducti gonozoöids. Both these families thus belong to the sub-order *Theca* In the *Campanulariida* the polype-cells are campanulate or b shaped, and are borne at the extremities of ringed stalks (fig. 601, in the *Sertulariida*, on the other hand, the polype-cells lie along t stem and branches, attached either to one side only, or to both si (fig. 604). In both the general structure of the individual poly (fig. 601, B, *d*) closely corresponds with that of the *Hydra* ; and t mode in which they obtain their food is essentially the same. the products of digestion, however, a portion finds its way down i the tabular stem, for the nourishment of the general fabric ; a very much the same kind of circulatory movement can be seen *Campanularia* as in Tubularia, the circulation being most vigor in the neighbourhood of growing parts. It is from the 'cœnosa (fig. 601, *f*) contained in the stem and branches that new poly buds (*b*) are evolved ; these carry before them (so to speak) a porti of the horny integument, which at first completely invests the bu but as the latter acquires the organisation of a polype, the c thins away at its most prominent part, and an opening is form through which the young polype protrudes itself.

The origin of the reproductive capsules or 'gonothecæ' (*e*) exactly similar, but their destination is very different. Wit them are evolved, by a budding process, the generative organs the zoöphyte ; and these in the *Campanulariida* may either devel themselves into the form of independent medusoids, which co pletely detach themselves from the stock that bore them, make th way out of the capsule, and swim forth freely, to mature th sexual products (some developing sperm-cells, and others ova), a give origin to a new generation of polypes ; or, in cases in whi the medusoid structure is less distinctly pronounced, may not co pletely detach themselves, but (like the flower-buds of a plant) expa one after another at the mouth of the capsule, withering and dro ping off after they have matured their generative products. In t *Sertulariida*, on the other hand, the medusan conformation is wantin as the gonozoöids are always fixed ; the reproductive cells (fig. 604, which were shown by Professor Edward Forbes to be really met

[1] The British *Tubulariida* form the subject of a most complete and beauti monograph by Professor Allman, published by the Ray Society.

morphosed branches developing in their interior certain bodies which were formerly supposed to be ova, but which are now known to be 'medusoids' reduced to their most rudimentary condition. Within these are developed—in separate gonothecæ, sometimes perhaps on distinct polyparies—spermatozoa and ova; and the latter are fertilised by the entrance of the former whilst still contained within their capsules. The fertilised ova, whether produced in free or in attached medusoids, develop themselves in the first instance into ciliated 'gemmules,' or planulæ, which soon evolve themselves into true polypes, from every one of which a new composite polypary may spring.

There are few parts of our coast which will not supply some or other of the beautiful and interesting forms of zoöphytic life which have been thus briefly noticed, without any more trouble in searching for them than that of examining the surfaces of rocks, stones, seaweeds, and dead shells between the tide-marks. Many of them habitually live in that situation; and others are frequently cast up by the waves from the deeper waters, especially after a storm. Many kinds, however, can only be obtained by means of the dredge. Of the remarkable forms dredged by the 'Challenger' mention can only be made here of the gigantic Tubularian—*Monocaulus*—the stem of which measured seven feet four inches, while there was a spread of nine inches from tip to tip of the extended tentacles, and of the elegant *Streptocaulus pulcherrimus*, in which by the twisting of the stem the ultimate ramules are thrown into 'a graceful and beautiful spiral.' For observing them during their living state, no means is so convenient as the zoöphyte-trough. In mounting compound Hydrozoa, as well as Polyzoa, it will be found of great advantage to place the specimens alive in the cells they are permanently to occupy, and to then add osmic acid drop by drop to the sea-water; this has the effect of causing the protrusion of the animals, and of rendering their tentacles rigid. The liquid may be withdrawn, and replaced by Goadby's solution, Deane's gelatine, glycerin-jelly, weak spirit, diluted glycerin, a mixture of spirit and glycerin with sea-water, or any other menstruum, by means of

FIG. 604.—*Sertularia cupressina*: A, natural size; B, portion magnified.

the syringe; and it is well to mount specimens in several ferent menstrua, marking the nature and strength of each some forms are better preserved by one and some by anot An excellent method of preservation has been discovered M. Foettinger[2] in the use of chloral hydrate: when all polypes in a vessel containing 100 c.c. of water are fully expa some crystals of chloral hydrate are to be dropped into vessel; these dissolve rapidly and gradually diffuse through water. About ten minutes later a little more chloral shoul added, and in three-quarters of an hour the whole colony wi found to have become insensible; the advantage of this me lies in the fact that the action is merely narcotic, and that the tis are not affected. When the influence is so complete that irrita fails to produce retraction of the polypes the colony may be put alcohol. The size of the cell must of course be proportioned to of the object; and if it be desired to mount such a specimen as serve for a characteristic illustration of the mode of growth of species it represents, the large shallow cells, whose walls are n by cementing four strips of glass to the plate that forms the bot will generally be found preferable. The horny polyparies of *Sertularidæ*, when mounted in Canada balsam, are beautiful ob for the polariscope; but in order to prepare them successfully a nicety of management is required. The following are the outl of the method recommended by Dr. Golding Bird, who very suc fully practised it. The specimens selected, which should not ex two inches in length, are first to be submitted, while immerse water of 120°, to the vacuum of an air-pump. The ebulli which will take place within the cavities will have the effect of f ing the polyparies from dead polypes and other animal matter; this cleansing process should be repeated several times. specimens are then to be dried, by first draining them for a seconds on bibulous paper, and then by submitting them to vacuum of an air-pump, within a thick earthenware ointment fitted with a cover, which has been previously heated to about 2 by this means the specimens are very quickly and completely d the water being evaporated so quickly that the cells and t hardly collapse or wrinkle. The specimens are then placed camphine, and again subjected to the exhausting process for displacement of the air by that liquid; and when they have b throughly saturated, they should be mounted in Canada balsa the usual mode. When thus prepared they become very beaut transparent objects for low magnifying powers; and they prese gorgeous display of colours when examined by polarised light, v the interposition of a plate of selenite, the effect being much hanced by the use of black-ground illumination.

No result of microscopic research was more unexpected t the discovery of the close relationship subsisting between hydroid *Zoöphytes* and the medusoid *Acalephæ* (or 'jelly-fish'). now know that the small free-swimming medusoids belonging

[1] See Mr. J. W. Morris in *Quart. Journ. of Micros. Sci.* n.s. vol. ii. 1862. p. 1
[2] *Archives de Biologie*, vi. p. 115.

the 'naked-eye' group, of which *Thaumantias* (fig. 605) may be taken as a representative, are really to be considered as the detached sexual apparatus of the zoöphytes from which they have been



FIG. 605.—A, *Thaumantias pilosella*, one of the 'naked-eyed' Medusæ: *a a*, oral tentacles; *b*, stomach; *c*, gastro-vascular canals, having the ovaries, *d d*, on either side, and terminating in the marginal canal, *e e*. B, *Thaumantias Eschscholtzii*, Haeckel.

budded off, endowed with independent organs of nutrition and locomotion, whereby they become capable of maintaining their own existence and of developing their sexual products. The general conformation of these organs will be understood from the accompanying

figure. Many of this group are very beautiful objects for mi
scopic examination, being small enough to be viewed entire in
zoöphyte-trough. There are few parts of the coast on which t
may not be found, especially on a calm warm day, by skimming
surface of the sea with the tow-net; and they are capable of b
stained and preserved in cells after being hardened by osmic a

The history of the large and highly developed *Medusæ*[1] or J
LEPHÆ which are commonly known as 'jelly-fish,' is essentially s
lar; for their progeny have been ascertained to develop themse
in the first instance under the polype form, and to lead a life w
in all essential respects is zoöphytic; their development into Me
taking place only in the closing phase of their existence, and
rather by gemmation from the original polype than by a metar
phosis of its own fabric. The huge *Rhizostoma* found comm
swimming round our coasts, and the beautiful *Chrysaora* remark
for its long 'furbelows' which act as organs of prehension, are oce
acalephs developed from very small polypites, which fix themse
by a basal cup or disc. The embryo emerges from the cavity o
parent, within which the first stages of its development have ta
place, in the condition of a ciliated 'planula,' of rather oblong f
very closely resembling an infusory animalcule, but destitute
mouth. One end soon contracts and attaches itself, however, s
to form a foot; the other enlarges and opens to form a mo
four tubercles sprouting around it, which grow into tentacles; w
a slit in the midst of the central cells gives rise to the cavity of
stomach. Thus a hydra-like polype is formed, which soon acq
many additional tentacles; and this, according to the observat
of Sir J. G. Dalyell on the *Hydra tuba*, which is the polype stag
the *Chrysaora* and other jelly-fish, leads in every important partic
the life of a Hydra; propagates like it by repeated gemmatio
that whole colonies are formed as offsets from a single stock;
can be multiplied like it by artificial division, each segment deve
ing itself into a perfect Hydra. There seems to be no definite l
to its continuance in this state, or to its power of giving origi
new polype-buds; but when the time comes for the developmen
its sexual gonozoöids, the polype quits its original condition
minute bell with slender tentacles (fig. 606), assumes a cy
drical form, and elongates itself considerably; a constrictio
indentation is then seen around it, just below the ring which encir
the mouth and gives origin to the tentacles; and similar constrict
are soon repeated round the lower parts of the cylinder, so as to
to the whole body somewhat the appearance of a rouleau of co
a sort of fleshy bulb, *a* (fig. 606, II), somewhat of the form of
original polype, being still left at the attached extremity.
number of circles is indefinite, and all are not formed at once,
constrictions appearing below, after the upper portions have been
tached; as many as thirty or even forty have thus been produce
one specimen. The constrictions then gradually deepen, so as to div
the cylinder into a pile of saucer-like bodies, the division be

[1] See Professor Claus, *Untersuchungen über die Organisation und Entwickel
der Medusen*, Prague and Leipzig, 1883.

most complete above, and the upper discs usually presenting some increase in diameter; and whilst this is taking place the edges of the discs become divided into lobes, each lobe soon presenting the cleft with the supposed rudimentary eye at the bottom of it, which is to be plainly seen in the detached Medusæ (fig. 607, C). Up to this period, the tentacles of the original polype surmount the highest of the discs; but before the detachment of the topmost disc, this circle disappears, and a new one is developed at the summit of the bulb which remains at the base of the pile. At last the topmost and largest disc begins to exhibit a sort of convulsive struggle; it



FIG. 606.—I, two *Hydræ tubæ* (*Scyphistoma*-stage) of *Cyanea capillata*, with two (*a*, *b*) undergoing fission (*Strobila*-stage). II, *a* and *b* of fig. I three days later. In *a* the tentacles are developed beneath the lowest of the *Ephyræ*, from the stalk of the *Strobila*, which will persist as a *Hydra* tube. (After Van Beneden.)

becomes detached, and swims freely away; and the same series of changes takes place from above downwards, until the whole pile of discs is detached and converted into free-swimming Medusæ. But the original polypoid body still remains, and may return to its original polype-like mode of gemmation, becoming the progenitor of a new colony, every member of which may in its turn bud off a pile of Medusa discs.

The bodies thus detached have all the essential characters of the adult *Medusæ*. Each consists of an umbrella-like disc divided at its edge into a variable number of lobes, usually eight; and of a

stomach, which occupies a considerable proportion of the disc, projects downwards in the form of a proboscis, in the centre of w is the quadrangular mouth (fig. 607, A, B). As the animal adva towards maturity the intervals between the segments of the bo of the disc gradually fill up, so that the divisions are obliter tubular prolongations of the stomach extend themselves ove disc ; and from its borders there sprout forth tendril-like filam which hang down like a fringe around its margin. From the angles of the mouth, which, even in the youngest detached ani admits of being greatly extended and protruded, prolongations put forth, which form the four large tentacles of the adult. young Medusæ are very voracious, and grow rapidly, so as to at



FIG. 607.—Development of *Chrysaora* from *Hydra tuba*: A, detached individual viewed sideways, and enlarged, showing the proboscis *a*, and *b* the bifid lobes; B, individual seen from above, showing the bifid lobes of the margin, and the quadrilateral mouth; C, one of the bifid lobes still more enlarged, showing the rudimentary eye (?) at the bottom of the cleft; D, group of young Medusæ, as seen swimming in the water, of the natural size.

a very large size. The *Cyanea* and *Chrysaora*, which are common round our coasts, often have a diameter of from six to fifteen inch while *Rhizostoma* sometimes reaches a diameter of from two to th feet. The quantity of solid matter, however, which their fabrics c tain is extremely small. It is not until adult age has been attai that the generative organs make their appearance, in four chamb disposed around the stomach, which are occupied by plaited membr ous ribands containing sperm-cells in the male and ova in the fema and the embryoes evolved from the latter, when they have be fertilised by the agency of the former, repeat the extraordinary cy of phenomena which has been now described, developing themselv in the first instance into hydroid polypes, from which medusoids a subsequently budded off.

This cycle of phenomena is one of those to which the term 'alternation of generations' was applied by Steenstrup,[1] who brought together under this designation a number of cases in which generation A does not produce a form resembling itself, but a different form, ; whilst generation B gives origin to a form which does not resemble itself, but returns to the form A, from which B itself sprang. ; was early pointed out, however, by the Author [2] that the term lternation of generations' does not appropriately represent the cts either of this case or of any of the other cases grouped under e same category, the real fact being that the two organisms, A nd B, constitute two stages in the life-history of *one generation*, nd the production of one form from the other being in only one stance by a truly *generative* or sexual act, whilst in the other it is y a process of *gemmation* or budding. Thus the *Medusæ* of both rders (the 'naked-eyed' and the 'covered-eyed' of Forbes) are detched flower-buds, so to speak, of the hydroid zoöphytes which bud em off, the zoöphytic phase of life being the most conspicuous in ach *Thecata* as *Campanulariida* and *Sertulariida*, whose Medusaads are of small size and simple conformation, and not unfrequently o not detach themselves as independent organisms; whilst the Medusan phase of life is the most conspicuous in the ordinary Acalephs, heir zoöphytic stage being passed in such obscurity as only to be letected by careful research. The Author's views on this subject, vhich were at first strongly contested by Professor E. Forbes, and ther eminent zoölogists, have now come to be generally adopted.[3]

Actinozoa.—Of this group the common sea-anemones may be aken as types, constituting, with their allies, the order *Zoantharia*, r helianthoid polypes, which have numerous tentacles disposed in everal rows. Next to them come the *Alcyonaria*, consisting of hose whose polypes, having always eight broad short tentacles, resent a star-like aspect when expanded; as is the case with various omposite sponge-like bodies, unpossessed of any hard skeleton, which nhabit our own shores, and also with the red coral and the *Tubipora* f warmer seas, which have a stony skeleton that is internal in the rst case and external in the second, as also with the sea-pens and he *Gorgonia* or sea-fans. A third order, *Rugosa*, consists of fossil orals, whose stony polyparies are intermediate in character between hose of the two preceding. And lastly, the *Ctenophora*, free-swimming gelatinous animals, many of which are beautiful objects for ne microscope, are by some zoölogists ranked with the Actinozoa.[4]

Of the *Zoantharia* the common *Actinia* or 'sea-anemone' may e taken as the type, the individual polypites of all the composite abrics included in the group being constructed upon the same model.[5]

[1] See his treatise on *The Alternation of Generations*, a translation of which has en published by the Ray Society.

[2] *Brit. and For. Med. Chir. Review*, vol. i. 1848, p. 192 *et seq.*

[3] Compare Huxley, *Anatomy of Invertebrated Animals*, p. 133; and Balfour, *omparative Embryology*, i. p. 151.

[4] Professor Haeckel, led by the study of *Ctenaria ctenophora*, associates the enophora with the Hydrozoa (*Sitzungsber. Jenaische Gesellschaft*, May 16, 1879).

[5] On the anatomy of *Actinia* and its allies, see O. and R. Hertwig's monograph vols. xiii. and xiv. of the *Jenaische Zeitschrift*.

In by far the larger proportion of these zoöphytes, the bases of the polypites, as well as the soft flesh that connects together the members of aggregate masses, are consolidated by calcareous deposit into stony corals; and the surfaces of these are beset with 'cells,' usually of a nearly circular form, each having numerous vertical plates or *lamellæ* radiating from its centre towards its circumference, which are formed by the consolidation of the lower portions of the radiating partitions that divide the space intervening between the stomach and the general integument of the animal into separate chambers. This arrangement is seen on a large scale in the *Fungia* or 'mushroom-coral' of tropical seas, which is the stony base of a solitary anemone-like animal; on a far smaller scale, it is seen in the little *Caryophyllia*, a like solitary anemone of our own coasts, which is scarcely distinguishable from an Actinia by any other character than the presence of this disc, and also on the surface of many of those stony corals known as 'madrepores'; whilst in some of these the individual polype-cells are so small that the lamellated arrangement can only be made out when they are considerably magnified. Portions of the surface of such corals, or sections taken at a small depth, are very beautiful objects for low powers, the former being viewed by reflected, and the latter by transmitted light. And thin sections of various fossil corals of this group are very striking objects for the lower powers of the oxy-hydrogen microscope. An exceedingly useful method of preparing sections of corals has been devised by Dr. G. von Koch; the corals with all their soft parts in plate are hardened in absolute alcohol, and then placed in a solution of copal in chloroform. After thorough permeation they are taken out and dried slowly until the masses become quite hard. These masses may now be cut into sections with a fine saw and rubbed down on a whetstone in the ordinary manner; after staining, the sections may be mounted in Canada balsam. The great value of this method lies in the fact that by it the soft and hard parts are retained in their proper relations with each other.[1]

The chief point of interest to the microscopist, however, in the structure of these animals lies in the extraordinary abundance and high development of those 'filiferous capsules,' or 'thread-cells,' the presence of which on the tentacles of the hydroid polypes has been already noticed, and which are also to be found, sometimes sparingly, sometimes very abundantly, in the tentacles surrounding the mouth of the Medusæ, as well as on other parts of their bodies. If a tentacle of any of the sea-anemones so abundant on our coasts (the smaller and more transparent kinds being selected in preference) be cut off, and be subjected to gentle pressure between the two glasses of the aquatic box or the compressorium, multitudes of little dart-like organs will be seen to project themselves from its surface near its tip; and if the pressure be gradually augmented, many additional darts will every moment come into view. Not only do these organs present different forms in different species, but even in one and the same individual very strongly marked diversities are shown, of which a few examples are given in fig. 608. At A, B, C, D is

[1] See *Zoologischer Anzeiger*, i. p. 86; and *Proc. Zoöl. Soc.* London, 1880. p. 24.

shown the appearance of the 'filiferous capsules,' whilst as yet the thread lies coiled up in their interior; and at E, F, G, H are seen a few of the most striking forms which they exhibit when the thread or dart has started forth. These thread-cells are found not merely in the tentacles and other parts of the external integument of Actinozoa, but also in the long filaments which lie in coils within the chambers that surround the stomach, in contact with the sexual organs which are attached to the lamellæ dividing the chambers. The latter sometimes contain 'sperm-cells' and sometimes ova, the two sexes being here divided, not united in the same individual. What can be the office of the filiferous filaments thus contained in the interior of the body it is difficult to guess at. They are often found to protrude from rents in the external tegument, when any violence has been used in detaching the animal from its base; and when there is no external rupture they are often forced through the wall of the stomach into its cavity, and may be seen hanging out of the mouth. The largest of these capsules, in their unprotected state, are about $\frac{1}{100}$th of an inch in length; while the thread or dart, in *Corynactis Allmanni*, when fully extended, is not less than $\frac{1}{8}$th of an inch, or thirty-seven times the length of its capsule.[1]



FIG. 608.—Filiferous capsules of *Actinozoa*: A, B, *Corynactis Allmanni*; C, E, F, *Caryophyllia Smithii*; D G, *Actinia crassicornis*; H, *Actinia candida*.

Of the *Alcyonaria* a characteristic example is found in the *Alcyonium digitatum* of our coasts; a lobed sponge-like mass, covered with a tough skin, which is commonly known under the name of 'dead-man's toes,' or by the more elegant name of 'mermaid's fingers.' When a specimen of this is first torn from the rock to which it has attached itself, it contracts into an unshapely mass, whose surface presents nothing

[1] See Mr. Gosse's *Naturalist's Rambles on the Devonshire Coast*, and Professor Möbius, 'Ueber den Bau u.s.w. der Nesselkapseln einiger Polypen und Quallen,' in *Abhandl. Naturw. Vereins zu Hamburg*, Band v. 1866. On the relations of stinging cells to the nervous system, see Dr. v. Lendenfeld, *Quart. Journ. Micros. Sci.* n.s. xxvii. p. 393.

but a series of slight depressions arranged with a certain regularity. But after being immersed for a little time in a jar of sea-water the mass swells out again, and from every one of these depressions an eight-armed polype is protruded, 'which resembles a flower of exquisite beauty and perfect symmetry. In specimens recently taken, each of the petal-like tentacula is seen with a hand-glass to be furnished with a row of delicately slender *pinnæ* or filaments, fringing each margin, and arching onwards; and with a higher power these pinnæ are seen to be roughened throughout their whole length with numerous prickly rings. After a day's captivity, however, the petals shrink up into short, thick, unshapely masses, rudely notched at their edges.' (Gosse.) When a mass of this sort is cut into, it is found to be channelled out somewhat like a sponge by ramifying canals; the vents of which open into the stomachal cavities of the polypes, which are thus brought into free communication with each other, a character that especially distinguishes this order. A movement of fluid is kept up within these canals (as may be distinctly seen through



FIG. 609.—Spicules of *Alcyonium* and *Gorgonia*.



FIG. 610.—A, Spicules of *Gorgonia guttata*; B, spicules of *Muricea elongata*.

their transparent bodies) by means of cilia lining the internal surfaces of the polypes: but no cilia can be discerned on their external surfaces. The tissue of this spongy polypidom is strengthened throughout, like that of sponges, with mineral spicules (always, however, calcareous), which are remarkable for the elegance of their forms; these are disposed with great regularity around the bases of the polypes, and even extend part of their length upwards on their bodies. In the *Gorgonia* or sea-fan, whilst the central part of the polypidom is consolidated into a horny axis, the soft flesh which clothes this axis is so full of tuberculated spicules, especially in its outer layer, that, when this dries up, they form a thick yellowish or reddish incrustation upon the horny stem. This crust is, however, so friable that it may be easily rubbed down between the fingers, and when examined with the microscope it is found to consist of spicules of different shapes and sizes, more or less resembling those shown in figs. 609, 610, sometimes colourless, but sometimes of a beautiful crimson, yellow,

or purple. These spicules are best seen by black-ground illumination, especially when viewed by the binocular microscope. They are, of course, to be separated from the animal substance in the same manner as the calcareous spicules of sponges; and they should be mounted, like them, in Canada balsam. The spicules always possess an organic basis, as is proved by the fact that when their lime is dissolved by dilute acid a gelatinous-looking residuum is left, which preserves the form of the spicule.

The *Ctenophora*, or 'comb-bearers,' are so named from the comb-like arrangement of the rows of tiny 'paddles' by the movement of which the bodies of these animals are propelled. A very beautiful and not uncommon representative of this order is furnished by the *Cydippe pileus* (fig. 611), very commonly known as the *Beroë*, which designation, however, properly appertains to another animal (fig. 612) of the same grade of organisation. The body of *Cydippe* is a nearly



FIG. 611.—*Cydippe pileus*, with its tentacles extended.



FIG. 612.—*Beroë Forskalii*, showing the tubular prolongations of the stomach.

globular mass of soft jelly, usually about $\frac{1}{8}$ths of an inch in diameter; and it may be observed, even with the naked eye, to be marked by eight bright bands, which proceed from pole to pole like meridian lines. These bands are seen with the microscope to be formed of rows of flattened filaments, far larger than ordinary cilia, but lashing the water in the same manner; they sometimes act quite independently of one another, so as to give to the body every variety of motion, but sometimes work altogether. If the sun-light should fall upon them when they are in activity, they display very beautiful iridescent colours. In addition to these 'paddles' the *Cydippe* is furnished with a pair of long tendril-like filaments, arising from the bottom of a pair of cavities in the posterior part of the body, and furnished with lateral branches (A); within these cavities they may lie doubled up, so as not to be visible externally; and when they are ejected, which often happens quite suddenly, the main filaments first come forth, and the lateral tendrils subsequently uncoil themselves, to be drawn in

again and packed up within the cavities with almost equal suddenness. The mouth of the animal situated at one of the poles leads first to a quadrifid cavity bounded by four folds which seem to represent the oral proboscis of the ordinary Medusæ (fig. 606); and this leads to the true stomach, which passes towards the opposite pole, near to which it bifurcates, its branches passing towards the polar surface on either side of a little body which has every appearance of being a nervous ganglion, and which is surmounted externally by a fringe-like apparatus that seems essentially to consist of sensory tentacles.[1] From the cavity of the stomach tubular prolongations pass off beneath the ciliated bands, very much as in the true *Beroë* (B). These may easily be injected with coloured liquids by the introduction of the extremity of a fine-pointed glass syringe into the mouth. The liveliness of this little creature, which may sometimes be collected in large quantities at once by the stick-net, renders it a most beautiful subject for observation when due scope is given to its movements; but for the sake of microscopic examination, it is of course necessary to confine these. Various species of true *Beroë*,[2] some of them even attaining the size of a small lemon, are occasionally to be met with on our coasts, in all of which the movements of the body are effected by the like agency of paddles arranged in meridional bands. These are splendidly luminous in the dark, and the luminosity is retained even by fragments of their bodies, being augmented by agitation of the water containing them. All the *Ctenophora* are reproduced from eggs, and are already quite advanced in their development by the time they are hatched. Long before they escape, indeed, they swim about with great activity within the walls of their diminutive prison, their rows of locomotive paddles early attaining a large size, although the long flexile tentacles of *Cydippe* are then only short stumpy protuberances. By *Coeloplana* and *Ctenoplana* the Ctenophora appear to be allied to the Planarian Worms.[3]

Those who may desire to acquire a more systematic and detailed acquaintance with the zoöphyte group may be especially referred to the following treatises and memoirs, in addition to those already cited, and to the various recent systematic treatises on zoölogy: -Dr. Johnston's *History of British Zoöphytes*; Professor Milne-Edwards' 'Recherches sur les Polypes,' and his 'Histoire des Coralliaires' (in the *Suites à Buffon*), Paris, 1857; Professor Van Beneden, 'Sur les Tubulaires' and 'Sur les Campanulaires,' in *Mém. de l'Acad. Roy. de Bruxelles*, tom. xvii., and his 'Recherches sur l'Hist. Nat. des Polypes qui fréquentent les Côtes de Belgique,' *op. cit.* tom. xxxvi.; Sir J. G. Dalyell's *Rare and Remarkable Animals of Scotland*, vol. ... Trembley's *Mém. pour servir à l'histoire d'un genre de Polype d'eau douce*; M...

[1] It is commonly stated that the two branches of the alimentary canal open on the surface by two pores situated in the hollow of the fringe, one on either side of the nervous ganglion. The Author, however, has not been able to satisfy himself of the existence of such excretory pores in the ordinary *Cydippe* or *Beroë*, although he has repeatedly injected their whole alimentary canal and its extensions, and has attentively watched the currents produced by ciliary action in the interior of the bifurcating prolongations, which currents always appear to him to return as from cæcal extremities. He is himself inclined to believe that this arrangement has reference solely to the nutrition of the nervous ganglion and tentacular apparatus, which lie imbedded (so to speak) in the bifurcation of the alimentary canal, so as to be able to draw its supply of nutriment direct from that cavity.

[2] On the anatomy of *Beroë*, see Eimer, *Zoologische Studien auf Capri. I. Ueber Beroë ovatus*, Leipzig, 1873.

[3] See Korotneff, *Zeitschr. f. Wiss. Zool.* xliii. p. 242.

Hollard's 'Monographie du Genre *Actinia*' in *Ann. des Sci. Nat.* ser. iii. tom. xv.; Professor Max Schultze, 'On the Male Reproductive Organs of *Campanularia geniculata*' in *Quart. Journ. Micr. Sci.* vol. iii. 1855, p. 59; Professor F. E. Schulze's memoirs on *Cordylophora lacustris*, Leipzig, 1871, and on *Syncoryne*, 1873; Professor Agassiz's beautiful monograph on American Medusæ, forming the third volume of his *Contributions to the Natural History of the United States of America*; Mr. Hincks' *British Hydroid Zoöphytes*; Professor Allman's admirable memoirs on *Cordylophora* and *Myriothela* in the *Phil. Trans.* for 1853 and 1875; Professor Lacaze-Duthiers' *Hist. Nat. du Corail*, Paris, 1864, and his essays on the Development of Corals, in vols. i. and ii. of the *Archives de Zool. experimentale*; Professor J. R. Greene's *Manual of the Sub-Kingdom Cœlenterata*, which contains a bibliography very complete to the date of its publication, and the articles 'Actinozoa,' 'Ctenophora,' and 'Hydrozoa' in the supplement to the Natural History Division of the *English Cyclopædia*. The *Ctenophora* are specially treated of in vol. iii. of Professor Agassiz's *Contributions to the Natural History of the United States*. See also Professor Alex. Agassiz's *Sea-side Studies in Natural History* and his *Illustrated Catalogue of the Museum of Comparative Zoölogy at Harvard College*; Professor James Clark in *American Journal of Science*, ser. ii. vol. xxxv. p. 348; Dr. D. Macdonald in *Trans. Roy. Soc. Edinb.* vol. xxiii. p. 515; Mr. H. N. Moseley, 'On the Structure of a Species of *Millepora*,' in *Phil. Trans.* 1877, p. 117, and 'On the Structure of the *Stylasteridæ*,' *ibid.* 1878, p. 425; and on the *Acalephæ*, Professor Haeckel's *Beiträge zur Naturgeschichte der Hydromedusen*; the masterly work of the brothers Hertwig, *Das Nervensystem und die Sinnesorgane der Medusen*, 1878; and the memoir of Professor Schäfer, 'On the Nervous System of *Aurelia aurita*,' in *Phil. Trans.* 1878, p. 563. Of later treatises Professor Ray Lankester's article on Hydrozoa, in the 9th edition of the *Encyclopædia Britannica*; the '*Challenger*' *Reports* of Professor Allman on the Hydroida (Plumularüidæ only), Professor Haeckel on the Medusæ, Professor Moseley on Deep-sea Corals, Dr. R. Hertwig on the Actiniaria, Professors R. P. Wright and Studer on the Alcyonaria, and Mr. George Brook on the Antipatharia; the monographs by Dr. A. Andres on Actiniæ and by Dr. C. Chun on Ctenophora, published in the *Fauna und Flora des Golfes von Neapel*, should be consulted.

CHAPTER XVI

ECHINODERMATA

As we ascend the scale of animal life, we meet with such a rapid advance in complexity of structure that it is no longer possible to acquaint one's self with any organism by microscopic examination of it as a whole; and the dissection or analysis which becomes necessary, in order that each separate part may be studied in detail, belongs rather to the comparative anatomist than to the ordinary microscopist. This is especially the case with the *Echinus* (sea-urchin), *Asterias* (star-fish), and other members of the class Echinodermata, even a general account of whose complex organisation would be quite foreign to the purpose of this work. Yet there are certain parts of their structure which furnish microscopic objects of such beauty and interest that they cannot by any means be passed by; while the study of their embryonic forms, which can be prosecuted by any sea-side observer, brings into view an order of facts of the highest scientific interest.

It is in the structure of that calcareous skeleton which probably exists under some form in every member of this class that the ordinary microscopist finds most to interest him. This attains its highest development in the *Echinoidea*, in which it forms a box-like shell or 'test,' composed of numerous polygonal plates jointed to each other with great exactness, and beset on its external surface with 'spines,' which may have the form of prickles of no great length, or may be stout club-shaped bodies, or, again, may be very long and slender rods. The intimate structure of the shell is everywhere the same: for it is composed of a *network*, which consists of carbonate of lime with a very small quantity of animal matter as a basis, and which extends in every direction (i.e. in thickness as well as in length and breadth), its *areolæ* or interspaces freely communicating with each other (figs. 613, 614). These 'areolæ,' and the solid structure which surrounds them, may bear an extremely variable proportion one to the other; so that in two masses of equal size the one or the other may greatly predominate; and the texture may have either a remarkable lightness and porosity, if the network be a very open one, like that of fig. 613, or may possess a considerable degree of compactness, if the solid portion be strengthened. Generally speaking, the different layers of this network, which are connected together by pillars that pass from one to the other in a direction perpendicu-

lar to their plane, are so arranged that the perforations in one shall correspond to the intermediate solid structure in the next; and their transparence is such that when we are examining a section thin enough to contain only two or three such layers, it is easy, by properly focussing the microscope, to bring either one of them into distinct view. From this very simple but very beautiful arrangement, it comes to pass that the plates of which the entire 'test' is made up possess a very considerable degree of strength, notwithstanding that their porousness is such that if a portion of a fractured edge, or any other part from which the investing membrane has been removed, be laid upon fluid of almost any description, this will be rapidly sucked up into its substance. A very beautiful example of the same kind of calcareous skeleton, having a more regular conformation, is furnished by the disc or 'rosette' which is contained in the tip of every one of the tubular suckers put forth by the living Echinus from the 'ambulacral pores' that are seen in the rows of



FIG. 613.—Section of shell of *Echinus* showing the calcareous network of which it is composed: *a a*, portions of a deeper layer.



FIG. 614.—Transverse section of central portion of spine of *Heterocentrotus*, showing its more open network.

smaller plates interposed between the larger spine-bearing plates of its box-like shell. If the entire disc be cut off, and be mounted when dry in Canada balsam, the calcareous rosette may be seen sufficiently well; but its beautiful structure is better made out when the animal membrane that incloses it has been got rid of by boiling in a solution of caustic potass; and the appearance of one of the five segments of which it is composed, when thus prepared, is shown in fig. 616.

The most beautiful display of this reticulated structure, however, is shown in the conformation of the 'spines' of *Echinus*, *Cidaris*, &c. in which it is combined with solid ribs or pillars, disposed in such a manner as to increase the strength of these organs, a regular and elaborate pattern being formed by their intermixture, which shows considerable variety in different species. When we make a thin transverse section of almost any spine belonging to the genus *Echinus* (the small spines of our British species, however, being exceptional in this respect) or its immediate allies, we see it to be

made up of a number of concentric layers, arranged in a manner t
strongly reminds us of the concentric rings of an exogenous



Fig. 615.—Transverse section of spine of *Echinometra*.

(fig. 615). The number of these layers is extremely variable,
pending not merely upon the age of the spine, but (as will prese
appear) upon the par
its length from which
section happens to
taken. The centre
usually occupied by
very open network
614); and this is boun
by a row of transpa
spaces (like those at
b b', *c c'*, &c. fig. 6
which on a cursory
spection might be
posed to be void, but
found on closer exami
tion to be the section
solid ribs or pillars, wh
run in the direction of the length of the spine, and form the exte
of every layer. Their solidity becomes very obvious when



Fig. 616.— One of the segments of the calcareous skeleton of an ambulacral disc of *Echinus*.

either examine a section of a spine whose substance is pervaded (as often happens) with a colouring matter of some depth, or when we look at a very thin section by black-ground illumination. Around the innermost circle of these solid pillars there is another layer of the calcareous network, which again is surrounded by another circle of solid pillars; and this arrangement may be repeated many times, as shown in fig. 617, the outermost row of pillars forming the projecting ribs that are commonly to be distinguished on the surface of the spine. Around the cup-shaped base of the spine is a membrane which is continuous with that covering the surface of the shell, and serves not merely to hold down the cup upon the tubercle over which it works, but also by its contractility to move the spine in any required direction. The increase in size of the spine appears to be due to the protoplasmic substance which fills up the spaces in the open network of the spine and other skeletal structures. Each new formation completely ensheathes the old; not merely surrounding the part previously formed, but also projecting considerably beyond it: and thus it happens that the number of layers shown in a transverse section



FIG. 617.—Portion of transverse section of spine of *Heterocentrotus mammillatus*.

will depend in part upon the place of that section. For if it cross near the base, it will traverse every one of the successive layers from the very commencement; whilst if it cross near the apex, it will traverse only the single layer of the last growth, notwithstanding that, in the club-shaped spines, this terminal portion may be of considerably larger diameter than the basal: and in any intermediate part of the spine, so many layers will be traversed as have been formed since the spine first attained that length. The basal portion of the spine is enveloped in a reticulation of a very close texture, without concentric layers, forming the cup or socket which works over the tubercle of the shell.

Their combination of elegance of pattern with richness of colouring renders well-prepared specimens of these spines among the most beautiful objects that the microscopist can anywhere meet with. The large spines of the various species of the genus *Heterocentrotus* furnish sections most remarkable for size and elaborateness, as well as for depth of colour (in which last point, however, the deep purple spines of *Echinus lividus* are pre-eminent); but for exquisite

neatness of pattern there are no spines that can approach those of *Echinometra* (fig. 615). The spines of *Stomopneustes variolaris* are also remarkable for their beauty. No succession of concentric layers is seen in the spines of the British *Echini*, probably because (according to the opinion of the late Sir J. G. Dalyell) these spines are cast off and renewed every year, each new formation thus going to make an entire spine, instead of making an addition to that previously existing. Most curious indications are sometimes afforded by sections of Echinus-spines of an extraordinary power of reparation inherent in these bodies. For irregularities are often seen in the transverse sections which can be accounted for in no other way than by supposing the spines to have received an injury when the irregular part was at the exterior, and to have had its loss of substance supplied by the growth of new



FIG. 618.—Transverse section of a spine of *Goniocidaris florigera*, which shows that the prickles on the spine are formed, not by the crust only, but also by the inner reticular tissue. (From Bell.)

tissue, over which the subsequent layers have been formed as usual. And sometimes a peculiar ring may be seen upon the surface of a spine, which indicates the place of a complete fracture, all beyond it being a new growth, whose unconformableness to the older or basal portion is clearly shown by a longitudinal section.[1] The spines of *Cidaris* present a marked departure from the plan of structure exhibited in Echinus; for not only are they destitute of concentric layers, but the calcareous network which forms their principal substance is incased in a solid calcareous sheath perforated with tubules, which seems to take the place of the separate pillars of the Echini. This is usually found to close in the spine at its tip also:

[1] See the Author's description of such reparations in the *Monthly Microscopical Journal*, vol. iii. 1870, p. 225.

and thus it would appear that the entire spine must be formed at once, since no addition could be made either to its length or to its diameter, save on the outside of the sheath, where it is never to be found. The sheath itself often rises up in prominent points or ridges on the surface of these spines; but, as is shown in fig. 618, the reticular portion may have a share in the formation of the rings. This view of the mode of formation of the Cidarid spine is contested by Professor Jeffrey Bell, who has brought forward [1] evidence to show that if two spines of different sizes be taken from two examples of *Cidaris metularia*, also differing in size, the quantity of solid calcareous sheath seen in transverse section is proportionately less in the larger than in the smaller spine; from this he concludes that the growth is due to the internal reticulated portion rather than to the outer crust. The slender, almost filamentary spines



FIG. 619.—Spine of *Spatangus*.

of *Spatangus* (fig. 619) and the innumerable minute hair-like processes attached to the shell of *Clypeaster* are composed of the like regularly reticulated substance [2]; and these are very beautiful objects for the lower powers of the microscope, when laid upon a black ground and examined by reflected light without any further preparation. It is interesting also to find that the same structure presents itself in the curious *Pedicellariæ* (forceps-like bodies often mounted on long stalks), which are found on the surface of many Echinida and Asterida, and the nature of which was formerly a source of much perplexity to naturalists, some having maintained that they were parasites, whilst others considered them as proper appendages of the Echinus itself. The complete conformity which exists between the structure of their skeleton and that of the animal to which they are attached removes all doubt of their being truly appendages to it, as observation of their actions in the living state would indicate.[3]

[1] *Journ. Roy. Micros. Soc.* 1884, p. 845.

[2] A number of rare spines are described and figured by Prof. H. W. Mackintosh in vols. xxvi. (p. 475) and xxviii. (pp. 241 and 259) of the *Trans. Roy. Irish Academy*.

[3] Prof. Alex. Agassiz has shown the relations of the Pedicellariæ to the spines. Much information regarding the various forms of these curious bodies will be found in Professor Perrier's memoir in the *Ann. Sc. Nat.* (5), vols. xii. and xiii.; Mr. Sladen's

Another example of the same structure is found in the peculiar framework of plates which surrounds the interior of the oral orifice of the shell, and which includes the five *teeth* that may often be seen projecting externally through that orifice, the whole forming what is known as the 'lantern of Aristotle.' The texture of the plates or jaws resembles that of the shell in every respect, save that the network is more open; but that of the teeth differs from it so widely as to have been likened to that of the bone and dentine of vertebrate animals. The careful investigations of Mr. James Salter,[1] however, have fully demonstrated that the appearances which have suggested this comparison are to be otherwise explained, the plan of structure of the *tooth* being essentially the same as that of the *shell*, although greatly modified in its working out. The complete tooth has some-



FIG. 620.—Structure of the tooth of *Echinus*: A, vertical section, showing the form of the apex of the tooth as produced by wear, and retained by the relative hardness of its elementary parts; *a*, the clear condensed axis; *b*, the body formed of plates; *c*, the so-called enamel; *d*, the keel. B, commencing growth of the tooth, as seen at its base, showing its two systems of plates; the dark appearance in the central portion of the upper part is produced by the incipient reticulations of the flabelliform processes. C, transverse section of the tooth, showing at *a* the ridge of the keel; at *b* its lateral portion, resembling the shell in texture; at *c c*, the enamel.

what the form of that of the front tooth of a rodent, save that its concave side is strengthened by a projecting 'keel,' so that a transverse section of the tooth presents the form of a ⊥. This keel is composed of cylindrical rods of carbonate of lime, having club-shaped extremities lying obliquely to the axis of the tooth (fig. 620, A. *d*): these rods do not adhere very firmly together, so that it is difficult to keep them in their places in making sections of the part. The

essay in *Ann. and Mag. Nat. Hist.* (5), vi. p. 101; and M. Foettinger's paper in vol. i. p. 455, of the *Archives de Biologie*.

[1] See his memoir, 'On the Structure and Growth of the Tooth of Echinus,' in *Phil. Trans.* for 1861, p. 387. See also Giesbrecht, 'Der feinere Bau der Seeigelzähne,' *Morph. Jahrbuch*, vi. p. 79.

convex surface of the tooth (*c*, *c*, *c*) is covered with a firmer layer, which has received the name of 'enamel.' This is composed of shorter rods, also obliquely arranged, but having a much more intimate mutual adhesion than we find among the rods of the keel. The principal part of the substance of the tooth (A, *b*) is made up of what may be called the 'primary plates.' These are triangular plates of calcareous shell-substance, arranged in two series (as shown at B), and constituting a sort of framework with which the other parts to be presently described become connected. These plates may be seen by examining the growing base of an adult tooth that has been preserved with its attached soft parts in alcohol, or (which is preferable) by examining the base of the tooth of a fresh specimen, the minuter the better. The lengthening of the tooth below, as it is worn away above, is mainly effected by the successive addition of new 'primary plates.' To the outer edge of the primary plates at some little distance from the base we find attached a set of lappet-like appendages, which are formed of similar plates of calcareous shell-substance, and are denominated by Mr. Salter 'secondary plates.' Another set of appendages termed 'flabelliform processes' is added at some little distance from the growing base; these consist of elaborate reticulations of calcareous fibres, ending in fan-shaped extremities. And at a point still further from the base we find the different components of the tooth connected together by 'soldering particles,' which are minute calcareous discs interposed between the previously formed structures; and it is by the increased development of this connective substance that the intervening spaces are narrowed into the semblance of tubuli like those of bone or dentine. Thus a vertical section of the tooth comes to present an appearance very like that of the *bone* of a vertebrate animal, with its lacunæ, canaliculi, and lamella; but in a transverse section the body of the tooth bears a stronger resemblance to *dentine*; whilst the keel and enamel layer more resemble an oblique section of *Pinna* than any other form of shell-structure.

The calcareous plates which form the less compact skeletons of the *Asteroidea* ('star-fish' and their allies) and of the *Ophiuroidea* ('sand-stars' and 'brittle stars') have the same texture as those of the shell of Echinus. And this presents itself, too, in the spines or prickles of their surface when these (as in the great *Goniaster equestris* or 'knotty cushion-star') are large enough to be furnished with a calcareous framework. An example of this kind, furnished by the *Astrophyton*, is represented in fig. 621. The spines with which the arms of the species of *Ophiothrix* ('brittle star') are beset are often remarkable for their beauty of conformation; those of *O. pentaphyllum*, one of the most common kinds, might serve (as Professor E. Forbes justly remarked), in point of lightness and beauty, as



FIG. 621.—Calcareous plate and claw of *Astrophyton*.

models for the spire of a cathedral. These are seen to the greatest advantage when mounted in Canada balsam, and viewed by the binocular microscope with black-ground illumination. It is interesting to remark that the minute tooth of *Ophiothrix* clearly exhibits, with scarcely any preparation, that gradational transition between the ordinary reticular structure of the shell and the peculiar substance of the tooth which in the adult tooth of the *Echinus* can only be traced by making sections of it near its base. The tooth of *Ophiothrix* may be mounted in balsam as a transparent object with scarcely any grinding down ; and it is then seen that the basal portion of the tooth is formed upon the open reticular plan characteristic of the 'shell,' whilst this is so modified in the older portion by subsequent addition that the upper part of the tooth has a bone-like character.

The calcareous skeleton is very highly developed in the *Crinoidea*, their stems and branches being made up of a calcareous network closely resembling that of the shell of the Echinus. This is extremely well seen, not only in the recent *Pentacrinus asterius*, a somewhat rare animal of the West Indian seas, but also in a large proportion of the fossil crinoids, whose remains are so abundant in many of the older geological formations ; for, notwithstanding that these bodies have been penetrated in the act of fossilisation by a mineral infiltration, which seems to have substituted itself for the original fabric (a regularly crystalline cleavage being commonly found to exist in the fossil stems of Encrinites, &c. as in the fossil spines of Echinida), yet their organic structure is often most perfectly preserved.[1] In the circular stems of *Encrinites* the texture of the calcareous network is uniform, or nearly so, throughout ; but in the pentangular *Pentacrini* a certain figure or pattern is formed by variations of texture in different parts of the transverse section.[2]

The minute structure of the shells, spines, and other solid parts of the skeleton of Echinodermata can only be displayed by thin sections made upon the general plan already described in Chapter VI. But their peculiar texture requires that certain precautions should be taken ; in the first place, in order to prevent the section from breaking whilst being reduced to the desirable thickness ; and in the second, to prevent the interspaces of the network from being clogged by the particles abraded in the reducing process, an illustration of a section cut from a spine of *Echinometra* is given in fig. 615. A section of the shell, spine, or other portion of the skeleton should first be cut with a fine saw, and be rubbed on a flat file until it is about as thin as ordinary card, after which it should be smoothed on one side by friction with water on a Water-of-Ayr

[1] The calcareous skeleton even of living Echinoderms has a crystalline aggregation, as is very obvious in the more solid spines of *Echinometræ* &c. ; for it is difficult, in sawing these across, to avoid their tendency to *cleavage* in the oblique plane of calcite. And the Author is informed by Mr. Sorby that the calcareous deposit which fills up the areolæ of the fossilised skeleton has always the same crystalline system with the skeleton itself, as is shown not merely by the uniformity of their cleavage, but by their similar action on polarised light.

[2] See figs. 74–76 of the Author's memoir on 'Shell Structure' in the *Report of the British Association*, 1847.

stone. It should then, after careful washing, be dried, first on white blotting-paper, afterwards by exposure for some time to a gentle heat, so that no water may be retained in the interstices of the network which would oppose the complete penetration of the Canada balsam. Next, it is to be attached to a glass slip by balsam hardened in the usual manner; but particular care should be taken, first, that the balsam be brought to exactly the right degree of hardness, and second, that there be enough not merely to attach the specimen to the glass, but also to saturate its substance throughout. The right degree of hardness is that at which the balsam can be with difficulty indented by the thumb-nail; if it be made harder than this, it is apt to chip off the glass in grinding, so that the specimen also breaks away; and if it be softer, it holds the abraded particles, so that the openings of the network become clogged with them. If, when rubbed down nearly to the required thinness, the section appears to be uniform and satisfactory throughout, the reduction may be completed without displacing it; but if (as often happens) some inequality in thickness should be observable, or some minute air-bubbles should show themselves between the glass and the under surface, it is desirable to loosen the specimen by the application of just enough heat to melt the balsam (special care being taken to avoid the production of fresh air-bubbles) and to turn it over so as to attach the side last polished to the glass, taking care to remove or to break with the needle point any air-bubbles that there may be in the balsam covering the part of the glass on which it is laid. The surface now brought uppermost is then to be very carefully ground down, special care being taken to keep its thickness uniform through every part (which may be even better judged of by the touch than by the eye), and to carry the reducing process far enough, without carrying it too far. Until practice shall have enabled the operator to judge of this by passing his finger over the specimen, he must have continual recourse to the microscope during the latter stages of his work; and he should bear constantly in mind that, as the specimen will become much more translucent when mounted in balsam and covered with glass than it is when the ground surface is exposed, he need not carry his reducing process so far as to produce at once the entire translucence he aims at, the attempt to accomplish which would involve the risk of the destruction of the specimen. In 'mounting' the specimen liquid balsam should be employed, and only a very gentle heat (not sufficient to produce air-bubbles or to loosen the specimen from the glass) should be applied; and if, after it has been mounted, the section should be found too thick, it will be easy to remove the glass cover and to reduce it further, care being taken to harden to the proper degree the balsam which has been newly laid on.

If a number of sections are to be prepared at once (which it is often useful to do for the sake of economy of time, or in order to compare sections taken from different parts of the same spine), this may be most readily accomplished by laying them down, when cut off by the saw, without any preliminary preparation save the blowing of the calcareous dust from their surfaces, upon a thick slip of

glass well covered with hardened balsam ; a large proportion of its surface may thus be occupied by the sections attached to it, the chief precaution required being that all the sections come into equally close contact with it. Their surfaces may then be brought to an exact level by rubbing them down, first upon a flat piece of grit (which is very suitable for the rough grinding of such sections) and then upon a large Water-of-Ayr stone whose surface is 'true. When this level has been attained the ground surface is to be well washed and dried, and some balsam previously hardened is to be spread over it, so as to be sucked in by the sections, a moderate heat being at the same time applied to the glass slide ; and when this has been increased sufficiently to loosen the sections without overheating the balsam, the sections are to be turned over, one by one, so that the *ground* surfaces are now to be attached to the glass slip, special care being taken to press them all into close contact with it. They are then to be very carefully rubbed down, until they are nearly reduced to the required thinness ; and if, on examining them from time to time, their thinness should be found to be uniform throughout, the reduction of the entire set may be completed at once : and when it has been carried sufficiently far, the sections, loosened by warmth, are to be taken up on a camel-hair brush dipped in turpentine, and transferred to separate slips of glass whereon some liquid balsam has been previously laid, in which they are to be mounted in the usual manner. It more frequently happens, however, that, notwithstanding every care, the sections, when ground in a number together, are not of uniform thickness, owing to some of them being underlaid by a thicker stratum of balsam than others ; and it is then necessary to transfer them to separate slips before the reducing process is completed, attaching them with hardened balsam, and finishing each section separately.

A very curious *internal* skeleton, formed of detached plates or spicules, is found in many members of this class, often forming an investment like a coat of mail to some of the viscera, especially the ovaries. The forms of these plates and spicules are generally so diverse, even in closely allied species, as to afford very good differential characters. This subject is one that has been as yet but very little studied, Mr. Stewart being the only microscopist who has given much attention to it,[1] but it is well worthy of much more extended research.

It now remains for us to notice the curious and often very beautiful structures, which represent, in the class *Holothurioidea* the solid calcareous skeleton of the classes already noticed. The greater number of the animals belonging to this order are distinguished by the flexibility and absence of firmness of their envelopes ; and excepting in the case of the various species which have a set of calcareous plates, disposed around the wall of the pharynx, we do not find among them any representation, that is apparent to the unassisted eye, of that skeleton which constitutes so distinctive a feature of the

[1] See his memoir in the *Linnean Transactions*, xxv. p. 365 ; see also Bell, *Journ. Roy. Micros. Soc.* 1882, p. 227.

class generally.[1] But a microscopic examination of their integument at once brings to view the existence of great numbers of minute isolated plates, every one of them presenting the characteristic reticulated structure, which are set with greater or less closeness in



FIG. 622.—Holothurioidea: I, *Stichopus Kefersteinii*; *a*, calcareous plate of same; *b*, *c*, calcareous plates of *Holothuria vagabunda*; *d*, the same of *H. inhabilis*; *e*, the same of *H. botellus*; *f*, of *H. pardalis*; *g*, of *H. edulis*.

the substance of the skin. Various forms of the plates which thus present themselves in *Holothuria* are shown in fig. 622. In the *Synapta*, one of the long-bodied forms of this order, which abounds in the Mediterranean Sea, and of which two species (the *S. digitata* and *S. inhærens*) occasionally occur upon our own coasts,[2] the calcareous plates of the integument have the regular form shown at A,



FIG. 623.—Calcareous skeleton of *Synapta*: A, plate imbedded in skin; B, the same, with its anchor-like spine attached; C, anchor-like spine separated.

fig. 623; and each of these carries the curious anchor-like appendage C, which is articulated to it by the notched piece at the foot, in the manner shown (in side view) at B. The anchor-like appendages

[1] For an account of a very remarkable form see Moseley 'On the Pharynx of an unknown Holothurian, of the family Dendrochirotæ, in which the calcareous skeleton is remarkably developed,' *Quart. Journ. Micros. Sci.* n.s. xxiv. p. 255.

[2] 'On the spicules of *Synapta*, together with some general remarks on the architecture of Echinoderm spicules,' consult R. Semon, *Mitth. Zool. Stat. Neapel*, vii. p. 272.

project from the surface of the skin, and may be considered as representing the spines of Echinida. Nearly allied to the Synapta is the *Chiridota*, the integument of which is entirely destitute of 'anchors,' but is furnished with very remarkable wheel-like plates: those represented in fig. 624 are found in the skin of *Chiridota violacea*, a species inhabiting the western parts of the Indian Ocean. These 'wheels' are objects of singular beauty and delicacy, being especially remarkable for the very minute notching (scarcely to be discerned in the figures without the aid of a magnifying glass) which is traceable round the inner margin of their 'tires.' There can be scarcely any reasonable doubt that almost every member of this class has some kind of calcareous skeleton disposed in a manner conformable to the examples now cited; and it is now generally acknowledged that the marked peculiarities by which they are respectively distinguished are most useful in the determination of genera and species.[1] The plates may be obtained separately by the usual method of treating the skin with a solution of potass, and they should be mounted in Canada balsam. But their position in the skin can only be ascertained by making sections of the integument, both vertical and parallel to its surface; and these sections, when dry, are most advantageously mounted in the same medium, by which their transparence is greatly increased. All the objects of this class are most beautifully displayed by the black-ground illumination, and their solid forms are seen with increased effect under the binocular. The black-ground illumination applied to *very thin* sections of Echinus spines brings out some effects of marvellous beauty; and even in these the solid form of the network connecting the pillars is better seen with the binocular than it can be with the ordinary microscope.[2]



FIG. 624.—Wheel-like plates from skin of *Chiridota violacea*.

Echinoderm Larvæ.—We have now to notice that most remarkable set of objects furnished to the microscopic inquirer by the *larval* states of this class; for our knowledge of which we are chiefly indebted to the painstaking and widely extended investigations of Professor J. Müller.[3] All that our limits permit is a notice of two of the most curious forms of these larvæ by way of sample of the won-

[1] No systematic account of a species of Holothurian can be regarded as complete which does not contain an account of the form of its spicules, when these are present. Figures of various forms will be found in Professor Semper's *Reisen im Archipel der Philippinen: Holothurien*, Dr. Théel's '*Challenger*' *Reports*, and the memoirs of Professors Bell, Ludwig, and Selenka.

[2] It may be here pointed out that the reticulated appearance is sometimes deceptive, what seems to be *solid* network being in many instances a *hollow* network of passages channelled out in a solid calcareous substance. Between these two conditions, in which the relation between the solid framework and the intervening space is completely reversed, there is every intermediate gradation.

[3] Of later works consult especially the 'Selections from Embryological Monographs, ii. Echinodermata,' edited by Mr. A. Agassiz, in vol. ix. of the *Memoirs of the Museum of Comparative Zoölogy*

derful phenomena which his researches brought to light, and to which the attention of microscopists who have the opportunity of studying them should be the more assiduously directed, as even the most delicate of these organisms have been found capable of such perfect preservation as to admit of being studied, when mounted as preparations, even better than when alive. The larval zoöids have, by secondary adaptations to their mode of life, acquired a type quite different from that which characterises the adults ; for instead of a *radial* symmetry they exhibit a *bilateral*, the two sides being precisely alike, and each having a ciliated fringe along the greater part or the whole of its length. The two fringes are united by a superior and an inferior transverse ciliated band, and between these two the mouth of the zoöid is always situated. The external forms of these larvæ, however, vary in a most remarkable degree, owing to the unequal evolution of their different parts ; and there is also a considerable diversity in the several orders as to the proportion of the fabric of the larva which enters into the composition of the adult form. When the young begins to acquire the characters of the fully developed star-fish and sea-urchin, the parts which are not retained shrivel up, and their substance goes to feed the young form.



Fig. 625.—*Bipinnaria asterigera*, or larva of star-fish : *a*, mouth ; *a'*, œsophagus ; *b*, intestinal tube and anal orifice ; *c*, furrow in which the mouth is situated ; *d d'*, bilobed peduncle ; 1, 2, 3, 4, 5, 6, 7, ciliated arms.

One of the most remarkable forms of Echinoderm larvæ is that which has received the name of *Bipinnaria* (fig. 625), from the symmetrical arrangement of its natatory organs. The mouth (*a*), which opens in the middle of a transverse furrow, leads through an œsophagus, *a'*, to a large stomach, around which the body of a star-fish is developing itself ; and on one side of this mouth are observed the intestinal tube and anus (*b*). On either side of the anterior portion of the body are six or more narrow fin-like appendages, which are fringed with cilia ; and the posterior part of the body is prolonged into a sort of pedicle, bilobed towards its extremity, which also is covered with cilia. The organisation of this larva seems completed, and its movements through the water become very active, before the mass at its anterior extremity presents anything of the aspect of the star-fish, in this respect corresponding with the movements of the *Pluteus* of the Echinoidea. The temporary mouth of the larva does not remain as the permanent mouth of the star-fish ; for the œso-

phagus of the latter enters on what is to become the dorsal side of its body, and the true mouth is subsequently formed by the thinning away of the integument on its ventral surface. The young star-fish is separated from the Bipinnarian larva by the forcible contractions of the connecting stalk, as soon as the calcareous consolidation of its integument has taken place and its true mouth has been formed, but long before it has attained the adult condition ; and as its ulterior development has not hitherto been observed in any instance, it is not yet known what are the species in which this mode of evolution prevails. The larval zoöid continues active for several days after its detachment ; and it is possible, though perhaps scarcely probable, that it may develop another asteroid by a repetition of this process of gemmation.

In the Bipinnaria, as in other larval zoöids of the *Asteroidea*, there is no internal calcareous framework ; such a framework, however, is found in the larvæ of the *Echinoidea* and *Ophiuroidea*, of which the form delineated in fig. 626 is an example. The embryo issues from the ovum as soon as it has attained, by repeated 'segmentation' of the yolk, the condition of the 'mulberry-mass,' and the superficial cells of this are covered with cilia by whose agency it swims freely through the water. So rapid are the early processes of development that no more than from twelve to twenty-four hours intervene between fecundation and the emersion of the embryo, the division into two, four, or even eight segments taking place within three hours after impregnation. Within a few hours after its emersion the embryo changes from the spherical into a subpyramidal form with a flattened base ; and in the centre of this base is a depression, which gradually deepens, so as to form a mouth that communicates with a cavity in the interior of the body which is surrounded by a portion of the yolk-mass that has returned to the liquid granular state. Subsequently a short intestinal tube is found, with an anal orifice opening on one side of the body. The pyramid is at first triangular, but it afterwards becomes quadrangular ; and the angles are greatly prolonged round the mouth (or base), whilst the apex of the pyramid is sometimes much extended in the opposite direction, but is sometimes rounded off into a kind of dome (fig. 626, A). All parts of this curious body, and especially its most projecting portions, are strengthened by a framework of thread-like calcareous rods (*e*). In this condition the embryo swims freely through the water, being propelled by the action of the cilia, which clothe the four angles of the pyramid and its projecting arms, and which are sometimes thickly set upon two or four projecting lobes (*f*) ; and it has received the designation of *Pluteus*. The mouth is usually surrounded by a sort of proboscis, the angles of which are prolonged into four slender processes (*g, g, g, g*), shorter than the four outer legs, but furnished with a similar calcareous framework.

The first indication of the production of the young Echinus from its 'pluteus' is given by the formation of a circular disc (fig. 626, A, *c*) on one side of the central stomach (*b*) ; and this disc soon presents five prominent tubercles (B), which subsequently become elongated into tubular processes, which will form the 'sucking-

feet' of the adult. The disc gradually extends itself over the stomach, and between its tubules the rudiments of spines are seen to protrude (D); these, with the tubules, increase in length, so as to project against the envelope of the pluteus, and to push themselves through it; whilst, at the same time, the original angular appendages of the pluteus diminish in size, the ciliary movement becomes less active, being superseded by the action of the suckers and spines, and the mouth of the pluteus closes up. By the time that the disc has grown over half of the gastric sphere, very little of the pluteus remains, except some of the slender calcareous rods, and the number of suckers and spines rapidly increases. The calcareous framework of the shell at first consists, like that of the star-fishes, of a series of isolated networks developed between the cirrhi, and upon these rest the first formed spines (D). But they gradually become more consolidated, and extend themselves over the granular mass, so as to form the series of plates constituting the shell. The mouth of the Echinus (which is altogether distinct from that of the pluteus) is formed at that side of the granular mass over which the shell is last extended; and the first indication of it consists in the appearance of the five calcareous concretions, which are the summits of the five portions of the framework of jaws and teeth that surround it. All traces of the original pluteus are now lost; and the larva, which now presents the general aspect of an Echinoid animal, gradually augments in size, multiplies the number of its plates, cirrhi, and



FIG. 626.—Embryonic development of *Echinus*: A, *Pluteus larva* at the time of the first appearance of the disc; *a*, mouth, in the midst of the four-pronged proboscis; *b*, stomach; *c*, Echinoid disc; *d*, *d*, *d*, *d*, four arms of the pluteus-body; *e*, calcareous framework; *f*, ciliated lobes; *g*, *g*, *g*, *g*, ciliated processes of the proboscis; B, disc with the first indication of the sucking-feet; C, disc, with the origin of the spines between the tubular sucking-feet; D, more advanced disc, with the feet, *g*, and spines, *x*, projecting considerably from the surface. (N.B.—In B, C, and D, the Pluteus is not represented, its parts having undergone no change, save in becoming relatively smaller.)

spines, evolves itself into its particular generic and specific type, and undergoes various changes of internal structure, tending to the development of the complete organism.[1]

An excellent summary of the developmental history of the several Echinoderm types, with references to the principal memoirs which treat of it, will be found in Chapter XX. of Mr. Balfour's 'Comparative Embryology.' In collecting the free-swimming larvæ of Echinodermata the stick-net should be carefully employed in the manner already described, and the search for them is of course most likely to be successful in those localities in which the adult forms of the respective species abound, and on warm calm days, in which they seem to come to the surface in the greatest numbers. The following mode of preparing and mounting them has been kindly communicated to the Author by Mr. Percy Sladen :—'For killing and preserving echinoderm zoöids, I have come to prefer either osmic acid or the picro-sulphuric mixture of Kleinenberg of one-third strength. The latter, of course, destroys all calcareous structures: but the soft parts are preserved in a wonderful manner. If the diluted Kleinenberg's mixture is used, let the zoöids remain in it for one or two hours ; then wash them *thoroughly* in 70 per cent. spirit, until all trace of acid is removed ; then stain ; then again wash in 70 per cent. spirit, transfer them to 90 per cent. spirit for some hours, and lastly to absolute alcohol. Transfer them from this to oil of cloves ; and finally mount in Canada balsam in the usual manner. If osmic acid be used, place three or four of the living zoöids in a watch-glass of sea-water, and add a drop of the 1-per-cent. solution. They should not remain even in this weak solution for more than a minute, and should then be thoroughly washed in a superabundance of 35 per cent. spirit, to prevent the deposit of crystals of salt consequent on the action of the osmic acid. Then transfer the specimens to 70 per cent. spirit, and proceed as in the other case.'

One of the most interesting to the microscopist of all Echinodermata is the *Antedon*[2] (more generally known as *Comatula*), or 'feather-star' (fig. 627), which is the commonest existing representative of the great fossil series of *Crinoidea*, or 'lily-stars,' that were among the most abundant types of this class in the earlier epochs of the world's history. Like these, the young of Antedon is attached by a stalk to a fixed base, part of which is shown in fig. 628 ; but when it has arrived at a certain stage of development it drops off from this like a fruit from its stalk, and the animal is thenceforth free to move through the ocean water it inhabits. It can swim with considerable activity, but it exerts this power chiefly to gain a suitable place for attaching itself by means of the jointed prehensile cirrhi put forth from the aboral (under) side of the central disc (fig. 627) ;

[1] An abbreviated development, in which there is no free-swimming larva, is now known to be more common than was once supposed: among Holothurians *Cucumaria crocea*, among Ophiuroids *Ophiacantha vivipara*, and among Echinoids *Hemiaster cavernosus* may be cited as examples.

[2] See the Author's 'Researches on the Structure, Physiology, and Development of *Antedon rosaceus*,' Part I. in *Phil. Trans.* 1866, p. 671.

so that, notwithstanding its locomotive power, it is nearly as stationary in its free adult condition as it is in its earlier pentacrinoid stage. The *pentacrinoid larva*[1]—first discovered by Mr. J. V. Thompson, of Cork, in 1823, but originally supposed by him to be a permanently attached Crinoid—forms a most beautiful object for the lower powers of the microscope, when well preserved in fluid, and viewed by a strong incident light (fig. 628, 3); and a series of specimens in different stages of development shows most curious modifications in the form and arrangement of the various component pieces of its calcareous skeleton. In its earliest stage (fig. 628, 1) the body is inclosed in a calyx composed of two circles of plates, namely, five *basals*, forming a sort of pyramid whose apex points downwards, and is attached to the highest joint of the stem; and five *orals* superposed on these, forming when closed a like pyramid whose apex points upwards, but usually separating to give passage to the tentacles, of which a circlet surrounds the mouth. In this condition there is no rudiment of arms. In the more advanced stage shown at 2,



FIG. 627.—*Antedon* (Comatula), or feather-star, seen from its aboral side.

the arms have begun to make their appearance, and the skeleton when carefully examined is found to consist of the following pieces, as shown in fig. 628, 1, *b*, *b*, the circlet of *basals* supported on the top of the stem; r^1, the circle of *first radials*, now interposed between the basals and the orals, and alternating with both; between two of these is interposed the single *anal* plate *a*; whilst they support the *second* and the *third radials* (r^2, r^3), from the latter of which the bifurcating arms spring; finally, between the second radials we see the five *orals* lifted from the basals on which they originally rested by the interposition of the first radials. In the more advanced stage shown in fig. 628, 3, we find the highest joint of the stem beginning to enlarge, to form the *centro-dorsal* plate (2, *c d*), from which are beginning to spring the dorsal cirrhi (*cir*) that serve to anchor the animal when it drops from the stem; this supports the

[1] The pentacrinoid larvæ of *Antedon* have been found abundantly (attached to sea-weeds and zoöphytes) at Millport, on the Clyde, and in Lamlash Bay, Arran; in Kirkwall Bay, Orkney; in Lough Strangford, near Belfast, and in the Bay of Cork; and at Ilfracombe and in Salcombe Bay, Devon.



FIG. 628.—Pentacrinoid larva of *Antedon*. 1. Skeleton of early pentacrinoid, under black-ground illumination, showing its component plates: *b, b*, basals, articulated below to the highest point of the stem; r^1, r^1, first radials, between two of which is seen the single anal plate, *a*; r^2, second radials; r^3, third radials, giving off the bifurcating arms at their summit; *o, o*, orals. 2, 3. Back and front views of a more advanced pentacrinoid, as seen by incident light, one of the pair of arms being cut away in fig. 3 in order to bring the mouth and its surrounding parts into view: *b, b*, basals; r^1, r^2, r^3, first, second, and third radials; *a*, anal, now carried upwards by the projection of the vent, *v*; *o, o*, orals; *cir*, dorsal cirrhi, developed from the highest joint of the stem.

basals, on which rest the *first radials* (r^1); whilst the *anal* plate is now lifted nearly to the level of the *second radials* (r^2) by the development of the anal funnel or vent to which it is attached. The *oral* plates are not at first apparent, as they no longer occupy their first position; but on being carefully looked for they are found still to form a circlet around the mouth (3, *o*, *o*), not having undergone any increase in size, whilst the visceral disc and the calyx in which it is lodged have greatly extended. These *oral* plates finally disappear by absorption; while the *basals* are at first concealed by the great enlargement of the centro-dorsal (which finally extends so far as to conceal the first radials also); and at last undergo metamorphosis into a beautiful 'rosette,' which lies between the cavity of the centro-dorsal and that of the calyx. In common with other members of its class, the *Antedon* is represented in its earliest phase of development by a free-swimming 'larval zoöid' or *pseudembryo*, which was first observed by Busch, and has been since carefully studied by Professors Wyville Thomson[1] and Goette.[2] This zoöid has an elongated egg-like form, and is furnished with transverse bands of cilia and with a mouth and anus of its own. After a time, however, rudiments of the calcareous plates forming the stem and calyx begin to show themselves in its interior; a disc is then formed at the posterior extremity by which it attaches itself to a sea-weed (very commonly *Laminaria*), zoöphyte, or polyzoary; the calyx containing the true stomach, with its central mouth surrounded by tentacles, is gradually evolved; and the sarcodic substance of the pseudembryo, by which this calyx and the rudimentary stem were originally invested, gradually shrinks, until the young pentacrinoid presents itself in its characteristic form and proportions.[3]

[1] 'On the Development of *Antedon rosaceus*' in *Phil. Trans.* for 1865, p. 513.

[2] *Archiv f. Mikrosk. Anat.* Bd. xii. p. 583.

[3] The general results of the Author's own later studies of this most interesting type (the key to the life-history of the entire geological succession of *Crinoidea*) are embodied in a notice communicated to the *Proceedings of the Royal Society* for 1876, p. 211, and in a subsequent note, p. 451. Of the further contributions recently made to our knowledge of it the memoir of Dr. H Ludwig 'Zur Anatomie der Crinoideen' (Leipzig, 1877), forming part of his *Morphologische Studien an Echinodermen*, is the most important. Those who wish to carry further their study of the Crinoidea should consult the two monographs by Dr. P. Herbert Carpenter in the '*Challenger*' *Reports*.

CHAPTER XVII

POLYZOA AND TUNICATA

As in previous editions of this work the Author followed the prevalent habit of regarding the Polyzoa and Tunicata as structurally allied, and as it would be necessary to entirely recast the work were the two groups to be now otherwise dealt with, and as, finally, there is no real inconvenience or impropriety in discussing them in one chapter, it is proposed to continue, with this word of warning, the original arrangement of the Author. Some members of both these groups are found on almost every coast, and are most interesting objects for anatomical examination, as well as for observation in the living state.

Polyzoa.—The group which is known under this name to British naturalists (corresponding with that which by Continental zoölogists is designated *Bryozoa*) was formerly ranked as an order of zoöphytes, and it has been entirely by microscopic study that its comparatively high organisation has been ascertained. The animals of the Polyzoa, in consequence of their universal tendency to multiplication by gemmation, are seldom or never found solitary, but form clusters or colonies of various kinds: and as each is inclosed in either a horny or a calcareous sheath or 'cell,' a composite structure is formed, closely corresponding with the 'polypidom' of a zoöphyte, which has been appropriately designated the *polyzoary*. The individual cells of the polyzoary are sometimes only connected with each other by their common relation to a creeping stem or *stolon*, as in *Lagunecula* (fig. 629); but more frequently they bud forth directly, one from another, and extend themselves in different directions over plane surfaces, as is the case with *Flustra*, *Lepralia*, &c. (fig. 630); whilst not unfrequently the polyzoary develops itself into an arborescent structure (fig. 631), which may even present somewhat of the density and massiveness of the stony corals. Each individual is composed externally of a sort of sac, of which the outer or tegumentary layer is either simply membranous, or is horny, or in some instances calcified, so as to form the cell; this investing sac is lined by a more delicate membrane, which closes its orifice, and which then becomes continuous with the wall of the alimentary canal: this lies freely in the visceral sac, floating (as it were) in the liquid which it contains.

The principal features in the structure of this group will be best understood from the examination of a characteristic example, such as the *Lagunecula repens*, which is shown in the state of expansion at A, fig. 629, and in the state of contraction at B and C. The mouth is

surrounded by a circle of tubular tentacles, which are clothed by vibratile cilia; these tentacles, in the species we are considering, vary from ten to twelve in number, but in some other instances they are more numerous. By the ciliary investment of the tentacles the Polyzoa are at once distinguishable from those hydroid polypes to which they bear a superficial resemblance, and with which they were at one time confounded; and accordingly, whilst still ranked among zoöphytes, they were characterised as *ciliobrachiate*. The tentacula are seated upon an annular disc, which is termed the *lophophore*, and which forms the roof of the visceral or perigastric cavity; and this cavity extends itself into the interior of the tentacula,[1] through perforations in the lophophore, as is shown at D, fig. 630, representing a portion of the tentacular circle on a larger scale, *a a* being the tentacula, *b b* their internal canals, *c* the muscles of the tentacula, *d* the lophophore, and *e* its retractile muscles. The mouth situated in the centre of the lophophore, as shown at A, leads to a funnel-shaped cavity or pharynx, *b*, which is separated from the œsophagus, *d*, by a valve at *c*; and this œsophagus opens into the stomach, *e*, which occupies a considerable part of the visceral cavity. (In the *Bower-*



FIG. 629.—Structure of *Lagunecula repens* (Van Beneden). A, polypide expanded; B, polypide retracted; C, another view of the same, with the visceral apparatus in outline, that the manner in which it is doubled on itself, with the tentacular crown and muscular system, may be more distinctly seen: *a a*, tentacula; *b*, pharynx; *c*, pharyngeal valve; *d*, œsophagus; *e*, stomach; *f*, its pyloric orifice; *g*, cilia on its inner surface; *h*, biliary follicles lodged in its wall; *i*, intestine; *k*, particles of excrementitious matter; *l*, anal orifice; *m*, testis; *n*, ovary; *o*, ova lying loose in the perivisceral cavity; *p*, outlet for their discharge; *q*, spermatozoa in the perivisceral cavity; *r*, *s*, *t*, *u*, *v*, *w*, *x*, muscles. D, portion of the lophophore more enlarged: *a a*, tentacula; *b b*, their internal canals; *c*, their muscles; *d*, lophophore; *e*, its retractor muscles.

[1] This communication between the tentacular and visceral cavities is denied by Dr. Vigelius, who has recently made a careful search for it.

bankia and some other Polyzoa a muscular stomach or gizzard for trituration of the food intervenes between the œsophagus and true digestive stomach.) The walls of the stomach, *h*, have consi able thickness, and the epithelial cells which line them seem to h the character of a rudimentary digestive gland. This, howeve more obvious in some other members of the group. The stomac lined, especially at its upper part, with vibratile cilia, as seen at and by the action of these the food is kept in a state of cons agitation during the digestive process. From the upper part of stomach, which is (as it were) doubled upon itself, the intestin opens, by a pyloric orifice, *f*, which is furnished with a regular va within the intestine are seen at *k* particles of excrementitious ma which are discharged by the anal orifice at *l*. No special circula apparatus here exists ; but the liquid which fills the cavity that rounds the viscera tains the nutri matter which has prepared by the di tive operation, which has transu through the walls the alimentary ca a few corpuscles o regular size are see float in it. No o respiratory organs than the tentacula, whose cavity the n tive fluid is prob sent from the visceral cavity for tion by the curren water that is cont ally flowing over t



FIG. 630.—Cells of *Polyzoa* : A, *Mastigophora Hyndmanni*; B, *Cribrilina figularis*; C, *Umbonula verrucosa*.

The productio *gemmæ* or buds take place either from the bodies of the polypides themselves, w is what always happens when the cells are in mutual apposi or from the connecting stem or 'stolon,' where the cells are dis one from the other, as in *Laguncula*. In the latter case the first seen a bud-like protuberance of the horny external int ment, into which the soft membranous lining prolongs itself ; cavity thus formed, however, is not to become (as in Hydra an allies) the stomach of the new zoöid, but it constitutes the cha surrounding the digestive viscera, which organs have their o in a thickening of the lining membrane that projects from one of the cavity into its interior, and gradually shapes itself into alimentary canal with its tentacular appendages. Of the pro tion of gemmæ from the polypides themselves the best examples furnished by the *Flustræ* and their allies. From a single cell of Flustra five such buds may be sent off, which develop themse

into new polypides around it ; and these in their turn produce buds from their unattached margins, so as rapidly to augment the number of cells. To this extension there seems no definite limit, and it often happens that the cells in the central portion of the leaf-like expansion of a Flustra are devoid of contents and have lost their vitality, whilst the edges are in a state of active growth.[1] Independently of their propagation by gemmation, the Polyzoa have a true sexual generation, the sexes, however, being usually, if not invariably, united in the same polypides. The sperm-cells are developed in a glandular body, the testis, *m*, which lies beneath the base of the stomach, or they are developed from large portions of the inner surface of the body-wall ; when mature they rupture, and set free the spermatozoa, *q q*, which swim freely in the liquid of the visceral cavity. The ova, on the other hand, are formed in an ovarium, *n*, which is lodged in the membrane lining the tegumentary sheath near its outlet or is placed near the end of the cæcal process of the stomach ; the ova, having escaped from this into the visceral cavity, as at *o*, are fertilised by the spermatozoa which they there meet with, and are finally discharged by an outlet at *p*, beneath the tentacular circle.

These creatures possess a considerable number of muscles, by which their bodies may be projected from their sheaths, or drawn within them ; of these muscles, *r*, *s*, *t*, *u*, *v*, *w*, *x*, the direction and points of attachment sufficiently indicate the uses ; they are for the most part *retractors*, serving to draw in and double up the body, to fold together the circle of tentacula, and to close the aperture of the sheath, when the animal has been completely withdrawn into its interior. The *projection* and *expansion* of the animal, on the contrary, appear to be chiefly accomplished by a general pressure upon the sheath, which will tend to force out all that can be expelled from it. The tentacles themselves are furnished with distinct muscular fibres, by which their separate movements seem to be produced. At the base of the tentacular circle, just above the anal orifice, is a small body (seen at A, *a*), which is a nervous ganglion ; as yet no branches have been distinctly seen to be connected with it in this species ; but its character is less doubtful in some other Polyzoa. Besides the independent movements of the individual polypides, other movements may be observed, which are performed by so many of them simultaneously as to indicate the existence of some connecting agency ; and such connecting agency, it is affirmed by Dr. Fritz Müller,[2] is furnished by what he terms a 'colonial nervous system.' In a *Serialaria* having a branching polyzoary that spreads itself on sea-weeds over a space of three or four inches, he states that a nervous ganglion may be distinguished at the origin of each branch, and another ganglion at the origin of each polypide-bud, all these ganglia being connected together, not merely by principal trunks, but also by plexuses of nerve-fibres, which may be distinctly made

[1] For further details consult Haddon 'On Budding in Polyzoa,' *Quart. Journ. Micros. Sci.* xxiii. p. 516.

[2] See his memoir in *Wiegmann's Archiv*, 1860, p. 311, translated in *Quart. Journ. of Micros. Sci.* n.s. vol. i. 1861, p. 300 ; Rev. T. Hincks' 'Note on the Movements of the Vibracula in *Caberea boryi*, and on the supposed common Nervous System in the Polyzoa,' *Quart. Journ. Micros. Sci.* xviii. p. 7.

out with the aid of chromic acid in the cylindrical joints of the polyzoary. His views, however, have not been universally accepted, observers of great histological experience maintaining that what he regards as nerve-fibres are only connective tissue.

Of all the Polyzoa of our own coasts the *Membraniporidæ*, or 'sea-mats' (*Flustra*, *Membranipora*) are the most common; these present flat expanded surfaces resembling in form those of many sea-weeds (for which they are often mistaken), but exhibiting, when viewed with even a low magnifying power, a most beautiful network, which at once indicates their real character. The cells are generally arranged on both sides, and it was calculated by Dr. Grant that as a single square inch of an ordinary Flustra contains 1,800 such cells, and as an average specimen presents about ten square inches of surface, it will consist of no fewer than 18,000 polypides. The want of transparence in the cell-wall, however, and the infrequency with which the animal projects its body far beyond the mouth of the cell, render the species of this genus less favourable subjects for microscopic examination than are those of the *Bowerbankia*, a polyzoon with a trailing stem and separated cells like those of Laguncula, which is very commonly found clustering around the base of masses of Flustræ. It was in this that many of the details of the organisation of the interesting group we are considering were first studied by Dr. A. Farre, who discovered it in 1837, and subjected it to a far more minute examination than any polyzoön had previously received;[1] and it is one of the best adapted of all the marine forms yet known for the display of the beauties and wonders of this type of organisation. The Alcyonidium, however, is one of the most remarkable of all the marine forms for the comparatively large size of the tentacular crowns, these, when expanded, being very distinctly visible to the naked eye, and presenting a spectacle of the greatest beauty when viewed under a sufficient magnifying power. The polyzoary of this genus has a spongy aspect and texture, very much resembling that of certain Alcyonian zoöphytes, for which it might readily be mistaken when its contained animals are all withdrawn into their cells; when these are expanded, however, the aspect of the two is altogether different, as the minute plumose tufts which then issue from the surface of the Alcyonidium, making it look as if it were covered with the most delicate downy film, are in striking contrast with the larger solid-looking polypes of the Alcyonium. The opacity of the polyzoary of the Alcyonidium renders it quite unsuitable for the examination of anything more than the tentacular crown and the œsophagus which it surmounts, the stomach and the remainder of the visceral apparatus being always retained within the cell. It furnishes, however, a most beautiful object for the binocular microscope, when mounted with all its polypides expanded.[2] Several of the fresh-water Polyzoa are peculiarly interesting subjects for microscopic examination, alike

[1] See his memoir 'On the Minute Structure of some of the Higher Forms of Polypi,' in the *Phil. Trans.* for 1837, p. 387.

[2] Mr. J. Lomas has recently detected calcareous spicules in *Alcyonidium gelatinosum*, and finds that they are more abundant in older than in younger colonies. See *Proceedings of the Liverpool Geological Society*, v. p. 241.

on account of the remarkable distinctness with which the various parts of their organisation may be seen and the very beautiful manner in which their ciliated tentacula are arranged upon a deeply crescentic or horse-shoe-shaped *lophophore*. By this peculiarity the fresh-water Polyzoa are distinguished from the marine; and they, with the marine *Rhabdopleura*, may be further distinguished by the possession of an epistome, or movable process above the mouth, whence Professor Allman calls them the *Phylactolæmata*, as compared with the others which are *Gymnolæmata*, or have no epistome. The cells of the *Phylactolæmata* are for the most part lodged in a sort of gelatinous sub-stratum which spreads over the leaves of aquatic plants, sometimes forming masses of considerable size; but in the very curious and beautiful *Cristatella* the polyzoary is unattached, so as to be capable of moving freely through the water.[1]

In the marine Polyzoa, constituting by far the most numerous division of the class, the anus either opens outside (Ectoprocta) or within (Entoprocta) the circlet of tentacles; the former comprise three groups:—I. *Cheilostomata*, in which the mouth of the cell is *sub-terminal*, or not quite at its extremity (fig. 630), is somewhat crescentic in form, and is furnished with a movable (generally membranous) lip, which closes it when the animal retreats. This includes a large part of the species that most abound on our own coast, notwithstanding their wide differences in form and habit. Thus the polyzoaries of some (as *Flustra*) are horny and flexible, whilst those of others (as *Eschara* and *Retepora*) are so penetrated with calcareous matter as to be quite rigid; some grow as independent plant-like structures (as *Bugula* and *Gemellaria*), whilst others, having a like arborescent form, creep over the surfaces of rocks or stones (as *Hippothoa*); and others, again, have their cells in close apposition, and form crusts which possess no definite figure (as is the case with *Lepralia* and *Membranipora*). II. The second order, *Cyclostomata*, consists of those Polyzoa which have the mouth at the *termination* of tubular calcareous cells, without any movable appendage or lip (fig. 631). This includes a comparatively small number of genera, of which *Crisia* and *Tubulipora* contain the largest proportion of the species that occur on our own coasts. III. The distinguishing character of the third order, *Ctenostomata*, is derived from the presence of a comb-like circular fringe of bristles, connected by a delicate membrane, round the mouth of the cell, when the animal is projected from it, this fringe being drawn in when the animal is retracted. The polyzoaries of this group are very various in character, the cells being sometimes horny and separate (as in *Farrella* and *Bowerbankia*), sometimes fleshy and coalescent (as in *Alcyonidium*). IV. In the *Entoprocta*, which are represented by *Loxosoma* and *Pedicellina*, and are doubtless the most archaic of the true Polyzoa, the lophophore is produced upwards on the back of the tentacles, uniting them at their base in a sort of muscular calyx, and giving to the animal when expanded somewhat the form of an inverted bell, like

[1] See Professor Allman's beautiful *Monograph of the British Fresh-water Polyzoa*, published by the Ray Society, 1857; and J. Jullien, 'Monographie des Bryozoaires d'eau douce,' *Bull. Soc. Zool. de France*, x. p. 91.

that of *Vorticella* (fig. 537). As the Polyzoa altogether resem
hydroid zoöphytes in their habits, and are found in the same localiti
it is not requisite to add anything to what has already been s
respecting the collection, examination, and mounting of this v
interesting class of objects.[1]

A large proportion of the *Cheilostomata* are furnished with v
peculiar motile appendages, which are of two kinds, *avicularia* a
vibracula. The avicularia or 'bird's head processes,' so named fr
the striking resemblance they present to the head and jaws of a b
(fig. 631, B), are genera
when highly differentia
'sessile' upon the an
or margins of the c
that is, are attached
once to them without
intervention of a stalk
at A, being either 'i
jecting' or 'immersed';
in the genera *Bugula*
Bicellaria, where they
present at all, they
'pedunculate,' or mou
on foot-stalks (B). Ur
one form or the other, t
are wanting in but fe
the genera belonging
this order: and their
sence or absence furni
valuable characters for
discrimination of spe
Each avicularium has
'mandibles,' of which
is fixed, like the upper
of a bird, the other u
able, like its lower jaw:
latter is opened and cl
by two sets of mus
which are seen in the interior of the 'head,' and between them
peculiar body, furnished with a pencil of bristles, which is probab
tactile organ, being brought forwards when the mouth is oper



FIG. 631.—A, portion of *Bicellaria ciliata*, enlarged; B, one of the 'bird's-head' processes of *Bugula avicularia*, more highly magnified, and seen in the act of grasping another.

[1] For a more detailed account of the structure and classification of the m
Polyzoa see Professor Van Beneden's 'Recherches sur les Bryozoaires de la
d'Ostende' in *Mém. de l'Acad. Roy. de Bruxelles*, tom. xvii.; Mr. G. B
Catalogue of the Marine Polyzoa in the Collection of the British Museum;
Hincks' *British Marine Polyzoa*, 1880; and Nitsche, 'Beiträge zur Kenntnis
Bryozoën,' in *Zeitschrift f. Wiss. Zool.* Bde. xx. xxi. xxiv. Of the more impo
recent publications we may note Mr. Busk's Reports on the Polyzoa of the *Challe*
voyage; Mr. Harmer, 'On the Structure and Development of *Loxosoma*' and
the Life-history of *Pedicellina*,' in vols. xxv. and xxvi. of the *Quart. Jour*
Micros. Sci.; J. Barrois, 'Recherches sur l'Embryologie des Bryozoaires,' Lille,
and other memoirs; W. J. Vigelius, 'Morphologische Untersuchungen über *Fis*
Membranaceo-truncata,' *Biolog. Centralblatt*, iii. p. 705, and *Bijdragen to*
Dierkunde, xi. For a general account see Professor Ray Lankester's article 'Poly
in the 9th edition of the *Encyclopædia Britannica*.

that the bristles project beyond it, and being drawn back when the mandible closes. The avicularia keep up a continual snapping action during the life of the polyzoary; and they may often be observed to lay hold of minute worms or other bodies, sometimes even closing upon the beaks of adjacent organs of the same kind, as shown at B. In the pedunculate forms, besides the snapping action, there is a continual rhythmical nodding of the head upon the stalk; and few spectacles are more curious than a portion of the polyzoary of *Bugula avicularia* (a very common British species) in a state of active vitality, when viewed under a power sufficiently low to allow a number of these bodies to be in sight at once. It is still very doubtful what is their precise function in the economy of the animal—whether it is to retain within the reach of the ciliary current bodies that may serve as food, or whether it is, like the Pedicellariæ of Echini, to remove extraneous particles that may be in contact with the surface of the polyzoary. The latter would seem to be the function of the *vibracula*, which are long bristle-shaped organs (fig. 630, A), each one springing at its base out of a sort of cup that contains muscles by which it is kept in almost constant motion, sweeping slowly and carefully over the surface of the polyzoary, and removing what might be injurious to the delicate inhabitants of the cells when their tentacles are protruded. Out of 191 species of Cheilostomatous Polyzoa described by Mr. Busk, no fewer than 126 are furnished either with avicularia, or with vibracula, or with both these organs.[1]

Tunicata.—The zoölogical position of the Tunicata, which has long been a subject of great discussion, appears to be now approximately settled; the study of their development has shown that they are provided with a notochord, and that their nervous system follows the course which is characteristic of what are often called *Vertebrata*, but should better be called *Chordata*. As the notochord is always restricted to the hinder part of the body, the Tunicata may be called Urochordata. In all (except, perhaps, *Appendicularia*) there are distinct signs of degeneration. They have been named Tunicata from the inclosure of their bodies in a 'tunic,' which is sometimes leathery or even cartilaginous in its texture, and which sometimes includes calcareous spicules, whose forms are often very beautiful. They are often found to resemble the Polyzoa in their tendency to produce composite structures by gemmation; but in their habits they are for the most part very inactive, exhibiting scarcely anything comparable to those rapid movements of expansion and retraction which it is so interesting to watch among the Polyzoa; whilst, with the exception of the *Salpidæ* and other floating species which are chiefly found in seas warmer than those that surround our coast, and the curious *Appendicularia* to be presently noticed, they are rooted to one spot during all but the earliest period of their lives. The larger forms of the *Ascidian* group, which constitutes the bulk of the class, are always solitary; not propagating by gemmation,

[1] See Mr. G. Busk's 'Remarks on the Structure and Function of the Avicularian and Vibracular Organs of Polyzoa' in *Trans. Micros. Soc.* ser. ii. vol. ii. 1854, p. 26; and Mr. A. W. Waters, 'On the use of the Avicularian Mandible in the determination of the Cheilostomatous Bryozoa,' *Journ. Roy. Micros. Soc.* (2), v. p. 774.

except in the case of the Clavelinidæ. Although of special importance to the comparative anatomist and the zoölogist, this group does not afford much to interest the ordinary microscopist, except in the peculiar actions of its respiratory and circulatory apparatus. In common with the composite forms of the group, the solitary Ascidians have a large branchial sac, with fissured walls, resembling that shown in figs. 632 B and 634 ; into this sac water is admitted by the oral orifice, and a large proportion of it is caused to pass through the fissures, by the agency of the cilia with which they are fringed, into a surrounding chamber, whence it is expelled through the atriopore, or opening of the mantle. This action may be distinctly watched through the external walls in the smaller and more transparent species ; and not even the ciliary action of the tentacles of the Polyzoa affords a more beautiful spectacle. It is peculiarly remarkable in one species that occurs on our own coasts, the *Corella parallelogramma*,[1] in which the wall of the branchial sac is divided into a number of areolæ, each of them shaped into a shallow funnel ; and round one of these funnels each branchial fissure makes two or three turns of a spiral. When the cilia of all these spiral fissures are in active movement at once, the effect is most singular. Another most remarkable phenomenon presented throughout the group, and well seen in the solitary Ascidian just referred to, is the *alternation* in the direction of the circulation. The heart, which lies at the bottom of the branchial sac, has its one end connected with the principal trunk leading to the body, and the other with that leading to the branchial sac. At one time it will be seen that the blood flows *from* the respiratory apparatus to the end of the heart in which its trunk terminates, which then contracts so as to drive it through the systemic trunk *to* the body at large ; but after this course has been maintained for a time the heart ceases to pulsate for a moment or two, and the course is reversed, the blood flowing into the heart *from* the body generally, and being propelled *to* the branchial sac. After this reversed course has continued for some time another pause occurs, and the first course is resumed. The length of time intervening between the changes does not seem by any means constant. It is usually stated at from half a minute to two minutes in the composite forms ; but in the solitary *Corella parallelogramma* (a species very common in Lamlash Bay, Arran), the Author has repeatedly observed an interval of from five to fifteen minutes, and in some instances he has seen the circulation go on for half an hour, or even longer, without change—always, however, reversing at last.

The *compound Ascidians* are very commonly found adherent to sea-weeds, zoöphytes, and stones between the tide-marks ; and they present objects of great interest to the microscopist, since the small size and transparence of their bodies when they are detached from the mass in which they are imbedded not only enables their structure to be clearly discerned without dissection, but allows many of their living actions to be watched. Of these we have a characteristic example in *Amaroucium proliferum*, of which the form of the com-

[1] See Alder in *Ann. of Nat. Hist.* ser. iii. vol. xi. 1863, p. 157; and Hancock in *Journ. Linn. Soc.* ix. p. 333.

nass and the anatomy of a single individual are displayed in
. Its clusters appear almost completely inanimate, exhibiting
y obvious movements when
d; but if they be placed
fresh in sea-water a slight
g of the orifices will soon be
ible, and a constant and
tic series of currents will be
to enter by one set and to be
by the other, indicating that
machinery of active life is
on within these apathetic

In the family *Polyclinidæ* ich this genus belongs the is elongated, and may be l into three regions: the thorax hich is chiefly occupied by the tory sac; the abdomen (B), contains the digestive appa- and the post-abdomen (C), in the heart and generative are lodged. At the summit thorax is seen the oral orifice, h leads to the branchial sac *e*; perforated by an immense r of slits, which allow part of ater to pass into the space n the branchial sac and the ar mantle. At *k* is seen the





632.—Compound mass of *Amaroucium proliferum* with the anatomy of a ngle zoöid: A, thorax; B, abdomen; C, post-abdomen; *c*, oral orifice; branchial sac; *f*, thoracic blood-vessel; *i*, atriopore; *i'*, projection over- nging it; *j*, nervous ganglion; *k*, œsophagus; *l*, stomach surrounded by gestive tubuli; *m*, intestine; *n*, anus opening into the cloaca formed by ie mantle; *o*, heart; *o'*, pericardium; *p*, ovarium; *p'*, egg ready to escape; testis; *r*, spermatic canal; *r'*, termination of this canal in the cloaca.

gus, which is continuous with the lower part of the pha- l cavity; this leads to the stomach, *l*, which is surrounded idular follicles; and from this passes off the intestine, *m*, which ates at *n* in the vent. A current of water is continually

drawn in through the mouth by the action of the cilia of the br chial sac and of the alimentary canal; a part of this current pas through the fissures of the branchial sac into the peribranch cavity, and thence into the cloaca; whilst another portion, enter the stomach by an aperture at the bottom of the pharyngeal s passes through the alimentary canal, giving up any nutrit materials it may contain, and carrying away with it any exc mentitious matter to be discharged; and this having met respiratory current in the cloaca, the two mingled currents pass fo together by the atrial orifice, *i*. The long post-abdomen is princip occupied by the large ovarium, *p*, which contain ova in various sta of development. These, when matured and set free, find their v into the cloaca, where two large ova are seen (one marked *p* the other immediately below it) waiting for expulsion. In this p tion they receive the fertilising influence from the testis, *q*, wh discharges its products by the long spermatic canal, *r*, that opens i the cloaca, *r'*. At the very bottom of the post-abdomen we find heart, *o*, inclosed in its pericardium, *o'*. In the group we are n considering a number of such animals are imbedded together in sort of gelatinous mass, and covered with an integument common them all: the composition of this gelatinous substance is remarkal as including cellulose, which generally ranks as a vegetable produ The mode in which new individuals are developed in this mass is the extension of *stolons* or creeping stems from the bases of th previously existing; and from each of these stolons several buds m be put forth, every one of which may evolve itself into the likene of the stock from which it proceeded, and may in its turn increa and multiply after the same fashion.

In the family of Didemnians the post-abdomen is absent, the he and generative apparatus being placed by the side of the intestine in t abdominal portion of the body. The zoöids are frequently arrang in star-shaped clusters, their anal orifices being all directed towar a common vent which occupies the centre. This shortening is s more remarkable, however, in the family of Botryllians, wh beautiful stellate gelatinous incrustations are extremely common up sea-weeds and submerged rocks (fig. 633). The anatomy of th animals is very similar to that of the *Amaroucium* already describe with this exception, that the body exhibits no distinction of caviti all the organs being brought together in one, which must be c sidered as thoracic. In this respect there is an evident approximati towards the solitary species.[1]

This approximation is still closer, however, in the 'social' As dians, or *Clavellinidæ*, in which the general plan of structure nearly the same, but the zoöids are simply connected by their stolo instead of being included in a common investment: so that th relation to each other is very nearly the same as that of the pol

[1] For more special information respecting the *compound Ascidians* see es cially the admirable monograph of Professor Milne-Edwards on that group; Mr. Liste memoir, 'On the Structure and Functions of Tubular and Cellular Polypi, and Ascidiæ,' in the *Phil. Trans.* 1834; and the article 'Tunicata,' by Professor T. Rup Jones, in the *Cyclopædia of Anatomy and Physiology*.

pides of *Lagúncula*, the chief difference being that a regular circulation takes place through the stolon in the one case, such as has no existence in the other. A better opportunity of studying the living actions of the Ascidians can scarcely be found, than that which is afforded by the genus *Perophora*, first discovered by Mr. Lister, which occurs not unfrequently on the south coast of England and in the Irish Sea, living attached to sea-weeds, and looking like an assemblage of minute globules of jelly, dotted with orange and brown, and linked by a silvery winding thread. The isolation of the body of each zoöid from that of its fellows, and the extreme transparence of its tunics, not only enable the movements of fluid within the body to be distinctly discerned, but also allow the action of the cilia that border the slits of the respiratory sac to be clearly made out. This sac is perforated with four rows of narrow oval openings, through which a portion of the water that enters its oral orifice escapes



FIG. 688.—*Botryllus violaceus*: A, cluster on the surface of a Fucus; B, portion of the same enlarged.

into the space between the sac and the mantle, and is thus discharged immediately by the atrial funnel. Whatever little particles, animate or inanimate, the current of water brings flow into the sac unless stopped at its entrance by the tentacles, which do not appear fastidious. The particles which are admitted usually lodge somewhere on the sides of the sac, and then travel horizontally until they arrive at that part of it down which the current proceeds to the entrance of the stomach, which is situated at the bottom of the sac. Minute animals are often swallowed alive, and have been observed darting about in the cavity for some days, without any apparent injury either to themselves or to the creature which incloses them. In general, however, particles which are unsuited for reception into the stomach are rejected by the sudden contraction of the mantle (or muscular tunic), the atriopore being at the same time closed, so that they are forced out by a powerful current through the oral orifice. The curious alternation of the circulation that is characteristic of the class generally may be particularly well studied in *Perophora*. The creeping stalk that connects the indivlduals of

any group contains two distinct canals, which send off bra into each peduncle. One of these branches terminates in the b which is nothing more than a contractile dilatation of the prin trunk ; this trunk subdivides into vessels (or rather *sinuses*, whic mere channels not having proper walls of their own), of which ramify over the respiratory sac, branching off at each of the pas between the oval slits, whilst others are first distributed to stomach and intestine, and to the soft surface of the mantle. these reunite so as to a trunk, which passes t peduncle and constitute returning branch. Alth the circulation in the ferent bodies is bro into connection by the mon stem, yet that of is independent of the continuing when the cu through its own foot-st interrupted by a ligat and the stream whic turns from the bran sac and the viscera is poured into the post part of the heart ins of entering the peduncl



FIG. 634.—Diagrammatic longitudinal section of *Ascidia* showing the heart, the blood-vessels, the branchial sac, the alimentary canal, &c. from the left side: *br.si.*, branchial siphon; *at.si.*, atrial siphon; *t.*, test; *m.*, mantle; *br.s.*, branchial sac; *p.br.*, peribranchial cavity; *cl.*, cloaca; *n.g.*, nerve ganglion; *tn.*, tentacle; *gl.*, neural gland; *œ.a.*, œsophageal aperture; *st.*, stomach; *i.*, intestine; *r.*, rectum; *a.*, anus; *ov*, genital organs; *g.d.*, genital ducts; *h.*, heart; *c.sp.*, cardio-splanchnic vessel; *v.t.*, vessel to the test; *t.k.*, terminal knob on vessel in test; *v.t'.*, vessel from the test; *v.st.*, vessel to the stomach &c.; *v.m.*, vessel to the mantle; *v.m'.*, vessel from the mantle; *d.v.*, dorsal vessel; *tr.*, transverse vessel of branchial sac; *l.v.*, fine longitudinal vessel of branchial sac; *sg.*, stigmata of branchial sac; *v.v.*, ventral vessel; *br.c.*, branchio-cardiac vessel; *sp.br.*, splanchno-branchial vessel. (After Herdman.)

The *development* of Ascidians, the early st of which are observ whilst the ova are within the cloaca of parent, presents some nomena of much int to the microscopist w alone can be noticed After the ordinary repe segmentation of the whereby a 'mulberry m is produced, a sort of is seen encircling its cen portion ; but this shows itself as a tape tail-like prolongation one side of the yolk, w gradually becomes and more detached it, save at the part which it springs. Ei whilst the egg is still wi the cloaca, or soon after it has escaped from the vent, its envel bursts, and the larva escapes, and in this condition it presents

much the appearance of a tadpole, the tail being straightened out, and propelling the body freely through the water by its lateral strokes. The centre of the body is occupied by a mass of liquid yolk, and this is continued into the interior of three prolongations which extend themselves from the opposite extremity, each terminating in a sort of sucker. After swimming about for some hours with an active wriggling movement, the larva attaches itself to some solid body by means of one of these suckers; if disturbed from its position, it at first swims about as before; but it soon completely loses its activity, and becomes permanently attached; and important changes manifest themselves in its interior. The organs and tissues which constitute the chief part of the future animal are gradually drawn back, so that the whole of it is concentrated into one mass; and the tail, now consisting only of the gelatinous envelope, is either detached entire from the body by the contraction of the connecting portion, or withers, and is thrown off gradually in shreds. The shaping of the internal organs out of the yolk mass takes place very rapidly, so that by the end of the second day of the sedentary state the outlines of the branchial sac and of the stomach and intestine may be traced, no external orifices, however, being as yet visible. The pulsation of the heart is first seen on the third day, and the formation of the branchial and anal orifices takes place on the fourth, after which the ciliary currents are immediately established through the branchial sac and alimentary canal. The embryonic development of other Ascidians, solitary as well as composite, takes place on a plan essentially the same as the foregoing, a free tadpole-like larva being always produced in the first instance with the curious exception of some species of *Molgula*.[1]

This larval condition is represented in a very curious adult free swimming form, termed *Appendicularia*, which is frequently to be taken with the tow-net on our own coasts. This animal has an oval or flask-like body, which in large specimens attains the length of one-fifth of an inch, but which is often not more than one-fourth or one-fifth of that size. It is furnished with a tail-like appendage three or four times its own length, broad, flattened, and rounded at its extremity; and by the powerful vibrations of this appendage it is propelled rapidly through the water. The structure of the body differs greatly from that of the Ascidians, its plan being much simpler; in particular, the pharyngeal sac is entirely destitute of ciliated branchial fissures opening into a surrounding cavity; but two canals,

[1] The study of the development of *Ascidians* derived a new interest and importance from the discovery, made by Kowalevsky in 1867, that their free-swimming larvæ present a most striking parallelism to vertebrate embryos, in exhibiting the beginnings of a spinal marrow and a notochord; thus bridging over the gulf that was supposed to separate them from Invertebrata, and (when taken in connection with the curious Ascidian affinities of *Amphioxus*, the lowest vertebrate at present known) affording strong reason for belief in the derivation of the vertebrate and tunicate types from a common original. See his memoir 'Entwickelungsgeschichte der einfachen Ascidien' in *Mém. St. Pétersb. Acad. Sci.* tom. x. 1867, and the abstract of it in *Quart. Journ. Micros. Sci.* x. n.s. 1870, p. 59; also Professor Haeckel's *History of Creation*, ii. pp. 152, 200. Further information will be found in chap. ii. of vol. ii. of the late Professor Balfour's *Comparative Embryology*, and an application of the facts of development to the philosophy of the subject in Professor Ray Lankester's *Degeneration* (London, 1880).

one on either side of the entrance to the stomach, are prolonged f
it to the external surface; and by the action of the long cilia
which these are furnished, in conjunction with the cilia of
branchial sac, a current of water is maintained through its ca
From the observations of Professor Huxley, however, it appears
the direction of this current is by no means constant; since, altho
it usually enters by the mouth and passes out by the ciliated ca
it sometimes enters by the latter and passes out by the former.
caudal appendage has a central axis (notochord), above and b
which is a riband-like layer of muscular fibres; a nervous c
studded at intervals with minute ganglia, may be traced along
whole length. By Mertens, one of the early observers of this ani
it was said to be furnished with a peculiar gelatinous envelop
Haus (house), very easily detached from the body, and capabl
being re-formed after having been lost. Notwithstanding the g
numbers of specimens which have been studied by Müller, Hu
Leuckart, and Gegenbaur, neither of these excellent observers
met with this appendage; but it has been since seen by Profe
Allman, who describes it as an egg-shaped gelatinous mass, in w
the body is imbedded, the tail alone being free; whilst from ei
side of the central plane there radiates a kind of double fan, w
seems to be formed by a semicircular membranous lamina folded u
itself. It is surmised by Professor Allman, with much probabi
that this curious appendage is 'nidamental,' having reference to
development and protection of the young; but on this point fur
observations are much needed; and any microscopist who may
with *Appendicularia* furnished with its 'house' should do all he
to determine its structure and its relations to the body of
animal.[1]

[1] For details in respect to the structure of *Appendicularia*, see Huxley in
Trans. for 1851, and in *Quart. Journ. of Micros. Sci.* vol. iv. 1856, p. 181;
Allman in the same journal, vol. vii. 1859, p. 86; Gegenbaur in *Siebold und Köll*
Zeitschrift, Bd. vi. 1855, p. 406; Leuckart's *Zoologische Untersuchungen*, He
1854; and Fol's 'Etudes sur les Appendiculaires' in *Archiv. zool. expér.* to
1872, p. 57. For the *Tunicata* generally, see Professor T. Rupert Jones in vol. iv. o
Cyclop. of Anatomy and Physiology; Professor Herdman's recently published ar
'Tunicata,' in the 9th edition of the *Encyclopædia Britannica*; Mr. Alder's 'Obs
tions on the British Tunicata' in *Ann. of Nat. Hist.* ser. iv. vol. xi. 1863, p. 153;
Mr. Hancock's memoir 'On the Anatomy and Physiology of the Tunicata' in the *Jou*
of the Linnean Society, vol. ix. p. 309. Great additions to our knowledge have
recently made by Professor Herdman, whose reports on the forms collected by H.
Challenger should be consulted, and by Professors Van Beneden and Julin (see
cially their memoirs in the *Archives de Biologie*). See also Roule, 'Recherches su
Ascidies simples des côtes de Provence,' *Ann. Museum Marseilles*, ii.; Seel
'Die Entwickelungsgeschichte der Socialen Ascidien,' *Jenaische Zeitschr.*
p. 528; Salensky, 'Neue Untersuchungen über die embryonale Entwickelung
Salpen,' *Mitth. Zool. Stat. Neapel*, iv. pp. 90, 327; and Ulianin, 'Die Arten
Gattung *Doliolum* im Golfe von Neapel,' in the *Fauna und Flora des Golfes*
Neapel, x.

CHAPTER XVIII

MOLLUSCA AND BRACHIOPODA

THE various forms of 'shell-fish,' with their 'naked' or shell-less allies, furnish a great abundance of objects of interest to the microscopist, of which, however, the greater part may be grouped under three heads—namely (1) the structure of the *shell*, which is most interesting in the CONCHIFERA (or LAMELLIBRANCHIATA) and BRACHIOPODA, in both of which classes the shells are 'bivalve,' while the animals differ from each other essentially in general plan of structure; (2) the structure of the *tongue* or *palate* of the GASTROPODA, most of which have 'univalve' shells, others, however, being 'naked'; (3) the *developmental history* of the embryo, for the study of which certain of the Gastropods present the greatest facilities. These three subjects, therefore, will be first treated of systematically, and a few miscellaneous facts of interest will be subjoined.

Shells of Mollusca.—These investments were formerly regarded as mere inorganic exudations, composed of calcareous particles, cemented together by animal glue; microscopic examination, however, has shown that they possess a definite *structure*, and that this structure presents certain very remarkable variations in some of the groups of which the molluscous series is composed. We shall first describe that which may be regarded as the characteristic structure of the ordinary bivalves, taking as a type the group of *Margaritacea*, which includes the *Meleagrina* or 'pearl oyster' and its allies, the common *Pinna* ranking amongst the latter. In all these shells we readily distinguish the existence of two distinct layers; an *external*, of a brownish yellow colour; and an *internal*, which has a pearly or 'nacreous' aspect, and is commonly of a lighter hue.

The structure of the *outer* layer may be conveniently studied in the shell of *Pinna*, in which it commonly projects beyond the inner, and there often forms laminæ sufficiently thin and transparent to exhibit its general characters without any artificial reduction. If a small portion of such a lamina be examined with a low magnifying power by transmitted light, each of its surfaces will present very much the appearance of a honeycomb; whilst its broken edge exhibits an aspect which is evidently fibrous to the eye, but which, when examined under the microscope with reflected light, resembles that of an assemblage of segments of basaltic columns (fig. 638). This outer layer is thus seen to be composed of a vast number of *prisms*,

having a tolerably uniform size, and usually presenting an approach to the hexagonal shape. These are arranged perpendicularly (or nearly so) to the surface of the lamina of the shell; so that its thickness is formed by their length, and its two surfaces by their extremities. A more satisfactory view of these prisms is obtained by grinding down a lamina until it possesses a high degree of transparence, the prisms being then seen (fig. 635) to be themselves composed of a very homogeneous substance, but to be separated by definite and strongly marked lines of division. When such a lamina is submitted to the action of dilute acid, so as to dissolve away the carbonate of lime, a tolerably firm and consistent membrane is left, which exhibits the prismatic structure just as perfectly as did the original shell (fig. 636), its hexagonal divisions bearing a strong resemblance to the walls of the cells of the pith or bark of a plant. By making a section of the shell perpendicularly to its surface, we obtain a view of the prisms cut in the direction of their length (fig. 637); these are frequently seen to be marked by delicate transverse striæ (fig. 638) closely resembling those observable on the prisms of the enamel of teeth, to which this kind of shell-structure may be considered as bearing a very close resemblance, except as regards the mineralising ingredient.



Fig. 635.—Section of shell of *Pinna*, taken transversely to the direction of its prism.



Fig. 636.—Membranous basis of the same.

If a similar section be decalcified by dilute acid the membranous residuum will exhibit the same resemblance to the walls of prismatic cells viewed longitudinally, and will be seen to be more or less regularly marked by the transverse striæ just alluded to. It sometimes happens in recent but still more commonly in fossil shells, that the decay of the animal membrane leaves the contained prisms without any connecting medium: as they are then quite isolated, they can be readily detached one from another; and each one may be observed to be marked by the like striations, which, when a sufficiently high magnifying power is used, are seen to be minute grooves, apparently resulting from a thickening of the intermediate wall in those situations. These appearances seem best

accounted for by supposing that each is lengthened by successive additions at its base, the lines of junction of which correspond with the transverse striation ; and this view corresponds well with the fact that the shell-membrane not unfrequently shows a tendency to split into thin laminæ along the lines of striation ; whilst we occasionally meet with an excessively thin natural lamina lying between the thicker prismatic layers, with one of which it would have probably coalesced, but for some accidental cause which preserved its distinctness. That the prisms are not formed in their entire length at once, but that they are progressively lengthened and consolidated at their lower extremities, would appear also from the fact that where the shell presents a deep colour (as in *Pinna nigrina*) this colour is usually disposed in distinct strata, the outer portion of each layer being the part most deeply tinged, whilst the inner extremities of the prisms are almost colourless.

FIG. 637.—Section of the shell of *Pinna* in the direction of its prisms.

This 'prismatic' arrangement of the carbonate of lime in the shells of *Pinna* and its allies has been long familiar to conchologists, and regarded by them as the result of crystallisation. When



FIG. 638.—Oblique section of prismatic shell-substance.

first more minutely investigated by Mr. Bowerbank [1] and the r,[2] and was shown to be connected with a similar arrangement membranous residuum left after the decalcification of the shell- ice by acid, microscopists generally [3] agreed to regard it as a

the Structure of the Shells of Molluscous and Conchiferous Animals,' in *icros. Soc.* ser. i. vol. i. 1844, p. 123.

the Microscopic Structure of Shells' in *Reports of British Association* for 1847.

Mr. Quekett's *Histological Catalogue of the College of Surgeons' Museum*, *ectures on Histology*, vol. ii.

'calcified epidermis,' the long prismatic cells being supposed to formed by the coalescence of the epidermic cells in piles, and giv their shape to the deposit of carbonate of lime formed within the The progress of inquiry, however, has led to an important modifi tion of this interpretation, the Author being now disposed to ag with Professor Huxley[1] in the belief that the entire thickness of t shell is formed as an *excretion* from the surface of the epidermis, a that the horny layer which in ordinary shells forms their exter envelope or 'periostracum,'[2] being here thrown out at the same ti with the calcifying material, is converted into the likeness of cellular membrane by the pressure of the prisms that are formed crystallisation at regular distances in the midst of it. The pec liar conditions under which calcareous concretions form themselv in an organic matrix have been carefully studied by Mr. Rain and Dr. W. M. Ord, of whose researches some account will be giv hereafter.

The *internal* layer of the shells of the *Margaritacea* and so other families has a 'nacreous' or iridescent lustre, which depen (as Sir D. Brewster has shown[3]) upon the striation of its surfa with a series of grooved lines, which usually run nearly parallel each other (fig. 639). As these lines are not obliterated by a amount of polishing, it is obvious that their presence depends up something peculiar in the texture of this substance, and not up any mere superficial arrangement. When a piece of the nacre (co monly known as 'mother-of-pearl') of the *Meleagrina* or 'pearl-oyste is carefully examined, it becomes evident that the lines are produc by the cropping out of laminæ of shell situated more or less oblique to the plane of the surface. The greater the *dip* of these laminæ, t closer will their edges be; whilst the less the angle which they mal with the surface, the wider will be the interval between the line When the section passes for any distance in the plane of a lamina, lines will present themselves on that space. And thus the appearan of a section of nacre is such as to have been aptly compared by Sir Herschel to the surface of a smoothed deal board, in which the wood layers are cut perpendicularly to their surface in one part, and near in their plane in another. Sir D. Brewster (*loc. cit.*) appears to hav supposed that nacre consists of a multitude of layers of carbonate lime alternating with animal membrane, and that the presence the grooved lines on the most highly polished surface is due to th wearing away of the edges of the animal laminæ, whilst those of th hard calcareous laminæ stand out. If each line upon the nacreou surface, however, indicates a distinct layer of shell-substance, a ver thin section of 'mother-of-pearl' ought to contain many hundre laminæ, in accordance with the number of lines upon its surface

[1] See his article, 'Tegumentary Organs,' in *Cyclopædia of Anatomy an Physiology*, supplementary volume, pp. 489–492.

[2] The *periostracum* is the yellowish-brown membrane covering the surface o many shells, which is often (but erroneously) termed their *epidermis*.

[3] *Phil. Trans.* 1814, p. 397.—The late Mr. Barton (of the Mint) succeeded in producing an artificial iridescence on metallic buttons by drawing closely approximating lines with a diamond point upon the surface of the steel die by which they were struck.

these being frequently no more than $\frac{1}{7500}$th of an inch apart. But when the nacre is treated with dilute acid, so as to dissolve its calcareous portion, no such repetition of membranous layers is to be found; on the contrary, if the piece of nacre be the product of one act of shell formation, there is but a single layer of membrane. This layer, however, is found to present a more or less folded or plaited arrangement, and the lineation of the nacreous surface may perhaps be thus accounted for. A similar arrangement is found in *pearls*, which are rounded concretions projecting from the inner surface of the shell of *Meleagrina*, and possessing a nacreous structure corresponding to that of 'mother-of-pearl.' Such concretions are found in many other shells, especially the fresh-water mussels, *Unio* and *Anodon*; but these are usually less remarkable for their pearly lustre; and, when formed at the edge of the valves, they may be partly or



FIG. 639.—Section of nacreous lining of shell of *Meleagrina margaritifera* (Pearl-oyster).

even entirely made up of the prismatic substance of the external layer, and may be consequently altogether destitute of the pearly character.

In all the genera of the *Margaritaceæ* we find the external layer of the shell prismatic, and of considerable thickness, the internal layer being nacreous. But it is only in the shells of a few families of bivalves that the combination of organic with mineral components is seen in the same distinct form; and these families are for the most part nearly allied to *Pinna*. In the *Unionidæ* (or 'fresh-water mussels') nearly the whole thickness of the shell is made up of the internal or 'nacreous' layer; but a uniform stratum of prismatic substance is always found between the nacre and the periostracum, really constituting the inner layer of the latter, the outer being simply horny. In the *Ostreaceæ* (or oyster tribe), also, the greater part of the thickness of the shell is composed of a 'sub-nacreous' substance, representing the inner layer of the shells of Margaritaceæ, its successively formed laminæ, however, having very little adhesion

to each other; and every one of these laminæ is bordered at its fre edge by a layer of the prismatic substance distinguished by it brownish-yellow colour. In these and some other cases a distinc membranous residuum is left after the decalcification of the prismati layer by dilute acid; and this is most tenacious and substantial where (as in the *Margaritaceæ*) there is no proper periostracum Generally speaking, a thin prismatic layer may be detected upon th external surface of bivalve shells, where this has been protecte by a periostracum, or has been prevented in any other manner from undergoing abrasion; thus it is found pretty generally in *Chama*, *Trigonia*, and *Solen*, and occasionally in *Anomia* and *Pecten*.

In many other instances, however, nothing like a cellular struc ture can be distinctly seen in the delicate membrane left after decal cification; and in such cases the animal basis bears but a very small proportion to the calcareous substance, and the shell is usually extremely hard. This hardness appears to depend upon the mineral arrangement of the carbonate of lime; for whilst in the *prismatic* and ordinary *nacreous* layer this has the crystalline condition of *calcite*, it can be shown in the hard shell of *Pholas* to have the arrangement of *arragonite*, the difference between the two being made evident by polarised light. A very curious appearance is presented by a section of the large hinge-tooth of *Mya arenaria* (fig. 640), in which the carbonate of lime seems to be deposited in nodules that possess a crystalline structure resembling that of the mineral termed *wavellite*. Approaches to this curious arrangement are seen in many other shells.



FIG. 640.—Section of hinge-tooth of *Mya arenaria*.

There are several bivalve shells which almost entirely consist of what may be termed a *sub-nacreous* substance, their polished surfaces being marked by lines, but these lines being destitute of that regularity of arrangement which is necessary to produce the iridescent lustre. This is the case, for example, with most of the *Pectinidæ* (or scallop tribe), also with some of the *Mytilaceæ* (or mussel tribe), and with the common *Oyster*. In the internal layer of by far the greater number of bivalve shells, however, there is not the least approach to the nacreous aspect; nor is there anything that can be described as definite structure; and the residuum left after its decalcification is usually a structureless 'basement membrane.'

The ordinary account of the mode of growth of the shells of bivalve Mollusca—that they are progressively enlarged by the deposition of new laminæ, each of which is in contact with the internal surface of the preceding, and extends beyond it—does not express

the whole truth ; for it takes no account of the fact that most shells are composed of two layers of very different texture, and does not specify whether *both* these layers are thus formed by the entire surface of the 'mantle' whenever the shell has to be extended, or whether only *one* is produced. An examination of fig. 641 will clearly show the mode in which the operation is effected. This figure represents a section of one of the valves of *Unio occidens*, taken perpendicularly to its surface, and passing from the margin or lip (at the left hand of the figure) towards the hinge (which would be at some distance beyond the right). This section brings into view the two substances of which the shell is composed, traversing the outer or prismatic layer in the direction of the length of its prisms, and passing through the nacreous lining in such a manner as to bring into view its numerous laminæ, separated by the lines *a a'*, *b b'*, *c c'*, &c. These lines evidently indicate the successive formations of this



FIG. 641.—Vertical section of the lip of one of the valves of the shell of *Unio*: *a*, *b*, *c*, successive formations of the outer prismatic layer; *a'*, *b'*, *c'*, the same of the inner nacreous layer.

layer, and it may be easily shown by tracing them, towards the hinge on the one side and towards the margin on the other, that at every enlargement of the shell its whole interior is lined by a new nacreous lamina in immediate contact with that which preceded it. The number of such laminæ, therefore, in the oldest part of the shell indicates the number of enlargements which it has undergone. The outer or prismatic layer of the growing shell, on the other hand, is only formed where the new structure projects beyond the margin of the old ; and thus we do not find one layer of it overlapping another, except at the lines of junction of two distinct formations. When the shell has attained its full dimensions, however, new laminæ of both layers still continue to be added, and thus the lip becomes thickened by successive formations of prismatic structure, each being applied to the inner surface of the preceding, instead of to its free margin. A like arrangement may be well seen in the *Oyster*, with this difference, that the successive layers have but a comparatively slight adhesion to each other.

The shells of *Terebratulæ* and of most other *Brachiopods* are distinguished by peculiarities of structure which differentiate them from those of the Mollusca. When thin sections of them are microscopically examined, they exhibit the appearance of long flattened prisms (fig. 642, A, *b*), which are arranged with such obliquity

that their rounded extremities crop out upon the inner surface of the shell in an imbricated (tile-like) manner (*a*). All true *Terebratulidæ*, both recent and fossil, exhibit another very remarkable peculiarity; namely, the *perforation* of the shell by a large number of canals,



FIG. 642.—A, internal surface, *a*, and oblique section, *b*, of shell of *Waldheimia australis*; B, external surface of the same.

which generally pass nearly perpendicularly from one surface to the other (as is shown in vertical sections, fig. 643), and terminate internally by open orifices (fig. 642, A), whilst externally they are covered by the periostracum (B). Their diameter is greatest towards the external surface, where they sometimes expand suddenly, so as to become trumpet-shaped; and it is usually narrowed rather suddenly when, as sometimes happens, a new internal layer is formed as a lining to the preceding (fig. 643, A, *d d*). Hence the diameter of these canals, as shown in different transverse sections of one and the same shell, will vary according to the part of its thickness which the section happens to traverse. The shells of different species of perforated *Brachiopods*, however, present very striking diversities in the size and closeness of their canals, as shown by sections taken in corresponding parts; three examples of this kind are given for the sake of comparison in figs. 644–646. These canals are occupied in the living state by tubular prolongations of the mantle, whose interior is filled with a fluid containing minute cells and granules, which, from its corresponding in appearance with the fluid contained in the great sinuses of the mantle, may perhaps



FIG. 643.—Vertical sections of shell of *Waldheimia australis*, showing at A the canals opening by large trumpet-shaped orifices on the outer surface, and contracting at *d*, *d* into narrow tubes; and showing at B a bifurcation of the canals.

be considered to be the animal's blood. Of their special function in the economy of the animal it is difficult to form any probable idea; but it is interesting to remark (in connection with the hypothesis of a relationship between Brachiopods and Polyzoa) that they seem to have their parallel in extensions of the perivisceral cavity of many species of *Flustra*, *Eschara*, *Lepralia*, &c. into passages excavated in the walls of the cells of the polyzoary. Professor Sollas[1] finds in the centre of these prolongations an axial fibre which can be traced backwards to the nerve-cells of the mantle; at the distal end is a terminal cell which is connected by a fibril with the axial fibre, and is covered externally by a transparent chitinous layer; save for the absence (or the unproved presence) of pigment cells we should be justified in regarding the processes as organs which are sensitive to luminous impressions.

In the family *Rhynchonellidæ*, which is represented by only



FIG. 644.



FIG. 645.



FIG. 646.

FIG. 644.—Horizontal section of shell of *Terebratula bullata* (fossil, Oolite).
FIG. 645. „ „ *Megerlia lima* (fossil, Chalk).
FIG. 646. „ „ *Spiriferina rostrata* (Triassic).

six recent species, but which contains a very large proportion of fossil Brachiopods, these canals are almost entirely absent; so that the uniformity of their presence in the *Terebratulidæ*, and their general absence in the *Rhynchonellidæ*, supplies a character of great value in the discrimination of the fossil shells belonging to these two groups respectively. Great caution is necessary, however, in applying this test; *mere surface markings cannot be relied on*; and no statement on this point is worthy of reliance which is not based on a microscopic examination of thin *sections* of the shell. In the families *Spiriferidæ* and *Strophomenidæ*, on the other hand, some species possess the perforations, whilst others are destitute of them; so that their presence or absence *there* serves only to mark out subordinate groups. This, however, is what holds good in regard to characters of almost every description in other departments of natural history; a character which is of fundamental importance from its close relation to the general plan of organisation in one group, being, from its want of constancy, of far less account in another.[2]

[1] *Proc. Roy. Dublin Soc.* v. 318.

[2] For a particular account of the Author's researches on this group see his memoir on the subject, forming part of the introduction of Mr. Davidson's *Monograph of the*

There is not by any means the same amount of diversity in the structure of the shell in the class of *Gastropods*, a certain typical plan of construction being common to by far the greater number of them. The small proportion of animal matter contained in most of these shells is a very marked feature in their character, and it serves to render other features indistinct, since the residuum left after the removal of the calcareous matter is usually so imperfect as to give no clue whatever to the explanation of the appearances shown by sections. Nevertheless, the structure of these shells is by no means homogeneous, but always exhibits indications, more or less clear, of a definite arrangement. The 'porcellanous' shells are composed of three layers, all presenting the same kind of structure, but each differing from the others in the mode in which this is disposed. For each layer is made up of an assemblage of thin laminæ placed side by side, which separate one from another, apparently in the planes of rhomboidal cleavage, when the shell is fractured; and, as was first pointed out by Mr. Bowerbank, each of these laminæ consists of a series of elongated spicules (considered by him as prismatic cells filled with carbonate of lime) lying side by side in close apposition; and these series are disposed alternately in contrary directions, so as to intersect each other nearly at right angles, though still lying in parallel planes. The direction of the planes is different, however, in the three layers of the shell, bearing the same relation to each other as have those three sides of a cube which meet each other at the same angle: and by this arrangement, which is better seen in the fractured edge of the *Cypræa* or any similar shell than in thin sections, the strength of the shell is greatly augmented. A similar arrangement, obviously answering the same purpose, has been shown by Mr. (now Sir) John Tomes to exist in the enamel of the teeth of Rodentia, and by Professor Rolleston in that of the elephant.

The principal departures from this plan of structure are seen in *Patella*, *Chiton*, *Haliotis*, *Turbo* and its allies, and in the 'naked' Gastropods, many of which last, both terrestrial and marine, have some rudiment of a shell. Thus in the common slug, *Limax rufus*, a thin oval plate of calcareous texture is found imbedded in the shield-like fold of the mantle covering the fore part of its back; and if this be examined in an early stage of its growth it is found to consist of an aggregation of minute calcareous nodules, generally somewhat hexagonal in form, and sometimes quite transparent, whilst in other instances it presents an appearance closely resembling that delineated in fig. 640. In the epidermis of the mantle of some species of *Doris*, on the other hand, we find long calcareous spicules, generally lying in parallel directions, but not in contact with each other, giving firmness to the whole of its dorsal portion; and these are sometimes covered with small tubercles, like the spicules of

British Fossil Brachiopoda, published by the Palæontographical Society. A very remarkable example of the importance of the presence or absence of the perforation in distinguishing shells whose internal structure shows them to be generically different, whilst from their external conformation they would be supposed to be not only *generically* but *specifically identical*, will be found in the *Ann. Nat. Hist.* ser. iii. vol. xx. 1867, p. 68.

Gorgonia. They may be separated from the soft tissue in which they are imbedded by means of caustic potash; and when treated with dilute acid, whereby the calcareous matter is dissolved away, an organic basis is left, retaining in some degree the form of the original spicule. This basis seems to be a cell in the earliest stage of its formation, being an isolated particle of protoplasm without wall or cavity, and the close correspondence between the appearance presented by thin sections of various univalve shells, and the forms of the spicules of *Doris*, seems to justify the conclusion that even the most compact shells of this group are constructed out of the like elements, in a state of closer aggregation and more definite arrangement, with the occasional occurrence of a layer of more spheroidal bodies of the same kind, like those forming the vestigial shell of *Limax*.

The structure of shells generally is best examined by making *sections* in different planes as nearly parallel as may be possible to the surfaces of the shell, and other sections at right angles to these; the former may be designated as *horizontal*, the latter as *vertical*. Nothing need here be added to the full directions for making such sections which have already been given. Many of them are beautiful and interesting objects for the polariscope. Much valuable information may also be derived from the examination of the surfaces presented by *fracture*. The membranous residua left after the decalcification of the shell by dilute acid may be mounted in weak spirit or in Goadby's solution.

The animals composing the class of *Cephalopoda* (cuttle-fish and nautilus tribe) are for the most part unpossessed of shells; and the structure of the few that we meet with in the genera *Nautilus*, *Argonauta* ('paper nautilus'), and *Spirula* does not present any peculiarities that need here detain us. The rudimentary shell or *sepiostaire* of the common cuttle-fish, however, which is frequently spoken of as the 'cuttle-fish bone,' exhibits a very beautiful and remarkable structure, such as causes sections of it to be very interesting microscopic objects. The outer shelly portion of this body consists of horny layers, alternating with calcified layers, in which last may be seen an hexagonal arrangement somewhat corresponding with that shown in fig. 640. The soft friable substance that occupies the hollow of this boat-shaped shell is formed of a number of delicate calcareous plates running across it from one side to the other in parallel directions, but separated by intervals several times wider than the thickness of the plates; and these intervals are in great part filled up by what appear to be fibres or slender pillars passing from one plate or floor to another. A more careful examination shows, however, that, instead of a large number of detached pillars, there exists a comparatively small number of very thin sinuous laminæ, which pass from one surface to the other, winding and doubling upon themselves, so that each lamina occupies a considerable space. Their precise arrangement is best seen by examining the parallel plates, after the sinuous laminæ have been detached from them, the lines of junction being distinctly indicated upon these. By this arrangement each layer is most effectually supported by those with which

it is connected above and below, and the sinuosity of the thin intervening laminæ, answering exactly the same purpose as the 'corrugation' given to iron plates for the sake of diminishing their flexibility, adds greatly to the strength of this curious texture, which is at the same time lightened by the large amount of open space between the parallel plates that intervenes among the sinuosities of the laminæ. The best method of examining this structure is to make sections of it with a sharp knife in various directions, taking care that the sections are no thicker than is requisite for holding together, and these may be mounted on a black ground as opaque objects, or in Canada balsam as transparent objects, under which last aspect they furnish very beautiful objects for the polariscope.

Palate of Cephalophorous Molluscs.—The organ which is sometimes referred to under this designation, and sometimes as the 'tongue,' is one of a very singular nature, and cannot be likened to either the tongue or the palate of higher animals. For it is a tube that passes backwards and downwards beneath the mouth, closed at its hinder end, whilst in front it opens obliquely upon the floor of the mouth, being (as it were) slit up and spread out so as to form a nearly flat surface. On the interior of the tube, as well as on the flat expansion of it, we find numerous transverse rows of minute teeth, which are set upon flattened plates, each principal tooth sometimes having a basal plate of its own, whilst in other instances one plate carries several teeth. Of the former arrangement we have an example in the palate of many terrestrial Gastropods, such as the snail (*Helix*) and slug (*Limax*), in which the number of plates in each row is very considerable (figs. 647, 648), amounting to 180 in the large garden slug (*Limax maximus*); whilst the latter prevails in many marine Gastropods, such as the common whelk (*Buccinum undatum*), the palate of which has only three plates in each row, one bearing the small central teeth, and the two others the large lateral teeth (fig. 651). The length of the palatal tube and the number of rows of teeth vary greatly in different species. Generally speaking, the tube of the terrestrial Gastropods is short, and is contained entirely within the nearly globular head; but the rows of teeth being closely set together are usually very numerous, there being frequently more than 100, and in some species as many as 160 or 170: so that the total number of teeth may mount up, as in *Helix pomatia*, to 21,000, and in *Limax maximus* to 26,800. The transverse rows are usually more or less curved, as shown in fig. 648.



FIG. 647.—Portion of the left half of the palate of *Helix hortensis*, the rows of teeth near the edge separated from each other to show their form.

whilst the longitudinal rows are quite straight, and the curvature takes its departure on each side from a central longitudinal row, the teeth of which are symmetrical, whilst those of the lateral portions of each transverse row present a modification of that symmetry, the prominences on the *inner* side of each tooth being suppressed, whilst those on the outer side are increased; this modification may be observed to augment in degree as we pass from the central line towards the edges.



FIG. 648.—Palate of *Hyalinia cellaria*.

The palatal tube of the marine Gastropods is generally longer, and its teeth larger, and in many instances it extends far beyond the head, which may, indeed, contain but a small part of it. Thus in a common limpet (*Patella*) we find the principal part of the tube to lie folded up, but perfectly free, in the abdominal cavity, between the greatly elongated intestine and the muscular foot; and in some species its length is twice or even three times as great as that of the entire animal. In a large proportion of cases these palates exhibit a very marked separation between the central and the lateral portions (figs. 649, 650), the teeth of the central band being frequently small and smooth at their edges, whilst those of the lateral are large and serrated. The palate of *Trochus zizyphinus*, represented in fig. 649, is one of the most beautiful examples of this form, not only the large teeth of the lateral bands, but the delicate leaf-like teeth of the central portion having their edges minutely serrated. A yet more complex type, however, is found in the palate of *Haliotis*, in which there is a central band of teeth having nearly straight edges instead of points; then, on each side, a lateral band consisting of large teeth shaped like those of the shark; and beyond this, again, another lateral band on either side, composed of several rows of smaller teeth. Very curious differences also present themselves among the different species of the same genus. Thus in *Doris pilosa* the central band is almost entirely wanting, and each lateral band is formed of a single row of very large hooked teeth, set obliquely like those of the lateral band in fig. 649; whilst in *Doris tuberculata* the central band is the part most developed, and contains a number of rows of conical



FIG. 649.—Palate of *Trochus zizyphinus*.

teeth, standing almost perpendicularly, like those of a harrow (fig. 650).

Many other varieties might be described did space permit; but we must be content with adding that the form and arrangement of the teeth of these 'palates' afford characters of great value in classification, as was first pointed out by Professor Lovèn (of Stockholm) in 1847, and has been since very strongly urged by Dr. J. E. Gray, who considers that the structure of these organs is one of the best guides to the natural affinities of the species, genera, and families of this group, since any important alteration in the form or position of the teeth must be accompanied by some corresponding peculiarity in the habits and food of the animal.[1] Hence a systematic examination and delineation of the structure and arrangement of these organs, by the aid of the microscope and camera lucida, would be of the greatest service to this department of natural history. The short thick tube of *Limax* and other terrestrial Gastropods appears adapted for the trituration of the food previously to its passing into the œsophagus; for in these animals we find the roof of the mouth furnished with a large strong horny plate, against which the flat end of the tongue can work. On the other hand, the flattened portion of the palate of *Buccinum* (whelk) and its allies is used by these animals as a file, with which they bore holes through the shells of the molluscs that serve as their prey; this they are enabled to effect by everting that part of the proboscis-shaped mouth whose floor is formed by the flattened part of the tube, which is thus brought to the exterior, and by giving a kind of sawing motion to the organ by means of the alternate action of two pairs of muscles—a protractor and a retractor—which put forth and draw back a pair of cartilages whereon the tongue is supported, and also elevate and depress its teeth. The use of the long blind tubular part of the palate in these Gastropods is that of a 'cavity of reserve,' from which a new toothed surface may be continually supplied as the old one is worn away—somewhat as the front teeth of the rodents are constantly being regenerated from the surface of the pulps which occupy their hollow conical bases—as fast as they are rubbed down at their edges, or as a nail is constantly being worn away at its free end, and fashioned anew in its 'bed.'



FIG. 650.—Palate of *Doris tuberculata*.

The preparation of these palates for the microscope can, of course, be only accomplished by carefully dissecting them from their attachments within the head; and it will be also necessary to remove the

[1] *Ann. Nat. Hist.* ser. ii. vol. x. 1852, p. 413.

membrane that forms the sheath of the tube, when this is thick enough to interfere with its transparence. The tube itself should be slit up with a pair of fine scissors through its entire length, and should be so opened out that its expanded surface may be a continuation of that which forms the floor of the mouth. The mode of mounting it will depend upon the manner in which it is to be viewed. For the ordinary purposes of microscopic examination no method is so good as mounting in fluid, either weak spirit or Goadby's solution answering very well. But many of these palates, especially those of the marine Gastropods, become most beautiful objects for the polariscope when they are mounted in Canada balsam, the form and arrangement of the teeth being very strongly brought out by it (fig. 651), and a gorgeous play of colours being exhibited when a selenite plate is placed behind the object, and the analysing prism is made to rotate.[1]

FIG. 651.—Palate of *Buccinum undatum* as seen under polarised light.

Development of Molluscs.—Leaving to the scientific embryologist the large field of study that lies open to him in this direction,[2] the ordinary microscopist will find much to interest him in the observation of certain special phenomena of which a general account will be here given. Attached to the gills of fresh-water mussels (*Unio* and *Anodon*) there are often found in the spring or early summer minute bodies which, when first observed, were described as parasites, under the name of *Glochidia*, but are now known to be their own progeny in an early phase of development. When they are expelled from between the valves of their parent, they attach themselves in a peculiar manner to the fins and gills of fresh-water fish. In this stage of the existence of the young *Anodon*, its valves are provided with curious barbed or serrated hooks (fig. 652, A), and are continually snapping together, until they have inserted their hooks into the skin of the fish, which seems so to retain the barbs as to prevent the reopening of the valves. In this stage of its existence no internal organ is definitely formed, except the strong 'adductor' muscle (*add*) which draws the valves together, and the long, slender byssus-filament (*by*) which makes its appearance while the embryo is still within the egg-membrane, lying coiled up between the lateral lobes. The hollow of each valve is filled with a soft granular-looking mass, in which are to be distinguished what are perhaps the rudiments of the

[1] For additional details on the organisation of the palate and teeth of the Gastropod molluscs, see Mr. W. Thomson in *Cyclop. Anat. and Physiol.* vol. iv. pp. 1142, 1143, and in *Ann. Nat. Hist.* ser. ii. vol. vii. p. 86; Professor Troschel, *Das Gebiss der Schnecken*, Berlin, 1856–79; A. Rücker, 'Ueber die Bildung der Radula bei *Helix pomatia*,' *Bericht oberhess. Gesellsch. Giessen*, xxii. p. 209; P. Geddes, 'On the Mechanism of the Odontophore in certain Molluscs,' *Trans. Zool. Soc.* x. p. 485.

[2] See Balfour's *Comparative Embryology*, vol. i. chap. ix.

branchiæ and of oral tentacles; but their nature can only be c
tainly determined by further observation, which is rendered diffic
by the opacity of the valves. By keeping a supply of fish, howe
with these embryos attached, the entire history of the developm
of the fresh-water mussel may be worked out.[1]

In certain members of the class *Gastropoda* the history of
bryonic development presents numerous phenomena of great inter
The eggs (save among the terrestrial species) are usually deposite
aggregate masses, each inclosed in a common protective envelope
nidamentum. The nature of this envelope, however, varies great
thus, in the common *Limnæus stagnalis*, or 'water-snail,' of our po
and ditches it is nothing else than a mass of soft jelly, about the
of a sixpence, in which from fifty to sixty eggs are imbedded.
which is attached to the leaves or stems of aquatic plants; in
Buccinum undatum, or common whelk, it is a membranous c



FIG. 652.—A. Glochidium immediately after it is hatched: *ad*, adductor; *sh*, shell; *by*, byssus-cord; *s*, sense-organs. B. the same after it has been on the fish for some weeks: *br*, branchiæ; *aur*, auditory sack; *f*, food; *a.ad* and *p.ad*, anterior and posterior adductors; *al*, mesenteron; *mt*, mantle.

connected with a considerable number of similar cases by short stal
so as to form large globular masses which may often be picked up
our shores, especially between April and June; in the *Purp*
lapillus, or 'rock-whelk,' it is a little flask-shaped capsule, havin
firm horny wall, which is attached by a short stem to the surface
rocks between the tide marks, great numbers being often fou
standing erect side by side; whilst in the Nudibranchiate or
generally (consisting of the *Doris*, *Eolis*, and other 'sea-slugs')
forms a long tube with a membranous wall, in which imme
numbers of eggs (even half a million or more) are packed clos
together in the midst of a jelly-like substance, this tube being dispo
in coils of various forms, which are usually attached to sea-weeds
zoöphytes. The course of development, in the first and last of th
instances, may be readily observed from the very earliest period do

[1] See the Rev. W. Houghton, 'On the Parasitic Nature of the Fry of the *A*
donta cygnea,' in *Quart. Journ. Micros. Sci.* n.s. vol. ii. 1861, p. 162, and espe
Balfour, *op. cit.* pp. 220–223. On the embryonal byssus-gland of *Anodonta*,
J. Carrière, *Zoolog. Anzeig.* vii. p. 41.

to that of the emersion of the embryo, owing to the extreme transparence of the nidamentum and of the egg-membranes themselves. The first change which will be noticed by the ordinary observer is the 'segmentation' of the yolk-mass, which divides itself (after the manner of a cell undergoing binary subdivision) into two parts, each of these two into two others, and so on until a *morula*, or mulberry-like mass of minute yolk-segments, is produced (fig. 653, A–F), which is converted by 'invagination' into a 'gastrula,' whose form



FIG. 653.—Embryonic development of *Doris bilamellata*: A, ovum, consisting of enveloping membrane, *a*, and yolk, *b*; B, C, D, E, F, successive stages of segmentation of yolk; G, first marking out of the shape of the embryo; H, embryo on the eighth day; I, the same on the ninth day; K, the same on the twelfth day, seen on the left side at L; M, still more advanced embryo, seen at N as retracted within its shell; *a*, position of shell-gland; *c*, *c*. ciliated lobes; *d*, foot; *g*, hard plate or operculum attached to it; *h*, stomach; *i*, intestine; *m*, *n*, masses (glandular?) at the sides of the œsophagus; *o*, heart (?); *s*, retractor muscle (?); *t*, situation of funnel; *v*, membrane enveloping the body; *x*, auditory vesicles; *y*, mouth.

is shown at G. This 'gastrula' soon begins to exhibit a very curious alternating rotation within the egg, two or three turns being made in one direction, and the same number in a reverse direction: this movement is due to the cilia fringing a sort of fold of the ectoderm termed the *velum*, which afterwards usually gives origin to a pair of large ciliated lobes (H–L, *c*) resembling those of Rotifers. The velum is so little developed in *Limnæus*, however, that its existence was commonly overlooked until recognised by Professor Ray Lankester,[1] who also has been able to distinguish its fringe of minute cilia. This, however, has only a transitory existence; and the later rotation of the embryo, which presents a very curious spectacle when a number of ova are viewed at once under a low magnifying power, is due to the action of the cilia fringing the head and foot.

A separation is usually seen at an early period between the anterior or 'cephalic' portion, and the posterior or 'visceral' portion of the embryonic mass, and the development of the former advances with the greater activity. One of the first changes which is seen in it consists in its extension into a sort of fin-like membrane on either side, the edges of which are fringed with long cilia (fig. 653, H–L, *c*), whose movements may be clearly distinguished whilst the embryo is still shut up within the egg; at a very early period may also be discerned the 'auditory vesicles' (K, *x*) or rudimentary organs of hearing which scarcely attain any higher development in these creatures during the whole of life; and from the immediate neighbourhood of these is put forth a projection, which is afterwards to be evolved into the 'foot' or muscular disc of the animal. While these organs are making their appearance, the shell is being formed on the surface of the posterior portion, appearing first as a thin covering over its hinder part and gradually extending itself until it becomes large enough to inclose the embryo completely, when this contracts itself. The ciliated lobes are best seen in the embryos of Nudibranchs: and the fact of the universal presence of a shell in the embryos of that group is of peculiar interest, as it is destined to be cast off very soon after they enter upon active life. These embryos may be seen to move about, as freely as the narrowness of their prison permits, for some time previous to their emersion; and when set free by the rupture of the egg-cases they swim forth with great activity by the action of their ciliated lobes—these, like the 'wheels' of Rotifera, serving also to bring food to the mouth, which is at that time unprovided with the reducing apparatus subsequently found in it. The same is true of the embryo of *Lymnæus*, save that its swimming movements are less active, in consequence of the non-development of the ciliated lobes; and the currents produced by the cilia that fringe the head and the orifice of the respiratory sac seem to have reference chiefly to the provision of supplies of food and of aërated water for respira-

[1] See his valuable 'Observations on the Development of *Limnæus stagnalis* and on the early stages of other Mollusca' in *Quart. Journ. Micros. Sci.* October 1874: and 'On the Developmental History of the Mollusca,' *Phil. Trans.* 1875. See also Lereboullet, 'Recherches sur le Développement du Limnée,' in *Ann. des Sci. Nat. Zool.* 4e série, tom. xviii. p. 47.

tion. The disappearance of the cilia has been observed by Mr. Hogg to be coincident with the development of the teeth to a degree sufficient to enable the young water-snail to crop its vegetable food; and he has further ascertained that if the growing animal be kept in fresh water alone for some time, without vegetable matter of any kind, the gastric teeth are very imperfectly developed, and the cilia are still retained.[1]

A very curious modification of the ordinary plan of development is presented in *Purpura lapillus*, and it is probable that something of the same kind exists also in *Buccinum*, as well as in other Gastropods of the same extensive order (*Pectinibranchiata*). Each of the capsules already described contains from 500 to 600 egg-like bodies (fig. 654, A) imbedded in a viscid gelatinous substance; but only from twelve to thirty embryos usually attain complete development, and it is obvious, from the large comparative size which these attain (fig. 655, B), that each of them must include an amount of substance equal to that of a great number of the bodies originally found within the capsule. The explanation of this fact (long since noticed by Dr. J. E. Gray in regard to *Buccinum*) seems to be as follows. Of those 500 or 600 egg-like bodies, only a small part are fertile *ova*, the remainder being unfertilised eggs, the yolk material of which serves for the nutrition of the embryos in the later stages of their intracapsular life. The distinction between them manifests itself at a very early period, even in the first segmentation; for, while the latter divide into two equal hemispheres (fig. 654, B), the fertilised ova divide into a larger and a smaller segment (D); in the cleft between these are seen the minute 'directive vesicles,' which appear to be always double, although, from being seen 'end on,' only one may be visible; and near these is generally to be seen a clear space in each segment. The difference is still more strongly marked in the subsequent divisions; for, whilst the cleavage of the infertile eggs goes on irregularly, so as to divide each into from fourteen to twenty segments, having no definiteness of arrangement (C, E, F, G), that of the fertile ova takes place in such a manner as to mark out the distinction already alluded to between the 'cephalic' and the 'visceral' portions of the mass (H), and the evolution of the former into distinct organs very speedily commences. In the first instance a narrow transparent border is seen around the whole embryonic mass, which is broader at the cephalic portion (I); next,



FIG. 654.—Early stages of embryonic development of *Purpura lapillus*: A, egg-like spherule; B, C, E, F, G, successive stages of segmentation of yolk-spherules; D, H, I, J, K, successive stages of development of early embryos.

[1] See *Trans. Micros. Soc.* ser. ii. vol. ii. 1854, p. 93.

this border is fringed with short cilia, and the cephalic extension into two lobes begins to show itself; and then between the lobes a large mouth is formed, opening through a short wide œsophagus, the interior of which is ciliated, into the visceral cavity, occupied as yet only by the yolk-particles originally belonging to the ovum (K).

Whilst these developmental changes are taking place in the embryo, the whole aggregate of segments formed by the yolk-cleavage of the infertile eggs coalesces into one mass, as shown at A, fig. 655; and the embryos are often, in the first instance, so completely buried within this as only to be discoverable by tearing its portions asunder: but some of them may commonly be found upon its exterior, and those contained in one capsule very commonly exhibit the different



FIG. 655.—Later stages of embryonic development of *Purpura lapillus*. A, conglomerate mass of vitelline segments, to which were attached the embryos *a*, *b*, *c*, *d*, *e*. B, full-size embryo in more advanced stage of development.

stages of development represented in fig. 654, H–K. After a short time, however, it becomes apparent that the most advanced embryos are beginning to *swallow* the yolk-segments of the conglomerate mass, and capsules will not unfrequently be met with in which embryos of various sizes, as *a*, *b*, *c*, *d*, *e* (fig. 655, A), are projecting from its surface, their difference of size not being accompanied by advance in development, but merely depending upon the amount of this 'supplemental' yolk which the embryos have respectively gulped down. For during the time in which they are engaged in appropriating this additional supply of nutriment, although they increase in *size*, yet they scarcely exhibit any other change; so that the large embryo, fig. 655, *e*, is not apparently more advanced, as regards the formation of its organs, than the small embryo, fig. 654, K. So soon as this operation has been completed, however, and the embryo has attained its full bulk, the evolution of its organs takes place very rapidly; the

ciliated lobes are much more highly developed, being extended in a long sinuous margin, so as almost to remind the observer of the 'wheels' of Rotifera, and being furnished with very long cilia (fig. 655, B); the auditory vesicles, the tentacula, the eyes, and the foot successively make their appearance; a curious rhythmically contractile vesicle is seen, just beneath the edge of the shell in the region of the neck, which may, perhaps, serve as a temporary heart; a little later the real heart may be seen pulsating beneath the dorsal part of the shell; and the mass of yolk-segments of which the body is made up gradually shapes itself into the various organs of digestion, respiration, &c., during the evolution of which (and while they are as yet far from complete) the capsule thins away at its summit and the embryos make their escape from it.[1]

It happens not unfrequently that one of the embryos which a capsule contains does not acquire its 'supplemental' yolk in the manner now described, and can only proceed in its development as far as its original yolk will afford it material; and thus, at the time when the other embryos have attained their full size and maturity, a strange-looking creature, consisting of two large ciliated lobes with scarcely the rudiment of a body, may be seen in active motion among them. This may happen, indeed, not only to one, but to several embryos within the same capsule, especially if their number should be considerable; for it sometimes appears as if there were not food enough for all, so that, whilst some attain their full dimensions and complete development, others remain of unusually small size, without being deficient in any of their organs; and others, again, are more or less completely abortive—the supply of supplemental yolk which they have obtained having been too small for the development of their viscera, although it may have afforded what was needed for that of the ciliated lobes, eyes, tentacles, auditory vesicles, and even the foot—or, on the other hand, no additional supply whatever having been acquired by them, so that their development has been arrested at a still earlier stage. These phenomena are of so remarkable a character that they furnish an abundant source of interest to any microscopist who may happen to be spending the months of August and September in a locality in which the *Purpura* abounds; since, by opening a sufficient number of capsules, no difficulty need be experienced in arriving at all the facts which have been noticed in this brief summary.[2] It is much to be desired that such microscopists

[1] The Author thinks it worth while to mention the method which he has found most convenient for examining the contents of the egg-capsules of *Purpura*, as he believes that it may be advantageously adopted in many other cases. This consists in cutting off the two ends of the capsule (taking care not to cut far into its cavity), and in then forcing a jet of water through it by inserting the end of a fine-pointed syringe into one of the orifices thus made, so as to drive the contents of the capsule before it through the other. These should be received into a shallow cell and first examined under the simple microscope. For some further observations on the development of *Purpura*, see Professor Haddon, 'Notes on the Development of the Mollusca,' *Quart. Journ. Micros. Sci.* xxii. p. 367.

[2] Fuller details on this subject will be found in the Author's account of his researches in *Trans. Micros. Soc.* ser. ii. vol. iii. 1855, p. 17. His account of the process was called in question by MM. Koren and Danielssen, who had previously given an entirely different version of it, but was fully confirmed by the observations of Dr. Dyster. See *Ann. Nat. Hist.* ser. ii. vol. xx. 1857, p. 16. The independent

as possess the requisite opportunity would apply themselves to the study of the corresponding history in other Pectinibranchiate Gastropods, with a view of determining how far the plan now described prevails through the order. And now that these molluscs have been brought not only to live, but to breed, in artificial aquaria, it may be anticipated that a great addition to our knowledge of this part of their life-history will ere long be made.

Ciliary Motion on Gills.—There is no object that is better suited to exhibit the general phenomena of ciliary motion than a portion of the gill of some bivalve mollusc. The *Oyster* will answer the purpose sufficiently well; but the cilia are much larger on the gills of the *Mussel* (*Mytilus*),[1] as they are also on those of the *Anodon* or common 'fresh-water mussel' of our ponds and streams. Nothing more is necessary than to detach a small portion of one of the riband-like bands which will be seen running parallel with the edge of each of the valves when the shell is opened, and to place this, with a little of the liquor contained within the shell, upon a slip of glass—taking care to spread it out sufficiently with needles to separate the *bars* of which it is composed, since it is on the edges of these, and round their knobbed extremities, that the ciliary movement presents itself—and then covering it with a thin glass disc. Or it will be convenient to place the object in the aquatic box, which will enable the observer to subject it to any degree of pressure that he may find convenient. A magnifying power of about 120 diameters is amply sufficient to afford a general view of this spectacle; but a much greater amplification is needed to bring into view the peculiar mode in which the stroke of each cilium is made. Few spectacles are more striking to the unprepared mind than the exhibition of such wonderful activity as will then become apparent in a body which to all ordinary observation is so inert. This activity serves a double purpose: for it not only drives a continual current of water over the surface of the gills themselves, so as to effect the aëration of the blood, but also directs a portion of this current to the mouth, so as to supply the digestive apparatus with the aliment afforded by the *Diatomaceæ*, *Infusoria*, &c. which it carries in with it.

Organs of Sense of Molluscs.—Some of the minuter and more rudimentary forms of the special organs of sight, hearing, and touch which the molluscous series presents are very interesting objects of microscopic examination. Thus, just within the margin of each valve of *Pecten*, we see (when we observe the animal in its living state under water) a row of minute circular points of great brilliancy, each surrounded by a dark ring; these are the eyes with which this creature is provided, and by which its peculiarly active movements are directed. Each of them, when their structure is carefully examined, is found to be protected by a sclerotic coat with a transparent

observations of M. Claparède on the development of *Neritina fluviatilis* (Müller *Archiv*, 1857, p. 109, and abstract in *Ann. of Nat. Hist.* ser. ii. vol. xx. 1857, p. 13) showed the mode of development in that species to be the same in all essential particulars as that of *Purpura*. The subject has again been recently studied with great minuteness by Selenka, *Niederlandisches Archiv für Zoologie*, Bd. i. July 1862.

[1] This shellfish may be obtained, not merely at the sea-side, but likewise at the shops of the fishmongers who supply the humbler classes, even in midland towns.

cornea in front, and to possess a coloured iris (having a pupil) that is continuous with a layer of pigment lining the sclerotic, a crystalline lens and vitreous body, and a retinal expansion proceeding from an optic nerve which passes to each eye from the trunk that runs along the margin of the mantle.[1] Professor H. N. Moseley has made the interesting discovery that many of the *Chitonidæ* are provided with a large number of minute eyes on the exposed areas of the outer surfaces of their shells; as the fibres of the optic nerve are directed to the rods from behind these eyes are of the ordinary invertebrate type, and differ therein from the just mentioned eyes of *Pecten*, or those which are found on the back of *Onchidium*, which resemble the vertebrate retina in having the optic fibres inserted into the front aspect of the layer of rods.[2] Eyes of still higher organisation are borne upon the head of most Gastropod molluscs, generally at the base of one of the pairs of tentacles, but sometimes, as in the *Snail* and *Slug*, at the points of these organs. In the latter case the tentacles are furnished with a very peculiar provision for the protection of the eyes; for when the extremity of either of them is touched it is drawn back into the basal part of the organ, much as the finger of a glove may be pushed back into the palm. The retraction of the tentacle is accomplished by a strong muscular band, which arises within the head and proceeds to the extremity of the tentacles; whilst its protrusion is effected by the agency of the circular bands with which the tubular wall of the tentacle is itself furnished, the inverted portion being (as it were) squeezed out by the contraction of the lower part into which it has been drawn back. The structure of the eyes and the curious provision just described may easily be examined by snipping off one of the eye-bearing tentacles with a pair of scissors. None but the Cephalopod molluscs have distinct organs of hearing; but rudiments of such organs may be found in most Gastropods (fig. 653, K, *x*), attached to some part of the nervous collar that surrounds the œsophagus, and even in many bivalves, in connection with the nervous ganglion imbedded in the base of the foot. These 'auditory vesicles,' as they are termed, are minute sacculi, each of which contains a fluid, wherein are suspended a number of minute calcareous particles (named *otoliths*, or ear-stones), which are kept in a state of continual movement by the action of cilia lining the vesicles. This 'wonderful spectacle,' as it was truly designated by its discoverer Siebold, may be brought into view without any dissection by submitting the head of any small and not very thick-skinned Gastropod, or the young of the larger forms, to gentle compression under the microscope and transmitting a strong light through it. The very early appearance of the auditory vesicles in the embryo Gastropod has been already alluded to. Those who have the opportunity of examining young specimens of the common *Pecten* will find it extremely interesting to watch the action of the very delicate tentacles which they have the power of putting forth

[1] See Mr. S. J. Hickson on 'The Eye of Pecten' in *Quart. Journ. Micros. Sci.* vol. xx. n.s. 1880, p. 443.

[2] See Professor Moseley 'On the Presence of Eyes in the Shells of certain Chitonidæ, and on the Structure of these Organs,' in *Quart. Journ. Micros. Sci.* xxv. p. 37.

from the margin of their mantle, the animal being confine shallow cell, or in the zoöphyte trough; and if the observer be fortunate enough to obtain a specimen so young that the are quite transparent, he will find the spectacle presented ciliary movement of the gills, as well as the active play of t (of which the adult can make no such use), to be worthy o than a cursory glance.[1]

Chromatophores of Cephalopods.—Almost any species of fish (*Sepia*) or squid (*Loligo*) will afford the opportunity of exa the very curious provision which their skin contains for chang hue. This consists in the presence of numerous large 'pigment containing colouring matter of various tints, the prevailing however, being that of the fluid of the ink-bag. These pigmen may present very different forms, being sometimes nearly gl whilst at other times they are flattened and extended into rad prolongations; and, by the peculiar contractility with which th endowed, they can pass from one to the other of these conditio as to spread their coloured contents over a comparatively surface, or to limit them within a comparatively small area. commonly there are different layers of these pigment-cells, thei tents having different hues in each layer; and thus a great vari coloration may be given by the alteration in the form of the c which one or another layer is made up. It is curious tha changes in the hue of the skin appear to be influenced, as in th of the chameleon, by the colour of the surface with which it m in proximity. The alternate contractions and extensions of pigment-cells, or *chromatophores*, may be easily observed in a pi skin detached from the living animal and viewed as a transp object, since they will continue for some time if the skin be p in sea-water. And they may also be well seen in the embryo c fish, which will sometimes be found in a state of sufficient adv ment in the grape-like eggs of these animals attached to sea-w zoöphytes, &c. The eggs of the small cuttle-fish termed the *Se* which is very common on our southern coasts, are imbedded, like t of the *Doris*, in gelatinous masses, which are attached to sea-w zoöphytes, &c.; and their embryos, when near maturity, are tremely beautiful and interesting objects, being sufficiently t parent to allow the action of the heart to be distinguished, as we to show most advantageously the changes incessantly occurrin the form and hue of the 'chromatophores.'[2]

[1] Much valuable information concerning the sensory organs of molluscs w found in Dr. H. Simroth's memoir, 'Ueber die Sinneswerkzeuge unserer ein ischen Weichthiere,' *Zeitschr. für Wiss. Zool.* xxvi. p. 227.

[2] For further information regarding the chromatophores see an essay by Klemensiewicz in the *Sitzungsberichte* of the Vienna Academy, vol. lxxviii. p. 7.

The following works and memoirs on the Mollusca generally may be consulte the student: S. P. Woodward, *A Manual of the Mollusca*, 3rd ed. London, 1 Keferstein, in Bronn's *Klassen und Ordnungen des Thierreichs*; the article 'Mollu by Professor Ray Lankester, in the 9th edition of the *Encyclopædia Britann* and M. P. Fischer's *Manuel de Conchyliologie*. Paris, 1881–87; as well a numerous reports on the Mollusca collected by H.M.S. *Challenger*.

CHAPTER XIX

WORMS

UNDER the general designation of Worms naturalists at present group a number of Metazoa, which differ considerably among themselves, and exhibit on the one hand very simple, and on the other somewhat complex plans of organisation ; the assemblage is, indeed, hardly anything else than a zoölogical lumber-room, from which, with the progress of research, group after group may be expected to be removed. Among others there are included in it the *Entozoa* or intestinal worms, the *Rotifera* or wheel animalcules, *Turbellaria*, and *Annelida*, each of which furnishes many objects for microscopic examination that are of the highest scientific interest. As our business, however, is less with the professed physiologist than with the general inquirer into the minute wonders and beauties of Nature, we shall pass over these classes (the Rotifera having been already treated of in detail, Chapter XIII) with only a notice of such points as are likely to be specially deserving the attention of observers of the latter order.

Entozoa.—This term is one which has been applied to such worms as are parasitic within the bodies of other animals, and which obtain their nutriment by the absorption of the juices of these, thus bearing a striking analogy to the parasitic Fungi.[1] The most remarkable feature in their structure consists in the entire absence or the extremely low development of their nutritive system, and the extraordinary development of their reproductive apparatus. Thus in the common *Tænia* ('tape-worm'), which may be taken as the type of the Cestoid group, there is neither mouth nor stomach, the so-called 'head' being merely an organ for attachment, whilst the segments of the 'body' contain repetitions of a complex generative apparatus, the male and female sexual organs being so united in each as to enable it to fertilise and bring to maturity its own very numerous eggs ; and the chief connection between these segments is established by two pairs of longitudinal canals, which appear to represent the 'water-vascular system,' whose simplest condition has been noticed in the wheel-animalcule. Few among the recent results of micro-

[1] The most important work on human entozoic parasites is that by Professor Leuckart, *Die menschlichen Parasiten*, of which a second edition is now in course of publication; of this—the first portion has already been translated into English by Mr. W. E. Hoyle.

scopic inquiry have been more curious than the elucidation of real nature of the bodies formerly denominated *cystic* Entozoa, w had been previously ranked as a distinct group. These are found, like the preceding, in the cavity of the alimentary can the animals they infest, but always occur in the substance of organs, such as the glands, muscles, &c. They present themselv the eye as bags or vesicles of various sizes, sometimes occu singly, sometimes in groups; but upon careful examination vesicle is found to bear upon some part a 'head' furnished hooklets and suckers; and this may be either single, as in *Cystic* (the entozoön whose presence gives to pork what is known as 'measly' disorder), or multiple, as in *Cœnurus*, which is develope the brain, chiefly of sheep, where it gives rise to the disorder kn as 'the staggers.' Now, in none of these cystic forms has generative apparatus ever been discovered, and hence they ar viously to be considered as imperfect animals. The close resembl between the 'heads' of certain *Cysticerci* and that of certain *T* first suggested that the two might be different states of the animal; and experiments made by those who have devoted t selves to the working out of this curious subject have led to assured conclusion that the cystic Entozoa are nothing else cestoid worms, whose development has been modified by peculiarity of their position, the large bag being formed by a of dropsical accumulation of fluid when the young are evolved i midst of solid tissues, whilst the very same bodies, conveyed int alimentary canal of some carnivorous animal which has fed upo flesh infested with them, begin to bud forth the generative segm the long succession of which, united end to end, gives to the e series a band-like aspect.

The higher forms of Entozoa, belonging to the *Nematoi* thread-like order—of which the common *Ascaris* may be take a type, one species of it (the *A. lumbricoides* or 'round worm') bei common parasite in the small intestine of man, while another *Oxyuris vermicularis* or 'thread-worm') is found rather in the l bowel are much less profoundly degraded in their organisation; have a distinct alimentary canal, which commences with a mou the anterior extremity of the body, and which terminates by an orifice near the other extremity; and they also possess a re arrangement of circular and longitudinal muscular fibres by w the body can be shortened, elongated, or bent in any direction. smaller Nematode worms, by some or other of which almost e vertebrated animal is infested, are so transparent that every pa their internal organisation may be made out, especially with assistance of the compressor, without any dissection; and the st of the structure and actions of their generative apparatus has yie many very interesting results, especially in regard to the first for tion of the ova, the mode of their fertilisation, and the histor their subsequent development. Some of the worms belonging this group are not parasitic in the bodies of other animals, but in the midst of dead or decomposing vegetable matter. Others, s as *Gordius* or the 'hair-worm,' are parasitic for the greater par

their existence, but leave their host for the purpose of maturing their generative products; in these later stages the *Gordius* is frequently found in large knot-like masses (whence its name) in the water or mud of the pools inhabited by the insects in which the earlier stages were passed. The *Anguillulæ* are little eel-like worms, of which one species, *A. fluviatilis*, is very often found in fresh water amongst *Desmidieæ*, *Confervæ*, &c., also in wet moss and moist earth, and sometimes also in the alimentary canals of snails, frogs, fishes, insects, and larger worms; whilst an allied species, *Tylenchus tritici*, is met with in the ears of wheat affected with the blight termed the 'cockle'; another, the *A. glutinis* (*A. aceti*) is found in sour paste, and was often found in stale vinegar, until the more complete removal of mucilage and the addition of sulphuric acid, in the course of the manufacture, rendered this liquid a less favourable 'habitat' for these little creatures. A writhing mass of any of these species of 'eels' is one of the most curious spectacles which the microscopist can exhibit to the unscientific observer; and the capability which they all possess (in common with Rotifers and Tardigrades) of revival after desiccation, at a very remote interval, enables him to command the spectacle at any time. A grain of wheat within which these worms (often erroneously called *Vibriones*) are being developed gradually assumes the appearance of a black peppercorn; and if it be divided the interior will be found almost completely filled with a dense white cottony mass, occupying the place of the flour, and leaving merely a small place for a little glutinous matter. The cottony substance seems to the eye to consist of bundles of fine fibres closely packed together; but on taking out a small portion, and putting it under the microscope with a little water under a thin glass cover, it will be found after a short time (if not immediately) to be a wriggling mass of life, the apparent fibres being really *Anguillulæ* or 'eels' of the microscopist. If the seeds be soaked in water for a couple of hours before they are laid open, the eels will be found in a state of activity from the first; their movements, however, are by no means so energetic as those of the *A. glutinis* or 'paste eel.' This last frequently makes its appearance spontaneously in the midst of paste that is turning sour; but the best means of securing a supply for any occasion consists in allowing a portion of any mass of paste in which they may present themselves to dry up, and then, laying this by so long as it may not be wanted, to introduce it into a mass of fresh paste, which if it be kept warm and moist will be found after a few days to swarm with these curious little creatures.

Besides the foregoing orders of Entozoa, the *Trematode* group, which is more closely allied to the *Cestoda* than to the Nematodes must be named; of this the *Distoma hepaticum*, or 'fluke,' found in the livers of sheep affected with the 'rot,' is a typical example. Into the details of the structure of this animal, which has the general form of a sole, there is no occasion for us here to enter; it is remarkable, however, for the branching form of its digestive cavity, which extends throughout almost the entire body, very much as in the allied *Planariæ* (fig. 656); and also for the curious

phenomena of its development, several distinct forms being pas through between one sexual generation and another. These h been especially studied in the Distoma, which infests *Paludi* the ova of which are not developed into the likeness of th parents, but into minute worm-like bodies, which seem to be lit else than masses of cells inclosed in a contractile integument, formed organs being found in them ; these cells, in their turn, developed into independent zoöids, which escape from their conta ing cyst in the condition of free ciliated animalcules ; in this c dition they remain for some time, and then imbed themselves the mucus that covers the tail of the mollusc, in which they unde a gradual development into true Distomata ; and having thus quired their perfect form, they penetrate the soft integument, take up their habitation in the interior of the body. Thus a c siderable number of Distomata may be produced from a single ov by a process of cell-multiplication in an early stage of its devel ment. In some instances the free ciliated larvæ are provided w pigment-spots or rudimentary optic organs, although these organs wanting in the fully developed Distoma, the peculiar 'habitat which would render them useless.[1]

Turbellaria.—This group of animals, which is distinguished the presence of cilia over the entire surface of the body, conta forms which are among the simplest of those in which the Meta organisation obtains. It deserves special notice here chiefly on count of the frequency with which the worms of the Planar tribe present themselves among collections both of marine an fresh-water animals (particular species inhabiting either local and on account of the curious organisation which many of t possess. Most of the members of this tribe have elongated, flatte bodies, and move by a sort of gliding or crawling action over surfaces of aquatic plants and animals. Some of the smaller k are sufficiently transparent to allow of their internal structure b seen by transmitted light, especially when they are slightly c pressed ; and the opposite figure (fig. 656) displays the gen conformation of their principal organs as thus shown. The l has the flattened sole-like shape of the Trematode Entozoa mouth, which is situated at a considerable distance from the ante extremity of the body, is surrounded by a circular sucker tha applied to the living surface from which the animal draws its n ment ; and the buccal cavity (*b*) opens into a short œsophagus which leads at once to the cavity of the stomach. This cavity not give origin to any intestinal tube, nor is it provided with second orifice ; but a large number of ramifying canals are prolo from it, which carry its contents into every part of the body. seems to render unnecessary any system of vessels for the circula of nutritive fluid ; and the two principal trunks, with connec and ramifying branches, which may be observed in them ma

[1] On the development and life-history of the 'Liver-fluke' see A. P. Th *Quart. Journ. Micros. Sci.* xxiii. p. 1 ; and Professor R. Leuckart, *Archiv für N gesch.* xlviii. p. 80. On its anatomy, see Dr. F. Sommer, *Zeitschr. für Wiss.* xxxiv.

arded in the light of a gastro-vascular system, the function of ich is not only digestive, but also circulatory. Both sets of sexual ans are combined in the same individuals, though the congress wo, each impregnating the ova of the other, seems to be gene- ly necessary. The ovaria, as in the Entozoa, extend through a ge part of the body, their ramifications proceeding from the two ducts (k, k), which have a dilatation (l) at their point of junction. ere is still much obscurity ut the history of the em- onic development of these mals, as the accounts given it by different observers by means harmonise with each ier.[1] The *Planariæ*, how- r, do not multiply by eggs ne; for they occasionally un- go spontaneous fission in a nsverse direction, each seg- nt becoming a perfect animal; d an artificial division into o or even more parts may be actised with a like result. In t, the power of the *Planariæ* reproduce portions which ve been removed seems but tle inferior to that of the *dra*; a circumstance which peculiarly remarkable when much higher character of ir organisation is borne in nd. They possess a distinct r of nervous ganglia (f, f), m which branches proceed to ious parts of the body; and the neighbourhood of these usually to be observed a mber (varying from two to ty) of *ocelli* or rudimentary s, each having its refracting ly or crystalline lens, its pig- nt-layer, its nerve-bulb, and cornea-like bulging of the n. The integument of many these animals is furnished h cells containing rods or spindles which are very possibly nparable to the 'thread-cells' of zoöphytes.[2]



FIG. 656.—Structure of *Polycelis levigatus* (a Planarian worm): a, mouth, surrounded by its circular sucker; b, buccal cavity; c, œsophageal orifice; d, stomach; e, ramifications of gastric canals; f, cephalic ganglia and their nervous filaments; g, g, testes; h, vesicula seminalis; i, male genital canal; k, k, oviducts; l, dilatation at their point of junction; m, female genital orifice.

[1] See Balfour's *Comparative Embryology*, vol. i. pp. 159–162.

[2] For further information regarding the *Turbellaria* consult Dr. L. Graff's article Planarians in the 9th edition of the *Encyclopædia Britannica*, and his magnifi- t *Monographie der Turbellariden*, Leipzig, 1882; A. Lang, *Die Polycladen*, pzig, 1884; P. Hallez, *Contributions à l'histoire naturelle des Turbellariés*, le, 1879. On transverse fission, see Bell, *Journ. Roy. Micros. Soc.* (2), vi. p. 1107.

Annelids.—This class includes all the higher kinds of worm animals, the greater part of which are marine, though there well-marked group, the members of which inhabit fresh wat live on land. The body in this class is usually elongated and r always presents a well-marke mental division, the segments for the most part similar and to each other, except at th extremities; though in som the leech and its allies, th mental division is very indist seen, on account of the g softness of the integument large portion of the marine nelids have special respirato pendages, into which the flui the body are sent for aer and these are situated upo head (fig. 657) in those s which (like the *Serpula*, *Ter Sabellaria*, &c.) have their l inclosed by tubes, either form a shelly substance produced their own surface, or built the agglutination of grains of fragments of shell &c.[1]; whils are distributed along the two of the body in such as swim through the water, or craw the surfaces of rocks, as is th with the *Nereidæ*, or simply themselves in the sand, a *Arenicola* or 'lob-worm.' In respiratory appendages the lation of the fluids may b tinctly seen by microscopic e nation; and these fluids are kinds: first, a colourless fluid taining numerous cell-like puscles, which can be seen i smaller and more transp species to occupy the space intervenes between the oute face of the alimentary cana the inner wall of the body, a pass from this into canals which often ramify extensively i respiratory organs, but are never furnished with a returning of passages; and second, a fluid which is usually red, contain floating particles, and is inclosed in a system of proper vessels



FIG. 657.—Circulating apparatus of *Terebella conchilega*: *a*, labial ring; *b*, *b*, tentacles; *c*, first segment of the trunk; *d*, skin of the back; *e*, pharynx; *f*, intestine; *g*, longitudinal muscles of the inferior surface of the body; *h*, glandular organ; *i*, organs of generation; *j*, feet; *k*, *k*, branchiæ; *l*, dorsal vessel acting as a respiratory heart; *m*, dorso-intestinal vessel; *n*, venous sinus surrounding œsophagus; *n'*, inferior intestinal vessel; *o*, *o*, ventral trunk; *p*, lateral vascular branches.

[1] For an interesting account of the formation of these tubes see Mr. A. T. Wa paper in *Journ. Roy. Micr. Soc.* 1890, p. 685.

communicates with a central propelling organ, and not only carries away the fluid away from this, but also brings it back again. In *Terebella* we find a distinct provision for the aëration of both fluids; for the first is transmitted to the tendril-like tentacles which surround the mouth (fig. 657, *b*, *b*), whilst the second circulates through the beautiful arborescent gill-tufts (*k*, *k*) situated just behind the head. The former are covered with cilia, the action of which continually renews the stratum of water in contact with them, whilst the latter are destitute of these organs; and this seems to be the general fact as to the several appendages to which these two fluids are respectively sent for aëration, the nature of their distribution varying greatly in the different members of the class. In the observation of the beautiful spectacle presented by the respiratory circulation of the various kinds of Annelids which swarm on most of our shores, and in the examination of what is going on in the interior of their bodies (where this is rendered possible by their transparence) the microscopist will find a most fertile source of interesting occupation; and he may easily, with care and patience, make many valuable additions to our present stock of knowledge on these points. There are many of these marine Annelids in which the appendages of various kinds put forth from the sides of their bodies furnish very beautiful microscopic objects; as do also the different forms of teeth, jaws, &c. with which the mouth is commonly armed in the free or non-tubicolar species, which are eminently carnivorous.

The early history of the development of Annelids, too, is extremely curious; for they come forth from the egg in a condition very little more advanced than the ciliated gemmules of polypes, consisting of a globular mass of untransformed cells, certain parts of whose surface are covered with cilia, which ordinarily become arranged in one or more definite rings; in a few hours, however, this embryonic mass elongates, and the indications of a segmental division become apparent, the head being (as it were) marked off in front, whilst behind this is a large segment thickly covered with cilia, then a narrower and non-ciliated segment, and lastly the caudal or tail-segment, which is furnished with cilia. A little later a new segment is seen to be interposed in front of the caudal, and the dark internal granular mass shapes itself into the outline of an alimentary canal.[1] The number of segments progressively increases by the interposition of new ones between the caudal and its preceding segments; the various internal organs become more and more distinct, eye-spots make their appearance,

[1] A most curious transformation once occurred within the Author's experience in the larva of an Annelid, which was furnished with a broad collar or disc fringed with very long cilia, and showed merely an appearance of segmentation in its hinder part; for in the course of a few minutes, during which it was not under observation, this larva assumed the ordinary form of a marine worm three or four times its previous length, and the ciliated disc entirely disappeared. An accident unfortunately prevented the more minute examination of this worm, which the Author would have otherwise made; but he may state that he is certain that there was no fallacy as to the fact above stated, this larva having been placed by itself in a cell, on purpose that it might be carefully studied, and having been only laid aside for a short time whilst other selections were being made from the same gathering of the tow-net.

little bristly appendages are put forth from the segments, the animal gradually assumes the likeness of its parent; a days being passed by the tubicolar kinds, however, in the act moving condition, before they settle down to the formation tube.[1]

To carry out any systematic observations on the embry development of Annelids the eggs should be searched for ir situations which these animals haunt; but in places where A lids abound free-swimming larvæ are often to be obtained a same time and in the same manner as small Medusæ; and the probably no part of our coasts off which some very curious f may not be met with. The following may be specially menti as departing widely from the ordinary type, and as in thems extremely beautiful objects: The *Actinotrocha* (fig. 658) be strong resemblance in many partic to the 'bipinnarian' larva of a fish, having an elongated body, a series of ciliated tentacles (*d*) metrically arranged; these tent however, proceed from a sort of which somewhat resembles the 'l phore' of certain Polyzoa. The m (*e*) is concealed by a broad but po hood or 'epistome' (*a*), which s times closes down upon the tenta disc, but is sometimes raised anc tended forwards. The nearly c drical body terminates abruptly a other extremity, where the anal o of the intestine (*b*) is surrounded circlet of very large cilia. This a swims with great activity, somet by the tentacular cilia, sometime the anal circlet, sometimes by combined; and besides its move of progression it frequently do itself together, so as to bring the extremity and the epistome almost contact. It is so transparent tha whole of its alimentary canal ma as distinctly seen as that of Lagun and, as in that polyzoön, the alin ary masses often to be seen within the stomach (*c*) are kept continual whirling movement by the agency of cilia with whic walls are clothed. This very interesting creature was for a time a puzzle to zoölogists; since, although there could be doubt of its being a larval form, there was no clue to the natur the adult produced from it until this was discovered by Kroh

FIG. 658.—*Actinotrocha branchiata*: *a*, epistome or hood; *b*, anus; *c*, stomach; *d*, ciliated tentacles; *e*, mouth.

[1] For further information on this subject see Balfour's *Comparative Embryo* vol. i. chap. xii. and the memoirs there cited.

1858 to be a Gephyrean worm (*Phoronis*).[1] An even more extraordinary departure from the ordinary type is presented by the larva which has received the name *Pilidium* (fig. 659), its shape being that of a helmet, the plume of which is replaced by a single long bristle-like appendage that is in continual motion, its point moving round and round in a circle. This curious organism, first noticed by Johannes Müller, has been since ascertained to be the larva of



FIG. 659.—*Pilidium gyrans*: A, young, showing at *a* the alimentary canal, and at *b* the rudiment of the Nemertid; B, more advanced stage of the same; C, newly freed Nemertid.

some species of the Nemertine worms, which belong to the division *Anopla*, a group in which there are no stylets to the proboscis.[2]

Among the animals captured by the tow-net the marine zoölogist will not be unlikely to meet with an Annelid which, although by no means microscopic in its dimensions, is an admirable subject for microscopic observation, owing to the extreme trans-

[1] 'Ueber *Pilidium* und *Actinotrocha*' in Müller's *Archiv*, 1858, p. 293. For more recent observations upon this interesting creature, see Balfour's *Comparative Embryology*, vol. i. pp. 299–302; and a paper on 'The Origin and Significance of the Metamorphosis of *Actinotrocha*,' by Mr. E. B. Wilson (of Baltimore), in *Quart. Journ. Micros. Sci.* April 1881.

[2] See especially Leuckart and Pagenstecher's 'Untersuchungen über niedere Seethiere' in Müller's *Archiv*, 1858, p. 569; and Balfour, *op. cit.* p. 165. The Author has frequently met with *Pilidium* in Lamlash Bay.

parence of its entire body, which is such as to render it diffic
be distinguished when swimming in a glass jar except by



FIG. 660.—Structure and development of *Tomopteris onisciformis*: A, port of caudal prolongations, containing the spermatic sacs, *a a*; B, adult n specimen; C, hinder part of adult female specimen, more enlarged, show ova, lying freely in the perivisceral cavity and its caudal prolongation; ciliated canal, commencing externally in the larger and smaller rosette-discs, *a*, *b*; E, one of the pinnulated segments, showing the position of ciliated canal, *c*, and its rosette-like discs, *a*, *b*; showing also the incipi development of the ova, *d*, at the extremity of the segment; F, cephalic g glion, with its pair of auditory (?) vesicles, *a a*, and its two ocelli, *b b*; G, v young *Tomopteris*, showing at *a a* the larval antennæ; *b b*, the incipi long antennæ of the adult; *c*, *d*, *e*, *f*, four pairs of succeeding pinnula segments, followed by bifid tail.

vourable light. This is the *Tomopteris*, so named from the vision of the lateral portions of its body into a succession of wing-:e segments (fig. 660, B), each of them carrying at its extremity a ir of pinnules, by the movements of which it is rapidly propelled rough the water. The full-grown animal, which measures nearly ı inch in length, has first a curious pair of 'frontal horns' pro-:ting laterally from the head, so as to give the animal the appear-ıce of a 'hammer-headed' shark; behind these there is a pair of ry long antennæ, in each of which we distinguish a rigid bristle-:e stem or *seta*, inclosed in a soft sheath, and moved at its base ' a set of muscles contained within the lateral protuberances at e head. Behind these are about sixteen pairs of the ordinary nnulated segments, of which the hinder ones are much smaller an those in front, gradually lessening in size until they become most rudimentary; and where these cease the body is continued ıwards into a tail-like prolongation, the length of which varies eatly according as it is contracted or extended. This prolongation, ›wever, bears four or five pairs of very minute appendages, and e intestine is continued to its very extremity, so that it is really be regarded as a continuation of the body. In the head we find, ›tween the origins of the antennæ, a ganglionic mass, the component lls of which may be clearly distinguished under a sufficient mag-fying power, as shown at F; seated upon this are two pigment-ots (*b*, *b*), each bearing a double pellucid lens-like body, which are ›viously rudimentary eyes; whilst imbedded in its anterior por-on are two peculiar nucleated vesicles, *a*, *a*, which are probably e rudiments of some other sensory organs. On the under side of e head is situated the mouth, which, like that of many other nnelids, is furnished with a sort of proboscis that can be either ›jected or drawn in; a short œsophagus leads to an elongated omach, which, when distended with fluid, occupies the whole ›vity of the central portion of the body, as shown in fig. B, but hich is sometimes so empty and contracted as to be like a mere ›rd, as shown in fig. C. In the caudal appendage, however, it is ways narrowed into an intestinal canal; this, when the appendage in an extended state, as at C, is nearly straight; but when the ›pendage is contracted, as seen at B, it is thrown into convolutions. ıe perivisceral cavity is occupied by fluid, in which some minute ›rpuscles may be distinguished; and these are kept in motion by lia which clothe some parts of the outer surface of the alimentary nal and line some part of the wall of the body. No other more ›ecial apparatus, either for the circulation or for the aëration of e nutrient fluid, exists in this curious worm, unless we are to gard as subservient to the respiratory function the ciliated canal hich may be observed in each of the lateral appendages except e five anterior pairs. This canal commences by two orifices at e base of the segment, as shown at fig. E, *b*, and on a larger scale fig. D; each of these orifices (D, *a*, *b*) is surrounded by a sort of sette, and the rosette of the larger one (*a*) is furnished with diating ciliated ridges. The two branches incline towards each ıer, and unite into a single canal that runs along for some dis-

tance in the wall of the body, and then terminates in the perivisceral cavity, and the direction of the motion of the cilia which line it is from without inwards.

The reproduction and developmental history of this Annelid present many points of great interest. The sexes appear to be distinct, ova being found in some individuals and spermatozoa in others. The development of the ova commences in certain 'germ-cells' situated within the extremities of the pinnulated segments, where they project inwards from the wall of the body: these, when set free, float in the fluid of the perivisceral cavity and multiply themselves by self-division; and it is only after their number has thus been considerably augmented that they begin to increase in size and to assume the characteristic appearance of ova. In this stage they usually fill the perivisceral cavity, not only of the body, but of its caudal extension, as shown at C; and they escape from it through transverse fissures which form in the outer wall of the body at the third and fourth segments. The male reproductive organs, on the other hand, are limited to the caudal prolongation, where the sperm-cells are developed within the pinnulated appendages, as the germ-cells of the female are within the appendages of the body. Instead of being set free, however, into the perivisceral cavity, they are retained within a saccular envelope forming a testis (A, *a*, *a*) which fills up the whole cavity of each appendage; and within this the spermatozoa may be observed, when mature, in active movement. They make their escape externally by a passage that seems to communicate with the smaller of the two just mentioned rosettes; but they also appear to escape into the perivisceral cavity by an aperture that forms itself when the spermatozoa are mature. Whether the ova are fertilised while yet within the body of the female by the entrance of spermatozoa through the ciliated canals, or after they have made their escape from it, has not yet been ascertained. Of the earliest stages of embryonic development nothing whatever is yet known; but it has been ascertained that the animal passes through a larval form, which differs from the adult not merely in the number of the segments of the body (which successively augment by additions at the posterior extremity), but also in that of the antennæ. At G is represented the earliest larva hitherto met with, enlarged as much as ten times in proportion to the adult at B; and here we see that the head is destitute of the frontal horns, but carries a pair of setigerous antennæ, *a*, *a*, behind which there are five pairs of bifid appendages, *b*, *c*, *d*, *e*, *f*, in the first of which, *b*, one of the pinnules is furnished with a *seta*. In more advanced larvæ having eight or ten segments this is developed into a second pair of antennæ resembling the first; and the animal in this stage has been described as a distinct species, *T. quadricornis*. At a more advanced age, however, the second pair attains the enormous development shown at B, and the first or larval antennæ disappear, the setigerous portions separating at a sort of joint (G, *a*, *a*), whilst the basal projections are absorbed into the general wall of the body. This beautiful creature has been met with on so many parts of our coast that it cannot be considered at all uncommon,

nd the microscopist can scarcely have a more pleasing object for tudy.[1] Its elegant form, its crystal clearness, and its sprightly, raceful movements render it attractive even to the unscientific bserver; whilst it is of special interest to the physiologist as one f the simplest examples yet known of the Annelid type.

To one phenomenon of the greatest interest presented by various mall marine Annelids the attention of the microscopist should be pecially directed; this is their *luminosity*, which is not a steady low like that of the glow-worm or fire-fly, but a series of vivid cintillations (strongly resembling those produced by an electric ischarge through a tube spotted with tinfoil), that pass along a onsiderable number of segments, lasting for an instant only, but apable of being repeatedly excited by any irritation applied to the ody of the animal. These scintillations may be discerned under he microscope, even in separate segments, when they are subjected o the irritation of a needle-point or a gentle pressure; and it has been scertained by the careful observations of M. de Quatrefages that hey are given out by the muscular fibres in the act of contraction.[2]

Among the fresh-water Annelids those most interesting to the icroscopist are the worms of the *Nais* tribe, which are common in ur rivers and ponds, living chiefly amidst the mud at the bottom, nd especially among the roots of aquatic plants. Being blood-red n colour, they give to the surface of the mud, when they protrude hemselves from it in large numbers and keep the protruded portion f their bodies in constant undulation, a very peculiar appearance; ut if disturbed they withdraw themselves suddenly and completely. hese worms, from the extreme transparency of their bodies, present eculiar facilities for microscopic examination, and especially for the tudy of the internal circulation of the red liquid commonly conidered as blood. There are here no external respiratory organs, and he thinness of the general integument appears to supply all needful acility for the aëration of the fluids. One large vascular trunk (dorsal) nay be seen lying above the intestinal canal, and another (ventral) beneath it, and each of these enters a contractile dilatation, or heart-ike organ, situated just behind the head. The fluid moves forwards n the dorsal trunk as far as the heart, which it enters and dilates; nd when this contracts it propels the fluid partly to the head and artly to the ventral heart, which is distended by it. The ventral eart, contracting in its turn, sends the blood backwards along the entral trunk to the tail, whence it passes towards the head as efore. In this circulation the stream branches off from each of he principal trunks into numerous vessels proceeding to different arts of the body, which then return into the other trunk; and here is a peculiar set of vascular coils, hanging down in the perisceral cavity that contains the corpusculated liquid representing he true blood, which seem specially destined to convey to it the

[1] See the memoirs of the Author and M. Claparède in vol. xxii. of the *Linnean Transactions* and the authorities there referred to; also a recent memoir by Dr. F. Vejdovsky in *Zeitschrift f. Wiss. Zool.* Bd. xxxi. 1878.

[2] See his memoirs on the Annelida of La Manche in *Ann. des Sci. Nat.* ser. ii. Zool. tom. xix. and ser. iii. Zool. tom. xiv.; and Professor McIntosh in *Nature*, xxii. p. 478.

aërating influence received by the red fluid in its circuit. acting (so to speak) like internal gills. The Naiad worms been observed to undergo spontaneous division during the su months, a new head and its organs being formed for the po segment behind the line of constriction before its separation the anterior.[1] In the Leech tribe the dental apparatus with the mouth is furnished is one of the most curious among points of minute structure, and the common 'medicinal' affords one of the most interesting examples of it. Wh commonly termed the 'bite' of the leech is really a saw-cu rather a combination of three saw-cuts, radiating from a co centre. If the mouth of the leech be examined with a magnifier, or even with the naked eye, it will be seen to triangular aperture in the midst of a sucking disc, and on tu back the lips of that aperture three little white ridges are br into view. Each of these is the convex edge of a horny semi strengthened by a deposit of carbonate of lime which is border a row of eighty or ninety minute hard and sharp teeth; the straight border of the semicircle is imbedded in the mu substance of the disc, by the action of which it is made to backwards and forwards in a saw-like manner, so that the tee enabled to cut into the skin to which the suctorial disc has a itself.[2]

[1] See Professor A. G. Bourne, 'On Budding in the Oligochæta,' *Repor Assoc.* 1885, p. 1096.

[2] Among the various sources of information as to the anatomy and physio the Annelids the following may be specially mentioned: the 'Histoire Natur Annelés Marins et d'Eau douce' of M. de Quatrefages, forming part of the S *Buffon*; the successive admirable monographs of the late Professor Ed. Cla *Recherches Anatomiques sur les Annélides, Turbellariés, Opalines et Grég observés dans les Hébrides*, Geneva, 1861; *Recherches Anatomiques sur les chètes*, Geneva, 1862; *Beobachtungen über Anatomie und Entwickelungsges Wirbellosen Thiere an der Küste von Normandie*, Leipzig, 1863; and *Les An Chétopodes du Golfe de Naples*, Geneva, 1868–70; the monograph of Dr. Ehl *Borstenwürmer* (*Annelida Chætopoda*), 1864–68. With the exception of Pr McIntosh's article in the *Encyclopædia Britannica* and Professor Vejdovsky's *und Morphologie der Oligochæten*, Prague, 1884, most of the recent pa Annelids have dealt with small groups only, but of these a very large numb appeared. For the descriptions of new forms the memoirs of Grube and M are especially to be consulted; Kleinenberg, Hatschek, and Salensky have the most important contributions to our knowledge of development; Bergh, E Eisig, Perrier, and Whitman have, among others, added to our knowledge anatomy and morphology.

CHAPTER XX

CRUSTACEA

SING to the division of Arthropods, in which the body is
nished with distinctly articulated or jointed limbs, some of which
always modified to serve as mouth-organs, we come first to the
s of *Crustacea*, which ordinarily includes (when used in its
t comprehensive sense) all those animals belonging to this group
ch are fitted for aquatic respiration, though the king-crab
nulus) has closer relations to the scorpions, and the Pycnogonids
the spiders. It thus comprehends a very extensive range of
ns ; for although we are accustomed to think of the crab, lobster,
r-fish, and other well-known species of the order *Decapoda* (ten-
ed), as its typical examples, yet all these belong to the highest
ts many orders ; and among the lower are many of a far simpler
cture, and not a few which would not be recognised as belonging
he class at all were it not for the information given by the
ly of their development as to their real nature, which is far more
arent in their early than it is in their adult condition. Many
he inferior kinds of Crustacea are so minute and transparent
t their whole structure may be made out by the aid of the
roscope without any preparation ; this is the case, indeed, with
rly the whole group of *Entomostraca*, and with the larval forms
n of the *crab* and its allies ; and we shall give our first atten-
to these, afterwards noticing such points in the structure of the
er kinds as are likely to be of general interest.

A curious example of the reduction of an elevated type to a
y simple form is presented by the group of *Pycnogonida*, or no-
y crabs, some of the members of which may be found by atten-
search in almost every locality where sea-weeds abound, it
ig their habit to crawl (or rather to sprawl) over the surfaces of
se, and probably to imbibe as food the gelatinous substance with
ch they are invested.[1] The general form of their bodies (fig.
) usually reminds us of that of some of the long-legged crabs,
abdomen being almost or altogether deficient, whilst the head is
r small, and fused (as it were) into the thorax ; so that the last-
ned region, with the members attached to it, constitutes nearly
whole bulk of the animal. The head is extended in front into

[1] It is remarkable that very large forms of this group, sometimes extending to
than twelve inches across, have been brought up from great depths of the sea.

a proboscis-like projection, at the extremity of which is the narrow orifice of the mouth, which draws in the semi-fluid aliment. Instead of being furnished (as in the higher crustaceans) with two pairs of antennæ and numerous pairs of 'foot-jaws,' it has but a single pair of either; it also bears four minute *ocelli*, or rudimentary eyes, set at a little distance from each other on a sort of tubercle. From the thorax proceed four pairs of legs, each composed of several joints and terminated by a hooked claw; and by these members the animal drags itself slowly along, instead of walking actively upon them like a crab. The mouth leads to a very narrow œsophagus (*a*), which passes back to the central stomach (*b*) situated in the



FIG. 661.—*Ammothea pycnogonoides*: *a*, narrow œsophagus; *b*, stomach; *c*, intestine; *d*, digestive cæca of the foot-jaws; *e*, *e*, digestive cæca of the legs.

midst of the thorax, from the hinder end of which a narrow intestine (*c*) passes off, to terminate at the posterior extremity of the body. From the central stomach five pairs of cæcal prolongations radiate, one pair (*d*) entering the foot-jaws, the other four (*e*, *e*) penetrating the legs, and passing along them as far as the last joint but one; and those extensions are covered with a layer of brownish-yellow granules, which are probably to be regarded as a digestive gland. The stomach and its cæcal prolongations are continually executing peristaltic movements of a very curious kind; for they contract and dilate with an irregular alternation, so that a flux and reflux of their contents is constantly taking place between the central portion and its radiating extensions. The perivisceral space between the widely extended stomach and the walls of the body and

bs is occupied by a transparent liquid, in which are seen floating umber of minute transparent corpuscles of irregular size; and s fluid, which represents the blood, is kept in continual motion, only by the general movements of the animal, but also by the ions of the digestive apparatus; since, whenever the cæcum of one of the legs undergoes dilatation, a part of the circumbient liquid will be pressed out from the cavity of that limb, ıer into the thorax or into some other limb whose stomach is tracting. The fluid must obtain its aëration through the general face of the body, as there are no special organs of respiration. e nervous system consists of a single ganglion in the head (formed the coalescence of a pair), and of another in the thorax (formed the coalescence of four pairs), with which the cephalic ganglion onnected in the usual mode, namely, by two nervous cords which erge from each other to embrace the œsophagus. In the study he very curious phenomena exhibited by the digestive apparatus, well as of the various points of internal conformation which have n described, the achromatic condenser will be found useful, even h the 1-inch, $\frac{2}{3}$-inch, or $\frac{1}{2}$-inch objectives; for the imperfect nsparence of the bodies of these animals renders it of importance drive a large quantity of light through them, and to give to this ıt such a quantity as shall sharply define the internal organs.[1]

Entomostraca.—This group of crustaceans, many of the existing mbers of which are of such minute size as to be only just visible to naked eye, is distinguished by the fact that they never have more n three pairs of their appendages converted into mouth-organs, any appendage on such segments as may lie behind the generative fices. The segments into which the body is divided are frequently y numerous, and are for the most part similar to each other; but re is a marked difference in regard to the appendages which they r, and to the mode in which these minister to the locomotion of animals. For in what have been called the *Lophyropoda*, or istly footed' tribe, a small number of legs not exceeding five pairs e their function limited to locomotion, the respiratory organs ng attached to the parts in the neighbourhood of the mouth; ilst in the *Branchiopoda*, or 'gill-footed' tribe, the members own as 'fin-feet') serve both for locomotion and for respiration, l the number of these is commonly large, being in *Apus* as many ixty pairs. The character of their movements differs accordingly; whilst all the members of the first-named tribe dart through the ter in a succession of jerks, so as to have acquired the common ne of 'water-fleas,' those among the latter which possess a great

[1] Certain points of resemblance borne by *Pycnogonida* to spiders make the ful study of their development a matter of special interest and importance, as e is some reason to regard them rather as *Arachnida* adapted to a marine tat than as Crustacea. See Balfour's *Comparative Embryology*, pp. 448, 449, the authorities there referred to. The most recent additions to the literature he Pycnogonids are Dr. A. Dohrn's *Die Pantopoden des Golfes von Neapel* Leipzig, 1881; Dr. P. P. C. Hoek's 'Report on the Pycnogonida of the *Challenger*,' , and his 'Nouvelle Etude sur les Pycnogonides,' in *Archives de Zool. Expér.* ix. 15; and Professor G. O. Sars' report in the *Zoölogy of the Norwegian North Sea* edition

number of 'fin-feet,' swim with an easy gliding movement, some
on their back alone (as is the case with *Branchipus*) and some
with equal facility on the back, belly, or sides (as is done by *Ar*
salina, the 'brine-shrimp'). Some of the most common form
both tribes will now be briefly noticed.

The first group contains two orders, of which the first, *Ostra*
is distinguished by the complete inclosure of the body in a bi
shell, by the small number of legs, and by the absence of an ext
egg-sac. One of the best known examples is the little *Cypris*, w
is a common inhabitant of pools and streams ; this may be recog
by its possession of two pairs of antennæ, the first having num
joints with a pencil-like tuft of filaments, and projecting forw
from the front of the head, whilst the second has more the sha
legs, and is directed downwards, and by the limitation of its le
two pairs, of which the posterior does not make its appearance ou
the shell, being bent upwards to give support to the ovaries.
valves are generally opened widely enough to allow the greater
of both pairs of antennæ and of the front pair of legs to pass
between them ; but when the animals are alarmed, they draw t
members within the shell, and close the valves firmly. They
very lively creatures, being almost constantly seen in motion, ei
swimming by the united action of their foot-like antennæ and
or walking upon plants and other solid bodies floating in the w
Nearly allied to the preceding is *Cythere*, whose body is furni
with three pairs of legs, all projecting out of the shell, and w
superior antennæ are destitute of the filamentous brush ; this g
is almost entirely marine, and some species of it may almost
variably be met with in little pools among the rocks between
tide-marks, creeping about (but not swimming) amongst Confe
and Corallines. There is abundant evidence of the former existe
of Crustacea, of larger size than any now existing, for in cer
fresh-water strata, both of the Secondary and Tertiary series, we
layers, sometimes of great extent and thickness, which are alm
entirely composed of the fossilised shells of *Cypridæ* ; whilst
certain parts of the chalk, which was a marine deposit, the rema
of bivalve shells resembling those of *Cythere* present themsel
in such abundance as to form a considerable part of its s
stance.[1]

In the order *Copepoda* there is a jointed shell forming a k
of buckler or carapace that almost entirely incloses the head
thorax, an opening being left beneath, through which the appenda
project ; and there are five pairs of legs, mostly adapted for sw
ming, the fifth pair, however, being rudimentary in the genus *Cycl*
the commonest example of the group. This genus receives its na
from possessing only a single eye, or rather a single cluster of ocel
which character, however, it has in common with the two gen
already named, as well as with *Daphnia*, and with many oth

[1] On the recent British Ostracoda see the monograph by G. S. Brady in vol. x
of the *Transactions of the Linnean Society* of London; compare also Zenk
'Monographie der Ostracoden,' *Archiv für Naturg.* xx. 1854. Claus has an essay
the development of *Cypris*, Marburg, 1868; see also Dr. Brady's '*Challenger*' Repo

Entomostraca. It contains numerous species, some of which belong to the fresh water, whilst others are marine. The fresh-water species often abound in the muddiest and most stagnant pools, as well as in the clearest springs ; the ordinary water with which London is supplied frequently contains large numbers of them. Of the marine species some are to be found in the localities in which the *Cythere* is most abundant, whilst others inhabit the open ocean, and must be collected by the tow-net. The body of the *Cyclops* is soft and gelatinous, and it is composed of two distinct parts, a thorax (fig. 662, *a*) and an abdomen (*b*), of which the latter, being comparatively slender, is commonly considered as a tail, though traversed by the intestine which terminates near its extremity. The head, which coalesces with the thorax, bears one very large pair of antennæ (*c*), possessing numerous articulations and furnished with bristly appendages, and another small pair (*d*) ; it is also furnished with a pair of mandibles or true jaws, and with two pairs of 'maxillæ,' of which the hinder pair is the longer and more abundantly supplied with bristles. The legs (*e*) are all beset with plumose tufts, as is also the tail (*f*, *f*) which is borne at the extremity of the abdomen. On either side of the abdomen of the female, there is often to be seen an egg-capsule (B) ; within which the ova, after being fertilised, undergo the earlier stages of their development. The *Cyclops* is a very active creature, and strikes the water in swimming, not merely with its legs and tail, but also with its antennæ. The rapidly repeated movements of its feet-jaws serve to create a whirlpool in the surrounding water, by which minute animals of various kinds, and even its own young, are brought to its mouth to be devoured.[1]



FIG. 662.—A, female of *Cyclops quadricornis*: *a*, body; *b*, tail; *c*, antenna; *d*, antennule; *e*, feet; *f*, plumose setæ of tail. B, tail, with external egg-sacs. C, D, E, F, G, successive stages of development of young.

The tribe of *Branchiopoda* is divided also into two groups, of which the *Cladocera* present the nearest approach to the preceding, having a bivalve carapace, no more than from four to six pairs of legs, two pairs of antennæ, of which one is large and branched and

[1] See for British forms Professor G. S. Brady's *Monograph of the free and semi-parasitic Copepoda of the British Islands*, published by the Ray Society, 1878–80.

adapted for swimming, and a single eye. The commonest for
this is the *Daphnia pulex*, which is sometimes called the 'arbores
water-flea,' from the branching form of its antennæ. It is
abundant in many ponds and ditches, coming to the surface in
mornings and evenings and in cloudy weather, but seeking
depths of the water during the heat of the day. It swim
taking short springs; and feeds on minute particles of vegetable
stances, but does not, however, reject animal matter when off
Some of the peculiar phenomena of its reproduction will be pres
described.

The other group, *Phyllopoda*, includes those Branchiopoda w
body is divided into a great number of segments, nearly all of w
are furnished with leaf-like appendages, or 'fin-feet.' The
families which this group includes, however, differ considerab
their conformation; for in that of which the genera *Apus* and *Neb*
are representatives, the body is inclosed in a shell, either shield
or bivalve, and the feet are generally very numerous; whilst in
which contains *Branchipus* and *Artemia*, the body is entirely u
tected, and the number of pairs of feet does not exceed eleven.
Apus cancriformis, which is an animal of comparatively large siz
entire length being about 2½ inches, is an inhabitant of stag
waters; but although occasionally very abundant in particular
or ditches, it is not to be met with nearly so commonly as the I
mostraca already noticed; in this country, indeed, it is exceed
rare. It is recognised by its large oval carapace, which cover
head and body like a shield; by the nearly cylindrical form o
body, which is composed of thirty articulations, and by the
number of its appendages, which amount to about sixty pairs.
number of joints in these is so great that in a single individual
may be safely estimated at not less than two millions. These or
however, are for the most part small; and the instruments cl
used by the animal for locomotion are the first pair of feet, whic
very much elongated (bearing such a resemblance to the prin
antennæ of other Entomostraca as to be commonly ranked in
same light), and are distinguished as *rami* or oars. With these
can swim freely in any position; but when the rami are at rest,
the animal floats idly on the water, its fin-feet may be seen in
cessant motion, causing a sort of whirlpool in the water, and brin
to the mouth the minute animals (chiefly the smaller Entomost
inhabiting the same localities) that serve for its food. The *Branch*
stagnalis has a slender, cylindriform, and very transparent bod
nearly an inch in length, furnished with eleven pairs of fin-feet.
is destitute of any protecting envelope; its head is furnished wi
pair of very curious prehensile organs (which are really mod
antennæ), whence it has received the name of *Cheirocephalus*;

[1] Professor Claus has pointed out the relations of *Nebalia* to the Malacostra
higher division of the Crustacea, and has suggested for the group which the
present the name of *Leptostraca*. See the *Zeitschr. für Wiss. Zool.* 1872, p.
and Claus, *Untersuchungen zur Erforschung der genealogischen Grundlage*
Crustaceen-Systems, Wien, 1876; but a different view is taken by Professor G
Sars in his Report on the *Challenger* Phyllocarida.

these are not used by it for the seizure of prey, as the food of this animal is vegetable, but to clasp the female in the act of copulation. The *Branchipus* or *Cheirocephalus* is certainly the most beautiful and elegant of all the Entomostraca, being rendered extremely attractive to the view by 'the uninterrupted undulatory wavy motion of its graceful branchial feet, slightly tinged as they are with a light reddish hue, the brilliant mixture of transparent bluish-green and bright red of its prehensile antennæ, and its bright red tail with the beautiful plumose setæ springing from it.' Unfortunately, however, it is a comparatively rare animal in this country. The *Artemia salina*, or 'brine-shrimp,' is an animal of very similar organisation, and almost equally beautiful in its appearance and movements, but of smaller size, its body being about half an inch in length. Its 'habitat' is very peculiar, for it is only found in the salt-pans or brine-pits in which sea-water is undergoing concentration (as at Lymington); and in these situations it is sometimes so abundant as to communicate a red tinge to the liquid.

Some of the most interesting points in the history of the Entomostraca lie in the peculiar mode in which their generative function is performed, and in their tenacity of life when desiccated, in which last respect they correspond with many Rotifers. By this provision they escape being completely exterminated, as they might otherwise soon be, by the drying up of the pools, ditches, and other small collections of water which constitute their usual habitats. We do not, of course, imply that the adult animals can bear a *complete* desiccation, although they will preserve their vitality in mud that holds the smallest quantity of moisture; but their eggs are more tenacious of life, and there is ample evidence that these will become fertile on being moistened, after having remained for a long time in the condition of fine dust. Most Entomostraca, too, are killed by severe cold, and thus the whole race of adults perishes every winter; but their eggs seem unaffected by the lowest temperature, and thus continue the species, which would be otherwise exterminated. Again, we frequently meet in this group with that *agamic* reproduction, which we have seen to prevail so extensively among the lower forms. In many species there is a double mode of multiplication, the sexual and the non-sexual. The former takes place at certain seasons only, the males (which are often so different in conformation from the females that they would not be supposed to belong to the same species if they were not seen in actual congress) disappearing entirely at other times. The latter, on the other hand, continues at all periods of the year, so long as warmth and food are supplied, and is repeated many times so as to give origin to as many successive 'broods.' Further, a single act of impregnation may serve to fertilise, not merely the ova which are then mature or nearly so, but all those subsequently produced by the same female, which are deposited at considerable intervals. In these two modes the multiplication of these little creatures is carried on with great rapidity, the young animal speedily coming to maturity and beginning to propagate, so that, according to the computation of Jurine, founded upon data ascertained by actual observation, a

single fertilised female of the common *Cyclops quadricornis* may be the progenitor in one year of 4,442,189,120 young.[1]

The eggs of some Entomostraca are deposited freely in the water, or are carefully attached in clusters to aquatic plants; but they are more frequently carried for some time by the parent in special receptacles developed from the posterior part of the body; and in many cases they are retained there until the young are ready to come forth, so that these animals may be said to be ovo-viviparous. In *Daphnia* the eggs are received into a large cavity between the back of the animal and its shell, and there the young undergo almost their whole development, so as to come forth in a form nearly resembling that of their parent. Soon after their birth a moult or exuviation of the shell takes place, and the egg-coverings are cast off with it. In a very short time afterwards another brood of eggs is seen in the cavity, and the same process is repeated, the shell being again exuviated after the young have been brought to maturity. At certain times, however, the *Daphnia* may be seen with a dark opaque substance within the back of the shell, which has been called the *ephippium*, from its resemblance to a saddle. This, when carefully examined, is found to be of dense texture, and to be composed of a mass of hexagonal cells; and it contains two oval bodies, each consisting of an ovum covered with a horny casing, enveloped in a capsule which opens like a bivalve shell. From the observations of Sir J. Lubbock,[2] it appears that the ephippium is really only an altered portion of the carapace, its outer valve being a part of the outer layer of the epidermis, and its inner valve the corresponding part of the inner layer. The development of the ephippial eggs takes place at the posterior part of the ovaries, and is accompanied by the formation of a greenish-brown mass of granules; and from this situation the eggs pass into the receptacle formed by the new carapace, where they become included between the two layers of the ephippium. This is cast off, in process of time, with the rest of the skin, from which, however, it soon becomes detached; and it continues to envelope the eggs, generally floating on the surface of the water until they are hatched with the returning warmth of spring. This curious provision obviously affords protection to the eggs which are to endure the severity of winter cold: and an approach to it may be seen in the remarkable firmness of the envelopes of the 'winter eggs' of some Rotifera. There seems a strong probability, from the observations of Sir J. Lubbock, that the 'ephippial' eggs are true sexual products, since males are to be found at the time when the ephippia are developed; whilst it is certain that the ordinary eggs can be produced non-sexually, and that the young which spring from them can multiply the race in like manner. The young which are produced from the ephippial

[1] For an interesting account of the parthenogenetic development of *Apus* and its allies see the sixth of Von Siebold's *Beiträge zur Parthenogenesis der Arthropoden* (Leipzig, 1871). A new explanation of the facts has recently been made by Mr. H. Bernard, who finds that many of the *Apodidæ* are hermaphrodite (*Jenaische Zeitschr.* xxv. p. 337).

[2] 'An Account of the two Methods of Reproduction in *Daphnia*, and of the Structure of the Ephippium,' in *Phil. Trans.* 1857, p. 79.

eggs seem to have the same power of continuing the race by non-sexual reproduction as the young developed under ordinary circumstances.

In most Entomostraca the young at the time of their emersion from the egg differ considerably from the parent, especially in having only the thoracic portion of the body as yet developed, and in possessing but a small number of locomotor appendages (see fig. 662, C–G); the visual organs, too, are frequently wanting at first. The process of development, however, takes place with great rapidity, the animal at each successive moult (which process is very commonly repeated at intervals of a day or two) presenting some new parts, and becoming more and more like its parent, which it very early resembles in its power of multiplication, the female laying eggs before she has attained her own full size. Even when the Entomostraca have attained their full growth, they continue to exuviate their shell at short intervals during the whole of life; and this repeated moulting seems to prevent the animal from being injured, or its movements obstructed, by the overgrowth of parasitic animalcules and confervæ, weak and sickly individuals being frequently seen to be so covered with such parasites that their motion and life are soon arrested, apparently because they have not strength to cast off and renew their envelopes. The process of development appears to depend in some degree upon the influence of light, being retarded when the animals are secluded from it; but its rate is still more influenced by heat; and this appears also to be the chief agent that regulates the time which elapses between the moultings of the adult, these, in *Daphnia*, taking place at intervals of two days in warm summer weather, whilst several days intervene between them when the weather is colder. The cast shell carries with it the sheaths not only of the limbs and plumes, but of the most delicate hairs and setæ which are attached to them. If the animal have previously sustained the loss of a limb, it is generally renewed at the next moult, as in higher Crustacea.[1]

Closely connected with the entomostracous group is the tribe of *suctorial* Crustacea,[2] which for the most part live as parasites upon the exterior of other animals (especially fish), whose juices they imbibe by means of the peculiar proboscis-like organ which takes in them the place of the jaws of other crustaceans; whilst other appendages, representing the foot-jaws, are furnished with hooks, by which these parasites attach themselves to the animals from whose juices they derive their nutriment. Many of the suctorial Crustacea bear a strong resemblance, even in their adult condition, to certain Entomostraca; but more commonly it is between the earlier forms of the two groups that the resemblance is the closest,

[1] For a systematic and detailed account of this group see Dr. Baird's *Natural History of the British Entomostraca*, published by the Ray Society. The numerous essays by Professor Claus should also be consulted.

[2] It is now generally recognised that these should be placed with the *Copepoda*, which may be divided into the *Eucopepoda* and the *Branchiura*; the former are divisible into the *Gnathostomata*, most of which are non-parasitic, and have been already described under *Copepoda*, and the *Siphonostomata*, of which *Lernæa* is an example.

most of the *Suctoria* undergoing such extraordinary changes in their progress towards the adult condition that, if their complete forms were alone attended to, they might be excluded from the class altogether, as has (in fact) been done by many zoölogists. Of the suctorial Crustacea which form the group *Branchiura* may be specially mentioned the *Argulus foliaceus* which attaches itself to the surface of the bodies of fresh-water fish, such as the stickleback, and is commonly known under the name of the 'fish-louse.' This animal has its body covered with a large firm oval shield, which does not extend, however, over the posterior part of the abdomen. The mouth is armed with a pair of styliform mandibles; and on each side of the proboscis there is a large, short, cylindrical appendage, terminated by a curious sort of sucking-disc, with another pair of longer jointed members, terminated by prehensile hooks. These two pairs of appendages, which are probably to be considered as representing the foot-jaws, are followed by four pairs of legs, which, like those of the branchiopods, are chiefly adapted for swimming; and the tail, also, is a kind of swimmeret. This little animal can leave the fish upon which it feeds, and then swims freely in the water, usually in a straight line, but frequently and suddenly changing its direction, and sometimes turning over and over several times in succession. The stomach is remarkable for the large cæcal prolongations which it sends out on either side, immediately beneath the shell; for these subdivide and ramify in such a manner that they are distributed almost as minutely as the cæcal prolongations of the stomach of the *Planaria* (fig. 656). The proper alimentary canal, however, is continued backwards from the central cavity of the stomach, as an intestinal tube, which terminates in an anal orifice at the extremity of the abdomen. A far more remarkable departure from the typical form of the class is shown in the *Lernæa*, which is found attached to the gills of fishes. This creature has a long suctorial proboscis; a short thorax, to which is attached a single pair of legs, which meet at their extremities, where they bear a sucker which helps to give attachment to the parasite; a large abdomen; and a pair of pendent egg-sacs. In its adult condition it buries its anterior portion in the soft tissue of the animal it infests, and appears to have little or no power of changing its place. But the young, when they come forth from the egg, are as active as the young of *Cyclops* (fig. 662, C, D), which they much resemble; and only attain the adult form after a series of metamorphoses, in which they cast off their locomotive members and eyes. It is curious that the original form is retained with comparatively slight change by the males, which increase but little in size, and are so unlike the females that no one would suppose the two to belong to the same family, much less to the same species, but for the study of their development.[1]

From the parasitic suctorial Crustacea the transition is not

[1] As the group of suctorial Crustacea is rather interesting to the professed naturalist than to the amateur microscopist, even an outline view of it would be unsuitable to the present work; and the Author would refer such of his readers as may desire to study it to the excellent treatise by Dr. Baird already referred to. Of the numerous recent essays and memoirs those of Professor Claus should by all means be consulted.

really so abrupt as it might at first sight appear to the group of *Cirripedia*, consisting of the *barnacles* and their allies; for these, like many of the *Suctoria*, are fixed to one spot during the adult portion of their lives, but come into the world in a condition that bears a strong resemblance to the early state of many other Crustacea. The departure from the ordinary crustacean type in the adults is, in fact, so great that it is not surprising that zoölogists in general should have ranked them in a distinct class, their superficial resemblance to the Mollusca, indeed, having caused most systematists to place them in that series, until due weight was given to those structural features which mark their 'articulated' character. We must limit ourselves, in our notice of this group, to that very remarkable part of their history, the microscopic



FIG. 663.—Development of *Balanus balanoides*: A, earliest form; B, larva after second moult; C, side view of the same; D, stage immediately preceding the loss of activity; *a*, stomach (?); *b*, nucleus of future attachment (?).

study of which has contributed most essentially to the elucidation of their real nature. The observations of Mr. J. V. Thompson [1] with the extensions and rectifications which they have subsequently received from others (especially Mr. Spence Bate [2] and Mr. Darwin [3]) show that there is no essential difference between the early forms of the *sessile* Cirripeds (*Balanidæ* or 'acorn-shells') and of the *pedunculated* (*Lepadidæ* or 'barnacles'); for both are active little animals (fig. 663, A), possessing three pairs of legs and a pair of compound eyes, and having the body covered with an expanded

[1] *Zoölogical Researches*, No. IV. 1830, and *Phil. Trans.* 1835, p. 355.
[2] 'On the Development of the Cirripedia' in *Ann. Nat. Hist.* ser. ii. vol. viii. 1851, p. 324.
[3] *Monograph of the Sub-Class Cirripedia*, published by the Ray Society.

carapace, like that of many entomostracous crustaceans, so as in no essential particular to differ from the larva of *Cyclops* (fig. 662, C). After going through a series of metamorphoses, one stage of which is represented in fig. 663, B, C, these larvæ come to present a form, D, which reminds us strongly of that of *Daphnia*, the body being inclosed in a shell composed of two valves, which are united along the back, whilst they are free along their lower margin, where they separate for the protrusion of a large and strong anterior pair of prehensile limbs, provided with an adhesive sucker and hooks, and of six pairs of posterior legs adapted for swimming. This bivalve shell, with the members of both kinds, is subsequently thrown off; the animal then attaches itself by its *head*, a portion of which, in the barnacle, becomes excessively elongated into the 'peduncle' of attachment, whilst in *Balanus* it expands into a broad disc of adhesion; the first thoracic segment sends backwards a prolongation which arches over the rest of the body, so as completely to inclose it, and of which the exterior layer is consolidated into the 'multivalve' shell; whilst from the other thoracic segments are evolved the six pairs of *cirrhi*, from whose peculiar character the name of the group is derived. These are long, slender, many-jointed, tendril-like appendages, fringed with delicate filaments covered with cilia, whose action serves both to bring food to the mouth and to maintain aërating currents in the water. The balani are peculiarly interesting objects in the aquarium on account of the pumping action of their beautiful feathery appendages, which may be watched through a tank microscope; and their cast skins, often collected by the tow-net, are well worth mounting.[1]

Malacostraca.—The chief points of interest to the microscopist in the more highly organised forms of Crustacea are furnished by the structure of the exoskeleton, and by the phenomena of *metamorphosis*, both which may be best studied in the commonest kinds. The exoskeleton of the *Decapods* in its most complete form consists of three strata, viz. 1, a horny structureless layer covering the exterior; 2, an areolated stratum; and 3, a laminated tubular substance. The innermost and even the middle layers, however, may be altogether wanting; thus, in the *Phyllosomata* or 'glass-crabs,' the envelope is formed by the transparent horny layer alone; and in many of the small crabs belonging to the genus *Portuna* the whole substance of the carapace beneath the horny investment presents the areolated structure. It is in the large thick-shelled crabs that we find the three layers most differentiated. Thus in the common *Cancer pagurus* we may easily separate the structureless horny covering after a short maceration in dilute acid; the areolated layer, in which the pigmentary matter of the coloured parts of the shell is chiefly contained, may be easily brought into view by grinding away from the *inner* side as flat a piece as can be selected, having first cemented the outer surface to the glass slide, and by examining this with a magnifying power of 250 diameters, driving a strong light through it with the achromatic condenser;

[1] Valuable details as to the structure of this group will be found in Dr. P. P. C. Hoek's report on the Cirripeds collected by H.M.S. *Challenger*.

whilst the tubular structure of the thick inner layer may be readily demonstrated by means of sections parallel and perpendicular to its surface. This structure, which resembles that of *dentine*, save that the tubuli do not branch, but remain of the same size through their whole course, may be particularly well seen in the black extremity of the claw, which (apparently from some peculiarity in the molecular arrangement of its mineral particles) is much denser than the rest of the shell, the former having almost the semitransparence of ivory, whilst the latter has a chalky opacity. In a transverse section of the claw the tubuli may be seen to radiate from the central cavity towards the surface, so as very strongly to resemble their arrangement in a tooth ; and the resemblance is still further increased by the presence, at tolerably regular intervals, of minute sinuosities corresponding with the laminations of the shell, which seem, like the 'secondary curvatures' of the dentinal tubuli, to indicate successive stages in the calcification of the animal basis. In thin sections of the areolated layer it may be seen that the apparent walls of the areolæ are merely translucent spaces from which the tubuli are absent, their orifices being abundant in the intervening spaces.[1] The tubular layer rises up through the pigmentary layer of the crab's shell in little papillary elevations, which seem to be concretionary nodules ; and it is from the deficiency of the pigmentary layer at these parts that the coloured portion of the shell derives its minutely speckled appearance. Many departures from this type are presented by the different species of decapods ; thus in the prawns there are large stellate pigment-spots resembling those of frogs, the colours of which are often in remarkable conformity with those of the bottom of the rock-pools frequented by these creatures ; whilst in the shrimps there is seldom any distinct trace of the areolated layer, and the calcareous portion of the skeleton is disposed in the form of concentric rings, which seem to be the result of the concretionary aggregation of the calcifying deposit.[2]

It is a very curious circumstance that a strongly marked difference exists between crustaceans that are otherwise very closely allied in regard to the degree of change to which their young are subject in their progress towards the adult condition. For, whilst the common crab, lobster, spiny lobster, prawn, and shrimp undergo a regular metamorphosis, the young of the crayfish and some land-crabs come forth from the egg in a form which corresponds in all essential particulars with that of their parents. Generally speaking, a strong resemblance exists among the young of all the species of decapods which undergo a metamorphosis, whether they are afterwards to belong to the *macrourous* (long-tailed) or to

[1] The Author is now quite satisfied of the correctness of the interpretation put by Professor Huxley (see his article, 'Tegumentary Organs,' in the *Cyclop. Anat. and Phys.* vol. v. p. 487), and by Professor W. C. Williamson ('On some Histological Features in the Shells of Crustacea' in *Quart. Journ. Micros. Sci.* vol. viii. 1860, p. 38) upon the appearances which he formerly described (*Report of British Association* for 1847, p. 128) as indicating a cellular structure in this layer.

[2] Consult Braun, 'Ueber die histologischen Vorgänge bei der Häutung von *Astacus fluviatilis*,' *Arbeit. Zool. Inst. Würzburg*, ii. p. 121.

the *brachyourous* (short-tailed) division of the group; and the forms of these larvæ are so peculiar, and so entirely different from any of those into which they are ultimately to be developed, that they were considered as belonging to a distinct genus, *Zoëa*, until their real nature was first ascertained by Mr. J. V. Thompson. Thus, in the earliest state of *Carcinus mænas* (small edible crab), we see the head and thorax, which form the principal bulk of the body, included within a large carapace or shield (fig. 664, A) furnished with a long projecting spine, beneath which the fin-feet are put forth; whilst the abdominal segments, narrowed and prolonged, carry at the end a flattened tail-fin, by the strokes of which upon the water the propulsion of the animal is chiefly effected. Its condition is hence comparable, in almost all essential particulars, to that of *Cyclops*. In the case of the lobster, prawn, and other 'macrourous' species the metamorphosis chiefly consists in the separation of the locomotor and respiratory organs, true legs being developed from the thoracic segments for the former, and true gills (concealed within a



Fig. 664.—Metamorphosis of *Carcinus mænas*: A, first or *Zoëa* stage; B, second or *Megalopa* stage; C, third stage, in which it begins to assume the adult form; D, perfect form.

special chamber formed by an extension of the carapace beneath the body) for the latter; while the abdominal segments increase in size and become furnished with appendages (false feet) of their own. In the crabs, or 'brachyourous' species, on the other hand, the alteration is much greater; for, besides the change first noticed in the thoracic members and respiratory organs, the thoracic region becomes much more developed at the expense of the abdominal, as seen at B, in which stage the larva is remarkable for the large size of its eyes, and hence received the name of *Megalopa*, when it was supposed to be a distinct type. In the next stage, C, we find the abdominal portion reduced to an almost rudimentary condition, and bent under the body; the thoracic limbs are more completely adapted for walking, save the first pair, which are developed into *chelæ* or pincers; and the little creature entirely loses the active swimming habits which it originally possessed, and takes on the mode of life peculiar to the adult.[1]

[1] On the metamorphoses of Crustacea and Cirripedia, see especially the *Untersuchungen über Crustaceen* of Professor Claus, Vienna, 1876. A number of

In collecting minute Crustacea the ring-net should be used for the fresh-water species, and the tow-net for the marine. In localities favourable for the latter the same 'gathering' will often contain multitudes of various species of Entomostraca, accompanied perhaps by the larvæ of higher Crustacea, echinoderm larvæ, annelid larvæ, and the smaller *Medusæ*. The water containing these should be put into a large glass jar, freely exposed to the light; and, after a little practice, the eye will become so far habituated to the general appearance and modes of movement of these different forms of animal life as to be able to distinguish them one from the other. In selecting any specimen for microscopic examination the dipping-tube will be found invaluable. The collector will frequently find *Megalopa* larvæ, recognisable by the brightness of their two black eye-spots, on the surface of floating leaves of *Zostera*. The study of the metamorphosis will be best prosecuted, however, by obtaining the fertilised eggs, which are carried about by the females, and watching the history of their products. For preserving specimens, whether of Entomostraca or of larvæ of the higher Crustacea, the Author would recommend glycerin-jelly as the best medium.

interesting facts and speculations on the Crustacea will be found in F. Müller's *Facts and Arguments for Darwin* (London 1869). The recent work of Reichenbach on the Development of the Crayfish is contained in vol. xxix. of the *Zeitschr. f. Wiss. Zool.* p. 123, 1877, and vol. xiv. of the *Abhandl. Senckenberg. Naturf. Gesells.* 1886. See also the essay, by W. K. Brooks, On the Development of *Lucifer*, in *Phil. Trans.* 1882, p. 57.

CHAPTER XXI

INSECTS AND ARACHNIDA

THERE is no class in the whole animal kingdom which affords t microscopist such a wonderful variety of interesting objects such facilities for obtaining an almost endless succession of nove as that of insects. For, in the first place, the number of diff kinds that may be brought together (at the proper time) wit tremely little trouble far surpasses that which any other gro animals can supply to the most painstaking collector; then, a each specimen will afford to him who knows how to emplo materials a considerable number of microscopic objects of different kinds; and thirdly, although some of these objects re much care and dexterity in their preparation, a large propo may be got out, examined, and mounted with very little sk trouble. Take, for example, the common house-fly: its *eyes* be easily mounted, one as a transparent, the other as an op object; its *antennæ*, although not such beautiful objects as tho many other Diptera, are still well worth examination; its *tongu* 'proboscis' is a peculiarly interesting object, though requiring s care in its preparation; its *spiracles*, which may be easily cut from the sides of its body, have a very curious structure alimentary canal affords a very good example of the minute di bution of the *trachea*; its *wing*, examined in a living speci newly come forth from the pupa state, exhibits the circulatio the blood in the 'nervures,' and when dead shows a most beau play of iridescent colours, and a remarkable areolation of surf when examined by light reflected from its surface at a partic angle; its *foot* has a very peculiar conformation, which is doubt connected with its singular power of walking over smooth surfa in direct opposition to the force of gravity, and on the actio which additional light has lately been thrown; while the struct and physiology of its *sexual* apparatus, with the history of its devel ment and metamorphoses, would of itself suffice to occupy the wh time of an observer who should desire thoroughly to work it out, only for months, but for years.[1] Hence, in treating of this departm in such a work as the present, the Author labours under the *embar*

[1] See Mr. Lowne's valuable treatise on *The Anatomy and Physiology of Blow-fly*, 1870, of which a new edition is now (1891) being published.

des richesses ; for, to enter into such a description of the parts of the structure of insects most interesting to the microscopist as should be at all comparable in fulness with the accounts which it has been thought desirable to give of other classes would swell out the volume to an inconvenient bulk ; and no course seems open but to limit the treatment of the subject to a notice of the *kinds* of objects which are likely to prove most generally interesting, with a few illustrations that may serve to make the descriptions more clear, and with an enumeration of some of the sources whence a variety of specimens of each class may be most readily obtained. And this limitation is the less to be regretted, since there already exists in our language numerous elementary treatises on entomology, wherein the general structure of insects is fully explained, and the conformation of their minute parts as seen with the microscope is adequately illustrated.[1]

A considerable number of the smaller insects—especially those belonging to the orders *Coleoptera* (beetles), *Neuroptera* (dragon-fly, May-fly, &c.), *Hymenoptera* (bee, wasp, &c.), and *Diptera* (two-winged flies)—may be mounted entire as opaque objects for low magnifying powers, care being taken to spread out their legs, wings, &c. so as adequately to display them, which may be accomplished, even after they have dried in other positions, by softening them by steeping them in hot water, or, where this is objectionable, by exposing them to steam. Full directions on this point, applicable to small and large insects alike, will be found in the various text-books of entomology. There are some, however, whose translucence allows them to be viewed as transparent objects, and these are either to be mounted in Canada balsam or in Deane's medium, glycerin jelly, or Farrant's gum, according to the degree in which the horny opacity of their integument requires the assistance of the balsam to facilitate the transmission of light through it, or the softness and delicacy of their textures render an aqueous medium more desirable. Thus, an ordinary *flea* or *bug* will best be mounted in balsam ; but the various parasites of the *louse* kind, with some or other of which almost every kind of animal is affected, should be set up in some of the 'media.' Some of the aquatic larvæ of the Diptera and Neuroptera, which are so transparent that their whole internal organisation can be made out without dissection, are very beautiful and interesting objects when examined in the living state, especially because they allow the circulation of the blood and the action of the dorsal vessel to be discerned. Among these there is none preferable to the larva of the *Ephemera marginata* (day-fly), which is distinguished by the possession of a number of beautiful appendages on its body and tail, and is, moreover, an extremely common inhabitant of our ponds and streams. This insect passes two or even three years in its larval state, and during this time it repeatedly throws off its skin ; the cast skin, when perfect, is an object of extreme beauty, since, as it formed a complete sheath to the various appendages of the body and tail, it continues to exhibit

[1] An excellent introduction to the study of insects will be found in *The Structure and Life-history of the Cockroach*, by L. C. Miall and A. Denny (London, 1886).

their outlines with the utmost delicacy ; and by keeping these larvæ in an aquarium, and by mounting the entire series of their cast skins, a record is preserved of the successive changes they undergo. Much care is necessary, however, to extend them upon slides in consequence of their extreme fragility ; and the best plan is to place the slip of glass under the skin whilst it is floating on water, and to lift the object out upon the slide. Thin *sections* of insects, caterpillars, &c. which bring the internal parts into view in their normal relations, may be cut with the microtome by first soaking the body (as suggested by Dr. Halifax) in thick gum-mucilage, which passes into its substance, and gives support to its tissues, and then inclosing it in a casing of melted paraffin made to fit the cavity of the section-instrument.

Structure of the Integument.—In treating of those separate parts of the organisation of insects which furnish the most interesting objects of microscopic study we may most appropriately commence with their integument and its appendages (scales, hairs, &c.). The body and members are closely invested by a hardened skin, which acts as their skeleton, and affords points of attachment to the muscles by which their several parts are moved, being soft and flexible, however, at the joints. This skin is usually more or less horny in its texture, and is consolidated by the animal substance termed *chitine*, as well as in some cases by a small quantity of mineral matter. It is in the Coleoptera that it attains its greatest development, the 'dermo-skeleton' of many beetles being so firm as not only to confer upon them an extraordinary power of passive resistance, but also to enable them to put forth enormous force by the action of the powerful muscles which are attached to it. The outer layer of this dermo-skeleton is continuous, the cells which secrete it lying beneath the parallel laminæ of which it is made up ; on the surface the chitinous cuticle may be seen to be marked out into a number of polygonal (usually hexagonal) areas which correspond to the subjacent secreting cells. Of this we have a very good example in the *superficial* layers (fig. 677, B) of the thin horny lamellæ or blades which constitute the terminal portion of the antenna of the cockchafer (fig. 676) this layer being easily distinguished from the intermediate portion (A) of the lamina by careful focussing. In many beetles the hexagonal areolation of the surface is distinguishable when the light is reflected from it at a particular angle, even when not discernible in transparent sections. The integument of the common *red ant* exhibits the hexagonal cellular arrangement very distinctly throughout ; and the broad flat expansion of the leg of the *Crabro* ('sand-wasp') affords another beautiful example of a distinctly cellular arrangement of the outer layer of the integument. The inner layer, however, which constitutes the principal part of the thickness of the horny casing of the beetle tribe, seldom exhibits any distinct organisation, though it may be usually separated into several lamellæ, which are sometimes traversed by tubes that pass into them from the inner surface, and extend towards the outer without reaching it.

Tegumentary Appendages.—The surface of the insects is often beset, and is sometimes completely covered, with *appendages* having

either the form of broad flat scales or that of hairs more or less approaching the cylindrical shape, or some form intermediate between the two. The *scaly* investment is most complete among the *Lepidoptera* (butterfly and moth tribe), the distinguishing character of the insects of this order being derived from the presence of a regular layer of scales upon each side of their large membranous wings. It is to the peculiar coloration of the scales that the various hues and figures are due, by which these wings are so commonly distinguished, all the scales on one patch (for example) being green, those of another red, and so on; for the subjacent membrane remains perfectly transparent and colourless when the scales have been brushed off from its surface. Each scale seems to be composed of two or more membranous lamellæ, often with an intervening deposit of pigment, on which, especially in Lepidoptera, their colour depends. Certain scales, however, especially in the beetle tribe, have a metallic lustre, and exhibit brilliant colours that vary with the mode in which the light glances from them; and this 'iridescence,' which is specially noteworthy in the scales of the *Curculio imperialis* ('diamond beetle'), seems to be a purely optical effect, depending either (like the prismatic hues of a soap-bubble) on the extreme thinness of the membranous lamellæ, or (like those of 'mother-of-pearl') on a lineation of surface produced by their corrugation. Each scale is furnished at one end with a sort of handle or 'pedicle' (figs. 665, 666), by which it is fitted into a minute socket attached to the surface of the insect; and on the wings of Lepidoptera these sockets are so arranged that the scales lie in very regular rows, each row overlapping a portion of the next, so as to give to their surface, when sufficiently magnified, very much the appearance of being *tiled* like the roof of a house. Such an arrangement is said to be 'imbricated.' The forms of these scales are often very curious, and frequently differ a good deal on the several parts of the wings and of the body of the same individual, being usually more expanded on the former and narrower and more hair-like on the latter. A peculiar type of scale, which has been distinguished by the designation *plumule*, is met with among the *Pieridæ*, one of the principal families of the diurnal Lepidoptera. The 'plumules' are not flat, but cylindrical or bellows-shaped, and are hollow; they are attached to the wing by a bulb at the end of a thin elastic peduncle that differs in length in different species, and proceeds from the broader, not from the narrower end of the scale; whilst the free extremity usually tapers off and ends in a kind of brush, though sometimes it is broad and has its edge fringed with minute filaments. These 'plumules'), which are peculiar to the males, are found on the upper surface of the wings, partly between and partly under the ordinary scales. They seem to be represented among the *Lycænidæ* by the 'battledore' scales to be presently described.[1]

The peculiar markings exhibited by many of the scales very early attracted the attention of opticians engaged in the application of

[1] See Mr. Watson's memoirs 'On the Scales of Battledore Butterflies,' in *Monthly Microscopical Journal*, ii. pp. 73, 314.

achromatism to the microscope; for, as th
with which they could be shown were f
degree to which the angular aperture of an o
without sacrifice of perfect correction for
aberration, such scales proved very serv
Author can well remember the time when th
laus (fig. 665), the ordinary and 'battledor
matus Argus (figs. 666, 667), and the scales o
(fig. 668), which are now only used for te
medium power, were the recognised tests fo
while the exhibition of alternating light
Podura scale was regarded as a first-rate p
for anyone possessed of a good apochrom
(½ inch) to obtain all the characteristic fe

Fig. 665.—Scale of *Morpho Menelaus*.

the determinat
construction of
interpretation
matter that th
prefer to relega
apertures of ou
be looked upon
look upon the
jectives. No
comprehensive
tion of the tru
scale, and yet
microscopy lavi
so many years.

The easier t
by the *Lepid*
moths), and an
of these, both f
larity of mark
Morpho Menela
of a rich blue
longitudinal st
ribbed elevations of one of the superficial l
appearance of transverse striation, which ca
an inferior objective, but becomes very decid
of medium focus; and this is found, when s
high power and good illumination, to depen
transverse thickenings or corrugations (fig. 6
ternal surface of one of the membranes. The
ommatus Argus ('azure blue' butterfly) resem
in form and structure, but are more delic
Their ribs are more nearly parallel than thos
and do not show the same transverse striati
scales lies partly over another, the effect of
of the two sets of ribs at an oblique angl
interrupted striations (*b*), very much resembl
scale. The same butterfly furnishes smaller

'battledore' scales, from their resemblance in
(fig. 666, *a*). These scales, which occur in the
genera of the family *Lycænidæ*, and present a
y of shape,[1] are marked by narrow longitudinal
intervals seem to expand into rounded or oval
e to the scales a dotted appearance (fig. 667); at
of the scale, however, these dots are wanting.
cribes and figures them as elevated bodies, some-
dumb-bells or shirt-studs, ranged along the ribs,
from the general surface.[2] Other good observers,
recognising the stud-like bodies described by Dr.
them as not projecting from the external surface
as interposed between its two lamellæ;[3] and this
e Author to be more conformable than Dr. Anthony's
bility.
ifficult 'test scales' are furnished by little wingless
together by Latreille in the order *Thysanura*, but



ales of *Polyommatus Argus*
): *a*, battledore scale; *b*,
striæ.

FIG. 667.—Battledore scale of *Polyommatus Argus* (azure blue).

ed by Sir John Lubbock,[4] on account of important
internal structure, into the two groups *Collembola* and
ura. Of the former of these the *Lepismidæ* constitute
family; and the scale of the common *Lepisma saccha-*
ugar-louse,'[5] very early attracted the attention of

n, *loc. cit.*
ings on the Battledore Scales of some of the *Lepidoptera*' in *Monthly Journal*, vol. vii. 1872, pp. 1, 250.
edings of the Microscopical Society,' *op. cit.* p. 278.
lonograph of the Collembola and Thysanura, published by the Ray

t may be found in most old houses, frequenting damp, warm cupboards, such as contain sweets; it may be readily caught in a small pill-box, have a few pin-holes in the lid; and if a drop of chloroform be put the inmate will soon become insensible, and may be then turned out clean paper, and some of its scales transferred to a slip of glass by this gently on its body.

microscopists on account of its beautiful shell-like sculpture. When viewed under a low magnifying power it presents a beautiful 'watered silk' appearance, which, with higher amplification, is found to depend (as Mr. R. Beck first pointed out) [1] upon the intersection of two sets of striæ, representing the different structural arrangements of its two superficial membranes. One of its surfaces (since ascertained by Mr. Joseph Beck [2] to be the *under* or attached surface of the scale) is raised, either by corrugation or thickening, into a series of strongly marked longitudinal ribs, which run nearly *parallel* from one end of the scale to the other, and are particularly distinct at its margins and at its free extremity; whilst the other surface (the free or *outer*, according to Mr. J. Beck) presents a set of less definite corrugations, *radiating* from the pedicle where they are strongest, towards the sides and free extremity of the scale, and therefore crossing the parallel ribs at angles more or less acute (fig. 668). It was further pointed out by Mr. R. Beck that the intersection of these two sets of corrugations at different angles produces most curious effects upon the appearances which optically represent them. For where the diverging ribs cross the longitudinal ribs very obliquely, as they do near the free extremity of the scale, the longitudinal ribs seem broken up into a series of 'exclamation markings,' like those of the *Podura*; but where the crossing is transverse or nearly so, as at the sides of the scale, an appearance is presented as of successions of large bright beads. The conclusion drawn by the Messrs. Beck, that these interrupted appearances are 'produced by two sets of uninterrupted lines on different surfaces,' has been confirmed by the careful investigations of Mr. Morehouse.[3] The minute beaded structure observed by Dr. Royston-Pigott [4] alike in the ribs and in the intervening spaces may now be certainly regarded as an optical effect of diffraction. In the scale of a type nearly allied to *Lepisma*, the *Machilis polypoda*, the very distinct ribbing (fig. 669) is produced by the corrugation of the under membranous lamina alone, the upper or exposed lamina being smooth, with the exception of slight undulations near the pedicle, and the cross-markings being due to structure between the superposed



FIG. 668.—Scale of *Lepisma saccharina*.

[1] *The Achromatic Microscope*, p. 50.
[2] See his appendix to Sir John Lubbock's *Monograph*.
[3] *Monthly Microscopal Journal*, vol. xi. 1874, p. 18, and vol. xviii. 1877, p. 31.
[4] *Ibid.* vol. ix. 1873, p. 63.

membranes, probably a deposit on the interior surface of one or both of them.[1]

Although the *Poduridæ* and *Lepismidæ* now rank as distinct families, yet they approximate sufficiently in general organisation, as well as in habits, to justify the expectation that their scales would be framed upon the same plan. The *Poduridæ* are found amidst the sawdust of wine-cellars, in garden tool-houses, or near decaying wood, and derive their popular name of 'spring-tails' from the possession by many of them of a curious caudal appendage by which they can leap like fleas. This is particularly well developed in the species now designated *Lepidocyrtus curvicollis*, which furnishes what are ordinarily known as 'Podura' scales. 'When full grown and unrubbed,' says Sir John Lubbock, 'this species is very beautiful, and reflects the most gorgeous metallic tints.' Its scales are of different sizes and of different degrees of strength of marking (fig. 670, A, B), and are therefore by no means of uniform value as tests. The general appearance of their surface, under a power not sufficient to resolve their markings, is that of watered silk, light and dark bands passing across it with wavy irregularity; but a well-corrected objective of very moderate aperture now suffices to resolve every dark band into a row of distinct 'exclamation marks.' A certain longitudinal continuity may be traced between the 'exclamation marks' in the ordinary test scale; but this is much more apparent in other scales from the same species (fig. 671), as well as in the scales of various allied types, which were carefully studied by the late Mr. R. Beck.[2] In certain other types, indeed, the scales have very distinct longitudinal parallel ribs, sometimes with regularly disposed cross-bars; these ribs, being confined to one surface only (that which is in contact with the body), are not subject to any such interference with their optical continuity as has been shown to occur in *Lepisma*; but more or less distinct indications of radiating corrugations often present themselves. The appearance of the interrupted 'exclamation marks' Mr. J. Beck considers to be due 'to irregular corrugations of the outer surface of the under membrane, to slight undulations on the outer surface of the upper membrane, and to structure between the superposed membranes.' It has been recently stated by Mr. Joseph



FIG. 669.—Scale of *Machilis polypoda*.

[1] See Mr. Joseph Beck in Sir J. Lubbock's *Monograph*, p. 255.

[2] *Trans. Micros. Soc.* n.s. vol. x. 1862, p. 83. See also Mr. Joseph Beck, in the appendix to Sir John Lubbock's *Monograph*, and in *Monthly Microscopical Journal*, iv. p. 253.

Beck that the scales of a lepidopterous insect belonging to the ge
Mormo, which under a low power present the watered-silk app
ance seen in the *Podura* scale, under a $\frac{1}{5}$ in. obj. show the 'excla
tion markings,' whilst under a $\frac{1}{10}$ in. obj. they exhibit distinct
from pedicle to apex, thus showing in one scale how the appearai
run from one into the other.[1]

The *hairs* of many insects, and still more of their larvæ,
very interesting objects for the microscope on account of t
branched or tufted conformation, this being particularly remark
in those with which the common hairy caterpillars are so abunda
beset. Some of these afford very good tests for the perfect correc
of objectives. Thus the hair of the *bee* is pretty sure to exh



FIG. 670.—Test scales of *Lepidocyrtus curvicollis*: A, large strongly marked scale; B, small scale, more faintly marked.



FIG. 671.—Ordinary scale of *Lepidocyrtus curvicollis*.

strong prismatic colours if the chromatic aberration should not h
been exactly neutralised; and that of the larva of a *Derme*
(commonly, but erroneously, termed the 'bacon-beetle') was o
thought a very good test of defining power, and is still useful
this purpose. It has a cylindrical shaft (fig. 672, B) with closely
whorls of spiny protuberances, four or five in each whorl; t
highest of these whorls is composed of mere knobby spines; and t
hair is surmounted by a curious circle of six or seven large filamen
attached by their pointed ends to its shaft, whilst at their free e
tremities they dilate into knobs. An approach to this structure
seen in the hairs of certain *Myriopods* (centipedes, galley-worms, &c
of which an example is shown in fig. 672, A; but a beautiful phot

[1] *Journ. Roy. Micros. Soc.* vol. ii. 1879, p. 810.

micrograph of the hair of *Polyxenus lagurus*, of the family *Polydesmidæ* (order *Chilognatha*) is given in fig. 6 of the frontispiece. This is one of the finest test objects for medium powers. Other minute forms of this class are most beautiful objects under the binocular microscope on account of the remarkable structure and regular arrangement of their hairs.

In examining the integument of insects and its appendages parts of the surface may be viewed either by reflected or transmitted light, according to their degree of transparence and the nature of their covering. The beetle and butterfly tribes furnish the greater number of the specimens suitable to be viewed as *opaque* objects; and nothing is easier than to mount portions of the *elytra* of the former (usually the most showy parts of their bodies), or of the wings of the latter, in the manner described in Chapter VII. pp. 388–390. The tribe of *Curculionidæ*, in which the surface is beset with scales having the most varied and lustrous hues, is distinguished among Coleoptera for the brilliancy of the objects it affords, the most remarkable in this respect being the well-known *Curculio imperialis*, or 'diamond beetle' of South America, parts of whose elytra, when properly illuminated and looked at with a low power, show like clusters of jewels flashing against a dark velvet ground. In many of the British *Curculionidæ*, which are smaller and far less brilliant, the scales lie at the bottom of little depressions of the surface; and if the elytra of the diamond beetle be carefully examined, it will be found that each of the clusters of scales which are arranged upon it in rows seems to rise out of a deep pit which sinks in by its side. The transition from scales to hairs is extremely well seen by comparing the different parts of the surface of the diamond beetle with each other. The beauty and brilliancy of many objects of this kind are increased by mounting them in cells in Canada balsam, even though they are to be viewed with reflected light; other objects, however, are rendered less attractive by this treatment; and in order to ascertain whether it is likely to improve or to deteriorate the specimen, it is a good plan first to test some other portion of the body having scales of the same kind by touching it with turpentine, and then to mount the part selected as an object, either in balsam or dry, according as the turpentine increases or diminishes the brilliancy of the scales on the spot to which it was applied. Portions of the wings of Lepidoptera are best mounted as opaque objects without any other preparation than gumming them flat down to the disc of the wooden slide, care being taken to avoid disturbing the arrangement of the scales and to keep the objects, when mounted, as secluded as possible from dust. In selecting such

FIG. 672.—A, hair of *Myriopod*; B, hair of *Dermestes*.

portions it is well to choose those which have the brightest and the most contrasted colours, exotic butterflies being in this respect usually preferable to British; and before attaching them to their slides care should be taken to ascertain in what position, with the arrangement of light ordinarily used, they are seen to the best advantage, and to fix them there accordingly. Whenever portions of the integument of insects are to be viewed as *transparent* objects, for the display of their intimate structure, they should be mounted in Canada balsam, after soaking for some time in turpentine, since this substance has a peculiar effect in increasing their translucence. Not only the horny cases of perfect insects of various orders, but also of those of their pupæ, are worthy of this kind of study; and objects of great beauty (such as the chrysalis case of the emperor moth), as well as of scientific interest, are sure to reward such as may prosecute it with any assiduity. Further information may often be gained by softening such parts in potash and viewing them in fluid. The *scales* of the wings of Lepidoptera &c. are best transferred to the slide by simply pressing a portion of the wing either upon the slip of glass or upon the cover; if none should adhere the glass may first be gently breathed on. Some of them are best seen when examined 'dry,' whilst others are more clear when mounted in fluid; and for the determination of their exact structure it is well to have recourse to both these methods. Hairs, on the other hand, are best mounted in balsam.



FIG. 673.—Head and compound eyes of the bee, showing the ocellites *in situ* on one side, A, and displaced on the other, B; *a*, *a*, *a*, stemmata; *b*, *b*, antennæ.

Parts of the Head.—The *eyes* of insects, situated upon the upper and outer part of the head, are usually very conspicuous organs, and are frequently so large as to touch each other in front (fig. 673). We find in their structure a remarkable example of that multiplication of similar parts which seems to be the predominating 'idea' in the conformation of articulated animals; for each of the large protuberant bodies which we designate as *an eye* is really a 'compound' eye, made up of many hundred or even many thousand minute conical *ocelli* (B). Approaches to this structure are seen in Entomostraca; but the number of 'ocellites' thus grouped together is usually small. In the higher Crustacea, however, the 'ocelli' are very numerous: and their compound eyes are constructed upon the same general plan as those of insects, though their shape and position are often very peculiar. The individual ocelli are at once recognised when the 'compound eyes' are examined under even a low magnifying power by the 'faceted' appearance of the surface (fig. 673, A), which is marked out by very regular divisions either into hexagons

or squares; each facet is the 'corneule' of a separate ocellite, and has a convexity of its own; hence, by counting the facets, we can ascertain the number of ocelli in each 'compound eye.' In the two eyes of the common fly there are as many as 4,000; in those of the cabbage-butterfly there are about 17,000; in the dragon-fly, 24,000; and in the Mordella bettle 25,000. The structure of the arthropod eye is best explained by a comparative account of the various stages of complication which it presents. In various larvæ the cuticular layer is modified to form a single lens, behind which are simple, separate, elongated hypodermic cells, some of which are continuous with fine branches of the optic nerve; these may be called retinal cells. The next stage in complication is seen when these last combine to form groups, 'retinulæ'; the sensitive cells may become divided into two regions, an outer one, which is 'vitreous' and refractive in function, while the inner part remains sensitive; the corneal surface may become broken up into a number of facets, each of which corresponds to one of the 'pyramids' so formed, and within the retinula there may be differentiated a rhabdom (see fig. 675) formed by the nerve-rod.



FIG. 674.—Diagram of a section of the composite eye of *Melolontha vulgaris* (cockchafer): *a*, facets of the cornea; *b*, transparent pyramids surrounded with pigment; *c*, fibres of the optic nerve; *d*, trunk of the optic nerve.



FIG. 675.—Part of the compound eye of *Phryganea*; the retinal cells are seen to be united into a retinula (*r*) which is differentiated into a rhabdom (*m*) posteriorly; *cc*, crystalline cone; *f*, facet of compound eye; *pg*, pigment. (After Grenacher.)

After traversing the pyramids the rays reach the extremities of the fibres of the optic nerve, which are surrounded, like the pyramid, by pigmentary substance. Thus the rays which have passed through the several 'corneules' are prevented from mixing with each other; and no rays, save those which pass in the axes of the pyramids, can reach the fibres of the optic nerve. Hence, it is evident that, as no two ocelli on the same side (fig. 673) have exactly the same axis, no two can receive their rays from the same point of an object; and thus, as each compound eye is immovably fixed upon the head, the combined action of the entire aggregate will probably only afford but

a single image, resembling that which *we* obtain by means of our single eyes. This judgment has received a confirmation as unexpected as it is complete and beautiful. The subject of the real nature of compound vision can be considered no longer a matter of doubt. We have as complete evidence of its character as we have of that of vision by vertebrate eyes. It is to Professor S. Exner, of Vienna, that we are indebted for the striking though simple results. He has been engaged for years on cognate researches, and has at length succeeded in taking a photo-micrograph of the image presented at the back of a compound insect eye in precisely the same manner as a similar photograph might be taken with the retina removed at the back of the eye of one of the higher vertebrates.

The demonstration has just reached us as these sheets are passing through the press, and the present Editor is indebted for a knowledge of the following details to the courtesy of a private communication from Professor Exner.

The general result of the researches on the subject is presented in fig. 675A, which is the image at the back of the compound eye of *Lampyris splendidula* (fire-fly) in the position in which it would be portrayed upon the retina, but magnified 120 diameters. On to the window pane a letter R cut out in black was fixed; the distance of the window from the eye was 225 cm. while the distance of the church from the window through which it is seen in the magnified image was 135 paces.

FIG. 675 A.—Image of a window with the letter R on one of its panes, and a church beyond, taken through the compound eye of *Lampyris splendidula*, and magnified 120 diams.

The result is unmistakable; there may appear to be some matters of interest still needing interpretation, but these are explained in the monograph by Exner, giving the complete details of the method he adopted and the mathematical explanation of the results he obtained. The rectitude of the image and the reversion of the R are certainly noteworthy; and as a contribution to our knowledge of the physiology of sight in insects and other animals with compound eyes, the importance of the result obtained by the ingenuity and skill of Professor Exner is great, giving us a new start on solid ground. The mathe-

matics of the question are fully discussed by Exner [1] in a memoir, to which the student must be referred for complete information. The kind of image formed by the compound eye has long been a matter of discussion amongst physiologists.[2]

The process of taking the photo-micrograph copied in fig. 675A was this: The eye of the *Lampyris* was carefully dissected out from the head, the retina and pigment removed with a fine camel-hair pencil, and the back of the eye immersed in a mixture of glycerin and water, possessing a refractive index of 1·346; this was already known to be the refractive index of the blood of the *Lampyris*. The whole was placed upon an ordinary cover-glass, and this being fixed by its edges to a slide or object-carrier with a circular aperture cut in it, as in fig. 675B, C; *a* is the slide with an aperture less in diameter than the cover-glass *b* cut through it; *c* is the fluid-medium of



FIG. 675B.—Diagrammatic illustration of the method by which the image in fig. 675A was photo-micrographed.

$n=1·346$ in which the back parts of the eye are immersed, thus fulfilling the conditions of living sight, while the cornea with its lenses is shown at *d*, being, as in the normal state, in air. If the eye be now examined with a microscope (the C of Zeiss was employed) the 'lenses' will be distinctly seen, but if the focus be readjusted

[1] *Sitzungsber. Akad. Wissench. Wien*, Bd. xcviii. (1889), pp. 13, 143; also *Die Physiologie der Facettirten Augen von Krebsen und Insecten* (Leipzig und Wien, 1891).

[2] A critical history of the discussion will be found in Chapter VII. of Sir J. Lubbock's *Senses of Animals* (London, 1888). The question of the physiology of the compound eye of Arthropods has given rise to much discussion. For further details as to its structure consult Grenacher's great work, *Untersuchungen über das Sehorgan der Arthropoden* &c. (Göttingen, 1879); Carrière, *Die Sehorgane der Thiere* &c. (Munich and Leipzig, 1885); Hickson, 'The Eye and Optic Tract of Insects,' *Quart. Journ. Micros. Sci.* xxv. p. 215; Lankester and Bourne, 'The Minute Structure of the Lateral and Central Eyes of Scorpio and Limulus,' *Quart. Journ. Micros. Sci.* xxiii. p. 177; Lowne 'On the Compound Vision and the Morphology of the Eye in Insects,' *Trans. Linn. Soc.* (2), ii. p. 389; Patten, 'Eyes of Molluscs and Arthropods,' *Mitth. Zool. Stat. Neapel*, vi.

to the focal plane of the image in the eye this image will be seen and magnified. This will be understood from D (fig. 675B), where *e*, *f* represent the image, *h* the cornea with its 'lenses' *g*, *e'–f'* being the image of the object thrown upon the position from which the retina has been removed, and which is now made the focal plane of the objective employed.

It was this image (*e'–f'*) which was photographed in the ordinary manner with a Zeiss photo-micrographic apparatus and the C object-glass. The manner in which this was done is seen diagrammatically at E (fig. 675B), where *i* indicates the cornea of the eye exposed to air, *k* the image thrown through the 'lenses' as a unified picture at the focal point of the microscope, and *l* is the sensitised plate on which the image was photographed.

This is doubtless but the beginning of much similar work to be done by others in Germany and elsewhere; but this piece of admirable research and its clear results have a value not only physiological but philosophical.

Although the structure already described may be considered as typical of the eyes of insects, yet there are various departures from it (most of them slight) in the different members of the class. Thus in some cases the posterior surface of each 'corneule' is concave; and a space is left between it and the iris-like diaphragm, which seems to be occupied by a watery fluid or 'aqueous humour.' In other instances, again, this space is occupied by a double-convex body, which seems to represent the 'crystalline lens,' and this body is sometimes found behind the iris, the number of ocelli being reduced, and each one being larger, so that the cluster presents more resemblance to that of spiders &c. Besides their 'compound' eyes, insects usually possess a small number of 'simple' eyes (termed *ocelli* or *stemmata*) seated upon the top of the head (fig. 673, *a*, *a*, *a*). Each of these consists of a single very convex corneule, to the back of which proceeds a bundle of rods that are in connection with fibrils of the optic nerve. Such ocelli are the only visual organs of the larvæ of insects that undergo complete metamorphosis, the 'compound' eyes being only developed towards the end of the pupa stage.

Various modes of preparing and mounting the eyes of insects may be adopted, according to the manner wherein they are to be viewed. For the observation of their external faceted surface by reflected light it is better to lay down the entire head, so as to present a front face or a side face, according to the position of the eyes, the former giving a view of *both* eyes when they approach each other so as nearly or quite to meet (as in fig. 673), whilst the latter will best display *one* when the eyes are situated more at the sides of the head. For the minuter examination of the 'corneules,' however, these must be separated from the hemispheroidal mass whose exterior they form by prolonged maceration, and the pigment must be carefully washed away by means of a fine camel-hair brush from the inner or posterior surface. In flattening them out upon the glass slide one of two things must necessarily happen, either the margin must tear when the central portion is pressed down to a level, or, the margin remaining entire, the central por-

tion must be thrown into plaits, so that its corneules overlap one another. As the latter condition interferes with the examination of the structure much more than the former does, it should be avoided by making a number of slits in the margin of the convex membrane before it is flattened out. Vertical sections, adapted to demonstrate the structure of the ocelli and their relations to the optic nerve, can be only made when the insect is fresh or has been preserved in strong spirit. Mr. Lowne recommends that the head should be hardened in a 2 per cent. solution of chromic acid, and then imbedded in cacao butter ; the sections must be cut *very* thin, and should be mounted in Canada balsam. The following are some of the insects whose eyes are best adapted for microscopic preparations : *Coleoptera*, Cicindela, Dytiscus, Melolontha (cockchafer), Lucanus (stag-beetle) ; *Orthoptera*, Acheta (house and field crickets), Locusta ; *Hemiptera*, Notonecta (boat-fly) ; *Neuroptera*, Libellula (dragon-fly), Agrion ; *Hymenoptera*, Vespidæ (wasps) and Apidæ (bees) of all kinds ; *Lepidoptera*, Vanessa (various species of), Sphinx ligustri (privet hawk-moth), Bombyx (silkworm moth and its allies); *Diptera*, Tabanus (gad-fly), Asilus, Eristalis (drone-fly), Tipula (crane-fly), Musca (house-fly), and many others.

The *antennæ*, which are the two jointed appendages arising from the upper part of the head of insects (fig. 673, *b b*), present a most wonderful variety of conformation in the several tribes of insects, often differing considerably in the several species of one genus, and even in the two sexes of the same species. Hence the characters which they afford are extremely useful in classification, especially since their structure must almost necessarily be in some way related to the habits and general economy of the creatures to which they belong, although our imperfect acquaintance with their function may prevent us from clearly discerning this relation. Thus among the Coleoptera we find one large family, including the glow-worm, fire-fly, skip-jack, &c. distinguished by the toothed or serrated form of the antennæ, and hence called *Serricornes* ; in another, of which the burying-beetle is the type, the antennæ are terminated by a club-shaped enlargement, so that these beetles are termed *Clavicornes* ; in another, again, of which the *Hydrophilus*, or large water-beetle, is an example, the antennæ are never longer, and are commonly shorter, than one of the pairs of palpi, whence the name of *Palpi-*

FIG. 676.—Antenna of *Melolontha* (cockchafer).

cornes is given to this group; in the very large family that includes the *Lucani*, or stag-beetles, with the *Scarabæi*, of which the cockchafer is the commonest example, the antennæ terminate in a set of leaf-like appendages, which are sometimes arranged like a fan or the leaves of an open book (fig. 676), are sometimes parallel to each other like the teeth of a comb, and sometimes fold one over the other, thence giving the name *Lamellicornes*; whilst another large family is distinguished by the appellation *Longicornes*, from the great length of the antennæ, which are at least as long as the body, and often longer. Among the Lepidoptera, again, the conformation of the antennæ frequently enables us at once to distinguish the group to which any specimen belongs. As every treatise on entomology contains figures and descriptions of the principal types of conformation of these organs, there is no occasion here to dwell upon them longer than to specify such as are most interesting to the microscopist: *Coleoptera*, Brachinus, Calathus, Harpalus, Dytiscus, Staphylinus, Philonthus, Elater, Lampyris, Silpha, Hydrophilus, Aphodius, Melolontha, Cetonia, Curculio; *Orthoptera*, Forficula (earwig), Blatta (cockroach); *Lepidoptera*, Sphingidæ (hawk-moths), and Noctuina (moths) of various kinds, the large 'plumed' antennæ of the latter being peculiarly beautiful objects under a low magnifying power; *Diptera*, Culicidæ (gnats of various kinds), Tipulidæ (crane-flies and midges), Tabanus, Eristalis, and Muscidæ (flies of various kinds). All the larger antennæ, when not mounted 'dry' as opaque objects, should be put up in balsam, after being soaked for some time in turpentine; but the small feathery antennæ of gnats and midges are so liable to distortion when thus mounted that it is better to set them up in fluid, the head with its pair of antennæ being thus preserved together when not too large. A curious set of organs has been recently discovered in the antennæ of many insects, which have been supposed to constitute collectively an apparatus for hearing. Each consists of a cavity hollowed out in the horny integument, sometimes nearly spherical, sometimes flask-shaped, and sometimes prolonged into numerous extensions formed by the folding of its lining membrane; the mouth of the cavity seems to be normally closed in by a continuation of this membrane, though its presence cannot always be satisfactorily determined; whilst to its deepest part a nerve-fibre may be traced. The expanded lamellæ of the antennæ of *Melolontha* present a great display of these cavities, which are indicated in fig. 677, A, by the small circles that beset almost their entire area; their form, which is very peculiar can here be only made out by vertical sections; but in many of the smaller antennæ, such as those of the bee, the



FIG. 677.—Minute structure of leaf-like expansions of antenna of *Melolontha*: A, their internal layer; B, their superficial layer.

vities can be seen sidewise without any other trouble than that bleaching the specimen to render it more transparent.[1]

The next point in the organisation of insects to which the attention of the microscopist may be directed is the structure of the *outh*. Here, again, we find almost infinite varieties in the details conformation; but these may be for the most part reduced to a nall number of types or plans, which are characteristic of the different orders of insects. It is among the *Coleoptera*, or beetles, that e find the several parts of which the mouth is composed in their ost distinct form; for, although some of these parts are much more ghly developed in other insects, other parts may be so much altered so little developed as to be scarcely recognisable. The Coleoptera esent the typical conformation of the *mandibulate* mouth, which is lapted for the prehension and division of solid substances; and this nsists of the following parts: 1, a pair of jaws, termed *mandibles*, equently furnished with powerful teeth, opening *laterally* on either de of the mouth, and serving as the chief instruments of manduca-on; 2, a second pair of jaws, termed *maxillæ*, smaller and weaker ian the preceding, beneath which they are placed, and serving to old the food, and to convey it to the back of the mouth; 3, an pper lip, or *labrum*; 4, a lower lip or *labium*; 5, one or two pairs small jointed appendages, termed *palpi*, attached to the maxillæ, nd hence called *maxillary palpi*; 6, a pair of *labial palpi*. The bium [2] is often composed of several distinct parts, its basal portion eing distinguished as the *mentum* or chin, and its anterior portion eing sometimes considerably prolonged forwards, so as to form an rgan which is properly designated the *ligula*, but which is more mmonly known as the 'tongue,' though not really entitled to that esignation, the real *tongue* being a soft and projecting organ which rms the floor of the mouth, and which is only found as a distinct art in a comparatively small number of insects, as the cricket. This *gula* is extremely developed in the *fly* kind, in which it forms the hief part of what is commonly called the 'proboscis' (fig. 678);[3] nd it also forms the 'tongue' of the *bee* and its allies (fig. 679).

[1] See the memoir of Dr. Hicks, 'On a new Structure in the Antennæ of Insects,' *Trans. Linn. Soc.* xxii. p. 147; and his 'Further Remarks' at p. 388 of the me volume. See also the memoir of M. Lespès, 'Sur l'Appareil auditif des Insectes,' *Ann. des Sci. Nat.* sér. iv. zool. tom. ix. p. 258; and that of M. Claparède, 'Sur les étendus Organes auditifs des Coléoptères lamellicornes et autres Insectes,' in *Ann. es Sci. Nat.* sér. iv. zool. tom. x. p. 236. Dr. Hicks lays great stress on the 'bleach-g process' as essential to success in this investigation, and he gives the following irections for performing it: Take of chlorate of potass a drachm, and of water a rachm and a half; mix these in a small wide bottle containing about an ounce; wait ve minutes and then add about a drachm and a half of strong hydrochloric acid. hlorine is thus slowly developed, and the mixture will retain its bleaching power r some time.

[2] The labium and the labial palps are, morphologically, a second pair of maxillæ hich have undergone more or less fusion of the basal parts along the median line.

[3] The representation given in the figure is taken from one of the ordinary pre-arations of the fly's proboscis, which is made by slitting it open, flattening it out. nd mounting it in balsam. For representations of the true relative positions of ne different parts of this wonderful organ, and for minute descriptions of them, the eader is referred to Mr. Suffolk's memoir, 'On the Proboscis of the Blow-fly,' in *Monthly Microsc. Journ.* i. p. 331, and to Mr. Lowne's treatise on *The Anatomy nd Physiology of the Blow-fly*, p. 41 (a new and elaborate edition of this work is n process of publication).



A



B

FIG. 678.—A, tongue of common fly: *a*, lobes of ligula; *b*, portion inclosing the lancets, formed by the metamorphosis of the maxillæ; *c*, maxillary palpi. B, a portion of some of the pseudo-tracheæ more highly magnified.

'he ligula of the common fly presents a curious modification of the rdinary tracheal structure, the purpose of which is not apparent; or instead of its tracheæ being kept pervious, after the usual ashion, by the winding of a continuous spiral fibre through their nterior, the fibre is broken into rings, and these rings do not surround the whole tube, but are terminated by a set of arches that pass rom one to another (fig. 678, B).[1] In the *Diptera*, or two-winged lies generally, the labrum, maxillæ, mandibles, and the internal ongue (where it exists) are converted into delicate lancet-shaped rgans termed *setæ*, which, when closed together, are received into hollow on the upper side of the labium (fig. 678), but which are apable of being used to make punctures in the skin of animals or he epidermis of plants, whence the juices may be drawn forth by the roboscis. Frequently, however, two or more of these organs may e wanting, so that their number is reduced from six to four, three, r two. In the *Hymenoptera* (bee and wasp tribe) the labrum and he mandibles (fig. 679, *b*) much esemble those of mandibulate nsects, and are used for correponding purposes; the maxillæ c) are greatly elongated, and orm, when closed, a tubular heath for the *ligula*, or 'tongue,' hrough which the honey is drawn p; the labial palpi (*d*) also are reatly developed, and fold toether, like the maxillæ, so as to orm an inner sheath for the tongue'; while the 'ligula' itself e) is a long tapering muscular rgan, marked by an immense umber of short annular divions, and densely covered over s own length with long hairs. t is not tubular, as some have ated, but is solid; when actively mployed in taking food it is exended to a great distance beyond he other parts of the mouth; ut when at rest it is closely acked up and concealed between he maxillæ. 'The manner,' says Ir. Newport, 'in which the honey is obtained when the organ is lunged into it at the bottom of a flower is by "lapping," or a



FIG. 679.—Parts of the mouth of *Apis mellifica* (honey-bee): *a*, mentum; *b*, mandibles; *c*, maxillæ; *d*, labial palpi; *e*, ligula, or prolonged labium, commonly termed the 'tongue.'

[1] According to Dr. Anthony (*Monthly Microscopical Journ.* vol. xi. p. 242), these 'pseudo-tracheæ' are suctorial organs, which can take in liquid alike at their extremities and through the whole length of the fissure caused by the interruption of he rings, the edges of this fissure being formed by the alternating series of 'ear-like ppendages' connected with the terminal 'arches,' the closing together of which onverts the pseudo-tracheæ into a complete tube. Dr. Anthony considers each of hese ear-like appendages to be a minute sucker, 'either for the adhesion of the fleshy ongue, or for the imbibition of fluids, or perhaps for both purposes.' The point is ell worthy of further investigation.

constant succession of short and quick extensions and contractions of the organ, which occasion the fluid to accumulate upon it and to ascend along its upper surface, until it reaches the orifice of the tube formed by the approximation of the maxillæ above, and of the labial palpi and this part of the ligula below.'

By the plan of conformation just described we are led to that which prevails among the *Lepidoptera*, or butterfly tribe, which, being pre-eminently adapted for suction, is termed the *haustellate* mouth. In these insects the labium and mandibles are reduced to three minute triangular plates; whilst the maxillæ are immensely elongated, and are united together along the median line to form the *haustellium*, or true 'proboscis,' which contains a tube formed by the junction of the two grooves that are channelled out along their mutually applied surfaces, and which serves to pump up the juices of deep cup-shaped flowers, into which the size of their wings prevents these insects from entering. The length of this haustellium varies greatly: thus in such Lepidoptera as take no food in their perfect state it is a very insignificant organ; in some of the white hawk-moths, which hover over blossoms without alighting, it is nearly two



FIG. 680.—Haustellium (proboscis) of *Vanessa*.

inches in length, and in most butterflies and moths it is about as long as the body itself; in *Amphonyx*, one of the *Sphingidæ*, it is more than nine inches long, or about three times the length of the body. This haustellium, which, when not in use, is coiled up in a spiral beneath the mouth, is an extremely beautiful microscopic object, owing to the peculiar banded arrangement it exhibits (fig. 680), which is probably due to the disposition of its muscles. In many instances the two halves may be seen to be locked together by a set of hooked teeth, which are inserted into little depressions between the teeth of the opposite side. Each half, moreover, may be ascertained to contain a trachea or air-tube, and it is probable, from the observations of Mr. Newport, that the sucking up of the juices of a flower through the proboscis (which is accomplished with great rapidity) is effected by the agency of the respiratory apparatus. The proboscis of many butterflies is furnished, for some distance from

its extremity, with a double row of small projecting barrel-shaped bodies (shown in fig. 680), which are surmised by Mr. Newport (whose opinion is confirmed by the kindred inquiries of Dr. Hicks) to be organs of taste. Numerous other modifications of the structure of the mouth, existing in the different tribes of insects, are well worthy of the careful study of the microscopist; but as detailed descriptions of most of these will be found in every systematic treatise on entomology, the foregoing general account of the principal types must suffice.

Parts of the Body.—The conformation of the several divisions of the *alimentary canal* presents such a multitude of diversities, not only in different tribes of insects, but in different states of the same individual, that it would be utterly vain to attempt here to give even a general idea of it, more especially as it is a subject of far less interest to the ordinary microscopist than to the professed anatomist. Hence we shall only stop to mention that the 'muscular gizzard,' in which the œsophagus very commonly terminates, is often lined by several rows of strong horny teeth for the reduction of the food, which furnish very beautiful objects, especially for the binocular. These are particularly developed among the grasshoppers, crickets, and locusts, the nature of whose food causes them to require powerful instruments for its reduction.[1]

The *circulation of blood* may be distinctly watched in many of the more transparent larvæ, and may sometimes be observed in the perfect insect. It is kept up by a 'dorsal vessel' (so named from the position it always occupies along the middle of the back in the thoracic and abdominal regions), which really consists of a succession of muscular contractile cavities, one for each segment, opening one into another from behind forwards, so as to form a continuous trunk divided by valvular partitions. In many larvæ, however, these partitions are very indistinct; and the walls of the 'dorsal vessel' are so thin and transparent that it can with difficulty be made out, a limitation of the light by the diaphragm being often necessary. The blood which moves through this trunk, and which is distributed by it to the body, is a transparent and nearly colourless fluid, carrying with it a number of 'oat-shaped' corpuscles, by the motion of which its flow can be followed. The current enters the 'dorsal vessel' at its posterior extremity, and is propelled forwards by the contractions of the successive chambers, being prevented from moving in the opposite direction by the valves between the chambers, which only open forwards. Arrived at the anterior extremity of the 'dorsal vessel,' the blood is distributed in three principal channels: a central one, namely, passing to the head, and a lateral one to either side, descending so as to approach the lower surface of the body. It is from the two lateral currents that the secondary streams diverge, which pass into the legs and wings, and then return back to the main stream; and it is from these also that in the larva of the *Ephemera marginata* (day-fly), the extreme transparence of

[1] The student who desires to carry further the study of the digestive apparatus should consult Professor Plateau's memoir, 'Recherches sur les Phénomènes de la Digestion chez les Insectes,' *Mém. Acad. Roy. de Belgique*, xli.

which renders it one of the best of all subjects for the observation of insect circulation, the smaller currents diverge into the gill-like appendages with which the body is furnished. The blood-currents seem rather to pass through channels excavated among the tissues than through vessels with distinct walls; but it is not improbable that in the perfect insect the case may be different. In many aquatic larvæ, especially those of the *Culicidæ* (gnat tribe), the body is almost entirely occupied by the visceral cavity; and the blood may be seen to move backwards in the space that surrounds the alimentary canal, which here serves the purpose of the channels usually excavated through the solid tissues, and which freely communicates at each end with the 'dorsal vessel.' This condition strongly resembles that found in many Annelida.[1]

The circulation may be easily seen in the wings of many insects in their *pupa* state, especially in those of the Neuroptera (such as dragon-flies and day-flies) which pass this part of their lives under water in a condition of activity, the pupa of *Agrion puella*, one of the smaller dragon-flies, being a particularly favourable subject for such observations. Each of the 'nervures' of the wings contains a 'trachea' or air-tube, which branches off from the tracheal system of the body; and it is in a space around the trachea that the blood may be seen to move when the hard framework of the nervure itself is not too opaque. The same may be seen, however, in the wings of pupæ of bees, butterflies, &c. which remain shut up motionless in their cases; for this condition of apparent torpor is one of great activity of their nutritive system, those organs, especially, which are peculiar to the perfect insect being then in a state of rapid growth, and having a vigorous circulation of blood through them. In certain insects of nearly every order a movement of fluid may be seen in the wings for some little time after their last metamorphosis; but this movement soon ceases and the wings dry up. The common fly is as good a subject for this observation as can be easily found; it must be caught within a few hours or days of its first appearance; and the circulation may be most conveniently brought into view by inclosing it (without water) in the aquatic box, and pressing down the cover sufficient to keep the body at rest without doing it any injury.

The *respiratory apparatus* of insects affords a very interesting series of microscopic objects; for, with great uniformity in its general plan, there is almost infinite variety in its details. The aëration of the blood in this class is provided for, not by the transmission of the fluid to any special organ representing the *lung* of a vertebrated animal or the *gill* of a mollusc, but by the introduction of air into every part of the body, through a system of minutely distributed *trachea*, or air-tubes, which penetrate even the smallest and most delicate organs. Thus, as we have seen, they pass into the *haustellium*, or 'proboscis,' of the butterfly, and they are minutely

[1] See the memoirs on *Corethra plumicornis*, by Professor Rymer Jones, in *Trans. Micros. Soc.* n.s. vol. xv. 1867, p. 99; by Professor E. Ray Lankester, in the *Popular Science Review* for October 1865; and by Dr. A. Weismann, in *Zeitschr. f. Wiss. Zool.* Bd. xvi. p. 45. On the circulatory system of insects consult Graber, 'Ueber den pulsatorischen Apparat der Insecten,' *Arch. für Mikr. Anat.* ix. p. 129.

distributed in the elongated *labium* or 'tongue,' of the fly (fig. 678). Their general distribution is shown in fig. 681, where we see two long trunks (*f*) passing from one end of the body to the other, and connected with each other by a transverse canal in every segment; these trunks communicate, on the one hand, by short wide passages with the 'stigmata,' 'spiracles,' or 'breathing pores' (*g*), through which the air enters and is discharged; whilst they give off branches to the different segments, which divide again and again into ramifications of extreme minuteness. They usually communicate also with a pair of air-sacs (*h*) which is situated in the thorax; but the size of these (which are only found in the perfect insect, no trace of them existing in the larvæ) varies greatly in different tribes, being usually greatest in those insects which (like the bee) can sustain the longest and most powerful flight, and least in such as habitually live upon the ground or upon the surface of the water. The structure of the air-tubes reminds us of that of the 'spiral vessels' of plants, which seemed destined (in part at least) to perform a similar office; for within the membrane that forms their outer wall an elastic fibre winds round and round, so as to form a spiral closely resembling in its position and functions the spiral wire spring of flexible gas pipes; within this, again, however, there is another membranous wall to the air-tubes, so that the spire winds between their inner and outer coats. When a portion of one of the great trunks with some of the principal branches of the tracheal system has been dissected out, and so pressed in mounting that the sides of the tubes are flattened against each other (as has happened in the specimen represented in fig. 682), the spire forms two layers which are brought into close apposition, and a very beautiful appearance, resembling that of watered silk, is produced



FIG. 681.—Tracheal system of *Nepa* (water-scorpion): *a*, head; *b*, first pair of legs; *c*, first segment of thorax; *d*, second pair of wings; *e*, second pair of legs; *f*, tracheal trunk; *g*, one of the stigmata; *h*, air-sac.

by the crossing of the two sets of fibres, of which one overlies the other. That this appearance, however, is altogether an optical illusion may be easily demonstrated by carefully following the course of any one of the fibres, which will be found to be perfectly regular.

The 'stigmata' or 'spiracles' through which the air enters the tracheal system are generally visible on the exterior of the body of the insect (especially on the abdominal segments) as a series of pores along each margin of the under surface. In most larvæ nearly every segment is provided with a pair, but in the perfect insect several of them remain closed, especially in the thoracic region, so that their number is often considerably reduced. The structure of the spiracles varies greatly in regard to complexity in different insects; and even where the general plan is the same the details of conformation are peculiar, so that perhaps in scarcely any two species are they alike. Generally speaking, they are furnished with some kind of sieve at their entrance by which particles of dust, soot, &c. which would otherwise enter the air-passages are filtered out; and this sieve may be formed by the interlacement of the branches of minute arborescent growths from the border of the spiracle, as in the common fly (fig. 683), or in the *Dytiscus*; or it may be a membrane perforated with minute holes, and supported upon a framework of bars that is prolonged in like manner from the thickened margin of the aperture (fig. 684), as in the larva of the *Melolontha* (cockchafer). Not unfrequently the centre of the aperture is occupied by an impervious disc, from which radii proceed to its margin, as is well seen in the spiracle of *Tipula* (crane-fly).[1] In those aquatic larvæ which breathe air we often find one

FIG. 682.—Portion of a large trachea of *Dytiscus*, with some of its principal branches.



FIG. 683.—Spiracle of common fly.

[1] Consult Landois and Thiele, 'Der Tracheenverschluss bei den Insecten,' *Zeitschrift f. Wiss. Zool.* xvii. p. 187.

f the spiracles of the last segment of the abdomen prolonged into a ube, the mouth of which remains at the surface while the body is mmersed ; the larvæ of the *gnat* tribe may frequently be observed n this position.

There are many aquatic larvæ, however, which have an entirely lifferent provision for respiration, being furnished with external leaf-ike or brush-like appendages into which the tracheæ are prolonged, so hat by absorbing air from the water that bathes them they may con-ey this into the interior of the body. We cannot have a better example f this than is afforded by the larva of the common *Ephemera* (day-y), the body of which is furnished with a set of branchial appendages esembling the 'fin-feet' of branchiopods, whilst the three-pronged ail also is fringed with clusters of delicate hairs which appear to ninister to the same function. In the larva of the *Libellula* dragon-fly) the extension of the surface for aquatic respiration akes place within the termination of the intestine, the lining iembrane of which is folded into an immense number of plaits, ach containing a minutely ramified system of tracheæ ; the water lowly drawn in through the anus or bathing this surface is ejected ith such violence that the body s impelled in the opposite direc-ion ; and the air taken up by its racheæ is carried through the ystem of air-tubes of which they orm part into the remotest organs. his apparatus is a peculiarly in-eresting object for the microscope n account of the extraordinary opiousness of the distribution of ie tracheæ in the intestinal folds.

FIG. 681.—Spiracle of larva of *cockchafer*.

The main trunks of the tracheal ystem, with their principal ramifi-ations, may generally be got out with little difficulty by laying pen the body of an insect or larva under water in a dissecting rough, and removing the whole visceral mass, taking care to leave s many as possible of the branches, which will be seen pro-eeding to this from the two great longitudinal tracheæ, to whose osition these branches will serve as a guide. Mr. Quekett recom-iends the following as the most simple method of obtaining a erfect system of tracheal tubes from a larva. A small opening aving been made in its body, this is to be placed in strong acetic cid, which will soften or decompose all the viscera ; and the tracheæ ay then be well washed with the syringe, and removed from the ody with the greatest facility, by cutting away the connections of ie main tubes with the spiracles by means of fine-pointed scissors. n order to mount them they should be floated upon the slide, on hich they should then be laid out in the position best adapted for isplaying them. If they are to be mounted in Canada balsam they ould be allowed to dry upon the slide, and should then be treated n the usual way ; but their natural appearance is best preserved

by mounting them in fluid (weak spirit or Goadby's solution), using a shallow cell to prevent pressure. The finer ramifications of the tracheal system may generally be seen particularly well in the membranous wall of the stomach or intestine; and this, having been laid out and dried upon the glass, may be mounted in balsam so as to keep the tracheæ full of air (whereby they are much better displayed), if care be taken to use balsam that has been previously thickened, to drop this on the object without liquefying it more than is absolutely necessary, and to heat the slide and the cover (the heat may be advantageously applied directly to the cover after it has been put on by turning over the slide so that its upper face shall look downward) only to such a degree as to allow the balsam to spread and the cover to be pressed down. The spiracles are easily dissected out by means of a pointed knife or a pair of fine scissors; they should be mounted in glycerin jelly when their texture is soft, and in balsam when the integument is hard and horny.

Wings.—These organs are essentially composed of an extension of the external membranous layer of the integument over a framework formed by prolongations of the inner horny layer, within which prolongations tracheæ are nearly always to be found, whilst they also include channels through which blood circulates during the growth of the wing and for a short time after its completion. This is the simple structure presented to us in the wings of *Neuroptera* (dragon-flies &c.), *Hymenoptera* (bees and wasps), *Diptera* (two-winged flies), and also of many *Homoptera* (*Cicadæ* and *Aphides*): and the principal interest of these wings as microscopic objects lies in the distribution of their 'veins' or 'nervures' (for by both names are the ramifications of their skeleton known) and in certain points of accessory structure. The venation of the wings is most beautiful in the smaller Neuroptera, since it is the distinguishing feature of this order that the veins, after subdividing, reunite again, so as to form a close network; whilst in the Hymenoptera and Diptera such reunions are rare, especially towards the margins of the wings, and the areolæ are much larger. Although the membrane of which these wings are composed appears perfectly homogeneous when viewed by transmitted light, even with a high magnifying power, yet when viewed by light reflected obliquely from their surfaces an appearance of cellular areolation is often discernible; this is well seen in the common fly, in which each of these areolæ has a hair in its centre. In order to make this observation, as well as to bring out the very beautiful iridescent hues which the wings of many minute insects (as the *Aphides*) exhibit when thus viewed, it is convenient to hold the wing in the stage-forceps for the sake of giving it every variety of inclination; and when that position has been found which best displays its most interesting features, it should be set up as nearly as possible in the same. For this purpose it should be mounted on an opaque slide, but instead of being laid down upon its surface the wing should be raised a little above it, its 'stalk' being held in the proper position by a little cone of soft wax, in the apex of which it may be imbedded. The wings of most Hymenoptera are remarkable for the peculiar apparatus by which

those of the same side are connected together, so as to constitute in flight but one large wing; this consists of a row of curved hooklets on the anterior margin of the posterior wing, which lay hold of the thickened and doubled down posterior edge of the anterior wing. These hooklets are sufficiently apparent in the wings of the common bee, when examined with even a low magnifying power; but they are seen better in the wasp, and better still in the hornet. The peculiar scaly covering of the wings of the Lepidoptera has already been noticed: but it may here be added that the entire wings of many of the smaller and commoner insects of this order, such as the *Tineidæ* or 'clothes-moths,' form very beautiful opaque objects for low powers, the most beautiful of all being the divided wings of the *Fissipennes* or 'plumed moths,' especially those of the genus *Pterophorus*.

There are many insects, however, in which the wings are more or less consolidated by the interposition of a layer of horny substance between the two layers of membrane. This plan of structure is most fully carried out in the *Coleoptera* (beetles), whose anterior wings are metamorphosed into *elytra* or 'wing-cases'; and it is upon these that the brilliant hues by which the integument of many of these insects is distinguished are most strikingly displayed. In the anterior wings of the *Forficulidæ*, or earwig tribe, the cellular structure may often be readily distinguished when they are viewed by transmitted light, especially after having being mounted in Canada balsam. The anterior wings of the *Orthoptera* (grasshoppers, crickets, &c.), although not by any means so solidified as those of Coleoptera, contain a good deal of horny matter; they are usually rendered sufficiently transparent, however, by Canada balsam to be viewed with transmitted light; and many of them are so coloured as to be very showy objects (as are also the posterior fan-like wings) for the electric or gas microscope, although their large size and the absence of any minute structure prevent them from affording much interest to the ordinary microscopist. We must not omit to mention, however, the curious sound-producing apparatus which is possessed by most insects of this order, and especially by the common *house-cricket*. This consists of the 'tympanum,' or drum, which is a space on each of the upper wings, scarcely crossed by veins, but bounded externally by a large dark vein provided with three or four longitudinal ridges; and of the 'file' or 'bow,' which is a transverse horny ridge in front of the tympanum, furnished with numerous teeth; and it is believed that the sound is produced by the rubbing of the two bows across each other, while its intensity is increased by the sound-board action of the tympanum. The wings of the *Fulgoridæ* (lantern-flies) have much the same texture as those of the Orthoptera, and possess about the same value as microscopic objects, differing considerably from the purely membranous wings of the *Cicadæ* and *Aphides*, which are associated with them in the order *Homoptera*. In the order *Hemiptera*, to which belong various kinds of land and water insects that have a suctorial mouth resembling that of the common bug, the wings of the anterior pair are usually of parchmenty consistence, though membranous near their tips, and

are often so richly coloured as to become very beautiful objects when mounted in balsam and viewed by transmitted light; this is the case especially with the terrestrial vegetable feeding kinds, such as the *Pentatoma* and its allies, some of the tropical forms of which rival the most brilliant of the beetles. The British species are by no means so interesting, and the aquatic kinds, which, next to the bed-bugs, are the most common, always have a dull brown or almost black hue; even among these last, however, of which the *Notonecta* (water-boatman) and the *Nepa* (water-scorpion) are well-known examples, the wings are beautifully variegated by differences in the depth of that hue. The *halteres* of the Diptera, which are the representatives of the posterior wings, have been shown by Dr. J. B. Hicks to present a very curious structure, which is found also in the elytra of Coleoptera and in many other situations, consisting in a multitude of vesicular projections of the superficial membrane, to each of which there proceeds a nervous filament, that comes to it through an aperture in the tegumentary wall on which it is seated. Various considerations are stated by Dr. Hicks which lead him to the belief that this apparatus, when developed in the neighbourhood of the spiracles or breathing pores, essentially ministers to the sense of *smell*, whilst, when developed upon the palpi and other organs in the neighbourhood of the mouth, it ministers to the sense of *taste*.[1]

Feet.—Although the feet of insects are formed pretty much on one general plan, yet that plan is subject to considerable modifications in accordance with the habits of life of different species. The entire limb usually consists of five divisions, namely, the *coxa* or hip, the *trochanter*, the *femur* or thigh, the *tibia* or shank, and the *tarsus* or foot; and this last part is made up of several successive joints. The typical number of these joints seems to be *five*,[2] but that number is subject to reduction; and the vast order Coleoptera is subdivided into primary groups, according as the tarsus consists of *five*, *four*, or *three* segments. The last joint of the tarsus is usually furnished with a pair of strong hooks or claws (figs. 685, 686); and these are often serrated (that is, furnished with saw-like teeth), especially near the base. The under surface of the other joints is frequently beset with tufts of hairs, which are arranged in various modes, sometimes forming a complete 'sole'; this is especially the case in the family *Curculionidæ*; a pair of the feet of the 'diamond beetle' mounted so that one shows the upper surface made resplendent by its jewel-like scales, and the other the hairy cushion beneath, is a very interesting object. In many insects, especially of the fly kind, the foot is furnished with a pair of membranous expansions termed *pulvilli* (fig. 685); and these are beset with numerous hairs, each of which has a minute disc at its extremity. This structure is evidently connected with the power which these insects possess of

[1] See his memoir, 'On a new Organ in Insects,' in *Journ. Linn. Soc.* vol. i. 1856, p. 136; his 'Further Remarks on the Organs found on the Bases of the Halteres and Wings of Insects,' in *Trans. Linn. Soc.* xxii. p. 141; and his memoir, 'On certain Sensory Organs in Insects hitherto undescribed,' in *Trans. Linn. Soc.* xxiii. p. 189.

[2] See, however, Professor Huxley (*Anat. of Invertebrate Animals*, p. 348), who, regarding the 'pulvillus' of the cockroach as a joint, finds the number to be six.

walking over smooth surfaces in opposition to the force of gravity; yet there is still considerable uncertainty as to the precise mode in which it ministers to this faculty. Some believe that the discs act as suckers, the insect being held up by the pressure of the air against their upper surface when a vacuum is formed beneath; whilst others maintain that the adhesion is the result of the secretion of a viscid liquid from the under side of the foot. The careful observations of Mr. Hepworth have led him to a conclusion which seems in harmony with all the facts of the case—namely, that each hair is a tube conveying a liquid from a glandular sacculus situated in the tarsus, and that when the disc is applied to a surface the pouring forth of this liquid serves to make its adhesion perfect. That this adhesion is not produced by atmospheric pressure alone is proved by the fact that the feet of flies continue to hold on to the interior of an exhausted receiver; whilst, on the other hand, that the feet pour forth a secreted fluid is evidenced by the marks left by their attachment on a clean surface of glass. Although, when all the hairs have the strain put upon them equally, the adhesion of their discs suffices to support the insect, yet each row may be detached separately by the gradual raising of the tarsus and pulvilli, as when we remove a piece of adhesive plaster by lifting it from the edge or corner. Flies are often found adherent to window-panes in the autumn, their reduced strength not being sufficient to enable them to detach their tarsi.[1] A similar apparatus on a far larger scale presents itself on the foot of the *Dytiscus* (fig. 686, A). The first joints of the tarsus of this insect are widely expanded, so as to form a nearly circular plate, and this is provided with a very remarkable apparatus of suckers, of which one disc (*a*) is extremely large, and is furnished with strong radiating fibres; a second (*b*) is a smaller one formed on the same plan (a third, of the like kind, being often present); whilst the greater number are comparatively small tubular club-shaped bodies, each having a very delicate membranous sucker at its extremity, as shown on a larger scale at B. These all have essentially the same structure, the large suckers being furnished, like the hairs of the fly's foot, with secreting sacculi, which pour forth fluid through the



FIG. 685.—Foot of fly.

[1] See Mr. Hepworth's communications to the *Quart. Journ. Microsc. Sci.* vol. ii. 1854, p. 158, and vol. iii. 1855, p. 312. See also Mr. Tuffen West's memoir, 'On the Foot of the Fly,' in *Trans. Linn. Soc.* xxii. p. 393; Mr. Lowne's *Anatomy of the Blow-fly*, p. 19; H. Dewitz in *Zoologischer Anzeiger*, vi. p. 278; and G. Simmermacher in *Zeitschr. f. Wiss. Zool.* xl. p. 481.

tubular footstalks that carry the discs, whose adhesion is thus secured; whilst the small suckers form the connecting link between the larger suckers and the hairs of many beetles, especially *Curculionidæ*.[1] The leg and foot of the *Dytiscus*, if mounted without compression, furnish a peculiarly beautiful object for the binocular microscope. The feet of caterpillars differ considerably from those of perfect insects. Those of the first three segments, which are afterwards to be replaced by true legs, are furnished with strong horny claws; but each of those of the other segments, which are termed 'pro-legs,' is composed of a circular series of comparatively slender curved hooklets, by which the caterpillar is enabled to cling to the minute roughnesses of the surface of the leaves &c. on which it feeds. This structure is well seen in the pro-legs of the common silkworm.

Stings and Ovipositors.—The insects of the order Hymenoptera are all distinguished by the prolongation of the antepenultimate and



FIG. 686.—A, foot of *Dytiscus*, showing its apparatus of suckers: *a*, *b*, large suckers; *c*, ordinary suckers. B, one of the ordinary suckers more highly magnified.

penultimate segments of the abdomen (the eighth and ninth abdominal segments of the larva) into a peculiar organ, which in one division of the order is a 'sting,' and in the other is an 'ovipositor' or instrument for the deposition of the eggs, which is usually also provided with the means of boring a hole for their reception. The former group consists of the bees, wasps, ants, &c.; the latter of the saw-flies, gall-flies, ichneumon-flies, &c. These two sets of instruments are not so unlike in structure as they are in function.[2] The

[1] See Mr. Lowne, 'On the so-called Suckers of *Dytiscus* and the Pulvilli of Insects,' in *Monthly Microsc. Journ.* v. p. 267.

[2] See Kraepelin, 'Untersuchungen über den Bau, Mechanismus und Entwicklungsgeschichte der bienenartigen Thiere,' in *Zeitschr. f. Wiss. Zool.* xxiii. p. 289; Dewitz, 'Ueber Bau und Entwickelung des Stachels und der Legescheide,' *op. cit.* xxv. p. 174; and 'Ueber Bau und Entwickelung des Stachels der Ameisen,' *op. cit.* xxviii. p. 527.

'sting' is usually formed of a pair of darts, beset with barbed teeth at their points, and furnished at their roots with powerful muscles, whereby they can be caused to project from their sheath, which is a horny case formed by the prolongation of the integument of the last segment, slit into two halves, which separate to allow the protrusion of the sting; whilst the peculiar 'venom' of the sting is due to the ejection, by the same muscular action, of a poisonous liquid, from a bag situated near the root of the sting, which passes down a canal excavated between the darts, so as to be inserted into the puncture which they make. The stings of the common bee, wasp, and hornet, may all be made to display this structure without much difficulty in the dissection. The 'ovipositor' of such insects as deposit their eggs in holes ready-made, or in soft animal or vegetable substances (as is the case with the *Ichneumonidæ*), is simply a long tube, which is inclosed, like the sting, in a cleft sheath. In the gall-flies (*Cynipidæ*) the extremity of the ovipositor has a toothed edge, so as to act as a kind of saw whereby harder substances may be penetrated; and thus an aperture is made in the leaf, stalk, or bud of the plant or tree infested by the particular species, in which the egg is deposited, together with a drop of fluid that has a peculiarly irritating effect upon the vegetable tissues, occasioning the production of the 'galls,' which are new growths that serve not only to protect the larvæ, but also to afford them nutriment. The oak is infested by several species of these insects, which deposit their eggs in different parts of its fabric; and some of the small 'galls' which are often found upon the surface of oak-leaves are extremely beautiful objects for the lower powers of the microscope. In the *Tenthredinidæ*, or 'saw-flies,' and in their allies, the *Siricidæ*, the ovipositor is furnished with a still more powerful apparatus for penetration, by means of which some of these insects can bore into hard timber. This consists of a pair of 'saws' which are not unlike the 'stings' of bees &c. but are broader and toothed for a greater length, and are made to slide along a firm piece that supports each blade, like the 'back' of a carpenter's 'tenon-saw'; they are worked alternately (one being protruded while the other is drawn back) with great rapidity; but when not in use they lie in a fissure beneath a sort of arch formed by the terminal segment of the body. When a slit has been made by the working of the saws they are withdrawn into this sheath; the ovipositor is then protruded from the end of the abdomen (the body of the insect being curved downwards), and, being guided into the slit by a pair of small hairy feelers, there deposits an egg.[1] Many other insects, especially of the order *Diptera*, have very prolonged ovipositors, by means of which they can insert their eggs into the integuments of animals or into other situations in which the larvæ will obtain appropriate nutriment. A remarkable example of this is furnished by the gad-fly (*Tabanus*), whose ovipositor is

[1] The above is the account of the process given by Mr. J. W. Gooch, who has informed the Author that he has repeatedly verified the statement formerly made by him (*Science Gossip*, Feb. 1, 1873), that the eggs are deposited, not, as originally stated by Réaumur, by means of a tube formed by the coaptation of the saws, but through a separate ovipositor, protruded when the saws have been withdrawn.

composed of several joints, capable of being drawn together or extended like those of a telescope, and is terminated by boring instruments; and the egg being conveyed by its means, not only *into* but *through* the integument of the ox, so as to be imbedded in the tissue beneath, a peculiar kind of inflammation is set up there, which (as in the analogous case of the gall-fly) forms a nidus appropriate both to the protection and to the nutrition of the larva. Other insects which deposit their eggs in the ground, such as the [illegible], have their ovipositors so shaped as to answer for digging holes for their reception. The preparations which serve to display the fore-

FIG. 687.—Various eggs, chiefly of the *Acarina*, etc.

going parts are best seen when mounted in balsam, save in the case of the muscles and poison-apparatus of the sting, which are better preserved in fluid or in glycerin jelly.

The sexual organs of insects furnish numerous objects of extreme interest to the anatomist and physiologist; but as an account of them would be unsuitable to the present work, a reference to the copious source of information respecting one of their most curious features, and to a list of the species that afford good illustrations, must here suffice.[1] The *eggs* of not only the class *Insecta*, but of

[1] See the memoirs of M. Lacaze-Duthiers, 'Sur l'Armure Génitale des Insectes' *Ann. des Sci. Nat.* sér. iii. zool. tomes xii. xiv. xvii. xviii. xix.; and M. C. Bol[illegible]

many of the minuter forms of the class *Arachnida*, as for example the *Acarina*, or mites and ticks, present to those who are in search of objects of beauty a wide and most interesting field. In fig. 687 we give a group of eggs, all but the central form being eggs of organisms of this order. It is thus with the eggs of many insects; they are objects of great beauty, on account of the regularity of their form and the symmetry of the markings on their surface (fig. 688). The most interesting belong for the most part to the order *Lepidoptera*; and there are few among these that are not worth examination, some of the commonest (such as those of the cabbage butterfly,



FIG. 688.—Eggs of butterflies and moths.

which are found covering large patches of the leaves of that plant) being as remarkable as any. Those of the puss-moth (*Cerura vinula*), the privet hawk-moth (*Sphinx ligustri*), the small tortoise-shell butterfly (*Vanessa urticæ*), the meadow-brown butterfly (*Hipparchia janira*), the brimstone-moth (*Rumia crataegata*), and the silkworm (*Bombyx mori*) may be particularly specified; and, from other orders, those of the cockroach (*Blatta orientalis*), field-cricket (*Acheta campestris*), water-scorpion (*Nepa ranatra*), bug (*Cimex*

Mémoire sur les Objets qui peuvent être conservés en Préparations microscopiques (Paris, 1856), which is peculiarly full in the enumeration of the objects of interest afforded by the class of Insects.

lectularius), cow-dung fly (*Scatophaga stercoraria*), and blow-fly (*Musca vomitoria*).[1] In order to preserve these eggs they should be mounted in fluid in a cell, since they will otherwise dry up, and may lose their shape. They are very good objects for securing some of the best binocular effects.

The remarkable mode of reproduction that exists among the *Aphides* must not pass unnoticed here, from its curious connection with the non-sexual reproduction of *Entomostraca* and *Rotifera*, as also of *Hydra* and *Zoöphytes* generally, all of which fall specially, most of them exclusively, under the observation of the microscopist. The *Aphides*, which may be seen in the spring and early summer, and which are commonly, but not always, wingless, are all of one sex, and give birth to a brood of similar *Aphides*, which come into the world alive, and before long go through a like process of multiplication. As many as from seven to ten successive broods may thus be produced in the course of a single season; so that from a single *Aphis* it has been calculated that no fewer than ten thousand million millions may be evolved within that period. In the latter part of the year, however, some of these viviparous *Aphides* attain their full development into males and females; and these perform the true generative process, whose products are eggs, which, when hatched in the succeeding spring, give origin to a new viviparous brood that repeat the curious life-history of their predecessors. It appears from the observations of Professor Huxley [2] that the broods of viviparous *Aphides* originate in ova which are not to be distinguished from those deposited by the perfect winged female. Nevertheless, this non-sexual or *agamic* reproduction must be considered analogous rather to the 'gemmation' of other animals and plants than to their sexual 'generation'; for it is favoured, like the gemmation of *Hydra*, by warmth and copious sustenance, so that by appropriate treatment the viviparous reproduction may be caused to continue (as it would seem) indefinitely, without any recurrence to the sexual process. Further, it seems now certain that this mode of reproduction is not at all peculiar to the *Aphides*, but that many other insects ordinarily multiply by 'agamic' propagation, the production of males and the performance of the true generative act being only an occasional phenomenon; and the researches of Professor Siebold have led him to conclude that even in the ordinary economy of the hive-bee the same double mode of reproduction occurs. The queen, who is the only perfect female in the hive, after impregnation by one of the drones (or males) deposits eggs in the 'royal' cells, which are in due time developed into young queens; others in the drone cells, which become drones; and others in the ordinary cells, which become workers or neuters. It has long been known that these last are really undeveloped females, which, under certain conditions, might become queens; and it has been observed by bee-keepers that worker-bees

[1] Compare R. Leuckart in *Archiv f. Anat.* 1853, p. 90, 'Ueber die Micropyle und den feinern Bau der Schalenhaut bei den Insecteneiern,' and A. Brandt, *Ueber das Ei und seine Bildungstätte*, Leipzig, 1878.

[2] 'On the Agamic Reproduction and Morphology of *Aphis*' in *Trans. Linn. Soc.* xxii. p. 193.

in common with virgin or unimpregnated queens, occasionally lay eggs from which eggs none but drones are ever produced. From careful microscopic examination of the drone eggs laid even by impregnated queens, Siebold drew the conclusion that they have not received the fertilising influence of the male fluid, which is communicated to the queen-eggs and worker eggs alone; so that the products of sexual generation are always female, the males being developed from these by a process which is essentially one of gemmation.[1]

The embryonic development of insects is a study of peculiar interest, from the fact that it may be considered as divided (at least in such as undergo a 'complete metamorphosis') into two stages that are separated by the whole active life of the larva—that, namely, by which the larva is produced within the egg, and that by which the imago or perfect insect is produced within the body of the pupa. Various circumstances combine, however, to render the study a very difficult one; so that it is not one to be taken up by the inexperienced microscopist. The following summary of the history of the process in the common blow-fly, however, will probably be acceptable. A *gastrula* with two membranous lamellæ having been evolved in the first instance, the outer lamella very rapidly shapes itself into the form of the larva, and shows a well-marked segmental division. The alimentary canal, in like manner, shapes itself from the inner lamella, at first being straight and very capacious, including the whole yolk, but gradually becoming narrow and tortuous as additional layers of cells are developed between the two primitive lamellæ, from which the other internal organs are evolved. When the larva comes forth from the egg it still contains the remains of the yolk; it soon begins, however, to feed voraciously; and in no long period it grows to many thousand times its original weight, without making any essential progress in development, but simply accumulating material for future use. An adequate store of nutriment (analogous to the 'supplemental yolk' of *Purpura*) having thus been laid up within the body of the larva, it resumes (so to speak) its embryonic development, its passage into the pupa state, from which the imago is to come forth, involving a degeneration of all the larval tissues; whilst the tissues and organs of the imago 'are redeveloped from cells which originate from the disintegrated parts of the larva, under conditions similar to those appertaining to the formation of the embryonic tissues from the yolk.' The development of the segments of the head and body in insects generally proceeds from the corresponding larval segments; but, according to Dr. Weismann, there is a marked exception in the case of the *Diptera* and other insects whose larvæ are unfurnished with legs, their head and thorax being newly formed from 'imaginal discs,' which adhere to the nerves and tracheæ of the anterior extremity of the larva;[2] and, strange as this assertion may seem,

[1] See Professor Siebold's memoir, *On true Parthenogenesis in Moths and Bees*, translated by W. S. Dallas (London, 1857); and his *Beiträge zur Parthenogenesis der Arthropoden* (Leipzig, 1871).

[2] See his 'Entwickelung der Dipteren' in *Zeitschrift f. Wiss. Zool.* xiii. and xiv.; Mr. Lowne's *Anatomy of the Blow-fly* (1st ed.), pp. 6–9, 113–121; and A. Kowalevsky,

it has been confirmed by the subsequent investigations of Mr. Lowne.

The *Arachnida*, or scorpions and pseudo-scorpions, and the *Araneida* or spiders, present much that is of interest even to the unscientific who use the microscope only for pleasure. The general remarks which have been made in regard to insects are equally applicable to these, but have special application in that group known as the *Acarina*, consisting of the *mites* and *ticks*. Some of these are parasitic, and are popularly associated with the wingless parasitic insects, to which they bear a strong general resemblance, save in having *eight* legs instead of *six*. The *Acarina* are the true 'mites': they generally have the legs adapted for walking, and some of them are of active habits. The common cheese-mite, as seen by the naked eye, is familiar to everyone; yet few who have not seen it under a microscope have any idea of its real conformation and movements: and a cluster of them, cut out of the cheese they infest, and placed under a magnifying power sufficiently low to enable a large number to be seen at once, is one of the most amusing objects that can be shown to the young. There are many other species, which closely resemble the cheese-mite in structure and habits, but which feed upon different substances; and some of these are extremely destructive.

The *Acarina* are the smallest of the *Arthropoda*, and are specially well fitted for microscopical examination; indeed, with the exception of the *Ixodidæ* (including the *Argasinæ*), which attain a substantial size, particularly in tropical countries, but little can be learnt respecting them without such aid; as far as is at present known, other mites are not larger in hot countries than in Europe. Many species make beautiful objects for the microscope, and may be well preserved, the hard-bodied specimens in balsam without heat or pressure, the soft-bodied in glycerin or glycerin jelly; e.g. the nymphs of *Leiosoma palmacinctum*, *Tegeocranus cepheiformis*, *T. dentatus*, and the adults of *Glyciphagus plumiger* and *G. palmifer* are admirable. They are all British, and are found respectively on lichen at the Land's End, on the fallen bark and needles of fir-trees, on fallen oak-wood, in the fodder in stables, and on cellar-walls. Many of the *Trombidiidæ* and *Hydrachnidæ* also are very beautiful: and the *Dermaleichi*, especially the males, and such creatures as *Myobia*, *Listrophorus*, &c. are extremely curious. With the exception of the *Phytoptidæ*, all *Acarina* in the adult stage have eight legs and the constriction between cephalo-thorax and abdomen is far less marked than in insects and spiders—in many genera it is wholly lost. The sexes are distinct and often very different from each other; the reproduction is oviparous or ovo-viviparous—possibly in rare and exceptional instances viviparous. The ova are usually elliptical or oval; in those which have a hard shell a curious stage known as the 'deutovium' exists: as the egg increases in size the shell splits into two symmetrical halves, which remain attached to the lining membrane, but are widely separated, the

Beiträge zur Kenntnis der Nachembryonalen-Entwickelung der Muscidæ. *Zeitschr. f. Wiss. Zool.* xliv. p. 542.

PLATE XVII.



Arachnida.



membrane becoming the external covering in the space left. The eggs of the so-called stone-mite (*Petrobia lapidum*) are discoidal and sculptured; they occasionally appear in countless numbers over a large space of ground in a single night, making the place look whitewashed; they have been mistaken for fungi and called *Craterium pyriforme*; they are good microscopical objects. The larvæ of all *Acarina*, except *Phytoptus* and possibly *Dermanyssus*, are hexapod; the fourth pair of legs is absent. The nymphal stage is usually the principal period of growth; occasionally, however, it is wanting. The nymph is an active chrysalis, as in the *Orthoptera*; it usually undergoes several ecdyses. In many species of the *Oribatidæ* the whole skin is not cast, but splits round the edge of the body, and the dorso-abdominal portion remains attached to the new skin; often it has a row of elegant spines or hairs round its edge; thus after two or three ecdyses these spines form concentric rings on the notogaster (Plate XIX, fig. 2). In the *Trombidiidæ*, *Tyroglyphi*, &c. the nymphs usually greatly resemble the adults; in the *Oribatidæ* they are often totally different, and every intermediate stage occurs. The change from nymph to adult is usually preceded by an inert period.

The number and variety of the families, and the differences in the external form and internal anatomy, are so great and so endless that it is impossible here to do more than indicate a few leading features and refer to a few examples of interest. The caput is, of course, fused with the thorax, but sometimes a constriction at the base of the rostrum gives a false appearance of there being a distinct head. The trophi are extremely different in the respective families, or even genera. In the more highly organised of the *Gamasidæ* almost all the parts which exist in the most elaborate insect-mouths except the labial palpi may be found; they are well described by M. Mégnin.[1] A large oral tube is formed by the anchylosed maxillæ and probably upper lip and lingua. Up the centre of this tube the mandibles pass freely; they are very long and chelate: the first joint is simply cylindrical; the second similar, but having the fixed chela at its distal end; the third is the movable chela. They are capable of being projected far beyond the body, or of being withdrawn wholly within it, the muscles which withdraw them often arising from quite the posterior end of the body. These mandibles are different in the two sexes, and those of the male often have most remarkable appendages. One of the best examples is that of *Gamasus terribilis*, a species found in moles' nests by Mr. Michael. Professor Canestrini, of Padua, also has figured some very singular forms. In the *Oribatidæ*, *Tetranychus*, the *Sarcoptidæ*, &c. the mandibles are also chelate, but of two joints only, shorter, more powerful, and not capable of such great protrusion. In the *Hydrachnidæ*, *Trombidiinæ*, &c. the mandible is not chelate, but the terminal joint shuts back like a clasp-knife, as in the poison-fangs of spiders. Other forms of mandible are found. The maxillæ are large toothed crushing organs in the *Oribatidæ*; they are very

[1] *Journ. de l'Anat. et de la Physiol.*, Robin, May 1876.

strongly developed in *Hoplophora*, which is a wood-boring creature. In other families they are more commonly joined, forming a maxillary lip with a flexible edge for sucking purposes. The maxillary palpi vary greatly; in the *Sarcoptidæ*, *Myobia*, &c. they are anchylosed to the lip; in the *Phytopti* Nalepa is of opinion that they are needle-like piercing organs, but these may well be the maxillæ. In some predatory forms, as *Cheyletus*, *Trombidium*, &c. they assume great importance, being the raptorial organs; in the first they are extremely large and powerful and work horizontally; they are provided with a number of long chitinous spines and comb-like appendages of a very singular character. In *Trombidium* the ultimate joint is articulated at the base of, or part of the way down, the penultimate, forming a species of chela. In *Bdella* the palpi are long thin organs, carried upward and backward, and have the appearance of antennæ. The joints of the legs are from three (*Demodex*) to seven (some *Trombidiidæ* and *Gamasidæ*); five is the most usual number. They are terminated by a sucker as in the *Sarcoptidæ*, where it is often very large; or by a claw or claws, or both together. In some parasitic species the claws are developed in a special manner for holding the hairs of the host; thus *Myobia* has the claw of the first leg flattened out so as to form a broad lamina, which curls round the hair and presses it against a chitinous peg on the tarsus; *Myocoptes* has a similar arrangement on the third leg. Both these genera contain species which are parasites of the mouse, and easily obtained. In the *Oribatidæ*, *Tyroglyphi*, &c. the legs are all strictly walking organs; but in *Cheyletus*, most *Gamasidæ*, &c. the first pair are tactile, and not used in locomotion. The legs generally correspond on the two sides of the body, but in *Freyana heteropus*, an extraordinary parasite of the cormorant discovered by Mr. Michael (Plate XX. fig. 3), the second leg of the male is developed to a much greater extent on one side than on the other, and is supported by a different sternal skeleton on the two sides; the strangest fact is that it is not always the same side that is thus developed: it is usually the left, but occasionally the right. The integument of the *Acarina* is almost always soft in the immature forms; in the adults it is hard and chitinised in the *Oribatidæ* and most *Gamasidæ*; partly so in the *Ixodidæ*; and usually soft in most other families, and often minutely striated. The hairs and other appendages of the integument of a similar nature are often very characteristic and extraordinary. In the nymph of *Leiosoma palmacinctum* they are large scale-like processes of a Japanese-fan shape, which entirely cover up and conceal the body of the creature: a leaf-like form is also common. In *Glyciphagus plumiger* they are elegant plumes; in some *Sarcoptidæ*, e.g. *Symbiotes tripilis*, some of the simple setiform hairs are three times the length of the body; in the *Trombidiidæ* the body-hairs are often extremely fanciful. The setiform hairs are the principal organs of touch, those on the front legs being specially important. So sensitive are they that *Cheyletus* and some Gamasids, which are predatory and capture such active creatures as *Thysanuridæ*, are entirely eyeless, and trust to the tactile sense only. Haller was of opinion that certain specialised

PLATE XIX.



West Newman ... ...

Acarina.

hairs had an auditory function. In the *Ixodidæ* a singular drum-like structure in the first leg has been considered by Haller and others to be the hearing organ ; while in the *Oribatidæ* that organ appears to be located in the pseudo-stigmata, two paired organs at the side of the cephalo-thorax which were long taken for true stigmata. The *Gamasidæ*, *Oribatidæ*, *Tyroglyphidæ*, *Sarcoptidæ*, &c. are entirely without special organs of vision. The *Hydrachnidæ* have two pairs of simple eyes, each pair being so close together as to look like a single eye. The *Trombidiidæ* mostly have simple eyes, the number and position of which vary with the species. As to internal anatomy it should be noted that there is almost endless variety. The alimentary canal most commonly consists of a long thin œsophagus, provided with distensor muscles on each side, so as to make it a sucking organ ; it usually passes right through or close under the great ganglion known as the brain ; in some species, as *Dameus geniculatus*, the œsophagus is followed by a large proventriculus, but this is not usual ; it more commonly leads directly into the ventriculus, which generally is a principal viscus, and in most families furnished with more or less glandular cæcal appendages, not numerous, but often very large, occasionally larger than the organ itself. A valve in many cases separates the ventriculus from the hind-gut, which is commonly divided into what may be called colon and rectum. In the *Gamasidæ* a single very large Malpighian vessel on each side of the body enters between the two last-named divisions of the alimentary canal. These vessels run right along the side of the body, and strong pulsation may be seen in them. In the *Oribatidæ* they are absent, their function being apparently performed by supercoxal glands. The *Tyroglyphidæ*, *Sarcoptidæ*, *Phytoptidæ*, &c. are without special respiratory organs ; the *Oribatidæ* and some *Uropoda* have simple unbranched tracheæ, much in the same condition as those of *Peripatus*. The other *Gamasidæ*, the *Trombidiidæ*, *Cheyletidæ*, *Ixodidæ*, &c. usually have branched tracheæ, like insects ; air-sacs are occasionallly found, but not anything like the tracheal lungs or gills (so called) of spiders and scorpions. The principal nerve-centre is much concentrated, and consists usually of either a large supra-œsophageal and smaller subœsophageal ganglion, joined by commissures ; or, more frequently, the whole forms one mass, which is pierced by the œsophagus, which may be pulled out, leaving a neat round hole ; the nerves, of course, radiate from this mass, but there is not space here to describe their course. A pulsating organ of the nature of the dorsal vessel of insects, but much shorter, and with only one or two pairs of ostia, has been detected in some *Gamasidæ*, and in *Ixodes*, first by Kramer and afterwards by Winkler and Claus ; it has a median aorta running forward ; it is best seen in life in young specimens still transparent ; it lies at the rear of the ventriculus, near the dorsal surface. Nothing of the nature of a heart has yet been discovered in other *Acarina*. The reproductive organs are, perhaps, most frequently of the 'ring' type, well known in the *Arachnida* ; thus in female *Oribatidæ* they consist of a central ovary, with an oviduct springing from near each end, in which the

eggs are matured; the oviducts both terminate in an unpai vagina, whence the eggs pass into a long, membranous, extensi ovipositor, often wrinkled or striated with singular fineness a beauty. The external aperture is closed by chitinous folding do A more or less similar arrangement may be found in most *Gamasi Hydrachnidæ*, &c. but without the ovipositor. Spermathec often found in the *Gamasidæ*, *Tyroglyphidæ*, &c., and access glands frequently accompany the vagina in almost all families. male system varies greatly, but is frequently constructed on sim lines, preserving somewhat of the 'ring' form.

The principal families into which the *Acarina* are divided ar follows:—

The *Gamasidæ*, which in the adult stage are mostly p vided with a hard chitinous cuticle in all parts of the body. T are mostly predatory, but the females and young are often parasi *Pteroptus* and *Dermanyssus*, however, are more leathery in textu and are parasitic during their whole lives, the former on bats, latter on birds. This family have the true stigmata, one on e side of the ventral surface, usually between the second and th pairs of legs; these do not communicate directly with the exter air, but have a long tubular peritreme in the chitin of the ven surface, often very elaborate in form, and emerging to the air usu between the first and second legs. This is highly characteristic the family.

The *Ixodidæ*, or ticks, most of which are probably prima vegetable feeders, but will, when opportunity offers, attach th selves to animals by sinking their long serrated rostral project into the skin, have a single ventral stigma on each side, c municating directly with the air by a large cullender-plate, wh is an interesting microscopical object. The males have the do surface of the abdomen almost entirely covered by a chitinous pl which is much smaller in the females; but the leathery portio the abdomen in that sex is capable of great distension for the p pose of permitting the suction of animal juices. The *Argas* must be included in this group; their tenacity of life and power existing without food are marvellous: their bite is severe, but terrible stories told of the results of the bite of the Persian *Ar* have not been supported on investigation.

The *Oribatidæ* are mostly wholly chitinised, the chitin be very hard and brittle. The stigmata are in the acetabula of legs. The pseudo-stigmata (hearing organs) of this family ha been before referred to. *Oribatidæ* are vegetable feeders, living moss, lichen, fungus, dead wood, under bark of trees, &c. and so few species on aquatic plants. They are widely distributed fr the arctic regions to the equatorial. *Hoplophora* has the power withdrawing the legs wholly within the carapace, and then shutti down the cephalo-thorax against the abdomen, so as to close t opening, when it appears like a chitinous ball: from this power has been called the 'box-mite.' The sexes have not any exter difference.

The *Trombidiidæ* are a large and varied group, mostly predato

PLATE XX.



Acarina.

West, Newman lith.

THE NEW YORK
PUBLIC LIBRARY
ART

nd with soft, often velvety skins, frequently of scarlet and other rilliant colours. The large *Trombidium holosericum* is a well-known nicroscopical object. The *Tetranychi* are usually included in this amily; they are, however, rather doubtful members; they are the 'red-piders' of our greenhouses, much dreaded by horticulturists. Each oot is provided with about four singular hairs with round knobs at he end. *Bryobia* is an allied genus found in great numbers on ivy tc. in gardens and is a beautiful object. The hexapod larvæ of several pecies of *Trombidium* often attach themselves temporarily to the skin f animals, including man, and produce intolerable itching. They were upposed by the earlier Acarologists to be all one species, and to e adult, and to form a distinct family; they were called *Leptus utumnalis*, and are known in England as the 'harvest-bug,' and n France as the *rouget*. The *Bdellidæ* are also included in this amily; some authors also include the *Cheyleti*, which, however, seem o need a separate family, having many curious characters, including he dorsal position of the male organs.

The *Hydrachnidæ*, or water-mites, as well as the *Trombidiidæ*, ave the two stigmata in the rostrum; the legs are swimming rgans, the sexes often very different; they live in fresh water and re often parasitic in their immature, but not in the adult stages. hey are mostly soft-bodied and often of brilliant colours.

The *Limnocaridæ* are sometimes treated as a sub-family of the *Hydrachnidæ*, but are crawling, not swimming creatures, and are ound in fresh water; but the *Halicaridæ*, which either constitute sub-family of, or are closely associated with them, are marine, nd are much found among *Hydrozoa*, on which they probably rey.

The parasitic *Myobiidæ* are by some included in the *Cheyletidæ*; he differences, however, are very considerable. They are the last racheate family.

The *Tyroglyphidæ* are the cheese-mite family; they are far the ost destructive of all *Acarina*, swarming in countless numbers and evouring hay, cheese, drugs, growing plants and roots, &c.; the enus *Glyciphagus* contains many singular and interesting forms, as *. platygaster* and *G. Krameri*, found in moles' nests. It is in this amily that the curious hypopial stage exists; some of the indi-iduals of some species, instead of following the ordinary life-history, re changed at one ecdysis into a totally different-looking creature, ith a highly chitinised cuticle and rudimentary mouth-organs, hich can endure draught and other unfavourable circumstances hich would kill the ordinary form. They attain the same adult age as other individuals. The *Hypopus* is provided with adhesive ickers whereby it attaches itself temporarily to other creatures, and is serves for the distribution of the species.

The *Tarsonemidæ* are minute creatures, some leaf-miners, some arasitic on bees &c.

The *Sarcoptidæ* are divided into two great sub-families, the *Sar-ptinæ*, or itch-mites, of which the well-known *Sarcoptes scabiei* of an (Plate XX, fig. 4) is the type, and the *Analgesinæ*, or bird-parasite ites; all have soft bodies with finely striated cuticles. *Sarcoptes*

scabiei is a minute creature of almost circular form, the female of which burrows under the epidermis, causing the disease. The mite is found at the end of the burrow, not in the pustule at its commencement. The first two pairs of legs and the third leg of the male are terminated by suckers, the other legs by long bristles. The male is smaller than the female. The *Analgesinæ* (*Dermaleichi*) are a very large and curious group; the males often differ greatly from the females, and the skin is often greatly strengthened by chitinous plates and structures. The species are not always parasitic on one bird only; often the same species may be found on numerous birds, while several species frequently live on the same bird; they are not usually supposed to be injurious to the birds; they are found on the feathers.

The *Phytoptidæ* are extremely minute creatures living in galls which they form on the leaves and twigs of numerous trees and plants; they are elongated in form with the two hind pairs of legs abortive; there is but little variety among them. Slightly resembling them in general form, but very different in other respects, is *Demodex folliculorum*, which is found in the sebaceous follicles of the human skin, particularly the nose. Those follicles which are enlarged and whitish, with a terminal exterior black spot, may be forced out by pressure, and the *Acarus* will often be found within. Similar parasites exist on the dog and pig.

There are numerous other curious and interesting forms which cannot be included in any of the families mentioned above.

The number of objects furnished to the microscopist by the spider tribe is very large from a biological point of view, although mere objects of microscopical interest popularly are not so numerous as in insects. Their eyes exhibit a condition intermediate between that of insects and crustaceans and that of vertebrata, for they are simple like the 'stemmata' of the former, usually number from six to eight, are sometimes clustered together in one mass, but more frequently disposed separately; while they present a decided approach in internal structure to the type characteristic of the visual organs of the latter.

The structure of the mouth is always mandibulate, and is less complicated than that of the mandibulate insects. The respiratory apparatus is not tracheal, as in insects and some *Acarina*, but is constructed upon a very different plan, for the 'stigmata,' which are usually four in number on each side, open upon a like number of respiratory sacculi, each of which contains a series of leaf-like folds of its lining membrane upon which the blood is distributed so as to afford a large surface to the air.

In the structure of the limbs, the principal point worthy of notice is the peculiar appendage with which they usually terminate, for the strong claws, with a pair of which the last joint of the foot is furnished, have their edges cut into comb-like teeth, which appear to be used by the animal as cleansing instruments, and in many cases for the manipulation of the silk of their snares. But a feature deserving study by the microscopist is the physical cause of the exquisite sensitiveness of these 'feet.' By resting these upon a

trap-line of silk carried to her den, she can, by a veritable telegraphy, discover instantly, not only the fact that there is prey upon her snare, but the exact spot in the web of the snare in which that prey is entangled. In the same way by seizing certain taughtened threads communicating with the main lines of the snare, she can discover in an instant the presence and position of her prey, though far beyond the reach of vision.

The most characteristic and interesting parts in the special organisation of the spider is the 'spinning apparatus,' by means of which its often elaborately constructed webs are produced. These consist of 'spinnerets' on the exterior of the body and glandular organs lying within the abdomen; it is by them that the silk from which all the elements of the snare are produced is secreted.

FIG. 689.—Foot, with comb-like claws, of the common spider (*Epeïra*).

Of these glands there are two pairs which are sac-like in form, with a coiled tube opening directly on the spinnerets; there are three pairs, of a convoluted appearance, opening on the hinder spinnerets; and there are three of a sinuous tubular form opening on the hinder and middle spinnerets. Beyond these there are respectively 200 and 400 smaller glands, which open on the front, middle, and hinder spinnerets. They all terminate in tubes of great delicacy, through which the silk is drawn at the will of the spinster; and, while the scaffolding or framework of the web of *Epeïra* is double and hardens rapidly in air (fig. 690, A), those which lie across the polygons of the scaffolding are studded at regular intervals with viscid globules, as seen in fig. 690, B; and it is to these viscid globules that the peculiarly adhesive character of the web is due.



FIG. 690.—Ordinary thread (A) and viscid thread (B) of the common spider.

The usual number of the spinnerets is six. They are little teat-like processes crowned with silk tubes. They are movable at the will of the spider, and can be erected or depressed, and one, many, or all of the tubes crowning a spinneret may be caused to exude, and have drawn from it or them the silk as the spider determines. There can be no doubt that there is a difference in the silk secreted by different glands, and its appropriate employment is a part of the skill of the spider.

It is certain that the silken threads of a snare are of two kinds:

(1) that which rapidly hardens on contact with the air, and wl
is employed in the construction of the framework of the snare :
(2) a viscid silk with which the entangling meshes by which pre
caught are put in. The latter present beautiful objects for pop
observation, because the thread has strung upon it, as it w
innumerable pearl-like globules in which the viscidity rema
These beads are produced after the thread is drawn out b
special vibratory action set up in the thread by the spider.

The eggs of spiders are not objects of special optical inter
but they afford opportunities for good embryological work, and
habits of spiders offer a good scope for industrious study in the fi

CHAPTER XXII

VERTEBRATED ANIMALS

We are now arrived at the highest division of the animal kingdom, in which the bodily fabric attains its greatest development, not only as to completeness, but also as to size; and it is in most striking contrast with the class we have been last considering. Since not only the entire bodies of vertebrated animals, but, generally speaking, the smallest of their integral parts, are far too large to be viewed as microscopic objects, we can study their structure only by a separate examination of their component elements; and it seems, therefore, to be a most appropriate course to give under this head a sketch of the microscopic characters of those *primary tissues* of which their fabric is made up, and which, although they may be traced with more or less distinctness in the lower tribes of animals, attain their most complete development in this group.[1]

Although there would at first sight appear but little in common between the simple bodies of those humble Protozoa which constitute the lowest types of the animal series, and the complex fabric of man or other vertebrates, yet it appears from recent researches that in the latter, as in the former, the process of 'formation' is essentially carried on by the instrumentality of *protoplasmic substance*, universally diffused through it in such a manner as to bear a close resemblance to the pseudopodial network of the rhizopod; whilst the *tissues* produced by its agency lie, as it were, on the outside of this, bearing the same kind of relation to it as the foraminiferal shell does to the sarcodic substance which fills its cavities and extends itself over its surface. For, as was first pointed out by

[1] This sketch is intended, not for the professional student, but only for the amateur microscopist who wishes to gain some general idea of the elementary structure of his own body and of that of vertebrate animals generally. Those who wish to go more deeply into the inquiry are referred to the following as the most recent and elaborate treatises that have appeared in this country: The translation of Stricker's *Manual of Histology*, published by the New Sydenham Society; the *Handbook for the Physiological Laboratory*, by Drs. Burdon-Sanderson, Michael Foster, Brunton, and Klein; the translation of the 4th edition of Professor Frey's *Histology and Histo-Chemistry of Man*; the 'General Anatomy' of the 9th edition of *Quain's Anatomy*, 1882; and the *Atlas of Histology*, by Professor Klein and Mr. Noble Smith, 1880–1 (a new edition is now in course of publication).

Dr. Beale [1] the smallest living 'elementary part' of every organised fabric is composed of organic matter in two states: the protoplasmic (which he termed *germinal matter*), possessing the power of selecting pabulum from the blood, and of transforming this either into the material of its own extension or into some product which it elaborates; whilst the other, which may be termed *formed material*, may present every gradation of character from a mere inorganic deposit to a highly organised structure, but is in every case altogether incapable of self-increase. A very definite line of demarcation can be generally drawn between these two substances by the careful use of the staining process; but there are many instances in which there is the same gradation between the one and the other as we have formerly noticed between the 'endosarc' and the 'ectosarc' of the *Amœba*. Thus it is on the protoplasmic component that the existence of every form of animal organisation essentially depends: since it serves as the instrument by which the nutrient material furnished by the blood is converted into the several forms of tissue. Like the sarcodic substance of the rhizopods, it seems capable of indefinite extension; and it may divide and subdivide into independent portions, each of which may act as the instrument of formation of an 'elementary part.' Two principal forms of such elementary parts present themselves in the fabric of the higher animals, viz. *cells* and *fibres* (which are modified cells); and it will be desirable to give a brief notice of these before proceeding to describe those more complex tissues which are the products of a higher elaboration.

The *cells* of which a few animal tissues are essentially composed consist, in some cases, of the same parts as the typical cell of the plant, viz. a definite 'cell-wall,' inclosing 'cell-contents' and a 'nucleus,' which is the seat of its formative activity. It is of such cells, retaining more or less of their characteristic spheroidal shape, that every mass of *fat*, whether large or small, is chiefly made up. In a large number of cases the cell shows itself in a somewhat different form, the 'elementary part' being a corpuscle of protoplasm of which the exterior has undergone a slight consolidation, like that which constitutes the 'primordial utricle' of the vegetable cell or the 'ectosarc' of the *Amœba*, but in which there is no proper distinction between 'cell-wall' and 'cell-contents.' This condition, which is characteristically exhibited by the nearly globular *colourless corpuscles* of the blood, appears to be common to all cells in the incipient stage of their formation, and the progress of their development consists in the gradual *differentiation* of their parts, the 'cell-

[1] Professor Beale's views are most systematically expounded in his lectures *On the Structure of the Simple Tissues of the Human Body*, 1861; in his *How to Work with the Microscope*, 5th edition, 1880; and in the introductory portion of his new edition of Todd and Bowman's *Physiological Anatomy*, 1867. The principal results of the inquiries of German histologists on this point are well stated in a paper by Dr. Duffin on 'Protoplasm, and the part it plays in the Actions of Living Beings' in *Quart. Journ. Micros. Sci.* n.s. vol. iii. 1863, p. 251. The Author feels it necessary, however, to express his dissent from Professor Beale's views in one important particular, viz. his denial of 'vital' endowments to the 'formed material' of any of the tissues; since it seems to him illogical to designate contractile muscular fibre (for example) as 'dead,' merely because it has not the power of self-reparation.

wall' becoming distinctly separated from the 'cell-contents,' and these from the 'nucleus,' and the original protoplasm being very commonly replaced more or less completely by some special product (such as fat in the cells of adipose tissue, or hæmoglobin in the red corpuscles of the blood), in which cases the nucleus often disappears altogether. In the earlier stages of cell-development multiplication takes place with great activity by a duplicative subdivision that corresponds in all essential particulars with that of the plant-cell, as is well seen in cartilage, a section of which will often exhibit in one view the successive stages of the process.[1] Whether 'free' cell-multiplication ever takes place in the higher animals is at present uncertain.

A large part of the fabric of the higher animals is made up of *fibrous* tissues, which serve to bind together the other components, and which, when consolidated by calcareous deposit, constitute the substance of the skeleton. In these the relation of the 'germinal matter' and the 'formed material' presents itself under an aspect which seems at first sight very different from that just described. A careful examination, however, of those 'connective-tissue corpuscles' that have long been distinguished in the midst of the fibres of which these tissues are made up, shows that they are the equivalents of the corpuscles of 'germinal matter,' which in the previous instance came to constitute cell-nuclei, and that the fibres hold the same relation to them that the 'walls' and 'contents' of cells do to their germinal corpuscles. The transition from the one type to the other is well seen in fibro-cartilage, in which the so-called 'intercellular substance' is often as fibrous as tendon. The difference between the two types, in fact, seems essentially to consist in this, that, whilst the segments of 'germinal matter' which form the cell-nuclei in cartilage and in other cellular tissues are completely isolated from each other, each being completely surrounded by the product of its own elaborating action, those which form the 'connective-tissue corpuscles' are connected together by radiating prolongations that pass between the fibres, so as to form a continuous network closely resembling that formed by the pseudopodia of the rhizopod. Of this we have a most beautiful example in bone; for, whilst its solid substance may be considered as connective tissue solidified by calcareous deposit, the 'lacunæ' and 'canaliculi' which are excavated in it (fig. 692) give lodgment to a set of radiating corpuscles closely resembling those just described; and these are centres of 'germinal matter,' which appear to have an active share in the formation and subsequent nutrition of the osseous

[1] Great attention has lately been given by many able observers to the changes which take place in the *nucleus* before and during its cleavage. A full account of these is contained in the recently published 3rd edition of Professor Strassburger's *Zellbildung und Zelltheilung*, 1880. See also Dr. Klein's 'Observations on the Structure of Cells and Nuclei' in *Quart. Journ. Micros. Sci.* n.s. vol. xviii. 1878, p. 315, and vol. xix. 1879, pp. 125, 404; and chap. xliv. of his *Atlas of Histology*. The numerous essays of Flemming, in recent volumes of the *Archiv f. mikr. Anat*; Gruber, on the Nucleus of Protozoa, in vol. xl. of the *Zeitschr. f. Wiss. Zool.*; and Carnoy, in *La Cellule*, may be studied by those who desire to carry further the history of the cell.

texture. In dentine (or tooth-substance) we seem to have another form of the same thing, the walls of its 'tubuli' and the 'intertubular substance' being the 'formed material' that is produced from thread-like prolongations of 'germinal matter' issuing from its pulp, and continuing during the life of the tooth to occupy its tubes; just as in the *Foraminifera* we have seen a minutely tubular structure to be formed around the individual threads of sarcode which proceeded from the body of the contained animal. It may now be stated, indeed, with considerable confidence that the bodies of even the highest animals are everywhere penetrated by that protoplasmic substance of which those of the lowest and simplest are entirely composed; and that this substance, which forms a continuous network through almost every portion of the fabric, is the main instrument of the formation, nutrition, and reparation of the more specialised or differentiated tissues. As it is the purpose of this work, not to instruct the professional student in histology (or the science of the tissues), but to supply scientific information of general interest to the ordinary microscopist, no attempt will here be made to do more than describe the most important of those distinctive characters which the principal tissues present when subjected to microscopic examination; and as it is of no essential consequence what order is adopted, we may conveniently begin with the structure of the *skeleton*,[1] which gives support and protection to the softer parts of the fabric.

Bone.—The microscopic characters of osseous tissue may sometimes be seen in a very thin natural plate of bone, such as in that forming the scapula (shoulder-blade) of a mouse; but they are displayed more perfectly by artificial sections, the details of the arrangement being dependent upon the nature of the specimen selected and the direction in which the section is made. Thus when the shaft of a 'long' bone of a bird or mammal is cut across in the middle of its length, we find it to consist of a hollow cylinder of dense bone, surrounding a cavity which is occupied by an oily marrow; but if the section be made nearer its extremity we find the outside wall gradually becoming thinner, whilst the interior, instead of forming one large cavity, is divided into a vast number of small chambers, partially divided by a sort of 'lattice-work' of osseous fibres, but communicating with each other and with the cavity of the shaft, and filled like it with marrow. In the bones of reptiles and fishes, on the other hand, this 'cancellated' structure usually extends throughout the shaft, which is not so completely differentiated into solid bone and medullary cavity as it is in the higher Vertebrata. In the most developed kinds of 'flat' bones, again, such as those of the head, we find the two surfaces to be composed of dense plates of bone, with a 'cancellated' structure between them; whilst in the less perfect type presented to us in the lower Vertebrata, the whole thickness is usually more or less 'cancellated,' that is, divided up into minute medullary cavities. When we examine, under a low

[1] This term is used in its most general sense, as including not only the proper internal skeleton, but also the hard parts protecting the exterior of the body, which form the *dermal* skeleton.

ing power, a *longitudinal* section of a long bone, or a section bone *parallel* to its surface, we find it traversed by numerous termed *Haversian* after their discoverer Havers, which are in ion with the central cavity, and are filled like it with marrow. hafts of 'long' bones these canals usually run in the direction length, but are connected here and there by cross-branches; n the flat bones they form an irregular network. On applygher magnifying power to a thin *transverse* section of a long observe that each of the canals whose orifices present themn the field of view (fig. 691) is the centre of a rod of bony), usually more or less circular in its form, which is arranged it in concentric rings, resembling those of an exogenous These rings are marked out and divided by circles of little ots, which, when closely examined (2), are seen to be minute d cavities excavated in the solid substance of the bone, from flat sides of which rth a number of ly minute tubules, extending inwards, e direction of the of the system of nd the other outor in the direction rcumference; and nosculation of the (or *canaliculi*) of ferent rings with her a continuous nication is estabetween the cenversian canal and ermost part of the d that surrounds h doubtless ministhe nutrition of



FIG. 691.—Minute structure of bone as seen in transverse section: 1, a rod surrounding an Haversian canal, 3, showing the concentric arrangement of the lamellæ; 2, the same, with the lacunæ and canaliculi; 4, portion of the lamellæ parallel with the external surface.

ture. Blood-vessels are traceable into the Haversian canals, 'canaliculi' are far too minute to carry blood-corpuscles; they upied, however, in the living bone by threads of protoplasmic ce, which bring the segments of 'germinal matter' contained lacunæ into communication with the walls of the blood-

minute cavities or *lacunæ* (sometimes but erroneously termed orpuscles,' as if they were solid bodies), from which the canaroceed (fig. 692), are highly characteristic of the true osseous re, being never deficient in the minutest parts of the bones higher Vertebrata, although those of fishes are occasionally te of them. The dark appearance which they present in s of a dried bone is not due to opacity, but is simply an optical lependent (like the blackness of air-bubbles in liquids) upon persion of the rays by the highly refracting substance that ids them. The size and form of the lacunæ differ considerably

in the several classes of Vertebrata, and even in some instances in the orders, so that it is often possible to determine the tribe to which a bone belonged by the microscopic examination of even a minute fragment of it. The following are the average dimensions of the lacunæ, in characteristic examples drawn from the four principal classes, expressed in fractions of an inch:—

	Long Diameter	*Short Diameter*
Man .	1–1440 to 1–2400	1–4000 to 1–8000
Ostrich .	1–1333 „ 1–2250	1–5425 .. 1–9650
Turtle .	1–375 „ 1–1150	1–4500 .. 1–5840
Conger-eel .	1–550 „ 1–1135	1–4500 „ 1–8000

The lacunæ of *birds* are thus distinguished from those of *mammals* by their somewhat greater length and smaller breadth, but they differ still more in the remarkable tortuosity of their canaliculi, which wind backwards and forwards in a very irregular manner. There is an extraordinary increase in length in the lacunæ of *reptiles*, without a corresponding increase in breadth; and this is also seen in some *fishes*, though in general the lacunæ of the latter are remarkable for their angularity of form and the fewness of their radiations, as shown in fig. 693, which represents the lacunæ and canaliculi in the bony scale of the *Lepidosteus* ('bony pike' of the North American lakes and rivers), with which the bones of its internal skeleton perfectly agree in structure. The dimensions of the lacunæ in any bone do not bear any relation to the size of the animal

FIG. 692.—Lacunæ of osseous substance: *a*, central cavity; *b*, its ramifications.



FIG. 693.—Section of the bony scale of *Lepidosteus*: *a*, showing the regular distribution of the lacunæ and of the connecting canaliculi; *b*, small portion more highly magnified.

to which it belonged; thus there is little or no perceptible difference between their size in the enormous extinct Iguanodon and in the smallest lizard now inhabiting the earth. But they bear a close relation to the size of the blood-corpuscles in the several classes; and this relation is particularly obvious in the 'perennibranchiate' Batrachia, the extraordinarily large size of whose blood-corpuscles will be presently noticed.

	Long Diameter	*Short Diameter*
Proteus . .	1–570 to 1–980	1–885 to 1–1200
Siren . .	1–290 „ 1–480	1–540 „ 1–975
Menopoma .	1–450 „ 1–700	1–1300 „ 1–2100
Lepidosiren .	1–375 „ 1–494	1–980 „ 1–2200
Pterodactyle .	1–445 „ 1–1185	1–4000 „ 1–5225[1]

In preparing sections of bone it is important to avoid the penetration of the Canada balsam into the interior of the lacunæ and canaliculi, since when these are filled by it they become almost invisible. Hence it is preferable not to employ this cement at all, except it may be in the first instance, but to rub down the section beneath the finger, guarding its surface with a slice of cork or a slip of gutta-percha, and to give it such a polish that it may be seen to advantage even when mounted dry. As the polishing, however, occupies much time, the benefit which is derived from covering the surfaces of the specimen with Canada balsam may be obtained without the injury resulting from the penetration of the balsam into its interior, by adopting the following method. A quantity of balsam proportioned to the size of the specimen is to be spread upon a glass slip, and to be rendered stiffer by boiling, until it becomes nearly solid when cold; the same is to be done to the thin glass cover; next, the specimen being placed on the balsamed surface of the slide, and being overlaid by the balsamed cover, such a degree of warmth is to be applied as will suffice to liquefy the balsam without causing it to flow freely, and the glass cover is then to be quickly pressed down, and the slide to be rapidly cooled, so as to give as little time as possible for the penetration of the liquefied balsam into the lacunar system. The same method may be employed in making sections of teeth.[2] The study of the *ossein* or organic basis of bone should be pursued by macerating a fresh bone in dilute nitro-hydrochloric acid, then steeping it for some time in pure water, and tearing thin shreds from the residual substance, which will be found to consist of an imperfectly fibrillated material, allied in its essential constitution to the 'white fibrous' tissue.

Teeth.—The intimate structure of the teeth in the several classes and orders of Vertebrata presents differences which are no less remarkable than those of their external form, arrangement, and succession. It will obviously be impossible here to do more than sketch some of the most important of these varieties. The principal part of the substance of all teeth is made up of a solid tissue that has been appropriately termed *dentine*. In the shark tribe, as in many other fishes, the general structure of this dentine is extremely analogous to that of bone, the tooth being traversed by numerous canals, which are continuous with the Haversian canals of the subjacent bone, and receive blood-vessels from them (fig. 694), and each of these canals

[1] See Professor J. Quekett's memoir on this subject in the *Trans. Micros. Soc.* ser. i. vol. ii.; and his more ample illustration of it in the *Illustrated Catalogue of the Histological Collection in the Museum of the Royal College of Surgeons*, vol. ii.

[2] Some useful hints on the mode of making these preparations will be found in the *Quart. Journ. Micros. Sci.* vol. vii. 1859, p. 258.

being surrounded by a system of tubuli (fig. 695), which radiate into the surrounding solid substance. These tubuli, however, do not enter lacunæ, nor is there any concentric annular arrangement around the medullary canals; but each system of tubuli is continued onwards through its own division of the tooth, the individual tubes sometimes giving off lateral branches, whilst in other instances their trunks bifurcate. This arrangement is peculiarly well displayed, when sections of teeth constructed upon this type are viewed as opaque objects (fig. 696). In the teeth of the higher Vertebrata, however, we usually find the centre excavated into a single cavity (fig. 697), and the remainder destitute of vascular canals; but there are intermediate cases (as in the teeth of the great fossil sloths) in which the inner portion of the dentine is traversed by prolongations of this cavity, conveying blood-vessels, which do not pass into the exterior



FIG. 694.—Perpendicular section of tooth of *Lamna*, moderately enlarged, showing network of medullary canals.



FIG. 695.—Transverse section of portion of tooth of *Pristis*, more highly magnified, showing orifices of medullary canals, with systems of radiating and inosculating tubuli.

layers. The tubuli of the 'non-vascular' dentine, which exists by itself in the teeth of nearly all mammalia, and which in the elephant is known as 'ivory,' all radiate from the central cavity, and pass towards the surface of the tooth in a nearly parallel course. Their diameter at their largest part averages $\frac{1}{1\,0\,0\,0\,0}$th of an inch; their smallest branches are immeasurably fine. The tubuli in their course present greater and lesser undulations; the former are few in number, but the latter are numerous; and as they occur at the same part of the course of several contiguous tubes they give rise to the appearance of lines concentric with the centre of radiation. These 'secondary curvatures' probably indicate in dentine, as in the crab's shell, successive stages of calcification. The tubuli are occupied, during the life of the tooth, by delicate threads of protoplasmic substance, extending into them from the central pulp.

Two other substances, one of them harder and the other softer

than dentine, are frequently found associated with it; the former is termed *enamel*, and the latter *cementum* or *crusta petrosa*. The *enamel* is composed of long prisms, closely resembling those of the 'prismatic' shell-substance formerly described, but on a far more minute scale, the diameter of the prisms not being more in man than $\frac{1}{5000}$th of an inch. The length of the prisms corresponds with the thickness of the layer of enamel; and the two surfaces of this layer present the ends of the prisms, the form of which usually approaches the hexagonal. The course of the enamel prisms is more or less wavy, and they are marked by numerous transverse striæ, resembling those of the prismatic shell-substance, and probably originating in the same cause—the coalescence of a series of shorter prisms to form the lengthened prism. In man and in carnivorous animals the enamel covers the crown of the tooth only, with a simple cap or superficial layer of tolerably uniform thickness (fig. 697, *a*), which follows the surface of the dentine in all its inequalities; and its component prisms are directed at right angles to that surface, their inner extremities resting in slight but regular depressions on the exterior of the dentine. In the teeth of many herbivorous animals, however, the enamel forms (with the cementum) a series of vertical plates which dip down into the substance of the dentine, and present their edges alternately with it at the grinding surface of the tooth; and there is in such teeth no continuous layer of enamel over the crown. This arrangement provides by the unequal *wear* of these three substances (of which the enamel is the hardest, and the cementum the softest) for the constant maintenance of a rough surface, adapted to triturate the tough vegetable substances on which these animals feed. Though the enamel is not always present, it has been shown by Mr. Charles Tomes that the germ from which it is formed always appears



FIG. 696.—Transverse section of tooth of *Myliobates* (eagle ray), viewed as an opaque object.



FIG. 697.—Vertical section of human molar tooth: *a*, enamel; *b*, cementum or crusta petrosa; *c*, dentine or ivory; *d*, osseous excrescence arising from hypertrophy of cementum; *e*, pulp-cavity; *f*, osseous lacunæ at outer part of dentine.

in the embryonic tooth ; and he has further shown that it is much more frequently present than used to be supposed. The *cementum*, or *crusta petrosa*, has the characters of true bone, possessing its distinctive stellate lacunæ and radiating canaliculi. Where it exists in small amount we do not find it traversed by medullary canals : but, like dentine, it is occasionally furnished with them, and thus resembles bone in every particular. These medullary canals enter its substance from the exterior of the tooth, and consequently pass towards those which radiate from the central cavity in the direction of the surface of the dentine, where this possesses a similar vascularity, as was remarkably the case in the teeth of the great extinct *Megatherium*. In the human tooth, however, the cementum has no such vascularity, but forms a thin layer (fig. 697, *b*), which envelopes the root of the tooth commencing near the termination of the cap of enamel. In the teeth of many herbivorous mammals it dips down with the enamel to form the vertical plates of the interior of the tooth ; and in the teeth of the Edentata, as well as of many reptiles and fishes, it forms a thick continuous envelope over the whole surface, until worn away at the crown.[1]

Dermal Skeleton.—The skin of fishes, of a few amphibians, of most reptiles, and of few mammals, is strengthened by plates of a horny, cartilaginous, bony, or even enamel-like texture, which are sometimes fitted together at their edges, so as to form a continuous box-like envelope ; whilst more commonly they are so arranged as partially to overlie one another, like the tiles on a roof ; and it is in this latter case that they are usually known as *scales*. Although we are accustomed to associate in our minds the 'scales' of fishes with those of reptiles, yet essentially different structures have been included under this name, those of the former and of many of the latter being developed in the *substance* of the true skin (with a layer of which, in addition to the epidermis, they are always covered), and bearing a resemblance to cartilage and bone in their texture and composition ; whilst others, such as the scales of snakes or the tortoise-shell, are formed upon the *surface* of the true skin, and are to be considered as analogous to nails, hoofs, &c. and other 'epidermic appendages.' In nearly all the existing fishes the scales are flexible, being but little consolidated by calcareous deposit ; and in some species they are so thin and transparent that, as they do not project obliquely from the surface of the skin, they can only be detected by raising the superficial layer of the skin and searching



FIG. 698.—Portion of skin of sole, viewed as an opaque object.

[1] The student is recommended to consult Mr. C. S. Tomes's *Manual of Dental Anatomy, Human and Comparative* (3rd edition, London, 1889). If he desires to go further, the first part of Baume's *Odontologische Forschungen* (Leipzig, 1892) should be consulted.

beneath it, or by tearing off the entire thickness of the skin and looking for them near its under surface. This is the case, for example, with the common *eel*, and with the *viviparous blenny*; of either of which fish the skin is a very interesting object when dried and mounted in Canada balsam, the scales being seen imbedded in its substance, whilst its outer surface is studded with pigment-cells. Generally speaking, however, the posterior extremity of each scale projects obliquely from the general surface, carrying before it the thin membrane that incloses it, which is studded with pigment-cells; and a portion of the skin of almost any fish, but especially of such as have scales of the *ctenoid* kind (that is, furnished at their posterior extremities with comb-like teeth, fig. 699), when dried with its scales *in situ*, is a very beautiful opaque object for the low powers of the microscope (fig. 698), especially with the binocular arrangement. Care must be taken, however, that the light is made to glance upon it in the most advantageous manner, since the brilliance with which it is reflected from the comb-like projections entirely depends upon the angle at which it falls upon them. The only appearance of structure exhibited by the thin flat scale of the eel, when examined microscopically, is the presence of a layer of isolated spheroidal transparent bodies, imbedded in a plate of like transparence; these, from the researches of Professor W. C. Williamson[1] upon other scales, appear not to be cells (as they might readily be supposed to be), but concretions of carbonate of lime. When the scale of the eel is examined by polarised light its surface exhibits a beautiful St. Andrew's cross: and if a plate of selenite be placed behind it, and the analysing prism be made to revolve, a remarkable play of colours is presented.

FIG. 699.—Scale of sole, viewed as a transparent object.

In studying the structure of the more highly developed scales, we may take as an illustration that of the *carp*, in which two very distinct layers can be made out by a vertical section, with a third but incomplete layer interposed between them. The outer layer is composed of several concentric laminæ of a structureless transparent substance like that of cartilage; the outermost of these laminæ is the smallest, and the size of the plates increases progressively from without inwards, so that their margins appear on the surface as a series of concentric lines: and their surfaces are thrown into ridges and furrows, which commonly have a radiating direction. The inner layer is composed of numerous laminæ of a fibrous

[1] See his elaborate memoirs, 'On the Microscopic Structure of the Scales and Dermal Teeth of some Ganoid and Placoid Fish,' in *Phil. Trans.* 1849; and 'Investigations into the Structure and Development of the Scales and Bones of Fishes,' in *Phil. Trans.* 1851.

structure, the fibres of each lamina being inclined at various angles to those of the lamina above and below it. Between these two layers is interposed a stratum of calcareous concretions, resembling those of the scale of the eel; these are sometimes globular or spheroidal, but more commonly 'lenticular,' that is, having the form of a double convex lens. The scales which resemble those of the carp in having a form more or less circular, and in being destitute of comb-like prolongations, are called *cycloid*; and such are the characters of those of the salmon, herring, roach, &c. The structure of the *ctenoid* scales (fig. 699), which we find in the sole, perch, pike, &c. does not differ essentially from that of the cycloid, save as to the projection of the comb-like teeth from the posterior margin; and it does not appear that the strongly marked division which Professor Agassiz has attempted to establish between the 'cycloid' and the 'ctenoid' orders of fishes, on the basis of this difference, is in harmony with their general organisation. Scales of every kind may become consolidated to a considerable extent by the calcification of their soft substance; but still they never present any approach to the true bony structure, such as is shown in the two orders to be next adverted to.

In the *ganoid* scales, on the other hand, the whole substance of the scale is composed of a material which is essentially bony in its nature, its intimate structure being always comparable to that of one or other of the varieties which present themselves in the bones of the vertebrate skeleton, and being very frequently identical with that of the bones of the same fish, as is the case with the *Lepidosteus* (fig. 693), one of the few existing representatives of this order, which, in former ages of the earth's history, comprehended a large number of important families. Their name (from γάνος, splendour) is bestowed on account of the smoothness, hardness, and high polish of the outer surface of the scales, which is due to the presence of a peculiar layer that has been likened to the enamel of teeth. The scales of this order are for the most part angular in their form, and are arranged in regular rows, the posterior edges of each slightly overlapping the anterior ones of the next, so as to form a very complete defensive armour to the body. The scales of the *placoid* type, which characterises the existing sharks and rays, with their fossil allies, are irregular in their shape, and very commonly do not come into mutual contact, but are separately imbedded in the skin, projecting from its surface under various forms. In the rays each scale usually consists of a flattened plate of a rounded shape, with a hard spine projecting from its centre; in the sharks (to which tribe belongs the 'dog-fish' of our own coast) the scales have more of the shape of teeth. This resemblance is not confined to external form; for their intimate structure strongly resembles that of dentine, their dense substance being traversed by tubuli, which extend from their centre to their circumference in minute ramifications, without any trace of osseous lacunæ. These tooth-like scales are often so small as to be invisible to the naked eye; but they are well seen by drying a piece of the skin to which they are attached, and mounting it in Canada balsam; and they are most brilliantly shown by the assistance of polarised light.

A like structure is found to exist in the 'spiny rays' of the dorsal fin, which, also, are parts of the dermal skeleton; and these rays usually have a central cavity filled with medulla, from which the tubuli radiate towards the circumference. This structure is very well seen in thin sections of the fossil 'spiny rays,' which, with the teeth and scales, are often the sole relics of the vast multitudes of sharks that must have swarmed in the ancient seas, their cartilaginous internal skeletons having entirely decayed away. In making sections of bony scales, spiny rays, &c. the method must be followed which has been already detailed under the head of bone.[1]

The *scales* of reptiles, the *feathers* of birds, and the *hairs*, *hoofs*, *nails*, *claws*, and *horns* (when not bony) of mammals are all *epidermic* appendages; that is, they are produced upon the surface, not within the substance of the true skin, and are allied in structure to the epidermis, being essentially composed of aggregations of cells filled with horny matter and frequently much altered in form. This structure may generally be made out in horns, nails, &c. with little difficulty by treating thin sections of them with a dilute solution of soda, which after a short time causes the cells that had been flattened into scales to resume their globular form. The most interesting modifications of this structure are presented to us in hairs and in feathers; which forms of clothing are very similar to each other in their essential nature, and are developed in the same manner—viz. by an increased production of epidermic cells at the bottom of a flask-shaped follicle, which is formed in the substance of the true skin, and which is supplied with abundance of blood by a special distribution of vessels to its walls. When a hair is pulled out 'by its root,' its base exhibits a bulbous enlargement, of which the exterior is tolerably firm, whilst its interior is occupied by a softer substance, which is known as the 'pulp'; and it is to the continual augmentation of this pulp in the deeper part of the follicle, and to its conversion into the peculiar substance of the hair when it has been pushed upwards to its narrow neck, that the growth of the hair is due. The same is true of feathers, the stems of which are but hairs on a larger scale; for the 'quill' is the part contained within the follicle answering to the 'bulb' of the hair; and whilst the outer part of this is converted into the peculiarly solid horny substance forming the 'barrel' of the quill, its interior is occupied, during the whole period of the growth of the feather, with the soft pulp, only the shrivelled remains of which, however, are found within it after the quill has ceased to grow.

Although the *hairs* of different mammals differ greatly in the appearances they present, we may generally distinguish in them two elementary parts—viz. a *cortical* or investing substance, of a dense horny texture, and a *medullary* or pith-like substance, usually of a much softer texture, occupying the interior. The former can sometimes be distinctly made out to consist of flattened scales arranged in an imbricated manner, as in some of the hairs of the

[1] For further information regarding the scales of fishes, see the papers by O. Hertwig in vol. viii. of the *Jenaische Zeitschrift*; and vols. ii. and v. of the *Morpholog. Jahrbuch.*

sable (fig. 700); whilst in the same hairs, the medullary substance is composed of large spheroidal cells. In the musk-deer, on the other hand, the cortical substance is nearly undistinguishable, and almost the entire hair seems made up of thin walled polygonal cells (fig. 701). The hair of the reindeer, though much larger, has a very

FIG. 700.—Hair of sable, showing large rounded cells in its interior, covered by imbricated scales or flattened cells.



FIG. 701.—Hair of musk-deer, consisting almost entirely of polygonal cells.

similar structure; and its cells, except near the root, are occupied with hair alone, so as to seem black by transmitted light, except when penetrated by the fluid in which they are mounted. In the hair of the mouse, squirrel, and other small rodents (fig. 702, A. B), the cortical substance forms a tube, which we see crossed at intervals by partitions that are sometimes complete, sometimes only partial: these are the walls of the single or double line of cells, of which the medullary substance is made up. The hairs of the bat tribe are commonly distinguished by the projections on their surface, which are formed by extensions of the component scales of the cortical substance: these are particularly well seen in the hairs of one of the Indian species, which has a set of whorls of long narrow leaflets (so to speak) arranged at regular intervals on its stem (C). In the hair of the peccary (fig. 703) the cortical envelope sends inwards a set of radial prolongations, the interspaces of which are occupied by the polygonal cells of the medullary substance; and this, on a larger scale, is the structure of the 'quills' of the porcupine, the radiating partitions of which, when seen through the more transparent parts of the cortical sheath, give to the surface of the latter a fluted appearance. The hair of the ornitho-



FIG. 702.—A, small hair of squirrel; B, large hair of squirrel; C, hair of Indian bat.

rhynchus is a very curious object; for whilst the lower part of it resembles the fine hair of the mouse or squirrel, this thins away and then dilates again into a very thick fibre, having a central portion composed of polygonal cells, inclosed in a flattened sheath of a brown fibrous substance.



FIG. 703.—Transverse section of hair of peccary.

The structure of the *human* hair is in certain respects peculiar. When its outer surface is examined, it is seen to be traversed by irregular lines (fig. 704, A), which are most strongly marked in fœtal hairs; and these are the indications of the imbricated arrangement of the flattened cells or scales which form the cuticular layer. This layer, as is shown by transverse sections (C, D), is a very thin and transparent cylinder; and it incloses the peculiar fibrous substance that constitutes the principal part of the shaft of the hair. The constituent fibres of the substance, which are marked out by the delicate striæ that may be traced in longitudinal sections of the hair (B), may be separated from each other by crushing the hair, especially after it has been macerated for some time in sulphuric acid; and each of them, when completely isolated from its fellows, is found to be a long spindle-shaped cell. In the axis of this fibrous cylinder there is very commonly a band which is formed of spheroidal



FIG. 704.—Structure of human hair: A, external surface of the shaft, showing the transverse striæ and jagged boundary caused by the imbrications of the cuticular layer; B, longitudinal section of the shaft, showing the fibrous character of the cortical substance, and the arrangement of the pigmentary matter; C, transverse section, showing the distinction between the cuticular envelope, the cylinder of cortical substance, and the medullary centre; D, another transverse section, showing deficiency of the central cellular substance.

cells; but this 'medullary' substance is usually deficient in the fine hairs scattered over the general surface of the body, and is not always present in those of the head. The hue of the hair is due partly to the presence of pigmentary granules, either collected into patches or diffused through its substance, but partly also to the existence of a multitude of minute air-spaces, which cause it to

appear dark by transmitted and white by reflected light. The cells of the medullary axis in particular are very commonly found to contain air, giving it the black appearance shown at C. The difference between the blackness of pigment and that of air-spaces may be readily determined by attending to the characters of the latter as already laid down, and by watching the effects of the penetration of oil of turpentine or other liquids, which do not alter the appearance of pigment spots, but obliterate all the markings produced by air-spaces, these returning again as the hair dries. In mounting hairs as microscopic preparations they should in the first instance be cleansed of all their fatty matter by maceration in ether, and they may then be put up either in weak spirit or in Canada balsam, as may be thought preferable, the former menstruum being well adapted to display the characters of the finer and more transparent hairs, while the latter allow the light to penetrate more readily through the coarser and more opaque. Tranverse sections of hairs are best made by gluing or gumming several together and then putting them into the microtome ; those of human hair may be easily obtained, however, by shaving a second time, very closely, a part of the surface over which the razor has already passed more lightly, and by picking out from the lather, and carefully washing, the sections thus taken off.[1]

The stems of *feathers* exhibit the same kind of structure as hairs, their cortical portion being the horny sheath that envelopes the shaft, and their medullary portion being the pith-like substance which that sheath includes. In small feathers this may usually be made very plain by mounting them in Canada balsam ; in large feathers, however, the texture is sometimes so altered by the drying up of the pith (the cells of which are always found to be occupied by air alone) that the cellular structure cannot be demonstrated save by boiling thin slices in a dilute solution of potass, and not always even then. In small feathers, especially such as have a downy character, the cellular structure is very distinctly seen in the lateral *barbs*, which are sometimes found to be composed of single files of pear-shaped cells, laid end to end ; but in larger feathers it is usually necessary to increase the transparence of the barbs, especially when these are thick and but little pervious to light, either by soaking them in turpentine, mounting them in Canada balsam, or boiling them in a weak solution of potass. In feathers which are destined to strike the air with great force in the act of flight, we find each barb fringed on either side with slender flattened filaments or 'barbules' ; the barbules of the distal side of each barb are furnished on their attached half with curved hooks, whilst those of the proximal side have thick turned-up edges in their median portion ; as the two sets of barbules that spring from two adjacent barbs cross each other at an angle, and as each hooked barbule of one locks into the thickened edge of several barbules of the other, the barbs are connected very firmly, in a mode very similar to that

[1] On the minute structure of hair, consult Grimm's *Atlas der menschlichen und tierischen Haare* (Lahr, 1884, 4to, with a preface by W. Waldeyer).

in which the anterior and posterior wings of certain hymenopterous insects are locked together. Feathers or portions of feathers of birds distinguished by the splendour of their plumage are very good objects for low magnifying powers when illuminated on an opaque ground; but care must be taken that the light falls upon them at the angle necessary to produce their most brilliant reflection into the axis of the microscope; since feathers which exhibit the most splendid metallic lustre to an observer at one point may seem very dull to the eye of another in a different position. The small feathers of humming-birds, portions of the feathers of the peacock, and others of a like kind, are well worthy of examination; and the scientific microscopist, who is but little attracted by mere gorgeousness, may well apply himself to the discovery of the peculiar structure which imparts to these objects their most remarkable character.[1]

Sections of *horns*, *hoofs*, *claws*, and other like modifications of epidermic structure, which can be easily made by the microtome, the substance to be cut having been softened, if necessary, by soaking in warm water—do not in general afford any very interesting features when viewed in the ordinary mode; but there are no objects on which polarised light produces more remarkable effects, or which display a more beautiful variety of colours when a plate of selenite is placed behind them and the analysing prism is made to rotate. A curious modification of the ordinary structure of horn is presented in the appendage borne by the rhinoceros upon its snout, which in many points resembles a bundle of hairs, its substance being arranged in minute cylinders around a number of separate centres, which have probably been formed by independent papillæ (fig. 705). When transverse sections of these cylinders are viewed by polarised light, each of them is seen to be marked by a cross, somewhat resembling that of starch-grains; and the light and shadow of this cross are replaced by contrasted colours when the selenite plate is interposed. The substance commonly but erroneously termed *whalebone*, which is formed from the surface of the membrane that lines the mouth of the whale, and has no relation to its true bony skeleton, is almost identical in structure with rhinoceros-horn, and is similarly affected by polarised light. The central portion of each of its component threads, like the medullary



FIG. 705.—Transverse section of horn of rhinoceros viewed by polarised light.

[1] See R. S. Wray, 'On the Structure of the Barbs, Barbules, and Barbicels of a typical Pennaceous Feather,' in the *Ibis* for 1887, p. 420.

substance of hairs, contains cells that have been so little altered as to be easily recognised; and the outer or cortical portion also may be shown to have a like structure by macerating it in a solution of potass and then in water. Sections of any of the horny tissues are best mounted in Canada balsam.

Blood.—Carrying our microscopic survey, now, to the elementary parts of which those softer tissues are made up that are subservient to the active life of the body rather than to its merely mechanical requirements, we shall in the first place notice the isolated floating cells contained in the blood which are known as blood-corpuscles. These are of two kinds: the 'red' and the 'white' or 'colourless.' The *red* present, in every instance, the form of a flattened disc, which is circular in man and most mammalia (fig. 707), but is oval in birds, reptiles (fig. 706), and fishes, as also in a few mammals (all belonging to the camel tribe). In the one form, as in the other, these corpuscles seem to be flattened cells, the walls of which, however, are not distinctly differentiated from the ground substance they contain, as appears from the changes of form which they spontaneously undergo when kept by means of a 'warm stage'[1] at a temperature of about 100°, and from the effects of pressure in breaking them up. The red corpuscles in the blood of oviparous Vertebrata are distinguished by the presence of a central spot or *nucleus*; this is most distinctly brought into view by treating the blood-discs with acetic acid, which causes the nucleus



FIG. 706.—Red corpuscles of frog's blood: *aa*, their flattened face; *b*, particle turned nearly edgeways; *c*, colourless corpuscle; *d*, red corpuscles altered by diluted acetic acid.



FIG. 707.—Red corpuscles of human blood: represented at *a*, as they are seen when rather within the focus of the microscope; and at *b*, as they appear when precisely in the focus.

[1] A very simple mode of applying continued warmth to an object under observation is to lay the slide on a thin plate of brass or tin, about three inches longer than the breadth of the stage, and about two inches broad; which must be perforated with a hole about one-fourth inch in diameter, at the distance of half the breadth of the stage from one end of it. When this plate is laid on the stage, and its hole is brought into the optic axis, so as to allow the light reflected upwards from the mirror to pass to the slide laid upon it, the plate will project about three inches on one side of the stage—preferably the right. By placing a small lamp beneath this projection and keeping the finger of the left hand on the part of the plate close to the object (so as to feel the degree of warmth imparted to it), the heat given by the lamp may be regulated by varying its position. For more exact and continuous regulation of the temperature the methods and apparatus described in this volume at pp. 289-295 should be studied.

to shrink and become more opaque, whilst rendering the remaining portion extremely transparent (fig. 706, *d*). By examining unaltered red corpuscles of the frog or newt under a sufficiently high magnifying power the nucleus is seen to be traversed by a network of filaments, which extends from it throughout the ground substance of the corpuscle, constituting an intracellular reticulation. The red corpuscles of the blood of mammals, however, possess no distinguishable nucleus, the dark spot which is seen in their centre (fig. 707, *b*) being merely an effect of refraction, consequent upon the double concave form of the disc. When these corpuscles are treated with water, so that their form becomes first flat and then double convex, the dark spot disappears; whilst, on the other hand, it is made more evident when the concavity is increased by the partial shrinkage of the corpuscles, which may be brought about by treating them with fluids of greater density than their own substance. When floating in a sufficiently thick stratum of blood drawn from the body, and placed under a cover-glass, the red corpuscles show a marked tendency to approach one another, adhering by their discoidal surfaces so as to present the aspect of a pile of coins; or, if the stratum be too thin to admit of this, partially overlapping, or simply adhering by their edges, which then become polygonal instead of circular. The size of the red corpuscles is not altogether uniform in the same blood; thus it varies in that of man from about the $\frac{1}{4000}$th to the $\frac{1}{2800}$th of an inch. But we generally find that there is an average size, which is pretty constantly maintained among the different individuals of the same species; that of man may be stated at about $\frac{1}{3200}$th of an inch. The following table[1] exhibits

MAMMALS			
Man	1–3200	Camel	1–3254, 1–5921
Dog	1–3542	Llama	1–3361, 1–6294
Whale	1–3099	Javan chevrotain	1–12325
Elephant	1–2745	Caucasian goat	1–7045
Mouse	1–3814	Two-toed sloth	1–2865
BIRDS			
Golden eagle	1–1812, 1–3832	Ostrich	1–1649, 1–3000
Owl	1–1830, 1–3400	Cassowary	1–1455, 1–2800
Crow	1–1961, 1–4000	Heron	1–1913, 1–3491
Blue-tit	1–2313, 1–4128	Fowl	1–2102, 1–3466
Parrot	1–1898, 1–4000	Gull	1–2097, 1–4000
REPTILES AND BATRACHIA			
Turtle	1–1231, 1–1882	Frog	1–1108, 1–1821
Crocodile	1–1231, 1–2286	Water-newt	1–8014, 1–1246
Green lizard	1–1555, 1–2743	Siren	1–420, 1–760
Slow-worm	1–1178, 1–2666	Proteus	1–400, 1–727
Viper	1–1274, 1–1800	Amphiuma	1–345, 1–561
FISHES			
Perch	1–2099, 1–2824	Pike	1–2000, 1–3555
Carp	1–2142, 1–3429	Eel	1–1745, 1–2842
Gold-fish	1–1777, 1–2824	Gymnotus	1–1745, 1–2599

[1] These measurements are chiefly selected from those given by Mr. Gulliver in his edition of Hewson's *Works*, p. 236 *et seq.*

the average dimensions of some of the most interesting examples of the red corpuscles in the four classes of vertebrated animals, expressed in fractions of an inch. Where two measurements are given they are the long and the short diameters of the same corpuscles. (See also fig. 708.) Thus it appears that the *smallest* red corpuscles known are those of the Javan chevrotain (*Tragulus javanicus*), whilst the *largest* are those of that curious group of Batrachia (frog tribe) which retain the gills through the whole of life; one of the oval blood-discs of the *Proteus*, being more than thirty times as long and seventeen times as broad as those of the musk-deer, would cover no fewer than 510 of them. Those of the *Amphiuma* are still larger.[1] According to the estimate of Vierordt, a cubic inch of human blood contains upwards of *eighty millions* of red corpuscles and nearly a *quarter of a million* of the colourless.



FIG. 708.—Comparative sizes of red blood-corpuscles: 1, man; 2, elephant; 3, musk-deer; 4, dromedary; 5, ostrich; 6, pigeon; 7, humming-bird; 8, crocodile; 9, python; 10, proteus; 11, perch; 12, pike; 13, shark.

The *white* or 'colourless' corpuscles are more readily distinguished in the blood of batrachians than in that of man, being in the former case of much smaller size, as well as having a circular outline (fig. 706, *c*); whilst in the latter their size and contour are so nearly the same that, as the red corpuscles themselves, when seen in a single layer, have but a very pale hue, the deficiency of colour does not sensibly mark their difference of nature. The proportion of *white* to *red* corpuscles being scarcely ever greater (in a healthy man) than 1 to 250, and often as low as from one-half to one-quarter of that ratio, there are seldom many of them to be seen in the field at once; and these may be recognised rather by their isolation than their colour, especially if the glass cover be moved a little on the slide, so as to cause the red corpuscles to become aggregated into rows and irregular masses. It is remarkable that, notwithstanding the great variations in the sizes

[1] A very interesting account of the 'Structure of the Red Corpuscles of the *Amphiuma tridactylum*' has been given by Dr. H. D. Schmidt, of New Orleans, in the *Journ. Roy. Microsc. Soc.* vol. i. 1879, pp. 57, 97.

of the red corpuscles in different species of vertebrated animals, the size of the white is extremely constant throughout, their diameter being seldom much greater or less than $\frac{1}{3000}$th of an inch in the warm-blooded classes and $\frac{1}{1500}$th in reptiles. Their ordinary form is globular, but their aspect is subject to considerable variations, which seem to depend in great part upon their phase of development. Thus, in their early state, in which they seem to be identical with the corpuscles found floating in *chyle* and *lymph*, they seem to be nearly homogeneous particles of protoplasmic substance, but in their more advanced condition, according to Dr. Klein, their substance consists of a reticulation of very fine contractile protoplasmic fibres, termed the 'intracellular network,' in the meshes of which a hyaline interstitial material is included, and which is continuous with a similar network that can be discerned in the substance of the single or double nucleus when this comes into view after the withdrawal of these corpuscles from the body. In their living state, however, whilst circulating in the vessels, the white corpuscles, although clearly distinguishable in the slow-moving stratum in contact with their walls (the red corpuscles rushing rapidly through the centre of the tube), do not usually show a distinct nucleus. This may be readily brought into view by treating the corpuscles with water, which causes them to swell up, become granular, and at last disintegrate, with emission of granules which may have been previously seen in active molecular movement within the corpuscle. When the white corpuscles in a drop of freshly drawn blood are carefully watched for a short time, they may be observed to undergo changes of form, and even to move from place to place, after the manner of *Amœbæ*. When thus moving they engulf particles which lie in their course—such as granules of vermilion that have been injected into the blood-vessels of the living animal—and afterwards eject these in the like fashion.[1] Such movements will



FIG. 709.—Altered white corpuscle of blood an hour after having been drawn from the finger.

[1] Metschnikoff has made the highly interesting and important observation that the immunity of certain animals to certain diseases appears to be due to the power that the white corpuscles possess of acting as 'phagocytes,' or eating the germs of the disease. Metschnikoff found that the virulent rods of the *Bacillus* of anthrax 'when introduced by inoculation into an animal liable to take the fever, such as a rodent, were absorbed by the blood-cells only in exceptional instances. They were readily absorbed by the blood-cells of animals not liable to the disease, as frogs and lizards, when the temperature was not artificially raised (fig. 710), and then disappeared inside the cells. . . . From all these data we must assume with Metschnikoff that the *Bacillus* is harmless because it is absorbed and destroyed by the blood-cells, and injurious because this does not happen; or at least that it becomes harmless if the destruction by the blood-cells takes place more rapidly, and to a greater extent than the growth and multiplication of the *Bacillus*, the converse being also true' (see A. de Bary, *On Bacteria*, English edition, p. 186).

continue for some time in the colourless corpuscles of cold-blooded animals, but still longer if they are kept in a temperature of about 75°. The movement will speedily come to an end, however, in the white corpuscles of man or other warm-blooded animals, unless the slide is kept on a warm stage at the temperature of about 100° F. A remarkable example of an extreme change of form in a white corpuscle of human blood is represented in fig. 709. Similar changes have been observed also in the corpuscles floating in the circulating fluid of the higher invertebrata, as the crab, which resemble the 'white' corpuscles of vertebrated blood, rather than its 'red' corpuscles—these last, in fact, being altogether peculiar to the circulating fluid of vertebrated animals.



FIG. 710.—*a*, blood-cell of a frog in the act of engulfing a rod of *Bacillus anthracis*, observed in the living state in a drop of aqueous humour; *b*, the same a few minutes later. (After Metschnikoff; highly magnified.)

In examining the blood microscopically it is, of course, important to obtain as thin a stratum of it as possible, so that the corpuscles may not overlie one another. This is best accomplished by selecting a piece of thin glass of perfect flatness, and then, having received a small drop of blood upon a glass slide, to lay the thin glass cover *not upon* this, but with its edge just touching the edge of the drop; for the blood will then be drawn in by capillary attraction, so as to spread in a uniformly thin layer between the two glasses. Such thin films may be preserved in the liquid state by applying a cover glass and cementing it with gold-size before evaporation has taken place; but it is preferable first to expose the drop to the vapour of osmic acid, and then to apply a drop of a weak solution of acetate of potass; after which a cover glass may be put on, and secured with gold-size in the usual way. It is far simpler, however, to allow such films to dry without any cover, and then merely to cover them for protection; and in this condition the general characters of the corpuscles can be very well made out, notwithstanding that they have in some degree been shrivelled by the desiccation they have undergone. And this method is particularly serviceable as affording a fair means of comparison, when the assistance of the microscopist is sought in determining, for medico-legal purposes, the source of suspicious blood-stains, the average dimensions of the dried blood-corpuscle of the several domestic animals being sufficiently different from each other, and from those of man, to allow the nature of any specimen to be pronounced upon with a high degree of probability.

Simple Fibrous Tissues.—A very beautiful example of a tissue of this kind is furnished by the membrane of the common fowl's egg; which (as may be seen by examining an egg whose shell remains soft for want of consolidation by calcareous particles) consist of two principal layers, one serving as a basis of the shell itself, and the other forming that lining to it which is known as the *membrana*

putaminis. The latter may be separated by careful tearing with needles and forceps, after prolonged maceration in water, into several matted lamellæ resembling that represented in fig. 711 ; and similar lamellæ may be readily obtained from the shell itself by dissolving



FIG. 711.—Fibrous membrane from egg-shell.



FIG. 712.—White fibrous tissue from ligament.

away its lime by dilute acid. The simply fibrous structures of the body generally, however, belong to one of two very definite kinds of tissue, the 'white' and the 'yellow,' whose appearance, composition, and properties are very different. The *white* fibrous tissue, though sometimes apparently composed of distinct fibres, more commonly presents the aspect of bands, usually of a flattened form, and attaining the breadth of $\frac{1}{300}$th of an inch, which are marked by numerous longitudinal streaks, but can seldom be torn up into minute fibres of determinate size. The fibres and bands are occasionally somewhat wavy in their direction ; and they have a peculiar tendency to fall into undulations, when it is attempted to tear them apart from each other (fig. 712). This tissue is easily distinguished from the other by the effect of acetic acid, which swells it up and renders it transparent, at the same time bringing into view certain oval nuclear particles of 'germinal matter,' which are known as 'connective tissue corpuscles.' These are relatively much larger, and their connections more distinct, in the earlier stages of the formation of this tissue (fig. 713). It is perfectly inelastic ; and we find it in such parts as tendons, ordinary ligaments, fibrous capsules, &c. whose function it is to resist tension without yielding to it. It constitutes, also, the organic basis or matrix of bone ; for although the substance which is left when a bone has been macerated sufficiently long in dilute acid for all its mineral components to be

FIG. 713.—Portion of young tendon, showing the corpuscles of 'germinal matter,' with their stellate prolongations, interposed among its fibres.

removed is commonly designated as cartilage, this is shown by careful microscopic analysis not to be a correct description of it, since it does not show any of the characteristic structure of cartilage, but is capable of being torn into lamellæ, in which, if sufficiently thin, the ordinary structure of a fibrous membrane can be distinguished. The *yellow* fibrous tissue exists in the form of long single, elastic, branching filaments, with a dark decided border: which are disposed to curl when not put on the stretch (fig. 714), and frequently anastomose, so as to form a network. They are for the most part between $\frac{1}{5000}$th and $\frac{1}{1000}$th of an inch in diameter: but they are often met with both larger and smaller. This tissue does not undergo any change when treated with acetic acid. It exists alone (that is, without any mixture of the white) in parts which require a peculiar elasticity, such as the middle coat of the arteries, the 'vocal cords,' the 'ligamentum nuchæ' of quadrupeds, the elastic ligament which holds together the valves of a bivalve shell, and that by which the claws of the feline tribe are retracted when not in use; and it enters largely into the composition of *areolar* or connective tissue.



FIG. 714.—Yellow fibrous tissue from ligamentum nuchæ of calf.

The tissue formerly known to anatomists as 'cellular,' but now more properly designated *connective* or *areolar* tissue, consists of a network of minute fibres and bands which are interwoven in every direction, so as to leave innumerable *areolæ* or little spaces that communicate freely with one another. Of these fibres some are of the 'yellow' or elastic kind, but the majority are composed of the 'white' fibrous tissue: and, as in that form of elementary structure, they frequently present the condition of broad flattened bands or membranous shreds in which no distinct fibrous arrangement is visible. The proportion of the two forms varies according to the amount of elasticity, or of simple resisting power, which the endowments of the part may require. We find this tissue in a very large proportion of the bodies of higher animals: thus it binds together the ultimate muscular fibres into minute fasciculi, unites these fasciculi into larger ones, these again into still larger ones which are obvious to the eye, and these into the entire muscle: whilst it also forms the membranous divisions between distinct muscles. In like manner it unites the elements of nerves, glands, &c. binds together the fat-cells into minute masses (fig. 720), these into large ones, and so on: and in this way penetrates and forms part of all the softer organs of the body. But whilst the fibrous structures of which the 'formed tissue' is composed have a purely mechanical function, there is good reason to regard the 'connective

issue corpuscles' which are everywhere dispersed among them, as aving a most important function in the first production and subquent maintenance of the more definitely organised portions of ie fabric. In these corpuscles distinct *movements*, analogous to iose of the sarcodic extensions of rhizopods, have been recognised i transparent parts, such as the cornea of the eye and the tail of ie young tadpole, by observations made on these parts whilst living. or the display of the characters of the fibrous tissues small and iin shreds may be cut with the curved issors from any part that affords iem ; and these must be torn asunder ith needles under the simple microope, until the fibres are separated to degree sufficient to enable them to s examined to advantage under a igher magnifying power. The differice between the 'white' and the rellow' components of connective tissue at once made apparent by the effect f acetic acid ; whilst the 'connecve tissue corpuscles' are best disnguished by the staining process, pecially in the early stage of the rmation of these tissues (fig. 713).



FIG. 715.—Vertical section of skin of finger: A, *epidermis*, the surface of which shows depressions *a a*, between the eminences *b b*, on which open the perspiratory ducts *s* ; at *m* is seen the deeper layer of the epidermis, or stratum Malpighii. B, *cutis vera*, in which are imbedded the sweat-glands *d*, with their ducts *e*, and aggregations of fat-cells *f* ; *g*, arterial twig supplying the vascular papillæ *p* ; *t*, one of the tactile papillæ with its nerve.

Skin; Mucous and Serous Membranes.—The skin, which forms the exrnal envelope of the body, is divisible ito two principal layers: the *cutis vera* r 'true skin,' which usually makes up y far the larger part of its thickness, nd the 'cuticle,' 'scarfskin,' or *epiermis*, which covers it. At the mouth, ostrils, and the other orifices of the *pen* cavities and canals of the body, he skin passes into the membrane that ines these, which is distinguished as he *mucous* membrane, from the peculiar glairy secretion of mucus by which ts surface is protected. But those great *losed* cavities of the body which surround the heart, lungs, intesines, &c. are lined by membranes of a different kind ; which, as hey secrete only a thin serous fluid from their surfaces, are known s *serous* membranes. Both mucous and serous membranes consist, ike the skin, of a cellular membranous basis, and of a thin cuticular ayer, which, as it differs in many points from the epidermis, is disinguished as the epithelium. The substance of the 'true skin' and f the 'mucous' and 'serous' membranes is principally composed of he fibrous tissues last described ; but the skin and the mucous memranes are very copiously supplied with blood-vessels and with glanulæ of various kinds ; and in the skin we also find abundance of erves and lymphatic vessels, as well as, in some parts, of hair-

follicles. The general appearance ordinarily presented by a thin vertical section of the skin of a part furnished with numerous sensory *papillæ* is shown in fig. 715: where we see in the deeper layers of the *cutis vera* little clumps of fat-cells, *f*, and the sweat-glands, *d d*, whose ducts, *e e*, pass upwards: whilst on its surface we distinguish the *vascular* papillæ, *p*, supplied with loops of blood-vessels from the trunk, *g*, and a *tactile* papilla, *t*, with its nerve twig. The spaces between the papillæ are filled up by the soft 'Malpighian layer,' *m*, of the epidermis, A, in which its colouring matter is chiefly contained, whilst this is covered by the horny layer, *h*, which is traversed by the spirally twisted continuations of the perspiratory ducts, opening at *s* upon the surface, which presents alternating depressions, *a*, and elevations, *b*. The distribution of the blood-vessels in the skin and mucous membranes, which is one of the most interesting features in their structure, and which is intimately connected with their several functions, will come under our notice hereafter. In serous membranes, on the other hand, whose function is simply protective, the supply of blood-vessels is more scanty.

Epidermic and Epithelial Cell-layers.—The epidermis or 'cuticle' covers the whole exterior of the body as a thin semitransparent pellicle, which is shown by microscopic examination to consist of a series of layers of cells that are continually wearing off at the external surface, and being renewed at the surface of the true skin: so that the newest and deepest layers gradually become the oldest and most superficial, and are at last thrown off by slow desquamation. In their progress from the internal to the external surface of the epidermis the cells undergo a series of well-marked changes. When we examine the innermost layer, we find it soft and granular, consisting of nucleated cells which are flatter in the upper than the lower strata which make up the layer. This was formerly considered as a distinct tissue, and was supposed to be the peculiar seat of the colour of the skin; it received the designation of Malpighian layer or *rete mucosum*. The change in form is accompanied by a change in the chemical composition of the tissue, which seems to be due to the metamorphosis of the contents of the cells into a horny substance identical with that of which hair, horn, nails, hoofs, &c. are composed. Mingled with the epidermic cells we find others which secrete colouring matter instead of horn: these, which are termed 'pigment-cells,' are especially to be noticed in the epidermis of the negro and other dark races, and are most distinguishable in the Malpighian layer, their colour appearing to fade as they pass towards the surface. The most remarkable development of pigment-cells in the higher animals, however, is on the inner surface of the choroid coat of the eye, where they have a very regular arrangement, and form several layers, known as



FIG. 716.—Cells from the *pigmentum nigrum* of the eye: *a*, pigmentary granules concealing the nucleus; *b*, the nucleus.

the *pigmentum nigrum*. When examined separately these cells are found to have a polygonal form (fig. 716, *a*), and to have a distinct nucleus (*b*) in their interior. The black colour is due to the accumulation, within each cell, of a number of flat rounded or oval granules, of extreme minuteness, which exhibit an active movement when set free from the cell, and even whilst enclosed within it. The pigment-cells are not always, however, of this simply rounded or polygonal form; they sometimes present remarkable stellate prolongations, under which form they are well seen in the skin of the frog (fig. 730, *c c*). The gradual formation of these prolongations may be traced in the pigment-cells of the tadpole during its metamorphosis (fig. 717). Similar varieties of form are to be met with in the pigmentary cells of fishes and small crustacea, which also present a great variety of hues; and these seem to take the colour of the bottom over which the animal may live, so as to serve the better for its concealment.

FIG. 717.—Pigment-cells from tail of tadpole: *a a*, simple forms of recent origin; *b b*, more complex forms subsequently assumed.

The structure of the epidermis may be examined in a variety of ways. If it be removed by maceration from the true skin, the cellular nature of its under surface is at once recognised, when it is subjected to a magnifying power of 200 or 300 diameters, by light transmitted through it, with this surface uppermost; and if the epidermis be that of a negro or any other dark-skinned race, the pigment-cells will be very distinctly seen. This under-surface of the epidermis is not flat but is excavated into pits and channels for the reception of the papillary elevations of the true skin; an arrangement which is shown on a large scale in the thick cuticular covering of the dog's foot, the subjacent papillæ being large enough to be distinctly seen (when injected) with the naked eye. The cellular nature of the newly forming layers is best seen by examining a little of the soft film that is found upon the surface of the true skin, after the more consistent layers of the cuticle have been raised by a blister. The alteration which the cells of the external layers have undergone tends to obscure their character; but if any fragment of epidermis be macerated for a little time in a weak solution of soda or potass, its dry scales become softened, and are filled out by imbibition into rounded or polygonal cells. The same mode of treatment enables us to make out the cellular structure in warts and corns, which are epidermic growths from the surface of papillæ enlarged by hypertrophy.

The *epithelium* may be designated as a delicate cuticle, covering all the free *internal* surfaces of the body, and thus lining all its cavities, canals, &c. Save in the mouth and other parts in which it approximates to the ordinary cuticle, both in locality and in

nature, its cells (fig. 718) usually form but a single layer; and are so deficient in tenacity of mutual adhesion that they cannot be detached in the form of a continuous membrane. Their shape varies greatly. Sometimes they are broad, flat, and scale-like, and their edges approximate closely to each other, so as to form what is termed a 'pavement' or 'tessellated' epithelium: such cells are observable on the web of a frog's foot or on the tail of a tadpole: for, though covering an external surface, the soft moist cuticle of these parts has all the characters of an epithelium. In other cases the cells have more of the form of cylinders, standing erect side by side, one extremity of each cylinder forming part of the free surface, whilst the other rests upon the membrane to which it serves as a covering. If the cylinders be closely pressed together, their form is changed into prisms; and such epithelium is often known as 'prismatic.' On the other hand, if the surface on which it rests be convex, the bases or lower ends of the cylinders become smaller than



FIG. 718.—Detached epithelium-cells: *a*, with nuclei *b*, and nucleoli *c*, from mucous membrane of the mouth.

FIG. 719.—Ciliated epithelium: *a*, nucleated cells resting on their smaller extremities; *b*, cilia.

their free extremities; and thus each has the form of a truncated cone rather than of a cylinder, and such epithelium (of which that covering the *villi* of the intestine is a peculiarly good example) is termed 'conical.' But between these primary forms of epithelial cells there are several intermediate gradations; and one often passes almost insensibly into the other. Any of these forms of epithelium may be furnished with *cilia*; but these appendages are more commonly found attached to the elongated than to the flattened forms of epithelial cells (fig. 719). Ciliated epithelium is found upon the lining membrane of the air-passages in all air-breathing Vertebrata; and it also presents itself in many other situations, in which a propulsive power is needed to prevent an accumulation of mucous or other secretions. Owing to the very slight attachment that usually exists between the epithelium and the membranous surface whereon it lies, there is usually no difficulty whatever in examining it, nothing more being necessary than to scrape the surface of the membrane with a knife and to add a little water to what has been thus removed. The ciliary action will generally be found to persist for some hours or even days after death if the animal has been previously in full vigour; and the cells that bear the cilia, when detached from each other, will

swim freely about in water. If the thin fluid that is copiously discharged from the nose in the first stage of an ordinary 'cold in the head' be subjected to microscopic examination, it will commonly be found to contain a great number of ciliated epithelium-cells, which have been thrown off from the lining membrane of the nasal passages.

Fat.—One of the best examples which the bodies of higher animals afford, of a tissue composed of an aggregation of cells, is presented by fat, the cells of which are distinguished by their power of drawing into themselves oleaginous matter from the blood. Fat-cells are sometimes dispersed in the interspaces of areolar tissue; whilst in other cases they are aggregated in distinct masses, constituting the proper adipose substance. The individual fat-cells always present a nearly spherical or spheroidal form; sometimes, however, when they are closely pressed together they become somewhat polyhedral, from the flattening of their walls against each other (fig. 720). Their intervals are traversed by a minute network of blood-vessels (fig. 734), from which they derive their secretion; and it is probably by the constant moistening of their walls with a *watery* fluid, that their contents are retained without the least transudation, although these are quite fluid at the temperature of the living body. Fat-cells, when filled with their characteristic contents, have the peculiar appearance which has been already described as appertaining to oil-globules, being very bright in their centre, and very dark towards their margin, in consequence of their high refractive power; but if, as often happens in preparations that have been long mounted, the oily contents should have escaped, they then look like any other cells of the same form. Although the fatty matter which fills these cells (consisting of a solution of stearine or margarine in oleine) is liquid at the ordinary temperature of the body of a warm-blooded animal, yet its harder portion sometimes crystallises on cooling, the crystals shooting from a centre, so as to form a star-shaped cluster. In examining the structure of adipose tissue it is desirable, where practicable, to have recourse to some specimen in which the fat-cells lie in single layers, and in which they can be observed without disturbing or laying them open; such a condition is found, for example, in the mesentery of the mouse; and it is also occasionally met with in the fat-deposits which present themselves at intervals in the connective tissues of the muscles, joints, &c. Small collections of fat-cells exist in the deeper layers of the true skin, and are brought into view by vertical sections of it (fig. 715, *f*). And the structure of large masses of fat may be examined by thin sections, these being placed under water in thin cells, so as to take off the pressure of the glass-cover from their surface, which would cause the escape of the oil-



FIG. 720.—Areolar and adipose tissue: *a a*, fat-cells; *b b*, fibres of areolar tissue.

particles. No method of mounting (so far as the Author is aware) is successful in causing these cells permanently to retain their contents.

Cartilage.—In the ordinary forms of cartilage, also, we have an example of a tissue obviously composed of cells; but these are commonly separated from each other by an 'intercellular substance,' which is so closely adherent to the outer walls of the cells as not to be separable from them. The thickness of this substance differs greatly in different kinds of cartilage, and even in different stages of the growth of any one. Thus in the cartilage of the external ear of a bat or mouse (fig. 721), the cells are packed as closely together as are those of an ordinary vegetable parenchyma; and this seems to be the early condition of most cartilages that are afterwards to present a different aspect. In the ordinary cartilages, however, that cover the extremities of the bones, so as to form smooth surfaces for the working of the joints, the amount of intercellular substance is usually considerable; and the cartilage-cells are commonly found imbedded there in clusters of two, three, or four (fig. 722), which are evidently formed by a process of 'binary subdivision.' The substance of these *cellular* cartilages is entirely destitute of blood-vessels being nourished solely by imbibition from the blood brought to the membrane covering their surface. Hence they may be compared, in regard to their grade of organisation, with the larger algæ, which consist, like them, of aggregations of cells held together by intercellular substance, without vessels of any kind, and are nourished by imbibition through their whole surface. There are many cases, however, in which the structureless intercellular substance is replaced by bundles of fibres, sometimes elastic, but more commonly non-elastic; such combinations, which are termed *fibro*-cartilages, are interposed in certain joints, wherein tension as well as pressure has to be resisted: as, for example, between the vertebræ of the spinal column and the bones of the pelvis. In examining the structure of cartilage nothing more is necessary than to make very thin sections, preferably with the microtome. These sections may be

Fig. 721.—Cellular cartilage of mouse's ear.



Fig. 722.—Section of the branchial cartilage of tadpole: *a*, group of four cells, separating from each other; *b*, pair of cells in apposition; *c c*, nuclei of cartilage-cells; *d*, cavity containing three cells (the fourth probably behind).

mounted in weak spirit, Goadby's solution, or glycerin-jelly; but in whatever way they are mounted, they undergo a gradual change by lapse of time, which renders them less fit to display the characteristic features of their structure.

Structure of the Glands.—The various secretions of the body (as saliva, bile, urine, &c.) are formed by the instrumentality of organs termed glands; which are, for the most part, constructed on one fundamental type, whatever be the nature of their product. The simplest idea of a gland is that which we gain from an examination of the 'follicles' or little bags imbedded in the wall of the stomach, some of which secrete mucus for the protection of its surface and other gastric juice. These little bags are filled with cells of a spheroidal form, which may be considered as constituting their epithelial lining; these cells, in the progress of their development, draw into themselves from the blood the constituents of the particular product they are to secrete; and they then seem to deliver it up, either by the bursting or by the melting away of their walls, so that this product may be poured forth from the mouth of the bag into the cavity in which it is wanted. The organ which is generally, though by no means accurately, called the liver presents this condition in the lowest animals wherein it is found. In many Polyzoa, compound Tunicata, and Annelida the cells of this organ can be seen to occupy follicles in the walls of the stomach; in insects these follicles are few in number, but are immensely elongated, so as to form tubes, which lie loosely within the abdominal cavity, frequently making many convolutions within it, and discharge their contents into the commencement of the intestinal canal; whilst in the higher Mollusca, and in Crustacea, the follicles are vastly multiplied in number, and are connected with the ramifications of gland-ducts, like grapes upon the stalks of their bunch, so as to form a distinct mass which now becomes known as the liver. The examination of the tubes of this organ in the insect, or of the follicles of the crab, which may be accomplished with the utmost facility, is well adapted to give an idea of the essential nature of glandular structure. Among vertebrated animals the salivary glands, the pancreas (sweetbreads), and the mammary glands are well adapted to display the follicular structure (fig. 723), nothing more being necessary than to make sections of these organs thin enough to be viewed as transparent objects. The kidneys of vertebrated animals are made up of elongated tubes, which are straight, and are lined with a pavement-epithelium in the inner or 'medullary' portion of the kidney, whilst they are convoluted and filled with a spheroidal epithelium in the outer or 'cortical.' Certain flask-shaped dilatations of these tubes include curious little knots of blood-vessels, which are known as the 'Malpighian bodies' of the kidney; these are well displayed in injected preparations. For such a full and



FIG. 723.—Ultimate follicles of mammary gland, with their secreting cells *a a*, containing nuclei *b b*.

complete investigation of the structure of these organs as the anatomist and physiologist require, various methods must be put in practice which this is not the place to detail. It is perfectly easy to demonstrate the cellular nature of the substance of the liver by simply scraping a portion of its cut surface, since a number of its cells will then be detached. The general arrangement of the cells in the lobules may be displayed by means of sections thin enough to be transparent; whilst the arrangement of the blood-vessels can only be shown by means of injections. Fragments of the tubules of the kidney, sometimes having the Malpighian capsules in connection with them, may also be detached by scraping its cut surface; but the true relations of these parts can only be shown by thin transparent sections, and by injections of the blood-vessels and tubuli. The simple follicles contained in the walls of the stomach are brought into view by vertical sections; but they may be still better examined by leaving small portions of the lining membrane for a few days in dilute nitric acid (one part to four of water), whereby the fibrous tissue will be so softened that the clusters of glandular epithelium lining the follicles (which are but very little altered) will be readily separated.

Muscular Tissue.—Although we are accustomed to speak of this tissue as consisting of 'fibres,' yet the ultimate structure of the 'muscular fibre' is very different from that of the 'simple fibrous tissues' already described. When we examine an ordinary muscle (or piece of 'flesh') with the naked eye, we observe that it is made up of a number of *fasciculi* or bundles of fibres (fig. 724), which are arranged side by side with great regularity, in the direction in which the muscle is to act, and are united by connective tissue. These fasciculi may be separated into smaller parts, which appear like simple fibres; but when these are examined by the microscope, they are found to be themselves fasciculi, composed of minuter fibres bound together by delicate filaments of connective tissue. By carefully separating these we may obtain the ultimate muscular fibre. This fibre exists under two forms, the *striated* and the *non-striated*. The former is chiefly distinguished by the transversely striated appearance which it presents (fig. 725), and which is due to an alternation of light and dark spaces along its whole extent; the breadth and distance of these striæ vary, however, in different fibres, and even in different parts of the same fibre, according to their state of contraction or relaxation. Longitudinal striæ are also frequently visible, which are due to a partial separation between the component fibrillæ into which the fibre may be broken up. When a fibre of this kind is more closely examined, it is seen to be enclosed within a delicate tubular sheath, which is quite distinct on the one hand from the connective tissue that binds the fibres into

FIG. 724.—Fasciculus of striated muscular fibre, showing at *a* the transverse striæ, and at *b* its junction with the tendon.

fasciculi, and equally distinct from the internal substance of tl fibre. This membranous tube, which is termed the *sarcolemma*, not perforated by capillary vessels, which therefore lie *outside* tl ultimate elements of the muscular substance; whether it is pen trated by the ultimate fibres of nerves is a point not yet certainly ascertained. The diameter of the fibres varies greatly in different kinds of vertebrated animals. Its average is greater in reptiles and fishes than in birds and mammals, and its extremes also are wider; thus its dimensions vary in the frog from $\frac{1}{100}$th to $\frac{1}{1000}$th of an inch, and in the skate from $\frac{1}{65}$th to $\frac{1}{300}$th; whilst in tl human subject the average is about $\frac{1}{400}$th of an inch, and tl extremes about $\frac{1}{200}$th and $\frac{1}{800}$th.



FIG. 725.—Striated muscular fibre, separating into fibrillæ.

The substance of the fibre, when broken up by 'teasing' wit needles, is found to consist of very minute fibrillæ, which, whe examined under a magnifying power of from 250 to 400 diameter are seen to present a slightly beaded form, and to show the sam alternation of light and dark spaces as when the fibrillæ are united into fibres or into small bundles (fig. 725). The dark and light spaces are usually of nearly equal length; each light space is divided by a transverse line, called 'Dobie's line,' while each dark space is crossed by a lighter band, known as 'Hensen's stripe.' It has been generally supposed that these markings indicate differences in the *composition* of the fibre; but Mr. J. B. Haycraft has recently revived an idea, which originated with Mr. Bowman, that they are the optical expressions of its *shape*. The borders of the striated fibre (he truly states) present wavy margins, indicative of a transverse ridging and furrowing, the whole fibre (or a single fibril) thus consisting of a succession of convex bead-like projections with intermediate concave depressions. When the *axis* of the fibre is in true focus Dobie's line, D (fig. 725A), crosses the deepest part of the concavity, while Hensen's stripe, H, crosses tl most projecting part of the convexity, and it can be shown, bot theoretically and experimentally, that this alternation of lights an shades will be produced by the passage of light through a similarl shaped homogeneous rod of any transparent substance. If, on tl other hand, the *surface* of the fibre be brought into focus, the conve

FIG. 725A.—Diagram of striated fibrilla.

ribbings appear light and intervening depressions dark, which is the aspect originally represented by Bowman. The appearances are the same in the extended and contracted states of the fibre; with the exception that the alternation of light and dark striæ is closer in the contracted state, while the breadth (representing the thickness) of the fibre is correspondingly increased.[1] It is well none the less in the present state of our knowledge to refrain from conclusions as to the absolute structure of the striated fibrillæ. It ranges itself, from the modern microscopist's point of view, with other striated objects, and will require the possession of lenses of a N.A. twice or thrice that which are now within our reach. There is no immediate prospect of these, it is true; but they cannot be considered impossible by the student of the past history of microscopy.

In the examination of muscular tissue a small portion may be cut out with the curved scissors; this should be torn up into its component fibres; and these, if possible, should be separated into their fibrillæ by dissection with a pair of needles under the simple microscope. The general characters of the *striated* fibre are admirably shown in the large fibres of the frog; and by selecting a portion in which these fibres spread themselves out to unite with a broad tendinous expansion, they may often be found so well displayed in a single layer as not only to exhibit all their characters without any dissection, but also to show their mode of connection with the 'simple fibrous' tissue of which that expansion is formed. As the ordinary characters of the fibre are but little altered by boiling, recourse may be had to this process for their more ready separation, especially in the case of the tongue. Dr. Beale recommends glycerin for the preparation, and glycerin media for the preservation of objects of this class; and states that the alternation of light and dark spaces in the fibrillæ is rendered more distinct by such treatment. The fibrillæ are often more readily separable when the muscle has been macerated in a weak solution of chromic acid. The shape of the fibres can only be properly seen in cross-sections; and these are best made by the freezing microtome. Striated fibres, separable with great facility into their component fibrillæ, are readily obtainable from the limbs of crustacea and of insects; and their presence is also readily distinguishable in the bodies of worms, even of very low organisation; so that it may be regarded as characteristic of the articulated series generally. On the other hand, the molluscous classes are, for the most part, distinguished by the non-striation of their fibre; there are, however, some exceptions, such as the muscles of the odontophore in the snail and the powerful adductor muscle of *Pecten*. Its presence seems related to energy and rapidity of movement, the non-striated presenting itself where the movements are slower and feebler in their character.

The 'smooth' or *non-striated* form of muscular fibre, which is especially found in the walls of the stomach, intestines, bladder, and other similar parts, is composed of flattened bands whose diameter is

[1] *Quart. Journ. Micros. Sci.* n.s. xxi. p. 307. The more recent views will be found in Mr. C. F. Marshall's paper in vol. xxviii. of the same journal, and in the memoirs cited by him.

usually between $\frac{1}{3000}$th and $\frac{1}{3000}$th of an inch ; and these bands are collected into fasciculi, which do not lie parallel with each other, but cross and interlace. By macerating a portion of such muscular substance, however, in dilute nitric acid (about one part of ordinary acid to three parts of water) for two or three days, it is found that the bands just mentioned may be easily separated into elongated fusiform cells, not unlike 'woody fibre' in shape (fig. 726, *a a*) ; each distinguished, for the most part, by the presence of a long staff-shaped nucleus, *b*, brought into view by the action of acetic acid, *c*. These cells, in which the distinction between cell-wall and cell-contents can by no means be clearly seen, are composed of a soft yellow substance often containing small pale granules, and sometimes yellow globules of fatty matter. In the coats of the blood-vessels are found cells having the same general characters, but shorter and wider in form ; and although some of these approach very closely in their



FIG. 726.—Structure of *non-striated* muscular fibre: A, portion of tissue showing fusiform cells *a a*, with elongated nuclei *b b*; B, a single cell isolated and more highly magnified; C, a similar cell treated with acetic acid.

FIG. 727.—Ganglion-cells and nerve-fibres from a ganglion of lamprey.

general appearance to epithelium-cells, yet they seem to have quite a different nature, being distinguished by their elongated nuclei, as well as by their contractile endowments.

Nerve-substance.—Wherever a distinct nervous system can be made out, it is found to consist of two very different forms of tissue, namely, the *cellular*, which are the essential components of the ganglionic centres, and the *fibrous*, of which the connecting trunks consist. The typical form of the nerve-cells or 'ganglion-globules' may be regarded as globular ; but they often present an extension into one or more long processes, which give them a 'caudate' or 'stellate' aspect. These processes have been traced into continuity, in some instances, with the axis-cylinders of nerve-tubes (fig. 727) ; whilst in other cases they seem to inosculate with those of other vesicles. The cells, which do not seem to possess a definite cell-wall, are, for the most part, composed of a finely granular substance, which

extends into their prolongations; and in the midst of this is usually to be seen a large well-defined nucleus. They also generally contain pigment-granules, which give them a reddish or yellowish-brown colour, and thus impart to collections of ganglionic cells in the warm-blooded Vertebrata that peculiar hue which causes it to be known as the *cineritious* or *grey* matter, but which is commonly absent among the lower animals. Each of the tubular nerve-fibres, on the other hand, of which the trunks are made up, consists, in its fully developed form, of a delicate membranous sheath, within which is a hollow cylinder of a material known as the 'white substance of Schwann,' whose outer and inner boundaries are marked out by two distinct lines, giving to each margin of the nerve-tube what is described as a 'double contour.' The contents of the membranous envelope are very soft, yielding to slight pressure; and they are so quickly altered by the contact of water or of any liquids which are foreign to their nature that their characters can only be properly judged of when they are quite fresh. The centre or axis of the tube is then found to be occupied by a transparent substance which is known as the 'axis cylinder': and there is reason to believe that this last, which is a protoplasmic substance, is the *essential* component of the nerve-fibre, while the function of the hollow cylinder that surrounds it, which is composed of a combination of fat and albuminous matter, is simply protective. The diameter of the nerve-tubes differs in different nerves, being sometimes as great as $\frac{1}{1500}$th of an inch, and as small in other instances as $\frac{1}{12000}$th. In many of the lower invertebrata, such as *Medusæ* and *Comatulæ*, we seem fully justified by physiological evidence in regarding as nerves certain protoplasmic fibres which do not possess the characteristic structure of 'nerve-tubes,' and fibres destitute of the 'double contour' are found also in certain parts of the body of even the highest vertebrates. These fibres, which are known as 'gelatinous,' are considerably smaller than the preceding, and do not exhibit any differentiation of parts (fig. 728). They are flattened, soft, and homogeneous in their appearance, and contain numerous nuclear particles which are brought into view by acetic acid. They can sometimes be seen to be continuous with the axis-cylinders of the ordinary fibres, and also with the radiating prolongations of the ganglion-cells; so that their nervous character, which has been questioned by some anatomists, seems established beyond doubt.

FIG. 728.—Gelatinous nerve-fibres, from olfactory nerve.

The ultimate distribution of the nerve-fibres is a subject on which there has been great divergence of opinion, and one which can only be successfully investigated by observers of great experience. The Author believes that it may be stated as a general fact, that in both the motor and the sensory nerve-tubes, as they approach their

ions in the muscles and in the skin respectively, the smic axis-cylinder is continued beyond its envelopes, en breaking up into very minute fibrillæ, which inosculate ch other, so as to form a network closely resembling that by the pseudopodial threads of Rhizopods. Recent observers scribed the fibrillæ of motor nerves as terminating in l end-plates' seated upon or in the muscular fibres; and m analogous to the little 'islets' of sarcodic substance into hose threads often dilate. Where the skin is specially with tactile sensibility we find a special *papillary* is, which in the skin may be readily made out in thin sections treated with solution of soda (fig. 729). It was supposed that all the cutaneous papillæ are furnished with res, and minister to sensation; but it is now known that a portion (at any rate) of those that are furnished with loops -vessels (figs. 715, *p*, 737), being destitute of nerve-fibres, ve for their special ie production of is; whilst those possessing nerve- ave sensory func- e usually destitute od-vessels. The part of the interior sensory papilla , *c c*) of the skin ied by a peculiar ody,' which seems erely a bundle of connective tissue, the nerve-fibre to terminate. The ibres are more seen, however, in giform' papillæ of ue, to each of which several of them proceed; these bodies, e very transparent, may be well seen by snipping off minute of the tongue of the frog; or by snipping off the papillæ es from the surface of the living human tongue, which can ly done by a dexterous use of the curved scissors, with no in than the prick of a pin would give. The transparence papillæ also is increased by treating them with a weak of soda. Nerve-fibres have also been found to terminate ry surfaces in minute 'end-bulbs' of spheroidal shape and $\frac{1}{60}$th of an inch in diameter, each of them being composed nple outer capsule of connective tissue, filled with clear ter, in the midst of which the nerve-fibre, after losing its der, ends in a knob. The 'Pacinian corpuscles,' which are in the mesentery of the cat, and are from $\frac{1}{13}$th to $\frac{1}{10}$th of long, seem to be more developed forms of these 'end-bulbs.' the sake of obtaining a general acquaintance with the



FIG. 729.—Vertical section of skin of finger, showing the branches of the cutaneous nerves, *a*, *b*, inosculating to form a plexus, of which the ultimate fibres pass into the cutaneous papillæ, *c c*.

microscopic characters of these principal forms of nerve-substance, it is best to have recourse to minute nerves and ganglia. The small nerves which are found between the skin and the muscles of the back of the frog, and which become apparent when the former is being stripped off, are extremely suitable for this purpose; but they are best seen in the *Hyla* or 'tree-frog,' which is recommended by Dr. Beale as being much superior to the common frog for the general purposes of minute histological investigation. If it be wished to examine the natural appearance of the nerve-fibres, no other fluid should be used than a little blood-serum; but if they be treated with strong acetic acid, a contraction of their tubes takes place, by which the axis-cylinders are forced out from their cut extremities, so as to be made more apparent than they can be in any other way. On the other hand, by immersion of the tissue in a dilute solution of chromic acid (about one part of the solid crystals to two hundred of water), the nerve-fibres are rendered firmer and more distinct. Again, the axis-cylinders are brought into distinct view by the staining process, being dyed much more quickly than their envelopes; and they may thus be readily made out by reflected light in transverse sections of nerves that have been thus treated. The *gelatinous* fibres are found in the greatest abundance in the sympathetic nerves: and their characters may be best studied in the smaller branches of that system. So for the examination of the ganglionic cells, and of their relation to the nerve-tubes, it is better to take some minute ganglion as a whole (such as one of the sympathetic ganglia of the frog, mouse, or other small animal), then to dissect the larger ganglionic masses, whose structure can only be successfully studied by such as are proficient in this kind of investigation. The nerves of the orbit of the eyes of fishes, with the ophthalmic ganglion and its branches, which may be very readily got at in the skate, and of which the components may be separated without much difficulty, form one of the most convenient objects for the demonstration of the principal forms of nerve-tissue, and especially for the connection of nerve-fibres and ganglion-cells. For minute inquiries, however, into the ultimate distribution of the nerve-fibres in muscles and sense-organs, certain special methods must be followed, and very high magnifying powers must be employed. Those who desire to follow out this inquiry should acquaint themselves with the methods which have been found most successful in the hands of the able histologists whose works have been already referred to.[1]

Circulation of the Blood.—One of the most interesting spectacles that the microscopist can enjoy is that which is furnished by the circulation of the blood in the *capillary* blood-vessels which distribute the fluid through the tissues it nourishes. This, of course, can only be observed in such parts of animal bodies as are sufficiently thin and transparent to allow of the transmission of light through them, without any disturbance of their ordinary structure; and the

[1] For further information regarding the nervous system the memoir of F. Nansen on 'The Structure and Combination of the Histological Elements of the Central Nervous System' in Bergen's *Museums Aarsberetning* for 1886 (1887), p. 29, should be consulted.

ıber of these is very limited. The web of the frog's foot is per-
s the most suitable for ordinary purposes, more especially since
animal is to be easily obtained in almost every locality ; and the
›wing is the simple arrangement preferred by the Author : A
e of thin cork is to be obtained, about nine inches long and three
ıes wide (such pieces are prepared by cork-cutters, as soles), and a
ı about $\frac{3}{8}$ths of an inch in diameter is to be cut at about the middle
:s length, in such a position that, when the cork is secured upon the
'e, this aperture may correspond with the axis of the microscope.
body of the frog is then to be folded in a piece of wet calico,
leg being left free, in such a manner as to confine its move-
ıts, but not to press too tightly upon its body ; and being then
down near one end of the cork-plate, the free leg is to be ex-
led, so that the foot can be laid over the central aperture. The
ading out of the foot over the aperture is to be accomplished
.er by passing pins through the edge of the web into the cork be-
th, or by tying the ends of the toes with threads to pins stuck
› the cork at a small distance from the aperture ; the former
hod is by far the least troublesome, and it may be doubted
›ther it is really the source of more suffering to the animal than
latter, the confinement being obviously that which is most felt.
'ew turns of tape, carried *loosely* around the calico bag, the pro-
ing leg, and the cork serve to prevent any sudden start ; and
›n all is secure, the cork-plate is to be laid down upon the stage
:he microscope, where a few more turns of the tape will serve to
p it in place. The web being moistened with water (a precaution
ch should be repeated as often as the membrane exhibits the
:t appearance of dryness) and an adequate light being reflected
›ugh the web from the mirror, this wonderful spectacle is brought
› view on the adjustment of the focus (a power of from 75 to 100
neters being the most suitable for ordinary purposes), provided
t no obstacle to the movement of the blood be produced by
lue pressure upon the body or leg of the animal. It will not un-
quently be found, however, that the current of blood is nearly or
›gether stagnant for a time ; this seems occasionally due to the
mal's alarm at its new position, which weakens or suspends the
.on of its heart, the movement recommencing again after the
se of a few minutes, although no change has been made in
of the external conditions. But if the movement should not
ew itself, the tape which passes over the body should be slackened ;
if this does not produce the desired effect, the calico envelope
› must be loosened. When everything has once been properly
usted, the animal will often lie for hours without moving, or
l only give an occasional twitch ; and even this may be avoided
previously subjecting it to the influence of ether or chloroform,
.ch may be renewed from time to time whilst it is under observa-
ı. The movement of the blood will be distinctly seen by that of
corpuscles (fig. 730), which course after one another through the
work of capillaries that intervenes between the smallest arteries
l the smallest veins ; in those tubes which pass most directly
n the veins to the arteries the current is always in the same

direction ; but in those which pass across between these it may not unfrequently be seen that the direction of the movement changes from time to time. The larger vessels with which the capillaries are seen to be connected are almost always *veins*, as may be known from the direction of the flow of blood in them from the branches (*b b*) towards their trunks (*a*) ; the *arteries*, whose ultimate subdivisions discharge themselves into the capillary network, are for the most part restricted to the immediate borders of the toes. When a power of 200 or 250 diameters is employed, the visible area is of course greatly reduced ; but the individual vessels and their contents are much more plainly seen : and it may then be observed that whilst the 'red' corpuscles flow at a very rapid rate along the centre of each tube, the 'white' corpuscles, which are occasionally discernible, move slowly in the clear stream near its margin.

The circulation may also be displayed in the *tongue* of the frog



FIG. 730.—Capillary circulation in a portion of the web of a frog's foot : *a*, trunk of vein ; *b*, *b*, its branches ; *c*, *c*, pigment-cells.

by laying the animal (previously chloroformed) on its back, with its head close to the hole in the cork-plate, and, after securing the body in this position, drawing out the tongue with the forceps and fixing it on the other side of the hole with pins. So, again, the circulation may be examined in the *lungs*—where it affords a spectacle of singular beauty—or in the *mesentery* of the living frog by laying open its body and drawing forth either organ, the animal having previously been made insensible by chloroform. The *tadpole* of the frog, when sufficiently young, furnishes a good display of the capillary circulation in its tail ; and the difficulty of keeping it quiet during the observation may be overcome by gradually mixing some warm water with that in which it is swimming until it becomes motionless ; this usually happens when it has been raised to a temperature of between 100° and 110° Fahr. ; and, notwithstanding that the muscles of the body are thrown into a state of spasmodic rigidity by this treatment, the heart continues to pulsate, and the circulation is

maintained.[1] The *larva of the water-newt*, when it can be obtained, furnishes a most beautiful display of the circulation, both in its external gills and in its delicate feet. It may be inclosed in a large aquatic box or in a shallow cell, gentle pressure being made upon its body, so as to confine its movements without stopping the heart's action. The circulation may also be seen in the tails of small fish, such as the *minnow* or the *stickleback*, by confining these animals in tubes, or in shallow cells, or in a large aquatic box ;[2] but although the extreme transparence of these parts adapts them well for this purpose in one respect, yet the comparative scantiness of their blood-vessels prevents them from being as suitable as the frog's web in another not less important particular. One of the most beautiful of all displays of the circulation, however, is that which may be seen upon the *yolk-bag* of young fish (such as the salmon or trout) soon after they have been hatched ; and as it is their habit to remain almost entirely motionless at this stage of their existence, the observation can be made with the greatest facility by means of the zoöphyte-trough. The store of yolk which the yolk-bag supplies for the nutrition of the embryo not being exhausted in the fish (as it is in the bird) previously to the hatching of the egg, this bag hangs down from the belly of the little creature on its emersion, and continues to do so until its contents have been absorbed into the body, which does not take place for some little time afterwards. And the blood is distributed over it in copious streams, partly that it may draw into itself fresh nutritive material, and partly that it may be subjected to the aërating influence of the surrounding water.

The tadpole serves, moreover, for the display, under proper management, not only of the capillary, but of the *general* circulation ; and if this be studied under the binocular microscope, the observer not only enjoys the gratification of witnessing a most wonderful spectacle, but may also obtain a more accurate notion of the relations of the different parts of the circulating system than is otherwise possible.[3] The tadpole, as every naturalist is aware, is essentially a fish in the early period of its existence, breathing by gills alone, and having its circulating apparatus arranged accordingly ; but as its limbs are developed, and its tail becomes relatively shortened, its lungs are gradually evolved in preparation for its terrestrial life, and the course of the blood is considerably changed. In the tadpole as it comes forth from the egg the gills are *external*, forming a pair of fringes hanging at the sides of the head (fig. 731, 1) and at the bases of these, concealed by opercula or gill-flaps resembling those of fishes, are seen the rudiments of the *internal* gills, which soon begin to be developed in the stead of the preceding.

[1] A special form of live-box for the observation of living tadpoles &c. contrived by Prof. F. E. Schultze, is described and figured in the *Quart. Journ. Micros. Sci.* n.s. vol. vii. 1867, p. 261.

[2] A convenient trough for this purpose is described in the *Quart. Journ. Micros. Sci.* vol. vii. 1859, p. 113.

[3] See Mr. Whitney's account of 'The Circulation in the Tadpole' in *Trans. Micros. Soc.* n.s. vol. x. 1862, p. 1, and his subsequent paper 'On the Changes which accompany the Metamorphosis of the Tadpole' in the same transactions, vol. xv. p. 43. In the first of these memoirs Mr. Whitney described the internal gills as lungs, an error which he corrected in the second.

The *external* gills reach their highest development on the four fifth day after emersion ; and they then wither so rapidly (w



FIG. 731.—Circulation in the tadpole.

1. Anterior portion of young tadpole, showing the external gills, with the in tufts of the internal gills, and the pair of minute tubes between the heart a spirally coiled intestine, which are the rudiments of the future lungs.

2. More advanced tadpole, in which the external gills have almost disapp *a*, remnant of external gills on the left side ; *b*, operculum ; *c*, remnant of exter on the right side, turned in.

3. Advanced tadpole, showing the course of the general circulation: *a*, *b*, branchial arteries; *c*, pericardium ; *d*, internal gill ; *e*, first or cephalic *f*, branch to lip ; *g*, branches to head ; *h*, second or branchial trunk ; *i*, third uniting with its fellow to form the abdominal aorta, which is continued as the artery, *k*, to the extremity of the tail; *l*, caudal vein ; *m*, kidney ; *n*, vena *o*, liver ; *p*, vena portæ ; *q*, sinus venosus, receiving the jugular vein, *r*, and t dominal veins, *t*, *u*, as also the branchial vein, *v*.

4. The branchial circulation on a larger scale: A, B, C, three primary bran the branchial artery ; *a*, cartilaginous arches ; *b*, additional framework ; *c*, *c*, t branchial artery ; *d*, *f*, rootlets of branchial vein.

5. Origin of the vessels of the internal gills, *g*, from the roots of those external.

6. The heart, systemic arteries, pulmonary arteries and veins, and lungs, adult frog, the heart being turned up in the right-hand figure, to show the ju of the pulmonary veins and their entrance into the left auricle.

being at the same time drawn in by the growth of the animal) that by the end of the first week only a remnant of the right gill can be seen under the edge of the operculum (2, *c*), though the left gill (*b*) is somewhat later in its disappearance. Concurrently with this change the *internal* gills are undergoing rapid development; and the beautiful arrangement of their vascular tufts, which originate from the roots of the arteries of the external gills, as seen at *g*, 5, is shown in 4. It is requisite that the tadpole subjected to observation should not be so far advanced as to have lost its early transparence of skin; and it is further essential to the tracing out of the course of the abdominal vessels that the creature should have been kept without food for some days, so that the intestine may empty itself. This starving process reduces the quantity of red corpuscles, and thus renders the blood paler; but this, although it makes the smaller branches less obvious, brings the circulation in the larger trunks into more distinct view. 'Placing the tadpole on his back,' says Mr. Whitney, 'we look, as through a pane of glass, into the chamber of the chest. Before us is the beating heart, a bulbous-looking cavity, formed of the most delicate transparent tissues, through which are seen the globules of the blood, perpetually, but alternately, entering by one orifice and leaving it by another. The heart (fig. 731, 3, *a*) appears to be slung, as it were, between two arms or branches, extending right and left. From these trunks (*b*) the main arteries arise. The heart is inclosed within an envelope or pericardium (*c*), which is, perhaps, the most delicate, and is, certainly, the most elegant structure in the creature's organism. Its extreme fineness makes it often elude the eye under the single microscope, but under the binocular its form is distinctly revealed. Then it is seen as a canopy or tent, inclosing the heart, but of such extreme tenuity that its *folds* are really the means by which its existence is recognised. Passing along the course of the great vessels to the right and left of the heart, the eye is arrested by a large oval body (*d*) of a more complicated structure and dazzling appearance. This is the internal gill, which in the tadpole is a cavity formed of most delicate transparent tissue, traversed by certain arteries, and lined by a crimson network of blood-vessels, the interlacing of which, with their rapid currents and dancing globules, forms one of the most beautiful and dazzling exhibitions of vascularity.' Of the three arterial trunks which arise on each side from the *truncus arteriosus*, *b*, the first, or *cephalic*, *e*, is distributed entirely to the head, running first along the upper edge of the gill, and giving off a branch, *f*, to the thick fringed lip which surrounds the mouth; after which it suddenly curves upwards and backwards, so as to reach the upper surface of the head, where it dips between the eye and the brain. The second main trunk, *h*, seems to be chiefly distributed to the gill, although it freely communicates by a network of vessels both with the first or cephalic and with the third or abdominal trunk. The latter also enters the gill and gives off branches; but it continues its course as a large trunk, bending downwards and curving towards the spine, where it meets its fellow to form the *abdominal aorta*, *i*, which, after giving off branches to the abdominal viscera, is con-

tinued as the *caudal artery*, *k*, to the extremity of the tail. The blood is returned from the tail by the *caudal vein*, *l*, which is gradually increased in size by its successive tributaries as it passes towards the abdominal cavity; here it approaches the kidney, *m*, and sends off a branch which incloses that organ on one side, while the main trunk continues its course on the other, receiving tributaries from the kidney as it passes. The venous blood returned from the abdominal viscera, on the other hand, is collected into a trunk, *p*, known as the *portal vein*, which distributes it through the substance of the liver, *o*, as in man; and after traversing that organ it is discharged by numerous fine channels, which converge towards the great abdominal trunk, or *vena cava*, *n*, as it passes in close proximity to the liver, onwards to the *sinus venosus*, *q*, or rudimentary auricle of the heart. This also receives the *jugular vein*, *r*, from the head, which first, however, passes downwards in front of the gill close to its inner edge, and meets a vein, *t*, coming up from the abdomen, after which it turns abruptly in the direction of the heart. Two other abdominal veins, *u*, meet and pour their blood direct into the sinus venosus; and into this cavity is also poured the aërated blood returned from the gill by the *branchial vein*, *v*, of which only the one on the right side can be distinguished. The lungs may be detected in a rudimentary state, even in the very young tadpole, being in that stage a pair of minute tubular sacs, united at the upper extremities, and lying behind the intestine and close to the spine. They may be best brought into view by immersing the tadpole for a few days in a weak solution of chromic acid, which renders the tissue friable, so that the parts that conceal them may be more readily peeled away. Their gradual enlargement may be traced during the period of the tadpole's transparence; but they can only be brought into view by dissection when the metamorphosis has been completed. The following are Mr. Whitney's directions for displaying the circulation in these organs: 'Put the young frog into a wineglass and drop on him a single drop of chloroform. This suffices to extinguish sensibility. Then lay him on the back on a piece of cork and fix him with small pins passed through the web of each foot. Remove the skin of the abdomen with a fine pair of sharp scissors and forceps. Turn aside the intestines from the *left* side, and thus expose the left lung, which may now be seen as a glistening transparent sac containing air-bubbles. With a fine camel-hair pencil the lung may now be turned out, so as to enable the operator to see a large part of it by *transmitted* light. Unpin the frog and place him on a slip of glass, and then transmit the light through the everted portion of lung. Remember that the lung is very elastic, and is emptied and collapsed by very slight pressure. Therefore, to succeed with this experiment, the lung should be touched as little as possible, and in the lightest manner, with the brush. If the heart is acting feebly you will see simply a transparent sac, shaped according to the quantity of air-bubbles it may happen to contain, but void of red vascularity and circulation. But should the operator succeed in getting the lung well placed, full of air, and have the heart still beating vigorously, he will see before him

a brilliant picture of crimson network, alive with the dance and dazzle of blood-globules, in rapid chase of one another through the delicate and living lace-work which lines the chamber of the lung.' The position of the lungs in relation to the heart and the great vascular trunks is shown in fig. 731, 6.

Injected Preparations.—Next to the circulation of the blood in the living body, the varied distribution of the capillaries in its several organs, as shown by means of 'injections' of colouring matter thrown into their principal vessels, is one of the most interesting subjects of microscopic examination. The art of making successful preparations of this kind is one in which perfection can usually be attained only by long practice and by attention to a great number of minute particulars; and better specimens may be obtained, therefore, from those who have made it a business to produce them than are likely to be prepared by amateurs for themselves. For this reason no account of the process will be here offered, the minute details which need to be attended to, in order to attain successful



FIG. 732.—Transverse section of small intestine of rat, showing the villi *in situ*.



FIG. 733.—Section of the toe of a mouse: *a*, *a*, *a*, tarsal bones; *b*, digital artery; *c*, vascular loops in the papillæ forming the thick epidermic cushion on the under surface; *d*, distribution of vessels in the matrix of the claw.

results, being readily accessible elsewhere to such as desire to put it in practice.[1]

Many anatomical parts, when well injected and mounted, become

[1] See especially the article 'Injection' in the *Micrographic Dictionary*; M. Robin's work, *Du Microscope et des Injections*; Prof. H. Frey's treatise, *Das Mikroskop und die mikroskopische Technik*; Dr. Beale's *How to Work with the Micro-*

objects of both interest and instruction. This is the case with the *villi of the intestine*, seen in fig. 732, which presents a transverse section, in which they are seen *in situ*. A thin section of the toe of a mouse (fig. 733) is another illustration of the effectiveness of this mode of preparation.

A relation may generally be traced between the disposition of the capillary vessels and the functions they subserve; but that relation is obviously, so to speak, of a mechanical kind, the arrangement of the vessels not in any way determining the function, but



FIG. 734.—Capillary network around fat-cells.



FIG. 735.—Capillary network of muscle.

merely administering to it, like the arrangement of water- or gas-pipes in a manufactory. Thus, in fig. 734, we see that the capillaries of adipose substance are disposed in a network with rounded meshes, so as to distribute the blood among the fat-cells; whilst in fig. 735 we see the meshes enormously elongated, so as to permit the muscular fibres to lie in them. Again, in fig. 736, we observe the disposition of the capillaries around the orifices of the follicles of a mucous membrane; whilst in fig. 737 we see the looped



FIG. 736.—Distribution of capillaries in mucous membrane.



FIG. 737.—Distribution of capillaries in skin of finger.

arrangement which exists in the papillary surface of the skin, and which is subservient to the nutrition of the epidermis and to the activity of the sensory nerves.

In no part of the circulating apparatus, however, does the disposition of the capillaries present more points of interest than it does in the respiratory organs. In bony fishes the respiratory surface is formed by an outward extension into fringes of *gills*, each of which consists of an arch with straight laminæ hanging down from it, and

scope; the *Handbook to the Physiological Laboratory*; and Rutherford's and Schäfer's treatises on *Practical Histology*.

every one of these laminæ (fig. 738) is furnished with a double row of leaflets, which is most minutely supplied with blood-vessels, their network (as seen at A) being so close that its meshes (indicated by the dots in the figure) cover less space than the vessels themselves. The gills of fish are not ciliated on their surface, like those of molluscs and of the larva of the water-newt, the necessity for such a mode of renewing the fluid in contact with them being superseded by the muscular apparatus with which their gill-chamber is furnished. But in batrachians and reptiles the respiratory surface is formed by the walls of an internal cavity, that of the *lungs*: these organs, however, are constructed on a plan very different from that which they present in higher Vertebrata, the great extension of surface which is effected in the latter by the minute subdivision of the cavity not being here necessary. In the frog (for example) the cavity of each lung is undivided; its walls, which are thin and membranous at the lower part, there present a simple smooth expanse; and it is only at the upper part, where the extensions of the tracheal cartilage form a network over the interior, that its surface is depressed into sacculi whose lining is crowded with blood-vessels (fig. 739). In this manner a set of air-cells is formed in the thickness of the upper wall of the lung, which communicate with the general cavity, and very much increase the surface over which the blood comes into relation with the air; but each air-cell has a capillary network of its own, which lies on one side against its wall, so as only to be exposed to the air on its free surface. In the elongated lung of the snake the same general arrangement prevails; but the cartilaginous reticulation of its upper part projects much further into the cavity, and incloses



FIG. 738.—Two branchial processes of the gill of the eel, showing the branchial lamellæ: A, portion of one of these processes enlarged, showing the capillary network of the lamellæ.

FIG. 739.—Interior of upper part of lung of frog.

in its meshes (which are usually square, or nearly so) several l
of air-cells, which communicate, one through another, with
general cavity. The structure of the lungs of birds presents us
an arrangement of a very different kind, the purpose of which
expose a very large amount of capillary surface to the influence o
air. The entire mass of each lung may be considered as subdi
into an immense number of 'lobules' or 'lunglets' (fig. 740, B), ea
which has its own bronchial tube (or subdivision of the wind
and its own system of blood-vessels, which have very little



FIG. 740.—Interior structure of lung of fowl, as displayed by a section, A passing in the direction of a bronchial tube, and by another section B cutting it across.



FIG. 741.—Arrangement of the capillaries on the walls of the air-cells of the human lung.

munication with those of other lobules. Each lobule has a cer
cavity, which closely resembles that of a frog's lung in miniat
having its walls strengthened by a network of cartilage derived f
the bronchial tube, A, in the interspaces of which are openings l
ing to sacculi in their substance. But each of these cavities is
rounded by a solid plexus of blood-vessels, which does not seem t
covered by any limiting membrane, but which admits air from
central cavity freely between its meshes ; and thus its capillaries
in immediate relation with air on all sides—a provision that is

viously very favourable to the complete and rapid aëration of the blood they contain.[1] In the lung of man and mammals, again, the plan of structure differs from the foregoing, though the general effect of it is the same. For its whole interior is divided up into minute air-cells, which freely communicate with each other, and with the ultimate ramifications of the air-tubes into which the trachea subdivides; and the network of blood-vessels (fig. 741) is so disposed in the partitions between these cavities that the blood is exposed to the air on both sides. It has been calculated that the number of these air-cells grouped around the termination of each air-tube in man is not less than eighteen thousand, and that the total number in the entire lung is *six hundred millions*.

[1] On the respiratory organs of birds, see Campana, *La Respiration des Oiseaux*, Paris, 1875.

CHAPTER XXIII

APPLICATION OF THE MICROSCOPE TO GEOLOGICAL INVESTIGATION

THE utility of the microscope is by no means limited to the determination of the structure and actions of the organised beings at present living on the surface of the earth; for a vast amount of information is afforded by its means to the geological inquirer, not only with regard to the essential nature and composition of the rock-masses of which its crust is composed, but also with regard to the minute characters of the many vegetable and animal remains that are intombed therein.

The systematic employment of the instrument in petrographical research dates from 1858, when Dr. H. C. Sorby, F.R.S., published his classical paper 'On the Microscopical Structure of Crystals, indicating the Origin of Minerals and Rocks.'[1] The observations in this paper were based upon the microscopical examination of thin sections of rocks and minerals; still, although Dr. Sorby was the first to apply this manner of investigation to such objects, the first to suggest and arrange the method of preparing thin sections appears to have been William Nicol. A description of his method is given by H. Witham (1831).[2] Previous to 1858 only those minerals could be examined microscopically which possessed the necessary degree of transparency, whilst rocks were largely closed secrets. Nevertheless Cordier (in 1815) was able to determine the constituent minerals of many rocks by the study of the powder under the microscope; a procedure which Fleurian de Bellevue had previously recommended in 1800, and which is still employed by some mineralogists. Seven years before Dr. Sorby's paper appeared, the German scholar Oschatz exhibited a series of thin sections of minerals and rocks and drew attention to their important bearing upon structural studies, but the collection was regarded more as a curiosity than as a scientific achievement, so great was the stagnation that characterised those years.[3]

The discovery of the method of preparation gave an enormous impetus to geological research, and the germs falling upon the fruitful

[1] *Quart. Journ. Geol. Soc.* vol. xiv. 1858, pp. 453–500.

[2] *Observations on Fossil Vegetables*, Edinburgh and London, 1831.

[3] The history of the application of the microscope to geology has been sketched by F. Zirkel in his paper *Die Einführung des Mikroskops in das mineralogisch-geologische Studium*, Leipzig, 1881.

soil of scientific Germany led to the growth of a 'micro-petrology.' Its development we owe to such Continental workers as Zirkel, Vogelsang, Rosenbusch, Renard, and others.

In order to examine minerals and rocks, sections must be prepared thin enough to permit of the use of transmitted light; for this purpose they should be from about $\frac{1}{100}$th to $\frac{1}{1000}$th of an inch thick.

A chip about an inch square is struck or cut off the specimen to be studied. One surface of this is then ground down on a flat cast-iron plate with emery and water. This grinding may be done either by hand or by means of a machine specially constructed for this purpose (pp. 424, 425).[1] The former method will be described here. When a smooth surface is at last obtained the specimen is well washed with water and then polished upon a slab of plate glass with the finest flour emery and water. When all inequalities are thus removed the fragment is again well cleansed from all adhering emery.

The next process is to cement it with Canada balsam upon a slab of glass about two inches square and about an eighth of an inch in thickness. The Canada balsam is first heated over a spirit lamp in an iron spoon, care being taken not to allow it to burn. This is the most difficult part of the whole process, and only experience can teach how long the balsam must be heated in order to possess, on cooling, the necessary hardness. If it be heated too long it will crack upon cooling. The right point appears to be that in which large air-bubbles force themselves through the viscous mass.

A small quantity of the warm balsam is poured upon the slab of glass and the smooth surface of the rock-fragment, being pressed into the balsam, is held down upon the glass till the balsam hardens. The slab is then examined from its under side to see that no air-bubbles have been included between the glass and the stone. Should they be present in any quantity the whole process must be repeated. When the balsam has quite hardened, the other side of the fragment is ground down with coarse emery and water on the iron plate. Upon the section commencing to become transparent, the grinding with the coarse emery must cease. The stone is then thoroughly cleansed with water, and the final grinding is conducted upon the plate-glass slab with flour emery and water.

The slide is then placed under a stream of water in order to remove all traces of the emery powder from the minute pores of the rock. This is now the time to employ chemical tests to the component minerals, if such a course be deemed advisable. If the rock is of a fragile nature, it is well to mount the section as it is; but in most cases it is possible by delicate manipulation to remove it to an object-glass more suited to optical work. This transference is effected by the application of a gentle heat to the slab until the balsam becomes liquefied, when the section can be pushed with a piece of wire on to a slide of fine material. Obviously a drop of balsam should be poured upon the latter before the section is transferred.

[1] Mr. F. G. Cuttell (52 New Compton Street, Soho) prepares good sections; Messrs. Voigt and Hochgesang (Göttingen, Rothe Str. 13) and R. Fuess (Berlin, S.W. 108 Alte Jacob Str.) do also most excellent work.

The slide is then warmed until the balsam becomes liquid, when superfluous quantity is drawn over the upper surface of the sec When the section is completely covered with the balsam, a clean cover-glass is held for a moment over the spirit flame and upon the section. Gentle pressure is then applied to the sur bring it close down to the section and to remove all air-bu The slide is then allowed to become quite hard, when it m cleansed with turpentine or alcohol and ether.

Very porous rocks must first be heated with Canada balsam, order to give them the consistency necessary for the preparatio thin sections. Isolated mineral grains and sands can be moun by means of Canada balsam dissolved in chloroform. The s must not be heated, but evaporation allowed to take place. Anot method is described by Thoulet;[1] whilst very soft or decompo rocks should be mounted according to Wichmann's proposal.[2]

In the application of the microscope to petrological and mine logical research the employment of polarised light is constantly quired, and various means and appliances are needful for its m advantageous application, which are not required by the ordin microscopist. Considerable pains have been bestowed by bo English and Continental makers to fulfil the requirements, and go instruments are now plentiful.[3]

An instrument having been recently brought out by Messrs. Swift and Son, which combines all that experience has led petrologi to consider desirable for mineralogical and petrological investigatio a brief account of it is here subjoined. It is specially adapted to t study of the optical properties of minerals generally, and particula to that of the thin plates of minerals seen in ordinary sections rocks prepared for microscopical examination. The microscope shown in fig. 742.[4]

The eyepiece tube is slotted at F to receive the micrometer sc (shown detached at F), and to the tube is hinged the analyser which is capable of independent rotation in the usual manne Upon the eyepiece tube is mounted a toothed wheel, which ge into another toothed wheel mounted on one end of a rod formed pinion wire. Below the stage, which has neither sliding nor rotato movements, is mounted the polariser, B, capable of independent ro tion like the analyser, and upon the tube of the polariser is mount a toothed wheel of the same size as that upon the analyser; t wheel gears into a wheel carried by a tube which forms a telesco extension of the pinion wire, the object being to allow of the raisi or lowering of the body of the microscope for focussing. The a lyser and the polariser may thus be rotated synchronously with disconnecting their toothed wheels. Now, in the microsco usually constructed for petrological work the rotation of a sm

[1] *Annales de Chimie et de Physique* (5), xx. pp. 362–432.

[2] Tschermak's *Mineralogische und Petrogr. Mitt.* Bd. v. 1882, p. 33.

[3] Mr. Watson, of Holborn, London, and Messrs. Henry Crouch, Limited, make s able instruments. Those constructed by Zeiss, of Jena; Nachet, of Paris; Voigt Hochgesang, of Göttingen; Fuess, of Berlin; and Hartnack, of Potsdam, can also recommended.

[4] The instrument is protected by letters patent.

n the stage between the polarising and the analysing prisms
:o put it out of position in regard to the cross-threads in



FIG. 742.—Swift's new petrological microscope.

iece, as the centring of the objective is scarcely ever so
not to produce *some* displacement ; and, if the centring

be adjusted so as to be perfect for one objective, it is likely to be faulty for another. (By a small crystal is meant a crystal under the $\frac{1}{1000}$th of an inch in diameter, and of such thickness as one finds at the edges of petrological sections.) Hence, by the arrangement described above, centring is dispensed with, and the object is made to rotate between the two prisms of the polarising apparatus without changing its position beneath the objective. To a petrologist who is accustomed to a rotating stage and fixed cross-wires a familiar section looks strange when first looked at on a fixed stage with movable cross-wires, but after a few hours' work with the instrument, the feeling of strangeness passes and that of the solid advantage of a perfect centring remains.

On the polariser tube, above the toothed wheel and below the stage, is fitted a goniometer, D, which, in combination with crossed lines in the eye-piece, will permit of the measurement of the angles of crystals without necessitating the shifting of the object when once adjusted in the field. C is a set screw by which the polarising apparatus and goniometer may be fixed in any desired position. Both the analysing and polarising prisms are divided to every 45°, a spring catch marking the extinction point. The opening between the upper lens of the eye-piece and the analysing prism B′ (fig. 742) is for the purpose of placing such plates as the $\frac{1}{4}$-undulation plate K in position.

The great value of the instrument is in the facility with which studies in convergent light can be performed. G is a slide fitted with a double convex lens which may be used for showing the optical figures of crystals, and H is a similar slide carrying a lens and diaphragm of small aperture used for showing optical pictures in minute crystals. The polariser is fitted with two convergent lenses which work in conjunction with the lens A on the slide of the stage when great convergence is required. This slide may be pushed in without disturbing the object upon the stage. The achromatic condenser, A, shown at the foot of the figure, also works in conjunction with the sliding lens, A, when the highest angular aperture is required. When convergent light is required the slide on the stage and either G or H are pushed in, and the eye-piece covered with the analyser B′. The optical figures of the crystal then appear with almost ideal clearness. If this simple method is compared with that previously in use the superiority of the instrument will be immediately recognised. It is in fact the most perfect petrological microscope yet issued, and is one which will suit equally the mineralogical and petrological student. The instrument was designed by Mr. Allan Dick and marks a great advance in this branch of microscopical science.

The microscopical investigation of rock sections has almost revolutionised petrology. Although the geologist has no difficulty in determining by his unaided eye with the use of simple chemical tests the mineral components of rocks of coarse texture, the case is different with those of extremely fine grain ; still more with such as present an apparently homogeneous, compact, and glassy character. The study reveals facts of the most striking significance, and wel-

come light has been thrown upon the question of the order and method of formation of rock-components.[1]

The material which issues from a volcano during an eruption is rarely in a state of true igneous fusion. In most cases it contains crystals and parts of crystals which have formed under high pressure before the arrival of the fluid mass at the surface of the earth. Such crystals are usually of large size and can generally be recognised with the naked eye. Now, pressure lowers the melting point of all substances. Accordingly, as the pressure is relieved upon the lava getting at or near the surface, a rise in the temperature of the fused mass must occur, and the crystals which are floating in it at the time are liable to become corroded or redissolved. Instances of this corrosion are numerous. The quartzes of the quartz-porphyries have this corroded appearance; whilst the porphyritic constituents of the basic rocks (hornblende, olivine, &c.) not infrequently show the same alteration (*vide* fig. 743; the dotted line marks the original outline). In the case of the hornblende the dissolved portions usually give rise to the formation of small grains of augite and magnetite, which are then found incircling the 'mother-crystal.'



FIG. 743.—Corroded olivine in basalt of Kilima Ndjaro, East Africa.

The rapid movement of the igneous mass may cause the crystals to come into violent contact with each other, fracture being the natural result. The pieces of such broken crystals may often be found in one and the same section, sometimes at no great distance from each other. As the lava solidifies, a further development of crystals occurs. The products of this period constitute the 'ground-mass' of the rock and are usually small in size, the microscope being frequently required for their detection and determination.

This last stage of consolidation often induces the formation of glass and gives rise to the appearance of very remarkable products, which are known to be the result of definite chemical compounds, endeavouring to crystallise under unfavourable circumstances. Generally speaking, these products are present in two stages of development. The less perfectly developed forms of these are known as *crystallites*. They occur in a variety of forms—hair-like, spherical, &c.—and represent matter in a state

[1] The reader is referred to the following works treating of the microscopic characters of minerals and rocks:—F. Fouqué et Michel Lévy, *Minéralogie micrographique*, Paris, 1878; E. Hussak, *Anleitung zum Bestimmen der gesteinsbildenden Mineralien*, Leipzig, 1885; E. Kalkowsky, *Elemente der Lithologie*, Heidelberg, 1886; A. V. Lasaulx, *Elemente der Petrographie*, Bonn, 1875, and *Einführung in die Gesteinslehre*, Breslau, 1886 (also edition in French); Lévy et Lacroix, *Les Minéraux des Roches*, Paris, 1888; F. H. Rosenbusch, *Mikroskopische Physiographie*, 2nd edition, vol. i. 'Die Mineralien' (translated into English by Iddings), vol. ii. 'Die massigen Gesteine;' and *Hülfstabellen zur mikroskopischen Mineralbestimmung in Gesteinen* (translated into English by F. H. Hatch); F. Rutley, *The Study of Rocks*, 3rd edition, 1884, and *Rock-forming Minerals*, 1888; J. J. H. Teall, *British Petrography*, 1888; Ch. Velain, *Conférences de Pétrographie*, 1er fascicule Paris, 1889; F. Zirkel, *Lehrbuch der Petrographie*, 2 vols. Bonn, 1866; *Basaltgesteine*, Bonn, 1870; *Die mikroskopische Beschaffenheit der Mineralien und Gesteine*, Leipzig, 1873; *Microscopical Petrography* (U.S. Geol. Exploration of 40th parallel), Washington, 1876.

intermediate between that of a glass and a crystalline body, hence are optically inactive. The conditions of their formation have been experimentally determined by Vogelsang.

The bodies belonging to the highest stage of development are called *microlites* (fig. 744). They differ from the crystallites in possessing the internal structure of true crystals and in acting on polarised light. The position of the microlites with reference to each other or to the large crystals is frequently an indicator of the movements of the original fluid mass. When streams of microlites are seen lying with their long axes in one direction, this direction is equivalent to that of the flow, and where such streams encounter large crystals they sweep round them in graceful curves: this appearance in a rock is known as fluxion-structure.

Masses of molten material may, however, consolidate at a considerable depth beneath the surface of the earth; in such cases the distinction between the first and second periods of crystallisation is not so well marked.

A crystal is, in one respect, like an organism—it is affected by its environment. The crystal modifies its surroundings, and is in



FIG. 744.—Microlites. (After Zirkel.)



FIG. 745.—Augite showing zonal structure. (After Zirkel.)

turn modified by them; there is action and reaction between it and its environment. This remarkable property of all crystalline bodies is well shown by the microscope. Crystals are constantly found built up of different layers or zones of material, unlike in their optical characters, and hence dissimilar in chemical constitution. This is the so-called zonal structure, and is common to the felspars and augites—in short, to nearly all minerals representing isomorphous mixtures (fig. 745). In the case of the augites a difference in colour often indicates its presence. This structure unquestionably signifies changes in the environment of the crystals during their growth, the precipitation of each successive zone affecting the chemical constitution of the succeeding one. This structure may be experimentally produced by placing an artificial crystal in a solution of a substance isomorphic with that of the crystal.

Another great service has been rendered by the microscope, inasmuch as it has enabled the petrologist to draw conclusions as to the physical condition of the fused mass or *magma* at the time crystallisation commenced. All chemists are aware that when

crystals are deposited from solutions at ordinary temperatures they usually contain small cavities full of the mother-liquor. Now, the growth of crystals in igneous rocks is exactly analogous to that in a supersaturated saline solution. Portions of the fused mass become entangled, which on cooling remain in a glassy condition, or 'become stony, so as to produce what may be called glass- or stone-cavities.'[1] When formed under great pressure by the combined influence of liquid water and fused mineral matter the crystals will contain glass-cavities and also fluid inclusions.

Glass inclusions are very abundant in the porphyritic crystals of volcanic rocks and represent to some extent the composition of the fused mass at the period of inclosure. The glass composing the inclusions is often darker in colour than the glass forming the base of the rock. This is probably due to the presence in the glass of the inclusions of a greater amount of iron and the bases usually associated with it. The glass often contains crystallites and microlites, sometimes due to inclosure at the same time, sometimes to a subsequent crystallising action set up by the glass. Gas bubbles are also inclosed along with the glass.

The existence of fluid inclusions in crystals has long been known; but not until Dr. Sorby directed his attention to the subject was their universal distribution in rock-constituents imagined, or their bearing upon geological problems recognised. They are often very minute, being frequently less than $\frac{1}{10000}$th of an inch in diameter. They are rare or absent in rocks of the volcanic group, but are especially characteristic of the plutonic rocks, such as granite, gabbro, diorite, &c. Where glass inclusions are common, fluid inclusions are rare or wanting.

Sometimes the fluid inclusions are so numerous in the quartzes of the granites as to be, according to Dr. Sorby,[2] 'not above the $\frac{1}{1000}$th of an inch apart. This agrees with the proportion of a thousand millions to a cubic inch, and in some cases they must be more than ten times as many.'

The forms of such inclusions vary, but they may be bounded by planes corresponding to the external faces of the crystals, and are then termed 'negative' crystals.

There is usually an intimate relation between the number of cavities in a crystal and the rate at which it was formed. Generally speaking, it may be said that the more rapid the growth, the more numerous the inclusions.

Not infrequently the cavities contain bubbles varying from $\frac{1}{15000}$th to $\frac{1}{30000}$th of an inch in size. These bubbles sometimes possess an apparently spontaneous movement, at other times heat must be applied to produce a change of position.

According to Dr. Sorby's experiments, the bubbles arise in consequence of the contraction of the liquid on cooling from the high temperature at which the cavities were filled.

The nature of the inclosed fluid has been determined with some accuracy. Generally the liquid is a solution of water charged with

[1] Sorby, *Quart. Journ. Geol. Soc.* 1858 p. 242. [2] *Op. cit.* p. 486.

salts; but it is seldom so concentrated as to cause the deposition in the cavities of little squares of salt. The presence has also been established of liquid carbonic dioxide, the bubble of which disappeared at about 32° C., the critical point for this gas.[1]

The discovery in the mineral components of plutonic rocks of these fluid inclusions is manifestly of the highest importance. Daubree's experiments have shown the enormous mineral-forming powers possessed by overheated water, whilst the presence of liquid carbonic dioxide testifies to the enormous pressure under which plutonic rocks, such as granite and diorite, have consolidated.

Inclusions of gaseous matter are also common; and it is self-evident that the occurrence of one mineral in another is no rarity; the included mineral is either contemporaneous or older, usually the latter. To such microscopic inclusions of crystalline bodies is due the remarkable colour of some minerals. Thus, red flakes of hematite cause the deep red colour of the carnallite of Stassfurt and the stibbite from the Fassathal in Tyrol. In fact, so numerous and so minute are the inclusions in some minerals that even with high powers the minerals appear to be charged with the finest dust. The leucite is a good instance of this (fig. 746).



Fig. 746.—Leucite from Kilima Ndjaro, East Africa.

The foregoing allows us to conclude, that an absolutely pure mineral is exceptional. All such mineral bodies contain inclosures of foreign matter which have become entangled during their formation; when they contain glass inclusions they have been precipitated out of a mass in the condition of igneous fusion. It follows, therefore, that a characteristic of igneous rocks is the presence of amorphous glass in their composition, either as a glassy residue or as glass-inclusions. Still, the absence of such material does not always demonstrate the non-igneous origin of the rock, for, on the other hand, plutonic rocks, such as granite, do not possess this feature. Their geological occurrence shows them to be eruptive. Glass-inclusions are certainly reported by Sigmund[2] to be present in the quartzes of the granites of the Monte Mulatto, near Predazzo, in South Tyrol, but V. Chrustschoff considers them products of contact-metamorphism.

We have dealt hitherto more especially with igneous masses, but the sedimentary rocks demand some attention.

The microscope enables us to recognise to some extent the sources whence the materials composing clastic[3] rocks were derived. For instance, the presence of quartzes containing numerous fluid inclusions (especially those of carbonic dioxide) and hair-like crystals of rutile lead us to conclude they are derived from granites or similar rocks. The cemented material can also be studied and its nature determined.

[1] The application of the burning end of a cigar to the section is usually sufficient to cause the bubble to disappear.

[2] 'Petrographische Studien am Granit von Predazzo,' *Jahrb. k. k. geol. Reichsanstalt*, Bd. xxix. 1879, pp. 305–316.

[3] Greek κλαστὸς = broken.

In some loose sands and sandstones there has sometimes occurred a curious process which the microscope first brought under notice. This is the precipitation on the outer surface of rounded quartz-grains of a greater or less amount of silica, which has been deposited in crystalline continuity with that of the original nuclei (fig. 747). The phenomenon is like that which happens when an irregular fragment of a crystal is placed in a concentrated solution of the same salt slowly evaporating. Restoration of the broken angles first takes place; then deposition goes on over the whole exposed surface, in perfect optical and crystalline continuity, so as to change a broken fragment into a definite crystal.



FIG. 747.—Sand-grain (A) with much quartz deposited on the surface. (After Dr. Sorby.)

By the microscopical examination of volcanic dust or ashes it is possible to determine the constitution of the igneous mass whose eruption gave rise to such material. Thus the ashes and dust which fell at various places after the great Krakatoa eruption in 1883 were found to belong to an acid lava, a pyroxene andesite.[1]

Further, the identification of glacial boulders with rocks *in situ* can only be satisfactorily carried out by a microscopical examination of their thin sections. The occurrence has accordingly been demonstrated of Norwegian rocks as boulders in the Eastern Counties, whilst Swedish and Finnish rocks are common in the drift of North Germany and Saxony. We now come to the discussion of the metamorphism to which all rock-masses are liable.

The metamorphism caused by atmospheric agencies results in decomposition and disintegration. The constituents are, of course, very differently affected, but rapidity of disintegration demands the decomposition of one of the principal constituents. Such a constituent is felspar, which decomposes under the influence of water charged with carbonic acid into kaolin; while the products of the decomposition of non-aluminous minerals are carbonates, ferric oxide, and quartz. The minute accessory constituents, such as the titanium-oxides, are not affected by these agencies, and hence are to be found in all clays and sands.

Thermal waters charged with various substances are common in all volcanic districts and play their part in the metamorphosis of rocks. In this way a volcanic rock may become silicified through the percolation of such solutions; and microscopical examination has shown that portions of the Roche Castle rock, in Pembrokeshire, have had their porphyritic felspars changed into quartz by this agency. Whilst treating of the metamorphosis caused by atmospheric agencies, mention should be made of the fact that a movement is now in progress to assist the selection of building stones suitable for public edifices, by a microscopical examination of thin sections of

[1] See the interesting paper by J. Murray and A. Renard on 'Volcanic Ashes and Cosmic Dust' in *Nature*, 1884, vol. xxix. p. 585.

the rocks proposed to be employed.[1] Obviously an increase in volume goes hand in hand with the decomposition of a constituent, and this may seriously affect the stability of the rock as a mass.

The intrusion of an igneous rock has generally an important influence on the structure and mineralogical composition of the surrounding mass, portions of which it can include and partially dissolve (contact-metamorphism). Sections from the junction of an igneous rock with one of sedimentary origin are highly interesting. The metamorphism is found to largely consist in the development of new minerals, such as garnets, andalusite, mica, fluorspar, or a new crystalline structure out of non-crystalline sedimentary materials. The formation of the new constituents points to the action of overheated water and gases of various nature, which accompany the eruption. Of very common occurrence is the metamorphism of fossiliferous chalk—which is amorphous carbonate of lime—into a marble consisting of crystalline calcite in which no trace of organic life can be discerned. The heat is often so intense as to fuse sandstones into a brownish glass.

It would be difficult to overestimate the utility of the microscope in questions relating to dynamic metamorphism, or that due to 'earth-stresses.'

The deformation by movement has sometimes been so enormous that the rocks have undergone a complete metamorphism, the original structure being partially or even wholly effaced. Mechanical energy is of course largely transformed into heat; hence under high pressure plasticity may be produced in bodies which are solid under ordinary circumstances.[2]

Chemical reactions must occur and must entail the formation of new minerals; for Spring[3] has demonstrated the truth that chemical action can take place under excessive pressure without the application of external heat.

These questions are now engaging wide-spread attention, and we may hope for welcome light being cast upon the vexed subject of the crystalline origin of the schists. These latter never show any trace of glassy matter, but their structure often reminds one of that of plutonic rocks. The opinion is daily gaining ground that some of them (e.g. the amphibolites) are nothing but altered igneous masses, an opinion which is strengthened by the knowledge that igneous rocks do pass into schists under the influence of dynamic metamorphism. This transition through molecular rearrangement first received its confirmation as a truth by the aid of the microscope. Let us take, for instance, the case of a felspar-pyroxene rock. Under dynamic metamorphism the twin lamellæ of the lath-shaped felspars become bent, actual fracture of the crystals may occur, and possibly recrystallisation of the component substance *in situ*: the new felspar, being granular, will arrange itself approximately along the planes of schistosity.

The pyroxene, which in the case of a dolerite was light chocolate

[1] Cf. Kloos, *Zeits. der deutschen geol. Gesellschaft*, Bd. xl. 1888, p. 612.
[2] Tresca, 'Flow of Solids,' *Proc. Inst. Mech. Eng.* 1878, p. 301.
[3] *Bull. Acad. Belgique*, tom. xlix. 1880 (2), p. 323.

brown, becomes altered into a pale green constituent, whose optical characters prove it to be hornblende. This latter also arranges itself so that the longest diameter of the grain lies itself in the planes of schistosity. Finally we obtain out of a rock, whose lighter and darker constituents were distributed uniformly through the mass, one in which the mineral components occur in wavy or parallel layers. In conjunction with this transformation a migration or concentration of certain substances is rendered possible. This generally shows itself in the white segregation veins common to 'moved' masses. Molecular tension can always be recognised by the presence of optical anomalies. The extinction shadows sweep over the sections as the stage is rotated, a phenomenon known as undulose extinction. Strain eventually overcomes the limit of elasticity, and there occurs granulation. The latter can be defined as the resolution of a grain, or the edges of a grain, into smaller individuals no longer in optical continuity with each other. As a rule, this alteration is confined to quartz and felspar, and becomes only visible under crossed nicols. It often leads to the formation of a quartz-felspar mosaic, in which secondary aggregate any relics of the original mineral will lie. Where large grains of the original constituents remain, the fine secondary aggregate sweeps round them in the manner characteristic of fluxion structure.

The quartz-granules of metamorphosed strata are sometimes observed to have lost the fluid inclusions so generally found in the quartz-grains of old sedimentary rocks. Hence it would appear that expulsion of such liquids is also a result of metamorphic action.

Secondary minerals become developed through the same causes. Pyroxene and olivine pass into hornblende, lime-soda felspars are altered into albite (soda-felspar) and epidote &c. Mica, both white and black, is generally developed along planes of movement, being formed at the expense of the felspar or the ferro-magnesian constituent.[1]

The degree of metamorphism is greatly influenced by chemical composition and varies accordingly. But it must be well understood that metamorphism does not produce a radical change in the elementary chemical composition. There has ensued rather a recrystallisation and a new association of the pre-existing elements (Delesse). The chemical constitution of a hornblende schist formed by the metamorphism of a dolerite is practically identical with that of the dolerite; the change has been here more mineralogical than chemical.

In conclusion, dynamic metamorphism causes sandstones to pass into quartzite or quartz schists; when they are felspathic, into mica schists. Argillaceous rocks are altered into phyllites &c.; basic igneous rocks into hornblendic, actinolitic or chloritic schists.

The optical methods now in use enable the petrologist to determine the constituents of rock-masses with astonishing success. The colour of the mineral in transmitted light, the crystallographic outlines,

[1] Cf. 'Recent Researches in the Metamorphism of Rocks,' by Dr. A. Geikie, in *Nature*, vol. xxvii. 1882, p. 121.

the direction of the cleavage planes, the polarisation tints, the position of the axes of elasticity, as also of the true optical axes, all these, with other minor properties, render his determinations of real value. A valuable test is further that of pleochroism, which is well developed in such minerals as hornblende, cordierite, tourmaline &c. This property has been artificially produced in colourless crystals by Sénarmont.

Very important service has been rendered by the microscope in the study of the phenomena known as optical anomalies. There exist a large number of minerals which show in thin-sections optical properties which do not agree with those of the crystal system to which they belong. The most satisfactory explanation for the anomaly of double refraction in crystals of the regular (cubic) system is that which considers it as the result of tension (Germ. *Spannung*). The admixture of an isomorphic substance can produce this disturbance in the molecular equilibrium. Experiment has proved that compression, strain, or other mechanical distortion, may cause amorphous bodies and crystals belonging to the regular system to become double-refracting. A uniaxial crystal becomes biaxial by the application of pressure at right angles to its optical axis, and ordinary glass may be given optical properties in the same manner.

Mention may well be made here of the anomalies presented by the mineral leucite, which is a most important constituent of the lavas of Vesuvius and the neighbourhood of Rome. It crystallises apparently in beautiful icositetrahedra (fig. 748), and to belong to the regular system should remain dark under crossed nicols, that is, isotropic. The small crystals certainly behave in this manner, but the large ones display more or less double refraction with decided traces of twin-lamellæ (fig. 748). This anomaly was for a long time inexplicable, till Klein showed[1] that such crystals revert when heated to 500° C. to a condition of perfect isotropy, which property they again lose upon becoming cool. The conclusion to be drawn from his classical investigation is, that the leucite originally crystallised in the regular system and that its present optical condition is owing to molecular change due to the reduction of temperature consequent upon solidification. It is worthy of notice that MM. Fouqué and Michel Lévy have synthetically produced a leucite rock, the leucites of which possessed the optical anomalies described above.

FIG. 748.—Leucite showing twin-striation under crossed nicols. (After Zirkel.)

The relation between optical characters and chemical constitution has received some degree of attention, and in the case of the felspar group has been accurately determined. Only the 'quantitative'

[1] For a description of the so-called 'Erhitzungs-Mikroskop,' see Groth's *Physikalische Krystallographie*, Leipzig, 1885, p. 631.

tion of the subject can be dealt with here, and we must abstain m the discussion of those minerals whose microscopical appearance ds the trained petrologist to draw *qualitative* conclusions. It is eresting, however, to note that the dark reddish or violet-brown our of some monoclinic pyroxenes is due, according to Knop, to presence of a not unimportant quantity of titanium oxide in their istitution. This was found in one instance to be as much as 4·57 cent., the angle between the axis of least elasticity γ and the tical crystallographic axis (commonly called the extinction angle) ng also very high. As a rule, the extinction angles of all mono- lic pyroxenes are found to vary between 36° and 54°. Hence ofessor Tschermak concluded that this was due to differences in ir chemical constitution, and suggested the varying amount of iron the cause. The subject has recently been investigated, though h poor success, by Wiik,[1] and later by Doelter. As a general e, the extinction angle may be said to be somewhat less in those gites which are poor in iron and alumina than in those rich in se substances. In the case of the hornblendes the positive angle he optical axis increases, according to Tschermak, with the quantity ron, whilst Wiik considers the extinction angle to be proportionate the quantity of alumina. The diversity of opinion demands a ther inquiry.

The researches of the late Max Schuster have established the im- tant fact that in the normal plagioclase felspars, which may be sidered as isomorphous mixtures of albite ($Na_2(Al_2)Si_6O_{16}$) and rthite ($Ca(Al_2)Si_2O_8$), the optical and chemical characters stand ie closest possible relations to each other. Hence, given the ction angle on a known surface, the chemical constitution is rn and, roughly speaking, the specific gravity.

trangely enough, the micro-spectroscope has not been ex- rely used by petrologists. It has been recently employed by ssor Orville Derby in the determination of the presence of ite in Brazilian sands.[2] This mineral contains a large per- e of didymium, and accordingly gives the bands characteristic t element.

discovery of the presence of foreign inclusions in all minerals to a remarkable revolution in mineral-chemistry. In earlier was customary to analyse a mineral without questioning its Hence the early analyses and the formulæ developed there- press the actual constitution *plus* the inclusions. Methods v been invented by which the foreign matter can be removed. ge is taken of the difference that is usual between the ravity of the mineral and that of its inclusions, the so-called lutions' being employed for the separation.[3] Most satis- sults have been obtained by such means. In cases where st accuracy is necessary, the apparatus designed by Dr.

[1] hållandet mellan de optiska egenskaperna och den kemiska samman- os pyroxen- och amphibol-arterna'—*Finska Vetensk. Soc. Förhdl.* vol. d vol. xxv. 1883.

[2] *n Journal of Science*, vol. xxxvii. 1889, p. 109.

[3] r mode of preparation see Rosenbusch, *Mikroskopische Physiographie*, (English edition by Iddings.)

P. Mann had better be employed.[1] It is well to microscopically examine the isolated substance before executing the analysis, for the optical test with polarised light is so sensitive as to detect the smallest impurities. Also, in the case of ordinary bulk analyses of rocks, it is advisable to follow the same course, as by doing so one is often enabled to make a qualitative analysis with the microscope alone.

A valuable adjunct to petrology is to be found in micro-chemistry.[2] Instances sometimes occur where a mineral cannot be satisfactorily determined by its optical characters, and in such cases micro-chemical methods are resorted to. Let us suppose it is desirable to see whether any of the rock-components are silicates containing soda and soluble in acids. The cover-glass is accordingly removed and the balsam dissolved in alcohol. A weak solution of hydrochloric acid is then poured over the surface, when, if soluble silicates are present, gelatinisation will take place. Upon allowing the gelatinous mass to evaporate little squares of salt will form if such a silicate is present. Sometimes colouring substances may be used for the same purpose. By the treatment of a slide with nitric acid a silicate like nepheline becomes porous and permeable to anilin blue, fuchsin, &c. In the case of nepheline the colouring matter cannot be washed out, and hence 'staining' proves a delicate test.

Where such a course is possible, minute pieces of the questionable minerals should be isolated and treated singly. There are two methods in use for testing such particles micro-chemically. The first is that proposed by Bovricky, who employed pure hydro-fluosilicic acid (H_2SiF_6), which attacks almost all rock-forming minerals. The mineral particle is placed upon a glass object-holder protected from the action of the acid by a covering of Canada balsam, and the acid allowed to attack the mineral. After evaporation an examination under the microscope reveals the presence of delicate crystals of the silico-fluorides of the metals present in the mineral. The nature of the crystals may then be determined microscopically.

The second method is that proposed by Behrens, and mostly follows the usual method of chemical analysis. The isolated particle is heated in a small platinum crucible with ammonium fluoride, the mass then evaporated with sulphuric acid and dissolved in hot water. A small quantity of the solution is then evaporated and examined. If calcium is present in the mineral small crystals of gypsum will form. Other quantities are treated with the ordinary reagents. The crystalline products, which are the result, can be identified by optical methods. It is possible by Behrens' tests to detect the presence of 0·0005 mgr. CaO in a grain.

[1] *Neues Jahrbuch für Mineralogie*, &c. Bd. ii. 1884, p. 172.

[2] The following works can be consulted on this subject:—E. Boricky, *Elemente einer neuen chemisch-mikroskopischen Mineral- und Gesteinsanalyse*, Prague, 1877; T. H. Behrens, *Mikrochemische Methoden zur Mineralanalyse*, Amsterdam, 1881; Haushofer, *Mikroskopische Reactionen*, Braunschweig, 1885; Klement et Renard, *Réactions microchimiques à cristaux*, &c. Bruxelles, 1886; Rosenbusch, *Mikroskopische Physiographie*, vol. i. 1885, pp. 195–288 (English edition by Iddings); F. Rutley, *Rock-forming Minerals*, London, 1888.

In all cases it is advisable to protect the objective during the microscopical examination with a thin sheet of white mica.

The microscope has always played an important part in the science of **Palæontology**. The great work on 'Micro-geology,' published in 1855 by Professor Ehrenberg, testifies to the influence it had, even at that period, upon research of this nature.

The result of the microscopic examination of lignite or fossilised wood and of ordinary coal is a good example of the value of the instrument in this interesting department.

Specimens of *fossilised wood* in a state of more or less complete preservation are found in numerous strata of very different ages. Generally speaking, it is only when the wood is found to have been penetrated by *silica* that its organic structure is well preserved; but instances occur every now and then in which penetration by *carbonate of lime* has proved equally favourable. In either case transparent sections are needed for the full display of the organisation; but such sections, though made with great facility when lime is the fossilising material, require much labour and skill when silica has to be dealt with. Occasionally, however, it has happened that the infiltration has filled the cavities of the cells and vessels, without consolidating their walls; and as the latter have undergone decay without being replaced by any cementing material, the lignite, thus composed of the internal 'casts' of the woody tissues, is very friable, its fibres separating from each other like those of asbestos; and laminæ split asunder with a knife, or isolated fibres separated by rubbing down between the fingers, exhibit the characters of the woody structure extremely well when mounted in Canada balsam. Generally speaking, the lignites of the Tertiary strata present a tolerably close resemblance to the woods of the existing period: thus the ordinary structure of *dicotyledonous* and *monocotyledonous* stems may be discovered in such lignites in the utmost perfection; and the peculiar modification presented by *coniferous* wood is also most distinctly exhibited. As we go back, however, through the strata to the Secondary period, we more and more rarely meet with the ordinary dicotyledonous structure; and the lignites of the earliest deposits of these series are, almost universally, either gymnosperms [1] or palms.

Descending into the palæozoic series, we are presented in the vast *coal* formations of our own and other countries with an extraordinary proof of the prevalence of a most luxuriant vegetation in a comparatively early period of the world's history. The determination of the characters of the *Ferns*, *Sigillariæ*, *Lepidodendra*, *Calamites*, and other kinds of vegetation whose forms are preserved in the shales or sandstones that are interposed between the strata of coal, has been hitherto chiefly based on their external characters; since it is seldom that these specimens present any such traces of minute internal structure as can be subjected to microscopic elucidation. But persevering search has recently brought to light

[1] Under this head are included the *Cycadeæ*, along with the ordinary *Coniferæ*, or pine and fir tribe.

numerous examples of coal-plants whose internal structure is sufficiently well preserved to allow of its being studied microscopically: and the careful researches of Professor W. C. Williamson have shown that they formed a series of connecting links between Cryptogamia and flowering plants, being obviously allied to *Equisetaceæ*, *Lycopodiaceæ*, &c., in the character of their fructification, whilst their stem-structure foreshadowed both the 'endogenous' and 'exogenous' types of the latter.[1] Notwithstanding the general absence of any definite *form* in the masses of decomposed vegetable matter of which coal itself consists, the traces of *structure* revealed by the microscope are often sufficient—especially in the ordinary 'bituminous' coal—not only to determine its vegetable origin, but in some cases to justify the botanist in assigning the character of the vegetation from which it must have been derived; and even where the stems and leaves are represented by nothing else than a structureless mass of black carbonaceous matter, there are found diffused through this a multitude of minute resinoid yellowish-brown granules, which are sometimes aggregated in clusters and inclosed in sacculi; and these may now be pretty certainly affirmed to represent the *spores*, while the sacculi represent the *sporangia*, of gigantic *Lycopodiaceæ* of the Carboniferous flora. The larger the proportion of these granules, the brighter and stronger is the flame with which the coal burns; thus in some blazing *cannel*-coals they abound to such a degree as to make up the greater proportion of their substance: whilst in *anthracite* or 'stone-coal' the want of them is shown by its dull and slow combustion. It is curious that the dispersion of these resinoid granules through the black carbonaceous matter is sometimes so regular as to give to transparent sections very much the aspect of a section of vegetable cellular tissue, for which they have been mistaken even by experienced microscopists; but this resemblance disappears under a more extended scrutiny, which shows it to be altogether accidental.[2]

Passing on now to the Animal Kingdom, we first cite some parallel cases in which the essential nature of deposits that form a very important part of the earth's crust has been determined by the assistance of the microscope, and then select a few examples of the most important contributions which it has afforded to our acquaintance with types of animal life long since extinct. It is an admitted rule in geological science that the past history of the earth is to be interpreted, so far as may be found possible, by the study of the changes which are still going on. Thus, when we meet with an extensive stratum of fossilised *Diatomaceæ* in what is now dry land, we can entertain no doubt that this silicious deposit originally accumulated either at the bottom of a fresh-water lake or beneath the waters of the ocean; just as such deposits are formed at the present time by the production and death of successive generations of these bodies, whose indestructible casings accumulate in the lapse

[1] See his succession of memoirs on the coal-plants in the recent volumes of the *Phil. Trans.*

[2] For notes upon methods to be employed in making preparations of coal, see Rutley, *Study of Rocks*, 1884, p. 71.

of ages, so as to form layers whose thickness is only limited by the time during which this process has been in action. In like manner, when we meet with a limestone rock entirely composed of the calcareous shells of Foraminifera, some of them entire, others broken up into minute particles (as in the case of the *Fusulina* limestone of the Carboniferous period, and the *nummulitic* limestone of the Eocene), we interpret the phenomenon by the fact that the dredgings obtained from certain parts of the ocean-bottom consist almost entirely of remains of existing Foraminifera, in which entire shells, the animals of which may be yet alive, are mingled with the *débris* of others that have been reduced to a fragmentary state. Such a deposit, consisting chiefly of *Orbitolites*, is at present in process of formation on certain parts of the shores of Australia, as the Author was informed by Mr. J. Beete Jukes, thus affording the exact parallel to the stratum of *Orbitolites* (belonging, as his own investigations have led him to believe, to the very same species) that forms part of the 'calcaire grossier' of the Paris basin. So in the fine white mud which is brought up from almost every part of the sea-bottom of the Levant, where it forms a stratum that is continually undergoing a slow but steady increase in thickness, the microscopic researches of Professor W. C. Williamson [1] have shown, not only that it contains multitudes of minute remains of living organisms, both animal and vegetable, but that it is entirely or almost wholly composed of such remains. Amongst these are about twenty-six species of Diatomaceæ (silicious), eight species of Foraminifera (calcareous), and a miscellaneous group of objects (fig. 749), consisting of calcareous and silicious spicules of sponges and *Gorgoniæ*, and fragments of the calcareous skeletons of echinoderms and molluscs. A collection of forms strongly resembling that of the Levant mud, with the exception of the silicious Diatomaceæ, is found in many parts of the 'calcaire grossier' of the Paris basin, as well as in other extensive deposits of the same early Tertiary period.

It is, however, in regard to the great *chalk* formation that the information afforded by the microscope has been most valuable. Mention has already been made of the fact that a large proportion of the North Atlantic sea-bed has been found to be covered with an 'ooze' chiefly formed of the shells of *Globigerinæ*; and this fact, first determined by the examination of the small quantities brought up by the sounding apparatus, has been fully confirmed by the results of the recent exploration of the deep-sea with the dredge; which, bringing up half a ton of this deposit at once, has shown that it is not a mere surface-film, but an enormous mass whose thickness cannot be even guessed at. 'Under the microscope,' says Professor Wyville Thomson [2] of a sample of 1½ cwt. obtained by the dredge from a depth of nearly three miles, 'the surface-layer was found to consist chiefly of entire shells of *Globigerina bulloides*, large and small, and of fragments of such shells mixed with a quantity of amorphous calcareous matter in fine particles, a little fine sand, and many spicules, portions

[1] *Memoirs of the Manchester Literary and Philosophical Society*, vol. vii.
[2] *The Depths of the Sea*, p. 110.

of spicules, and shells of *Radiolaria*, a few spicules of sponges, and a few frustules of diatoms. Below the surface-layer the sediment becomes gradually more compact, and a slight grey colour, due probably to the decomposing organic matter, becomes more pronounced, while perfect shells of *Globigerina* almost disappear, fragments become smaller, and calcareous mud, structureless, and in a fine state of



FIG. 749.—Microscopic organisms in Levant mud: A, C, D, silicious spicules of *Tethya*; B, H, spicules of *Geodia*; E, calcareous spicule of *Grantia*; F, G, M, O, portions of calcareous skeleton of *Echinodermata*; I, calcareous spicule of *Gorgonia*; K, L, N, silicious spicules of sponges; P, portion of prismatic layer of shell of *Pinna*.

division, is in greatly preponderating proportion. One can have no doubt, on examining this sediment, that it is formed in the main by the accumulation and disintegration of the shells of *Globigerina*: the shells fresh, whole, and living, in the surface-layer of the deposit; and in the lower layers dead, and gradually crumbling down by the decomposition of their organic cement, and by the pressure of the layers above.' This white calcareous mud also contains in large

amount the 'coccoliths' and 'coccospheres' formerly described. Now the resemblance which this *Globigerina*-mud, when dried, bears to chalk is so close as at once to suggest the similar origin of the latter; and this is fully confirmed by microscopic examination. For many samples of it consist in great part of the minuter kinds of Foraminifera, especially *Globigerinæ*, whose shells are imbedded in a mass of apparently amorphous particles, many of which, nevertheless, present indications of being the disintegrated fragments of similar shells, or of larger calcareous organisms. In the chalk of some localities the disintegrated prisms of *Pinna*, or of other large shells of the like structure (as *Inoceramus*), form the great bulk of the recognisable components; whilst in other cases, again, the chief part



FIG. 750.—Microscopic organisms in chalk from Gravesend: *a*, *b*, *c*, *d*, *Textularia globulosa*; *e*, *e*, *e*, *Rotalia aspera*; *f*, *Textularia aculeata*; *g*, *Planularia hexas*; *h*, *Navicula*.

is made up of the shells of *Cytherina*, a marine form of entomostracous crustacean. Different specimens of chalk vary greatly in the proportion which the distinctly organic remains bear to the amorphous residuum, and which the different kinds of the former bear to each other; and this is quite what might be anticipated when we bear in mind the predominance of one or another tribe of animals in the several parts of a large area; but it may be fairly concluded, from what has been already stated of the amorphous component of the *Globigerina*-mud, that the amorphous constituent of chalk likewise is the disintegrated residuum of foraminiferal shells. But, further, the *Globigerina*-mud now in process of formation is in some places literally crowded with sponges having a complete *silicious*

skeleton; and some of them bear such an extraordinarily close resemblance, alike in structure and in external form, to the *Ventriculites* which are well known as chalk fossils, as to leave no reasonable doubt that these also live as silicious sponges on the bottom of the cretaceous sea. Finally (as was first pointed out by Mr. Sorby) the coccoliths and coccospheres at present found on the sea-bottom are often to be discovered by the microscopic examination of chalk.[1] All these correspondences show that the formation of chalk took place under conditions essentially similar to those under which the deposit of *Globigerina*-mud is being formed over the Atlantic sea-bed at the present time.

In examining chalk or other similar mixed aggregation, whose component particles are easily separable from each other, it is de-

FIG. 751.—Microscopic organisms in chalk from Meudon, seen partly as opaque, and partly as transparent objects.

sirable to separate, with as little trouble as possible, the larger and more definitely organised bodies from the minute amorphous particles: and the mode of doing this will depend upon whether we are operating upon the large or upon the small scale. If the former, a quantity of soft chalk should be rubbed to powder with water by means of a soft brush; and this water should then be proceeded with according to the method of levigation already directed for separating the *Diatomaceæ*. It will usually be found that the first deposits contain the larger Foraminifera, fragments of shell, &c., and that the smaller

[1] 'On the Organic Origin of the so-called "Crystalloids" of Chalk' in *Ann. Nat. Hist.* ser. iii. vol. viii. 1861, pp. 198–200.

Foraminifera and sponge-spicules fall next, the fine amorphous particles remaining diffused through the water after it has been standing for some time, so that they may be poured away. The organisms thus separated should be dried and mounted in Canada balsam. If the smaller scale of preparation be preferred, as much chalk scraped fine as will lie on the point of a knife is to be laid on a drop of water on the glass slide, and allowed to remain there for a few seconds; the water, with any particles still floating on it, should then be removed; and the sediment left on the glass should be dried and mounted in balsam. For examining the structure of flints such chips as may be obtained with a hammer will commonly serve very well, a clear translucent flint being first selected, and the chips that are obtained being soaked for a short time in turpentine (which increases their transparence); those which show organic structure, whether sponge-tissue or xanthidia, are to be selected and mounted in Canada balsam. The most perfect specimens of sponge-structure, however, are only to be obtained by slicing and polishing.

There are various other deposits, of less extent and importance than the great chalk-formation, which are, like it, composed in great part of microscopic organisms, chiefly minute Foraminifera; and the presence of animals of this group may be largely recognised, by the assistance of the microscope, in sections of calcareous rocks of various dates, whose other materials were fragments of corals, encrinite-stems, or the shells of molluscs. In the formation of the coralline crag (Tertiary) of the eastern coast of England, polyzoaries had the greatest share; but the Tertiary limestone of which Paris is chiefly built consists almost exclusively of the shells of *Miliolida*, and is thus known as miliolite (millet-seed) limestone. In the vast stratum of nummulitic limestone which was formed at the commencement of the Tertiary period the microscope enables us to see that the *matrix* in which the large entire nummulites are imbedded is itself composed of comminuted fragments and young shells of the same, together with minuter Foraminifera. In the Oölitic (Secondary) formation, again, there are many beds which are shown by the microscope to have been chiefly composed of foraminiferal shells; and in those portions which exhibit the 'roe-stone' arrangement from which the rock derives its name (such as is beautifully displayed in many specimens of Bath stone and Portland stone), it is found by microscopic examination of transparent sections that each rounded concretion is composed of a series of concentric spheres formed by successive calcareous deposits upon a central nucleus, which is sometimes a foraminiferal shell. In these and similar calcareous formations, the entire materials of which were obviously furnished by the accumulation of animal remains, it not unfrequently happens that all traces of their origin are obliterated by 'metamorphic' action; and thus a crystalline marble, whose particles present not the least evidence of organic arrangement, may have been formed by the metamorphosis of chalky, Oölitic, or nummulitic limestone. Now there is very strong evidence that the vast mass of sub-crystalline 'carboniferous' limestone which forms our coal-basins has had a similar origin in foraminiferal and zoöphytic life, the traces of

which have been for the most part removed by the metamorphic action involved in its upheaval. For where it has sustained but little disturbance, the evidences of its organic (chiefly foraminiferal) origin are unmistakable. Thus in the great plains of Russia there are certain bands of limestone of this epoch, varying in thickness from fifteen inches to five feet, and frequently repeated through a vertical depth of two hundred feet over very wide areas, which are almost entirely composed of the extinct genus *Fusulina*. Again, those parts of the carboniferous limestone of Ireland which have undergone least disturbance can be plainly shown, by the examination of microscopic sections, to consist of the remains of Foraminifera, Polyzoa, fragments of corals, &c. And where, as not unfrequently happens, beds of this limestone are separated by clay seams, these are found to be loaded with 'microzoa' of various kinds, particularly Foraminifera (of which the *Saccamina* has come down to the present time), and the beautiful polyzoaries known as 'lace-corals.'

Mention has been already made of Professor Ehrenberg's very remarkable discovery that a large proportion (to say the least) of the *green sands* which present themselves in various stratified deposits, from the Silurian epoch to the Tertiary period, and which in certain localities constitute what is known as *the* Greensand formation (beneath the chalk), is composed of the *casts* of the interior of minute shells of Foraminifera and Mollusca, the shells themselves having entirely disappeared. The mineral material of these casts has not merely filled the chambers and their communicating passages, but has also penetrated, even to its minutest ramifications, the canal-system of the intermediate skeleton. The precise parallel to these deposits presents itself in certain spots of the existing sea-bottom, such as the Agulhas bank, near the Cape of Good Hope, where the dredge comes up laden with a green sand, which on microscopic examination proves to consist almost entirely of 'internal casts' of existing Foraminifera.

It is, however, in the case of the teeth, the bones, and the dermal skeleton of vertebrated animals that the value of microscopic inquiry becomes most apparent; since their structure presents so many characteristics which are subject to well-marked variations in their several classes, orders, and families that a knowledge of these characters frequently enables the microscopist to determine the nature of even the most fragmentary specimens with a positiveness which must appear altogether misplaced to such as have not studied the evidence. It was in regard to *teeth* that the possibility of such determinations was first made clear by the laborious researches of Professor Owen;[1] and the following may be given as examples of their value:—A rock-formation extends over many parts of Russia whose mineral characters might justify its being likened either to the *Old* or to the *New* Red Sandstone of this country, and whose position relatively to other strata is such that there is great difficulty in obtaining evidence from the usual sources as to its place in the series. Hence the only hope of settling this question (which was

[1] See his *Odontography*.

one of great practical importance, since, if the formation were *New* Red, coal might be expected to underlie it, whilst if *Old* Red, no reasonable hope of coal could be entertained) lay in the determination of the organic remains which this stratum might yield; but unfortunately these were few and fragmentary, consisting chiefly of teeth, which are seldom perfectly preserved. From the gigantic size of these teeth, together with their form, it was at first inferred that they belonged to saurian reptiles, in which case the sandstone would have been considered as New Red; but microscopic examination of their intimate structure unmistakably proved them to belong to a genus of fishes (*Dendrodus*) which is exclusively palæozoic, and thus decided that the formation must be Old Red. So, again, the microscopic examination of certain fragments of teeth found in a sandstone of Warwickshire disclosed a most remarkable type of tooth-structure (shown in fig. 752), which was also ascertained to exist in certain teeth that had been discovered in the 'Keupersandstein' of Würtemberg; and the identity or close resemblance of the animals to which these teeth belonged having been thus established, it became almost certain that the Warwickshire and Würtemberg sandstones were equivalent formations, a point of much geological importance. The next question arising out of this discovery was the nature of the animal (provisionally termed *Labyrinthodon*, a name expressive of the most peculiar feature in its dental structure) to which these teeth belonged. They had been referred, from external characters merely, to the order of saurian reptiles; but it is now clear that they were gigantic salamandroid Amphibia, having many points of relationship to *Ceratodus* (the Australian 'mud-fish'), which shows a similar, though simpler, dental organisation.

FIG. 752.—Section of tooth of *Labyrinthodon*.

The researches of Professor Quekett on the minute structure of *bone*[1] have shown that from the average size and form of the lacunæ, their disposition in regard to each other and to the Haversian canals, and the number and course of the canaliculi, the nature of even a minute fragment of bone may often be determined with a considerable approach to certainty, as in the following examples, among many which might be cited:—Dr. Falconer, the distinguished

[1] See his memoir on the 'Comparative Structure of Bone' in the *Trans. Micros. Soc.* ser. i. vol. ii.; and the *Catalogue of the Histological Museum of the Roy. Coll. of Surgeons*, vol. ii.

investigator of the fossil remains of the Himalayan region, and the discoverer of the gigantic fossil tortoise of the Sivalik hills, having met with certain small bones about which he was doubtful, placed them for minute examination in the hands of Professor Quekett, who informed him, on microscopic evidence, that they might certainly be pronounced reptilian, and probably belonged to an animal of the tortoise tribe; and this determination was fully borne out by other evidence, which led Dr. Falconer to conclude that they were toe-bones of his great tortoise. Some fragments of bone were found many years since, in a chalk-pit, which were considered by Professor Owen to have formed part of the wing-bones of a long-winged sea-bird allied to the albatross. This determination, founded solely on considerations derived from the very imperfectly preserved external forms of these fragments, was called in question by some other palæontologists, who thought it more probable that these bones belonged to a large species of the extinct genus *Pterodactylus*, a flying lizard whose wing was extended upon a single immensely prolonged digit. No species of pterodactyle, however, at all comparable to this in dimensions, was at that time known ; and the characters furnished by the configuration of the bones not being in any degree decisive, the question would have long remained unsettled had not an appeal been made to the microscopic test. This appeal was so decisive, by showing that the minute structure of the bone in question corresponded exactly with that of pterodactyle bone, and differed essentially from that of every known bird, that no one who placed much reliance upon that evidence could entertain the slightest doubt on the matter. By Professor Owen, however, the validity of that determination was questioned, and the bone was still maintained to be that of a bird, until the question was finally set at rest, and the value of the microscopic test triumphantly confirmed, by the discovery of undoubted pterodactyle bones of corresponding and even of greater dimensions in the same and other chalk quarries.

The microscopic examination of the sediments now in course of deposition on various parts of the great oceanic area, and especially of the large number of samples brought up in the 'Challenger' soundings, has led to this very remarkable conclusion—that the *débris* resulting from the degradation of continental land-masses are not carried far from their shores, being *entirely absent* from the bottom of the ocean-basins. The sediments *there* found were not of organic origin, mainly consist of volcanic *sands* and *ashes*, which are found in volcanic areas, and of *clay* that seems to have been produced by the disintegration of masses of pumice (vesicular lava), which, after long floating and dispersion by surface-drift or ocean-currents, have become water-logged and have sunk to the bottom. As no ordinary silicious sand is found anywhere save in the neighbourhood of continents and continental islands, and as all oceanic islands are the products of local volcanic outbursts, this absence of all trace of submerged continental land over the great oceanic area affords strong confirmation to the belief which geological evidence has been gradually tending to establish, that the sedimentary rocks which form the existing land were deposited in the immediate

neighbourhood of pre-existing land, whose degradation furnished their materials; and consequently that the *original* disposition of the great continental and oceanic areas was not very different from what it now is.[1] Further, the microscopic examination of these oceanic sediments reveals the presence of extremely minute particles, which seem to correspond in composition to *meteorites*, and which there is strong reason for regarding as 'cosmic dust' pervading the interplanetary spaces. Thus the application of the microscope to the study of these deposits brings us in contact with the greatest questions not only of terrestrial, but also of cosmical physics, and furnishes evidence of the highest value for their solution.

[1] See Professor Geikie's lecture on 'Geographical Evolution' in the *Proc. Roy. Geog. Soc.* July 1879; also 'A Search for Atlantis with the Microscope,' by the same author, *Nature*, 1882, p. 25.

CHAPTER XXIV

CRYSTALLISATION. POLARISATION. MOLECULAR COALESCENCE

ALTHOUGH by far the most numerous and most important applications of the microscope are those by which the structure and actions of organised beings are made known to us, yet there are many mineral substances which constitute both interesting and beautiful objects, being remarkable either for the elegance of their forms, or for the beauty of their colours, or for both combined. The natural forms of inorganic substances, when in any way symmetrical, are so in virtue of that peculiar arrangement of their molecules which is termed *crystallisation* ; and each subject which crystallises at all does so after a certain type or plan, the identity or difference of these types furnishing characters of primary value to the mineralogist. It does not follow, however, that the form of the crystal shall be constantly the same for each substance ; on the contrary, the same plan of crystallisation may exhibit itself under a great variety of forms ; and the study of these in such minute crystals as are appropriate subjects for observation by the microscope is not only a very interesting application of its powers, but is capable of affording some valuable hints to the designer. This is particularly the case with crystals of *snow*, which belong to the 'hexagonal system,' the basis of every figure being a hexagon of six rays ; for these rays 'become incrusted with an endless variety of secondary formations of the same kind, some consisting of thin laminæ alone, others of solid but translucent prisms heaped one upon another, and others gorgeously combining laminæ and prisms in the richest profusion,'[1] the angles by which these figures are bounded being invariably 60° or 120°. Beautiful arborescent forms are not unfrequently produced by the peculiar mode of aggregation of individual crystals ; of this we have often an example on a large scale on a frosted window ; but microscopic crystallisations sometimes present the same curious phenomenon (fig. 753). The Mineral Kingdom presents many interesting microscopic objects : avanturine, lapis lazuli, crystallised silver, &c. make very good specimens ; whilst thin sections of granite, gabbro, and other rocks of the more or less regularly crystalline

[1] Glaisher on 'Snow-crystals in 1855,' *Quart. Journ. Micros. Sci.* vol. iii. 1855, p. 179.

structure, also of agate, arragonite, piedmontite, zeolite, and other minerals, are very beautiful objects for the polariscope.

The actual process of the *formation of crystals* may be watched under the microscope with the greatest facility, all that is necessary being to lay on a slip of glass, previously warmed, a saturated solution of the salt, and to incline the stage in a slight degree, so that the drop shall be thicker at its lower than at its upper edge. The crystallisation will speedily begin at the upper edge, where the proportion of liquid to solid is most quickly reduced by evaporation, and will gradually extend downwards. If it should go on too slowly, or should cease altogether, whilst yet a large proportion of the liquid remains, the slide may be again warmed, and the part already solidified may be re-dissolved, after which the process will recommence with increased rapidity. This interesting spectacle may be watched under any microscope, but the instrument specially designed by O. Lehmann[1] is particularly adapted to studies of this kind. The degree of heat can be varied at will. The phenomena become far more striking, however, when the crystals, as they come into being, are made to stand out bright upon a dark ground, by the use of the spot lens, the paraboloid, or any other form of black-ground illumination; still more beautiful is the spectacle when the polarising apparatus is employed, so as to invest the crystals with the most gorgeous variety of hues.

FIG. 753.—Crystallised silver.

By chemically precipitating crystalline products under the microscope we can obtain a still deeper insight into the crystallisation process. One of the earliest workers at this subject was Link in 1839. He observed that the precipitates first appeared in the form of very minute *liquid* globules, which ran together and eventually by almost insensible gradations passed into the solid and crystalline condition. In fact, the deposition of crystalline precipitates out of solutions seems mostly to occur in this way. Carbonate of lime is a good instance of this, the liquid globules finally arranging themselves into the little rhombohedra peculiar to the substance. On the temperature of the glass slide during the solidification depend the size and arrangement of the crystals. Thus *santonine*, when crystallising rapidly on a very hot plate, forms large crystals radiating from centres without any undulations; when the heat is less considerable the crystals are smaller, and show concentric waves of very decided form (fig. 754); but when the slip of glass is cool the crystals are exceedingly minute. In the case of sulphate of copper, Mr. R. Thomas[2] succeeded, by keeping the slide at a

[1] 'Ueber Krystallanalyse,' *Pogg. Ann.* Bd. xiii. 1881, pp. 506–522.

[2] See his paper 'On the Crystallisation at various temperatures of the Double

temperature of from 80° to 90°, in obtaining most singular and beautiful forms of *spiral* crystallisation, such as that represented in fig. 755. Mr. Slack has shown that a great variety of spiral and curved forms can be obtained by dissolving metallic salts, or salicine, santonine, &c. in water containing 3 or 4 per cent. of colloid silica. The nature of the action that takes place may be understood by allowing a drop of the silica solution to dry upon a slide: the result of which will be the production of a complicated series of cracks, many of them curvilinear. When a group of crystals in formation tend to radiate from a centre, the contractions of the silica will often give them a tangential pull. Another action of the silica is to introduce a very slight curling with just enough eleva-



FIG. 754.—Radiating crystallisation of santonine.

tion above the slide to exhibit fragments of Newton's rings, when it is illuminated with Powell and Lealand's modification of Professor Smith's dark-ground illuminator for high powers, and viewed with a $\frac{1}{8}$th objective. With crystalline bodies these actions add to the variety of colours to be obtained with the polariscope, the best slides exhibiting a series of tertiary tints.[1] Very interesting results may often be obtained from a mixture of two or more salts, and some of the double salts give forms of peculiar beauty. O. Lehmann has done excellent work in this department; but reference must be had to his papers in the 'Zeitschrift für Krystallographie' for a description of the phenomena such mixtures exhibit. The fol-

Salt, Sulphate of Magnesia and Sulphate of Zinc,' in *Quart. Journ. Micros. Sci.* n.s. vi. pp. 137, 177. See also H. N. Draper on 'Crystals for the Micro-polariscope,' in *Intellectual Observer*, vol. vi. 1865 p. 437.

[1] 'On the Employment of Colloid Silica in the preparation of Crystals for the Polariscope,' in Monthly Micros. Journ. v. p. 50.

lowing list specifies the salts and other substances whose crystalline forms are most interesting. When these are viewed with polarised light some of them exhibit a beautiful variety of colours of their own, whilst others require the interposition of the selenite plate for the development of colour. The substances marked *d* are distinguished by the curious property termed *dichroism*, which was first noticed by Dr. Wollaston, and specially investigated by Sir D. Brewster. This property consists in the exhibition of different colours by these crystals, according to the direction in which the light is transmitted through them, a crystal of chloride of platinum, for example, appearing of a deep red when the light passes along its axis, and of a vivid green when the light is transmitted in the opposite direction, with various intermediate shades. It is only possessed by doubly refracting substances; and it depends on the

FIG. 755.—Spiral crystallisation of sulphate of copper.

absorption of some of the coloured rays of the light which is polarised during its passage through the crystal, so that the two pencils formed by double refraction become differently coloured, the degree of difference being regulated by the inclination of the incident ray to the axis of double refraction.

Acetate of Copper, *d*
" Manganese
" Soda
" Zinc
Alum
Arseniate of Potass
Asparagine
Aspartic Acid
Bicarbonate of Potass
Bichromate of Potass
Bichloride of Mercury
Binoxalate of Chromium and Potass
Bitartrate of Ammonia
" Lime
" Potass
Boracic Acid
Borate of Ammonia
" Soda (borax)
Carbonate of Lime (from urine of horse)
" Potass
" Soda
Chlorate of Potass
Chloride of Barium
" Cobalt

Chloride of Copper and Ammonia
" Palladium, *d*
" Sodium
Cholesterine
Chromate of Potass
Cinchonoidine
Citric Acid
Cyanide of Mercury
Hippuric Acid
Hypermanganate of Potass
Iodide of Potassium
" Quinine
Mannite
Margarine
Murexide
Muriate of Ammonia
Nitrate of Ammonia
" Barytes
" Bismuth
" Copper
" Potass
" Soda
" Strontian
" Uranium
Oxalic Acid
Oxalate of Ammonia
" Chromium
" Chromium and Ammonia, *d*
" Chromium and Potass, *d*
" Lime
" Potass
" Soda
Oxalurate of Ammonia
Phosphate of Ammonia
" Ammoniaco-Magnesian (triple, of urine)
" Lead, *d*
" Soda
Platino-chloride of Thallium
Platino-cyanide of Ammonia, *d*
Prussiate of Potass (red)
" " (yellow)
Quinidine
Salicine
Saliginine
Santonine
Stearine
Sugar
Sulphate of Ammonia
" Cadmium
" Copper
" Copper and Ammonia
" Copper and Magnesia
" Copper and Potass
" Iron
" Iron and Cobalt
" Magnesia
" Nickel
" Potassa
" Soda
" Zinc
Tartaric Acid
Tartrate of Soda
Uric Acid
Urate of Ammonia
" Soda

It not unfrequently happens that a remarkably beautiful specimen of crystallisation develops itself, which the observer desires to keep for display. In order to do this successfully, it is necessary to exclude the air; and Mr. Warrington recommends castor oil as the best preservative. A small quantity of this should be poured on the crystallised surface, a gentle warmth applied, and a thin glass cover then laid upon the drop and gradually pressed down; and after the superfluous oil has been removed from the margin a coat of gold-size or other varnish is to be applied. Although most of the objects furnished by vegetable and animal structures, which are advantageously shown by polarised light, have been already noticed in their appropriate places, it will be useful here to recapitulate the principal, with some additions.

Vegetable

Cuticles, Hairs, and Scales, from Leaves
Fibres of Cotton and Flax
Raphides
Spiral cells and vessels
Starch-grains
Wood, longitudinal sections of, mounted in balsam

Animal

Fibres and Spicules of Sponges
Polypidoms of Hydrozoa
Spicules of Gorgonise
Polyzoaries
Tongues (Palates) of Gasteropods mounted in balsam
Cuttle-fish bone
Scales of Fishes
Sections of Egg-shells
" Hairs
" Quills
" Horns
" of Shells
" Skin
" Teeth
" Tendon, longitudinal

Molecular Coalescence.—Remarkable modifications are shown in the ordinary forms of crystallisable substances, when the aggregation of the inorganic particles takes place in the presence of certain kinds of organic matter; and a class of facts of great interest in their bearing upon the mode of formation of various calcified structures in the bodies of animals was brought to light by the ingenious researches of Mr. Rainey,[1] whose method of experimenting essentially consisted in bringing about a slow decomposition of the salts of lime contained in gum-arabic by the agency of subcarbonate of potash. The result is the formation of spheroidal concretions of carbonate of lime, which progressively increase in diameter at the expense of an amorphous deposit which at first intervenes between them, two such spherules sometimes coalescing to produce 'dumb-bells,' whilst the coalescence of a larger number gives rise to the mulberry-like body shown in fig. 756, *b*. The particles of such composite spherules appear subsequently to undergo rearrangement according to a definite plan, of which the stages are shown at *c* and *d*; and it is upon this plan that the further increase takes place, by which such larger concretions as are shown at *a*, *a* are gradually produced. The structure of these, especially when examined by polarised light, is found to correspond very closely with that of the small calculous concretions which are common in the urine of the horse, and which were at one time supposed to have a matrix of cellular structure. The small calcareous concretions termed *otoliths*, or ear-stones, found in the auditory sacs of fishes, present an arrangement of their particles essentially the same. Similar concretionary spheroids have already been mentioned as occurring in the skin of the shrimp and other imperfectly calcified shells of Crustacea; they occur also in certain imperfect layers of the shells of Mollusca; and we have a very good example of them in the outer layer of the envelope of what is commonly known as a 'soft egg,' or an 'egg without shell,' the calcareous deposit in the fibrous matting already described being here insufficient to solidify it. In the external layer of an ordinary egg-shell, on the other hand, the concretions have enlarged themselves by the progressive accretion of calcareous particles, so as to form a continuous layer, which consists of a series of polygonal plates resembling those



FIG. 756.—Artificial concretions of carbonate of lime.

[1] See his treatise 'On the Mode of Formation of the Shells of Animals, of Bone, and of several other structures, by a process of Molecular Coalescence, demonstrable in certain artificially formed products,' 1858; and his 'Further Experiments and Observations' in *Quart. Journ. Micros. Sci.* n.s. vol. i. 1861, p. 28.

of a tessellated pavement. In the solid 'shells' of the eggs of the ostrich and cassowary this concretionary layer is of considerable thickness; and vertical as well as horizontal sections of it are very interesting objects, showing also beautiful effects of colour under polarised light. And from the researches of Professor W. C. Williamson on the scales of fishes, there can be no doubt that much of the calcareous deposit which they contain is formed upon the same plan.

This line of inquiry has been contemporaneously pursued by Professor Harting, of Utrecht, who, working on a plan fundamentally the same as that of Mr. Rainey (viz. the slow precipitation of insoluble salts of lime in the presence of an organic 'colloid'), has not only confirmed but greatly extended his results, showing that with *animal* colloids (such as egg-albumen, blood-serum, or a solution of gelatine) a much greater variety of forms may be thus produced, many of them having a strong resemblance to calcareous structures hitherto known only as occurring in the bodies of animals of various classes. The mode of experimenting usually followed by Professor Harting was to cover the hollow of an ordinary porcelain plate with a layer of the organic liquid to the depth of from 0·4 to 0·6 of an inch, and then to immerse in the border of the liquid, but at diametrically opposite points, the solid salts intended to act on one another by double decomposition, such as muriate, nitrate, or acetate of lime, and carbonate of potash or soda; so that, being very gradually dissolved, the two substances may come slowly to act upon each other, and may throw down their precipitate in the midst of the 'colloid.' The whole is then covered with a plate of glass, and left for some days in a state of perfect tranquillity; when there begins to appear at various spots on the surface minute points reflecting light, which gradually increase and coalesce, so as to form a crust that comes to adhere to the border of the plate; whilst another portion of the precipitate subsides, and covers the bottom of the plate. Round the two spots where the salts are placed in the first instance the calcareous deposits have a different character: so that in the same experiment several very distinct products are generally obtained, each in some particular spot. The length of time requisite is found to vary with the temperature, being generally from two to eight weeks. By the introduction of such a colouring matter as madder, logwood, or carmine, the concretions take the hue of the one employed. When these concretions are treated with dilute acid, so that their calcareous particles are wholly dissolved out, there is found to remain a basis substance which preserves the form of each; this, which consists of the 'colloid' somewhat modified, is termed by Harting *calco-globuline*. Besides the globular concretions with the peculiar concentric and radiating arrangement obtained by Mr. Rainey (fig. 756), Professor Harting obtained a great variety of forms bearing some resemblance to the following: 1. The 'discoliths' and 'cyatholiths' of Professor Huxley. 2. The tuberculated 'spicules' of *Alcyonaria*, and the very similar spicules in the mantle of some species of *Doris*. 3. Lamellæ of 'prismatic shell-substance,' which are very closely imitated by crusts formed of flattened polyhedra, found on the surface of the 'colloid.' 4. The

spheroidal concretions which form a sort of rudimentary shell within the body of *Limax*. 5. The sinuous lamellæ which intervene between the parallel plates of the 'sepiostaire' of the *cuttle-fish*, the imitation of this being singularly exact. 6. The calcareous concretions that give solidity to the 'shell' of the bird's egg, the semblance of which Professor Harting was able to produce *in situ* by dissolving away the calcareous component of the egg-shell by dilute acid, then immersing the entire egg in a concentrated solution of chloride of calcium, and transferring it thence to a concentrated solution of carbonate of potass, with which, in some cases, a little phosphate of soda was mixed.[1] Other forms of remarkable regularity and definiteness, differing entirely from anything that ordinary crystallisation would produce, but not known to have their parallels in living bodies, have been obtained by Professor Harting. Looking to the relations between the calcareous deposits in the scales of fishes and those by which bones and teeth are solidified, it can scarcely be doubted that the principle of 'molecular coalescence' is applicable to the latter, as well as to the former; and that an extension and variation of this method of experimenting would throw much light on the process of ossification and tooth formation. The inquiry has been further prosecuted by Dr. W. M. Ord, with express reference to the formation of urinary and other calculi.[2]

Micro-chemistry of Poisons.—By a judicious combination of microscopical with chemical research, the application of reagents may be made effectual for the detection of poisonous or other substances in quantities far more minute than have been previously supposed to be recognisable. Thus it is stated by Dr. Wormley[3] that micro-chemical analysis enables us by a very few minutes' labour to recognise with unerring certainty the reaction of the $\frac{1}{100000}$th part of a grain of either hydrocyanic acid, mercury, or arsenic; and that in many other instances we can easily detect by its means the presence of very minute quantities of substances, the true nature of which could only be otherwise determined in comparatively large quantity, and by considerable labour. This inquiry may be prosecuted, however, not only by the application of ordinary chemical tests under the microscope, but also by the use of other means of recognition which the use of the microscope affords. Thus it has been shown that by the careful sublimation of arsenic and arsenious acid, the sublimates being deposited upon small discs of thin glass, these are distinctly recognisable by the forms they present under the microscope (especially the binocular) in extremely minute quantities; and that the same method of procedure may be applied to the volatile metals, mercury, cadmium, selenium, tellurium, and some of their salts, and to some other volatile bodies, as sal-ammoniac, camphor, and sulphur. The method of sublimation was afterwards extended to the vegetable

[1] See Prof. Harting's *Recherches de Morphologie synthétique sur la production artificielle de quelques Formations Calcaires Inorganiques, publiées par l'Académie Royale Néerlandaise des Sciences*, Amsterdam, 1872; and *Quart. Journ. Micros. Sci.* xii. p. 118.

[2] See his treatise *On the Influence of Colloids upon Crystalline Form and Cohesion*, London, 1879.

[3] *Micro-chemistry of Poisons.*

alkaloids, such as morphine, strychnine, veratrine, &c. And su
quently it was shown that the same method could be furthe
tended to such animal products as the constituents of the b
and of urine, and to volatile and decomposable organic substa
generally. By the careful prosecution of micro-chemical inq
especially with the aid of the spectroscope (where admissible)
detection of poisons and other substances in very minute quan
can be accomplished with a facility and certainty such as
formerly scarcely conceivable.

APPENDICES AND TABLES

USEFUL TO THE MICROSCOPIST

APPENDIX A

TABLE OF NATURAL SINES

°	0′	15′=¼°	30′=½°	45′=¾°	°	0′	15′=¼°	30′=½°	45′=¾°
0	·0000	·0044	·0087	·0131	46	·7193	·7224	·7254	·7284
1	·0174	·0218	·0262	·0305	47	·7313	·7343	·7373	·7402
2	·0349	·0393	·0436	·0480	48	·7431	·7460	·7489	·7518
3	·0523	·0567	·0610	·0654	49	·7547	·7576	·7604	·7632
4	·0697	·0741	·0784	·0828	50	·7660	·7688	·7716	·7744
5	·0871	·0915	·0958	·1002	51	·7771	·7799	·7826	·7853
6	·1045	·1089	·1132	·1175	52	·7880	·7907	·7933	·7960
7	·1219	·1262	·1305	·1348	53	·7986	·8012	·8038	·8064
8	·1392	·1435	·1478	·1521	54	·8090	·8116	·8141	·8166
9	·1564	·1607	·1650	·1693	55	·8191	·8216	·8241	·8266
10	·1736	·1779	·1822	·1865	56	·8290	·8315	·8339	·8363
11	·1908	·1951	·1994	·2036	57	·8387	·8410	·8434	·8457
12	·2079	·2122	·2164	·2207	58	·8480	·8503	·8526	·8549
13	·2249	·2292	·2334	·2377	59	·8572	·8594	·8616	·8638
14	·2419	·2461	·2504	·2546	60	·8660	·8682	·8703	·8725
15	·2588	·2630	·2672	·2714	61	·8746	·8767	·8788	·8809
16	·2756	·2798	·2840	·2882	62	·8829	·8850	·8870	·8890
17	·2924	·2965	·3007	·3049	63	·8910	·8930	·8949	·8969
18	·3090	·3132	·3173	·3214	64	·8988	·9007	·9026	·9044
19	·3256	·3297	·3338	·3379	65	·9063	·9081	·9100	·9118
20	·3420	·3461	·3502	·3543	66	·9135	·9153	·9171	·9188
21	·3584	·3624	·3665	·3705	67	·9205	·9222	·9239	·9255
22	·3746	·3786	·3827	·3867	68	·9272	·9288	·9304	·9320
23	·3907	·3947	·3987	·4027	69	·9336	·9351	·9367	·9382
24	·4067	·4107	·4147	·4187	70	·9397	·9412	·9426	·9441
25	·4226	·4266	·4305	·4344	71	·9455	·9469	·9483	·9497
26	·4384	·4423	·4462	·4501	72	·9510	·9524	·9537	·9550
27	·4540	·4579	·4617	·4656	73	·9563	·9576	·9588	·9600
28	·4695	·4733	·4771	·4810	74	·9613	·9624	·9636	·9648
29	·4848	·4886	·4924	·4962	75	·9659	·9670	·9681	·9692
30	·5000	·5038	·5075	·5113	76	·9703	·9713	·9724	·9734
31	·5150	·5188	·5225	·5262	77	·9744	·9753	·9763	·9772
32	·5299	·5336	·5373	·5410	78	·9781	·9790	·9799	·9808
33	·5446	·5483	·5519	·5556	79	·9816	·9824	·9832	·9840
34	·5592	·5628	·5664	·5700	80	·9848	·9855	·9863	·9870
35	·5736	·5771	·5807	·5842	81	·9877	·9884	·9890	·9896
36	·5878	·5913	·5948	·5983	82	·9903	·9909	·9914	·9920
37	·6018	·6053	·6088	·6122	83	·9925	·9931	·9936	·9940
38	·6157	·6191	·6225	·6259	84	·9945	·9950	·9954	·9958
39	·6293	·6327	·6361	·6394	85	·9962	·9966	·9969	·9972
40	·6428	·6461	·6494	·6528	86	·9976	·9978	·9981	·9984
41	·6560	·6593	·6626	·6659	87	·9986	·9988	·9990	·9992
42	·6691	·6724	·6756	·6788	88	·9994	·9995	·9996	·9998
43	·6820	·6852	·6883	·6915	89	·9998	·9999	·9999	1·0000
44	·6946	·6978	·7009	·7040	90	1·0000			
45	·7071	·7102	·7132	·7163					

Note.—The sine of any given angle is the length of the perpendicular opposite the given angle in a right-angled triangle which contains the given angle divided by the length of the hypotenuse. The above table is constructed on the principle that the hypotenuse is always equal to unity, by which means the fraction is got rid of, as the denominator may be left out. Thus,

$$\text{Sin } 30° = \frac{\text{perpendicular}}{\text{hypotenuse}} = \frac{\frac{1}{2}}{1} = \cdot 5.$$

APPENDIX B

TABLE OF REFRACTIVE INDICES

(Suitable for experiment and study for obtaining media for mounting, and supplying unit substances for homogeneous lens systems.)

Substance		Refractive Index
Water	μ_D	= 1·333
Saliva	μ_E	1·339
Sea-water	μ_E	1·343
Human blood	μ_E	1·354
Alum (sat. sol.)	μ_E	1·356
Ether (50° Fahr.)	μ_D	1·359
Albumen	μ_E	1·36
Absolute Alcohol	μ_D	1·366
Oil of Ambergris	μ_E	1·368
Salt (sat. sol.)	μ_E	1·375
Fluor Spar	μ_E	1·436
Spermaceti (melted)	μ_E	1·444
Bees-wax (melted)	μ_E	1·453
Oil of Olives (sp. gr. 0·913)	μ_E	1·470
Borax	μ_E	1·475
Naphtha	μ_E	1·475
Oil of Turpentine (sp. gr. ·885)	μ_E	1·478
Oil of Linseed (sp. gr. ·932)	μ_D	1·482
Castor Oil	μ_E	1·487
Bees-wax (cold)	μ_E	1·492
Chloride of Tin	μ_D	1·503
Spermaceti (cold)	μ_E	1·503
Oil of Cinnamon	μ_F	1·508
Oil of Cedar	μ_D	1·510
Gum Arabic	μ_E	1·512
Dammar	μ_D	1·520
Oil of Cloves	μ_D	1·530
Sugar	μ_D	1·535
Felspar	μ_F	1·536 to 1·764
Cedrene	μ_D	1·539
Canada Balsam	μ_D	1·540
Oil of Fennel	μ_D	1·544
Rock Crystal	μ_D	1·547
Rock Salt (sp. gr. 2·143)	μ_D	1 555
Nitro-benzene	μ_D	1·558
Styrax	μ_D	1·582
Benzylaniline	μ_D	1·611
Methyldiphenylamine	μ_D	1·616
Balsam of Tolu	μ_F	1·618
Oil of Cassia	μ_E	1·626 to 1·647
Quinoline	μ_D	1·633
Tourmalin (ordinary ray)	μ_D	1·636
Iceland Spar (ordinary ray)	μ_F	1·654
Monobromide of Naphthalin	μ_D	1·657
Bromide of Antimony (approximately)	μ_D	1·680
Piperine	μ_D	1·684

Bisulphide of Carbon	μ_D	1·687
Quinidine (approximately)	μ_D	1·700
Zircon	μ_E	1·782 to 2·015
Carbonate of Lead	μ_D	1·81 to 2·08
Borate of Lead	μ_A	1·866
Sulphur (melted)	μ_E	2·148
Phosphorus	μ_D	2·224
Realgar (artificial)	μ_E	2·549
Diamond (sp. gr. 3·4)	μ_E	2·47
Chromate of Lead	μ_D	2·50 to 2·97

Glass

Crown	μ_D	1·51 to 1·53
Plate	μ_D	1·516
Flint	μ_D	1·54 to 1 62
Dense Flint	μ_D	1·650
Extra Dense Flint	μ_D	1·710
Jena Glass: Boro-silicate Crown	μ_D	1·51
Jena Glass: Phosphate Crown	μ_D	1·51 to 1·56
Jena Glass: Barium Silicate Crown	μ_D	1·54 „ 1·60
Jena Glass: Boro-silicate Flint	μ_D	1·55 „ 1·57
Jena Glass: Borate Flint	μ_D	1·55 „ 1·68
Jena Glass: Barium Phosphate Crown	μ_D	1·57 „ 1·59
Jena Glass: Very heavy Silicate Flint	μ_D	1·96
Glass of Antimony	μ_D	2·216

. . . . .

APPENDIX C

TABLE OF ENGLISH MEASURES AND WEIGHTS, WITH THE METRICAL EQUIVALENTS

The following are calculated from the values of the metre, determi by Col. Clarke, R.E. (1867), as equal to 39·370432 inches; and the wei of a cubic foot of water at 62° F. found by Mr. H. J. Chaney (1890) to equal to 62·278601 lb. avoirdupois.

LENGTH

Inch	= 2·53998	Centimetres.
Foot = 12 inches	= 3·04797	Decimetres.
Yard = 3 feet	= ·91439	Metre.
Fathom = 2 yards	= 1·82878	„
Pole = 5½ yards	= 5·02915	Metres.
Chain = 4 poles	= 2·01166	Decametres.
Furlong = 10 chains	= 2·01166	Hectometres.
Mile = 8 furlongs	= 1·60933	Kilometre.

SUPERFICIES

Square Inch	= 6·45148	Square Centimetres.
	= ·00645	Milliare.
„ Foot = 144 Square Inches	= ·92901	„
„ Yard = 9 „ Feet	= 8·36112	Milliares.
	= ·83611	Centiare.
Perch = 30¼ „ Yards	= 2·52924	Deciares.
Rood = 40 Perches . .	= 10·11696	Ares.
Acre = 4 Roods . . .	= 40·46784	„

VOLUME

Cubic Inch	=	·01638	Millistere.
„ Foot . . = 1728 Cubic Inches	=	2·83161	Centisteres.
„ Yard . . = 27 „ Feet	=	7·64534	Decisteres.

CAPACITY

Apothecaries'

Minim, ♏ . . . =	·05920	Cubic Centimetre or Millilitre.
Drachm, f ʒ = 60 ♏ =	3·55209	„ Centimetres or Millilitres.
Ounce, f ℥ = 8 f ʒ =	28·41671	„ „ = 2·84167 Centilitre
Pint, O . = 20 f ℥ =	568·33415	„ „ = 5·68334 Decilitres
Gallon, C = 8 O =	4·54667	„ Decimetres, Millisteres, or Litr

Imperial

Gill	= 142·08354	Cubic Centimetres	= 1·42083 Decilitre
Pint. . = 4 gills	= 568·33415	„ „	= 5·68334 Decilitre
Quart . = 2 pints	= 1·13667	„ Decimetre, Millistere, or Litre.	
Gallon . = 4 quarts	= 4·54667	„ Decimetres, Millisteres, or Litr	
Pecks . = 2 gallons	= 9·09335	„ „ „ „	
Bushel = 4 pecks	= 3·63733	Decalitres.	
Quarter = 8 bushels	= 2·90986	Hectolitres.	

Weight

Apothecaries'

Grain, gr.		=	6·48799 Centigrammes.
Scruple, ℈	=	20 gr. =	1·29760 Gramme.
Drachm, ʒ	= 3 ℈ =	60 gr. =	3·89280 Grammes.
Ounce, ℥	= 8 ʒ =	480 gr. =	3·11424 Decagrammes.
Pound, lb.	= 12 ℥ =	5760 gr. =	3·73708 Hectogrammes.

Avoirdupois

Drachm, dr.	= 27·34375 gr. =	1·77406	Gramme.
Ounce, oz.	= 16 dr. = 437·5 gr. =	2·83850	Decagrammes.
Pound, lb.	= 16 oz. = 7000 gr. =	4·54160	Hectogrammes.
Quarter, qr.	= 28 lb. =	12·71647	Kilogrammes.
Hundredweight, cwt.	= 4 qr. =	1·01732	Centner.
Ton	= 20 cwt. =	1·01732	Tonneau.

1 lb. Avoirdupois = ·822857 lb. Troy or Apothecaries'.
1 lb. Troy or Apothecaries' = 1·21527 lb. Avoirdupois.

TABLE OF METRIC MEASURES AND WEIGHTS, WITH THEIR ENGLISH EQUIVALENTS

The metre was originally intended to be the $\frac{1}{10000000}$th part of the distance from the pole of the earth to the equator, measured along a certain meridian, but owing to an error its length is too short. The metre is therefore the length of a definite standard in Paris.

Length

Micron, i.e. μ	= $\frac{1}{1000}$ Millimetre	=	·00003937 Inch.
Millimetre	= $\frac{1}{10}$ Centimetre	=	·03937 „
Centimetre	= $\frac{1}{10}$ Decimetre	=	·39370 „
Decimetre	= $\frac{1}{10}$ Metre	=	3·93704 Inches.
Metre	= Unit	=	3·28087 Feet.
		=	1·093623 Yard.
Decametre	= 10 Metres	=	1·98840 Pole.
Hectometre	= 10 Decametres	=	4·97101 Chains.
Kilometre	= 10 Hectometres	=	4·97101 Furlongs.
		=	·6213767 Statute Mile.

Superficies

Milliare	= 10 Sq. Decimetres =	1·07641	Sq. Ft. = 155·00 Sq. In.
Centiare	= 1 „ Metre =	1·19601	Square Yard.
Deciare	= 10 „ Metres =	11·96011	„ Yards.
Are = Unit	= 1 „ Decametre =	119·60115	„ „
Hectare	= 1 „ Hectometre =	2·47110	Acres.

Volume

Millistere	= 1 Cubic Decimetre =	61·02537	Cubic Inches.
Centistere	= 10 „ Decimetres =	610·25368	„ „
Decistere	= 100 „ „ =	3·53156	„ Feet.
Stere = Unit	= 1 „ Metre =	1·30798	„ Yard.
Decastere	= 10 „ Metres =	13·07985	„ Yards.
Hectostere	= 10 Decasteres =	130·79854	„ „

Capacity

Millilitre	= Cubic Centimetre	= 16·89148 ♏, Minims.			
Centilitre	= 10 „ Centimetres	= 2·81525 f ʒ, Drachms.			
Decilitres	= 100 „ „	= 3·51906 f ʒ, Ounces	= ·70381	Imp. Gill.	
Litre .	= Millistere . .	= 1·75958 O, Pint	= 1·75953	„	Pint.
Decalitre	= 10 Litres . .	= 2·19941 C, Gals.	= 2·19941	„	Gals.
Hectolitre	= 10 Decalitres		= 2·74926	..	Bush.
Kilolitre	= 10 Hectolitres = 1 Stere = 1 Cubic Metre		= 3·43658	..	Qrs.

Weight

Milligramme	= $\frac{1}{10}$ Centigramme	= ·01541	Grain.
Centigramme	= $\frac{1}{10}$ Decigramme	= ·15413	„
Decigramme	= $\frac{1}{10}$ Gramme	= 1·54131	„
Gramme .	= Unit	= 15·4130811036	Grains.

		Apothecaries'	*Avoirdupois*
Decagramme	= 10 Grammes	= 2·56885 ʒ	= 5·63678 dr.
Hectogramme	= 10 Decagrammes	= 3·21106 ℥	= 3·52299 oz.
Kilogramme	= 10 Hectogrammes	= 2·67588 lb.	= 2·2018687291 lb.
Myriagramme	= 10 Kilogrammes		= 22·01869 „
Quintal . .	= 10 Myriagrammes		= 1·96595 cwt.
Tonneau . .	= 10 Quintals		= ·98298 ton.

Note.—The Centner of 5 myriagrammes, or 110·1 lb., is sometimes called a Quintal. A Centner of 100 lb. and a Ton of 2000 lb. are used in the United States. The Tonneau is sometimes called a Millier.

In the United States the measures for length, surface, volume, and weight are the same as the English. Those for dry measure are derived from the 'Winchester' gallon, which = 268·8 cubic inches; and those for fluid measure from the 'Winchester' fluid gallon, which = 231 cubic inches.

Winchester into Metric

Dry		*Fluid*	
Pint . .	= 5·50590 Decilitres.	Gill . .	= 1·18291 Decilitre.
Gallon .	= 4·40472 Litres.	Pint . .	= 4·73163 Decilitres.
Peck . .	= 8·80944 „	Quart .	= 9·46326 „
Bushel .	= 3·52377 Decalitres.	Gallon .	= 3·78530 Litres.
Quarter .	= 2·81902 Hectolitres.		

Metric into Winchester

Dry		*Fluid*	
Litre . .	= 1·81624 Pint.	Decilitre .	= ·84537 Gill.
Decalitre	= 1·13515 Peck.	Litre . .	= 1·05672 Quart.
Hectolitre	= 2·83787 Bushels.	Decalitre	= 2·64179 Gallons.
Kilolitre .	= 3·54734 Quarters.		

United States fluid gallon = ·832544 English gallon.
English gallon . . . = 1·201138 United States fluid gallon.
United States dry gallon = ·968778 English gallon.
English gallon . . . = 1·032228 United States dry gallon.

CONVERSION OF BRITISH AND METRIC MEASURES

LINEAL

Micromillimetres &c. into Inches &c.

μ	ins.	mm.	ins.	mm.	ins.
1	·000039	*1*	·039370	*51*	2·007892
2	·000079	*2*	·078741	*52*	2·047262
3	·000118	*3*	·118111	*53*	2·086633
4	·000157	*4*	·157482	*54*	2·126003
5	·000197	*5*	·196852	*55*	2·165374
6	·000236	*6*	·236223	*56*	2·204744
7	·000276	*7*	·275593	*57*	2·244115
8	·000315	*8*	·314963	*58*	2·283485
9	·000354	*9*	·354334	*59*	2·322855
10	·000394	*10* (1 cm.)	·393704	*60* (6 cm.)	2·362226
11	·000433	*11*	·433075	*61*	2·401596
12	·000472	*12*	·472445	*62*	2·440967
13	·000512	*13*	·511816	*63*	2·480337
14	·000551	*14*	·551186	*64*	2·519708
15	·000591	*15*	·590556	*65*	2·559078
16	·000630	*16*	·629927	*66*	2·598449
17	·000669	*17*	·669297	*67*	2·637819
18	·000709	*18*	·708668	*68*	2·677189
19	·000748	*19*	·748038	*69*	2·716560
20	·000787	*20* (2 cm.)	·787409	*70* (7 cm.)	2·755930
21	·000827	*21*	·826779	*71*	2·795301
22	·000866	*22*	·866150	*72*	2·834671
23	·000906	*23*	·905520	*73*	2·874042
24	·000945	*24*	·944890	*74*	2·913412
25	·000984	*25*	·984261	*75*	2·952782
26	·001024	*26*	1·023631	*76*	2·992153
27	·001063	*27*	1·063002	*77*	3·031523
28	·001102	*28*	1·102372	*78*	3·070894
29	·001142	*29*	1·141743	*79*	3·110264
30	·001181	*30* (3 cm.)	1·181113	*80* (8 cm.)	3·149635
31	·001220	*31*	1·220483	*81*	3·189005
32	·001260	*32*	1·259854	*82*	3·228375
33	·001299	*33*	1·299224	*83*	3·267746
34	·001339	*34*	1·338595	*84*	3·307116
35	·001378	*35*	1·377965	*85*	3·346487
36	·001417	*36*	1·417336	*86*	3·385857
37	·001457	*37*	1·456706	*87*	3·425228
38	·001496	*38*	1·496076	*88*	3·464598
39	·001535	*39*	1·535447	*89*	3·503968
40	·001575	*40* (4 cm.)	1·574817	*90* (9 cm.)	3·543339
41	·001614	*41*	1·614188	*91*	3·582709
42	·001654	*42*	1·653558	*92*	3·622080
43	·001693	*43*	1·692929	*93*	3·661450
44	·001732	*44*	1·732299	*94*	3·700820
45	·001772	*45*	1·771669	*95*	3·740191
46	·001811	*46*	1·811040	*96*	3·779561
47	·001850	*47*	1·850410	*97*	3·818932
48	·001890	*48*	1·889781	*98*	3·858302
49	·001929	*49*	1·929151	*99*	3·897673
50	·001969	*50* (5 cm.)	1·968522	*100* (10 cm. = 1 decim.)	
60	·002362				
70	·002756				
80	·003150				
90	·003543				
100	·003937				
200	·007874				
300	·011811				
400	·015748				
500	·019685				
600	·023622				
700	·027559				
800	·031496				
900	·035433				
1000	(= 1 mm.)				

decim.	ins.
1	3·937043
2	7·874086
3	11·811130
4	15·748173
5	19·685216
6	23·622259
7	27·559302
8	31·496346
9	35·433389
10 (= 1 metre)	39·370432
	= 3·280869 ft
	= 1·093623 yd.

Inches &c. into Micromillimetres &c.

ins.	μ
1/25000	1·015991
1/20000	1·269989
1/15000	1·693318
1/10000	2·539977
1/8000	2·822197
1/6000	3·174972
1/5000	3·628539
1/4000	4·233295
1/3000	5·079954
1/2000	6·349943
1/1000	12·699886
	25·399772

	mm.
1/500	·028222
1/400	·031750
1/350	·036285
1/300	·042333
1/250	·050500
1/200	·056444
1/150	·063499
1/100	·072571

ins.	mm.
1/300	·084666
1/250	·101599
1/200	·126999
1/150	·169332
1/100	·253998
1/50	·507995
1/25	1·015991
1/20	1·269989
1/16	1·587486
1/13	1·693318
1/12	2·116648
1/10	2·539977
1/8	3·174972
1/6	4·233295
3/16	4·762457
1/5	5·079954
1/4	6·349943
5/16	7·937429
3/8	9·524915

	cm.
7/16	1·111240
1/2	1·269989

ins.	cm.
9/16	1·428737
5/8	1·587486
11/16	1·746234
3/4	1·904983
13/16	2·063732
7/8	2·222480
15/16	2·381229
1	2·539977
2	5·079954
3	7·619932

	decim.
4	1·015991
5	1·269989
6	1·523986
7	1·777984
8	2·031982
9	2·285979
10	2·539977
11	2·793975
1 ft.	3·047973

	metre
1 yd. =	·914392

Inches and Millimetres

Lines per inch	Lines in mm.
5,000	197
10,000	394
15,000	590
20,000	787
25,000	984
30,000	1,181
35,000	1,378
40,000	1,575
45,000	1,772
50,000	1,968
55,000	2,165
60,000	2,362
65,000	2,559
70,000	2,756
75,000	2,953
80,000	3,150
85,000	3,346
90,000	3,543
95,000	3,740
100,000	3,937
110,000	4,331
120,000	4,724
130,000	5,118
140,000	5,512
150,000	5,905
160,000	6,299
170,000	6,693
180,000	7,087
190,000	7,480

Lines per inch	Lines in mm.
200,000	7,874
210,000	8,268
220,000	8,661
230,000	9,055
240,000	9,449
250,000	9,843
260,000	10,236
270,000	10,630
280,000	11,024
290,000	11,417
300,000	11,811
350,000	13,780
400,000	15,748
450,000	17,717
500,000	19,685

	Lines in μ
25,399·77	1
50,799	2
76,199	3
101,599	4
126,999	5
152,399	6
177,798	7
203,198	8
228,598	9
253,998	10

Fractions of an inch	μ
1–5,000th	5·08
10,000	2·54
20,000	1·27
30,000	·847
40,000	·635
50,000	·508
60,000	·423
70,000	·363
80,000	·317
90,000	·282
100,000	·254
110,000	·231
120,000	·212
130,000	·195
140,000	·181
150,000	·169
160,000	·159
170,000	·149
180,000	·141
190,000	·134
200,000	·127
250,000	·1016
300,000	·0847
350,000	·0726
400,000	·0635
450,000	·0564
500,000	·0508

The legal equivalent of the metre is 39·37079 inches, and of the kilogramme 15432·34874 grains. In the above tables Colonel Clarke's measures of 39·370432 inches in 1867 have been adopted as being the more accurate. In 1882 the metre was again measured by Rogers, who found it equal to 39·37027 inches.

Weights can be more accurately compared than either lengths or capacities. The actual weight of the standard kilogramme in Paris is 15432·35639 grains. Its theoretical value, viz. the weight of a cubic decimetre of water, according to Colonel Clarke and Mr. Chaney, is 15413·08110 grains. If Rogers' value of the metre were used it would be a trifle less. The kilogramme is some 19½ grains heavier than theoretically it ought to be, and the litre, a vessel holding a kilogramme of water, has therefore a greater capacity than a cubic decimetre.

It is often necessary in the examination of a photo-micrograph of diatomic or other periodic structures to determine at what rate per inch or per mm. the structure is in the original object, the amplification of the photo-micrograph being known.

Example: In a photo-micrograph of a diatom amplified 735 diams. 12 dots can be counted in ·3 of an inch. At what rate per inch is the structure in the diatom?

(1) $$\frac{\text{magnifying power} \times \text{number counted}}{\text{space counted}};$$

$$\frac{735 \times 12}{\cdot 3 \text{ inch}} = 29{,}400 \text{ per inch.}$$

(2) If the answer is required in rate per mm., the space in which the number is counted being in inches as before, then, because 1 inch = 25·39977 mm.

$$\frac{735 \times 12}{\cdot 3 \text{ inch} \times 25{\cdot}39977} = 1157{\cdot}5 \text{ per mm.}$$

(3) Suppose a rule divided in mm. is used to determine the space in which the number on the photo-micrograph is counted, and the rate per inch is required; if twelve dots can be counted in 7 mm., then, because 1 mm. = ·03937 inch,

$$\frac{675{\cdot}2 \times 12}{7 \text{ mm.} \times \cdot 03937} = 29{,}400 \text{ per inch.}$$

APPENDIX D

COMPARISON OF THE SCALES OF FAHRENHEIT'S, THE CENTIGRADE, AND RÉAUMUR'S THERMOMETERS

THESE three thermometers are graduated so that the range of temperature between the freezing and boiling points of water is divided by Fahrenheit's scale into 180° (from 32° to 212°), by the Centigrade into 100° (from 0° to 100°), and by that of Réaumur into 80° (from 0° to 80°) portions or degrees. Hence we derive the following equivalents :—

A degree of Fahrenheit is equal to ·5 of the Centigrade, or to ·4 of Réaumur's; a degree of the Centigrade is equal to 1·8 of Fahrenheit's, or to ·8 of Réaumur's; and a degree of Réaumur's is equal to 2·25 of Fahrenheit's, or to 1·25 of the Centigrade.

To convert degrees of Fahrenheit into the Centigrade or Réaumur's subtract 32 and multiply the remainder by $\frac{5}{9}$ for the Centigrade, or $\frac{4}{9}$ for Réaumur's.

To convert degrees of the Centigrade or Réaumur's into Fahrenheit's multiply the Centigrade by $\frac{9}{5}$, or Réaumur's by $\frac{9}{4}$, as the case may be, and add 32 to the product.

EXAMPLE

Let F, C, and R = the number of degrees Fahrenheit, Centigrade, and Réaumur respectively. Then

$$F = \frac{9\,C}{5} + 32; \qquad F = \frac{9\,R}{4} + 32;$$

$$C = \frac{5\,(F-32)}{9}; \qquad C = \frac{5\,R}{4},$$

$$R = \frac{4\,(F-32)}{9}; \qquad R = \frac{4\,C}{5};$$

$$F = C + R + 32.$$

This last formula is of use, because in England thermometers are usually graduated in Fahrenheit and Centigrade. Réaumur may be found by inspection by subtracting the Centigrade from the Fahrenheit and taking 32 from the remainder. On the Continent thermometers are generally graduated in Réaumur and Centigrade. Fahrenheit can be found by adding Réaumur and Centigrade and 32.—Example: If the thermometer reads 8 Réaumur and 10 Centigrade, the Fahrenheit will be

$$8 + 10 + 32 = 50\ F.$$

APPENDIX E

OPTICAL FORMULÆ

To find C, the optical centre of a lens: Let A and B be the vertices, let the radius of the curve A = r, and that of B = s, t = thickness of the lens and μ the refractive index. Then

$$AC = \frac{rt}{r-s}; \quad BC = \frac{st}{r-s} \quad \ldots\ldots\ldots \text{(i)}$$

Example explaining the method of treating the signs: First, it should be particularly noticed that all curves which are convex to the left hand have positive radii, and those turned the other way negative radii.

In a biconvex let $r = 2$, $s = -8$, and $t = 1$; then by (i)

$$AC = \frac{2\times 1}{2-(-8)} = \frac{2}{2+8} = \frac{2}{5}; \quad BC = \frac{-8\times 1}{2-(-8)} = \frac{-8}{2+8} = -\frac{8}{5}.$$

The point C is measured, therefore, to the right hand from A, and to the left from B. In a plano-concave let $r = -2$, $s = \infty$, and $t = 1$; then

$$AC = \frac{-2\times 1}{-2-\infty} = 0; \quad BC = \frac{\infty \times 1}{-2-\infty} = \frac{\infty}{-\infty} = -1 \quad \ldots \text{(i)}$$

c is therefore coincident with A.

The nodal points D and E may be found thus:

$$AD = \frac{1}{\mu}\cdot\frac{rt}{r-s}; \quad BE = \frac{1}{\mu}\cdot\frac{st}{r-s} \quad \ldots\ldots \text{(ii)}$$

Example: In a meniscus $r = -8$, $s = -2$, $t = \frac{1}{4}$, and $\mu = \frac{3}{2}$;

$$AD = \frac{1}{\frac{3}{2}}\cdot\frac{-8\cdot\frac{1}{4}}{-8-(-2)} = \frac{2}{3}\cdot\frac{-\frac{8}{4}}{-8+2} = \frac{2}{3}\cdot\frac{-\frac{8}{4}}{-1} = \frac{2}{3}\cdot\frac{8}{4} = \frac{1}{2} \quad \text{(ii)}$$

D is measured $\frac{1}{2}$ inch to the right from A.

$$BE = \frac{1}{\frac{3}{2}}\cdot\frac{-2\cdot\frac{1}{4}}{-8-(-2)} = \frac{2}{3}\cdot\frac{-\frac{1}{2}}{-8+2} = \frac{2}{3}\cdot\frac{1}{2} = \frac{1}{3} \quad \ldots \text{(ii)}$$

E is measured $\frac{1}{3}$ inch to the right from B.

If the meniscus is turned round so that its convexities face the left hand, $r = 2$, $s = 3$, $t = \frac{1}{4}$, $\mu = \frac{8}{2}$;

$$AD = \frac{1}{\frac{3}{2}}\cdot\frac{2\cdot\frac{1}{4}}{2-3} = \frac{2}{3}\cdot\frac{1}{2}\cdot -1 = -\frac{1}{3} \quad \ldots\ldots \text{(ii)}$$

Similarly $BE = -\frac{1}{2}$. Both are therefore measured to the left. The

formulæ (ii) are approximations, sufficiently accurate for general practical purposes, but in cases of importance the following, longer but more accurate, formulæ should be used:

$$AD = \frac{rt}{\mu(r-s)-t(\mu-1)}; \quad BE = \frac{st}{\mu(r-s)-t(\mu-1)} \quad \ldots\ldots \text{(iii)}$$

Plano-convex Lens.—Let f = the principal focal point and y = the semi-aperture; then if parallel rays are incident on A, the plane side of the lens, $r = \infty$, and by (ii) $BE = 0$. The nodal point is therefore at the vertex B, and the focal length

$$Bf = \frac{-s}{\mu-1}; \quad Ef = Bf \quad \ldots\ldots \text{(iv)}$$

The spherical aberration

$$\delta f = -\frac{1}{2}\left(\frac{\mu}{\mu-1}\right)^2 \frac{y^2}{f} \quad \ldots\ldots \text{(v)}$$

Thus when $\mu = \frac{3}{2}$,

$$\delta f = -4{\cdot}5\,\frac{y^2}{f} \quad \ldots\ldots \text{(v')}$$

If the parallel rays are incident on the convex side A, $s = \infty$. $BE = -\frac{t}{\mu}$ (ii), and the focal length

$$Bf = \frac{r}{\mu-1} - \frac{t}{\mu} \quad \ldots\ldots \text{(vi)}. \qquad Ef = \frac{r}{\mu-1} \quad \ldots\ldots \text{(vii)}$$

The spherical[1] aberration

$$\delta f = -\frac{\mu^2(\mu-2)+2}{2\mu(\mu-1)^2}\cdot\frac{y^2}{f} \quad \ldots\ldots \text{(viii)}$$

When $\mu = 1{\cdot}516$ (plate glass)

$$\delta f = -1{\cdot}1\,\frac{y^2}{f} \quad \ldots\ldots \text{(viii')}$$

When $\mu = 1{\cdot}62$ (flint glass)

$$\delta f = -{\cdot}8042\,\frac{y^2}{f} \quad \ldots\ldots \text{(viii'')}$$

To find the radius of a plano-convex lens, the ref. index and focus Ef being given:

$$r = f(\mu-1) \quad \ldots\ldots \text{(ix)}$$

To find the radius of a plano-convex lens, the ref. index, the thickness and the focus Bf being given:

$$r = \frac{(\mu-1)(\mu f+t)}{\mu} \quad \ldots\ldots \text{(x)}$$

A plano-concave lens follows a plano-convex; f will be negative, which shows that the focus is virtual. Concaves being thin, t is usually neglected.

Equi-convex and equi-concave generally:

$$Bf = \frac{r}{2(\mu-1)} \quad \ldots\ldots \text{(xi)}$$

Equi-convex more accurately:

[1] Heath's *Geometrical Optics*, 1887.

$$Bf = \frac{r}{2(\mu-1)} - \frac{t}{2(\mu+1)} \quad \ldots\ldots\ldots \text{(x)}$$

Spherical[1] aberration

$$\delta f = -\frac{4\mu^2(\mu-1)-\mu+2}{8\mu(\mu-1)^2} \cdot \frac{y^2}{f} \quad \ldots\ldots\ldots \text{(xi)}$$

In an equi-convex lens when $\mu = \frac{3}{2}$,

$$\delta f = -1{\cdot}6\,\frac{y^2}{f} \quad \ldots\ldots\ldots \text{(xi)}$$

To find the radius of either an equi-convex or equi-concave lens, generally, the ref. index and the focus Bf being given:

$$r = 2(\mu-1)f \quad \ldots\ldots\ldots \text{(ix)}$$

To find the radius of an equi-convex lens, the ref. index, the thickness, and the focus Bf being given:

$$r = \frac{(\mu-1)\{2f(\mu+1)+t\}}{\mu+1} \quad \ldots\ldots\ldots \text{(x)}$$

Bi-convex and bi-concave, generally:

$$Ef = \frac{1}{\mu-1} \cdot \frac{rs}{s-r} \quad \ldots\ldots\ldots \text{(xii)}$$

Bi-convex, generally:

$$Bf = \frac{1}{\mu-1} \cdot \frac{rs}{s-r} - \frac{1}{\mu} \cdot \frac{st}{s-r} \quad \ldots\ldots\ldots \text{(xiii)}$$

The same when about equi-convex, generally:

$$Bf = \frac{1}{\mu-1} \cdot \frac{rs}{s-r} - \frac{t}{2(\mu+1)} \quad \ldots\ldots\ldots \text{(xiv)}$$

Bi-concave t may be neglected $Bf = Ef$ practically.
Bi-convex more accurately, and converging and diverging menisci:

$$Bf = \frac{s\left\{(\mu-1)\frac{t}{\mu} - r\right\}}{(\mu-1)\left\{r-s-(\mu-1)\frac{t}{\mu}\right\}} \quad \ldots\ldots\ldots \text{(xv)}$$

When the light is travelling from right to left

$$Af' = \frac{r\left\{(\mu-1)\frac{t}{\mu} + s\right\}}{(\mu-1)\left\{r-s-(\mu-1)\frac{t}{\mu}\right\}} \quad \ldots\ldots\ldots \text{(xv)}$$

Spherical aberration:

$$\delta f = -\frac{\mu-1}{2\mu^2}\left\{\frac{1}{r^3} + \left(\frac{\mu+1}{f} - \frac{1}{s}\right)\left(\frac{1}{f} - \frac{1}{s}\right)^2\right\} f^3 \frac{y^2}{f} \quad \ldots \text{(xvi)}$$

Example: Let $r = 2$, $s = -3$, $t = 1$, and $\mu = \frac{3}{2}$; then by (xv)

[1] Heath's *Geometrical Optics*, 1887.

$$Bf = \frac{-8\left\{\left(\frac{8}{2}-1\right)\frac{1}{8}-2\right\}}{\left(\frac{8}{2}-1\right)\left\{2-(-8)-\left(\frac{8}{2}-1\right)\frac{1}{8}\right\}} - \frac{-8\left(\frac{1}{2}\cdot\frac{2}{3}-2\right)}{\frac{1}{2}\left(2+8-\frac{1}{2}\cdot\frac{2}{3}\right)}$$

$$= \frac{-8\times -\frac{5}{8}}{\frac{1}{2}\cdot\frac{14}{8}} = \frac{5}{\frac{7}{3}} = 2\frac{1}{7}.$$

Similarly $$Af = -2\frac{2}{7}.$$

By (xiv) $$Bf = \frac{12}{5} - \frac{1}{5} = 2\frac{1}{5}.$$

Therefore (xiv) and (xv) are respectively $\frac{77}{35}$ and $\frac{75}{35}$.

The following is an example worthy of note. Suppose

$$r - s < t \text{ and } > (\mu - 1)\frac{t}{\mu}.$$

Thus let $$r = 5\frac{1}{2},\ s = 5,\ t = 1,\ \mu = \frac{3}{2}.$$

Then by (xv) $$Bf = \frac{5\left(\frac{1}{3}-\frac{11}{2}\right)}{\frac{1}{2}\left(\frac{1}{2}-\frac{1}{3}\right)} = \frac{-\frac{155}{6}}{\frac{1}{12}} = -810.$$

It will be observed that, although this meniscus is thickest in the middle, it has, however, a large negative focus.

The nodal points of a sphere are at its centre.

The focus of a sphere, measured from the centre:

$$Ef = \frac{\mu r}{2(\mu-1)} \quad \ldots\ldots\ldots \text{(xvii)}$$

The focus of a sphere measured from its surface:

$$Bf = \frac{r(2-\mu)}{2(\mu-1)} \quad \ldots\ldots\ldots \text{(xvii)}$$

The focus of a hemisphere measured from the vertex, the light being incident on the convex surface:

$$Bf = \frac{r}{\mu(\mu-1)} \quad \ldots\ldots\ldots \text{(vi)}$$

But when the light is incident on the plane surface

$$Bf = \frac{-s}{\mu-1} \quad \ldots\ldots\ldots \text{(iv)}$$

When $\mu = 1{\cdot}5$ the focus of a sphere measured from the surface = $\frac{1}{4}$ the radius.

The focus of a hemisphere measured from the plane side = $1\frac{1}{2}$ the radius, and when measured from the convex side the focus = 2 radii.

In a cylindrical lens the nodal points cross over.

To find the radii r and s of a crossed lens of minimum aberration for parallel rays:

$$r=\frac{2(\mu-1)(\mu+2)}{\mu(2\mu+1)}f; \qquad s=\frac{2(\mu-1)(\mu+2)}{\mu(2\mu-1)-4}f \quad . \quad . \quad . \text{(xviii)}$$

For plate glass $\mu=1{\cdot}516$; $r={\cdot}5935f$; and $s=-3{\cdot}944f$; (xviii)

$$\delta f=-1{\cdot}025\frac{y^2}{f} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \text{(xvi)}$$

For flint glass $\mu=1{\cdot}62$; $r={\cdot}653f$; and $s=-12{\cdot}06f$; (xviii)

$$\delta f=-{\cdot}798\frac{y^2}{f} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \text{(xvi)}$$

Critical angle.—Let θ be the critical angle for a ray passing out of a denser medium into a rarer one.

Then $$\sin\theta=\frac{1}{\mu} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \text{(xix)}$$

When $\mu=1{\cdot}333$, $\theta=48°\ 36\frac{1}{2}'$; $\mu=\frac{3}{2}$, $\theta=41°\ 48\frac{1}{2}'$; $\mu=1{\cdot}52$ $\theta=41°\ 8\frac{1}{4}'$; $\mu=1{\cdot}62$, $\theta=38°\ 7'$.

Let f be the principal focus, and p = the distance from the object to the optical centre of the lens, p' = the distance from the optical centre of the lens to the conjugate image.

Then $$p=\frac{pf}{p-f}; \qquad p=\frac{p'f}{p'-f}; \qquad f=\frac{pp'}{p+p'} \quad . \quad . \quad . \quad . \quad . \text{(xx)}$$

Let v be the distance from the object to f, and w be the distance from f on the other side of the lens to the conjugate image.

Then

$$v=p-f;\ w=p'-f;\ p=v+f;\ p'=w+f;\ \text{and}\ vw=f^2;\ v=\frac{f^2}{w};$$

$$w=\frac{f^2}{v} \quad . \text{(xxi)}$$

If o be the size of the object and i the size of its conjugate image

$$i=\frac{ow}{f}=\frac{of}{v}=\frac{op'}{p}=\frac{of}{p-f}=\frac{o(p'-f)}{f};$$

$$o=\frac{iv}{f}=\frac{if}{w}=\frac{ip}{p'}=\frac{if}{p'-f}=\frac{i(p-f)}{f};$$

$$p=\frac{op'}{i}=\frac{f(i+o)}{i};\ p'=\frac{ip}{o}=\frac{f(i+o)}{o};$$

$$v=\frac{of}{i};\ w=\frac{if}{o};\ f=\frac{ip}{i+o}=\frac{op'}{i+o}=\frac{ow}{i} \quad . \quad . \quad . \quad . \text{(xxii)}$$

Examples: With an objective of $\frac{1}{4}$-inch focus it is required to project an image of a diatom ·03 long, so that it may be 1·5 inch on the screen, what must be the distance of the screen from the optical centre of the lens?

$$p'=\frac{f(i+o)}{o}=\frac{{\cdot}5(1{\cdot}5+{\cdot}03)}{{\cdot}03}=25{\cdot}5.$$

Therefore $p'=25\frac{1}{2}$ inches, the distance required . . . . . (xxii)

Conversely, if the image of a diatom projected by a $\frac{1}{4}$-inch objective measures 2 inches on the screen at $40\frac{1}{4}$ inches from the optic centre what is the size of the diatom?

$$o=\frac{if}{p'-f}=\frac{2\times\frac{1}{4}}{40\frac{1}{4}-\frac{1}{4}}=\frac{1}{80}={\cdot}0125 \quad . \quad . \quad . \quad . \quad . \text{(xxii)}$$

the size of the diatom required.

The last formula of (xxii) is very convenient for finding the focus of an objective; w must, of course, be large in proportion to the focus; o may be a stage micrometer.

As the posterior focus, f, is in ordinary microscope objectives of 1-inch focus and upwards, near the back lens, the distance w may be measured from there.

Example: The image of ·01 inch on a stage micrometer projected by an objective is 2·4 inches on a screen, distant 5 feet from the back lens; required the focus of the objective.

$$f = \frac{o\,w}{i} = \frac{\cdot 01 \times 60}{2\cdot 4} = \frac{\cdot 6}{2\cdot 4} = \frac{1}{4} \quad \ldots\ldots\ldots \text{(xxii)}$$

To find F, the equivalent focus of two lenses in contact:

$$\mathrm{F} = \frac{f f'}{f + f'} \quad \ldots\ldots\ldots\ldots\ldots \text{(xxiii)}$$

where f is the focus of one lens and f' that of the second.

Example: It is required to make a combination of two plano-convex lenses, the focus of one lens, f, being twice f', that of the other, and whose combined focus $\mathrm{F} = \cdot 6$, $\mu = \frac{3}{2}$; find their radii (see figs. 4, 6, 8, and 9).

Then $f = 2f'$.

$$\mathrm{F} = \frac{2f'f'}{2f' + f'} = \frac{2f'^2}{3f'} = \frac{2f'}{3};$$

$$f' = \frac{3\,\mathrm{F}}{2} = \frac{1\cdot 8}{2} = \cdot 9; \text{ and } f = 3\,\mathrm{F} = 1\cdot 8 \quad \ldots\ldots \text{(xxiii)}$$

$$r = (\mu - 1) f = \left(\frac{3}{2} - 1\right) 1\cdot 8 = 9; \text{ similarly } r' = \cdot 45 \quad \ldots \text{(vii)}$$

The focus for three lenses follows that for two, thus:

$$\mathrm{F} = \frac{f f' f''}{f f' + f f'' + f' f''} \quad \ldots\ldots\ldots \text{(xxiii)}$$

which may be written $\frac{1}{\mathrm{F}} = \Sigma \frac{1}{f}$.

To find F, the equivalent focus of two lenses, not in contact, generally. F to be measured from the last nodal point (E′) of the second lens: Let d = the distance between the lenses:

$$\mathrm{F} = \frac{f'(f - d)}{f + f' - d} \quad \ldots\ldots\ldots\ldots \text{(xxiv)}$$

More accurately let D E be the nodal points of the first lens and D′ E′ those of the second, A B and A′ B′ being the respective vertices, d = the distance from E to D′; then G G′, the nodal points of the combination, are:

$$\mathrm{G} = \mathrm{D} - \frac{df}{f + f' - d} \quad \ldots\ldots\ldots\ldots \text{(xxv)}$$

$$\mathrm{G}' = \mathrm{E}' - \frac{df'}{f + f' - d} \quad \ldots\ldots\ldots\ldots \text{(xxvi)}$$

and

$$\mathrm{F} = \frac{f f'}{f + f' - d} \quad \ldots\ldots\ldots\ldots \text{(xxvii)}$$

F is measured from one of the nodal points of the combination An

example will be of interest. Let parallel rays fall on the convex face of the field lens of a Huyghenian eyepiece; find their focus.

Let f, the focus of the field lens = 8, and that of the eye lens $f' = 1$; $\mu = \frac{8}{2}$, and the distance between the surfaces, that is B A′, = 1·8; t the thickness of the field lens = $\frac{8}{10}$; and t' that of the eye lens = $\frac{8}{20}$; A D = 0 (ii); B E = $-\frac{t}{\mu} = -\cdot 2$ (ii). Similarly A′ D′ = 0; B′ E′ = $-\frac{t}{\mu} = -\frac{1}{10}$ (ii); d = E B + B A′ = ·2 + 1·8 = 2. Now

$$G' = E' - \frac{2 \times 1}{8 + 1 - 2} = E' - 1 \quad \ldots\ldots \quad \text{(xxvi)}$$

$$F = \frac{8 \times 1}{8 + 1 - 2} = \frac{8}{2} \quad \ldots\ldots\ldots \quad \text{(xxvii)}$$

We see, therefore, that the equivalent focus is 1½ inch, but the principal point, G′, from which the focus is measured is 1 inch to the left from E′; therefore the focal point is ½ inch to the right from E′. Now as E′ is $\frac{1}{10}$ inch to the left of B′, the plane surface of the eye lens, it follows that F, the focal point, is $\frac{4}{10}$ inch to the right of the plane surface of the eye lens.

This explains 'the microscope objective of 10-ft. focus.'

The equivalent focus of the objective was 10 ft., but the nodal point, G′, from which that focus was measured was 9 ft. 11½ inches from the objective, which would give ½ inch as the working distance of the lens. The objective in question has a double convex back lens and a plano-concave front; a small decrease in the distance between the lenses, such as a $\frac{1}{10}$ inch, has the effect of causing the principal point, G′, to recede many feet, and of causing a great increase in the equivalent focus.

With regard to the optical tube length, the position of the principal points of a combination plays an important part. Suppose the Huyghenian eyepiece, in the preceding example, was mounted as an objective; the tube length would have to be measured from the right-hand principal point of the eyepiece, wherever that might be, to the left-hand principal point of the objective, which in the example before us is

$$G = D - \frac{2 \times 8}{8 + 1 - 2} = D - 3 \quad \ldots\ldots \quad \text{(xxv)}$$

G is therefore measured 3 inches to the left from the point D; D is, as we have seen, coincident with A, the convex vertex of the field lens. So anyone measuring the tube length from the field lens, which is the posterior lens of our supposed objective, or from the middle of the combination, would be 3 or 4 inches in error.

The importance of this cannot be over-estimated, as the optical tube length has a direct bearing on the power. If Q = the distance of vision (say 10 inches), M = the magnifying power, F = the equivalent focus of the eyepiece, F′ = the equivalent focus of the objective, O = the optical tube length measured in the manner indicated above; then

$$M = \frac{O\,Q}{F\,F'} \quad \ldots\ldots\ldots \quad \text{(xxviii)}$$

If ϕ = the focal length of the entire microscope, N.A. = the numerical aperture, and ϵ = the diameter of the eye-spot, then

$$\phi = \frac{Q}{M} = \frac{F\,F'}{O} \quad \ldots\ldots\ldots \quad \text{(xxix)}^1$$

[1] *Journal R.M.S.*

$$\epsilon = 2\,(\text{N.A.})\,\phi\,; \quad \text{N.A.} = \frac{\epsilon}{2\phi} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (\text{xxxi})^1$$

If λ = the number of waves per inch of light of a given colour, L the limit of resolving power of any objective is

$$L = 2\lambda\,(\text{N.A.}) \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad .$$

The aberration for non-parallel rays.—It is a little more troublesome to find the aberration of rays other than parallel, but if the following instructions are carefully attended to the problem merely becomes the simplification of a vulgar fraction. Let P and P′ be the distances of the point and its image from the lens. First find a, by either (xxxii) or (xxxiii):

$$a = \frac{2f}{\text{P}} - 1 \quad . \quad . \quad . \quad . \quad . \quad (\text{xxxii}); \qquad a = 1 - \frac{2f}{\text{P}'} \quad . \quad . \quad . \quad . \quad . \quad (\text{xxxiii})$$

Next find x by (xxxiv) or (xxxv):

$$x = \frac{2\,(\mu-1)f}{r} - 1 \quad . \quad . \quad . \quad (\text{xxxiv}); \qquad x = 1 + \frac{2\,(\mu-1)f}{s} \quad . \quad . \quad . \quad (\text{xxxv})$$

Then find ω by (xxxvi):

$$\omega = \frac{1}{8\mu\,(\mu-1)f^3}\left\{\frac{\mu+2}{\mu-1}x^2 + 4\,(\mu+1)\,a\,x + (3\,\mu+2)\,(\mu-1)\,a^2 + \frac{\mu^3}{\mu-1}\right\} \quad (\text{xxxvi})$$

$$\frac{1}{\text{P}'} = \frac{1}{f} - \frac{1}{\text{P}} + \frac{1}{\mu}(x-a)^2\,\frac{t}{4f^2} + \omega\,y^2 \quad . \quad . \quad . \quad . \quad . \quad (\text{xxxvii})$$

$$\text{The aberration } \delta\,\text{P}' = -\omega\,\text{P}'^2\,y^2 \quad . \quad . \quad . \quad (\text{xxxviii})$$

To find the aberration of two lenses in contact. Let Q and Q′ be the object and its conjugate at the second lens, f' be the focus of the second lens, and F the focus of the combination; then P′ = −Q.

$$\frac{1}{\text{P}'} = \frac{1}{f} - \frac{1}{\text{P}} \quad . \quad . \quad . \quad . \quad (\text{xx}); \qquad \frac{1}{\text{Q}'} = \frac{1}{f'} + \frac{1}{\text{Q}} \quad . \quad . \quad . \quad . \quad (\text{xxxix})$$

$$\text{for the first lens, } \frac{1}{\text{P}'} = \frac{1}{f} - \frac{1}{\text{P}} + \omega\,y^2 \quad . \quad . \quad . \quad . \quad (\text{xxxvii})$$

$$\text{for the second lens, } \frac{1}{\text{Q}'} = \frac{1}{f'} + \frac{1}{\text{Q}} + \omega'\,y^2 \quad . \quad . \quad . \quad (\text{xxxviii})$$

$$\text{for both lenses, } \frac{1}{\text{Q}'} = \frac{1}{f} + \frac{1}{f'} - \frac{1}{\text{P}} + (\omega+\omega')\,y^2 \quad . \quad . \quad (\text{xxxix})$$

$$\text{Therefore, for } n \text{ lenses, } \frac{1}{\text{Q}^n} = \Sigma\,\frac{1}{f} - \frac{1}{\text{P}} + \Sigma\,\omega\,y^2 \quad . \quad . \quad (\text{xxxix})$$

The aberration $\delta\,\text{Q}' = -\Sigma\omega\,\text{Q}'^2 y^2$ and $\delta\,\text{F} = -\Sigma\,\omega\,\text{F}^2 y^2$ . . . . (xl)

Example: Two plano-convex lenses of equal foci have their convex surfaces in contact; find the aberration for parallel rays (fig. 7). Then

$$\mu = \frac{3}{2}; \; f = f'. \qquad \text{F} = \frac{f}{2} \quad . \quad . \quad . \quad . \quad . \quad . \quad (\text{xxxiii})$$

For the first lens $r = \infty$; therefore $x = -1$ (xxxiv); P = ∞; therefore $a = -1$ (xxxii); and $\omega = \frac{9}{2f^3}$ (xxxvi).

For the second lens $s = \infty$; therefore $x = 1$ (xxxv); $\frac{1}{\text{Q}} = -\frac{1}{f}$; there-

[1] *Journal R.M.S.*

fore $a = -8$ (xxxii); $\omega' = \frac{18}{6f^3}$ (xxxvi); $\omega + \omega' = \Sigma\omega = \frac{20}{8f^3}$;

$f = 2\,F$ (xxiii); therefore $\Sigma\omega = \frac{20}{24\,F^3}$;

$$\delta F = -\frac{20\,F^2y^2}{24\,F^3} = -\frac{5}{6}\cdot\frac{y^2}{F} \quad \ldots\ldots\ldots \text{(xl)}$$

This is half the aberration of an equi-convex lens (fig. 1) of the same focal length as the combination where

$$\delta f = -\frac{5}{8}\cdot\frac{y^2}{f} \quad \ldots\ldots\ldots \text{(xi)}$$

If the front lens of the combination be turned round so that its convex surface faces the incident light the aberration is

$$\delta F = -\frac{5}{12}\cdot\frac{y^2}{F} \quad \ldots\ldots\ldots \text{(xl)}$$

or half what it was before (fig. 5).

This is nearly a third of the aberration of a plano-convex in the best position (fig. 2), which is

$$\delta f = -\frac{7}{6}\cdot\frac{y^2}{f} \quad \ldots\ldots\ldots \text{(viii)}$$

The following figures pictorially illustrate spherical aberration in single lenses and in various combinations of two plano-convex lenses, all having the same focus, F, the same aperture, and the same refractive index, $\frac{3}{2}$. The dot nearer the lens is the focal point for the marginal, and that farther away the focal point for the central rays; the distance between the dots is the spherical aberration δF

FIG. 1.

FIG. 2.

FIG. 5.

Fig. 1. An equi-convex, $r = F$;

$$\delta F = -1{\cdot}6\,\frac{y^2}{F} = -{\cdot}178 \quad \ldots\ldots\ldots \text{(xi)}$$

Fig. 2. A plano-convex, $r = \frac{F}{2}$;

$$\delta F = -1{\cdot}16\,\frac{y^2}{F} = -{\cdot}121 \quad \ldots\ldots\ldots \text{(viii)}$$

Fig. 3. A crossed convex, $r = \frac{7}{12}\,F$; $s = -\frac{7}{2}\,F$ (xviii);

$$\delta F = -1{\cdot}07\,\frac{y^2}{F} = -{\cdot}111 \quad \ldots\ldots\ldots \text{(xvi)}$$

Fig. 7. A combination of two planos with their convex faces in contact, the focus f of the first lens being equal to f', that of the second. The focus of the combination $F = \frac{f}{2}$ . . . . . (xxiii)

$$\delta F = -{\cdot}833\,\frac{y^2}{F} = -{\cdot}087 \quad \ldots\ldots\ldots \text{(xl)}$$

Fig. 4. The same, only $2f = f'$;

$$\delta F = -1{\cdot}611\,\frac{y^2}{F} = -{\cdot}168 \quad \ldots\ldots\ldots \text{(xl)}$$

Fig. 6. The same, only $f = 2f'$;

$$\delta F = -\cdot 5 \frac{y^2}{F} = -\cdot 052 \quad \ldots\ldots\ldots \text{(xl)}$$

Fig. 5. The first lens inverted, $f = f'$;

$$\delta F = -\cdot 410 \frac{y^2}{F} = -\cdot 043 \quad \ldots\ldots\ldots \text{(xl)}$$

Fig. 8. The same, only $2f = f'$;

$$\delta F = -\cdot 628 \frac{y^2}{F} = -\cdot 065 \quad \ldots\ldots\ldots \text{(xl)}$$

Fig. 9. The same, only $f = 2f'$;

$$\delta F = -\cdot 376 \frac{y^2}{F} = -\cdot 039 \quad \ldots\ldots\ldots \text{(xl)}$$



Fig. 4. Fig. 5. Fig. 6.



Fig. 7. Fig. 8. Fig. 9.

We see, therefore, that with the same focal length F the aberration of fig. 1 is the greatest, and that of fig. 9 the least. We also see in the combinations that by decreasing up to a certain point the focus of the first lens the aberration is increased, and *vice versâ*. The best form of a combination of plate glass, $\mu = 1{\cdot}516$, for parallel rays similar in arrangement to fig. 9 is when $f = \frac{5}{3} f'$.

The Aplanatic Meniscus.—A spherical refracting surface has two aplanatic foci, such that if converging rays, which have their focus at P', meet a convex spherical refracting surface, whose centre of curvature is r, and if the distance between the points P' and $r = \mu r$, then those rays will be refracted aplanatically to some other point, say P, which will lie on the same side of the surface as P'. This fact is of great service, because it enables an aplanatic meniscus to be constructed; thus, if we make r the radius of the curve A, we can make s, the radius of the curve B, a radius from the point P. If, then, P is a radiant, the light travelling from left to right will pass through the curve B without refraction, because P is the centre of the curve B. The light will then pass on unchanged to the curve A, and will by it be refracted aplanatically, as if it had come from P'. P will be negative and P' positive.

The formulæ for finding r and P' when P is given are:

$$r = -\frac{\mu P}{\mu + 1}; \quad P' = -\mu P \quad \ldots\ldots\ldots \text{(xlii)}$$

and those for finding r and P when P' is given are:

$$r = \frac{P'}{\mu + 1}; \quad P = -\frac{P'}{\mu} \quad \ldots\ldots\ldots \text{(xliii)}$$

An excellent combination, suitable for a bull's-eye, can be made of an aplanatic meniscus and a plano-convex of flint, or a crossed plate lens. The following are the radii of some examples. A doublet of plate glass $\mu = 1{\cdot}516$.

1st lens, a meniscus, diam. 1·7″; $r = +{\cdot}964''$; $s = +1{\cdot}375''$.

2nd lens, bi-convex crossed, diam. 2·1″; $r' = +1{\cdot}816''$; $s' = -12{\cdot}07''$.

The flatter side of the crossed lens to face the meniscus, the distance between the lenses ·05″, P = 1·6″, P′ = 2·425″, $\delta F = -{\cdot}168''$, angle 70°.

A better combination can be made by substituting a flint plano-convex for the second lens, diam. 2·1″; $\mu = 1{\cdot}62$; $r' = +1{\cdot}83''$; $\delta F = -{\cdot}132''$. The aberration is therefore ·036″ less than before.

The aberration may be further reduced by adding another meniscus and by making all the lenses of flint $\mu = 1{\cdot}62$.

1st lens, a meniscus, diam. 1·65″; $r = +{\cdot}958''$; $s = +1{\cdot}35''$.

2nd lens, a meniscus having its concave side facing the convex side of the first lens; diam. 2·0″; $r' = +1{\cdot}67''$; $s' = +2{\cdot}55''$.

The third lens is a plano-convex, with its plane side facing the convex side of the second meniscus; diam. 2·1″; $r'' = +2{\cdot}914''$; P = 1·55; $\delta F = -{\cdot}0226$; angle 70°.

The aberration is therefore ·145″ less than that of the first example. The distance between the lenses is ·05″ as before.

To find the radii r and s of a lens which will refract light from a point p to point p' with minimum aberration.

$$K = \frac{p + p'}{(\mu - 1)\, p'} \quad \text{(xliii)}; \qquad f = \frac{p\, p'}{p + p'} \quad \text{(xx)}$$

$$r = -\frac{2\,(\mu + 2)\, p}{\mu\,(2\,\mu + 1)\, K - 4\,(\mu + 1)} \quad \text{(xliv)}$$

$$s = \frac{p\, r}{p - r\, K} \quad \text{(xlv)}$$

Let β be the coefficient of $\frac{y^2}{f}$ in formulæ v, viii, xi, and xvi, then for parallel rays in each particular case the lateral aberration $= \beta \frac{y^3}{f^2}$. (xlvi)

Diameter of least circle of aberration $= \frac{1}{2}\beta \frac{y^3}{f^2}$ (xlvii)

Distance of least circle of aberration from focus $= -\frac{8}{4}\beta \frac{y^2}{f}$ (xlviii)

When the rays are not parallel

(xlvi) $= \omega\, p'\, y^3$ (xlvii) $= \frac{1}{2}\omega\, p'\, y^3$ (xlviii) $= -\frac{8}{4}\omega\, p'^2\, y^2$

It is interesting to note that $\frac{y^2}{f} = 2\,(\mu - 1)t$ (xlix)

Therefore, when $\mu = \frac{3}{2}$, $\frac{y^2}{f} = t$.

To find m, the magnifying power of simple lenses or magnifying glasses. Let d be the *least* distance of distinct vision apart from the lens, and f be the principal or solar focus of the lens. Then

$$m = 1 + \frac{d}{f} \quad \text{(l)}$$

It may be of interest to note that formula (xx) on this page may be used to determine the focus of spectacles required to bring the abnormal focus

of either a presbyopic or myopic person to a normal focus. Make p the abnormal, and p' the normal focus; then f will be the focus of the spectacles required.

In both cases p is a negative quantity, because it is on the same side of the lens as p'; it is usual to make p' 10 or 12 inches.

Achromatism

Let μ be the refractive index of a mean ray (E line nearly) for a certain material, μ_v that for a blue ray, and μ_r that for a red ray; the dispersive power of the material is $\frac{\mu_v - \mu_r}{\mu - 1}$; this is usually written $\frac{\delta\mu}{\mu-1}$, or ω. The formula for achromatism is

$$\frac{\delta\mu}{\mu-1}\cdot\frac{1}{f} + \frac{\delta\mu'}{\mu'-1}\cdot\frac{1}{f'} = 0;$$

that is,

$$\frac{\omega}{f} + \frac{\omega'}{f'} = 0 \quad \ldots\ldots\ldots\ldots \text{(li)}$$

The foci of the two lenses are therefore directly as their dispersive powers, and the focus of one will be negative.

An achromatic effect, which is not achromatism in the strict meaning of the term, can be obtained with two lenses of the same kind of glass by making d the distance between the lenses:

$$d = \frac{p\,(f+f')}{2p-f} \quad \ldots\ldots\ldots\ldots \text{(lii)}$$

If p is large, f in the denominator may be neglected; this will make d half the sum of the foci, which is the formula for both the Huyghenian and Ramsden eyepieces; but when $p = f$, d is the sum of the foci.

Formulæ relating to Spherical Mirrors

Let p = one focus, p' = its conjugate, f = principal focus, and r = radius of curvature; then in concave mirrors

$$p' = \frac{p\,r}{2p-r};\quad p' = \frac{p\,f}{p-f};\quad f = \frac{p\,p'}{p+p'};\quad f = \frac{r}{2};$$

$$r = \frac{2\,p\,p'}{p+p'};\quad r = 2f;\quad \frac{p}{p'} = \frac{p-f}{f} \quad \ldots\ldots\ldots \text{(xxi)}$$

To find p interchange p and p'.

If o is the size of an object, and i the size of its image, and v the distance of the image from the principal focal point, then

$$i = \frac{o\,p'}{p};\quad i = \frac{o\,f}{v} \quad \ldots\ldots\ldots\ldots \text{(xxiii)}$$

In convex mirrors prefix a negative sign, thus: $r = -2f$, and so on with the other formulæ.

The formulæ for mirrors may be derived from those of lenses by substituting -1 for μ; thus $r = -2f$ (vii).

Let y = the semi-aperture; then the spherical aberration

$$\delta f = -\frac{1}{8}\cdot\frac{y^2}{f} \quad \ldots\ldots \text{(v) or (viii)}$$

A mirror to be aplanatic for parallel rays must have a parabolic curve.

A mirror to reflect rays diverging from a point p, so that they may converge aplanatically to another point p', must be elliptical, having p and p' for its foci.

Formulæ relating to Prisms

Let ι = the refracting angle of the prism, ϕ the angle of incidence on the first surface, ϕ' the angle of refraction at the first surface, ψ the angle of incidence in the prism at the second surface, and ψ' the angle of refraction on emergence; then the total deviation

$$D = \phi + \psi' - \iota; \qquad \phi' + \psi = \iota \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(liii)}$$

When the ray passes through the prism symmetrically the deviation is at a minimum: $\phi = \psi'$, $\phi' = \psi = \frac{\iota}{2}$, and

$$\mu = \frac{\sin \frac{\iota + D}{2}}{\sin \frac{\iota}{2}} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(liv)}$$

by which formula the refractive indices of media can be found, because both ι and D are capable of accurate measurement.

Formulæ relating to Conic Sections

Ellipse.—Let A = major axis; a = minor axis. Then

$$\text{Focus} = \frac{A - \sqrt{A^2 - a^2}}{2} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(lv)}$$

Parabola.—Let A = height; $a = \frac{1}{2}$ base. Then

$$\text{Focus} = \frac{a^2}{4A} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(lvi)}$$

Hyperbola.—Let A = major axis; a = minor axis. Then

$$\text{Focus} = \frac{\sqrt{A^2 + a^2} - A}{2} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad \text{(lvii)}$$

Works consulted:—Coddington, Camb. 1830; Parkinson, Camb.; 'Encyclopædia Britannica'; 'Journal R.M.S.'; Heath, Camb. 1887, &c. It will be seen that several of the formulæ have been entirely reset, while some appear now for the first time.

APPENDIX F

EXAMPLES USEFUL TO THE MICROSCOPIST

Square $\frac{1}{8}$ inch	=	10·08045	square millimetres.		
,, $\frac{1}{10}$,,	=	6·45148	,,	,,	
,, $\frac{1}{12}$,,	=	4·48021	,,	,,	
,, $\frac{1}{100}$,,	=	·06451	,,	,,	
	=	64514·8	,,	μ	
,, $\frac{1}{1000}$,,	=	645·148	,,	,,	

Square centimetre	= 15·5003	square $\frac{1}{10}$	inch.
,, millimetre	= 15·5003	,, $\frac{1}{100}$	,,
,, 100 μ	= 15·5003	,, $\frac{1}{1000}$	,,
,, 10 μ	= ·1550	,, ,,	,,
,, μ	= ·00155	,, ,,	,,

Multiples of the above may be found by multiplying the values given by the square of the multiplier.

Thus, square $\frac{4}{10}$ inch = $\frac{1}{10} \times 4$; the square of $4 = 4 \times 4 = 16$, and $6{\cdot}45148 \times 16 = 103{\cdot}22368$ square millimetres, the answer required.

Cubic $\frac{1}{8}$ inch	=	32·00508	cubic millimetres.		
,, $\frac{1}{10}$,,	=	16·38662	,,	,,	
,, $\frac{1}{12}$,,	=	9·48300	,,	,,	
,, $\frac{1}{100}$,,	=	·01638	,,	,,	
,, $\frac{1}{1000}$,,	=	16386·62	,,	μ	

Cubic centimetre	= 61·02537	cubic $\frac{1}{10}$	inch.
,, millimetre	= 61·02537	,, $\frac{1}{100}$	,,
,, 100 μ	= 61·02537	,, $\frac{1}{1000}$	,,
,, 10 μ	= ·061025	,, ,,	,,
,, μ	= ·000061025	,, ,,	,,

Multiples of the above may be found by multiplying the values given by the cube of the multiplier.

Thus, 2 cubic millimetres: 2 cubed $= 2 \times 2 \times 2 = 8$, and $61{\cdot}02537 \times 8 = 488{\cdot}20296$ cubic $\frac{1}{100}$ inch, the answer required.

Areas of Circles

$\frac{1}{8}$ inch diameter	= 1·22718	sq. $\frac{1}{10}$ inch	=	7·9171	sq. millimetres.
$\frac{1}{10}$,, ,,	= ·78539816	,, ,, ,,	=	5·0670	,, ,,
$\frac{1}{12}$,, ,,	= ·54541	,, ,, ,,	=	3·5187	,, ,,
$\frac{1}{100}$,, ,,	= ·78540	,, $\frac{1}{100}$,,	=	·05067	,, ,,
			=	50670·0	,, μ
$\frac{1}{1000}$,, ,,	= ·78540	,, $\frac{1}{1000}$,,	=	506·7	,, ,,

1 millimetre diam.	= ·78539816	sq. mm.	= 12·1737	sq. $\frac{1}{100}$	inch.
100 μ	= 7854·0	,, μ	= 12·1737	,, $\frac{1}{1000}$	,,
10 μ	= 78·54	,, ,,	= ·1217	,, ,,	,,
μ	= ·7854	,, ,,	= ·001217	,, ,,	,,

Multiples of any of the above may be obtained in the same manner as in the preceding example.

Thus, if the diameter of the circle = $\frac{3}{100}$ inch, then the square of 8 being 9 and ·7854 × 9 = 7·0686 sq. $\frac{1}{100}$ inch and ·05067 × 9 = ·45603 sq. millimetre, are the areas required.

Volumes of Spheres

1	in.	diameter	.	= 1·02266	cubic	$\frac{1}{10}$	inch	=	16·758	cubic	millimetres.
$\frac{1}{10}$	,,	,,	.	= ·52360	,,		,,	=	8·580	,,	,,
$\frac{1}{12}$	,,	,,	.	= ·30301	,,		,,	=	4·965	,,	,,
$\frac{1}{100}$	,,	,,	.	= ·52360	,,	$\frac{1}{100}$	,,	=	·00858	,,	,,
$\frac{1}{1000}$	,,	,,	.	= ·52360	,,	$\frac{1}{1000}$	,,	=	8580·0	,,	μ

1	mm.	diam.	. . .	= ·52360	cubic	mm.	=	31·958	cubic	$\frac{1}{100}$	inch.
100	μ	,,	. . .	= 523600·0	,,	μ	=	31·958	,,	$\frac{1}{1000}$	,,
10	μ	,,	. . .	= 523·60	,,	,,	=	·03195	,,	,,	,,
μ		,,	. . .	= ·52360	,,	,,	=	·00003195	,,	,,	

Multiples of any of the above follow the preceding example of cubic measures. Thus, if the diameter of the sphere = 30 μ, then the cube of 3 being 27 and 523·6 × 27 = 14137·2 cubic μ and ·03195 × 27 = ·86265 cubic $\frac{1}{1000}$ inch, are the volumes required.

APPENDIX G

USEFUL NUMBERS AND FORMULÆ

Paris line = ·088813783 inch.
Statute mile = 5280 ft. = 1609·330 metres.
Geographical mile = 6082·66 ft. = 1853·978 metres.
Nautical mile = 6080 ft. = 1853·167 metres.
Cubic foot of water weighs 62·2786 lb. avoirdupois at 62° Fahr.
Cubic inch of water weighs 252·286 grs. at 62° Fahr.
Gallon of water weighs 10 lb. avoirdupois at 62° Fahr.
1 gallon = 277·46288 cubic inches.
Cubic foot of sea water weighs 63·963 lb.
Weight of sea water = 1·027 weight of fresh water.
1 inch of rainfall = 100 tons per acre.
Pressure of water in lb. per sq. inch = ·433 head of water.
Expansion of water between 32° Fahr. and 212° Fahr. = ·04775.
Dip of horizon in nautical miles = $1{\cdot}23\sqrt{\text{height}}$.

Marks on hand lead line for sea soundings 1, 2, and 3 fathoms, 1, 2, and 3 tags of leather respectively; 5 and 15 fathoms white rag; 7 and 17 fathoms red rag; 10 fathoms leather with hole in it; 13 fathoms blue rag; 20 fathoms 2 knots; 30 fathoms 3 knots &c. A small knot is placed at intermediate 5 fathoms after 20 fathoms—viz. at 25, 35, 45, &c.

Pressure of wind in lb. per sq. foot = 0·002288 (velocity in feet per second)^2.

Areas and Volumes.

Area of triangle = base × ½ perpendicular.
Volume of wedge = area of base × ½ perpendicular height.
Volume of cone or pyramid = area of base × ⅓ perpendicular height.
Surface of side of cone = circumference of base × ½ length of side.
Area of parabola = base × ⅔ height.
Velocity of light = 187,272 statute miles per second.[1]

Wave-length of yellow light = $\frac{1}{50000}$ inch.

Number of vibrations per second 593,276,600,000,000.

Falling Bodies.

S, space fallen in feet; V, velocity in feet per second; $g = 32{\cdot}2$; t, time in seconds.

$$S = \frac{g\,t^2}{2};\quad V = \sqrt{2\,g}\cdot\sqrt{S} = 8{\cdot}025\sqrt{S}.$$

Arithmetical Progression

A, first term; B, last term; S, sum; d, difference between terms; n, number of terms.

[1] Latest determinations by Young and Forbes with Fizeau's method.

$$A = B - d\,(n-1). \quad B = A + d\,(n-1). \quad S = (A+B)\,\frac{n}{2}.$$

Geometrical Progression

m, multiplier or divisor.

$$A = \frac{B}{m^{(n-1)}}. \quad B = m\,A^{(n-1)}. \quad S = \frac{Bm - A}{m-1}.$$

Properties of Circles and Spheres &c.

π . . = 3·14159265358979 +		$\log \pi$. = 0·4971499
$\pi^2 = 9{\cdot}86962$	$\sqrt{\pi}$. = 1·77245	$\frac{1}{\pi}$ = ·31831
$\frac{1}{\pi^2}$ . . = ·10132		$\frac{1}{\sqrt{\pi}}$ = ·56419
$\frac{\pi}{6}$ . . = ·52360	$\sqrt{2} = 1{\cdot}41421$	$\sqrt{2g} = 8{\cdot}02496$

Circumference, C. Area, A. Radius, r. Diameter, d. Volume, V. Surface, S.

$C = 2\pi r = \pi d$. $A = \pi r^2$. $S = \pi d^2$. $V = \frac{\pi d^3}{6}$. $d = \frac{C}{\pi}$.

Area of sector of circle $= \frac{\text{degrees in arc} \times \text{area of circle}}{360}$.

Length of arc = number of degrees × ·017453 r.
Unit of circular measure = 57°·29578.
Side of square of equal area to a circle = $r\sqrt{\pi}$.
Side of inscribed square = $r\sqrt{2}$
Area of ellipse = ½ major axis × ½ minor axis × π.
Volume of ellipsoid = major axis × (minor axis)² × $\frac{\pi}{6}$.

Number of Threads in Whitworth's Standard Screws

Sizes $\frac{1}{10}$	No. of threads 48
„ $\frac{1}{8}$	„ 40
„ $\frac{1}{4}$	„ 20
„ $\frac{3}{8}$	„ 16
„ $\frac{1}{2}$	„ 12

Convenient Approximations for rapid Calculations

6 knots	= 7 miles, more correctly	13 knots	= 15 miles.
5 kilometres	= 3 „ „ „	50 kilometres	= 31 „
1 metre	= 3 ft. 3½ in. „ „	64 metres	= 70 yards.
5 centimetres	= 2 inches „ „	33 centimetres	= 13 inches.
8 millimetres	= ⅛ inch „ „	5 millimetres	= ⅛ inch.

1 pole = 5 metres; 1 furlong = 2 hectometres.
5 μ = $\frac{1}{5000}$ inch; $\frac{1}{100}$ inch = ¼ mm.; $\frac{1}{100000}$ inch = ¼ μ.
2 are = 239 sq. yds.; 1 rood = 10 are; 2 acres = 81 are; 100 hectare = 247 acres; 3 cubic yards = 23 decisteres; 1 decastere = 13 cubic yards; 2 millilitres = 34 ♏ (minims); 2 decilitres = 7 f ℥ (ounces); 4 litres

= 7 pints (imperial); 2 grammes = 31 grains; 4 grammes = 1 ʒ (drachm) (apothecaries'); 7 grammes = 4 dr. (drachms) (avoirdupois).

5 kilogrammes = 11 lb. (avoirdupois).

50 kilogrammes = 1 centner = 1 cwt.

Nobert's 19 *Band Test Plate*

Band	Lines per inch	Band	Lines per inch
1	11259·5	15	90076·1
5	33778·5	19	112595·1
10	61927·3		

Difference between each band = 5629·75.

Nobert's last 20 *Band Test Plate*

Band	Lines per inch	Band	Lines per inch
1	11259·5	15	168892·7
5	56297·6	20	225190·3
10	112595·1		

Difference between each band = 11259·5.

Convenient Formula for Lantern Projection or Enlargement and Reduction.

Let D be the distance of the screen, and d the distance of the object from the optical centre of the lens, F the equivalent focus of the lens, M the magnifying power or 'number of times' for enlargement or reduction. then—

$$D = F(M+1);\ d = F + \frac{F}{M} = \frac{D}{M};\ F = \frac{D}{M+1};\ M = \frac{D-F}{F};$$

Example: It is required to project by a lens of 6 inches equivalent focus a slide having a 3-inch mask so that it may give a 10-ft. disc, what must be the distance of the screen? Here M the magnification will be 40 times. $D = F(M+1) = 6(40+1) = 246$ inches = 20½ feet.

Note, in a double combination the optical centre may be assumed to be half way between the lenses. To reduce, interchange the object and the screen.

INDEX

A

Abbe (Prof.), his compensation eye-piece, 42, 323; binocular eye-piece, 103; stereoscopic eye-piece, 103; achromatic condenser, 212, 256–259, 329; chromatic condenser, 212, 256, 267; camera lucida, 237; apertometer, 255, 337; condenser, iris-diaphragm fitted to, 259; diffraction theory and homogeneous immersion, 312, 313; method of testing object-glasses, 326–333; test plate, 330, 331; experiments in diffraction phenomena, 376
— on amplifying power of lens, 25; on homogeneous immersion, 28; on improvement of optical glass, 31; on classification of eye-pieces, 34; on principle of microscopic vision, 43, 44, 45; on definition of aperture, 45; on aperture, 48 *note*; on radiation, 57; on angle of aperture, 60, 61, 62; on diffraction, 63–75; on 'intercostal points,' 73; on 'penetration,' 82; on over-amplification, 90; on stereoscopic vision, 90, 93; on 'aplanatic system,' 94; on orthoscopic effect, 95; on Ramsden's circles, 107; on solid cones of light, 362
Aberration, 19; positive, 21, 309 *note*; negative, 21, 27, 309 *note*; chromatic, 31; spherical, 31, 251, 254, 331; errors of spherical and chromatic, corrected by Ross, 306
Abies balsamea, 383
Abiogenesis, 686
Abraham's prism, 344
Absorption or dioptrical image, 64
— and diffraction images due to diffraction, 65 *note*
— of light rays, Angström's law, 273
— bands, 273, 274, 275, 277
Abstriction of spores, 562
Acalephæ, sexual zoöids of polypes, 786; relationship to hydroids, 796; development of, 798; medusan phase of, 801
Acanthometra xiphicantha, 774; *echinoides*, 777
Acanthometrina, 772, 776; central capsule of, 776
Acarina, eggs of, 928–929; anatomy of, 933–936; larvæ of, 933; nymph of, 933; integument of, 934; legs of, 934; eyes of, 935; classification of, 936
Accommodation, of the eye, 88; depth, 89
Acetabularia, 493; pileus of, 493
Acetic acid, as a test for nuclei, 440
Acheta, 911
— *campestris*, eggs of, 929
Achlya, zoöspores of, 494; oöspores of, 495; zoösporanges of, 569
— *prolifera*, 493 and *note*, 494
Achnantheæ, characters of, 545
Achnanthes, frustules of, 517, 544; stipe of, 518, 544; 'stauros' of, 545; structure of frustule, 545
Achnanthes longipes, 545
Achromatic, comparison of, with chromatic and apochromatic lenses, 315
— condenser, Abbe's, 212, 256–259, 267; Powell and Lealand's, 251, 258; for observation of pycnogonids, 883
— doublet, Fraunhofer's, 146; meniscus, 322
— lenses, Charles's, 146; Marzoli's, 302; Selligue's, 308
— objectives, 19, 32; Powell & Lealand's, dry, 190; Tully's, 303; Wenham's, 310; cover slips for use with, 380
— oil condenser, Powell & Lealand's, 267
Achromatism, 17, 19, 148; in photomicrography, 33; rise of, 145; inaugurated, 313; imperfect, causing yellowness, 360
Acineta, 697
'Acinetiform young' of *Ciliata*, 712 *note*
Acinetina, 696; food of, 697
'Acorn' monad, 684
'Acorn-shells,' 891
Actinia, reproduction from fragments, 787, 801
— *candida*, thread-cells of, 803
— *crassicornis*, thread-cells of, 803
Actinocyclus, 518, 539, 550
Actinomma inerme, 774, 776
Actinophrys, 770
— form of *Microgromia*, 662
— *sol*, 662–665
Actinoptychus, 518, 540, 541

ACT

Actinosphærium Eichornii, 665
Actinotrocha, 874
ACTINOZOA, 787, 801–806
Actius on myopy, 120
Actuarius on myopy, 120
Adams' variable microscope, 141; non-achromatic microscope, 146
'Adder's tongue' fern, 604; sporanges of, 601
Adipose substance, 969
Adjusting objectives, Ross's, 306, 309
Adjustment, coarse, 156, 157, 185; Wale's, 185
— fine, 157–164
— — long lever system, 151; Ross's, 151, 161; to Pritchard's microscope, 151; applied to stage, 153; Powell's, 161; short side lever, 162; Swift's vertical side lever, 162, 181; Campbell's differential screw, 164, 193; to the sub-stage, Nelson's, 169; for Powell & Lealand's sub-stage, 174; in Beck's No. 1, 180; Wale's, 185; in Beck's third-class microscope, 190
— screw collar, 309
Æcidiospore generation of *Puccinia*, 566
Æcidium berberidis, relation to *Puccinia*, 566
— *tussilaginis*, 567
Æthalium septicum, plasmode of, 563
Agaricus, 575
— *campestris*, 576, 577
Agate, 1017
Agave, leaf of, 611; raphides of, 621
Agrion, 911
— *pulchellum*, wing of, as test for definition, 368
— *puella*, pupa of, 918; wing of, 918
Air-angle, 50, 78
Air-bubbles, microscopic appearance of, 370, 371
Air-chamber of leaves, 641
Airy's modification of Huyghenian eyepiece, 321
Alæ of *Surirella*, 535
'Alar prolongations' in *Fusulina*, 750; in *Nummulites*, 752, 756; of *Calcarina*, 755
Albite, 1001, 1003
Albuminous substances, tests for, 440
Alburnum, 629, 633
Alcohol, as solvent for resins, &c., 441; as hardening agent, 428
Alcyonaria, 801, 803; spines of, imitated, 1022
Alcyonian, resembled by polyzoan, 832
Alcyonidium, 832; polyzoary of, 833
— *gelatinosum*, calcareous spicules in, 832 *note*
Alcyonium, 781
— *digitatum*, 803; spicules of, 804
Alder on branchial sac of *Corella*, 836 *note*
Alexander on myopy and presbyopy, 120
ALGÆ, preparation of, 427; included under general term of 'thallophytes,' 470; symbiotic in radiolarians, 773

AND

Algal constituents of lichens, 579
Alkaloids, micro-chemical examination of, 1024
Allman's experiments on luminosity of *Noctiluca*, 694
Allman on *Polyzoa*, 833; on the 'Hau' of *Appendicularia*, 842; on *Myriothela*, 787 *note*
Aloe, raphides of, 621
Alternation of generations in *Batrachospermum*, 504; in *Fungi*, 563; in ferns, 605; in *Medusæ*, 801
Althæa rosea, pollen-grains, 646
Alveolina, 729; resembled by *Loftusia*, 743; resembled by *Fusulina*, 750
Amaranthaceæ, pollen-grains, 646
Amaranthus hypochondriacus, seeds of, 648
Amaroucium proliferum, as example of compound ascidian, 836
Amici suggests oil for immersion lenses, 29
Amici's invention of immersion system, 27; horizontal microscope, 146; camera lucida, 235; objectives, 304; triple-back objectives, 310; water-immersion objectives, 310; oil-immersion objectives, 312
Ammodiscus, 739
Ammothea pycnogonoides, 882
Amœba, 658, 667–669, 942
Amœba-phase of *Monas*, 681
Amœba proteus, 667
— *radiosa*, experiments on, 668
Amœbæ, cells of sponges resembling, 779
Amœboid phase of *Tetramitus*, 686
Amphibians, plates in skin of, 950
Amphibolites, 1000
Amphioxus, affinities with ascidians, 841 *note*
Amphipleura pellucida, with oblique illumination, 59, 75; resolution of, 85; markings measured, 230; markings on, 521
Amphistegina, 752; internal cast of, 766
Amphitetras, 543
Amphiuma, red blood-corpuscle of, 960
Amphonyx, haustellum of, 916
Amplification, 83
— linear, 25, 26, 39; of images, 45
Ampullaceous sacs of sponges, 780, 781
Anabæna, 491
Anacharis, 458
— *alsinastrum*, cyclosis in, 613, 615; habitat, 614
Anagallis, raphides of, 621; seeds of, 649
— *arvensis*, petals of, 644
Anal plate of *Antedon*, 827
Analgesinæ, 937, 938
Analyser, 269
Analysing nose-piece, 244
Anaraphideæ, 527
Anchor-like plates of *Synapta*, 819
Andalusite, 1000
Androspore of *Œdogonium*, 503

ANE

Anemones, 787. *See* ACTINOZOA
Anemophilous flowers, 647
Anethum graveolens, seeds of, 649
Angle of incidence, 3; of refraction, 3; of aperture, 61
Angles of aperture, air, balsam, oil, water, 83–87
Angström's law for the absorption of light rays, 273
Anguillula aceti, 869
— *fluviatilis*, 869
— *glutinis*, 869
Anguillulæ, 869
Angular aperture, 338
— — of dry objective, 334; of oil immersion, 334
— — of aperture, resolution dependent on, 44
— — of water immersion, 334
Angular distribution of rays, 56; grip, 61; semi-aperture, 77
Anguliferæ, characters of, 542
Anilin dyes for blue and green stains, 436
Animal kingdom, two divisions of, 652
Animalcule cage, 294
Animalcules, 678. *See* ROTIFERA, *Infusoria*, RHIZOPODA, &c.
Animals and plants, differences between, 461
Anisochelæ of sponges, 783, 784
Anisonema, 690
ANNELIDA, larvæ of, collecting, 459; marine, 872; appendages of, 873; jaws of, 873; development of, 873; eggs of, 874; fresh-water, 879; luminosity of, 879; bibliography, 880; 'liver' of, 971
Annual layers in trees, 628
Annular cell, Weber's, 299
— ducts of Phanerogams, 623
— illumination and false images, 362
— illumination for examining perforated membrane of diatom, 362
Annulus of sporange of fern, 601
Anodon, pearls in, 847; glochidia of, 857; for observation of ciliary motion, 864
Anomia, prismatic layer in, 848
Anopla (Nemertines), 875
Anoplophrya circulans, 702
Anorthite, 1003
Antedon, food of, 696; pentacrinoid larva of, 825, 826; pseudembryo of, 827
Antennæ of insects, 911; preparation of, 912, 913 *note*
Antherid of Vaucheria, 492; of *Chara*, 507, 508; of *Fucaceæ*, 556, 557; of *Florideæ*, 561; of *Peronosporeæ*, 567; of *Marchantia*, 590, 592; of mosses, 595; of *Sphagnaceæ*, 598; of ferns, 602; tapetal cells in, 603
Antherozoids, 467, 470; of *Volvox*, 488; of *Vaucheria*, 492; of *Sphæroplea*, 501; of *Œdogonium*, 503; of *Batrachospermum*, 504; of *Chara*, 507, 508; of *Phæosporeæ*, 556; of *Fucaceæ*, 558; of ferns, 603; of *Rhizocarpeæ*, 606

ARA

Anthers, 644
Anthony (Dr.) on pseudo-tracheæ of fly's proboscis, 915 *note*
Anthophysa, 690
Anthracite coals, 1006
Antirrhinum majus, seed of, 648
Apertometer, 174, 333; Abbe's, 255, 337 Tolles', 333; use of, 337
Aperture, in microscopic objectives, 33, 43–47, 60–67; how obtained, 45; Abbe on definition of, 45, 48 *note*
— relation of, to power, 82, 83, 311; ascertained by vertical illumination, 286
— angular, 49 *note*, 53, 338
— numerical, 49 *note*, 53, 76, 333; for dry objective 50; for oil immersion, 50; for water immersion, 50
— numerical, of Zeiss's apochromatic series of objectives, 318
— of objective, 332, 333
— numerical, table of, 84–87
Apertures, relative, 49
Aphanizomenon, 491
Aphanocapsa, 477
Aphides, wings of, 922, 923; agamic reproduction in, 930
Aphodius, antennæ of, 912
Apidæ, 911
Apis mellifica, mouth-parts of, 915
Aplanatic system, 20, 23
— objective, use of, 21
— cone, 255
— aperture, 257, 262
— foci, Lister's discovery, 304
Apochromatic objectives, 19, 30, 32, 34, 80, 211; advantages of, 33, 34; objective, Zeiss's, 314–320; dry, 315; comparison of, with chromatic and achromatic lenses, 315; homogeneous objectives, value of, in study of monads, 687; objective, use with various test scales, 900
— condenser, Powell and Lealand's, 254
Apochromatism, 314
Apocynaceæ, laticiferous tissue of, 620
Apogamy in ferns, 605
Apospory in ferns, 605
Apotheces of lichens, 578, 579
Apparent creation of structure, 68
Appendicularia, 835, 841; pharyngeal sac of, 841; tail of, 842; notochord, 842; 'Haus' of, 842
Apple, raphides in bark of, 621
Apposition, growth by, 463
— mode of growth of starch, 620
Apus, 883, 886; parthenogenesis of, 888 *note*
— *cancriformis*, carapace of, 886
Aquarium microscopes, 219–225; Collins's, 221, 222; Schultze's, 222, 224
Aquatic microscope, 145
ARACHNIDA, 932
— eggs of, 929; related to *Pycnogonida*, 883 *note*; reproductive organs of, 935
Arachnoidiscus, 518, 541
Arachnosphæra obligacantha, 774, 776

ARA

Aralia papyrifera, parenchyme of, 611
Araneida, 932
Arcella, 670
Archegones of *Vaucheria*, 492; of *Chara*, 507, 508; of *Marchantia*, 590, 593; of mosses, 595, 596; of *Sphagnaceæ*, 598; of ferns, 602, 603; of *Lycopodieæ*, 606; of *Rhizocarpeæ*, 606
Archer, on amœbiform phase of *Stephanosphæra*, 485 *note*; on desmids, 509 *note*; classification of, 515; on *Clathrulina*, 666 *note*; on rhizopods, 677
Archerina Boltoni, 655
Arctium, stem of, 634
Arcyria flava, sporanges of, 564
Arenacea, 735–739
Arenaceous character of *Textulariniæ*, 748
— *Foraminifera*, varying size of particles in test of, 748
— test of *Foraminifera*, 735
Arenicola, 872
Areolæ of frustule of *Coscinodiscus*, 520
Areolar connective tissue, 964, 969
Argas, bite of, 936
Argasidæ, 936
Argonauta, 858
Argosinæ, 932
Argulus foliaceus, 890
Aristolochia, stem of, 634
'Aristotle's lantern' of echinids, 814
Aristotle on myopy and presbyopy, 120
Arragonite, 1017
— in shell of *Pholas*, 848
Arsenic, micro-chemical analysis of, 1023
Artemia, 886
— *salina*, movement of, 884; habitat of, 887
Arteries, 980
Arthrodesmus incus, 498
ARTHROPODA, 881–940; smallest of, 932; eye of, 907
— limbs of *Pedalion* compared with those of, 718
Arthrosporous *Bacteria*, 582
Artificial light, 359
'Artificial lightning,' 607
Ascaris lumbricoides, 868
Asci of *Ascomycetes*, 571; of lichens, 578
Ascidians, diatoms in stomach of, 544, 552; solitary, 835; branchial sac of, 836, 837, 839; circulation in, 836, 839; compound, 836; cloaca of, 837; stolons of, 838; bibliography of, 838; social, 838; general structure of, 840; development of, 840; tadpole of, 841; affinities with *Amphioxus*, 841 *note*
Asclepiadeæ, pollinium of, 647
Ascogone of *Ascomycetes*, 572; of lichens, 579
Ascomycetes, 571–574; as fungus-constituents of lichens, 579
Ascopores of *Ascomycetes*, 571; of lichens, 578
Asellus aquaticus, ciliated parasite in blood of, 702

BAC

Asilus, eye of, 911
Aspergillus, fermentation by, 575
Asphalte for cells, 386
— varnish, 383
Aspidisca, a phase in development of *Trichoda*, 709
Aspidium, indusium of, 600; sori of, 600
Asplanchna, in confinement, 458
Astasia, 475; mouth in, 690
Asteroidea, skeleton of, 815; spines of, 815; larva of, 821
Asterolampra, 524, 539
Asteromphalus, 539
Astromma, 774
Astrophyton, spines of, 815
Astrorhiza, 736, 740
Astrorhizida, 737
Athecata, 792
Athyrium Filix-fœmina, apospory in, 605
Atrium of *Noctiluca*, 691
Auditory vesicles of *Mollusca*, 865
Audouin on 'muscardine,' 574
Augite, 995; zonal structure in, 996
Aulacodiscus, 541
— *Kittonii*, markings on, 521
— *Sturtii*, markings on, 521
Autofission of diatoms, 523
Auxospore, 523–530
Avanturine, 1016
Avicularia of *Polyzoa*, 834, 835
'Awns' of *Chætocereæ*, 543
Axile body of tactile papilla, 977
Axinella paradoxa, 782
Axis cylinders of nerve-tube, 975, 976

B

Bacillariaceæ of Kützing, 517
Bacillaria paradoxa, movements of, 528, 531, 535
Bacilli, form of, 581
Bacillus, 'granular spheres' of, 588 *note*
— *anthracis*, 582; spores live in absolute alcohol, 587
— *megaterium*, 582
— *subtilis*, 582, 583, 585; spores of, 587
— of anthrax, 961 *note*
— of tuberculosis, modes of staining, 438, 439
'Bacon-beetle,' 904
Bacon (Roger), inventor of simple microscope, 128
Bacteria, use of large and small cones in examining, 363; photo-micrographs, 365; as test for definition, 368; preserved by osmic acid, 428; violet of methylanilin as a stain for, 437; methylblue as a stain for, 438; staining, 437, 438; (see *Schizomycetes*), 579; affinities to *Algæ*, 580; to *Flagellata*, 580; to *Nostocaceæ*, 580; forms of, 581; movements of, 581; mode of multiplication, 581; classification of, 582; nutrition of, 585; flagella of, 587; germinating power of, 587; spores of, 587
Bacteriastrum furcatum, 543

Bacteriology, 589
Bacterium lineola, compared with *Cercomonas*, 580
— *lineola*, 586
— *termo*, flagellum of, 72; movement of, 581; zoöglœa of, 585, 586; germination of, 587
Bailey, on internal casts of *Foraminifera*, 753 *note*
Bailey's method of isolating diatoms, 553
Baker on Cuff's microscope, 140
Baker's students' microscope, 193; optic axis of, 194
— lamp, 350
Balanidæ, 891
Balanus balanoides, 891; disc of, 892
Balbiani on supposed sexual reproduction of *Ciliata*, 709
Balsam angle, 50, 78
— refractive index of, 77
Banksia, stomates of, 641
Barbadoes earth, 771, 774
Bark, 625, 627, 633
Barker's Gregorian telescope, 144
Bar movement, 215
'Barlow lens' applied to a microscope, 147
Barnacles, 891. See *Cirripedia*
Basals of *Antedon*, 825
Basidiomycetes, 575; as fungus-constituent of lichens, 579
Basidiospores of *Basidiomycetes*, 576; of *Hymenomycetes*, 576
Basids of *Puccinia*, 566; of *Basidiomycetes*, 576
Bast, 635
Bat, parasite of, 936; hair of, 954; cartilage in ear of, 970
'*Bathybius*,' 672
Batrachia, red blood-corpuscles, 959; lungs of, 987
Batrachospermeæ, 503
Batrachospermum moniliforme, 504
— protoneme of, 505
'Battledore scale' of *Lycœnidæ*, 899
Bausch and Lomb's microscope, 185–188; chemical microscopes, 217–220; 'laboratory' microscope, 218; 'University' chemical microscope, 219, 220; neutral tint camera lucida, 235
Bdella, maxillary palps of, 934
Bdellidæ, 937
Bdelloida, 717, 718
Bead-moulds, 573
Beale's microscope for class demonstration, 225; camera, 234, 235, 239; carmine, 435; bioplasm, 435; glycerin method of preserving, 444
Beale on organic structure, 942
Beck's No. 1 microscope, 180, 182; substage in, 181, 182; small first-class microscope, 189; third-class microscope, 190–192; 'Star' microscope, 194; 'economic' microscope, 194, 196; histological dissecting microscope, 197, 198; portable microscope, 199, 202; binocular dissecting microscope, 207; rotatory nose-piece, 242; variable condenser, 260; mode of using parabolic speculum, 281; light modifier, 284; vertical illuminator, 285; disc-holder, 288; rings for locking coarse adjustment, 301; lamp, 348, 349; achromatic binocular magnifier, 396 *note*; disc-holder for examination of *Foraminifera*, 770
Beck (R.) on markings of Podura scale, 902
Beck-Jackson model, 162
Bee, hairs of, 904; head of, 906; wing of, 918, 922; sting of, 927
Beeldsnyder's achromatic objective, 145
Beetles. See *Coleoptera*
Beggiatoa, form of, 581
— *alba*, 583, 584
Begonia, seeds of, 649
Behrens' method of analysing minerals, 1004
Bell (Jeffrey) on the spines of *Cidaris*, 818
Bell's cements, 383, 448
Beneden (Ed. Van), on *Gregarina gigantea*, 674 *note*; on movement of gregarines, 675
Benzol, uses of, 441
Bergh on *Flagellata*, 689
'Bergmehl,' 551
Berkeleya, 528
Bermuda earth, 538, 540
Beroë, collecting, 459
— *Forskalii*, 805
— *ovatus*, Eimer on, 806 *note*
Bicellaria ciliata, 834
Bichromate of potash, 430
Biconvex lens, formulæ relating to, 21
Biddulphia, 542
— cyclosis in, 517; chains of, 517, 525; structure of frustule, 519 *note*
Biddulphieæ, character of, 541
Biflagellate monad, 684
Bignonia, seed of, 648
Bignoniaceæ, winged seeds, 648
Biloculina, 727
Binary subdivision of cell, 465, 466
Binocular eye-piece, Tolles', 102; Abbe's, 103
Binocular magnifier, Beck's achromatic, 396 *note*
Binocular microscope, 61, 97
— — Riddell's, 96; Nachet's, 98; stereoscopic, Wenham's, 98; Stephenson's, 100; Stephenson's erecting, 102; stereoscopic, for study of opaque objects, 105, 107; use of, 105; non-stereoscopic, 106; Powell & Lealand's high-power, 107; portable, Rousselet's, 200; body in Beck's portable, 200; Stephenson's for dissection, 201, 203, 344, 395; dissecting, Beck's, 207; spectrum microscope, 276
Biology, 460
Bioplasm, 435
'Bipinnaria,' resemblance of *Actinotrocha* to, 874
Bipinnaria asterigera, 821

BIR

Birch, pollen-grains of, 647
Bird, parasite of, 936, 938; lacunæ in bone of, 946; epidermic appendages of, 953; red blood-corpuscles of, 958, 959; lungs of, 988
Bird's egg, concretions on shell imitated, 1023
'Bird's head processes,' see *Avicularia*, 834
Bismarck brown, 437
Bivalves, structure of ligament in, 964
'Black dot,' Nelson's, 233
'Bladderwrack,' 556
Blanchard (R.) on osmic acid, 428; on *Sporozoa*, 674 *note*
Blatta, antennæ of, 912
— *orientalis*, eggs of, 929
Blenny, scales of, 951
Blood, colourless corpuscles, 942; method of mounting, 962; circulation of, 978; flow of, 979; micro-chemical examination, 1024
— of insects, circulation of, 917, 918; of *Vertebrata*, 958
Blood-corpuscle, relation of size to that of bone lacunæ, 946
Blood-corpuscles of *Vertebrata*, 958
Blowfly's maxillary palpus, hairs on, examination of, 365
Blowfly, proboscis of, examination with apochromatic, 318; hairs on, as test for definition, 368
— development of 931; 'imaginal discs' of, 931
Blue-black, for nerve-cells, 437
Blue glass for softening light, 360
'Blue mould,' 571
Bodo, 475
Body of the microscope, 155
'Bog-mosses,' 598
Boletus, 575
Bombyx, 911
— *mori*, eggs of, 929
Bonanni's microscope, 134; his horizontal microscope, 135; his compound condensers, 248, 249
Bone, 943; structure of, 944; preparation of, 947; matrix of, 963; decalcification of, 426
Bones, fossilised, 1012, 1013
'Bony pike,' scale of, 946
Borax carmine, 435
Bordered pits in the tracheïdes of conifers, 622, 628
Boscovich on chromatic dispersion, 42
Botryllians, 838
Botryllus violaceus, 839
Botryocystis, 475
Botrytis bassiana, 573
Botterill's growing slides, 289; his zoöphyte trough, 298
Bouguet on uniform radiation, 51
Bowerbank on sponge spicules, 783 *note*; on structure of molluscan shells, 845
Bowerbankia, gizzard of, 829; stem of, 832; polyzoaries of, 833

BUL

'Box-mite,' 936
Brachinus, antennæ of, 912
Brachionus rubens, 714, 715, 718; male of, 717
Brachiopoda, shells of, 843, 849, 851; relation of shell to mantle, 850; affinities to *Polyzoa*, 851
Brachyourous decapods, young of, 894
Brady (H. B.) on *Foraminifera*, 735; on arenaceous *Foraminifera*, 736; on affinity of *Carpenteria*, 748
Brady and Carpenter on fossil *Lituola* 742
Brain, Hill's method of preparation of, 434
'Brake-fern,' 600. See *Aspidium*
Bran, 649
Branchiæ of annelids, 872, 873
Branchiopoda, 883; divisions of, 885
Branchipus, movement of, 884
— *stagnalis*, 886, 887
Branchiura, 889 *note*, 890
Brandt (K.) on artificial division of *Actinosphærium*, 666 *note*; on zoöxanthellæ, 773
Braun on *Pediastrum*, 497
Brewster, his hand magnifier, 37; on modification of stereoscope, 91; on 'lens' from Sargon's palace, 121; his 'Treatise on the Microscope,' 122; on achromatic condensers, 249
Bright-line spectro-micrometer, 274
Brightwell on *Triceratium*, 543 *note*; on *Chætocereæ*, 544 *note*
Brilliancy of image, 326
'Brimstone moth,' eggs of, 929
Brine shrimp, 884, 887
'Brittle stars,' 815. See *Ophiuroidea*
Brooke's nose-piece, 241
Brownian movement, experiments, 373-374
Brücke lens, 38
Brunswick black as a black 'ground,' 384; for cells, 386
Bryaceæ, 598
Bryobia, 937
Bryony, cells of pollen chambers, 645
Bryozoa, 828. See Polyzoa
Bryum intermedium, peristome of, 597
Bubbles in cavities of crystals, 997
Buccinum, 861
— *undatum*, palate of, 854, 856, 857; nidamentum of, 858
Buchner's experiment on spores of *Bacteria*, 587
Buckthorn, stem of, 628
Bug, mounting medium for, 897
Bugula, polyzoary of, 833
— *avicularia*, 834, 835
Built-up 'cells,' 389
Bulbils of *Nitella*, 507
Bulloch's modification of Zentmayer's microscope, 184, 186, 187
Bull's-eye, 250; use of, 278, 279, 351, 357; with high power, 280; for use in study of saprophytic organisms, 280; Powell and Lealand's, 280

BUL

Bull's-eye stand, 201
Bundle-sheath, 685
Burdock, stem of, 684
Bütschli on *Rhizopoda* and *Sporozoa*, 677; on mouth of *Astasia*, 690; on *Vorticellæ*, 701 *note*
— and Engelmann on conjugating vorticellids, 711
Butterflies, wing of, 918
Butterfly. See *Lepidoptera*

C

Cabbage-butterfly, eye of, 907; number of facets in, 907; eggs of, 929
Caberea Boryi, vibracula of, 881 *note*
Cabinet for slides, 454; arrangement of, 454
Cactus, cells of pollen-chambers, 645
Cactus senilis, raphides of, 621; brittleness of, 621
Cucumaria crocea, development of, 824 *note*
Calamites, 1005
Calathus, antennæ of, 912
Calcarina, 750, 755; compared with *Eozoön*, 763
Calcispongiæ, spicules of, 783
Calcite in shells, 848
Calco-globuline, 1022
Callithamnion, 559
Calosanthes indica, winged seed of, 649
Calotte diaphragms, 247
Calycanthus, bark of, 684
Calycine monad, 685
Calycles of hydroids, 792
Calypter of mosses, 596
Calyx of *Flagellata*, 689
Cambium, 635
— in Exogens, 622
— layer, 633
Cambridge rocking microtome, 408
Camera lucida, 233; Beale's, 234, 235, 239; Soemmering's, 234; Wollaston's, 234; Amici's, 235; Bausch and Lomb's, 235; Schröder's, 236; Abbe's, 237
Campani's microscope, 130; eye-piece, 321
Campanula, pollen-grain of, 646
Campanularia, 794
— *gelatinosa*, 789
Campanulariida, 794; zoöphytic stage of, 801
Campbell's differential screw, 158, 193; adapted to the Continental model, 164; fine adjustment, 164, 193; used in photo-micrography, 194
Campylodiscus, 518, 524, 536; movements of, 531; structure of frustule, 536
— *clypeus*, 536
— *spiralis*, cyclosis in, 517
Canada balsam, 383
——as a preservative medium, 441; mode of preparation, 441; as mounting medium, 444, 449; refractive index, 445; capped jars for, 447; for mounting insects, 897
Canal system of *Calcarina*, 750; of *Polystomella*, 752; of *Nummulites* 752
Canaliculi of bone, 943, 945
Cancellated structure of bone, 944
Cancer pagurus, skeleton of, 892
Canna, starch-grains of, 620
Cannel coals, 1006
Cannocchiale, 127
Capacity of object-glass, 326
Capillaries, 980, 986
Capillitium of *Myxomycetes*, 565
Capsule, central, of *Radiolaria*, 772
— of mosses, 595; of *Purpura*, 858
— silicious, of *Clathrulina*, 666
Carapace of *Copepoda*, 884; of *Cladocera*, 885
Carbolic acid: for mounting preparations, 442; for dehydration, 450
Carbon bisulphide as a solvent for oils, &c., 441
Carboniferous epoch, vegetation of, 606
— limestone, 1011
Carchesium, collecting, 457
Carcinus mœnas, metamorphosis of, 894
Carnallite, 998
Carnation, parenchyme of, 613
Carnivora, arrangement of enamel in, 949
Carp, scales of, 951
Carpenter (H. P.) on crinoids, 827 *note*
Carpenter (W. B.) on stereoscopic vision, 93; on classification of *Foraminifera*, 724; on *Eozoön*, 763; on alternation of generations in *Medusæ*, 801; on the so-called excretory pores of *Ctenophora*, 806 *note*; on development of *Antedon*, 827 *note*; on structure of molluscan shells, 845
Carpenteria, 747; mode of growth compared with *Eozoön*, 763
— *rhaphidodendron*, 748
Carpogone of *Florideæ*, 561; of *Ascomycetes*, 572
Carpospores of *Florideæ*, 561
Carrot, seeds of, 649
Carter (H. J.) on affinity of *Carpenteria*, 748
Cartilage, 970; mounting, 971
Carum carui, seeds of, 649
Caryophyllia, lamellæ of, 802
— *Smithii*, thread-cell of, 803
Cascarilla, raphides of, 621
Cassowary, egg-shell of, 1021
Castracane, on beaded structure of diatoms, 522; on Pfitzer's auxospores, 523, 524; on sporangial frustules of diatoms, 524; on reproduction of diatoms, 526; on diatoms, 528
Cat, Pacinian corpuscles of, 977
Catadioptric illuminator, Stephenson's, 170, 263–265
Caterpillars, 'pro-legs' of, 926; feet of, 926
Cathcart's freezing microtome, 412, 418

CAT

Catoptric form of microscope, 144
Cattle-plague, 588
Caulerpa, 498
Cauterisation by focussing the sun's rays (Pliny), 119
Cedar, stem of, 630
Cell, contents of, 463–465; binary subdivision of, 465
'Cell' of *Polyzoa*, 828
Cell-division and nucleus, 948 and *note*
Cell-sap, 464
Cell-structure, Strasburger on, 467
Cell-wall, 463; mode of growth of, 463; apposition, 463; intussusception, 463
— of Phanerogams, 617
Cells of plants, 462; multi-nucleated, 464; primordial, 465; of vertebrates, 942
Celloidin as an imbedding mass, 417; as congelation mass, 419; for freezing, Hill's method, 419; clearing agents
'Cells' for mounting *Infusoria*, &c., 299; for dry mounting, 385; sunk, 388; of cement, 382; paraffin, 386; paper, 386; of plate glass, for zoöphytes, &c., 388; built up, 389; mounting in, 451, 452; of bone, 452; of tin, 452
for, 419; Schering's, 419
Cellular cartilage, 970
— parenchyme, 618
Cellulose, 463
— tests for, 440; envelope of desmids, 509; in *Dinoflagellata*, 695; in zoöcytium of *Ophrydium*, 706
Cement-cells, 386
Cements, 382; liquid, 382; Bell's, 383, 448; japanner's gold size, 383; Brunswick black, 384; glue and honey, 384; shellac, 384; Hollis's liquid glue, 384, 449; Venice turpentine, 384; marine glue, 385; Heller's porcelain, 445
Cementum of teeth, 949, 950
Centipedes. See *Myriopoda*
Central capsule of *Radiolaria*, 659
Centring, 326
Centring nose-piece, 242; as sub-stage, 193
Centro-dorsal plate of *Antedon*, 825
Cephalolithis sylvina, 771
Cephalophorous mollusca, palates of, 854–857
CEPHALOPODA, 853
— organs of hearing in, 865; chromatophores of, 866
Ceramiaceæ, 559
Ceramium, 559
Ceratium, 695
— *furca*, 696
— *tripos*, 696
Ceratodus, 1013
Cercomonas typica, compared with *Bacteria*, 580
Cereals, seeds of, starch in, 619
Certes on osmic acid, 428
Cerura vinula, eggs of, 929
Cestoid, 867
Cetonia, antennæ of, 912
Chætocereæ, affinities of, 543
Chætocereæ, 'awns' of, 543
— occurrence in marine animals, 544
Chætoceros Wighamii, 543
Chætophoraceæ, 503, 589
'Chaff-scales,' silex in, 640
Chalk, metamorphism of, 1000; microscopic constituents of, 1007, 1009; resemblance to *Globigerina* ooze, 1009; mode of preparation for examination, 1010
Chama, prismatic layer in, 848
Chamberlets in *Foraminifera*, 723, 728, 729; of *Parkeria*, 742; in *Fusulina*, 750; of *Cycloclypeus*, 760
Chamidæ, *Foraminifera* attached to shells of, 770
Changes of form of white corpuscles, 963
Chantransia and *Batrachospermum*, 504, 505
Chara, 505; antherozoids of, 593
Characeæ, 505–509
Charbon, due to *Bacillus anthracis*, 582
Charles's achromatic lenses, 146
Cheese-mite, 932, 937
Cheilostomata, characters of, 833; examples of, 834
Cheirocephalus, 886, 887
Chemical tests for biological work, 439, 440
Cherry-stone, section of, 617
Chérubin d'Orléans, his binocular microscope, 132, 133; his compound microscope, 132
Chevalier on Charles's achromatic lenses, 146
Chevalier's combination of lenses, 38; achromatic microscope, 146, 148; modifications of Selligue's lenses, 303; objectives, Lister's note on, 304
Cheyleti, 937
Cheyletidæ, tracheæ of, 935
Cheyletus, hairs of, 934; legs of, 934; mouth parts of, 934
Chickweed, petals of, 644
Chicory, adulteration of, 650 *note*
Chilodon, mouth of, 702
— *cucullus*, binary division of, 704, 706
Chilognatha, 905
Chirodota violacea, 'wheels' of, 820
Chitin, in test of *Arcella*, 670; of insects' skin, 898
Chitinous substances, mounting, 450
Chiton, shell structure, 852; eyes on shells of, 865
Chlamydomonas, 473 *note*, 475
Chlamydomyxa, affinity with *Monerozoa*, 652
Chlamydospores, of *Mucorini*, 569; of gregarines, 675
Chloral hydrate as a preservative medium, 442
Chloride of gold, for histology, 437
Chloroform, uses of, 441
Chlorophyll corpuscles, 464, 465
Chlorosporeæ, 554
CHORDATA, 885. *See* VERTEBRATA
Choroid coat of eye, pigment-cells in, 966

CHR

Chromatic, comparison of, with achromatic and apochromatic lenses, 315
— aberration, 16, 17, 31
— condenser, Abbe's, 212, 256, 267, 329; Powell and Lealand's oil, 258
— correction, test for, 331
— dispersion, diminished by Huyghens' objective, 42
Chromatophores of *Peridinium*, 695; of Cephalopods, 866
Chromatoplasm, 467
Chromic acid as hardening agent, 428
Chroöcoccaceæ, characters of, 477
Chroöcoccus, 477; as gonid of lichen, 579
Chroölepus, as gonid of lichen, 579
Chrysaora, 798, 800; development of, 800
Chyle, corpuscles in, 961
Chytridiaceæ, 565
— zoöspores of, 555
Cicadæ, wings of, 922, 923
Cichoriaceæ, pollen-grains of, 646
Cicindela, 911
Cidaris, spine of, 809, 812
— *metularia*, mode of formation of spines in, 813
Cienkowski on decaying cells of *Nitella*, 509 *note*; on parasitic plasmode in *Nitella*, 509 *note*; on reproduction of *Noctiluca*, 694
Cilia, 462, 968; of *Infusoria*, 699; use of, in *Ciliata*, 701; of *Turbellaria*, 870
Ciliary action, 699
— motion on gills of *Mollusca*, 864
— movement in protophytes, 465
Ciliata, 699–712; ciliary action of, 699, 701; 'shield' of, 700; lorica of, 700; myophan-layer, 701; trichocysts of, 701; ento-parasitic forms, 702; mouth of, 702; foot-stalk in, 702; impressionable organs of, 702; 'eye-spots' of, 702; food of, 703; artificial feeding, 703; contractile vesicles of, 704; multiplication of, 704; colonial forms, 705; encystment of, 707–709; supposed sexual reproduction, 705, 709–711; dispersion of, 709; desiccation of, 709; conjugation of, 711; Stein on acinetiform young of, 712 *note*
Ciliate *Infusoria*, general structure of, 679
Ciliated epithelium, 968
Ciliobrachiate zoöphytes, 829
Cilio-flagellata, 695
Cilium of *Noctiluca*, 691 *note*
Cimex lectularius, eggs of, 929
Cinchona, raphides of, 621
Cinclidium arcticum, peristome of, 597
Cineraria, pollen-grains of, 647
Cineritious matter, 976
Circulation in ascidians, 836, 839
— of blood, 978
Circumambient chamber in *Orbitolites*, 731
Cirrhi of *Cirripedia*, 892
Cirripedia, 891
Cladocera, 885

COH

Cladococcus viminalis, 774, 776
Cladonia furcata, 579
Cladophora glomerata, 499; cell division of, 499, 504
Cladorhiza inversa, 784
Claparède and Lachmann on *Lieberkuehnia*, 656; on 'rolling' movement of *Amœba*, 669
Clark (James) on *Flagellata*, 689
Clastic rocks, 998
Clathrulina elegans, 666
Clausius on emission of light, 54
Clavelinidæ, gemmation of, 836; stolons of, 838
Claviceps purpurea, 572
Clavicornes, antennæ of, 911
Claws, 953, 957
Clay, 1014
Cleanliness, importance of, 453
Clematis, stem of, 627
'Closed' bundles, 635
Closterium, cyclosis in, 510; 'swarming of granules' in, 511; binary division in, 511; two zygospores in, 513 *note*; zygospore of, 514; form of cell, 515
Clostridia, form of, 581
'Clothes-moth,' 923
Clove-pink, seed of, 648
'Club-mosses,' 606
Clypeaster, spines of, 813
Coagulation, imbedding by, 418
Coal-plants, 1005
Coarse adjustment, 'stepped' diagonal rackwork for, 157; of Ross model, 177; Wale's, 185; arrangements for 'locking,' 301
Cobœa, testa of seeds of, 649
— *scandens*, pollen-grains of, 646
Coccidia, 676, 677
Coccidium oviforme, 676
Coccoliths, 672–674; in chalk, 1010
Cocconeideæ, characters of, 544
Cocconeis, 544
Cocconema, 528, 545, 551
— *fusidium*, 551
Coccospheres, 672, 674; in chalk, 1010
Cockchafer, antennæ of, 898. See *Melolontha*
'Cockle' in wheat, 869
Cockroach. See *Blatta*
Cocoa-nut, 649
— shell of, 618
Cocos-wood, 629
Coddington lens, 37
Codium, 493
Codosiga umbellata, fission of, 689; arborescent colonies of, 690
Cœlenterata, 786–807; bibliography of, 806; permanent gastrula-stage of, 652
— *See* Zoöphytes
Cœloplana, 806
Cœnosarc, of hydroids, 791, 794
Cœnurus, 868
Cohn, on sexual generation of *Volvox*, 483; on movements in *Oscillaria*, 490; on reproduction of *Sphæroplea*, 500, 501; on affinities of *Bacteria*, 519

COL

Cole (Arthur) on use of absolute alcohol, 428; on use of borax carmine for vegetable substances, 436
Coleoptera, 897; dermo-skeleton of, 898; scales of, 899; elytra of, 905; eyes of, 911; antennæ of, 911, 912; mouth-parts of, 918; wings of, 923; leg of, 924
Coleps, food of, 703
Collar correction, 307
Collared cells of sponges, 780
'Collars' of *Flagellata*, 689
'Collateral' bundles, 635
Collection of microscopic objects, apparatus for, 456
Collembola, 901
Colletonema, 528
Collins's aquarium microscope, 221–223; condenser with rotating sub-stage, 329
Collonia, testa of seeds of, 649
— *grandiflora*, spiral fibres in seeds of, 618
Colloæoa, 777
Colonial *Acinetina*, 698
Colonies, in *Codoniga*, 689; of Radiolarians, 773; of *Polyzoa*, 828
Columel of *Sphagnaceæ*, 599
Comatula, 824, 825; nerves of, 976
'Comb-bearers,' 805. See *Ctenophora*
Commensalism, in lichens, 598
Compensating eye-pieces, 34, 229, 323
Compositæ, laticiferous tissue of, 623
Compound condenser, sub-stage, 135
— microscope, construction of, 39; invention of, Govi on, 122
Compression of light rays, 57
Compressor, 295; Rowland's reversible, 295; Powell and Lealand's, 296; Delage's, 296, 297
Compressorium, 295
'Concentric' bundles, 635
Conceptacles of *Fucaceæ*, 556; of *Marchantia*, 591
Conchifera, shell of, 843
Concretionary spheroids, 1021
Condensers, 170, 248–263
— Kellner eye-piece used as, 177; Gillett's, 184, 250; Hartsoeker's, 248; Bonanni's compound, 248, 249; Swift's low-power, 252; Webster's, 256; Abbe's, 256–259; Beck's variable, 260; Powell and Lealand's 262; Swift's, for use with polariscope, 262; Collins's, with rotating sub-stage, 329
— total aperture of, 255
— tabular list of, 263
— achromatic, 198; Abbe's, 212; Powell and Lealand's, 251–254, 263, 267; Brewster on, 249
— chromatic, Abbe's, 212, 329
— sub-stage, Stephenson's, 101; compound, 135
Cone of light, 170
Conferva, 486
Confervaceæ, 478, 498–500; binary division of, 499; zoöspores of, 500; resemblance of *Melosireæ* to, 537

COR

Confervæ, 869, 884
Congelation mass: gum arabic, 41
loidin, 419
Conical epithelium, 968
Conids, of *Ascomycetes*, 571; of *B*
mycetes, 576
Coniferæ, 609; woody cells of, 62
Coniferous wood fossilised, 630, 10
Conjugatæ, affinities of, 477
Conjugate foci, 13; focus, 24; ima
Conjugating cells, 470
Conjugation, a sexual act, 467
Conjugation of *Mesocarpus*, 4
Spirogyra, 478; of *Ulothrix*,
Hydrodictyon, 495; of *Desmi*
513; of diatoms, 528; of *Phæo*
556; of *Myxomycetes*, 564; of *A*
671; (zygosis) of *Gregarinæ*, 6
Heteromita, 685; of *Tetramitu*
of *Noctiluca*, 694; of *Glenod*
695; of *Podophrya*, 699; of *C*
711; of *Vorticella*, 711
Connective tissue, 943; fibrous
areolar, 964; corpuscles of, 963,
Contact metamorphism, 1000
Continental correctional collar, 30
— microscopes, objections to, 158
— model, 208–213; criticism on, 2
Continuity of protoplasm in *Flo*
560
Contractile vacuole in *Volvox*, 481
— vesicle, of *Actinophrys*, 66
Microgromia, 661; of *Amœba*
of *Infusoria*, function of, 67
Flagellata, 689; of *Paramecium*
of *Stentor*, 704; of *Ciliata*, 7
Rotifera, 716
Convergence of light, 18
Conversion of relief in spectroscop
shown by *Arachnoidiscus*, 541
Convolvulaceæ, laticiferous tissue
Convolvulus, pollen-grains, 646
Copepoda, 884; classification of, 8
Copeus cerberus, 718
Copper sulphate, crystallisation of,
Coquilla-nut, 649
— section of, 617
Coralline crag, microscopic constit
of, 1011
Corallines, 884
— conceptacles of, 561; ostiole of,
— (sertularids), 794
Corals, section of hard and soft
423
— red, 801; stony, 802; mushroom
Cordierite; pleochroism in, 1002
Corella parallelogramma, branchu
of, 836
Coreopsis tinctoria, seeds of, 649
Cork, 633
Corky layer of bark, 633
Cormophytic type, 594
Cormorant, parasite of, 934
Corneules of arthropod eyes, 907
Corn-grains, husk of, 649
Cornuspira, 726, 728
'Corpuscle' of gymnosperms, 610

Corpuscles, white, 961; change of form of, 962; of connective tissue, 963, 965; of blood, flow of, 980
Corrected lenses, 326
Correction collar, 21, 29, 50, 230
Correctional collar, Continental, 307; English method, 308
Corroded crystals, 995
Corrosive sublimate, as a preservative medium, 443
Corynactis Allmanni, thread-cell of, 808
Coscinodisceæ, characters of, 537
Coscinodiscus, 518, 550
— cyclosis in, 517; markings on frustule of, 520; areolæ of, 520; frustules of, 537, 538
— *asteromphalus*, for testing lenses, 333
— *oculus iridis*, 538
— *punctatus*, fossil, with embryonal form, 527
Cosmarium, division of, 512; form of cell, 515
— *botrytis*, zygospore of, 514
Cosmic dust, 1015
Costæ of *Campylodiscus*, 536
Costonella, silicious shell of, 700
Cotyledons, 610
Cover-glass, 330
— consequence of using, 19; as section lifter, 432
— tester, Zeiss's, 331; Ross's, 331, 332
— varying thicknesses of, 330; with achromatic objectives, 330; cleaning them, 332
Cox (J. D.) on structure of frustule in *Isthmia*, 519 *note*
Crab, 881; metamorphosis, 893; blood-corpuscles of, 962; 'liver' of, 971
Crabro, leg of, 898
Crane-fly. *See* Tipula
Craterium pyriforme, 933
Crayfish, 881; young of, 893
Creation of structure by diaphragms, 68
Cribrilina figularis, 830
Cricket, gizzard of, 917; wings of, 923; sound-producing apparatus, 923. See *Acheta*
Crinoidea, skeleton of, 816; larva of, 822
Crisia, 833
Crisp (F.) on 'aperture,' 45; on radiation, 75; on collection of microscopes, 119
Cristatella, 833
Cristellaria, shell of, 723, 744
Critical angle, 6, 7; image, 30, 249; images, 238; mode of obtaining, 352, 353
Crocus, pollen-grains of, 647
Crouch's adapter for parabolic speculum, 281
'Crow silk,' 499
Crown glass, refractive index of, 5; composition of, 32
Crusta petrosa of teeth, 949, 950
CRUSTACEA, 881–895
— larvæ of, collecting, 459
CRUSTACEA, suctorial, 889
— collecting, 895; preserving, 895; compound eyes of, 906; pigment-cells of, 967; 'liver' of, 971; concretionary spheroids in shells of, 1021
CRYPTOGAMIA, 462–609
— preparation of, 427; structure of, 462–465; reproduction of, 465–479; literature, 608; passage to PHANEROGAMIA, 609
Cryptoraphideæ, 527
Crystalline forms, list of, for microscope, 1019
Crystallisation, microscopic examination of, 1016, 1017
— effect of temperature on, 1017
— preservation of specimens of, 1020
Crystallites, 995
— in glass cavities, 997
Crystals, corroded, 995; in lava, 995; zonal markings in, 996; cavities in, 997; inclusions in, 997, 998; microscopical structure of, 990; optical properties and chemical constitution, 1002; as microscopic objects, 1016; of snow, 1016; as objects for polariscope, 1017
Ctenaria ctenophora, 801 *note*
Ctenoid scales, 951
Ctenophora, 801, 805, 806; excretory pores of, 806 *note*
Ctenostomata, characters of, 833
Cucurbitaceæ, pollen-grains of, 646
Cuff's micrometer, 140; microscope, 140
Culicidæ, antennæ of, 912; larvæ, blood of, 918
Curculio, antennæ of, 912
— *imperialis*, scales of, 899; elytra of, 905
Curculionidæ, 905; foot of, 924; suckers on foot of, 926
Currant, parenchyme of fruit, 613; pollen-tubes of, 648
Curvature of the field, 332
Curved scissors, for section cutting, 397
'Cushion-star, 815.' See *Goniaster*
Cuticle, 965, 966
— of leaves, 638; of *Ciliata*, 700
Cutin, 638
Cutis vera, 965
Cutleria, conjugation of, 556
Cuttle-fish, 853, 866. See *Sepia*
— 'sepiostaire' of, structure, 853; imitated, 1023
'Cuttle-fish bone,' structure of, 853
Cyanæa capillata, ephyræ of, 799; scyphistoma of, 799; strobila, 799
Cyanthus minor, seed of, 649
Cyatholiths, 672–674; artificially produced, 1022
Cycadeæ, 609
Cycas, raphides of, 621
Cyclammina cancellata, 741, 743
Cyclical mode of growth in shell of *Foraminifera*, 723
Cycloclypeus, 754; shell of, 723
— compared with *Orbitolites*, 726, 760
Cycloid scales, 952

Cyclops, eye of, 884; larva, 892
— *quadricornis*, 885; number of offspring of, 888
Cyclosis, 464; in *Chara*, 506; in desmids, 510; in *Diatomaceæ*, 517; in Phanerogam cells, 613; in plant hairs, 615; in *Lieberkuehnia*, 657; in *Acinetina*, 697
Cyclostomata (*Polyzoa*), characters of, 833
Cydippe, collecting, 459
— *pileus*, 805
Cymbella, 528
Cymbelleæ, affinities of, 545
Cynipidæ, ovipositor of, 927
Cypræa, shell of, 852
Cypris, 884
Cyst, of *Protomyxa*, 653; of gregarines, 675; of *Dallingeria*, 684; of *Polytoma*, 685; of *Clathrulina*, 667; of *Protococcus*, 480
Cystic *Entozoa*, relation to cestoids, 868
Cysticercus, relation to cestoids, 868
Cystids of *Hymenomycetes*, 576
Cystocarp of *Florideæ*, 561; of *Batrachospermum*, 504
Cystopus candidus, 568
Cythere, 884, 885
Cytherina, shells of, in chalk, 1009
Cytodes, contrasted with plastid, 652
Cytoplasm, 467

D

Dallinger and Drysdale's moist stage, 289; tripod, 345; on life-history of monads, 681–688; on effects of temperature on monads, 686
Dallinger (W. H.) on *Navicula*, &c., as test objects, 530 *note*; on nucleus of monads, 687
Dallinger's thermo-static stage, 292–293
Dallingeria Drysdali, life-history and structure of, 683; nucleus of, 687
Dalyell (J. G.) on *Hydra tuba*, 798
Damæus geniculatus, proventriculus of, 935
Dammar, as a preservative medium, 441; as a mounting medium, 444; refractive index of, 445
Dandelion, laticiferous tissue of, 620; pollen-grains of, 647
Daphnia, eye of, 884; mouth of, 888, 889; eggs of, 888; ephippial eggs of, 888
Daphnia pulex, 886
Darwin (Charles) on *Cirripedia*, 891
Datura, seeds of, 649
Davis on desiccation of *Rotifera*, 718 *note*
Dawson (W.) on foraminiferal nature of *Eozoön*, 763
'Day-fly.' See *Ephemera*
'Dead-man's toes,' 803. See *Alcyonium*
Deane's medium for mounting insects, 897

De Bary on fungi, &c., 563 *note*; on potato-disease, 569; on alternation of generations in ferns, 605
Decalcification, 425; of echinoderms, 426; of bones, 426; of teeth, 426; of *Foraminifera*, 426; of *Eozoön*, 426
Decapoda, 881; exoskeleton of, 891; macrourous, 893; brachyourous, 894
Decomposition, produced by *Bacteria*, 588
— of rock-masses, 999
Defining power, 368; tests for, 368
Definition of image, 326
Degeneration in *Tunicata*, 835
Dehydration by carbolic acid, 450
Delage's parallel compressor, 296, 297
Dellebarre's microscope, 142
Delphinium, seeds of, 649
Demodex, legs of, 934
— *folliculorum*, 938
De Monconys, his compound microscope, 130
Dendritina, a varietal form of *Peneroplis*, 728
Dendrodus, teeth of, 1013
Dendrosoma, 698
Dentine, 944, 947
— resemblance of cuticle of crabs to, 893; in placoid scales, 952
Deparia, indusium of, 600
— *prolifera*, 601
Depth of focus, 88, 89; of vision, 88, 89, 90; perception of, 94
Dermal skeleton of *Vertebrata*, 950
Dermaleichi, 932, 938
Dermanyssus, 936
— larva of, 933
Dermestes, hair of larva, 904
Descartes' simple microscope with reflection, 128
Desiccation of rotifers, 718
Desiderata in a microscope, 215
Desilicification, 427
Desmidiaceæ, 477, 509–516; connection with *Pediastreæ*, 496; sutural line of, 509; cellulose envelope, 509; mucilaginous sheath, 510; primordial utricle, 510; endochrome, 510; movements of, 510; cyclosis in, 510; binary division of, 511; sexual reproduction, 513; classification of, 515; habitat of, 515, 516; mode of collecting, 516
— Hantzsch's glycerin method of preserving, 444
Desmidieæ, 869
— conjugation of, 514; zygospore of, 514
— preserved by osmic acid, 428
Desmidium, binary division, 511; filaments of, 512, 515
Desmids. See *Desmidiaceæ*
Deutovium of *Acarina*, 932
Deutzia scabra, stellate hairs of, 639; epiderm of, 640
Development of *Hydra*, 791; of hydroids, 792; of embryo in *Gastropoda*, 843; of molluscs, 857, 864; of *Annelida*, 873; of *Tomopteris*, 878; of insects, 931

Deviation, 9
'Diamond Beetle,' 899
Dianthus, seed of, 648
— *caryophyllæus*, parenchyme of, 613
Diaphragm, 213, 255, 288, 321
— with two openings for double illumination, 106
— use of, 261
— Zeiss's iris, 246, 248; calotte, 247; in eye-pieces, 325; for use in testing object-glasses, 329
— in Tully's microscope, 147
Diatoma, 517; frustules of, 517, 518; girdle of, 518
— *vulgare*, chains of, 534
DIATOMACEÆ, 477, 509, 516–554
— Möller's type-slide, 286; perforated membrane of, examined with annular illumination, 362; mode of examination of, 363; preserved by osmic acid, 428; silicious coat, refractive index of, 445; mounting, 450; stipes of, 517, 518; beaded appearance, 521, 522; markings of, 522; binary division of, 523, 524; reproduction of, 523–527; classification of, 527, 532; placochromatic, 527; coccochromatic, 527; movements of, 528; conjugation of, 528; zygospores of, 528; gonids of, 529; habits of, 548, 549; habitats of, 549; distribution of, 549; fossil forms of, 550, 551; used as food, 551; collecting, 551; cleaning, 552, 553 *note*; mounting, 553; as food of *Ciliata*, 703; in mud of Levant, 1007
Diatom-frustules in ooze, 1008
Diatomin, 517
Diatoms in stomach of ascidians, *Holothuriæ*, &c., 544, 552
Diatoms. *See* DIATOMACEÆ
Dichroism, 1019
Dickiea, 528
Dicotyledonous stems, fossilised, 1005
DICOTYLEDONS, 625; stem of medullary rays of, 627; epiderm of, 637
Dictyocalyx pumiceus, 785
Dictyochya fibula, 550
Dictyocysta, silicious shell of, 700
Dictyoloma peruviana, winged seed, 649
Dictyospyris clathrus, 771
Dictyota, oöspheres of, 556
Didemnians, 888
Didymium serpula, plasmode of, 564
Differential screw, Campbell's fine adjustment, 164, 188–193
Differential staining, 439
Differentiation of cell, 468
Difflugia, 670; test of, 671
Diffraction, 62
— Abbe's theory of, and homogeneous immersion, 312
— Fraunhofer's law, 57
— rays are image-forming, 59
— spectra, 28, 67; phenomena, 62, 64; image, 64, 72; experiments, 66–70; fan of isolated corpuscles, 72; problem, 73; pencil, 74, 75; hypothesis of Abbe, 74; fan, 75; theory, application of, 76, 78; bands, 283; phenomena, Abbe's experiments, 376; ghost, 377
Digestive vesicles of *Ciliata*, 708
Digitalis, seeds of, 649
Dimorphism in *Foraminifera*, 727
Dinobryon, 690
Dinoflagellata, 695
Dinomastigophora, 695 *note*
Dioptric investigations by Gauss, 108–112
Dioptrical image, 30, 72
Diorite, fluid inclusions in, 997
Dipping tubes, 299
Diptera, 897; eyes of, 911; antennæ of, 912; mouth-parts of, 915; wings of, 922; ovipositor of, 927; imaginal discs of, 931
Direct division of nucleus, 468
'Directive vesicles' of egg of *Purpura*, 861
Disc-holder, Beck's, 288
Discida, 771
Discoliths, 672–674; artificially produced, 1022
Discorbina, 749
— *globularis*, 723
Disintegration of rock-masses, 999
Dispersion, 9, 17; in glass, 31
— and desiccation of encysted *Ciliata*, 709
Dispersive power, 2, 9, 18; of flint glass, 10
Dissecting apparatus, 394
— microscope, Beck's histological, 197, 198; Stephenson's binocular, 201, 203, 395; Huxley's, 204, 205; Zeiss's, 205, 206; Beck's binocular, 207
Distance of projection of image, 26, 27
Distinct vision, 26
Distoma, life-history of, 870
— *hepaticum*, 869
Divergence of light, 18
Divini's compound microscope, 131
Division, binary, of cells, 465; of desmids 511
— artificial, of *Actinosphærium*, 666 *note*
— of naiads, 880
Dobie's line, 973
Dog-fish, scales of, 252
D'Orbigny on plan of growth of *Foraminifera*, 724
Doris, spicules in mantle, 852, 853; nidamentum of, 858; eggs of, 866; spines of, imitated, 1022
— *bilamellata*, development of, 859–861
— *pilosa*, palate of, 855
— *tuberculata*, palate of, 855
Double illumination, Stephenson's method, 106
Doublet, Wollaston's, 36, 151
Dragmata, of sponges, 784
Dragon-flies, wings of, 922
Dragon-fly, facets in eyes of, 907
— See *Libellula*
Draparnaldia glomerata, 508
Draw-tube of microscope, 155
Drebbel's modification of Keplerian telescope, 123

DRE

Dredge, 458
Drepanidium ranarum, 677
Drone-fly. See *Eristalis*
Dropping-bottle, 446; German, 447; expansion, 447
Drosera, glands of, 689; seeds of, 649
Dry-mounting, Smith's 'cells' for, 885
Ducts of Phanerogams, 623
Dudresnaya, fertilisation in, 561; fertilising tubes, 561
Dujardin, on 'sarcodé,' 460 *note*
— separates *Amœba* from *Infusoria*, 658
Dunning's zoöphyte trough, 298
Duramen, 629
Dwarf-male of *Œdogonium*, 503
Dytiscus, eye of, 911; antennæ of, 912; spiracle of, 920; trachea of, 920; foot of, 925, 926

E

Earth-stresses, 1000
Earwig. See *Forficula*
Eccremocarpus scaber, winged seeds of, 648, 649
Echinoderm larvæ, collecting, 824; preparing, 824; mounting, 824
— skeletons in mud of Levant, 1007
ECHINODERMATA, larvæ of, collecting, 459
— 808–827; skeleton of, 808, 815, 816, 818; spines of, 809–813, 815; pedicellariæ of, 813; teeth in, 814, 816; preparation of skeleton, spines, &c., 816; internal skeleton, 818; larvæ of, 820
Echinoderms, decalcification of, 426
Echinoidea, skeleton of, 808; spines of, 809, 813; pedicellariæ of, 813; larva of, 822; direct development in, 824 *note*
Echinometra, spine of, 810, 816; colour of spines, 812
Echinus, shell of, 809, 810; spines of, 809; teeth of, 813
— *lividus*, coloured spines of, 811
Ectocarpaceæ, 555
Ectocarpus siliculosus, conjugation of, 556
Ectoderm, 651
Ectoplasm, 463
Ectoprocta, 833
Ectosarc, 464; in *Rhizopoda*, 658; experiments on 668; of *Ciliata*, 699
Edentata, cement in teeth of, 950
Edible crab, metamorphosis of, 894
Edmunds' immersion paraboloid, 269
Edwards (A. M.) on supposed 'swarm-spores' of *Amœba*, 669
Eel, scales of, 951
'Egg without shell,' concretionary spheroids in, 1021
Egg-capsule of *Cyclops*, 885
Egg-sacs of *Lernæa*, 890
Egg-shell membrane, 962
Eggs of *Sepiola*, *Doris*, 866; of *Acarina*, 928, 929; of insects, 928

ENT

Ehrenberg on eye-spot in *Protococcus*, 478; on *Volvox*, 479; on structure of frustules, 519; on rapidity of reproduction of *Paramecium*, 704; on internal casts of *Foraminifera*, 753 *note*; on fossil *Radiolaria*, 778 *note*
Elæagnus, raphides in pith of, 621; peltate scales of, 639
Elastic ligament of bivalves, structure of, 964
Elater, antennæ of, 912
Elaters of *Marchantia*, 593; of *Equisetaceæ*, 605
Elatine, seeds of, 649
Elder, pith of, 611
Ellis's aquatic microscope, 145
Elm, raphides of, 621
Elodea canadensis, cyclosis in, 613
Elytra of *Coleoptera*, 905, 923
Embryo of Phanerogams, 648
— cell of fern, development of, 604
Embryo-sac, 610
— of ovule in Phanerogams, 464; free-cell formation in, 466
— Strasburger's method for study of, 435
Emission of light, power of, 51, 54; unequal, 52
Emitted light, unequal intensity of, 51
Empusa muscæ, 571
Enamel of teeth, 949
— of teeth of *Echinus*, 815
— on ganoid scales, 952
Encephalartos, raphides of, 621
Encrinites, 816
End-bulbs, 977
Endochrome, 463; of *Palmoglœa*, 471; of *Spirogyra*, 478; of *Volvox*, 479, 482; of desmids, 510
Endoderm, 651
Endogenous spores of *Mucorini*, 569
— stems, 625–627
Endogens, spiral vessels of, 623
Endonema, 528
Endophlœum, 633
Endoplasm, 463
Endosarc, 463; in *Rhizopoda*, 658; of *Ciliata*, 699
Endosperm, 610
Endospores of mosses, 597; in ferns, 602; of *Volvox*, 484; of *Hymenomycetes*, 576
Endosporous *Bacteria*, 582
Enock's metallic ring for mounting, 451
Entomophilous flowers, 647
Entomophthoreæ, 571
Entomostraca, 881, 883, 885; desiccation of, 887; agamic reproduction of, 887; eggs of, 888; development of, 889; eye of, 906; non-sexual reproduction, 930
— collecting, 459
— *Rotifera* upon, 713
Entomostracan eggs as food of *Ciliata*, 703
Entoprocta, 833
Entosphærida, 776
Entozoa, 867

EOL

Eolis, nidamentum of, 858
Eosin, red stain, 436
Eozoön, mounting, 450; mode of growth of, compared with that of *Polytrema*, 749; canal system compared with *Calcarina*, 750; affinities of, 763; intermediate skeleton, 764; nummuline layer, 764; internal cast of, 765; asbestiform layer, 766; pseudopodia of, 766; young of, 767
— *canadense*, 762
— decalcification, 426
Epeïra, foot of, 939; silk threads of, 939
Ephemera, branchiæ of larva, 921
— *marginata*, larva of, 897; circulation of blood in larva of, 917
Ephippial eggs of *Rotifera*, 717
Ephyræ of *Cyanæa*, 799; of *Chrysaora*, 800
Epiblast, 651 *note*
Epiderm of leaves, 637
Epidermic appendages, 958
Epidermis, 965, 966; method of preparation, 967
Epidote, 1001
Epilobium, emission of pollen-tubes, 647
Epilucent zones of light, 815
Epipactis, pollen-tubes of, 648
Epiphlœum, 633
Epispore of *Mucorini*, 570
Epistome of *Polyzoa*, 833; of *Actinotrocha*, 874
Epistylis, collecting, 457
Epithelia, preservative for, 443
Epithelium, 967, 968
Epithemia, conjugation of 529; zygospores of, 529
— *turgida*, 533
Equiconcave lens, 22
Equisetaceæ, 605; in coal, 1006
Equisetum, spores and elaters of, 606; epiderm of, 639; silex in, 639
Equitant leaves of *Iris*, &c., 642
Erecting binocular, Stephenson's, 102
— prism, Stephenson's, 102
Ergot, 572
Erica, seeds of, 649
Eristalis, eye of, 911; antennæ of, 912
Error of centring, 332
Errors in Tolles' mechanical stage, 166
Erythropsis agilis, eye-spot of, 702
Eschara, calcareous polyzoaries of, 833; extension of perivisceral cavity, 851
Ether as a solvent, 441
Ether-spray microtome, 418; Rutherford on, 419
Ethmosphæra siphonophora, 774, 776
Eucalyptra vulgaris, 594
Eucopepoda, 889 *note*
Eucyrtidium elegans, 771–776
— *Mongolfieri*, 771
— *tubulus*, 771
Eudorina, sexual process of, 485
Euglena, 475, 690
Euglypha alveolata, reproduction of, 671

FAR

Euler's microscope, 146
Euler on achromatic microscopes, 145
Eunotia, 533
Eunotieæ, characters of 553
Euphorbiaceæ, laticiferous tissue of, 620
Euphrasia, micropyle of, 648
Euplectella aspergillum, 785 *note*
Eupodisceæ, characters of, 541
Eurotium repens, 572
Evening primrose, emission of pollen-tubes, 647
'Exclamation markings' on scales, 902
Excretory organ of *Rotifera*, 716; of *Oribatidæ*, 935
Exner (S.) on the image in eye of *Lampyris*, 908
Exogenous stems, 625
— stem, structure of, 633
— and endogenous stems contrasted, 634, 635
Exogens, fibro-vascular bundles, 622, 623; medullary sheath of, 623; spiral vessels in, 623
Exoskeleton of decapods, 892
Exospores of mosses, 597; of ferns, 602; of *Hymenomycetes*, 576
Extine of pollen-grains, 644; markings on, 645
Eye, accommodation of, 88
— of *Pecten*, 865; of *Onchidium*, 865; of slug, 865; of snail, 865; of arthropod, structure of, 907
Eye-glass of compound microscope, 86, 39
Eye-lens, 321
Eye-piece, Abbe's compensation, 42, 322; Huyghenian, 42; Kellner's, 42, 322; Ramsden's, 42, 323; Airy's, 321; Campani's, 321; Huyghens', 321
— binocular, Tolles', 102; Abbe's, 103
— Kellner's, as condenser, 177
— adapter, 228; multiplying power of, 240; orthoscopic, 322; projecting, 323; micrometer, 323; field of, 323; pointer in, 325; diaphragms in, 325; index, 325
— stereoscopic, Abbe's, 103
Eye-pieces, classification of, by Abbe, 84; compensating, 84; positive, 321; negative, 321–323; solid, 322; field of, 323; working, 323; searcher, 323
Eyes on *Chiton* shells, 865
— compound, of insects, 906, 907
— compound, 906–911; simple, 906, 910; preparing, 910; mounting, 910

F

Faber, inventor of the name microscope, 126, 127
Falciform young of *Coccidia*, 677
False images, 362
Farrant's medium, 443, 449; for mounting insects, 897
Farre (A.) on structure of *Polyzoa*, 832 *note*

Farrella, polyzoaries of, 833
Fat, 969
Fat-cells, 942, 964, 966, 969; capillary network around, 986
Fats, solvents for, 441
Feathers, 953–956
'Feather-star,' 824. See *Antedon*
Feeding, mode of, in *Actinophrys*, 662; in sponges, 780
Feet of insects, 924–926; of spiders, 938
Felspar, decomposition of, 999
Felspar-pyroxene rock, effect of dynamic metamorphism on, 1000
Felspars, zonal structure in, 996
'Female' plants of *Polytrichum*, 596
Fermentation of alcohol by yeast, 574; by *Penicillium*, *Mucor*, &c., 575
— putrefactive, 588
Fermentative action of *Fungi*, 462
Ferns (see *Filices*), 599; in coal, 1005
Fertilisation of Phanerogams, 647
Fertilisation-tube of *Peronosporeæ*, 567
Fertilising tubes of *Dudresnaya*, 561
Festuca pratensis, palea of, 640
Fibres and cells of Vertebrates, 942
Fibro-cartilage, 948, 970
Fibro-vascular bundles, 635
— of ferns, 599; in the 'veins' of leaves, 622; of Exogens, 622, 623; of Phanerogams, 625
Fibrous tissues of Vertebrates, 948
— tissue, 962; white, 963, 964; yellow, 964
Field of eye-pieces, 328
Field-glass, 40
Field-lens, 321; applied to eye-lens by Hooke, 321
FILICES, 599–605; stem, structure of, 599; fructification of, 600; prothallium of, 602; antherids of, 603; archegones of, 603; development of, 604; aposporv in, 605; apogamy in, 605; alternation of generations in, 605
'Filiferous capsules.' *See* Thread-cells
Finder, 166; Maltwood's, 246; Pantoscsek's, 246
Fine adjustment, 157–164
— — continental, 151; Ross's, 151; Oberhauser's spiral, 151; applied to the stage by Powell, 153; by moving the whole body, 158; by simply moving the nose-piece, 158, 161; for Powell and Lealand's sub-stage, 174; of Ross model, 177; Wale's, 185; in Beck's students' microscope, 190
Fire-fly, antennæ of, 911
'Fire-fly,' 879. See *Lampyris*
Fish, circulation in tail of, 981; on yolk-sac, 981
'Fish-louse,' 890
Fish-scales, concretions in, 1021
Fishes, lacunæ in bone of, 946; dentine of, 947; cement of teeth in, 950; plates in skin of, 950; red blood-corpuscles of, 958, 959; pigment-cells of, 967; muscle fibre of, 973; gills of, 986, 987
Fission in *Lieberkuehnia*, 658; of *Monas*, 681; of *Monosiga*, 689; of *Codosiga*, 689; of planarians, 871
Fissipennes, wings of, 923
Flabella of *Licmophora*, 534
Flagella, 462; of *Bacteria*, 581, 586, 587
Flagellata, 680–696
— experiments on, 686; nucleus in, 687; karyokinesis in, 688; colonial forms, 689
— collared, resembling cells of sponges, 779
Flagellate chambers of sponges, 780, 781
Flagellum of *Noctiluca*, 691 *note*
Flat bottle for collecting, 457
Flatness of field, 368
Flea, presumed auditory organ of, 364; hairs on pygidium of, as a test, 364; mounting medium for, 397
'Flesh,' 972
Flint, derivation of, 550
— glass, refractive index of, 5; dispersive power of, 10; composition of, 23
— implements found with *Orbitolina* 749
Flints, preparation of, 1011
Floral envelope, 643
Florideæ, 559, 560–561; affinities of, 559
Flosculariadæ, 717
Flosculos in confinement, 458
'Flowering fern,' sporanges of, 601
'Flowering plants,' 609. *See* PHANEROGAMIA
Flowers, 643–648; Inman's method of preparation, 644
'Flowers of tan,' 563
Fluid inclusions in crystals, 997
'Fluke,' 869
Fluorite lenses for apochromatic objective, 34, 35
Fluorspar, 1000
Flustra, mode of growth in, 828; gemmation in, 830; number of polypides, 832; polyzoaries of, 833; extensions of perivisceral cavity in, 851
Flustrella concentrica, 771
Fly, various instructive organs to be obtained from, 896; eye of, facets in, 907; proboscis of, 913; wing of, 918; spiracle of, 920; areolæ on wings of, 922; foot of, 924
Focal alteration and form of objects, 363
— depth, 38
— distances, by feeling, 167
— length of a plano-convex lens, 15
Focke on *Navicula* and *Surirella*, 532 *note*
Focus, virtual conjugate, 14, 25; principal, 16; mean, 17; virtual, 22; conjugate, 24; depth of, 88, 89
— of lenses, 13, 21, 22; chromatic, 16
Focussing arrangements, 156–165
Fontinalis antipyretica, 596
Food of *Hydra*, 789
Foraminifera, 658, 720–770
— study of, by means of Beck's disc-holder, 288; examination of, 365; wooden slides for mounting, 390; method for

sectionising, 421 *note*; decalcification of, 426; structure of, 720; chamberlets in, 723, 728, 729, 730; cyclical mode of growth in, 723; porcellanous shells, 724; vitreous shells, 724; tubulation of shell in, 724, 725; plans of growth, 724, 729; rotaline type, 725; nummuline type, 725; *Porcellanea*, 726; intermediate skeleton of, 726; canal system of, 726; fossilised forms of, 726, 729, 787, 749, 762; dimorphism in, 727; secondary septa in, 728; *Arenacea*, 735; sandy isomorphs, 739; nodosarine type, 740; *Vitrea*, 744; internal casts, 748, 752 *note*; nummuline series, 751; alar prolongations, 755, 756; interseptal canals, 755; marginal cord in, 755, 759; collecting, 769; method of separating from sand, &c., 769; mounting, 770; tubuli of, compared with those of dentine, 944; in mud of Levant, 1007; in rocks, 1007; internal casts of, 1012
Forbes, on reproduction of *Sertularida*, 794
Forceps, 301
— slide, 393
— stage, 287
Forficula, antennæ of, 912
Forficulidæ, wings of, 923
Form of objects and focal alteration, 363
Formation of microscopic images, 43
'Formed material,' 942; of fibrous tissue, 943; of dentine, 944
Fossil coniferous wood, 630, 1005
— crinoids, 816; echinids, 816
— *Cypridæ*, 884
— *Foraminifera*, 726, 749–750
— *Lituolæ*, 741
— *Radiolaria*, 771, 778 *note*
— *Saccammina*, 737
— wood, 631
Fossilised *Foraminifera* (*Eozoön*), 762
— wood, sections of, 637
Fragilaria, 534
Fragilarieæ, characters of, 534
Fragmentation of nucleus, 468
Fraunhofer's law of diffraction, 57
— achromatic doublet, 146
— lines, 273, 274
Fredericella, collecting, 458
Free-cell formation, 465, 644
— — in embryo-sac, 464, 466
Freezing apparatus for Thoma's (Jung's) microtome, 405, 406
— microtome, Hayes's, 411; Cathcart's, 412, 413
— imbedding by, 418
Fresnel on Selligue and Adams's microscope, 146; on range of magnification, 147
Freyana heteropus, legs of, 934
Fripp's method of testing object-glasses, 330
Frog, blood-corpuscles of, 958, 959; muscle fibre of, 973; papillæ on tongue of, 977; circulation in mesentery of, 980; circulation in tongue of, 980; lung of, 987
Frog's bladder, histology of, as seen with apochromatic, 316
— foot, epithelium of web of, 968; circulation in web of, 979
Frond of *Phæosporeæ*, 555
Fructification, gonidial, 470; sexual, 470
— of thallophytes, 470; of *Ascomycetes*, 571; of lichens, 578; of mosses, 595; of ferns, 600; of *Equisetaceæ*, 605
Fruit juice as a preservative medium, 442
Frustules of *Diatomaceæ*, 517, 518; structure of, 518, 519 *note*; girdle, 518; shapes of, 518, 519; ostioles in, 519; markings on, 520; character of, as basis of classification, 532; of *Coscinodiscus*, 538
Fucaceæ, 556; conceptacles of, 556
Fuchsia, pollen-grains of, 647
Fucus, 555
Fucus platycarpus, 556–558
— *vesiculosus*, 556–558
Fulgoridæ, wings of, 923
Funaria hygrometrica, 594
— sporange of, 596
FUNGI, 470, 562–589
— preparation of, 427; zymotic action of, 462; alternation of generations in classification of, 568; parasitic on insects, 571
Fungia, lamellæ of, 802
Fungiform papillæ, 977
Fungin, 562
Fungus-cellulose, 562
Fusion in *Dallingeria*, 684
Fuss's description of a microscope, 145
Fusulina, 750, 751, 1012
Fusulina-limestone, 750, 1007

G

Gabbro, 1016
— fluid inclusions in, 997
Gad-fly, ovipositor of, 927
— See *Tabanus*
Gaillonella procera, 551
— *granulata*, 551
— *biseriata*, 551
Galileo, inventor of the compound microscope, 122–127; Viviani's life of, 122; his invention of compound microscope, Wodderborn on, 123; his *occhialino* 123, 126; his *occhiale*, 124, 125; his microscope, 129
'Gall-flies,' ovipositor of, 927
Galley-worms. See *Myriopoda*
Gamasidæ, legs of, 934; integument of, 934; Malpighian vessel of, 935; heart of, 935; tracheæ of, 935; characters of, 936; reproductive organs of, 936
Gamasus terribilis, mandibles of, 933
Ganglion-globules (cells), 975
Ganglionic cells, 978

GAN

Ganoid scales, 952
Garlic, raphides of, 621
Garnets, 1000
Gas bubbles in glass cavities, 997
Gaseous inclusions in crystals, 998
Gastræa, Haeckel on, 677
Gastropoda, palates of, mounting, 450; palate of, 843; development of, 843; shell structure of, 852; embryonic development of, 858–864; organs of hearing in, 865
Gastrula, 651; -stage in *Cœlenterata*, 651; formation of, 651 *note*; of zoöphytes, 786; of *Gastropoda*, 859; of blowfly, 931
Gastrulæ of sponges, 781
Gauss's optical investigations, 108–112; his dioptric investigations, 108–112; his system, practical example of, 112–118
Gelatinous nerve-fibres, 976
— — in sympathetic, 978
Gemellaria, polyzoary of, 833
Gemmæ of *Marchantia*, 591, 592; of *Salpingœca*, 689; of *Suctoria*, 698; in *Foraminifera*, 723; of *Polyzoa*, 830
Gemmation and shape of shell in *Foraminifera*, 721
Gemmules of *Noctiluca*, 694; of sponges, 781
Gentiana, seeds of, 649
Geodia, spicules of, 784, 1008
Gephyrean worm, 875
Geranium, glandular hairs of, 639; cells of pollen-chambers, 645; pollen-grains, 646
Germ-cells of *Volvox*, 483, 484; of ferns, 604; of *Marchantia*, 593; of mosses, 596; of Phanerogams, 609; of sponges, 781; of *Hydra*, 790
'Germinal matter,' 942; of fibrous tissue, 943; of dentine, 944
Gesneria, seeds of, 649
Ghostly diffraction image, Nelson on, 72 *note*
Gibbes (Heneage) on multiple staining, 438; on staining *Bacteria*, 438
Gill (C. Haughton) on the 'dots' of *Navicula*, 522
Gillett's condenser, 184, 250
Gills of tadpole, 981, 983
Giraudia, conjugation of, 556
'Gizzard' of insects, 917
Glanders, 588
Glands, structure of, 971
— of *Drosera*, 639
Glass-cavities in crystals, 997; gas bubbles in, 997
'Glass-crabs,' 892
Glass inclusions in crystals, 997
— rings for cells, 386, 387
Glaucium luteum, cyclosis in, 616
Glenodinium cinctum, conjugation of, 695
Globigerina, shell of, 723; mud, 736; mode of life of, 746; Wyville Thomson's views on, 746; Carpenter's views on, 747; pseudopodia of, 746

GRA

Globigerina bulloides, 745; in the 'ooze', 1007
— *conglobata*, 746
— ooze, 748, 1007; resemblance to chalk, 1009
— *rubra*, colour of, 724
Globigerine shell, sandy isomorph of, 739
Globigerinida, 745
Globule of *Chara*, 507, 508
Glochidia of *Anodon*, 857
Glœocapsa, 477; as gonid of lichen, 579
Glow-worm, 879; antennæ of, 911
Glue and honey cement, 884
Gluten of grass seeds, 650
Glycerin, as preservative medium, 441; Hantzsch's method, 444; as a preservative medium, Beale's method, 444
— -jelly, Lawrence's mounting in, 443, 449; solvent for $CaCO_3$, 444; for mounting insects, 497; for mounting cartilage, 971
G'yciphagus Krameri, 937
— *palmifer*, 932
— *platygaster*, 937
— *plumiger*, 932; hairs of, 934
Gnathostomata (Crustacean), 889 *note*
Goadby's solution for mounting cartilage, 971
Goes (Dr.) on affinity of *Carpenteria*, 748
Goette on development of *Antedon*, 887
Gold size, 383
Gomphonema, stipe of, 518, 544; movements of, 531; attacked by *Vampyrella*, 655
— *geminatum*, 545, 546; stipe of, 545
— *gracile*, 551
Gomphonemeæ, characters of, 545
Goniaster equestris, spines of, 815
Gonidial cells, 470
— fructification, 470
— layer of lichens, 577
Gonidiophores of *Peronosporeæ*, 568
Gonids, or non-sexual spores of Cryptogams, 470 *note*; of *Vaucheria*, 493; of *Podosphenia*, 526; of *Florideæ*, 561; of *Fungi*, 562; of *Peronosporeæ*, 568
Goniocidaris florigera, spine of, 813
Gonium, 475
Gonothecæ of *Campanulariida*, 794
Gonozoid of hydroids, 792; of *Syncoryne*, 793; of *Tubularia*, 793
Gonozoids of *Sertulariida*, 794
Gordius, 868, 869
Gorgonia, spicules in, 853
— *guttata*, spicules of, 804
Gorgoniæ, 801; spicules of, in mud of Levant, 1007
Goring (Dr.) on magnification of objects, 44
'Gory dew,' due to *Palmella cruenta*, 486
Govi on invention of microscope by Galileo, 122
Graduated rotary stage, 338
Grammatophora, chains of, 517, 534
— *angulosa*, 550
— *marina*, 537

Grammatophora parallela, 550
— *serpentina*, 536
— *subtilissima*, 537
Granite, 1016
— fluid inclusions in, 997
Grantia, 781, 785; spicule of, 1008
Grasses, nodes of, 626; silex in epiderm of, 629; paleæ of, 640; seed of, 649
Grasshopper, gizzard of, 917; wings of, 923
Greensands, microscopic constituents of, 1012
Gregarina, characters of, 674; movement of, 675
— *gigantea*, in lobster, 674 *note*
— *Sænuridis*, 676
Gregarinida, 674
Gregory (J. W.) on *Eozoön*, 768 *note*
Gregory (W.) on species of diatoms, 580 *note*
Greville on *Spatangidium*, 539; on *Triceratium*, 543 *note*
Grey matter, 976
Griffith's turn-table, 891
Griffithsia, 559
Grinding sections of hard substances, 420
Grindl's microscope, 134
Gromia, 659, 660, 721
— and *Arcella*, pseudopodia of, contrasted, 671
Ground-mass of rocks, 995
Groundsel, pollen-grains of, 647
Growing slides, Botterill's, 289; Maddox's, 289, 290; Lewis's, 289
Guard-cells, 640
'Gulf-weed,' 559
Gum and glycerin, 448; and syrup, as a preservative medium, 443
— imbedding for vegetable substances, 427
— arabic, formula, 885; for freezing, 418
— resins, latex of, 620
— styrax, as a mounting medium, 444; index of refraction, 445
Gyges, 475
Gymnochroa, 792
Gymnolæmata, 833
Gymnosperms, fossilised, 1005
— generative apparatus in, compared with Cryptogams, 609
Gypsina, 749

H

Haddon on budding in *Polyzoa*, 831 *note*
Haeckel (E.) on *Monera*, 677 *note*
— on the *Gastræa* theory, 677 *note*
— on *Radiolaria*, 772; on nature of sponges, 789; on Hydrozoön affinity of *Ctenophora*, 801 *note*
— and Hertwig on classification of radiolarians, 773 *note*
Hæmatococcus, red phase of *Protococcus*, 473
— *sanguineus*, 486
Hæmatoxylin, alcoholic solution, 433; aqueous solution, 432; Weigert's, 433; Hill's method, 433
Hæmionitis, sori of, 600
Haime (Jules) on development of *Trichoda*, 707
'Hair-moss,' 596
'Hair-worm,' 868
Hairs of leaves, 639; of insects, 904; of *Acarina*, 934; of mammals, 958
Halicaridæ, 937
Haliomma Humboldtii, 776
— *hystrix*, 772
Haliotis (diatom), 542
— (mollusc), shell structure of, 852; palate of, 855
Haliphysema, 789; sponge-spicules in, 747
Haller on auditory organs of *Acarina*, 934
Halteres of *Diptera*, 924
Hand-magnifier, Brewster's, 87
Hansgirg on movement of *Oscillariaceæ*, 490
Hantzsch's glycerin method for desmids, 444
Haplophragmium, 739
— *globigeriniforme*, 738
Hardening agents, 427, 428
absolute alcohol, 428; chromic acid, 428; osmic acid, 428; picric acid, 428
Hardy's flat bottle for collecting, 457
Harpalus, antennæ of, 912
Harting on Janssen's microscope, 122; his experiments on formation of concretions, 1022
Hartnack on immersion system, 27
Hartnack's model, 210; his stage, 211
Hartsoeker's simple microscope, 135; his condenser, 248
'Hart's-tongue,' 600. See *Scolopendrium*
'Harvest-bug,' 937
'Haus' of *Appendicularia*. 842
Haustellate mouth, 916
Haustellium, 916
Haversian canals in bone, 946, 947
Haycraft (J. B.) on structure of striated muscle fibre, 978
Hayes's ether freezing microtome, 411; minimum thickness of sections therewith, 412
Hazel, peculiar stem of, 628; pollen-grains of, 647
Hearing, organs of, in *Gastropoda*, 865; in *Cephalopoda*, 865
Heart of ascidians, 836; of *Acarina*, 935
Heartsease, pollen-tubes of, 648
'Heart-wood,' 629
Heating-bath, Mayer's, 393
Heliopelta, 518, 540
Heliozoa, characters of, 659; examples of, 662–667; pseudopodia of, 770
Helix pomatia, teeth of, 854
— *hortensis*, palate of, 854
Heller's porcelain cement, 445
Helmholtz on aperture, 47
Hematite in carnallite, 998

HEM

Hemiaster cavernosus, development of, 824 *note*
Hemiptera, eyes of, 911; wings of, 923; suctorial mouth of, 928
Hensen's stripe, 973
Hepaticæ, 590; thalloid, 593; foliose, 593; elaters of, compared with spiral cells, &c., of pollen-chamber, 645
Herbivora, arrangement of enamel in teeth of, 949; cement in teeth of, 950
Herring, scales of, 982
Herschellian doublet, 257
Hertel's compound microscope, 137, 138
Hertwig's research on *Microgromia*, 660 *note*; on *Actinia*, 801 *note*
Heterocentrotus, spine of, 809
— *mammillatus*, spine of, 811
Heterocysts of *Nostoc*, 491
Heteromita uncinata, life-history of, 685
Heterostegina, 759
Heurck (Van) on markings of diatoms, 522
Hexarthra, 718
Hicks on amœbiform phase of *Volvox*, 485; on preparation of insect antennæ, 913 *note*; on structure of halteres and elytra, 924
Hill's (A.) method of using Weigert's hæmatoxylin, 433
Himantidium, 533
Hipparchia janira, eggs of, 929
Hippopus, 542
Hippothoa, 833
Holland's triplet, 37
Hollis's liquid glue, 384
Hollyhock, pollen-grains of, 646, 647
Holothuria botellus, plates of, 819
— *edulis*, plates of, 819
— *inhabilis*, plates of, 819
— *vagabunda*, plates of, 819
Holothuriæ, diatoms in stomach of, 544, 552
Holothurioidea, skeleton of, 818; pharyngeal skeleton of, 819 *note*; plates in skin of, 819; preparation of calcareous plates, 820; direct development in, 824 *note*
Holtenia Carpenteri, 785
Homeocladia, 528
Homogeneous immersion, 312, 313; Abbe's combination, 313
— immersion lenses of Powell and Lealand, 29; of Zeiss, 29
— objectives, value of, in study of monads, 687
— system, 28
Homoptera, wings of, 922, 923
Hood of mosses, 596
Hoofs, 953, 957
— sections of, mounting, 450; for polariscope, 450
Hooke's application of field-lens to eye-lens, 321
— compound microscope, 130
Hooked monad, 685
Hooker (J. D.) on diatoms of Antarctic Circle, 549

HYD

Hooklets on wings of *Hymenoptera*, 923
Hoplophora, 936
— maxillæ of, 934
Hormogones of *Oscillariaceæ*, 490; of *Rivulariaceæ*, 490; of *Scytonemaceæ*, 490; of *Nostoc*, 491
Hormosina globulifera, 738, 740
— *Carpenteri*, 740
Hornblende, 1001
— corroded crystals of, 995; pleochroism in, 1002
Hornet, wing of, 923; sting of, 927
Horns, 953, 957
Horny substances, chemical treatment of, 440
'Horse-tails,' 605. See *Equisetaceæ*
Hosts of parasitic plants, 462
House-fly. See Musca
Hudson on the functions of contractile vesicle of rotifers, 716 *note*
Hudson and Gosse on classification of rotifers, 717
Human blood-corpuscles, 958
— hair, 954
Husk of corn-grains, 644
Huxley on the ectosarc of *Amœba*, 668 *note*; on coccoliths, 672; on *Bathybius*, 672; on *Collozoa*, 778 *note*; on structure of molluscan shells, 846; on pulvillus of cockroach, 924 *note*; on agamic reproduction of *Aphis*, 930
Huxley's simple dissecting microscope, 204, 205
Huyghenian eye-piece and spherical aberration, 42
— Airy's modification of, 321
Hyacinth, raphides of, 621; cells of pollen-chambers, 645; pollen-grains of, 647
Hyaline shells of *Foraminifera*, 724
Hyalinia cellaria, palate of, 855
Hyalodiscus subtilis, 537
Hyaloplasm, 468
Hydra, collecting, 457; cells of, 786; intracellular digestion in, 787; structure of, 788; reproduction of, 790; gemmation of, 930
— *fusca*, 787, 789
— *viridis*, 787
— *vulgaris*, 787
'Hydra tuba' of *Chrysaora*, 798, 800
Hydrachnidæ, 932; eyes of, 935; mandible of, 933; reproductive organs of, 936; characters of, 937
Hydrangea, number of stomates in, 641; seeds of, 649
Hydrodictyon, 486, 495
— *utriculatum*, 495
Hydroida, classification of, 792
Hydroids, compound, 791; habitats of, 795; *Medusæ* of, 792; planulæ of, 792, 795; structure of, 791 *et seq.*; examination of, 795; mounting, 795; polariscope with, 796; preparation of, 796
Hydrophilus, antennæ of, 911, 912
Hydrozoa, 787–801

HYD

Hydrozoa and marine mites, 937
Hyla, nerves of, 978
Hymene of *Ascomycetes*, 571; of *Basidiomycetes*, 576; of *Hymenomycetes*, 576
Hymenomycetes, 576; pileus of, 576; stipe of, 576
Hymenoptera, 897; eyes of, 911; mouth-parts of, 915; wings of, 922; sting of, 926, 927; ovipositor of, 926, 927
Hyoscyamus, spiral cells of pollen-chambers of, 645; seeds of, 649
Hypericum, seeds of, 649
Hyphæ of *fungi*, 562
Hypnospore of *Hydrodictyon*, 495
Hypnospores, meaning of, 470 *note*
Hypoblast, 651 *note*
Hypopial stage of *Tyroglyphidæ*, 937
Hypopus, 937

I

'Ice-plant,' epiderm of, 639
Ichneumonidæ, ovipositor of, 927
Illuminating power, 367
— power of objectives, 54; compared with penetrating power, 336
Illumination for dissection, 344
— for opaque objects, 147
— oblique, 170, 171, 331; in Zentmayer's microscope, 184
— of objects, Ross on, 250; by reflexion, 278; opaque, 281; from the open sky, 355; by diffused daylight, 355; for dark ground, 356; experiments in, 357; monochromatic, means of obtaining, 360, 361; annular, 362; double, objects for study with, 366; with small cones, as cause of errors in interpretation, 369
Illuminator, Stephenson's catadioptric, 170, 263–265; oblique, 170; white cloud, 172; Wenham's reflex, 265, 266; parabolic, 267–269; Swift's substage, 271; Powell and Lealand's, 283; Smith's vertical, 284, 285; Beck's, 285; Tolles' vertical, 285
Image, real, 14 *note*; virtual, 14 *note*, 321; conjugate, 24; inverted conjugate, 24; aborption or dioptrical, 64; diffraction, 64; negative, 64; positive, 64; solid, 95; real object, 321; definition of, 326; formed by compound eye, 908, 909
Images, by diffraction, dioptric and interference, 72
Imaginal discs in larva of blowfly, 931
Imbedding processes, 414; simple, 414; in wax, 415; in paraffin, 415; metal case for, 415
— masses, 416; paraffin, 417; wax, 417; celloidin, 417
— by coagulation or freezing, 418
Immersion lenses and vertical illuminators, 285, 286
— — homogeneous, outcome of Abbe's theory of diffraction, 312, 313
— — water, Zeiss's, 317

INT

Immersion lenses, water, Amici's, 310; Powell and Lealand's, 310, 313; Prazmowski and Hartnack's, 310; Tolles', 310
— objectives, 28; examination of, 331
— system, 27–29; invented by Amici, 27
Imperfect achromatism, cause of yellowness, 360
'Impressionable organs' in *Ciliata*, 702
Incidence, angle of, 3
Incident ray, 2
Incus of *Rotifera*, 715
Index eye-piece, 325
— of visibility, 445
Indian corn, epiderm of, 637; stomates of, 640
Indigo carmine, 437
Indirect division of nucleus, 468
Indusium in ferns, 600
Inflection of diverging rays, 62
Infusoria, preserved by osmic acid, 428; as food of *Actinophrys*, 663; Ehrenberg's work on, 678; ciliate, 679; character of, 679; unicellular nature of, 680 *note*
Infusorial earth, 536, 538, 540, 542, 546, 550, 552, 771; from Barbadoes, 771, 774
Injected preparations, 984
Inoceramus, portions of shell of, in chalk, 1009
Insects, 896–931
— parts of, wooden slides for mounting, 390
— parasitic fungi in, 573–574
— mounting media for, 897; integument of, 898; tegumentary appendages of, 898; scales of, 899–904; hairs of, 904; parts of head, 906; eyes, 906–911; antennæ of, 911; mouth-parts of, 913; circulation of blood, 917; alimentary canal, 917; wings of, 918, 922–924; tracheæ of, 918; stigmata of, 919; sound-producing apparatus, 928; organ of smell, 924; organ of taste, 924; feet of, 924–926; stings of, 926, 927; ovipositors of, 926, 927; eggs of, 928; agamic reproduction of, 930; embryonic development of, 931; 'liver' of, 971
Insect work, polarised light for, 366
Integument of insects, 898; of *Acarina*, 934
Integuments of ovule, 610
Intensity of light, necessaries for, 359
Intercellular substance, 943; in cartilage, 970
Intercostal points, Stephenson on, 78; not revelation of real structure, 78
Interference, 62
— image, 72
Intermediate skeleton in *Foraminifera*, 726; of *Globigerinida*, 745; of *Calcarina*, 750; of *Rotalia*, 750; of *Nummulites*, 751; of *Eozoön*, 764
Internal casts of *Rotalia*, 748; of *Textularia*, 748; of *Eozoön*, 765; of wood, 1005; of shells in greensand, 1012

INT

Interpretation, errors of, 368
'Interseptal canals' of *Calcarina*, 755
Intestine, cells of villi in, 968
Intine of pollen-grains, 640
Intracellular digestion in zoöphytes, 787
Intussusception, 468
— mode of growth of starch, 620
Invagination, 651
Invertebrata, blood-corpuscles of, 962
Inverted conjugate image, 24
— microscope for chemical purposes (Nachet's), 216
Iodin, as a test for starch, &c., 440
Ipomœa purpurea, pollen-grains of, 646
Iridescent scales of insects, 899
Iris, epiderm of, 637; leaves of, 642; cells of pollen-chambers, 645
Iris-diaphragm, 229, 252, 258, 260; fitted to Abbe's condenser, 259
Iris germanica, epiderm and stomates of, 640, 641
Irrationality of spectrum, 19, 314
Isochelæ of sponges, 784
Isoeteæ, 607
Isthmia, chains and frustules of, 517, 542; structure of frustules, 519 *note*; division of, 525
— *nervosa*, 542
— areolations in, 521
Italian reed, stem of, 624
'Itch-mites,' 937
Ivory, 948
Ixodes, heart of, 935
Ixodidæ, 932; integument of, 934; auditory organ, 935; tracheæ of, 935; characters of, 936

J

Jackson's modification of Ross model, 78; his limb, 181, 215; his model, 190; his eye-piece micrometer, 232
Janczewski on antherozoids of *Sphacelaria*, 555
Janssen on invention of lens, 122; his compound microscope, 122
Jars, capped, for Canada balsam, 447
Jelly-fish. See *Acalephæ* and *Medusæ*
Jones's compound microscope, 143, 146
Jungermannia, 593
Jung's (Thoma's) microtome, 401

K

Kaolin, 999
Karop and Nelson on fine structure of diatoms, 521 *note*
Karyokinesis in monads, 688
Kellner's eye-piece, 42, 322; as a condenser, 177
Kent (Saville) on contractile vacuoles of *Volvox*, 481 *note*; on *Flagellata*, 689
Keplerian telescope, Drebbel's modification as a microscope, 123
Keramosphæra Murrayi, 785 *note*

LAR

Keratose network of sponges, preparation of, 779, 781
Kidneys of *Vertebrata*, 971
King-crab, 881
Kirchner on the oöspores of *Volvox*, 484
Klebs on mucilaginous sheath of desmids, 510; on movement of desmids, 510
— and Bütschli on the 'cilia' of *Dinoflagellata*, 695
Klein on *Volvox*, 484 *note*
Knife, two-bladed, Valentin's, 396; special, for microtome, 399
Koch's method of sectionising corals, 802
Kowalevsky on development of ascidians, 841 *note*
Krukenberg on digestion in sea-anemones, 787
Kützing on *Palmodictyon*, 487; on structure of frustules of diatoms, 519; his classification of diatoms, 532

L

Labarraque's fluid for bleaching vegetable substance, 427
Labels, permanent, 454
Labyrinthic structure of *Cyclammina*, 741; of *Parkeria*, 743
Labyrinthodon, tooth of, 1013
Lacunæ and canaliculi of bone, misinterpretation of, 370
— of bone, 943–945; dimensions of, in various animals, 946
— relation of size to that of blood-corpuscle, 946
Lagena, 721, 744
Lagenida, 744
Laguncula, 835, 874
— stolon of, 828; polypides of, compared with *Clavellinidæ*, 839
— *repens*, anatomy of, 828, 829
'Lamellæ' of corals, 802
— of *Hymenomycetes*, 576
Lamellibranchiata, shell of, 843
Lamellicornes, antennæ of, 912
Laminaria, 555, 556
Laminariaceæ, 556
Lamna, tooth of, 948
Lamp, Nelson's, 347; Beck's, 348, 349; Baker's, 350
Lampyris, antennæ of, 912
— *splendidula*, photograph through eye of, 908
Land-crab, young of, 893
Langley on use of osmic vapour for mucous glands, 429
Lankester (E. Ray) on *Bacteria*, 581; on movement of gregarines, 675; on *Protozoa*, 677 *note*; on intracellular digestion in *Limnocodium*, 787
Lantern-flies, wings of, 923
Lapis lazuli, 1016
Larva of *Echinodermata*, 820; of *Asteroidea*, 822; of *Echinoidea*, 823; of

Ophiuroidea, 822; of *Crinoidea*, 824; of ascidians, 840; of fly, 931; of *Acarina*, 933
Latex of Phanerogams, 620
Lathræa squamaria, embryo of, 648
Laticiferous tubes, free-cell formation in, 464
— tissue of Phanerogams, 620
Laurentian rocks, 762, 767
'Laver,' or green seaweed, 487
Lawrence's glycerin jelly, 448
Leaves, epiderm of, 637; internal structure of, 641; mode of preparation for examination of, 642
Leech, 880
Leeuwenhoek's simple microscope, 134
Legg's method of selecting *Foraminifera*, 769
Legs of insects, 924, 926; of *Acarina*, 932, 934
Leguminosæ, seeds of, 610
Leiosoma palmacinctum, 932; hairs of, 934
Leitz's objectives, 320
— semi-apochromatic objective, 320
Lens spherical, 12; biconvex, 12, 13; plano-concave, 13; diverging meniscus, 13; plano-convex, 13, 15, 22, 37; converging meniscus, 13; biconcave, 13; plano-convex, focal length of, 15; crossed biconcave, 16; crossed biconvex, 16; equiconvex, 16, 22; Stanhope, 37; Coddington, 37; Brücke, 38
— from Sargon's palace, 121
— invention of, 121–122
— achromatic, Charles's, 146; Barlow's, 147
Lenses, refraction by, 10, 25
— homogeneous immersion, of Powell and Lealand, 29; of Zeiss, 29
— fluorite; for apochromatic objectives, 34, 35
— combination of, 37
— resolving power of, 64; amplifying power of, 25, 26
— testing by *Coscinodiscus*, 333
Lepadidæ, 891
Lepidium, seeds of, 649
Lepidocyrtus curvicollis, scales of, 903
Lepidodendra, 607, 1005
Lepidoptera, scales of, 899, 900; wings of, 905, 923; scales of, mounting, 906; eyes of, 911; antennæ of, 912; mouth-parts, 916; eggs of, 929
Lepidosteus, bony scale of, 946, 952
Lepidostrobi, 607
Lepisma saccharina, scales of, 900, 901
Lepismidæ, 903
Lepralia, 833; extension of perivisceral cavity of, 851; mode of growth in, 828
Leptodiscus (ally of *Noctiluca*), 694 *note*
Leptogonium scotinum, 578
Leptothrix, form of, 581
Leptus autumnalis, 937
Lernæa, 889 *note*, 890
Lessonia, 556
Lettuce, laticiferous tissue, 620

Leucite, mineral inclusions in, 998; anomalies in, 1002
Lever of contact, Ross's, for testing covers, 381
Libellula, 911; respiratory apparatus of larva, 921
Liber, or inner bark, 633
LICHENS, 576–579; fungus-constituents of, 579
Licmophora, stipe of, 518–533, 534; flabella of, 534
— *flabellata*, 517, 533
Licmophoreæ, 545
— characters of, 533; vittæ of, 534
Lieberkuehnia, movement of, 657
— *paludosa*, 658
— *Wagneri*, 656–658
Lieberkühn's microscope, 138; his speculum, 282–284
'Ligamentum nuchæ,' structure of, 964
Light; refraction of, 2; recomposition of, by prisms, 18; convergence of, 18; path of, through compound microscope, 40; quantity of, 50, 51, 54; emission of, 51, 54; quantity of, and aperture, 54 *note*; cone of, 170; monochromatic, 271, 372; intensity of, necessaries for, 359
— modifiers, 284
Lignified tissue, test for, 440
Lignites, 1005
Lignum vitæ, wood of, 629
Lilac, pith of, 611
Lilium, experiments with pollen-grains of, 646
'Lily-stars,' 824. See *Crinoidea*
Limax maximus, palate of, 854
— shell of, imitated, 1023
— *rufus*, shell structure of, 852, 856
Lime, raphides of, 621
Limestone rocks, 1007
Limnæus stagnalis, nidamentum of, 858; velum of, 860
Limnocaridæ, characters of, 937
Limnocharis, seeds of, 649
Limnocodium, intracellular digestion in, 787
Limpet. See *Patella*
Limulus, 881
Linaria, seeds of, 649
Lister's struts for support of body, 147; his influence on improvement of English achromatic object-glasses, 148; his zoophyte trough, 297; his discovery of two aplanatic foci, 304; his note on Chevalier's objectives, 304; his influence on microscopical optics, 305; his triple-front combination, 309
Listrophorus, 932
Lithasteriscus radiatus, 550
Lithistid sponges, spicules of, 784
Lithocyclia ocellus, 771
Lituola, 739
Lituolæ, large fossil forms of, 741
Lituolida, 739
Live-boxes, 294, 295
Liver, 971

Liver-cells, 972
'Liverworts,' 590. See *Hepaticæ*
Lobosa, characters of, 659; examples of, 667–672
Lobster, 881; metamorphosis of, 893
'Lob-worm,' 872
Loculi, of anthers, 644
Locust, gizzard of, 917; ovipositors of, 928
Locusta, eye of, 911
Loftusia, 743
Loligo, pigment-cells of, 866
Lomas (J.) on calcareous spicules in *Alcyonidium*, 832 *note*
'London Pride,' parenchyme of, 618
Longicornes, antennæ of, 912
Lophophore of *Polyzoa*, 829, 874; of fresh-water *Polyzoa*, 833
Lophopus, collecting, 458
Lophospermum erubescens, winged seed of, 649
Lophyropoda, 883
Lorica of *Acineta*, 697; of *Ciliata*, 700; of *Rotifera*, 715
Loup-holders, 203
— for tank work, Steinheil's, 224
Loups, Reichert's, 38; Steinheil's, 38, 322, 457; Steinheil's aplanatic, 205; Zeiss's, 261
Louse, mounting media for, 897
Lovèn on classificatory value of palates in *Gastropoda*, 856
Loxosoma, lophophore of, 833
Lubbock on *Thysanura*, 901; on *Podura* scale, 903
Lucanus, 911; antennæ of, 912
Luminosity of *Noctiluca*, 690; of *Ctenophora*, 806; of annelids, 879
Lungs, circulation in, 980, 984
Lychnis, seeds of, 649
Lychnocanium falciferum, 771
— *lucerna*, 771
Lycoperdon, 575; hymene of, 576
Lycopodiaceæ, 606; in coal, 1006
Lycopodieæ, 606
Lyminas, collecting, 457
Lymph corpuscles, 961
Lysigenous spaces in Phanerogams, 613

M

Maceration of vegetable tissues, 624; Schultz's method, 625
Machilis polypoda, scale of, 902
Machines for cutting hard sections, 424, 425
Macrocystis, 556
Macrospores of *Polytoma*, 685; of sponges, 781
Macrourous *Decapoda*, young of, 893, 894
Madder, cells of pollen-chambers, 645
'Madre,' *Acanthometra* occurring in, 777
Madrepores, 802
Magenta as a selective stain, 436
Magma, 996
Magnetite, 995

Magnification, range of, 147
Magnifying power, 367; determination of, 238
Mahogany, size of ducts of, 624; stem of, 630
Malacostraca, 892
'Male' plants of *Polytrichum*, 596
Mallei of *Rotifera*, 715
Mallow, pollen-grains of, 646, 647
Malpighian vessel of *Gamasidæ*, 935
— layer of skin in mammals, 966
— bodies in vertebrate kidney, 971
Maltwood's finder, 246
Malva sylvestris, pollen-grains of, 646
Malvaceæ, pollen-grains of, 646
MAMMALIA: lacunæ in bones of, 946; plates in skin of, 950; epidermic appendages of, 953; red blood-corpuscles of, 958, 959; epidermis of, 966; muscle fibre of, 973; lungs of, 989
Mammary glands, 971
Man, arrangement of enamel in teeth of, 949; cement in teeth of, 950; hair of, 955; muscle fibre of, 973; lung of, 989
Mandibulate mouth, 913
'Mantle' and growth of shell in *Mollusca*, 849
Marble derived from limestones, 1011
Marchantia, 590–593; archegones of, 596; prothallium of, 602; stomates of, 640; elaters of, 645
— *androgyna*, 590
— *polymorpha*, 590–593
Margaritaceæ, 843; nacreous layer of, 846; prismatic layer of, 847
'Marginal cord' of *Calcarina*, 755
— of *Nummulites*, 759
Marine forms, collecting, 458
— glue for forming 'cells,' 385
— mites, 937
— work, tow-net for, 458; dredge for, 458; stick-net for, 459
Marshall's compound microscope, 135, 136
Marsipella elongata, 738
Martin's 'pocket reflecting microscope, 138; his large microscope, 139; his achromatic microscope, 145; his reflecting microscope, 145; his achromatic objective, 145
Marzoli's achromatic lenses, 302
Masonella, 736
Mastax of *Rotifera*, 715
Mastigophora Hyndmanni, 830
Mastogloia, stipe of, 518, 548; gelatinous sheath of, 518, 548; development of, 526; range of variation in, 547
— *lanceolata*, 548
— *Smithii*, 548
Matthews's method of sectionising hard substances, 420
Mayall on history of microscope, 119; on Assyrian 'lens' from Sargon's palace, 121; on Divini's microscope, 132
Mayall's removable mechanical stage, 134
Mayer's heating bath, 393
'Meadow-brown,' eggs of 929

'Measley pork,' due to *Cysticercus*, 868
'Mechanical finger' for selecting diatoms, 554
— movements of the stage in Tully's microscope, 147
— stage, 215
— — Turrell's, 165; Tolles', 166; Zeiss's, 167; Mayall's removable, 194
— tube-length of microscope, 155
— — Continental, 156
Medullary rays, 629
— — in dicotyledons, 627
'Medullary sheath' of Exogens, 623; of dicotyledons, 627
Medusa of fresh water, 787
Medusæ, mounting, 388; of Hydroids, 792; naked-eyed, 792; development of, 798; alternation of generations in, 801; nerves of, 976
Medusoids, collecting, 459
Megalopa, 894
Megaloscleres, 783
Megasphere of certain *Foraminifera*, 727
Megaspores of *Rhizocarpeæ*, 606; of carboniferous trees, 607; of *Isoeteæ*, 607; of *Selaginelleæ*, 607
Megatherium, teeth of, 950
Megatricha of Ehrenberg, a phase in development of *Suctoria*, 698; Badcock on, 698
Megazoöspores of *Ulothrix*, 486; of *Ulva*, 489; of *Scenedesmus*, 496
Megerlia lima, shell of, 851
Melanosporeæ, 554
Meleagrina, 843, 846
— *margaritifera*, 847
Melicerta, collecting, 457; in confinement, 458
Melicertadæ, 717
Melolontha, eye of, 911; antennæ of, 912; spiracle of larva, 920
— *vulgaris*, eye of, 907
Melosira, frustules of, 517, 530; auxospores of, 525, 526, 530; sporules of, 526; zygospore of, 530
— *ochracea*, 537
— *subflexilis*, 523, 524
— *varians*, 523, 524; endochrome of, 527
Melosireæ, characters of, 537; resemblance to *Confervaceæ*, 537
Membrana putaminis, 962
Membranipora, 832, 833
Membraniporidæ, 832
Mercury nitrate as a test for albuminous substances, 440
Mereschkowski on movements of diatoms, 531
Meridieæ, 545
— characters of, 533
Meridion circulare, 517, 532, 533
Merismopedia, 477
'Mermaid's fingers,' 803. See *Alcyonium*
Mesembryanthemum, seeds of, 649
— *crystallinum*, epiderm of, 639
Mesocarpus, conjugation of, 478; zygospore of, 478

Mesoderm of sponges, 780
Mesoglœa of *Hydra*, &c., 788 *note*
Mesophlœum, 633
Metal case for imbedding, 415
Metamorphism of rock-masses, 999, 1000; of limestones, 1011
Metamorphosis of *Lernæa*, 890; of *Cirripedia*, 892; of *Malacostraca*, 892, 893
Metazoa, 652, 779
Meteorites in oceanic sediments, 1015
Metschnikoff on acinetan character of *Erythropsis*, 702; on intracellular digestion, 787; on phagocytes, 961 *note*
Mica, 1000, 1001
Michael's (A.) opalescent mirror, 172
Micrasterias denticulata, binary division of, 512; form of cell of, 575
Micro-chemistry in Petrology, 1004; of poisons, 1023
Micrococci, form of, 581
Microcysts of *Myxomycetes*, 565
Microgromia socialis, 660, 661
Microlites, 996; in glass-cavities, 997
Micrometer, Cuff's, 140
— use of, 231
— eye-piece, 323
— — Nelson's new, 227, 228, 229; Jackson's, 232
Micrometers, 226–233
Micron, a, 82 *note*, 400
Micro-petrology, 991
'Microplasts' of *Bacterium rubescens*, 588 *note*
Micropyle in ovule, 610; of *Euphrasia*, 648; in orchids, &c., 648
Microscleres, 783, 784
Microscope, Mayall on the, 119; history and evolution of the, 119–225; invention of, 122; inventor of the name, 126; essentials in, 154–172; adjustments in, 156–165; stage of, 165–168; desiderata in, 215; preservation of, 278
— Galileo's, 129; Campani's, 130; Pritchard's, with Continental fine adjustment, 150; Ross-Jackson model, 151; Powell's (H.), 153; Smith and Beck's, 153
— achromatic, Euler on 145; Martin's, 145; Chevalier's, 146, 148; Selligue's, 146; Tully's, 147; Ross's early form of, 150
— aquarium, 219–225
— binocular, 61; Riddell's, 97; Nachet's, 98; Chérubin d'Orléans', 132; Wenham's stereoscopic, 98; Stephenson's, 100, 395; Ross-Zentmayer's, 178; Powell and Lealand's, 107, 175; Ross's, 177; Rousselet's, 200
— chemical, Nachet's, 216; Bausch and Lomb's, 217–220
— compound, 36, 39, 123, 127; construction of, 39; path of light through, 40; Rezzi on invention of, 127; Hooke's, 130; de Monconys', 130; Divini's, 131; Janssen's, 122; Marshall's, 135; Hertel's, 138; Martin's, 139; Adams's

variable, 140, 146 ; Jones's, 143, 146
Microscope, concentric, 171, 178
— demonstration, 225
— dissecting, Beck's histological, 197; Stephenson's binocular, 201 ; Ward's, 205; Baker's (Huxley's), 204; Zeiss's, 205; Beck's binocular, 207
— horizontal, Bonanni's, 135 ; Amici's, 146
— petrological, 992
— photographic, 211
— radial, 171, 178 ; Ross-Wenham's, 184
— reflecting, Newton's, 133; Martin's, 139, 145; Smith's, 144
— simple, 36, 128, 201 ; path of light through, 25 ; inventor of, 128 ; Bacon's, 128; Descartes', 128 ; Bonanni's, 134; Ward's, 205 ; Muschenbroek's, 134 ; Leeuwenhoek's, 135 ; Hartsoeker's, 135
— spectrum binocular, 276
Microscopes, modern, Powell and Lealand's, 172, 190; Beck's, 180, 189, 190, 194, 196; Swift's, 181, 190, 194, 197; Zentmayer's, 184 ; Baker's, 193; Continental models, 208; Zeiss's, 208–213
— portable, 198–200
Microscopic and macroscopic vision, 62
— determination of geological formations, 1012
— dissection, single lenses for, 88
— investigation of rocks, &c., 990
— vision, principles of, 48
Microscopical optics, principles of, 1
Microscopist's work-table, 341, 345
Microscopy, definition of, 340
Microsomes, 461, 468
Micro-spectroscope, Sorby-Browning, 272, 273
— use of, 277 ; in petrology, 1003
Microsphere of certain *Foraminifera*, 727
Microspores of *Sphagnaceæ*, 599; of *Rhizocarpeæ*, 606; in carboniferous trees, 607; of *Isoeteæ*, 607; of *Selaginelleæ*, 607 ; of *Polytoma*, 685 ; of sponges, 781
Microtome, ether-spray, 48
— Ryder's, 344 ; simple, 398 ; Rivet's model, 401 ; Thoma's (Jung's), 401–408 ; freezing apparatus for, 405, 406
— Cambridge rocking, 408; advantages of, 411
— freezing, Hayes', 411; minimum thickness of sections with, 412 ; Cathcart's, 412
Microzoöspores of *Ulothrix*, 486; of *Ulva*, 489 ; of *Hydrodictyon*, 495
'Mildew,' 566. See *Uredineæ*
Miliola, shell of, 724; encrusted with sand, 735
Miliolæ, 727
Miliolida, 726 ; in limestone, 1011
Miliolina, 727
Milioline *Foraminifera*, fossils of, 726
Miliolite limestone, 1011

Millepore, resemblance of *Polytrema* to, 749
Millon's test for albuminous substances, 440
Mineral nature of *Eozoön*, 767
Minerals, analysis of, 1003, 1004; microscopic testing, 1004
Minnow, circulation in tail of, 981
Mirror, 171, 172
— opalescent, as a substitute for polarising prism, 172
— replaced by rectangular prism, 173
Mites, 932. See *Acarina*
Möbius on mineral nature of *Eozoön*, 767
Mohl (Von) on protoplasm, 460 *note*
Moist-stage, Dallinger and Drysdale's, 289
Molecular coalescence, 1021
Molgula, development of, 841
Möller's diatom type-slide, 286
Mollusca, larvæ of, collecting, 459
— shells of, 843 ; shell-structure of, 843–849; colour of shell, 845; mantle and shell-growth, 849 ; palate of, 854; development of, 857 ; ciliation of gills, 864 ; organs of sense in, 864; bibliography, 866 ; resemblance of barnacles to, 891 ; 'liver' of, 971 ; muscle fibre of, 974 ; internal casts of, 1012; concretionary spheroids in shells of, 1021
Molluscan shells in mud of Levant, 1007
Molybdate of ammonia as a general stain, 437
Monad-form of *Microgromia*, 662
Monadinæ, life-histories of, 680–686; saprophytic affinities of, 681; effect of temperature on, 686; nucleus in 687
Monads, 680. See *Monadinæ*
Monas, 475
— *Dallingeri*, life-history of, 681
— *lens*, 680
Monaxonida, spicules of, 783
Monconys (De), inventor of field-lens, 130
Monera, Haeckel on, 677
Monerozoa, 552–658
Monocaulus, 795
Monochromatic light, 271, 372
— illumination, means of obtaining, 360, 361
Monocotyledons, 625 ; stem of, 625; nodes of, 626; epiderm of, 637
Monocotyledonous stem, fossilised, 1005
Monocular, Powell and Lealand's, 173, 174
Monocystis agilis, cyst of,
Monophytes, digestion in, 787 *note*
Monosiga, fission of, 689
Monothalamous *Foraminifera*, 721
Monotropa, seeds of, 649
Moraceæ, laticiferous tissue of, 620
Mordella beetle, eye of, facets in, 907
Mormo, scales of, 904
Morpho Menelaus, scales of, 900
Morula of sponges, 781
— compared to higher *Protozoa*, 651

Morula of *Gastropoda*, 859
Moseley (H. N.) on skeleton of pharynx of holothurian, 819 *note*; on *Chiton's* eyes, 865
Mosses, 594–599
— capsules of, wooden slides for mounting, 390
'Mother-of-pearl,' 846
Moths. See *Lepidoptera*
Motion, spiral, 875
Motor nerves, 976
Motorial end-plates, 977
'Moulds,' 569, 571
Moults of *Entomostraca*, 888, 889
'Mountain-flour,' 551
Mounted objects, keeping, 453; labelling, 453; arrangement of, 454
Mounting plate, 391, 392
— instrument, James Smith's, 394
— thin sections, 447
— in natural balsam, 449; in aqueous liquids, 450; in deep cells, 451
— diatoms, 450; *Ophiurida*, 450; *Polycystinæ*, 450; sponge-spicules, 450; chitinous substances, 450; palates of gastropods, 450; sections of horns, &c., 450; *Lepidoptera* scales, 906; wings of *Lepidoptera*, 906; hairs of insects, 906; eyes of insects, 910; blood, 962
— media, Canada balsam, 444, 449
Mouse, hair of, 954–955; cartilage in ear of, 970
Mouth, suctorial, of *Hemiptera*, 928
— of *Acarina*, 933
Mouth-parts of insects, 913
Movement, interpretation of, 874, 875
— of *Lieberkuehnia*, 657; of *Amœba*, 668; of *Dallingeria*, 683; of planarians, 870; of *Artemia*, 884; of *Branchipus*, 884; of fly on smooth surface, 925; of white corpuscles, 961; of connective tissue corpuscles, 965; of *Oscillariaceæ*, 490; of desmids, 510; of diatoms, 528; of *Naviculæ*, 531; of *Bacteria*, 581; of *Ciliata*, 701
Mucilaginous sheath of desmids, 510
Mucor, fermentation by, 575
— *mucedo*, 570
Mucorini, 569; spores of, 569; epispores of, 570
Mucous glands, Langley's method of preparing, 429
— membrane, 965, 966; capillaries in, 986
Mud of Levant, microscopic constituents of, 1007
Mulberry, laticiferous tissue of, 620
Mulberry-mass, 651
Müller (J.) on the *Radiolaria*, 771; on larva of Nemertines, 875
Müller's (Fr.) 'Common Nervous System' in *Polyzoa*, 831 and *note*
Müller's fluid, 430
Multicellular organisms, 651
Multiplication of *Palmoglœa*, 472; of *Protococcus*, 474; of *Volvox*, 488; of *Palmella*, 486; of *Bacteria*, 581; of *Microgromia*, 661; of *Amœba*, 669;

of *Dallingeria*, 683; of *Heteromita*, 685; of *Tetramitus*, 685; of *Noctiluca*, 694; of *Peridinium*, 695; of *Suctoria*, 698; of *Ciliata*, 704
Multiplying power of eye-piece, 240
Munier Chalmas and Schlumberger on dimorphism of *Foraminifera*, 727
Munier-Charles on certain fossil *Foraminifera*, 493
Muricea elongata, spicules of, 804
Musca, eye of, 911; antennæ of, 912
— *vomitoria*, eggs of, 930
'Muscardine,' 573
Musci, 594–599
Muscineæ, 598
Muscle-cells, 975
Muscular fibre, 972; structure of, 973; capillary network in, 986
Muscular tissue, preservative for, 448 preparation of, 974
Mushroom, 576
— spawn of, 575
Musk-deer, hair of, 954
Musschenbroek's simple microscope, 184
Mussels. See *Unionidæ* and *Mytilaceæ*
Mya arenaria, hinge tooth of, 848
Mycele of *Fungi*, 562; of *Ustilagineæ* 565
Mycetozoa, 563
Myliobates, tooth of, 949
Myobia, 932; legs of, 934; maxillæ of 934
Myobiidæ, 937
Myocoptes, legs of, 934
'Myophan-layer' of *Vorticella*, 701
Myopy, 120
Myriophyllum, a good weed to collect, 458
Myriopoda, hairs of, 904
Myriothela, intracellular digestion in, 787
Mytilaceæ, sub-nacreous layer in, 848
Mytilus, for observation of ciliary motion, 864
Myxamœbæ, 564
Myxogastres, 563
Myxomycetes, 509 *note*, 563; development of, 563, 566; spores of, 563, 565; swarm-spores of, 563; affinity with *Monerozoa*, 652
Myxosporidia, 674, 677

N

Nachet on 'immersion system,' 27; his binocular, 95, 98; his stereo-pseudoscopic microscope, 208; his changing nose-piece, 243
Nacreous layer in molluscan shells, 843, 846, 848
Naegeli and Schwendener on microscopical optics, 67
Nägeli's theory of formation of starch, 619
Nails, 953, 957
Nais, 879

NAP

Naphthalin, monobromide of, as a mounting medium, 445; refractive index of, 444
Narcissus, spiral cells of pollen-chambers in, 645
Nassula, mouth of, 702
Nauplius, compared with *Pedalionidæ*, 719
Nautiloid shell of *Foraminifera*, 722
Nautilus, 853
Navicula, 520, 528, 546; markings on, 522; cysts of, 526; zygospores of, 526; zoözygospores of, 526
— *bifrons*, presumed relation to *Surirella microcora*, 532 *note*
— in chalk, 1009
— *lyra*, as test for definition, 368
— *rhomboides*, markings on, 521; as test for definition, 368
Naviculaceæ, frustule of, 518; ostioles in, 519
Naviculeæ, characters of, 546
Nebalia, carapace of, 886
Needles for dissection, their mode of use, 397
Negative aberration, 27, 309 *note*
— crystals, 997
— eye-pieces, 321, 322, 323
Nelson on the sub-stage condenser, 72; his model, with Swift's fine-adjustment screw, 163; his horse-shoe stage, 167, 190; his fine adjustment to the sub-stage, 169; his screw micrometer eye-piece, 227; his new micrometer eye-piece, 228, 229; his 'black dot,' 233; his plan for estimating edges of minute objects, 233; his changing nose-piece, 244; his revolving nose-piece, 244; his lamp, 347; his means of obtaining monochromatic illumination, 361; his gelatin, 443
— on ghostly diffraction images, 72 *note*
Nelson and Karop on fine structure of diatoms, 521 *note*
Nemalion multifidum, 560
Nematodes, desiccation of, 869
Nematoid worms, 868
Nemertine larva, 875
Nepa, tracheal system, 919; wings of, 924
— *ranatra*, eggs of, 929
Nepenthes, spiral fibre-cells of, 623
Nereidæ, 872
Nereocystis, 556
Nerve-cells, 975
— staining with blue-black, 437
Nerve-fibres, 976
Nerve-substance, 975; mode of preparation, 978
Nerve-tubes, 975
Nerves, preservative for, 443
Nervures of wing of *Agrion*, 918
Nettle, hairs of, 639
Neuroptera, 897; eyes of, 911; circulation in wings of pupa, 918; wings of, 922
Newt, red blood-corpuscles of, 959; circulation in gills of larva, 981

NUC

Newton's reflecting microscope, 133
— suggestion of reflecting microscope, 144
— rings, 1018
Nicol prisms, 269
Nicol's analysing prism, 244; for resolving striæ, 325
Nicotiana, seeds of, 649
'Nidamentum' of *Gastropoda*, 858
Nitella, 505, 506
Nitrate of silver for tendon-cells, &c., 437
Nitric acid as a test for albuminous substances, 440
Nitrogenous substances, test for, 440
Nitzschia, 528
— *scalaris*, cyclosis in, 577
— *sigmoidea*, 535
Nitzschieæ, 535
Nobert's test lines, 286
Noctiluca, collecting, 459; tentacle (flagellum) of, 691, 692; cilium of, 691 *note*; protoplasmic network of, 692; reproduction of, 694
— *miliaris*, 690–694
Noctuina, antennæ of, 912
Nodes of monocotyledons, 620
Nodosaria, 744
Nodosarinæ, shell of, 722
Nodosarine shell, sandy isomorphs of, 740
Nonionina, 754
— shell of, 722, 723
Nonionine shell, sandy isomorph of, 739
Non-stereoscopic binoculars, 106
Non-striated muscle, 972, 974
Nose-piece, centring, used as sub-stage, 193; Brooke's, 241; centring, 242; Zeiss's calotte, 242; Beck's rotating, 242; Powell and Lealand's, 242; Nachet's changing, 243; analysing, 244; Nachet's changing, 244; Nelson's revolving, 244; Vogan's, 244
Nosema bombycis, cause of pébrine, 588
Nostoc, 490, 491; as gonid of lichen, 579; resemblance of *Ophrydium* to, 705
Nostocaceæ, 490; affinities with *Bacteria*, and *Myxomycetes*, 580
Notochord in *Tunicata*, 835; of *Appendicularia*, 842
Notonecta, 911; wings of, 924
Nucellus, 610
Nuclear stains, 430
— spindle, 468; plate, 468
Nuclein, 468
Nucleoli, 464
Nucleoplasm, 467
Nucleus, 464
— of minute organisms, 80
— action of acetic acid on, 440; its importance to cell, 465; division of, 468; fragmentation of, 468; presumed absence of, in some forms, 652; in monads, 687
— and cell division, 943 *note*
Nucule of *Chara*, 507, 508

NUD

Nudibranchs, nidamentum of, 858; embryos of, 860
Numerical aperture, 29, 53, 60, 333, 367; formula for, 333; problems on, 334
— — of Zeiss's apochromatic series of objectives, 318; of dry objective, 334; of water-immersion, 334; of oil-immersion, 334
— — and resolving power of objective, 336
— apertures, table of, 84–87
Nummuline layer of *Eozoön*, 764
— plan of growth, Parker and Rupert Jones on, 752 *note*
Nummulinidæ, 751
Nummulites, 751, 752, 756
— *distans*, 757
— *garansensis*, 757
— *lævigata*, 757
— *striata*, internal cast of, 759
— tubuli in shell of, 725
Nummulitic limestone, 756, 760, 1007, 1011
Nuphar lutea, parenchyme, 612; stellate cells of, 612
Nymph of *Acarina*, 933; of *Oribatidæ*, 933

O

Oak, size of ducts in, 624
— galls, 927
Oberhäuser's spiral fine adjustment, 151
Object-glass of compound microscope, 36, 39; of long focus, 40; of short focus, 40; capacity of, 326
Object-glasses, power of, 44
— — testing, 325; Abbe's method of testing, 326–333; diaphragms for use in testing, 329; Tripp's method of testing, 330
Object-holder for Thoma's (Jung's) microtome, 403, 404
— changer, Zeiss's, 243, 244
Objectives, achromatic, 19, 32; aplanatic, 19; apochromatic, 19, 30, 34, 80, 211; corrected, 20, 21; immersion, 28, 34, 58; aperture of, 43, 65, 333; maximum aperture of, 44; comparison of, 46; illuminating power of, 54 *note*; immersion *v.* dry, 54, 79; dry, with balsam mounted objects, 55; dry, 58; dry, for study of life-histories, 81; penetrating power of, 83, 336; sliding plate with, 241; rotating disc with, 241; of wide aperture, 316; of small aperture, examination of, 332; tests for, 332, 337; resolving power of, and numerical aperture, 336
— triple-back, 310; Wenham's duplex front, 311; Leitz's, 320; Reichert's, 321; adjusting, 306, 309
— achromatic, Martin's, 145; Marzoli's, 302; Tully's, 303; Selligue's, 303; Amici's, 304; Ross's, 305, 309; Powell's, 305, 309; Smith's, 305, 309; Wenham's, 310; covers for use with, 380

OPE

Objectives, apochromatic, 314, 315, 320
— oil-immersion, Amici's, 312; Tolles', 312; Zeiss's, 313, 317
— water-immersion, Powell and Lealand's, 310, 313; Prazmowski and Hartnack's, 310; Zeiss's, 317
Oblique illumination, 170, 171, 331
— illuminator, 170
Obliteration of structure by diaphragms, 68
Occhiale, Galileo's, 124, 125
Occhialino, Galileo's, 123, 126
Oceanic sediments, microscopic examination of, 1014
Ocelli of planarians, 871; of insects, 906, 910
Ocellites of compound eye, 906
Ocular, 40, 321; spectral, 276
Œdogoniaceæ, 502, 503
Œdogonium ciliatum, 502
Œnothera, pollen-grain, 646; emission of pollen-tubes of, 647; embryo of, 648
Oil for immersion lenses, suggested by Amici, 29
— of cassia, used with Stephenson's illuminator, 265
— of cedar-wood, for immersion objectives, 29
Oil-globules, 370, 371
Oil-immersion, 29
— — objectives, Amici's, 312; Tolles', 312; Zeiss's, 317
Oils, solvents for, 441
Okeden on isolation of diatoms, 553 *note*
Oleander, epiderm of, 638; stomates of, 641
Olivine, alteration of, 1001
— corroded crystals of, 995
Onchidium, eyes of, 865
Oncidium, spiral cells of, 618
Onion, raphides of, 621
Oögones of *Vaucheria*, 492; of *Sphæroplea*, 501; of *Œdogonium*, 503; of *Chara*, 507; of *Fucaceæ*, 556, 557; of *Peronosporeæ*, 567
Oölitic rocks, structure of, 1011
Oöphyte in ferns, 605
Oöspheres, use of the term, 467 *note*; of *Volvox*, 484; of *Vaucheria*, 492; of *Sphæroplea*, 501; of *Œdogonium*, 502; of *Chara*, 507; of *Phæosporeæ*, 556; of *Fucaceæ*, 557; of *Marchantia*, 593; of ferns, 604
Oöspores, 470; of *Volvox*, 484; of *Vaucheria*, 493; of *Achlya*, 495; of *Sphæroplea*, 500; of *Œdogonium*, 503; of *Chara*, 509; of *Fucaceæ*, 558
Ooze, *Globigerina*, organisms in, 736, 745; compared with chalk, 1007
Opalescent mirror as a substitute for polarising prism, 172
Opalina, 702
Opaque illumination by side reflector, 281
— mounts, 283
'Open' bundles, 635

OPE

Operculina, 752, 755; and *Nummulites* compared, 759
Operculum of mosses, 596
Ophiacantha vivipara, development of, 824 *note*
Ophioglossaceæ, development of prothallium of, 604
Ophioglossum, sporanges of, 601; prothallium of, 606
Ophiothrix pentaphyllum, spines of, 815; teeth of, 816
Ophiurida, mounting, 450
Ophiuroidea, skeleton of, 815; spines of, 815; teeth of, 816; larva of, 822; direct development in, 824 *note*
Ophrydia, quantities of, 706
Ophrydina, colonies in, 705
Ophrydium, cellulose in zoöcytium of, 706
— *versatile*, effect of light on, 702
Ophryodendron, 697
Opium poppy, latex of, 620
Optic axis of Powell and Lealand's No. 1, 174; of Baker's third-class, 194
Optical anomalies in petrology, 1002
— centre, 24
— tube-length of microscope, 155
— tube-length, Continental, 156
Orals of *Antedon*, 825
Orbiculina, 728, 729, 733
— shell of, 722
— compared with *Heterostegina*, 759
Orbitoides, 757
— *Fortisii*, 760
Orbitolina, 749
Orbitolinæ, occurring with flint instruments, 749
Orbitolites, 729–735
— shell of, 723; range of variation in, 735; structure of *Parkeria* resembling, 742; deposits of, 1007
— and *Cycloclypeus* compared, 726, 760
— *complanata*, animal of, 732–734
— *italiaca*, 731 *note*, 733
— *tenuissima*, 733
Orbulina, 745
Orbuline shell, sandy isomorph of, 740
Orchideæ, pollinium of, 647
Orchids, micropyle of, 648
Orchis, pollen-tubes of, 647; seeds of, 649
Organised structure and living action, 460
Organisms, minute, nucleus of, 80
Organs, 463
'Organs of sense' in *Ciliata*, 702 *note*
Oribatidæ, nymph of, 933; mouth-parts of, 933; legs of, 934; integument of, 934; auditory organ, 935; reproductive organs, 935; supercoxal glands of, 935; tracheæ of, 935; characters of, 936
Orienting small objects for sectionising, 416; Kingsley's method, 415
Origanum onites, seeds of, 649
Ornithorhynchus, hair of, 954
Orobanche seeds of 649

PAP

Orthoptera, eyes of, 911; antennæ of, 912; wings of, 923; nymph of, 933
Orthoscopic effect, 95; with Ramsden's circles, 107
— eye-piece, 322
Orthosira Dickiei, sporangial frustule of, 524
Oscillaria, movement of, 490
Oscillariaceæ, 490
— movements of, 375
Oscula of sponges, 780
Osmic acid and fatty structures, 429
Osmunda, sporanges of, 601
— *regalis*, prothallium of, 604 *note*
Ossein, of bone, 947
Ostiole of conceptacle of corallines, 561
Ostioles of *Naviculaceæ*, 529; of *Cymbelleæ*, 519
Ostracoda, 884
Ostreaceæ, shell of, 847
Ostrich, egg-shell of, 1021
Otoliths compared with artificial concretions, 1021
— of *Mollusca*, 865
Ovarium of *Polyzoa*, 831
Over-amplification, 88
Over-corrected objective, 20
Over-correction, 307, 308
Overton on *Volvox*, 484 *note*
Ovipositor of *Oribatidæ*, 936
Ovipositors of insects, 926, 927
Ovule of Phanerogams, 609
— suspensor of, 464
— structure of, 609, 610; development of, 647
Ovum of *Hydra*, 790
Oxytricha, a phase in development of *Trichoda*, 707
Oxyuris vermicularis, 868
Oysters, shell of, 847

P

Pacinian corpuscles, 977
Palæontology, use of microscope in, 1005
'Palate' of *Gastropoda*, 843, 854; classificatory value of, 856; preparation of, 856; viewed with polariscope, 857; bibliography, 857
Paleæ of grasses, silex in, 640
Palisade-parenchyma of leaves, 641
Palm, stem of, 626
Palmella, as gonid of lichen, 579
— *cruenta*, 486
Palmellaceæ, 486; frond of, 486
Palmodictyon, 487; zoöspores of, 487
Palmoglœa macrococca, life-history of, 471–473
Palpicornes, antennæ of, 911
Paludina, infested by *Distoma*, 870
Pancreas, 971
Pandorina, 475
— *morum*, generative process of, 485; swarm-spores of, 485
Pantocsek's finder, 246
Papaveraceæ, laticiferous tissue of, 620

PAP

Paper-cells, 386
Parabolic illuminator, 267–269; reflector (Sorby's), 281; speculum, 281
Paraboloid, 267–269; Edmunds', 269; Wenham's flat-topped, 269
Paraffin, solvents for, 417
for imbedding, melting point of, 417
cells, 386
Paramecium, Cohn's experiments on, 668
contractile vesicles of, 704
— *aurelia*, supposed sexual reproduction of, 710
Paraphyses of *Puccinia*, 567; of lichens, 578; of mosses, 596
Parasites, nourishment of, 462
Parasitic *Crustacea*, 889
— *Fungi*, 562
Parietal utricle, 463
Parker (T. J.) on osmic acid for *Entomostraca*, 428; on use of osmic acid for vegetable structures, 428, on *Hydra*, 787
Parkeria, 742; a possible *Stromatoporoid*, 742 *note*
Parnassia, seeds of, 649
Parthenogenesis, 931 *note*
— in *Saprolegniæ*, 569
Passiflora cærulea, pollen-grains of, 646
Passifloreæ, pollen-grains of, 646
Paste-worm, 869
Pasteur's solution for growing yeast, 574 *note*; his experiments with *Bacteria*, 587, 588
Patella, shell structure, 852; palate of, 855
Path of ray of light through a compound microscope, 40
Pathogenic bacteria, 585
Pavement epithelium, 968
Pear, constitution of fruit, 618
'Pearl oyster.' See *Meleagrina*
Pearls, 847
'Pébrine' in silkworms, 588
Peccary, hair of, 954
Pecten, prismatic layer in, 848; pallial eyes of, 864; eye of, 865; fibres of adductor muscle, 974
Pectinibranchiata, 861
Pectinidæ, sub-nacreous layer in, 848
Pedalion, 718
Pedalionidæ, 718
Pedesis, 373; experiments in, 373–4
Pediastreæ, 496; affinities of, 496
Pediastrum, zoöspores, 496, 497; microzoöspores, 497
— *Ehrenbergii*, 498
— ***granulatum***, 496, 497
— ***pertusum***, 497
— ***tetras***, 498
Pedicellariæ of echinids and asterids, 813
Pedicellina, lophophore of, 833
Pedicularis palustris, 648
— ***sylvatica***, embryo of, 648
Peduncle of *Lepas*, 891
Pedunculated cirripeds, 891

PHI

Pelargonium, petal of, 643; pollen-grain, 646
Pelletan on osmic acid, 428
Pelomyxa palustris, 669
Peneroplis, 726
— variation in shape of shell in, 722; shell of, 724; varietal forms of, 728
Penetrating power, 367
— — in objectives, 83; of objective, compared with illuminating power, 336
Penetration, 38, 82, 83
Penicillium, fermentation by, 575
— *glaucum*, 571
Pentacrinus asterius, skeleton of, 816
Pentatoma, wings of, 924
Peony, starch in cells of, 619
'Pepperworts,' 606
Perception of depth, 94
Perch, scales of, 952
Perforated shells of *Brachiopoda*, 850
Perforation of shell in *Foraminifera*, 724, 725
Perianth, 643
Perichlamydium prætextum, 775
Peridinium uberrimum, 695
Perigone of mosses, 595
Periodic structures, 74
Periostracum of molluscan shells, 846; of brachiopod shells, 850
Peripatus, tracheæ of, 935
Peritheces of lichens, 578
Peronosporeæ, 567, 568
Perophora, respiratory sac of, 839; circulation of, 839
'Perspicillum,' Wodderborn's, 127
Petals, 643
Petrobia lapidum, eggs of, 933
Petrological microscope, Swift's, 992
Petrology: micro-spectroscope in, 1003; micro-chemistry in, 1004
Pettenkofer's test, 440
Petunia, seeds of, 649
Peziza, *botrytis*-form of, 572
Pfitzer, on reproduction of diatoms, 523
Phæodaria, 777
Phæosporeæ, 554, 555
Phagocytes, 961 *note*
Phakellia ventilabrum, 782
Phallus, 575
PHANEROGAMIA, woody structures, preparation of, 427
— embryo-sac of, free-cell formation in, 464–466
— relation of, to Cryptogams, 607, 609; structure of stems, &c., 610, 625; structure of cells, 612, 613; intermediate lamella, 613; intercellular spaces, 613; cell-wall of, 617; sclerogen, 617; spiral cells in, 618; laticiferous tissue of, 620; mineral deposits in cells of, 620, 621; woody fibre in, 621 *et seq.*; fibro-vascular bundles, 625; root, structure of, 625; flowers of, 643; pollen-grains of, 644; fertilisation of, 647; ovules of, 647; seeds of, 648
Phanerogams. *See* PHANEROGAMIA
Philonthus, antennæ of, 912

Phloëm, 635
— of Exogens, 622
Pholas, shell of, 848
Phoronis, 875
Phosphorescence of sea, due to *Noctiluca*, 693
Phosphorus, as a mounting medium, 445
Photographic microscope, Zeiss's, 211, 212
Photometrical equivalent of different apertures, 50
Photo-micrograph through eye of *Lampyris*, 908
Photo-micrography, 174, 233, 324
— Campbell's differential screw used in, 194
— illumination for, 356
Phryganea, eye of, 907
Phycocyanin in *Chroöcoccaceæ*, 477
Phyco-erythrin, 560
Phycomyces nitens, 570
Phycophæin, 555
Phylactolæmata, 833
Phyllites, 1001
Phyllopoda, 886
Phyllosomata, skeleton of, 892
Physarum album, development of, 564
Physcia parietina, 579
Physma chalaganum, 579
Phytelephas, endosperm of seed of, 618
Phytophthora infestans, 568
Phytopti, mouth-parts of, 934
Phytoptidæ, 932; characters of, 938
Phytoptus, larva of, 938
Picro-anilin, 437
Picro-carminate of ammonia, 436
Picro-carmine, 436
Piedmontite, 1017
Pieridæ, scales of, 899
Pigment-cells of cuttles, 866; of vertebrate skin, 966; of fishes, 967; of Crustacea, 967
Pigmentum nigrum, of eye, 967
Pike, scales of, 952
Pileorhiza, 636
Pileus of *Acetabularia*, 493
Pilidium gyrans, 875
Pilulina Jeffreysii, 737
Pimpernel, petals of, 644
Pines, pollen-grains, showers of, 646 *note*
Pinna, structure of shell of, 815, 843–846; prisms of shell of, in *Globigerina* ooze, 1008; prisms of, in chalk, 1009
— *nigrina*, colour of shell of, 845
Pinnularia, 546
— *dactylus*, 551
— *nobilis*, 551
Pinus canadensis, 383
Pipette, 447
Pistil, 647
Pitcher-plant, spiral fibre-cells of, 623
Pith, arrangement of, 625, 627
Pitted ducts of Phanerogams, 623
Placoid scales, 952
Plagioclase felspar, 1003
Planaria, stomach of, 890
Planariæ, 869; movement of, 870; fission of, 871; ocelli of, 871; intracellular digestion in, 787

Planarians. See *Planariæ*
— allied to *Ctenophora*, 806
Plano-concave lens, 13
Plano-convex lenses, 13, 15, 22, 37
Planorbulina, 749
Plantago, cyclosis in, 616
'Plantain,' cyclosis in, 616
Plants and animals, differences between, 461
Planulæ, 792
Planularia hexas, in chalk, 1009
Plasmode in cells of *Nitella*, 509 *note*; of *Æthalium*, 563; of *Myxomycetes*, 564, 565
Plasmodium of *Protomyxa*, 654
Plastid, contrasted with cytode, 652
Plastidules, flagellated, of *Protomyxa*, 654
Plates, calcareous, of *Holothuricidæ*, 819
Pleochroism, 1002
Pleurosigma, 518, 546
— diffraction image of, 71
— *angulatum*, 69–71; as test for definition, 368; markings on, 521, 522
— *formosum*, as test for definition, 368
— *Spencerii*, sporules of, 526
Pliny on cauterisation by focussing sun's rays, 119; on sight, 120
Ploïma, 717, 718
Plumatella, collecting, 458
'Plumed-moths,' wings of, 923
Plumule of *Pieridæ*, 899
Plutarch on myopy, 120
Pluteus larva of echinoids, 821, 822, 823
Podocyrtis cothurnata, 771
— *mitra*, 771, 776
— *Schomburgkii*, 773, 776
Podophrya quadripartita, 697; immature form, 698
— *elongata*, 697
Podosphenia, sporules of, 526
Podura scale as test for high power, 332
'Podura scales,' 900, 903
Poduridæ, 903
Pointer in eye-piece, 325
Poisons, micro-chemistry of, 1023
Polariscope, condensers for use with, 262; for examination of gastropod palates, 857; crystals for use with, 1017; list of objects for, 1020
Polarised light for insect work, 366; use of, in micro-petrology, 992
Polariser, 262, 269
Polarising prism, substitution of opalescent mirror for, 172
'Polierschiefer,' 546
Polishing ground sections, 424
— sections of hard substances, 420
— -slate, 546
— -stones, 421, 546
Polistes (wasp), with attached mould, 571
Pollen-chambers of anthers, 644

Pollen-grain and tube, 609
— grains, 644; form of, 645; experiments with, 646
— mass, of orchids, 647
— tube, 645
— tubes, traced through the style, 647
Pollinium of orchids and asclepiads, 647
Pollinoids of *Florideæ*, 561; of lichens, 578
Polyaxial spicules, 783
Polycelis levigatus, 871
Polyclinidæ, 837
Polycystina, 771, 772, 776
— skeleton of, 659
Polycystinæ, as test for low powers, 332; mounting, 450
Polydesmidæ, 905
Polygastrica, Ehrenberg's erroneous views on, 678
Polygonum, pollen-grains of, 646
Polymorphina, 745
Polyommatus Argus, scales of, 900
Polyparies of zoöphytes, 786
Polypary of hydroids, 791
Polypes, 787. See *Hydrozoa*
Polypide, of *Polyzoa*, 829; formation of buds from, 830
Polypidom of zoöphyte, 828
Polypite, of hydroids, 791
Polypodium, sori of, 600
Polyporus, 575
Polystichum angulare, aposporv in, 605
Polystomella, shell of, 723
— *craticulata*, 752, 753
— *crispa*, 752, 754, 765
Polythalamous *Foraminifera*, 721
Polytoma uvella, life-history of, 684
Polytrema, 749; mode of growth compared with *Eozoön*, 763
— *miniaceum*, colour of, 724
Polytrichum commune, 595, 596
Polyxenus lagurus, hair of, 905
— — hair of, as test for objectives, 332; as test for definition, 368
Polyzoa, collecting, 457, 458; keeping alive, 458; 'cell' of, 828; structure of, 828; gemmæ of, 830; muscular system, 831; sexual reproduction of, 831; 'colonial nervous system,' 831 and *note*; fresh-water, lophophore of, 832; epistome of, 833; classification of the group, 833; bibliography of, 834; relation to *Brachiopoda*, 851; 'liver' of, 971
Polyzoaries in coralline crag, 1011
Polyzoary, 828
Pond-stick, 456
Poplar, pollen-grains of, 647
Poppy, laticiferous tissue, 620; seed of, 648
Porcellanea, 726–735
Porcellanous shells of *Foraminifera*, 724; of *Gastropoda*, 852
— and vitreous *Foraminifera*, difference in, 725, 726
Porcupine, hair of, 954
Pores of sponges, 780

Porphyra, trichogyne of, 561
Porphyritic crystals, glass inclusions in, 997
'Portable' microscope, Powell and Lealand's, 198, 199; Beck's, 199, 202; Rousselet's binocular, 200; Swift's, 198, 200
Portuna, skeleton of, 892
Positive aberration, 309 *note*
— eye-piece, 43
— eye-pieces, 321, 322, 328
Potash, caustic, action on horny substances, 440
Potato-disease, 568
— starch-grains of, 620
— tubers, starch in, 619
Powell, T., formula for objective, 34
Powell and Lealand's homogeneous immersion objective, 29; fluorite lenses, 34, 35; high-power binocular, 107; sub-stage, 170, 174; their microscopes, 173, 189, 190; binocular, 176; achromatic dry, 190; portable microscope, 198; rotating nose-pieces, 242; achromatic condenser, 251, 267; new low-power condenser, 252; apochromatic condenser, 254; dry achromatic condenser, 258; chromatic oil condenser, 258; condenser for polariscope, 262; achromatic oil condenser, 263, 267; latest condenser, 267; bull's-eye, 280; vertical illuminator, 285; compressor, 296; protecting ring for coarse adjustment, 301; water-immersion objectives, 310, 313; $\frac{1}{25}$-inch objective, for observation of cyclosis, 614; objectives, for study of monads, 687
Powell's (H.) microscope, 152, 153; fine adjustment applied to the stage, 153
— fine adjustment, 161
Prawn, skeleton of, pigment of, 893
Prazmowski and Hartnack's water-immersion objectives, 310
Preparation of vegetable tissues, 427
Presbyopy, 120
Preservative media, 441–443
Primary tissues of *Vertebrata*, 941
Primordial cells, 465, 466
— utricle, 463; of desmids, 510; of Phanerogam cells, 613
— chamber in *Foraminifera*, 723; of *Orbitolites*, 731
Primrose, cells of pollen-chambers, 645
'Prince's feather,' seed of, 648
Principle of microscopic vision, 43
Principles of microscopical optics, 1
Pringsheim on generative process of *Pandorina*, 485; on *Vaucheria*, 492
Prism, refraction by, 8, 9; Wenham's, 99; Stephenson's erecting, 102
— polarising, substitution of opalescent mirror for, 172
— rectangular, in place of mirror, 172
— Nicol's, 244, 269; Nicol's analysing, 325; Abraham's, 344
— refracting angle of, 9, 18

Prismatic epithelium, 968
— layer in molluscan shells, 844, 845, 847, 848
— layer of shells compared with enamel, 949
— shell-substances imitated, 1022
Prisms, recomposition of light by, 18
Pristis, tooth of, 948
Pritchard's doublets, 249
— microscope with Continental fine adjustment, 150, 151
Privet hawk-moth, eggs of, 929
Problems on refractive index, 5
Procarp, of *Florideæ*, 561
Projection eye-piece, 323
Promycele of *Puccinia*, 566
Prosenchymatous tissue, 621
Proteus, red blood-corpuscle of, 960
Prothallium of *Sphagnaceæ*, 599; of ferns, 602; of *Equisetaceæ*, 606; of *Rhizocarpeæ*, 606; of *Lycopodiaceæ*, 607
Protococcus, as gonid of lichens, 579
— *pluvialis*, 473–480; life-history of, 473; multiplication of, 474; zoöspores of, 474, 475; mobile and still forms of, 475–477; encysted, 480
Protomyxa aurantiaca, 652–654
Protoneme of *Batrachospermum*, 505
Protophytes, 460, 580, 651
— mounting, 442; mode of nourishment of, 462; movement by cilia and contracting vacuoles of, 465
Protoplasm, 461; vital attributes of, 461; continuity of, 469; of *Rhizopoda*, 658; of *Noctiluca*, 692
Protoplasmic substance in *Vertebrata*, 941
Protoplasts, 435
Protozoa, 651–712
— mode of nourishment of, 462
— Lankester's papers on, 677
'Pseudembryo' of *Antedon*, 827
Pseudo-navicellæ, 675
Pseudo-parenchyme of *Fungi*, 562
Pseudopodia of *Protomyxa*, 653; of *Vampyrella*, 655; of *Lieberkuehnia*, 656; of *Rhizopoda*, 658; of *Reticularia*, 658; of *Heliozoa*, 659; of *Gromia*, 660; of *Microgromia*, 661; of *Actinophrys*, 663; of *Amœba*, 668; of *Arcella*, &c., 671; in *Amœba*-phase of monad, 682; of *Eozoön*, 766; of *Globigerina*, 746; of *Radiolaria*, 772; of endoderm cells in zoöphytes, 787
Pseudoraphideæ, 527
Pseudoscope, Wheatstone's, 92
Pseudoscopic effects, 95
— effect with Ramsden's circles, 107
— vision, 92
Pseudo-scorpions, 932
Pseudo-stigmata of *Oribatidæ*, 935, 936
Pseudo-tracheæ, on fly's proboscis, 915 *note*
'Psorosperms,' 677
Pteris, sori of, 600; indusium of, 600
— *serrulata*, apogamy in, 605

Pterocanium, 772, 776
Pterodactylus, bones of, 1014
Pterophorus, wings of, 923
Pteroptus, 936
Ptilota, 560
Puccinia graminis, 566
Puff-ball, 576
Pulvilli of insects, 924; cockroach, 924 *note*
Pumice, 1014
Pupa of *Neuroptera*, circulation in, 918
— stage of fly, 931
'Purple layer,' 561
Purpura, method of examination of egg-capsules of, 863; supplemental yolk of, 931
— *lapillus*, nidamentum of, 858; development of yolk-segments of, 861, 862
'Puss-moth,' eggs of, 929
Pycnogonida, 881; related to *Arachnida*, 883 *note*
Pyrola, seeds of, 649
Pyroxene, alteration of, 1001
— andesite, 999

Q

Quadrula symmetrica, 671, 672
Quartz-porphyries, 995
Quartzite, 1001
Quekett (E.) on Martin's microscope, 139; on production of raphides, 621; on preparation of tracheæ of insects, 921; on minute structure of bone, 1013
Quekett's loup-holder, 204
'Quills' of porcupine, 954
Quinqueloculina, 727

R

Radials of *Antedon*, 825
Radiating crystallisation, 1017
Radiation of light in different media, 53–58; in air and balsam, 55–57
Radiolaria, collecting, 459; skeleton of, 659, 773–777; fossilised forms of, 771, 778 *note*; central capsule of, 772; zoöxanthellæ in, 773; bibliography of, 778
— colonies of, 773; distribution of, 778; mounting, 778
Radiolarian shells in 'ooze,' 1008
Rainey, on presumed cause of cattle plague, 677; on molecular coalescence, 1021
Ralfs on British desmids, 509 *note*; classification, 515; on *Nitzschia* and *Bacillaria*, 535
Ralph on dehydration by carbolic acid, 450
Ramsden circles, 107
Ramsden's eye-piece, 43; 'screw micrometer eye-piece,' 227, 228; positive eye-piece, 323; micrometer eye-piece, 325
Raphideæ, 527
Raphides of Phanerogams, 620, 621;

of plants and sponge-spicules compared, 784
Rat's intestine, villi of, 986
Rays, scales of, 952
Reagents, mode of labelling bottles, 345
Real image, 14 *note*; formation of, 23, 24
— object image, 321
Recomposition of light by prisms, 18
Red ant, integument of, 898
— blood-corpuscles of *Vertebrata*, 958; size of, in various *Vertebrata*, 959; relative sizes of, in various *Vertebrata*, 960
— coral, 801
— corpuscles, flow of, 980
'Red snow,' due to *Palmella cruenta*, 486
'Red spider,' 937
Red spots in *Infusoria*, 702
Reflector, Sorby's parabolic, 281
Refracted ray, 2
Refracting angle of a prism, 9, 18
Refraction, 57
— angle of, 3
— of light, laws of, 2, 3
— by plane surface, 3, 4; by curved surface, 5; by prisms, 8, 9; by lenses, 10–25
Refractive index, absolute, 2; of water, 3; relative, 4, 5; of crown glass, 5; of flint glass, 5; of balsam, 77; of gum styrax, 445; of Canada balsam, 445; of monobromide of naphthalin, 445; of phosphorus, 445
Refractive index of silicious coat of diatoms, 445
— indices of air, of cedar oil, of water, 60
Regulator, Reichert's, 393
Reichert's loups, 38; his objectives, 321; his thermo-regulator, 393
Reindeer, hair of, 954
Reproduction in *Actinophrys*, 664; of *Actinosphærium*, 666; of *Clathrulina*, 667; of *Euglypha*, 671; of sponges, 781; of *Campanulariida*, 794; sexual, of *Polyzoa*, 831; agamic, of *Entomostraca*, 887; agamic, 930; of *Acarina*, 932
Reproductive organs of *Acarina*, 935; of *Arachnida*, 935
REPTILES, lacunæ in bone of, 946; cement in teeth of, 950, plates in skin of, 950; epidermic appendages of, 953; red blood-corpuscles of, 958, 959; muscle-fibre of, 973; lungs of, 987
Reseda, seeds of, 649
Residuary secondary spectrum, 313
Resins, solvents for, 441
Resolving power of objectives, 367
— — of object-glasses, 44; of lenses, 64; of objective and numerical aperture, 75, 336
Respiration of insects, apparatus of, 918
Respiratory organ of spiders, 938
Rete mucosum, 966
Retepora, calcareous polyzoaries of, 833
Reticularia, 720
Reticularia, characters of, 658; examples of, 659–662
Reticulated ducts of Phanerogams, 623
Retinulæ, 907
Revolving nose-piece, Nelson's, 244
Rezzi on invention of compound microscope, 127
Rhabdammina, 738
— *abyssorum*, 740
Rhabdolithus pipa, 771
— *sceptrum*, 771
Rhabdom, 907
Rhabdopleura, 833
Rhamnus, stem of, 628
Rheophax sabulosa, 740
— *scorpiurus*, 740
Rhinoceros, horn of, 957
Rhizocarpeæ, 606
Rhizoids of mosses, 594
Rhizome of ferns, 600
RHIZOPODA, 658–674, 770
— protoplasm of, 461; ectosarc of, 464; Archer's papers on, 677; Bütschli on, 677; skeletons of, 720; sarcode of, 942; pseudopodial network of, 977
Rhizosolenia, 548
— cyclosis in, 517
Rhizostoma, 798, 800
Rhizota, 717
Rhododendron, pollen-grains of, 647
Rhodospermeæ, 503
Rhodospermin, 560
Rhodosporeæ, 554
Rhopalocanium ornatum, 773, 776
Rhubarb, stellate raphides of, 621; spiral ducts of, 623
Rhynchoflagellata, 694 *note*
Rhynchonellidæ, shell structure of, 851
Ribbons of sections, 408
Ribes, pollen-tubes of, 648
Rice, silicified epiderm of, 640
'Rice-paper,' 611
Rice-starch, 620
Riddell's binocular microscope, 96, 97
Ring-cells, 386, 387
Rivalto (Giordano da) on invention of spectacles, 120
Rivulariaceæ, hormogones of, 490
Roach, scales of, 952
Rochea falcata, epiderm of, 639
Rock, ground-mass of, 995; fluxion-structure of, 996
Rocks, method of making sections of, 991; metamorphism of, 999
Rodents, hair of, 954
Roe-stone, structure of, 1011
Root of Phanerogams, structure of, 625, 636 *et seq.*
Root-cap, 635
Rosalina varians, 723
Rose, glandular hairs of, 639
Ross (Andrew) on correction of object-glass, 19–21; his early form of achromatic microscope, 150; mechanical movements of his stage, 151; his fine adjustment, 151, 161; on illumination of objects, 250; his arrangement for lock-

ROS

ing coarse adjustment, 301; his achromatic objectives, 305–306; his lever of contact for testing covers, 381
Ross, model, 177
— and Co.'s tank microscope, 221
Ross-Jackson model, 178
Ross's 'Jackson' microscope, 151
Ross-Wenham's radial microscope, 178, 180
Ross-Zentmayer model, 178
Rotalia, 749; intermediate skeleton of, 750
— *aspera*, in chalk, 1009
— *Beccarii*, shell of, 722
— *Schroeteriana*, 750
Rotalian series, 748
Rotaliinæ, colour of shell, 724
Rotaline shells of *Foraminifera*, 722
— shell, sandy isomorph of, 739
Rotating disc of objectives, 241
Rotatoria, 678. *See* ROTIFERA
Rotifer vulgaris, 713
ROTIFERA, preserved by osmic acid, 428; collecting, 457; keeping alive, 458; as food of *Actinophrys*, 663; divisions of, 678, 712–719, 867, 869; habitats of, 713; structure of, 714–717; *mastax* of, 715; *lorica* of, 715; contractile vesicle of, 716; males of, 717; eggs of, 717; classification of, 717; desiccation of, 718, 887; bibliography of, 719; wheel apparatus of, compared with velum of gastropods, 860, 863; winter eggs of, 888; non-sexual reproduction of, 930
Rotten-stone, 546
'Round worm,' 868
Rousselet's binocular portable microscope, 200; his tank microscope, 224. 225; his compressorium, 295; his live-box, 295
Rowland's reversible compressor, 295
Rugosa, 801
Rumia crataegata, eggs of, 929
Rush, stellate tissue in, 612
Rutherford on freezing process, 419
Rutile in clastic rocks, 998
Ryder's microtome, 344

S

Sabellaria, tubes of, 872
Sable, hair of, 954
Saccammina in limestone, 1012
— *Carteri*, 737
— *spherica*, 737
Saccharomyces cerevisiæ, 574
Saccharomycetes, 574; zymotic action of, 574; endospores of, 575
Saccolabium guttatum, spiral cells of 618
Sachs on *Chara*, 509 *note*
Sago, starch-grains of, 620
Salicylic acid, for mounting, 442
Salivary glands, 971
Salmon, scales of, 952
— disease, 569

SCH

Salpæ, diatoms in stomach of, 544.
Salpidæ, 835
Salpingœca, calyx of, 689
Salt solution as a preservative me 442
Salter (J.) on the 'teeth' of *Ech* 814
Salvia verbenaca, spiral fibres in of, 618
Sand-grains surrounded by silica, 9
'Sand-stars.' See *Ophiuroidea*
'Sand-wasp,' 898
Sandy isomorphs (*Foraminifera*.
— tests of *Lituolida*, 739
Santonine, crystallisation of, 1017
Sap-wood, 629
Saprolegnia, 493, 494 *note*
— *ferox*, 569
Saprolegniæ, 569
Saprophytes, 575
Saprophytic organisms, study of, 2
— *Bacteria*, 585
— fungi, 562
Sarcocystids, 677
Sarcode, 460 *note*, 461; of *Rhiz* 658
Sarcolemma, 973
Sarcoptes scabiei, 937
Sarcoptidæ, mandibles of, 933; m of, 934; hairs of, 934; legs of, characters of, 937
Sarcoptinæ, 937
Sarcosporidia, 674
Sargassum bacciferum, 559
Sarsia (Medusa of *Syncoryne*), 78
'Saw-flies,' ovipositor of, 927
Saxifraga, seeds of, 649
— *umbrosa*, parenchyme of, 613
Saxifrage, cells of pollen-chambers
Scalariform ducts of ferns, 59 modified spiral ducts, 623
'Scales,' covering epiderm of leave of *Elæagnus*, 639
— of *Lepidoptera*, 899, 900; of *ptera*, 899; of *Curculio imperial* of *Lycænidæ*, 899, 901; of *Pi* 899; as tests for objectives of insects, markings of, 90 *Thysanura*, 901; on wing of *L ptera*, 923; of fishes, 950; of re 950, 953;
Scallops. See *Pecten*
Scarabæi, antennæ of, 912
'Scarf-skin,' 965
Scatophaga stercoraria, eggs of, 9
Scenedesmus, megazoöspores of, 4
Schists, 1000, 1001
Schizogenous spaces in Phanerogam
Schizomycetes, 579–589
Schizonema, 528
— *Grevillii*, 547
— mucous sheath of, 518, 547
Schizonemeæ, character of, 547
Schnetzler, on movement of *Oscil* 490
Schott (Dr.) on improvement of o glasses, 31

r on binocular vision, 107; his
ıdjustment, 160; his camera
, 236
s method of macerating vege-
issues, 625
(Prof. E.), his aquarium micro-
222
(Prof. Max) on identity of
de' and 'protoplasm,' 460 *note*;
closis in *Diatomaceæ*, 517; on
y of *Carpenteria*, 747
(Prof. F. E.) on soft parts of
ctella, 785 *note*
lener on lichens, 577
ula, 717, 718
spring, 396; for section cutting,

hyme of ferns, 600
n, 621
in *Fungi*, 562; of *Myxomycetes*,

idrium, indusium of, 600; sori
; sporanges of, 601
is, 881, 932
llar adjustment, 309
laria, seeds of, 649
toma' of *Cyanea*, 799
na, as gonid of lichen, 579
maceæ, 490; hormogones of,

hon, conjugation of, 556
none. See *Actinia*
nones, intracellular digestion in,

, 801. See *Gorgoniæ*
ies,' 777
wax varnish, 384
ts,' 832. See *Flustra* and *Mem-
bora*
eye-pieces, 323
gs.' See *Doris*, *Eolis*
hin,' 808. See *Echinus*
ls, 554
uity of protoplasm in, 469
08
y minerals, 1001
um, 19, 31; overcome by Abbe's
ves, 314
utting, scissors for, 397
, 431, 432; cover glass as, 432
ting, 447
ribbons of, 408; of hard sub-
s, 420; of bones, 420, 428; of
420, 423; of enamel, 420; of
420; of shells, 420; of teeth,
23; of hard and soft substances
er, 423; of Phanerogam tissues,

pollen-grains of, 646; seeds of,

9, 648
ation of *Gastropoda* egg, 859; of
l body, 872
olution for cleaning slides, 380
lla, archegone of, homology of,

lleæ, 607

Selective staining, 431
— stains, 436
Selenite, 270
— with mica film, 271
— stage, 270
Selenites, 262; blue and red, 271
Selligue's achromatic microscope, 146, 148; objectives, 303
Semi-apochromatic objective of Leitz, 320
Sempervivum, seeds of, 649
Seneca, on magnifying by water, 120
Sense, organs of, in *Mollusca*, 864
Sensory nerves, 976
— organs of sponges, 780
Sepals, 643
Sepia, pigment-cells, 866
Sepiola, eggs of, 866
'Sepiostaire' of cuttle-fish, structure of, 853; imitations of, 1023
Septa in shell of *Foraminifera*, 721, 728, 729
Serialaria, presumed nervous system in, 831
Serous membrane, 965, 966
Serpula, tubes of, 872
Serricornes, antennæ of, 911
Sertularia cupressina, 795
Sertularida, gonozoöids of, 794; zoöphytic stage of, 801
Sessile cirripeds, 891
Seta of *Tomopteris*, 877
'Sewage fungus,' 583
Sexual fructification, 470
— generation of *Volvox*, 488
Shadbolt on structure of *Arachnoidiscus*, 541
Shadbolt's turn-table, 386, 391
Shadow effects, 61
Shark, dentine of, 947
Sharks, scales of, 952
Sheep-pox, 588
Sheep-rot, 869
Shell, bivalve, of *Ostracoda*, 889
— calcareous, of *Reticularia*, 658; of *Microgromia*, 661
— silicious, of *Dictyocysta*, *Costonella*, 700
— of *Foraminifera*, 721–726; of *Lamellibranchiata*, 843; of *Brachiopoda*, 843
Shellac cement, protection against cedar oil, 384
'Shell-fish,' 843. See *Mollusca*
Shells of *Mollusca*, nacreous layer of, 843, 846, 848; prismatic layer of, 844, 845, 847, 848; colour of, 845; an excretory product, 846; sub-nacreous layer of, 847, 848
— of *Brachiopoda*, 849; periostracum of, 850; perforations of, 850
— of *Gastropoda*, structure of, 852
— of *Cirripedia*, 892
'Shield' of *Ciliata*, 700
Shrimp, concretionary spheroids in skin of, 1021
Shrimps, skeleton of, 893

SID

Side reflector, 281
— lever, short, fine adjustment, 162
— — Swift's vertical fine adjustment, 162, 181
Siebold on agamic reproduction in bees, 930
Sieve-plates, 635
Sieve-tubes, 635; in Exogens, 622
Sigillariæ, 607, 1005
Silene, seeds of, 649
Silex in *Equisetaceæ*, 605; in epiderm of grasses, 639
Silk glands of spiders, 939
'Silk-weeds,' 499
'Silkworm,' eggs of, 929
Silkworm disease, 573
Silpha, antennæ of, 912
Simple magnifier, 37
— microscope, 261
Sines, law of, 3
Siphonaceæ, 491–493; Munier-Charles on fossil forms of, 493
Siphonostomata, 889 *note*
Siricidæ, ovipositor of, 927
Sirodot on alternation of generations in *Batrachospermum*, 504
Skate, muscle fibre, 973
Skeleton, dermal, of *Vertebrata*, 950; fossilised, 1012
— fibrous, of sponges, 781
— silicious, of *Heliozoa*, 659; of *Radiolaria*, 771
— of sponges, 779; of zoöphytes, 786; of *Echinoidea*, 808; of *Asteroidea*, 815; of *Ophiuroidea*, 815; of *Crinoidea*, 816; of *Holothurioidea*, 818; of *Antedon*, 825; of *Vertebrata*, structure of, 944
Skin, 965; pigment-cells in, 966; capillaries in, 986
Skip-jack, antennæ of, 911
Slack on the costæ of *Pinnularia*, 546
Slack's optical illusion, 370
Slide-forceps, 393
Slide-glass, 379
Slides for cultures, 288, 289
— Seiler's solution for cleansing, 380
Sliding-plate of objectives, 241
Sloths, fossil, teeth of, 948
Slug. See *Limax*
Slug's eye, 865
Slugs, *Rotifera* in, 713
Smell, organ of, in insects, 924
Smith and Beck's microscope, 153, 154
Smith's Cassegrainian microscope, 144; his reflecting microscope, 144
Smith (H. L.) on Tolles' binocular eyepiece, 103; his vertical illuminator, 284, 285; on classification of diatoms, 527
Smith (James) on use of bull's-eye with high powers, 280; his separating lenses, 309; his mounting instrument, 394
Smith (T. F.) on markings of diatoms, 522
Smith (W.) on cyclosis in *Diatomaceæ*, 517; on species of diatoms, 530 *note*; on habits of diatoms, 548

SPH

Smith (W. H.) on structure of f
519 *note*; on movements of
531
Snail, 854; eye of, 865. See *He*
— muscle of odontophore, 974
Snake, lung of, 987
Snapdragon, seed of, 648
Snell's 'Law of Sines,' 49
Snow, crystals of, 1016
Snowberry, parenchyme of fruit
Snowdrop, pollen-grains of, 647
Soda, caustic, action on horny su
440
Soemmering's simple camera, 2
Sole, scales of, 950, 951, 952
Solen, prismatic layer in, 848
Solid cones of light for minute
tion, 362
— eye-pieces, 42, 322
— image, 95
— objects, delineation of, 83;
appreciation of, 88
— vision, the consequence of
illumination, 61
Sollas on sponges, 783 *note*; or
tensions of the perivisceral
Polyzoa, 851
Sorby (H. C.) on microscopic
of crystals, 990
Sorby's parabolic reflector, 281
Sorby-Browning's micro-spec
272, 273
Soredes of lichens, 577
Sori of ferns, 600
Sound-producing apparatus of
923
Spatangidium, 539
Spatangus, spines of, 813
'Spawn' of mushroom, 575
Spectacles, invention of, 120
Spectra, diffraction, 67
— artificial, 274
Spectral ocular, Zeiss's, 276
Spectro-micrometer, bright-line,
Spectroscope in micro-chemica
tions, 1024
Spectroscopic test, 273
Spectrum, 19; irrationality of, 1
— binocular, microscope, 276
— map, 275
— natural, 274
— of dark lines, 273; of bright l
Speculum, parabolic, 281; Lieb
282–284; in Smith's illumina
285
Spermathecæ of *Gamasidæ*,
Tyroglyphidæ, 936
Spermatia of *Puccinia*, 567; of
578
Spermatic fluid, preservative for,
Sperm-cells, 467; of *Volvox*,
ferns, 603; of sponges, 781; of
790; of *Polyzoa*, 831
Spermogones of *Puccinia*, 5
lichens, 578
Sphacelaria, 555
Sphacele, 555

SPH

Sphæria in caterpillars, 574
Sphæroplea annulina, 500, 501
Sphærozosma, rows of cells in, 512
Sphærozoum ovodimare, 777
Sphagnaceæ, 598, 599
Sphagnum, leaf of, 598
Sphenogyne speciosa, winged seed of, 649
Spherical aberration, 14, 15, 31, 249, 251, 254, 331
—— diminished by Huyghens' objective, 42
Spheroidal concretions of carbonate of lime, 1021
Sphingidæ, antennæ of, 912
Sphinx, eye of, 911; antennæ of, 912
— *ligustri*, eggs of, 929
Spicules of alcyonariáns, 804
— of sponges, 772; their names, 783–784
— silicious, of sponges, 781
— calcareous, of sponges, 781
Spiders, 881, 932, 938; microscopic objects furnished by, 938; spinning apparatus, 939
Spinal cord, Hill's method of preparation of, 434
Spindle fibres, 468
Spinnerets of spiders, 939
Spiny lobster, metamorphosis, 893
Spiracles of insects, 919, 920
Spiral cells in Phanerogams, 618; mode of preparation of, 619
— crystallisation, 1018
— focussing for projection-lens, 324
— vessels of Phanerogams, 622, 623; observation of, *in situ*, 644; of plants compared with tracheæ of insects, 919
Spiriferidæ, perforation in shells of, 851
Spiriferina rostrata, shell of, 851
Spirillina, 744
— sandy isomorph of, 739
Spirillum, movement of, 375; granular spheres of, 588 *note*
— *undula*, 586
— *volutans*, movement of, 581, 583, 586
Spirit, dilute, as a preservative medium, 442
Spirochæte, 581
Sprogyra, 478; attacked by *Vampyrella*, 654
Spirolina, a varietal form of *Peneroplis*, 728
Spiroloculina, 727
Spirula, 853
— shells of, bearing *Protomyxa*, 652
Spirulina, movement of, 490
Splachnum, sporange of, 594
Splenic fever, 588
— due to *Bacillus anthracis*, 582
Sponge-spicules, 781–784
— mounting, 450
— in *Carpenteria*, 747; in mud of Levant, 1007
Sponges, 779–786; skeleton of, structure of, 779, 780; reproduction of, 781; habitat of, 785; preparation of, 785, 786; bibliography of, 786; pseudopodia of cells in, 786; intracellular digestion in, 787; fresh-water form of, 787

STA

Spongilla, 785
Spongolithis acicularis, 550
Spongy parenchyma of leaves, 641
Spontaneous generation, 686
Sporange of *Fungi*, 562; of *Marchantia*, 590, 593; of mosses, 596; of *Sphagnaceæ*, 599; of ferns, 600; of *Equisetaceæ*, 605; of *Myxomycetes*, 565
Sporangia of *Lycopodiaceæ* in coal, 1006
Sporangiophores of *Mucorini*, 569
Spore, use of the term, 467 *note*
Spores of *Nostoc*, 491; of *Myxomycetes*, 563, 565; of *Peronosporeæ*, 568; of *Bacteria*, 587; of *Marchantia*, 593; of mosses, 597; of ferns, 601; of ferns, method for studying development of, 604 *note*; of *Equisetaceæ*, 605; of *Lycopodieæ*, 606; of gregarines, 675; of *Monas Dallingeri*, 682; of *Lycopodiaceæ* in coal, 1006
— different kinds of, 470 *note*
— resting, of *Chætophoraceæ*, 588
Sporids of *Ustilagineæ*, 565; of *Puccinia*, 566
Sporocarp of *Ascomycetes*, 572
Sporogone of mosses, 597
Sporophores of *Myxomycetes*, 565; of *Peronosporeæ*, 568; of *Ascomycetes*, 571
Sporophyte in ferns, 605
Sporozoa, 674–677
Sporules of *Melosira*, 526; of *Pleurosigma*, 526; of *Podosphenia*, 526
Spot-lens, 267
Spring-clip, 394
— press, 394
— scissors, 396
'Spring-tails,' 903. See *Poduridæ*
Squid, 866
Squirrel, hair of, 954, 955
Stag-beetle, antennæ of, 912
Stage, horse-shoe, Nelson's, 163, 190; of the microscope, 165–168; concentric, rotatory motion of, 167; qualities needful in a, 167; in Hartnack's model, 211; mechanical, 215; graduated rotary, 388
— -forceps, 287
— -micrometer, 226, 230, 239, 240
— moist, 290
— -plate, glass, 288
— thermostatic, 292, 293
— Turrell's, 165, 189; Tolles', 166, 184; Zeiss's, 167
— -vice, 287
'Staggers' of sheep, due to *Cœnurus*, 868
Stahl on movement of desmids, 510
Staining, process of, on glass slides, 430, 431; multiple, 438; double, 438; methods, 439; differential, 439
— *Bacteria*, 437, 438
— fluids, 432–437
— processes, 430
Stains, violet of methanilin for *Bacteria*, 437; methyl-blue for *Bacteria*, 638

STA

Stains, Nicholson's blue, 439
Stanhope lens, 37
Stanhoscope, 38
Staphylinus, antennæ of, 912
Star-anise, tissue of testa of, 617; testa of seeds of, 649
Starch, tests for, 440; formation of, 619
— grains, 464, 465; mode of growth, 620; hilum of, 619; in *Canna*, 620; in potato, 620; in wheat, 620; in rice, 620
'Star-fish,' 815. See *Asteroidea*
Statospore of *Protomyxa*, 653
Staurastrum, binary division of, 512; form of cell, 515
— *dejectum*, 498
Stauroneis, 546
'Stauros' of *Achnanthes*, 545
Steenstrup on alternation of generations, 801
Stein on affinities of *Volvox*, 479; on contractile vacuoles of *Volvox*, 481 *note*; on *Flagellata*, 689; on *Noctiluca*, 694 *note*; on *Acinetina*, 699 *note*
Steinheil's loups, 38; his combination of lenses, 38; his aplanatic loup, 205; his loup for tank work, 234; his formula for combination of lenses, 316; his triple loups, 322
Stellaria, seeds of, 649
— *media*, petals of, 644
Stem of mosses, 594; of *Bryaceæ*, 598; of *Sphagnaceæ*, 598; structure of, in Phanerogams, 625; of Phanerogams, development of, 634, 635; treatment of, for examination of their structure, 636, 637
Stemmata of insects, 910; of spiders, 938
Stentor, collecting, 457; impressionable organs of, 702; contractile vesicle of, 704; conjugation of, 711
Stephanoceros, collecting, 457; in confinement, 458
Stephanolithis spinescens, 771
— *nodosa*, 771
Stephanosphæra pluvialis, amœbiform phase of, 485 *note*
Stephenson on *Pleurosigma angulatum*, 70; on 'intercostal points,' 73
— his suggestion on homogeneous immersion, 28
— on *Coscinodiscus*, 538
Stephenson's binocular, 100, 344; substage condenser, 101; erecting binocular, 102; erecting prism, 102; catadioptric illuminator, 170, 263; binocular dissecting microscope, 201, 203, 395; tank microscope, 220
Stereocaulon ramulosus, 579
Stereo-pseudoscopic microscope, Nachet's, 208
Stereoscope, 90; Brewster's modification of, 91
Stereoscopic binocular, Wenham's, 98; for study of opaque objects, 105, 107
— eye-piece, Abbe's, 103
— vision, 89–98

SUN

Sterigmata of *Puccinia*, 566
Sterile cells of *Volvox*, 483
Stibbite, 998
Stichopus Kefersteinii, 819
Stick-net for marine work, 459
Stickleback, parasite of, 890; circulation in tail of, 981
Stigmata of insects, 919, 920
'Stinging hairs' of nettle, 632
Stings of insects, 926, 927
Stipe of diatoms, 517, 518; of *Licmophora*, 534; of *Gomphonema*, 545
Stolon of *Foraminifera*, 721; of *Ectocarpus*, 764; of *Lagunculæ*, 828; of ascidians, 838
Stomach, follicles of, 971
Stomates, 640
— of *Marchantia*, 591
Stomopneustes variolaris, spines of, 812
Stone-cavities in crystals, 997
Stone-mites, eggs of, 933
Stones of fruit, preparing sections of, 624
— of stone fruit, constitution of, 618
Stone-wort, 505
Stony corals, resembled by polyzoaries, 828
Stop, introduction of, 37; in the eye-piece, 42; use of, 261, 263
Strasburger's borax carmine, for study of embryo-sac, 435
Strawberry, parenchyme of fruit, 613
Streptocaulus pulcherrimus, 795
Striated muscle, 972; size of fibres in different groups, 973
Striatella unipunctata, 527
Striatellæ, characters of, 536
'Strobila' of *Cyanea*, 789
Stromatopora, doubtful character of, 767
Stromatoporoids, 742 *note*
Strophomenidæ, perforations in shells of, 851
Stylodyctya gracilis, 775
Suberous layer of bark, 633
Sub-nacreous layer in molluscan shells, 847, 848
Sub-stage, 169–171, 215; Nelson's fine adjustment to, 169; Powell and Leland's, 170, 174; swinging, 170, 171, 184; in Ross-Zentmayer's model, 178; in Beck's microscope, 181; central nose-piece used as, 193
'Sub-stage condenser,' Nelson's, 72; Stephenson's, 101; compound, 185
— illumination, 248
— simplest form of, 261
Succulent plants, stomates in, 640
Sucker on legs of *Sarcoptidæ*, 934
Suckers on foot of *Dytiscus*, 925; of *Culicinidæ*, 926
Suctoria (*Protozoa*), 696–699
— (*Crustacea*), 890, 891
'Sugar-louse,' 901. See *Lepisma*
Sulphuric acid, as a test, 440
'Sun-animalcule,' 662
'Sundew,' glands of, 639
Sunk-cells, 388

SUP

Super-amplification, 33
Super-stage, 169
Supplemental yolk in *Purpura*, 862, 863, 931
Surirella, 518, 535; conjugation of, 528; zygospores of, 529; movements of, 531; frustule of, 535
— *biseriata*, cyclosis in, 517
— *caledonica*, 551
— *constricta*, 536
— *craticula*, 551
— *plicata*, 551
Surirelleæ, 535
Suspensor of ovule of Phanerogams, 464
Sutural line of desmids, 590
Swarm-spores, 466; not a new generation, 467; meaning of term, 470 *note*; of *Pandorina*, 485; of *Hydrodictyon*, 495; of *Cutleria*, 556; of *Clathrulina*, 667; presumed, of *Pelomyxa*, 670
Sweat-glands, 966
'Sweetbread,' 971
Swift's side-lever, 158; vertical side-lever fine adjustment, 162, 181; microscopes, 181, 190, 194, 197; portable microscope, 198; low-power condenser, 252; condenser for polariscope, 262; sub-stage illuminator, 271; microspectroscope, 275; live-box, 295; petrological microscope, 992
Symbiosis in lichens, 578
Symbiotes tripilis, hairs of, 934
Symbiotic algæ in radiolarians, 773
Sympathetic nerves, 978
Symphytum asperrimum, seeds of, 649
Synalissa symphorea, 579
Synapta digitata, 'anchors' of, 819
— *inhærens*, 'anchors' of, 819
Synaptæ, rotifers in, 713
Syncoryne Sarsii, gonozoöids of, 792
Syncrypta, 475
Synedra, 535
Syringammina, 736
Syringe for catching minute aquatic objects, 300
Syrup, as a preservative medium, 442
— and gum, as a preservative medium, 443

T

Tabanus, 911; ovipositor of, 927
Tabellaria vulgaris, 551
Table of numerical apertures, 84–87
— for microscopists, 341–345; for dissecting and mounting, 342
Tactile papillæ of skin, 966; nerve to, 977
Tadpole, pigment-cells of, 967; circulation in tail of, 980; general circulation in, 981; blood-vessels of, 983, 984
— of ascidians, 841
Tadpole's tail, epithelium of, 968
Tænia, 867
Tank microscopes, 219–225
Tannin, test for, 440
Tapetal cells in fern antherid, 603

THA

'Tape-worm,' 867
Tardigrada, desiccation of, 869
Tarsonemidæ, 937
Taste, organs of, in insects, 917, 924
Teeth, decalcification of, 426
— fossilised, 1012
— in palate of *Helix*, 854; of *Limax*, 854; of *Buccinum*, 854; of *Mollusca*, 854
— preparation of, 947
— of *Echinus*, 814; of *Ophiothrix*, 816; of *Vertebrata*, 947
— of elephant, Rolleston on enamel in, 852; of *Rodentia*, Tomes on enamel in, 852
Tegeocranus cepheiformis, 932
— *dentatus*, 932
Tegumentary appendages of insects, 898
Telescope, Barker's Gregorian, 144
Teleutospore generation of *Puccinia*, 566
Temperature, effect of, on various monads, 686
Tendon, 948
Tentacle of *Noctiluca*, 691, 692
'Tentacles' of *Drosera*, 639; of *Suctoria*, 697; of *Hydra*, 788; of annelids, 873
Tenthredinidæ, ovipositor of, 927
Terebella, tubes of, 872; gills of, 873
— *conchilega*, 872
Terebratula bullata, shell of, 851
Terebratulæ, shells of, 849, 850
Terpsinoë musica, 537
Terpsinoëæ, character of, 537
Tertiary tints in crystalline bodies, 1018
Tesselated epithelium, 968
Test of *Gromia*, 660; of *Arcella*, 670; of *Difflugia*, 671
Testa of seeds, 649
Testaceous amœbans, 670, 671
Testing object-glasses, 325; diaphragm for use in, 329; Fripp's method, 330; Abbe's method, 326–333
Test-plate, Abbe's, 330, 331
Tests, sandy, of *Lituolida*, 739
Tethya, spicules of, 1008
Tetramitus rostratus, life-history of, 685; nucleus of, 688
Tetranychi, 937
Tetranychus, mandibles of, 933
Tetraspores of *Florideæ*, 561; of *Vampyrella*, 655
Textularia, 248
— *aculeata*, in chalk, 1009
— *globulosa*, in chalk, 1009
Textularian form of shell, 723
— series, 748
Textulariidæ, 736
Textulariniæ, arenaceous character of, 748
Thalassicolla, 772, 777
Thallophytes, 467, 470
Thallophytic type, passage to cormophytic, 594
Thallus of *Ulva*, 488; of *Phæosporeæ*, 555; of lichens, 577
Thaumantias Eschscholtzii, 797

THA

Thaumantias pilosella, 797
'Theca' of mosses, 596
Thecaphora, 792
Thecata, 792, 794
— zoöphytic stage of, 801
Thermo-regulator, Reichert's, 393
Thermostatic stage, Dallinger's, 292–293
Thoma's (Jung) microtome, 401
Thompson (J. Vaughan) on pentacrinoid larva of *Antedon*, 825; on *Cirripedia*, 891
Thomson (Wyville) on development of *Antedon*, 827
Thread-cells of zoöphytes, 701; of *Hydra*, 788; of *Zoantharia*, 801, 802; of planarians, 871
'Thread-worm,' 868
Threads of spiders' webs, 939
Thurammina papillata, 738, 740
Thwaites on conjugation of *Epithemia*, 529; of *Melosira*, 530
Thysanura, scales of, 901
Ticks, 932. See *Acarina*
Tineidæ, wings of, 923
Tinoporus baculatus, 749
Tipula, eye of, 911; antennæ of, 912; spiracle of, 920
Tolles' binocular eye-piece, 102; his mechanical stage, 166, 184; his vertical illuminator, 285; his water-immersion objectives, 310; his apertometer, 333
Tomes (Charles) on teeth, 949
Tomopteris onisciformis, 876, 877; development of, 878
— *quadricornis*, 878
'Tongue' of *Gastropoda*. *See* Palate
'Tortoise-shell butterfly,' eggs of, 929
Torula cerevisiæ, 574
Total reflexion, 6, 7
Tourmaline, pleochroism in, 1002
Tow-net, 458
Tow-nets of *Challenger* Expedition, 459 *note*
Tracheæ of insects, 918; of *Acarina*, 935
Tracheïdes of ferns, 600; of conifers, 622, 628
Trachelomonas, 475
Tradescantia virginica, cyclosis in hairs of, 615, 616
Tragulus javanicus, red blood-corpuscle of, 960
Trematodes, 869
Triceratium, 518, 520
— experiments with, 357, 358
— *favus*, 542
— markings on, 522
— *fimbriatum*, as test for higher powers, 332
Trichocysts of *Ciliata*, 701
Trichoda lynceus, crawling of, 702; reproduction of, 707–709
Trichodina grandinella, a phase in development of *Vorticella*, 707
Trichogyne of *Florideæ*, 561; in lichens, 578
Trichonympha, 702

UND

Trichophore of *Florideæ*, 561
Trichophrya, a phase in development of *Suctoria*, 698
Trigonia, prismatic layer in, 848
Triloculina, 727
Triple-backed objectives, 310
Triplet, Holland's, 37
Triplex front to objectives, 317
Tripoli stone, 546
Trochus zizyphinus, palate of, 855
Trombidiidæ, 932; legs of, 934; hairs of, 934; eyes of, 935; tracheæ of, 935; characters of, 936
Trombidium, maxillæ of, 934; larvæ of, 937
— *holosericum*, 937
Trophi of *Rotifera*, 715
Truncatulina rosea, colour of, 724
'Tube-cells,' 382
Tube-length, English and Continental, 155
Tuberculosis, bacillus of, 437; Pittion and Roux's method of staining, 439
Tubifex rivulorum, gregarine of, 676
Tubipora, 801
Tubularia, gonozoöids of, 793
— *indivisa*, 793
Tubuli in *Nummulites*, 751; of dentine, 948
Tubulipora, 833
Tulip, raphides of, 621
Tully's achromatic microscope, 147; his live-box, 294; his triplet, 303; his achromatic objective, 303
'Tunic' of *Tunicata*, 835
TUNICATA, 828, 835–842; zoölogical position of, 835; bibliography of, 842; 'liver' of, 971
Turbellaria, 867, 870
— larvæ of, collecting, 459
Turbinoid shell of *Foraminifera*, 722
Turbo, shell structure of, 852
Turkey-stone, use of, 421; constituents of, 546
Turn-table, Shadbolt's, 386, 391; Griffith's, 391
Turpentine, uses of, 441
Turrell's mechanical stage, 165, 189
Twin lamellæ in leucite, 1002
Tylenchus tritici, 869
Tympanum of cricket, 923
Typhoid of the pig, due to *Bacillus*, 588
Tyroglyphi, nymph of, 933; legs of, 934
Tyroglyphidæ, reproductive organs of, 936; characters of, 937

U

Ulothrix, conjugation of, 486
Ulva, 488, 489
Ulvaceæ, 487
Umbelliferous plants, seeds of, 649
Umbonula verrucosa, 830
Under-corrected objective, 20, 21
Under-correction, 255, 307, 308

UNG

Unger on the zoöspores of *Vaucheria*, 492
Unicellular plants, 469
Unio, pearls in, 847; glochidia of, 857
— *occidens*, formation of shell in, 849
Unionidæ, nacreous layer of, 847
Unit (standard) for microscopy, 400
Uredineæ, 565; alternation of generations in, 565
Uredo-form of *Puccinia*, 567
Uredospores of *Puccinia*, 567
Urinary calculi and molecular coalescence, 1023
Urine, micro-chemical examination, 1024
Urochordata, 835
Uropoda, tracheæ of, 935
'Urticating organs.' *See* Thread-cells
Ustilagineæ, 565
Uvella, 475

V

Vacuoles in cell, 464
— contractile, in protophytes, 465; of *Volvox*, 481
— of *Actinophrys*, 662
Vagine of mosses, 596
Valentin's two-bladed knife, 398
Vallisneria, habitat, 613, 614; mode of demonstration of cyclosis, 613, 614
Valvulina, shell of, 723
Vampyrella, 654, 655
— *gomphonematis*, 655, 656
— *spirogyræ*, 654, 655
Vanessa, 911; haustellium of, 916
— *urticæ*, eggs of, 929
Variation, range of, in *Astromma*, 774
Varley's live-box, 294
Varnish, test for, 383; asphalte, 383
Varnishes, 382; sealing-wax in alcohol, 384; red, 385; white, 385; various colours, 385
'Vascular Cryptogams,' links with Phanerogams, 607
Vascular papillæ of skin, 966
Vaucher, on *Siphonaceæ*, 492
Vaucheria, 491–493
— *Rotifera* in, 713
'Vegetable ivory,' endosperm of, 618
Vegetable substance, preparation of, 427; gum-imbedding for, 427; bleaching of, 427; Cole's staining method, 486
— structures, hardened in osmic acid, 428
Veins of vertebrates, 980
Velum,' in gastropod larva, 860
Venice turpentine cement, for glycerin mounts, 384
Ventriculites, 785, 1010
Venus' flower basket, 783, 784; spicules of, 784
Verbena, seeds of, 649
Vertebrata, 835; bone of, 944; teeth of, 947; dermal skeleton of, 950; blood of, 958; red blood-corpuscles, 958; white blood-corpuscles, 960; distribution of ciliated epithelium, 968; kidney of, 971

WAR

Vertebrated animals, 941
Vertical illuminator for ascertaining 'aperture,' 206
Vespidæ, 911
Vibracula of *Polyzoa*, 834, 835
Vibrio, movement of, 375
— *rugula*, 586
'Vibriones,' as applied to certain nematodes, 869
Vibriones, form of, 581, 586
Vigelius on tentacular cavity of *Polyzoa*, 829 *note*
Vignal on osmic acid for *Noctiluca*, 428
Vine, size of ducts of, 623
Viola tricolor, pollen-tubes of, 648
Violet, cells of pollen-chamber, 645
— of methanilin, for staining *Bacteria*, 437
Virginian spiderwort, cyclosis in, 615, 616
Virtual image, 14 *note*, 24, 25, 321
Vision, depth of, 88, 89, 90; stereoscopic, 89
Visual angle, 27
Vitrea (*Foraminifera*), 744
Vitreous cells (arthropod eye), 907
— optical compounds, 31
— shells of *Foraminifera*, 724
'Vittæ' of *Licmophoreæ*, 534; of seeds of umbellifers, 649
Vocal cords, structure of, 964
Vogan's changing nose-piece, 244
Volcanic ashes, microscopical examination of, 101
— dust, examination of, 999
Volvocineæ, 479–485
Volvox associated with *Astasia*, 690
— vegetable nature of, 484 *note*; amœbiform phase of, 485; *Rotifera* in, 713
— *aureus*, cellulose in, 481; starch in, 481
— *globator*, 479–485; flagellate affinities of, 479; contractile vacuoles in, 481; endochrome of, 482; multiplication of, 483; reproductive cells of, 483, 484
Vorticella, foot-stalk of, 701; contraction of foot-stalk, 702; fission of, 704; gemmiparous reproduction of, 711; conjugation of, 711
— *microstoma*, encystment of, 706, 707
Vorticellina, encystment of, 706

W

Waldheimia australis, shell of, 850
Wale's coarse adjustment, 185; his fine adjustment, 185; his limb, 185, 189
Wallflower, pollen-grains of, 647
Wall-lichens, 577
Wallich, on structure of diatom frustule, 519 *note*; on *Triceratium*, 543 *note*; on *Chætocereæ*, 544 *note*; on coccospheres, 672; on *Polycystina*, 776 *note*
Wallich's plan for sectionising a number of hard objects, 421 *note*
'Wanghie cane,' stem of, 626
Ward's simple microscope, 205

WAR

'Warm-stage' for observing blood-corpuscles, 958
Warmth, mode of applying, for cyclosis, 616
Wasps, wings of, 922, 923; sting of, 927
Water, refractive index of, 3, 7
— distilled, for mounting *Protophytes*, 442
— milfoil, 458
Water-angle, 50
Water-bath, 392
Water-boatman, wings of, 924
'Water-fleas,' 883, 886
Water-globules in oil, 370, 371
Water-immersion objectives, 310; Zeiss's, 317
Water-lily, leaf-structure of, 642; cells of pollen-chambers, 645
'Water-mites,' 937
'Water-net,' or *Hydrodictyon*, 495
Water-of-Ayr stone, 421
Water-scorpion, 919. See *Nepa*
'Water-snail.' See *Limnæus*
Water-vascular system of *Tænia*, 867
Wavellite in *Mya*, 848
Wax and olive oil for imbedding, 417
Web of spiders, 939
Weber's annular cells, 299
Webster condenser, 256
Weismann on development of *Diptera*, 931
Wenham on binocular vision, 107; on cyclosis of *Vallisneria*, 615
Wenham's suggestion of homogeneous immersion, 29; his stereoscopic binocular, 95–98; his prism, 99; his reflex illuminator, 265, 266; his disc and button illuminators, 266; his paraboloid, 267–269; his achromatic objective with single front, 310; his duplex front objective 311
West on *Chætocereæ*, 544 *note*
'Whalebone,' 957
Wheat, starch-grains of, 620
Wheatstone's stereoscope, 90; his pseudoscope, 92
'Wheel-animalcules,' 678, 712. *See* ROTIFERA
Wheel-like plates of *Chirodota*, 820
'Wheels' of *Rotifera*, 713
Whelk. See *Buccinum*
'White ant,' ciliate parasite of, 702
White blood-corpuscles of *Vertebrata*, 960; flow of, 980
— fibrous tissue, 963, 964
— of egg, as a preservative medium, 442
Whitney's directions for examination of frog's circulation, 984
Wild clary, spiral fibres of, 618
Williamson (W. C.) on *Volvox*, 484 *note*; on structure of fish-scales, 951; on structure of coal-plants, 1006
Willow-herb, emission of pollen-tubes, 647
Wing of *Agrion*, 918
Winged seeds, 648
Wings of insects, 922–924; of *Pterophorus*, 923; venation of, in *Neuroptera*, 922
Wodderborn on Galileo's invention of compound microscope, 123
Wodderborn's 'perspicillum,' 127
Wollaston's doublets, 36, 151; his camera lucida, 234
Wood, arrangement of, 625, 627; concentric rings of, 628; fossilised, 630, 1005
Wooden slides for opaque objects, 399
Woody fibre, 621
— tissue of ferns, 599
Working eye-pieces, 323
Worms, 867–880

X

Xylem of Exogens, 622, 623, 635
Xylol-balsam as a preservative medium, 442

Y

Yeast, 574; fermentation due to, 574
Yellow cells, in *Actiniæ*, 773; in radiolarians, 773
— fibrous tissue, 963, 964
Yolk-bag of young fish, circulation in, 981
Yucca, epiderm of, 637; guard-cells of stomates in, 640, 641

Z

Zanardinia, swarm-spores of, 556
Zea Mais, epiderm of, 637; stomates of, 640
Zeiss's oil-immersion objectives, 24; his eye-pieces and objectives, 34; his mechanical stage, 167; his dissecting microscope, 205; his photographic microscope, 211, 212; his latest microscope, 213; his calotte nose-piece, 242; his sliding objective changer, 245; his iris-diaphragm, 246, 248; his aplanatic loup, 261; his apparatus for monochromatic light, 272; his spectral ocular, 276; his apochromatic objectives, 314–320; his water-immersion, 317; his apochromatic, for resolving diatom markings, 521; his apochromatic for study of monads, 687
Zeiss-Steinheil's loups, 207
Zentmayer's microscope, 184; swinging sub-stage in, 184
Zeolite, 1017
Zinc, chlor-iodide of, as a test, 440
— cement, Cole's, 385; Zeigler's, 385
Zoantharia, 801
Zoëa, 894
Zonal structure in crystals, 996
Zoöchlorellæ of *Heliozoa*, 659
Zoöcytium of *Ophrydium*, chemical composition of, 706
Zoöglœa of *Beggiatoa*, 583

ZOO

Zoöglœæ, 581
Zoöphytes, 786–807
— mounting, 388, 389
— non-sexual reproduction of, 930
Zoöphyte troughs, 297, 298
Zoösporange of *Volvox*, 483, 485
Zoösporanges of *Phæosporeæ*, 556
Zoöspores, 466; of *Palmoglœa*, 472; of *Protococcus*, 474, 475; of *Palmodictyon*, 487; of *Ulva*, 488; of *Vaucheria*, 492; of *Achlya*, 494; development of, 494; of *Hydrodictyon*, 495; of *Confervaceæ*, 500; of *Œdogonium*, 502; of *Chætophoraceæ*, 503; of *Chytridiaceæ*, 555; of *Phæosporeæ*, 556; of *Florideæ*, 561; of *Fungi*, 562; of radiolarians, 773
Zoöthamium, collecting, 457

ZYM

Zoöxanthellæ in radiolarians, 773
Zoözygospores of *Navicula*, 526
Zukal on movement of *Spirulina*, 490
Zygnemaceæ, characters of, 477; habitats of, 477; conjugation of, 478
Zygosis in *Actinophrys*, 665; of *Amœba*, 669; of gregarines, 677
Zygospore, 467; formation of, 470; of *Hydrodictyon*, 495; in *Desmidiaceæ*, 513, 514
Zygospores of *Palmoglœa*, 472; of *Mesocarpus*, 478; of *Spirogyra*, 478; of *Pandorina*, 485; of *Ulva*, 490; of *Navicula*, 526; of diatoms, 528; of *Mucorini*, 569
Zygote of *Glenodinium*, 695
Zymotic or fermentative action of *Fungi*, 462

JUL 1 5 1930